

CA-EW-1

Earthwork Quantity Calculations

Project No. PID 76256 Co-Rt-Sec HAM-75-14.61 Date 1-15-2021

Station	CUTS				FILLS				
	End Area ft <sup>2</sup>	Average End Area ft <sup>2</sup>	Length Between Stations ft	Volume yd <sup>3</sup>	End Area ft <sup>2</sup>	Average End Area ft <sup>2</sup>	Length Between Stations ft	Volume yd <sup>3</sup>	
368+34.09	130				0				358
		116	65.91	282		3	65.91	7	
369+00	101				5				
		171	50.00	317		5	50.00	10	
369+50	241				5				
		339	50.00	627		5	50.00	10	359
370+00	436				5				
		462	50.00	855		5	50.00	10	
370+50	487				5				
		505	50.00	936		5	50.00	10	
371+00	523				5				
		527	50.00	976		10	50.00	19	360
371+50	531				15				
		496	50.00	919		25	50.00	46	
372+00	461				34				
		431	50.00	799		77	50.00	142	
372+50	401				119				
		374	50.00	692		143	50.00	265	361
373+00	346				167				
		318	50.00	588		208	50.00	386	
373+50	289				249				
		267	50.00	494		286	50.00	529	362
374+00	244				322				
		216	50.00	400		409	50.00	757	
374+50	187				495				
		171	50.00	316		510	50.00	944	363
375+00	154				524				
		138	50.00	256		549	50.00	1016	
375+50	122				573				
		111	50.00	205		570	50.00	1055	364
376+00	99				566				
		88	50.00	163		550	50.00	1019	
376+50	76				534				
		68	50.00	125		580	50.00	1075	365
377+00	59				626				
		52	50.00	96		608	50.00	1125	
377+50	44				589				
		33	50.00	62		591	50.00	1094	366
378+00	22				592				
		23	50.00	42		591	50.00	1094	
378+50	23				589				
		22	50.00	40		594	50.00	1100	367
379+00	20				598				
		18	50.00	33		610	50.00	1130	
379+50	15				622				
		17	50.00	32		610	50.00	1130	368
380+00	19				598				

