

PIPE								
ITEM #	QUANTITY	UNIT	SIZE	DESCRIPTION	\$/Unit	Total	notes	lead time
1	40	FT	12"	Pipe, PE, ERW, API-5L PSL-2, Grade X-42, 0.375" Wall, Uncoated	\$31.10	\$1,244.00		2 wks
2	2040	FT	8"	Pipe, PE, ERW, API-5L PSL-2, Grade X-42, 0.322" STD. Wall, w/14 mils FBE	\$20.25	\$41,310.00		2 wks
3	250	FT	8"	Pipe, PE, ERW, API-5L PSL-2, Grade X-42, 0.322" STD. Wall, w/14 mils FBE, w/ 40 mils powercrete coating	\$29.30	\$7,325.00		2 wks
4	40	FT	8"	Pipe, PE, ERW, API-5L PSL-2, Grade X-42, 0.322" STD. Wall, Uncoated	\$17.57	\$702.80		2 wks
5	40	FT	6"	Pipe, PE, ERW, API-5L PSL-2, Grade X-42, 0.280" STD. Wall, Uncoated	\$10.92	\$436.80		2 wks
6	40	FT	4"	Pipe, PE, ERW, API-5L PSL-2, Grade X-42, 0.237" STD. Wall, Uncoated	\$6.51	\$260.40		2 wks
7	21	FT	2"	Pipe, PE, ERW, API-5L PSL-2, Grade X-42, 0.154" STD. Wall, Uncoated	\$2.37	\$49.77		2 wks
VALVES								
ITEM #	QUANTITY	UNIT	SIZE	DESCRIPTION	\$/Unit	Total	notes	lead time
8	1	EA	8"	Valve, Ball, Full Port, Trunnion Mounted, RF Flange x RF Flange, Steel Body, ANSI 300, 720# W.P., STD. Construction, Complete with Gear Operator Manufacturer: WKM	\$5,627.48	\$5,627.48	370D4-24-YRF-24-WGA	3-4 days
9	2	EA	6"	Valve, Ball, Full Port, Trunnion Mounted, RF Flange x RF Flange, Steel Body, ANSI 300, 7200# W.P., STD. Construction, Complete with Gear Operator Manufacturer: WKM	\$2,902.23	\$5,804.45	370D4-24-YRF-24-WR	3-4 days
10	1	EA	6"	Valve, Check, Swing, RF Flange x RF Flange, Steel Body, ANSI 300, 720# W.P. Manufacturer: WKM	\$985.69	\$985.69	3-62-RF BONNEY	3-4 days
11	1	EA	4"	Valve, Ball, Full Port, Trunnion Mounted, RF Flange x RF Flange, Steel Body, ANSI 300, 720# W.P., STD. Construction, Complete with Gear Operator Manufacturer: WKM	\$1,542.64	\$1,542.64	370D4-24-YRF-24-WR	3-4 days
12	2	EA	2"	Valve, Plug, Standard Port, Flanged Steel Body, ANSI 300, 720# W.P.	\$566.35	\$1,132.69	NORD 2024	3-4 days
13	6	EA	1"	Valve, Ball, Standard Port, Screw Steel Body, 2000# Minimum W.P.	\$48.46	\$290.74	24190-413110	3-4 days
14	1	EA	1/2"	Valve, Ball, Standard Port, Screw Steel Body, 2000# Minimum W.P.	\$20.24	\$20.24	NAVCO 520 2203941-03	3-4 days
PIG SIG								
ITEM #	QUANTITY	UNIT	SIZE	DESCRIPTION	\$/Unit	Total	notes	lead time
15	1	EA	-	TDW Pig-Sig V Scraper Passage Indicator, Flag/Electrical Indicator, Assembly #04-3800-2000-51, Complete w/ Thread-O-Ring Nipple Part #00-1023-0333-51	\$1,785.71	\$1,785.71		1 wk
FLANGES								
ITEM #	QUANTITY	UNIT	SIZE	DESCRIPTION	\$/Unit	Total	notes	lead time
16	3	EA	8"	Flange, Steel, ANSI 300, F-42, Weld Neck, Raised Face, 0.322" Std. Wall, 7.981" Bore	\$250.00	\$750.00	F52	3-4 days
16a	1	EA	12"	Flange, Blind, Steel, F-52, ANSI 300, Raised Face, Drilled & Tapped w/ 1" NPT	\$250.00	\$250.00		
17	8	EA	6"	Flange, Steel, ANSI 300, F-42, Weld Neck, Raised Face, 0.280" Std. Wall, 6.065" Bore	\$121.79	\$974.29	F52	3-4 days
18	1	EA	6"	Flange, Blind, Steel, F-52, ANSI 300, Raised Face, Drilled & Tapped w/ 1" NPT	\$65.12	\$65.12		1 wk
	1			LABOR TO DRILL 1" NPT IN CETNER	\$23.60	\$23.60		
19	2	EA	4"	Flange, Steel, F-52, ANSI 300, Weld Neck, Raised Face, 0.237" Std. Wall, 4.026" Bore	\$71.96	\$143.93		3-4 days
20	4	EA	2"	Flange, Steel, F-52, ANSI 300, Weld Neck, Raised Face, 0.154" Std. Wall, 2.067" Bore	\$20.83	\$83.33	not F52	3-4 days
GASKETS								
ITEM #	QUANTITY	UNIT	SIZE	DESCRIPTION	\$/Unit	Total	notes	lead time
21	3	EA	8"	Gasket, Flexitallic Style CG Spiral Wound, ANSI 300, ASME 16.5 Flange, Carbon Steel Inner & Outer Rings	\$4.48	\$13.43		3-4 days
22	8	EA	6"	Gasket, Flexitallic Style CG Spiral Wound, ANSI 300, ASME 16.5 Flange, Carbon Steel Inner & Outer Rings	\$3.27	\$26.19		3-4 days
23	2	EA	4"	Gasket, Flexitallic Style CG Spiral Wound, ANSI 300, ASME 16.5 Flange, Carbon Steel Inner & Outer Rings	\$2.21	\$4.43		3-4 days
24	4	EA	2"	Gasket, Flexitallic Style CG Spiral Wound, ANSI 300, ASME 16.5 Flange, Carbon Steel Inner & Outer Rings	\$4.52	\$18.10		3-4 days
BOLTS								
ITEM #	QUANTITY	UNIT	SIZE	DESCRIPTION	\$/Unit	Total	notes	lead time
25	36	EA	-	1 1/8" x 8 1/4" Bolt, Stud, Steel, with Nuts, ASTM A-193/A-194	\$4.43	\$159.43		3-4 days
26	96	EA	-	1" x 7 1/4" Bolt, Stud, Steel, with Nuts, ASTM A-193/A-194	\$3.09	\$296.23		3-4 days
27	16	EA	-	7/8" x 6 1/4" Bolt, Stud, Steel, with Nuts, ASTM A-193/A-194	\$2.10	\$33.60		3-4 days
28	32	EA	-	5/8" x 4 3/4" Bolt, Stud, Steel, with Nuts, ASTM A-193/A-194	\$0.86	\$27.43		3-4 days
FITTINGS								

ITEM #	QUANTITY	UNIT	SIZE	DESCRIPTION	\$/Unit	Total			
29	1	EA	12" X 8"	Reducer, Eccentric, Grade WPHY-52, 0.375" x 0.322" STD. Wall, Weld End	\$316.84	\$316.84		3-4 days	
30	1	EA	12" X 6"	Weldolet, Steel, 3000 PSIG	\$113.04	\$113.04	14->12	3-4 days	
31	2	EA	12" X 2"	Weldolet, Steel, 3000 PSIG	\$9.59	\$19.18	18->12	3-4 days	
32	0	EA	12"	TDW 12" D2000 Hinged Closure (Part #19-6712-0600-53), Ends to Match 0.375", w/ Viton O-Ring	\$5,136.17	\$0.00		3 wks	
33	1	Ea	8"	TDE 8", Stopple Fitting	\$4,715.96	\$4,715.96	06-8807-0830	6 wks	
34	1	EA	8" X 6"	Tee, Reducing, Steel, Grade WPHY-42, 0.322" x 0.280" STD Wall, Weld End	\$239.52	\$239.52	Y52	3-4 days	
35	1	EA	8" X 4"	Weldolet, Steel, 3000 PSIG	\$26.88	\$26.88	8 X 4	1 wk	
36	1	EA	8" X 2"	Weldolet, Steel, 3000 PSIG	\$9.59	\$9.59	10->8	3-4 days	
37	2	EA	6"	Tee, Steel, Weld, API-5L PSL-2 WPHY-42, Std. Wall	\$112.69	\$225.37	Y52	3-4 days	
38	1	EA	4"	Closure, Weld End, 2000 PSIG, Yale 500 (WILL NEED TO CLARIFY WALL THICKNESS)	\$268.33	\$268.33	ansi 900 (2220psi) NO HINGE	2-1/2 wks	
39	1	EA	2"	Closure, Weld End, 2000 PSIG, Yale 500 (WILL NEED TO CLARIFY WALL THICKNESS)	\$154.00	\$154.00	ansi 900 (2220psi)	2-1/2 wks	
39	4	EA	8"	Eil, 90 Deg, Steel, Grade WPHY-42, 0.280" Wall, LR, Weld End (STD 0.322W)	\$127.85	\$511.38	Y52	3-4 days	
40	4	EA	8"	Eil, 45 Deg, Steel, Grade WPHY-42, 0.280" Wall, SR, Weld End (STD 0.322W)	\$95.51	\$382.02	Y52	1 wk	
41	1	EA	6"	Eil, 90 Deg, Steel, Grade WPHY-42, 0.280" Wall, LR, Weld End	\$73.27	\$73.27	Y52	3-4 days	
42	1	EA	6"	Eil, 90 Deg, Steel, Grade WPHY-42, 0.280" Wall, SR, Weld End	\$204.26	\$204.26		8 wks	
43	2	EA	2"	Eil, 90 Deg, Steel, Grade WPHY-42, 0.154" Wall, LR, Weld End	\$40.43	\$80.85	Y52	3-4 days	
44	6	EA	1"	Threadolet, Threaded, Steel, 3000 PSIG	\$3.77	\$22.62	10->6	3-4 days	
45	6	EA	1"	1" x 3" Nipple, Pipe, Steel, Grade B, XS, TBE	\$1.80	\$10.79	SMLS	3-4 days	
46	6	EA	1"	Plug, Steel, Hex Head, Threaded, XS	\$1.16	\$6.99		3-4 days	
47	1	EA	1/2"	Threadolet, Threaded, Steel, 3000 PSIG	\$2.81	\$2.81	8->3	3-4 days	
48	1	EA	1/2"	1/2" x 3" Nipple, Pipe, Steel, Grade B, XS, TBE	\$1.21	\$1.21	SMLS	3-4 days	
49	1	EA	1/2"	Plug, Steel, Hex Head, Threaded, XS	\$0.45	\$0.45		3-4 days	
SKID & PIPE SUPPORTS									
ITEM #	QUANTITY	UNIT	SIZE	DESCRIPTION	\$/Unit	Total			
50	1	EA	12"	E-Z Line Adjustable Shim Block Support Assembly #CSB12, Galvanized	\$128.17	\$128.17		1 wk	
51	3	EA	8"	E-Z Line Adjustable Shim Block Support Assembly #CSB8, Galvanized	\$85.17	\$255.50		1 wk	
52	2	EA	6"	E-Z Line Adjustable Pipe Support Assembly #510-F, D = 2'-3 1/8"	\$58.89	\$117.79		1 wk	
53	8	EA	-	Concrete Fiber From, 2' Diameter x 42" Long	\$115.71	\$925.71	2'x12'	3-4 days	
54	24	EA	-	3/4" x 18" Anchor Bolt with Washer, Nut, & Clamp Down Glvanized Bolt to include 4" 90° Bend at Base	\$12.42	\$298.00		2 days	
55	8	EA	-	5/8" x 18" Anchor Bolt with Washer, Nut, & Clamp Down Glvanized Bolt to include 4" 90° Bend at Base	\$8.39	\$67.14		2 days	
					Total	\$26,239.54	\$80,565.16		

MRC Global™

ALL SUBJECT TO PRIOR SALE / MRC TERMS APPLY

PRICING IS QUOTED IN US DOLLARS UNLESS OTHERWISE NOTED.

PRICING IS FOR THIS QUOTATION ONLY AND IS BASED ON THE COMPLETE QUANTITIES QUOTED

MRC HAS THE RIGHT TO REQUOTE THIS OFFER SHOULD ANY REVISIONS OCCUR.

OTHER TERMS ARE SUBJECT TO THE MRC GENERAL TERMS AND CONDITIONS

PRODUCT WARRANTY: PER MANUFACTURE STANDARDS

PIPE OFFERED IN RANDOM LENGTHS.

*** MATERIAL SUBJECT TO PRIOR SALE****