

HEN-US6/CR424 INFIELDS TP

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 9/24/2026 TIME: 9:55:12 AM PLTDRV: OHDOT_PDF.pltG PENITBL: OHDOT_Pen.tbl USER: KerdallGirdling@stoneenvironmental.com WORKSPACE: OHDOTCEV02 WORKSET: 122871 PRODUCT: OpenRoadsDesigner 24.00.00.205
 pw:\ohdotdtpw.bentley.com:ohdotdtpw-02\Documents\01 Active Projects\District 02\Henry\122871\405-Engineering Stone\EnvironmentalRoadway\Sheets\122871 GG501.dgn

SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.05	P.06	P.07	P.13	P.17	P.18	P.20	P.21	P.22	P.23	P.49	P.50	P.62	01/NFP						
LS													LS	201	11000	LS		CLEARING AND GRUBBING	
				137.5				86					86	202	23000	86	SY	PAVEMENT REMOVED	
				1									137.5	202	38000	137.5	FT	GUARDRAIL REMOVED	
				1									1	202	42010	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E	
													1	202	47000	1	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
													721	203	10000	721	CY	EXCAVATION	
							721						19,955	203	20000	19,955	CY	EMBANKMENT	
							19,955						17,525	204	10000	17,525	SY	SUBGRADE COMPACTION	
	562							17,525					562	204	13000	562	CY	EXCAVATION OF SUBGRADE	
	562												562	204	30020	562	CY	GRANULAR MATERIAL, TYPE C	
6													6	204	45000	6	HOUR	PROOF ROLLING	
	1,687												1,687	204	50000	1,687	SY	GEOTEXTILE FABRIC	
				453									453	209	10000	453	FT	DITCH CLEANOUT	
				1									1	209	15000	1	STA	RESHAPING UNDER GUARDRAIL	
				25									25	606	15050	25	FT	GUARDRAIL, TYPE MGS	
				1									1	606	26150	1	EACH	ANCHOR ASSEMBLY, MGS TYPE E	
				1									1	606	35002	1	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	
				38									38	607	98000	38	FT	FENCE, MISC.:WOODEN SLAT FENCE	P.06
													LS	623	50000	LS		PRECONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
													LS	623	51000	LS		POST CONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
				5									5	SPECIAL	69050600	5	EACH	BOLLARD	P.06
													LS	878	25000	LS		INSPECTION AND COMPACTION TESTING OF UNBOUND MATERIALS	
6						8							14	601	21050	14	SY	EROSION CONTROL TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT	
					1								1	601	32200	1	CY	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
				17									17	601	32310	17	CY	ROCK CHANNEL PROTECTION, TYPE D WITH AGGREGATE FILTER	
2													2	659	00100	2	EACH	SOIL ANALYSIS TEST	
800									370				1,170	659	00300	1,170	CY	TOPSOIL	
7,106													7,106	659	00590	7,106	SY	SEEDING AND MULCHING, CLASS 6	
									3,330				3,330	659	10000	3,330	SY	SEEDING AND MULCHING	
0.97													0.97	659	20000	0.97	TON	COMMERCIAL FERTILIZER	
1.49													1.49	659	31000	1.49	ACRE	LIME	
40													40	659	35000	40	MGAL	WATER	
					153								153	660	25000	153	SY	SODDING STAKED	

GENERAL SUMMARY

DESIGN AGENCY  ENVIRONMENTAL, ENGINEERING & SCIENCE	
DESIGNER FRR	
REVIEWER BAT 06/18/26	
PROJECT ID 122871	
SHEET P.15	TOTAL 72

SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.05	P.06	P.07	P.13	P.17	P.18	P.20	P.21	P.22	P.23	P.49	P.50	P.62	01/NFP						
																		LIGHTING	
												60	60	611	00400	60	FT	4" CONDUIT, TYPE E	
												10	10	625	00450	10	EACH	CONNECTION, FUSED PULL APART	
												9	9	625	00480	9	EACH	CONNECTION, UNFUSED PERMANENT	
												5	5	625	13500	5	EACH	LIGHT TOWER, MISC.: LIGHT TOWER BBBB45	P.60
												5	5	625	15700	5	EACH	LIGHT TOWER FOUNDATION, MISC.:36" X 10' DEEP	P.60
												4,245	4,245	625	23300	4,245	FT	NO. 2 AWG 2400 VOLT DISTRIBUTION CABLE	
												1,375	1,375	625	25504	1,375	FT	CONDUIT, 3", 725.051	
												20	20	625	26263	20	EACH	LUMINAIRE, HIGH MAST, SOLID STATE (LED), AS PER PLAN, HMLED_P3_3K	P.60
												1,375	1,375	625	29002	1,375	FT	TRENCH, 24" DEEP	
												3	3	625	30706	3	EACH	PULL BOX, 725.08, 24"	
												10	10	625	32000	10	EACH	GROUND ROD	
												1	1	625	34001	1	EACH	POWER SERVICE, AS PER PLAN	P.60
												1	1	625	34450	1	EACH	CONTROL CENTER CABINET, COMPLETE	
												1,375	1,375	625	36010	1,375	FT	UNDERGROUND WARNING/MARKING TAPE	
												1	1	625	76000	1	EACH	ARC FLASH CALCULATIONS AND LABEL, LIGHTING CONTROL CENTER	
																		TRAFFIC CONTROL	
				2									2	626	00110	2	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL	
											244	244	630	03100	244	FT	GROUND MOUNTED SUPPORT, NO. 3 POST		
											100	100	630	07000	100	FT	GROUND MOUNTED STRUCTURAL BEAM SUPPORT, W8X18		
											4	4	630	09000	4	EACH	BREAKAWAY STRUCTURAL BEAM CONNECTION		
											6	6	630	79500	6	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED		
											1	1	630	79604	1	EACH	SIGN SUPPORT ASSEMBLY, BRIDGE MOUNTED, TYPE 2		
											181	181	630	80100	181	SF	SIGN, FLAT SHEET		
											220	220	630	80200	220	SF	SIGN, GROUND MOUNTED EXTRUSHEET		
											4	4	630	84500	4	EACH	GROUND MOUNTED STRUCTURAL BEAM SUPPORT FOUNDATION		
											8	8	630	84900	8	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL		
											4	4	630	86002	4	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL		
										7,354		7,354	646	20200	7,354	FT	PARKING LOT STALL MARKING		
										5		5	646	20300	5	EACH	LANE ARROW		
																		MAINTENANCE OF TRAFFIC	
			2									2	SPECIAL	61411300	2	EACH	WORK ZONE TRAFFIC SIGNAL	P.13	
		2										2	614	12384	2	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (BIDIRECTIONAL)		
		10										10	614	13310	10	EACH	BARRIER REFLECTOR, TYPE 1 BI-DIRECTIONAL		
		9										9	614	13360	9	EACH	OBJECT MARKER, TWO WAY		
		0.06										0.06	614	21000	0.06	MILE	WORK ZONE CENTER LINE, CLASS I		
		0.13										0.13	614	22010	0.13	MILE	WORK ZONE EDGE LINE, CLASS I, 6"		
		40										40	614	26000	40	FT	WORK ZONE STOP LINE, CLASS I		
		46										46	616	10000	46	MGAL	WATER		
		430										430	622	41100	430	FT	PORTABLE BARRIER, UNANCHORED		
																		INCIDENTALS	
												LS	614	11000	LS		MAINTAINING TRAFFIC		
												LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING		
												LS	624	10000	LS		MOBILIZATION		

PAVEMENT CALCULATIONS	
DESIGN AGENCY 	
DESIGNER FRR	
REVIEWER BAT 06/18/26	
PROJECT ID 122871	
SHEET P.22	TOTAL 72