

I:\ProjectData\00674\Design\Roadway\Sheets\00674_GN006.dgn Sheet 23-NOV-2021 3:06PM akemp

SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	7	8	9	10	11					01/STR/PV	02/NFA/PV								
																	ROADWAY		
	2,544										2,183	361	202	23500	2,544	SY	WEARING COURSE REMOVED		
		32.14									23.02	9.12	209	72051	32.14	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN	2	
																	EROSION CONTROL		
											500	500	832	30000	1,000	EACH	EROSION CONTROL		
																	DRAINAGE		
				6,400							4,000	2,400	605	31100	6,400	FT	AGGREGATE DRAINS		
																	PAVEMENT		
				6,400							4,000	2,400	253	02000	6,400	CY	PAVEMENT REPAIR		
	1,277		1,462								2,402	337	254	01000	2,739	SY	PAVEMENT PLANING, ASPHALT CONCRETE (1-1/2")		
	225,330	14,395									178,825	60,900	254	01001	239,725	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN (3-1/2")	2	
	31,724	2,015	125								25,293	8,571	407	20000	33,864	GAL	NON-TRACKING TACK COAT		
		14,878									10,804	4,074	408	10001	14,878	GAL	PRIME COAT, AS PER PLAN	2	
	106										91	15	441	50401	106	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), (DRIVEWAYS), AS PER PLAN	2	
	9,441	936	54								7,788	2,643	442	10001	10,431	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446), AS PER PLAN (PG76-22M)	2	
	12,440	809									9,882	3,367	442	10100	13,249	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446)		
		3,615									2,625	990	617	10100	3,615	CY	COMPACTED AGGREGATE		
		37,192									27,008	10,184	617	20000	37,192	SY	SHOULDER PREPARATION		
																	TRAFFIC CONTROL		
					2,097						1,522	575	621	00100	2,097	EACH	RPM		
					2,097						1,522	575	621	54000	2,097	EACH	RAISED PAVEMENT MARKER REMOVED		
					31.7						23.02	8.68	646	10010	31.7	MILE	EDGE LINE, 6"		
					15.85						11.51	4.34	646	10200	15.85	MILE	CENTER LINE		
					74						40	34	646	10400	74	FT	STOP LINE		
					2						2	2	646	20100	2	EACH	SCHOOL SYMBOL MARKING, 72"		
					380						280	100	646	20504	380	FT	DOTTED LINE, 6"		
																	MAINTENANCE OF TRAFFIC		
	96										71	25	614	12460	96	EACH	WORK ZONE MARKING SIGN		
	47.55										34.53	13.02	614	21500	47.55	MILE	WORK ZONE CENTER LINE, CLASS II, 642 PAINT		
	47.55										34.53	13.02	614	21550	47.55	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT		
	222										120	102	614	26610	222	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT		
																	INCIDENTALS		
	LS										LS	LS	614	11000	LS		MAINTAINING TRAFFIC		
											LS	LS	624	10000	LS		MOBILIZATION		

CALCULATED ADK	CHECKED JPB	GENERAL SUMMARY
4 14		