SHEET NUMBER									PARTICIPATION				ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	6	7	9	10	11	12	18	01/STR/PV									
																	TRAFFIC CONTROL	
					377				377				621	00100	377	EACH	RPM	
					377				377				621	54000	377	EACH	RAISED PAVEMENT MARKER REMOVED	
							10		10				626	00100	10	EACH	BARRIER REFLECTOR	
						30			30				630	03100	30	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
						18			18				630	80100	18	SF	SIGN, FLAT SHEET	
						2			2				630	84900	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
						2			2				630	86002	2	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
					10.1				10.1				642	00104	10.1	MILE	EDGE LINE, 6", TYPE 1	
					5.05				5.05				642	00300	5.05	MILE	CENTER LINE, TYPE 1	
					214				214				644	00500	214	FT	STOP LINE	
					44				44				644	00600	44	FT	CROSSWALK LINE	
					167				167				644	01200	167	FT	PARKING LOT STALL MARKING	
					2				2				644	01410	2	EACH	WORD ON PAVEMENT, 96" ("X-ING")	
					2				2				644	01620	2	EACH	BIKE CROSSING SYMBOL	
																	STRUCTURE UNDER 20 FOOT SPAN (LOR-511-1420)	
								225	225				202	38603	225	FT	BRIDGE RAILING REMOVED FOR REUSE, AS PER PLAN	19
								60	60				202	98200	60	FT	REMOVAL MISC.:POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	19
								99	99				512	10100	99	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
								99	99				512	74000	99	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES	
								225	225				517	75600	225	FT	DEEP BEAM BRIDGE RETROFIT RAILING	
								60	60				846	00100	60	FT	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	
																	MAINTENANCE OF TRAFFIC	
		40							40				614	12460	40	EACH	WORK ZONE MARKING SIGN	
		75							75				614	13000	75	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
					10.1				10.1				614	21500	10.1	MILE	WORK ZONE CENTER LINE, CLASS II, 642 PAINT	
					138				138				614	26610	138	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
													614	11000	LS		MAINTAINING TRAFFIC	
									3				619	16010	3	MNTH	FIELD OFFICE, TYPE B	
													623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													624	10000	LS		MOBILIZATION	

CALCULATED CAG
CHECKED CAD

GENERAL SUMMARY

LOR-511-13.41

I:\projects\88767\roadway\sheets\88767GG001.dgn