

UTILITIES

LISTED BELOW ARE ALL UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS:

AT&T OHIO
50 WEST BOWERY STREET
AKRON, OH 44308
ATTN: HAROLD MAYNARD
PHONE: 330-384-8974

AEP OHIO POWER COMPANY
120 JOHN SCOTT HIGHWAY
STEBENVILLE, OH 43952
ATTN: BRIAN BROWN
PHONE: 740-266-3094

COMCAST
2810 DARLINGTON ROAD
BEAVER FALLS, PA 15010
ATTN: DAVE TATAREK
PHONE: 724-384-1861

THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE AS OBTAINED FROM THE OWNERS AS REQUIRED BY SECTION 153.64 O.R.C.

THE OHIO DEPARTMENT OF TRANSPORTATION HAS UTILITY FACILITIES (HIGHWAY LIGHTING AND/OR TRAFFIC SIGNALS) WITHIN THE LIMITS OF THIS PROJECT.

IN ADDITION TO THE INFORMATION OUTLINED IN THIS CONTRACT, THE CONTRACTOR SHALL TAKE THE FOLLOWING ACTION TO PROTECT ODOT'S FACILITIES DURING CONSTRUCTION:

HIGHWAY LIGHTING AND/OR TRAFFIC SIGNALS: EVEN THOUGH ODOT IS LISTED AS A MEMBER OF THE OHIO UTILITIES PROTECTION SERVICE (OUPS), THE CONTRACTOR IS REQUIRED TO CONTACT ODOT DIRECTLY SO THAT THE ODOT UTILITIES LOCATED WITHIN THIS PROJECT ARE MARKED. THE CONTRACTOR SHALL NOTIFY THE ODOT PROJECT ENGINEER/PROJECT SUPERVISOR, FOURTEEN (14) CALENDAR DAYS IN ADVANCE OF ANY WORK, FOR THE NEED TO MARK ODOT OWNED UTILITIES.

THE ABOVE REQUIREMENTS ARE IN ADDITION TO SECTION 105.07 & 107.16 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS. THE CONTRACTOR SHALL NOTIFY OTHER UTILITIES THROUGH OUPS OR DIRECTLY A MINIMUM OF FORTY-EIGHT HOURS IN ADVANCE OF ANY WORK.

WORK LIMITS

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. PROVIDE THE INSTALLATION AND OPERATION OF ALL WORK ZONE TRAFFIC CONTROL AND WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

ROUNDING

THE ROUNDING AT SLOPE BREAKPOINTS SHOWN ON THE TYPICAL SECTIONS APPLIES TO ALL CROSS-SECTIONS EVEN THOUGH OTHERWISE SHOWN.

INTERIM COMPLETION DATE

ALL STRUCTURE WORK (EXCEPT FOR SEALING OF CONCRETE SURFACES) SHALL BE COMPLETED AND ALL LANES OF S.R. 213 SHALL BE OPEN TO TRAFFIC BY DECEMBER 15, 2020. DECEMBER 15, 2020 SHALL BE CONSIDERED AN INTERIM COMPLETION DATE, AND LIQUIDATED DAMAGES SHALL BE ASSESSED IN ACCORDANCE WITH CMS 108.07 FOR EACH CALENDAR DAY THAT ALL LANES OF S.R. 213 ARE NOT OPEN TO TRAFFIC.

EXISTING PLANS

EXISTING PLANS MAY BE INSPECTED ONLINE OR IN THE ODOT DISTRICT 11 OFFICE IN NEW PHILADELPHIA, OHIO.

S.R. 213 UPGRADE
JEF-7-(33.83-34.10)/COL-7-(0.00-0.50) (1957)

REST AREA PLAN
JEF-7-34.29 (1967)

CONVERSION TO NON-COMPOSITE BOX BEAMS
JEF-213-18.62 (1984)

ORIGINAL ARCH PLANS ARE NOT AVAILABLE.

<http://www.dot.state.oh.us/Divisions/ContractAdmin/Contracts/Pages/designfiles.aspx>

SURVEYING PARAMETERS

PRIMARY PROJECT CONTROL MONUMENTS GOVERN ALL POSITIONING ON ODOT PROJECTS. SEE SHEET 10 OF THE PLANS FOR A TABLE CONTAINING PROJECT CONTROL INFORMATION.

USE THE FOLLOWING PROJECT CONTROL, VERTICAL POSITIONING, AND HORIZONTAL POSITIONING PARAMETERS FOR ALL SURVEYING:

PROJECT CONTROL

POSITIONING METHOD: ODOT VRS
MONUMENT TYPE: TYPE A

VERTICAL POSITIONING

ORTHOMETRIC HEIGHT DATUM: NAVD 88
GEOID: GEOID 12A

HORIZONTAL POSITIONING

REFERENCE FRAME: NAD 83 (2011)
ELLIPSOID: GRS 1980
MAP PROJECTION: LAMBERT CONFORMAL CONIC
COORDINATE SYSTEM: OHIO STATE PLANE, NORTH ZONE
COMBINED SCALE FACTOR: 1.00005215089904
ORIGIN OF COORDINATE SYSTEM:
N 334278.849, E 2477797.471

USE THE POSITIONING METHODS AND MONUMENT TYPE USED IN THE ORIGINAL SURVEY TO RESTORE ALL MONUMENTS RELATED TO PRIMARY PROJECT CONTROL THAT ARE DAMAGED OR DESTROYED BY CONSTRUCTION ACTIVITIES. RESTORE THE DAMAGED OR DESTROYED MONUMENTS IN ACCORDANCE WITH CMS 623. UNITS ARE IN U.S. SURVEY FEET.

CLEARING AND GRUBBING

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROJECT, A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201, CLEARING AND GRUBBING. ALL PROVISIONS AS SET FORTH IN THE SPECIFICATIONS UNDER THIS ITEM ARE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201, CLEARING AND GRUBBING.

SEEDING AND MULCHING

SEEDING AND MULCHING SHALL BE APPLIED TO ALL AREAS OF EXPOSED SOIL BETWEEN THE RIGHT-OF-WAY LINES, AND WITHIN THE CONSTRUCTION LIMITS FOR AREAS OUTSIDE THE RIGHT-OF-WAY LINES COVERED BY WORK AGREEMENT OR SLOPE EASEMENT. QUANTITY CALCULATIONS FOR SEEDING AND MULCHING ARE BASED ON THESE LIMITS.

CONNECTION BETWEEN EXISTING AND PROPOSED GUARDRAIL

WHEN IT IS NECESSARY TO SPLICE PROPOSED GUARDRAIL TO EXISTING GUARDRAIL, ONLY THE EXISTING GUARDRAIL SHALL BE CUT, DRILLED, OR PUNCHED. THE CONNECTION SHALL BE MADE USING A W-BEAM, BEAM SPLICE AS SHOWN IN AASHTO M 180-12, EXCEPT THE BEAM WASHERS ARE NOT TO BE USED. PAYMENT SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE RESPECTIVE GUARDRAIL ITEMS.

ITEM 441 - ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), AS PER PLAN (PG70-22M)

THE CONTRACTOR SHALL FOLLOW THE SPECIFICATIONS OF CMS 703.05, EXCEPT DO NOT USE COARSE AGGREGATE FROM A SOURCE DESIGNATED "SR" OR "SRH" AS DEFINED BY THE OFFICE OF MATERIALS MANAGEMENT (OMM) IN ANY JOB MIX FORMULA (JMF) FOR THIS ITEM OF WORK.

ITEM SPECIAL - AS-BUILT CONSTRUCTION PLANS

THE CONTRACTOR SHALL PROVIDE AS-BUILT CONSTRUCTION PLANS OF THE BRIDGE SHOWING THE ACTUAL CLEARANCES AS CONSTRUCTED TO NORFOLK SOUTHERN. THESE PLANS SHALL BE SIGNED, DATED, AND SEALED BY A REGISTERED PROFESSIONAL SURVEYOR IN THE STATE OF OHIO. ALL LABOR, MATERIALS, EQUIPMENT, AND OTHER INCIDENTALS NECESSARY TO SUBMIT THESE PLANS SHALL BE INCLUDED IN ITEM SPECIAL - AS-BUILT CONSTRUCTION PLANS.

ITEM 623 - CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN

ONCE THE BRIDGE CONSTRUCTION IS COMPLETE, THE CONTRACTOR SHALL SURVEY THE HORIZONTAL AND VERTICAL CLEARANCES WITH RESPECT TO THE RAILROAD. THE MINIMUM VERTICAL CLEARANCE SHALL BE MEASURED FROM A POINT NORMAL TO THE TOP OF HIGH (NORTH) RAIL TO THE LOWEST POINT OF THE STRUCTURE, MEASURED FROM A POINT OFFSET 5'-6" FROM THE TRACK CENTERLINE. THE POST-CONSTRUCTION SURVEYED CLEARANCES SHALL BE INCLUDED IN THE AS-BUILT CONSTRUCTION PLANS AS DESCRIBED ABOVE. ALL LABOR, MATERIALS, EQUIPMENT, AND OTHER INCIDENTALS NECESSARY TO PERFORM THIS SURVEY WORK AND ALL OTHER REQUIREMENTS OF CMS 623 SHALL BE INCLUDED IN ITEM 623 - CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN.

NORFOLK SOUTHERN RAILROAD NOTES

ALL WORK ON, OVER, UNDER OR ADJACENT TO NORFOLK SOUTHERN RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH THE NORFOLK SOUTHERN "SPECIAL PROVISIONS FOR THE PROTECTION OF RAILWAY INTERESTS."

"ONE CALL" SERVICES DO NOT LOCATE BURIED RAILROAD SIGNAL AND COMMUNICATION LINES. THEREFORE, THE CONTRACTOR SHALL CONTACT THE RAILROAD'S REPRESENTATIVE TWO (2) DAYS IN ADVANCE OF ACTIVITIES IN PLACES WHERE HEAVY LOADS MAY DAMAGE RAILROAD UNDERGROUND LINES ON RAILROAD PROPERTY. UPON REQUEST FROM THE CONTRACTOR OR AGENCY, RAILROAD SIGNAL FORCES WILL LOCATE AND PAINT MARK OR FLAG RAILROAD UNDERGROUND SIGNAL, COMMUNICATION, AND POWER LINES IN THE AREA TO BE DISTURBED FOR THE CONTRACTOR. THE CONTRACTOR SHALL AVOID EXCAVATION OR OTHER DISTURBANCE OF THESE LINES WHICH ARE CRITICAL TO THE SAFETY OF THE RAILROAD AND THE PUBLIC. IF DISTURBANCE OR EXCAVATION IS REQUIRED NEAR A BURIED RAILROAD SIGNAL, COMMUNICATION, OR POWER LINE, THE LINE SHALL BE POTHOLED MANUALLY WITH CAREFUL HAND EXCAVATION BY THE CONTRACTOR AND PROTECTED BY THE CONTRACTOR DURING THE COURSE OF THE DISTURBANCE UNDER THE SUPERVISION AND DIRECTION OF A RAILROAD SIGNAL REPRESENTATIVE.

ALL UTILITY INSTALLATIONS OR RELOCATIONS ON NORFOLK SOUTHERN RIGHT-OF-WAY THAT ARE REQUIRED IN CONJUNCTION WITH THIS PROJECT CAN BE INSTALLED OR RELOCATED AS PART OF THE PROJECT PROVIDED THE CONSTRUCTION IS PERFORMED BY THE PROJECT CONTRACTOR OR PROJECT CONTRACTOR'S SUB-CONTRACTOR. HOWEVER, THE UTILITY MUST SUBMIT AN APPLICATION FOR THE INSTALLATION OR RELOCATION TO AECOM FOR APPROPRIATE HANDLING FOR LICENSE AGREEMENT AND APPLICABLE FEES. FOR UTILITY APPLICATIONS GO TO: WWW.NSCORP.COM > REAL ESTATE > NS SERVICES > WIRE, PIPELINE, AND FIBER OPTICS PROJECTS. LICENSE AGREEMENT MUST BE EXECUTED PRIOR TO UTILITY BEING INSTALLED OR RELOCATED.

THE PROPOSED PROJECT WILL NOT CHANGE THE QUANTITY AND/OR CHARACTER OF FLOW ON NORFOLK SOUTHERN RIGHT-OF-WAY OR IN THE DITCHES AND DRAINAGE STRUCTURES.

THE ELEVATION OF THE TOP-OF-RAIL SHALL BE VERIFIED TO MATCH THE APPROVED FINAL PLANS BEFORE BEGINNING CONSTRUCTION. THE TOP-OF-RAIL ELEVATIONS FOR BOTH RAILS SHALL BE CONFIRMED. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE NORFOLK SOUTHERN PUBLIC PROJECTS ENGINEER.

CALCULATED
SAH
CHECKED
DUL

GENERAL NOTES

JEF - 213 - 18.43

4
35