

PID: 111004
C-R-S: LAK-90-11.51

SEEDING AND MULCHING QUANTITY CALCULATIONS

ITEM 659 - SEEDING AND MULCHING 505 SY
505 SY from cross sections
0 SY additional CAD generated area

ITEM 659 - SOIL ANALYSIS TEST 2 EACH
2 Tests minimum
or 1 Test per 48400 SY of seeded area if no topsoil is to be placed
or 1 Test per 10000 CY of topsoil if topsoil is being placed

ITEM 659 - TOPSOIL 56 CY
111 CY per 1000 SY of seeded area

ITEM 659 - REPAIR SEEDING AND MULCHING
5% of the permanent seeded area 25 SY

ITEM 659 - INTER-SEEDING
5% of the permanent seeded area 25 SY

ITEM 659 - COMMERCIAL FERTILIZER 0.08 TON
1 Ton per 7410 SY of permanent seeded area
0.7 Ton per 7410 SY of inter-seeding area

ITEM 659 - LIME 0.10 ACRES
Applied over entire permanent seeded area

ITEM 659 - WATER 3 M. GAL.
0.0054 Gallons per 1 SY of permanent seeded area
0.0027 Gallons per 1 SY of inter-seeding area