

STATION RANGE			ROUTE	SIDE	DISTANCE (D)	AVERAGE WIDTH (W)	SURFACE AREA (A) A=DxW/9	CADD GENERATED AREA	202	204	301	304	407	441									
					FT	FT	SY		SY	SY	SY	SY	SY	SY	CY	CY	GAL	CY					
247+75.00	TO	248+13.41	US 6	LT/RT	38.41	30.00	128.03		128.0				14.1	10.67									
247+75.00	TO	248+13.41	US 6	LT/RT	38.41	30.67	130.88				16.4		7.2										
247+75.00	TO	248+13.41	US 6	LT/RT	38.41	31.67	135.15				16.9												
247+75.00	TO	248+13.41	US 6	LT/RT	38.41	32.67	139.41			139.4		23.2											
252+66.74	TO	253+00.00	US 6	LT/RT	33.26	30.00	110.87		110.9				12.2	12.32									
252+66.74	TO	253+00.00	US 6	LT/RT	33.26	30.67	113.33				14.2		6.2										
252+66.74	TO	253+00.00	US 6	LT/RT	33.26	31.67	117.03				14.6												
252+66.74	TO	253+00.00	US 6	LT/RT	33.26	32.67	120.72			120.7		20.1											
248+13.41	TO	248+25.33	US 6	LT/RT	11.92	30.00	39.73		39.7		9.9		6.6	4.41									
248+13.41	TO	248+25.33	US 6	LT/RT	11.92	32.00	42.38			42.4		7.1											
248+25.33	TO	248+43.41	US 6	LT/RT	18.08	30.00	60.27		60.3		15.1		9.9	6.70									
248+25.33	TO	248+43.41	US 6	LT/RT	18.08	35.00	70.31			70.3		11.7											
252+36.74	TO	252+52.24	US 6	LT/RT	15.50	33.00	56.83		56.83		14.2		9.4	6.31									
252+36.74	TO	252+52.34	US 6	LT/RT	15.60	35.00	60.67			60.67		10.1											
252+52.24	TO	252+66.74	US 6	LT/RT	14.50	31.00	49.94		49.94		12.5		8.2	5.55									
252+52.24	TO	252+66.74	US 6	LT/RT	14.50	33.00	53.17			53.17		8.9											
TOTALS CARRIED TO GENERAL SUMMARY									445.68	486.66	113.74	81.11	73.83	45.96									
									446	487	114	81	74	46									

PAVEMENT CALCULATIONS

DESIGN AGENCY  
  
 CARPENTER MARTY

DESIGNER  
 JJJ

REVIEWER  
 TWG 03-17-23

PROJECT ID  
 113000

SHEET TOTAL  
 1 1