

SHEET NUM.		PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
3	5	01/NFA/04		EXT	TOTAL			
							EROSION CONTROL	
		500	832	30000	500	EACH	EROSION CONTROL	
							PAVEMENT	
	78	78	204	10000	78	SY	SUBGRADE COMPACTION	
	3,946	3,946	254	01000	3,946	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	
10		10	251	98000	10	CY	PARTIAL DEPTH REPAIR, MISC.: (ASPHALT)	3
	9	9	301	56000	9	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
	13	13	304	20000	13	CY	AGGREGATE BASE	
	349	349	407	20000	349	GAL	NON-TRACKING TACK COAT	
	172	172	441	50000	172	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
5		5	441	50101	5	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), AS PER PLAN, PG64-22	3
							MAINTENANCE OF TRAFFIC	
	8	8	614	12460	8	EACH	WORK ZONE MARKING SIGN	
							DRAINAGE	
50		50	611	00510	50	FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	
70		70	839	30000	70	FT	TRENCH DRAIN, TYPE B WITH STANDARD GRATE, TYPE B	
							INCIDENTALS	
		LS	614	11000	LS		MAINTAINING TRAFFIC	
		LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER
KDR

REVIEWER

DMB

PROJECT ID

111169

SHEET TOTAL

P.4 6

ROAD DESIGNATION	SPLITS	AVERAGE LENGTH	AVERAGE WIDTH OF PAVING (WP)	PAVEMENT AREA	407	441	254	301	304	441	204	COMMENTS
					NON-TACKING COAT (0.085 GAL/SY)	ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (448), PG64-22	PAVEMENT PLANING ASPHALT CONCRETE, CLASS A	ASPHALT CONCRETE BASE, PG64-22	AGGREGATE BASE	ASPHALT CONCRETE SURFACE COURSE, TYPE I, (448) PG64-22	SUBGRADE COMPACTION	
		FT	FT	SY	GALLON	1.5" CY	1.5" SY	4" CY	6" CY	3" CY	SY	
DEAN FOREST ROAD SECTION 1	01/NFA/04	782.53	13	1130.321	96.08	47.10	1130.32					
DEAN FOREST ROAD SECTION 2		218.76	11.5	279.527	23.76	11.65	279.53					
DEAN FOREST ROAD SECTION 3		221.32	13	319.684	27.17	13.32	319.68					
RANGER STATION LOT	01/NFA/04	AREA QUANTITY MEASURED IN GOOGLE EARTH AND IN THE FIELD		1463.92	124.43	61.00	1463.92					RESURFACING OF RANGER STATION ROAD AND PARKING
RANGER LOT ROADS				751.97	63.92	31.33	751.97					
NEW PAVEMENT AREA	01/NFA/04	AREA QUANTITY MEASURED ON GOOGLE EARTH AND IN THE FIELD		77.78	13.22			8.64	12.96	6.48	77.78	NEW PAVEMENT BESIDE EQUIPMENT GARAGE
01/NFA/04 TOTALS:					348.58	164.39	3945.42	8.64	12.96	6.48	77.78	
TOTALS CARRIED TO GENERAL SUMMARY:					349	165	3946	9	13	7	78	

PAVEMENT CALCULATIONS

DESIGN AGENCY



DESIGNER
KDR

REVIEWER

DMB

PROJECT ID

111169

SHEET

P.5

TOTAL
6