

SHEET NUM.										PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	6	7	8	9	01/STR/PV	02/STR/BR											
<b>PAVEMENT</b>																		
1,500						1,500				251	01001	1,500	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN	3			
29,687						29,687				254	01600	29,687	SY	PATCHING PLANED SURFACE				
		90,478	57,089			147,567				254	01000	147,567	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"				
		7,691	4,853			12,544				407	20000	12,544	GAL	NON-TRACKING TACK COAT				
		3,770	2,379			6,149				441	50000	6,149	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22				
		11.5	7.3			18.8				209	60500	18.8	MILE	LINEAR GRADING				
465						465				617	10100	465	CY	COMPACTED AGGREGATE				
		5.76	3.65			9.41				618	43000	9.41	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)				
		5.76	3.65			9.41				874	21000	9.41	MILE	LONGITUDINAL JOINT PREPARATION				
<b>TRAFFIC CONTROL</b>																		
						18.93				644	00104	18.93	MILE	EDGE LINE, 6"				
						9.46				644	00300	9.46	MILE	CENTER LINE				
						0.11				646	10010	0.11	MILE	EDGE LINE, 6"				
						0.06				646	10200	0.06	MILE	CENTER LINE				
						870				621	54000	870	EACH	RAISED PAVEMENT MARKER REMOVED				
						870				621	00100	870	EACH	RPM				
<b>STRUCTURE REPAIR (LAW-93-12.83 SFN: 4401573)</b>																		
					77		77			409	30000	77	FT	SAWING AND SEALING ASPHALT CONCRETE PAVEMENT JOINTS				
<b>STRUCTURE REPAIR (LAW-93-17.84 SFN: 4401816)</b>																		
					44		44			846	00110	44	CF	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM				
<b>STRUCTURE REPAIR (LAW-93-19.17 SFN: 4401840)</b>																		
					440		440			512	10400	440	SY	TREATING OF CONCRETE BRIDGE DECK WITH SRS				
					44		44			512	10300	44	SY	SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN				
					20		20			519	12304	20	SY	PATCHING CONCRETE BRIDGE DECK - TYPE C				
<b>STRUCTURE REPAIR (LAW-93-19.61 SFN: 4401875)</b>																		
					288		288			512	10400	288	SY	TREATING OF CONCRETE BRIDGE DECK WITH SRS				
					29		29			512	10300	29	SY	SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN				
<b>STRUCTURE REPAIR (LAW-93-20.90 SFN: 4401914)</b>																		
					412		412			512	10400	412	SY	TREATING OF CONCRETE BRIDGE DECK WITH SRS				
					41		41			512	10300	41	SY	SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN				
<b>MAINTENANCE OF TRAFFIC</b>																		
	18					18				614	12460	18	EACH	WORK ZONE MARKING SIGN				
	38.08					38.08				614	22360	38.08	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT				
	19.04					19.04				614	21550	19.04	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT				
<b>INCIDENTALS</b>																		
						0.97	0.03			614	11000	LS		MAINTAINING TRAFFIC				
						0.97	0.03			623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING				
						0.97	0.03			624	10000	LS		MOBILIZATION				

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER  
ZDR


REVIEWER  
CLC 08-24-22

PROJECT ID  
114527

SHEET TOTAL  
P.5 | 9

SPLITS	TYPICAL SECTIONS	ROUTE	S.L.M.		LENGTH FT	644		646		RAISED PAVEMENT MARKER REMOVED REMOVED	621			COMMENTS
			FROM	TO		EDGE LINE, 6" MILE	CENTER LINE MILE	EDGE LINE, 6" MILE	CENTER LINE MILE		RPM			
											ONE WAY WHITE	TWO WAY YELLOW / YELLOW		
01/STR/PV	1	93	12.00	21.52	50266	18.93	9.46			870		870		
01/STR/PV		93	LAW-93-19.17		110			0.04	0.02					
01/STR/PV		93	LAW-93-19.61		81			0.03	0.015					
01/STR/PV		93	LAW-93-20.90		92.5			0.04	0.02					
01/STR/PV TOTALS:						18.93	9.46	0.11	0.055	870		870		
TOTALS CARRIED TO GENERAL SUMMARY:						18.93	9.46	0.11	0.06	870		870		

PAVEMENT MARKINGS

DESIGN AGENCY  
  
 DESIGNER  
 ZDR  
 REVIEWER  
 CLC 08-24-22  
 PROJECT ID  
 114527  
 SHEET TOTAL  
 P.8 | 9