


SHEET NUM.											PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	6	7	8	9						01/STR/05	EXT	TOTAL				
ROADWAY																	
1.59											1.59	209	60500	1.59	MILE	LINEAR GRADING	
EROSION CONTROL																	
											1,000	832	30000	1,000	EACH	EROSION CONTROL	
PAVEMENT																	
1,000											1,000	251	01001	1,000	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN	
		133,846	1,396								135,242	254	01000	135,242	SY	PAVEMENT PLANING, ASPHALT CONCRETE 1.5"	
26,769											26,769	254	01600	26,769	SY	PATCHING PLANED SURFACE	
		12,046	119								12,165	407	20000	12,165	GAL	NON-TRACKING TACK COAT	
		5,577	49								5,626	441	50000	5,626	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
3.11											3.11	617	10100	3.11	CY	COMPACTED AGGREGATE	
3											3	617	25000	3	MGAL	WATER	
TRAFFIC CONTROL																	
			1,035								1,035	621	00100	1,035	EACH	RPM	
			1,035								1,035	621	54000	1,035	EACH	RAISED PAVEMENT MARKER REMOVED	
			15.69								15.69	644	00104	15.69	MILE	EDGE LINE, 6"	
			7.84								7.84	644	00300	7.84	MILE	CENTER LINE	
			136								136	644	00500	136	FT	STOP LINE	
			2								2	644	01110	2	EACH	SCHOOL SYMBOL MARKING, 96"	
			0.25								0.25	646	10010	0.25	MILE	EDGE LINE, 6"	
			0.13								0.13	646	10200	0.13	MILE	CENTER LINE	
STRUCTURE REPAIR (SFN: 4402405, LAW-141-1171)																	
					56						56	846	00110	56	CF	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	
MAINTENANCE OF TRAFFIC																	
	52										52	614	12460	52	EACH	WORK ZONE MARKING SIGN	
	15.94										15.94	614	21550	15.94	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
	31.88										31.88	614	22360	31.88	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
INCIDENTALS																	
											LS	614	11000	LS		MAINTAINING TRAFFIC	
											LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

 DESIGNER
 JBS
 REVIEWER
 EMB MM-DD-YY
 PROJECT ID
 118758
 SHEET TOTAL
 P.5 | 9

