

SHEET NUMBER												PART.		ITEM	ITEM	GRAND		UNIT	DESCRIPTION	SEE SHEET NO.
4	5		7		9			31				01/STR/04		EXT	TOTAL					
																		ROADWAY		
LS												LS	201	11000	LS			CLEARING AND GRUBBING		
17												17	202	23000	17	SY		PAVEMENT REMOVED		
								25,588				25,588	203	10001	25,588	CY		EXCAVATION, AS PER PLAN	4	
								66				66	203	20000	66	CY		EMBANKMENT		
19												19	204	10000	19	SY		SUBGRADE COMPACTION		
60												60	862	00500	60	HOUR		SCALING		
																		DRAINAGE		
					505							505	202	32500	505	FT		CURB AND GUTTER REMOVED		
					77							77	202	35100	77	FT		PIPE REMOVED, 24" DIAMETER AND UNDER		
					1							1	202	58100	1	EACH		CATCH BASIN REMOVED		
					2							2	202	98100	2	EACH		REMOVAL MISC.:CATCH BASIN CLEAN OUT	4	
					40							40	SPECIAL	20270000	40	FT		FILL AND PLUG EXISTING CONDUIT, 15"	4	
					250							250	209	10001	250	FT		DITCH CLEANOUT, AS PER PLAN (TYPE 5, CURB AND GUTTER)	4	
					10							10	601	39500	10	FT		PAVED GUTTER, TYPE 5		
					77							77	611	05900	77	FT		15" CONDUIT, TYPE B		
																		EROSION CONTROL		
1,118												1,118	659	10000	1,118	SY		SEEDING AND MULCHING		
0.1												0.1	659	20000	0.1	TON		COMMERCIAL FERTILIZER		
0.23												0.23	659	31000	0.23	ACRE		LIME		
4												4	659	35000	4	MGAL		WATER		
5,000												5,000	832	30000	5,000	EACH		EROSION CONTROL		
																		MAINTENANCE OF TRAFFIC		
			3									3	SPECIAL	61411300	3	EACH		WORK ZONE TRAFFIC SIGNAL	5	
			4									4	614	12384	4	EACH		WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (BIDIRECTIONAL)		
			42									42	614	13310	42	EACH		BARRIER REFLECTOR, TYPE 1, BI-DIRECTIONAL		
			23									23	614	13314	23	EACH		BARRIER REFLECTOR, TYPE 3 (FOR GUARDRAIL)		
			36									36	614	13360	36	EACH		OBJECT MARKER, TWO WAY		
			0.1									0.1	614	21000	0.1	MILE		WORK ZONE CENTER LINE, CLASS I		
			0.03									0.03	614	22000	0.03	MILE		WORK ZONE EDGE LINE, CLASS I, 4"		
			25									25	614	26000	25	FT		WORK ZONE STOP LINE, CLASS I		
	70											70	616	10000	70	MGAL		WATER		
			732									732	622	41011	732	FT		PORTABLE BARRIER, 50", AS PER PLAN	5	
																		PAVEMENT		
2												2	301	56000	2	CY		ASPHALT CONCRETE BASE, PG64-22, (449)		
3												3	304	20000	3	CY		AGGREGATE BASE		
2												2	407	10000	2	GAL		TACK COAT		
2												2	441	70000	2	CY		ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22		
																		INCIDENTALS		
	LS											LS	614	11000	LS			MAINTAINING TRAFFIC		
	LS											LS	614	12420	LS			DETOUR SIGNING		
												6	619	16000	6	MNTH		FIELD OFFICE, TYPE A		
LS												LS	623	10001	LS			CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	4	
LS												LS	623	50000	LS			PRECONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT		
LS												LS	623	51000	LS			POST CONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT		
												LS	624	10000	LS			MOBILIZATION		

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER
AJC

REVIEWER

MWH 10/17/25

PROJECT ID
118778

SHEET	TOTAL
P.10	5