

ITEM 614, MAINTAINING TRAFFIC

A MINIMUM OF TWO (2) LANES OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES, EXCLUDING THE CLOSURE TIMES STATED IN THE LANE VALUE CONTRACT TABLE BELOW.

AREAS THAT ARE PLANNED SHALL NOT BE OPENED TO TRAFFIC. ALL PLANNED AREAS MUST BE INLAID WITH A PROPOSED COURSE OF ITEM 442, ASPHALT CONCRETE PRIOR TO BEING OPENED TO TRAFFIC.

OVERNIGHT CLOSURES MUST MEET SPECIFICATIONS AS OUTLINED IN THE CONSTRUCTION AND MAINTENANCE OPERATIONS SECTION OF THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS. THE ROADWAY SHALL NOT BE OPENED TO TRAFFIC WITHOUT EITHER THE PERMANENT OR WORK ZONE MARKINGS IN PLACE. **THE ROADWAY SHALL NOT BE OPENED TO TRAFFIC WITHOUT EITHER THE PERMANENT OR WORK ZONE MARKINGS IN PLACE.**

LANE VALUE CONTRACT TABLE

LOCATION	CRITICAL WORK: TIME WHEN ONE (1) LANE MAY BE CLOSED	TIME UNIT	DISINCENTIVE (\$ PER TIME UNIT)
I.R. 70 E.B. & W.B.	HTTP://PLCM.DOT.STATE.OH.US SPRING/FALL MONDAY-THURSDAY: 6PM-2PM FRIDAY-SUNDAY: 7PM-11AM	15 MIN.	\$2,500
	SUMMER MONDAY-THURSDAY: 7PM-12PM FRIDAY-SUNDAY: 8PM-9AM		

BRIDGES LIC-70-2653 (T.R. 345), LIC-70-2754 (S.R. 668), LIC-70-2863 (T.R.7) ONE-LANE, TWO-WAY TRAFFIC WILL BE PERMITTED, WITH PORTABLE TRAFFIC SIGNALS FOR DECK SEALING PER **SS 961** (SUPPLEMENT 1050), AT APPROVAL OF THE ENGINEER.

I.R. 70/S.R. 668 RAMP RESURFACING

10-HOUR MAXIMUM RAMP CLOSURE WILL BE PERMITTED FOR RESURFACING AT I.R. 70 /S.R. 668 RAMPS. USE PCMS FOR DETOUR, AT APPROVAL OF THE ENGINEER.

LANE CLOSURES WILL BE ACCOMPLISHED IN ACCORDANCE WITH THE STANDARD DRAWINGS LISTED ON THE TITLE SHEET, IN CONSIDERATION OF THE TRAFFIC FLOW. LANE CLOSURES SHALL ONLY OCCUR DURING CONTRACTOR WORK HOURS.

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE NO LONGER THAN 2 MILES, UNLESS DIRECTED BY THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT, IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

THE CONTRACTOR WILL HAVE ON SITE AND IN WORKING AND OR SUITABLE CONDITION; ALL EQUIPMENT, TOOLS, LABORERS, LEO'S, TRAFFIC CONTROL DEVICES AND INCIDENTALS NECESSARY TO EFFICIENTLY PERFORM THE CLOSURE BEFORE INITIALIZING THE LANE CLOSURE.

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

LANES OPEN DURING HOLIDAYS OR SPECIAL EVENTS

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES ON I.R. 70 SHALL BE OPENED TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR EVENTS:

MEMORIAL DAY, FOURTH OF JULY, LABOR DAY, THANKSGIVING, CHRISTMAS, NEW YEARS, EASTER

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPEN DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE THIS PERIOD:

DAY OF WEEK	TIME ALL LANES MUST BE OPEN TO TRAFFIC
SUNDAY	12:00N FRIDAY THROUGH 6:00AM MONDAY
MONDAY	12:00N FRIDAY THROUGH 6:00AM TUESDAY
TUESDAY	12:00N MONDAY THROUGH 6:00AM WEDNESDAY
WEDNESDAY	12:00N TUESDAY THROUGH 6:00AM THURSDAY
THURSDAY	12:00N WEDNESDAY THROUGH 6:00AM FRIDAY
THURSDAY (THANKSGIVING)	12:00N WEDNESDAY THROUGH 6:00AM MONDAY
FRIDAY	12:00N THURSDAY THROUGH 6:00AM MONDAY
SATURDAY	12:00N FRIDAY THROUGH 6:00AM MONDAY

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE PER LANE VALUE CONTRACT (PN 127).

WINDOW CONTRACT TABLE

DESCRIPTION OF CRITICAL WORK	CALENDAR DAYS	DISINCENTIVE (\$ PER TIME UNIT)
ALL WORK ON PROJECT	120	PER CMS 108.07

NOTIFICATION OF ROAD CLOSURE OR RESTRICTIONS

THE CONTRACTOR WILL ADVISE THE PROJECT ENGINEER A MINIMUM OF TWENTY-ONE (21) DAYS PRIOR TO THE FOLLOWING: THE START OF CONSTRUCTION ACTIVITIES, LANE RESTRICTIONS, LANE CLOSURES, AND OR ROAD CLOSURES. THE PROJECT ENGINEER WILL FORWARD THIS INFORMATION TO THE FOLLOWING:

DISTRICT PUBLIC INFORMATION OFFICER (PIO) BY FAX AT (614) 887-4510 OR EMAIL AT D05.PIO@DOT.STATE.OH.US

DISTRICT PERMIT SECTION BY FAX AT (614) 887-4525 OR EMAIL AT BRIAN.BOSCH@DOT.STATE.OH.US

CENTRAL OFFICE SPECIAL HAUL PERMITS SECTION BY FAX AT (614) 728-4099 OR EMAIL AT HAULING.PERMITS@DOT.STATE.OH.US

THE PIO WILL, IN TURN, NOTIFY THE PUBLIC, THE LOCAL EMERGENCY SERVICES, AFFECTED SCHOOLS AND BUSINESSES, AND ANY OTHER IMPACTED LOCAL PUBLIC AGENCY OF ANY OF THE ABOVE-MENTIONED ITEMS, VIA MEDIA SOURCES.

WORK RESTRICTIONS

NO WORK SHALL BEGIN PRIOR TO MAY 1ST, 2022.

NO WESTBOUND PAVING SHALL BEGIN UNTIL COMPLETION OF PROJECT LIC-70-19.47 PID 93013 (ESTIMATED COMPLETION JULY 31ST, 2022)

FLOODLIGHTING

FLOODLIGHTING OF THE WORK SITE FOR OPERATIONS CONDUCTED DURING NIGHTTIME PERIODS SHALL BE ACCOMPLISHED SO THAT THE LIGHTS DO NOT CAUSE GLARE TO THE DRIVERS ON THE ROADWAY. TO ENSURE THE ADEQUACY OF THE FLOODLIGHT PLACEMENT, THE CONTRACTOR AND THE ENGINEER SHALL DRIVE THROUGH THE WORK SITE EACH NIGHT WHEN THE LIGHTING IS IN PLACE AND OPERATIVE PRIOR TO COMMENCING ANY WORK. IF GLARE IS DETECTED, THE LIGHT PLACEMENT AND SHIELDING SHALL BE ADJUSTED TO THE SATISFACTION OF THE ENGINEER BEFORE WORK PROCEEDS. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE **LUMP SUM BID FOR ITEM 614, MAINTAINING TRAFFIC.**

BUTT JOINT

A BUTT JOINT WILL BE REQUIRED AT THE LOCATIONS SPECIFIED BELOW PER STANDARD DRAWING **BP-3.1** EXCEPT THE MINIMUM LENGTH SHALL BE **300' PER INCH**, UNLESS DIRECTED OTHERWISE BY THE ENGINEER. THE GRINDING FOR BUTT JOINTS SHALL BE INCLUDED WITH ITEM 254, PAVEMENT PLANING, ASPHALT CONCRETE.

THE MINIMUM ASPHALT WEDGE LENGTH AT BUTT JOINTS SHALL BE 20'.

LOCATION	ROUTE	DESCRIPTION	S.L.M.	ITEM 614, ASPHALT CONCRETE FOR MAINTAINING TRAFFIC
				CU. YD.
1	I.R. 70	BEGIN WORK	23.84	7.0
		BRIDGE: LIC-70-2421 L/R	24.21	14.0
		BRIDGE: LIC-70-2583 L/R	25.83	14.0
		BRIDGE: LIC-70-2888 L/R	28.88	14.0
		TOTAL		49.0
2	I.R. 70	END WORK	0.76	7.0

DROP-OFFS IN WORK ZONES

DROP-OFFS THAT DEVELOP DURING CONSTRUCTION OPERATIONS AND THAT ARE NOT OTHERWISE PROVIDED FOR IN THE PLANS SHALL BE TREATED AS SHOWN ON STANDARD DRAWING MT-101.90. WHERE THE PLANS DO NOT PROVIDE SPECIFIC ITEMS FOR LABOR, EQUIPMENT, OR MATERIALS TO IMPLEMENT THE DROP-OFF TREATMENTS SPECIFIED, THEY SHALL BE INCLUDED FOR PAYMENT IN THE **LUMP SUM BID FOR ITEM 614, MAINTAINING TRAFFIC.**

COOPERATION BETWEEN CONTRACTORS

THE STATE OF OHIO HAS CONTRACTED PROJECTS **LIC-70-19.47 PID 93013 AND D05-PM-2022(C) R-WR PID 113444**, WHICH MAY BE CONSTRUCTED CONCURRENTLY WITH THIS PROJECT. IT IS IMPERATIVE THAT THE CONTRACTORS COOPERATE FULLY WITH EACH OTHER AS OUTLINED IN SECTION 105.08 OF THE CMS MANUAL. ALL MAINTENANCE OF TRAFFIC SHALL BE COORDINATED BETWEEN PROJECTS AND NOT CONFLICT WITH ONE ANOTHER

I:\ProjectData\LIC\13922\Design\Roadway\Sheets\13922_MN001.dgn_Sheet 7/21/2021 12:43:36 PM jlutzi

CALCULATED
LIME
CHECKED
JSL

MAINTENANCE OF TRAFFIC NOTES

LIC / MUS-70-
23.84 / 0.00