SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
							3	4	11	12	17	18	1/NHS/14						
																		EROSION CONTROL	
													500	832	30000	500	EACH	EROSION CONTROL	
																		TRAFFIC CONTROL	
									0.4				0.4	646	10000	0.4	MILE	EDGE LINE, 4"	
									0.1				0.1	646	10200	0.1	MILE	CENTER LINE	
																		STRUCTURE OVER 20 FOOT SPAN (LIC-16-29.80 or SFN 4501446)	
										10			10	202	11301	10	CY	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (DECK)	12
										5			5	202	11301	5	CY	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (PARAPET)	12
										483			483	202	11401	483	LB	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (SECONDARY MEMBERS)	12
											7,095		7,095	202	11401	7,095	LB	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN (MAIN MEMBERS)	12
												4,462	4,462	509	25000	4,462	LB	UNCOATED REINFORCING STEEL	
													10	511	34410	10	CY	CLASS QC2 CONCRETE, SUPERSTRUCTURE (DECK)	
													5	511	34448	5	CY	CLASS QC2 CONCRETE, BRIDGE DECK (PARAPET)	
										483			483	513	10201	483	LB	STRUCTURAL STEEL MEMBERS, LEVEL UF, AS PER PLAN	12
													7,095	513	10240	7,095	LB	STRUCTURAL STEEL MEMBERS, LEVEL 2	
										474			474	514	80020	474	SF	SHOP PAINTING AND FIELD TOUCH-UP OF STRUCTURAL STEEL	12
										LS			LS	516	47001	LS		JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN	12
										LS			LS	849	10000	LS		DAMAGE ASSESSMENT	12
													LS	849	10500	LS		SURFACE PREPARATION	
													2	849	10600	2	HOUR	REPAIRING DAMAGED MEMBERS BY GRINDING	
													LS	849	10700	LS		STRAIGHTENING DAMAGED MEMBERS	
																		MAINTENANCE OF TRAFFIC	
								100					100	614	11110	100	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	4
									3				3	614	12384	3	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (BIDIRECTIONAL)	4
									18				18	614	13310	18	EACH	BARRIER REFLECTOR, TYPE 1, ONE WAY	
									18				18	614	13350	18	EACH	OBJECT MARKER, ONE WAY, ONE WAY	
							4						4	614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	3
									0.3				0.3	614	22350	0.3	MILE	WORK ZONE EDGE LINE, CLASS III, 4", 642 PAINT	
									744				744	622	41100	744	FT	PORTABLE BARRIER, UNANCHORED, 32"	
									172				172	622	41111	172	FT	PORTABLE BARRIER, ANCHORED, AS PER PLAN, 32", BRIDGE MOUNTED	2
																		INCIDENTALS	
													LS	614	11000	LS		MAINTAINING TRAFFIC	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER
YEL

REVIEWER
TAG 12/30/22

PROJECT ID
117735

SHEET 10 TOTAL 18

LIC-16-29.80

MODEL: General Summary PAPERSIZE: 17x11 (in.) DATE: 4/10/2023 TIME: 8:40:55 AM USER: tgreenwa
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Licking\117735\400-Engineering\Roadway\Sheets\117735_GG001.dgn