

H:\2013\130545\029 - Newark Arlington Avenue SRTS\98235.LIC-MR313-000\Design\Roadway\Sheets\98235_G0001.dgn Sheet 5/28/2019 12:44:46 PM wncdermitt

SHEET NUM.											PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
5	9	10	11	28	43	47					CALC	01/SC2/OT /NEWA						
ROADWAY																		
LS												LS	201	11000	LS		CLEARING AND GRUBBING	
	121											121	202	23000	121	SY	PAVEMENT REMOVED	
	868											868	202	23010	868	SY	PAVEMENT REMOVED, ASPHALT	
	8,411											8,411	202	30000	8,411	SF	WALK REMOVED	
		75										75	202	30200	75	FT	STEPS REMOVED	
	116											116	202	32000	116	FT	CURB REMOVED	
	446											446	202	35100	446	FT	PIPE REMOVED, 24" AND UNDER	
	5											5	SPECIAL	20252990	5	EACH	PARKING BLOCK REMOVED	5
	5											5	202	58100	5	EACH	CATCH BASIN REMOVED	
	2											2	202	58101	2	EACH	CATCH BASIN REMOVED, AS PER PLAN	6
	1											1	202	75610	1	EACH	VALVE BOX REMOVED	
	2											2	202	98100	2	EACH	REMOVAL MISC.: CINDER BLOCK	5
				527								527	203	10000	527	CY	EXCAVATION	
				110								110	203	20000	110	CY	EMBANKMENT	
	347											347	204	10000	347	SY	SUBGRADE COMPACTION	
		8,145										8,145	608	10000	8,145	SF	4" CONCRETE WALK	
		67										67	608	40000	67	FT	CONCRETE STEPS, TYPE A	
		4										4	608	41000	4	FT	CONCRETE STEPS, TYPE B	
		129										129	608	52000	129	SF	CURB RAMP	
		56										56	608	53020	56	SF	DETECTABLE WARNING	
						6						6	623	40500	6	EACH	REFERENCE MONUMENT	
						10						10	623	40520	10	EACH	RIGHT-OF-WAY MONUMENT	
EROSION CONTROL																		
106												106	659	00300	106	CY	TOPSOIL	
949												949	659	00500	949	SY	SEEDING AND MULCHING, CLASS 1	
0.13												0.13	659	20000	0.13	TON	COMMERCIAL FERTILIZER	
0.2												0.2	659	31000	0.2	ACRE	LIME	
6												6	659	35000	6	MGAL	WATER	
												LS	832	15000	LS		STORM WATER POLLUTION PREVENTION PLAN	
												LS	832	15002	LS		STORM WATER POLLUTION PREVENTION PLAN INSPECTIONS	
												LS	832	15010	LS		STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE	
												20,000	832	30000	20,000	EACH	EROSION CONTROL	
DRAINAGE																		
			1,146									1,146	605	06000	1,146	FT	4" BASE PIPE UNDERDRAINS	
			294									294	611	00510	294	FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	
			5									5	611	03100	5	FT	10" CONDUIT, TYPE B	
			816									816	611	04400	816	FT	12" CONDUIT, TYPE B	
			233									233	611	04600	233	FT	12" CONDUIT, TYPE C	
			32									32	611	08900	32	FT	21" CONDUIT, TYPE B	
			5									5	611	98470	5	EACH	CATCH BASIN, NO. 2-2B	
			3									3	611	98471	3	EACH	CATCH BASIN, NO. 2-2B, AS PER PLAN, TRAPPED STRUCTURE	40
			9									9	611	98690	9	EACH	CATCH BASIN, MISC.:YARD INLET	6
			1									1	611	99574	1	EACH	MANHOLE, NO. 3, 60" DIA.	
2			2									4	611	99575	4	EACH	MANHOLE, NO. 3, AS PER PLAN, NEWARK SD 900	42
			9									9	611	99900	9	EACH	DRAINAGE STRUCTURE, MISC.: NEWARK SD 600-2	40
			1									1	611	99900	1	EACH	DRAINAGE STRUCTURE, MISC.: NEWARK SD 600-2, AS PER PLAN, TRAPPED STRUCTURE	40
PAVEMENT																		
											286	286	301	46000	286	CY	ASPHALT CONCRETE BASE, PG64-22	
	2											2	301	48000	2	CY	ASPHALT CONCRETE BASE, PG64-22 (DRIVEWAYS)	
	60	102										289	451	20000	451	CY	AGGREGATE BASE	
	1											69	70	20000	70	GAL	NON-TRACKING TACK COAT	
											60	60	441	50000	60	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
											83	83	441	50300	83	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	
	1											1	441	50400	1	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), (DRIVEWAYS)	

GENERAL SUMMARY

**LIC-MR313-00.00
SRTS(ARLINGTON)**