SHEET NUM. 3	5	6	8	9	10	11	PART. 01/NHS/05	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
												DRAINAGE	
34							34	611	98635	34	EACH	CATCH BASIN RECONSTRUCTED TO GRADE, AS PER PLAN	3
												PAVEMENT	
1,000							1,000	251	01021	1,000	SY	PARTIAL DEPTH PAVEMENT REPAIR (442), AS PER PLAN	3
			222,252				222,252	421	10010	222,252	SY	MICROSURFACING, SURFACE COURSE	
			155,801				155,801	421	10020	155,801	SY	MICROSURFACING, LEVELING COURSE	
			12,000				12,000	423	00250	12,000	SY	CRACK SEALING, TYPE IV	
					27.63		27.63	850	10010	27.63	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
					4,820		4,820	850	10110	4,820	FT	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
					5,545		5,545	850	10130	5,545	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)	
												TRAFFIC CONTROL	
						667	667	621	00100	667	EACH	RPM	
						667	667	621	54000	667	EACH	RAISED PAVEMENT MARKER REMOVED	
				0.03			0.03	642	00300	0.03	MILE	CENTER LINE, TYPE 1	
				0.18			0.18	642	30030	0.18	MILE	REMOVAL OF PAVEMENT MARKING, CENTER LINE, TYPE 1	
				17.78			17.78	642	30030	17.78	MILE	REMOVAL OF PAVEMENT MARKING, EDGE LINE, 6", TYPE 1	
				9.7			9.7	642	30030	9.7	MILE	REMOVAL OF PAVEMENT MARKING, LANE LINE, 6", TYPE 1	
				5,893			5,893	643	30000	5,893	FT	REMOVAL OF PAVEMENT MARKING, CHANNELIZING LINE, 12"	
				4,820			4,820	643	30000	4,820	FT	REMOVAL OF PAVEMENT MARKING, DOTTED LINE	
				57			57	643	30000	57	FT	REMOVAL OF PAVEMENT MARKING, STOP LINE	
				66			66	643	30000	66	FT	REMOVAL OF PAVEMENT MARKING, TRANSVERSE/DIAGONAL LINE	
				4			4	643	30020	4	EACH	REMOVAL OF PAVEMENT MARKING, LANE ARROW	
				20			20	643	30020	20	EACH	REMOVAL OF PAVEMENT MARKING, SPEED MEASUREMENT MARKING	
					348		348	646	10310	348	FT	CHANNELIZING LINE, 12"	
					57		57	646	10400	57	FT	STOP LINE	
					66		66	646	10600	66	FT	TRANSVERSE/DIAGONAL LINE	
					4		4	646	20300	4	EACH	LANE ARROW	
					400		400	646	20510	400	FT	DOTTED LINE, 12"	
					20		20	646	20710	20	EACH	SPEED MEASUREMENT MARKING	
					17.78		17.78	807	14010	17.78	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6"	
					9.7		9.7	807	14110	9.7	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"	
					0.15		0.15	807	14200	0.15	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CENTER LINE	
					5,545		5,545	807	14310	5,545	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12"	
					4,820		4,820	807	14410	4,820	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 6"	
												MAINTENANCE OF TRAFFIC	
200							200	614	11110	200	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
	4						4	614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6
				0.09			0.09	614	21550	0.09	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
				1,044			1,044	614	23690	1,044	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 12", 642 PAINT	
				171			171	614	26610	171	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
				12			12	614	30650	12	EACH	WORK ZONE ARROW, CLASS III, 642 PAINT	
				0.45			0.45	614	98000	0.45	MILE	WORK ZONE PAVEMENT MARKING, MISC.: WORK ZONE CENTER LINE, CLASS I, 807 PAINT	9
				53.34			53.34	614	98000	53.34	MILE	WORK ZONE PAVEMENT MARKING, MISC.: WORK ZONE EDGE LINE, CLASS I, 6", 807 PAINT	9
				29.1			29.1	614	98000	29.1	MILE	WORK ZONE PAVEMENT MARKING, MISC.: WORK ZONE LANE LINE, CLASS I, 6", 807 PAINT	9
				16,635			16,635	614	98100	16,635	FT	WORK ZONE PAVEMENT MARKING, MISC.: WORK ZONE CHANNELIZING LINE, CLASS I, 12", 807 PAINT	9
				14,460			14,460	614	98100	14,460	FT	WORK ZONE PAVEMENT MARKING, MISC.:WORK ZONE DOTTED LINE, CLASS I, 6", 807 PAINT	9
	10						10	808	18700	10	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY	
												INCIDENTALS	
							LS	614	11000	LS		MAINTAINING TRAFFIC	
							LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER TMK

REVIEWER RPH 4-18-24

PROJECT ID 107476

SHEET P.7 TOTAL 12

LOG-33-10.71

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 9/17/2024 TIME: 9:45:01 AM USER: bcao
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 07\Logan\107476\400-Engineering\Roadway\Sheets\107476_GG001.dgn

PAVEMENT MARKING SUBSUMMARY

PARTICIPATION	ROUTE	SLM / LOCATION FROM	SLM / LOCATION TO	LANE WIDTH	SOLID LINE EQUIVALENT	646 CHANNELIZING LINE, 12", WHITE	646 CHANNELIZING LINE, 12", YELLOW	646 STOP LINE	646 TRANSVERSE/DIAGONAL LINE, YELLOW	646 LANE ARROW, LEFT	646 SPEED MEASUREMENT MARKING	646 DOTTED LINE, 12"	807 WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6", WHITE	807 WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6", YELLOW	807 WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"	807 WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CENTER LINE	807 WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12", WHITE	807 WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12", YELLOW	807 WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 6"		850 GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	850 GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	850 GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)		
						FT	FT	FT	FT	EACH	EACH	FT	MILE	MILE	MILE	MILE	FT	FT	FT		MILE	FT	FT		
1	LOG-33	10.71	15.66	12.00							20.00		8.08	9.70	9.70	0.15					27.63				
1	LOG-33	SLM 10.81 TRANSITION 2 TO 4 LANES							66.00																
1	LOG-33	SLM 10.92 US-33 EB/SR-117 RAMPS				132.00													1100.00			1100.00			
1	LOG-33	SLM 11.05 US-33 WB TO SR-117 EXIT RAMP															500.00		330.00			330.00	500.00		
1	LOG-33	SLM 11.32 INTERSECTION US-33/CR-37				105.00		24.00		2.00		220.00													
1	LOG-33	SLM 12.64 INTERSECTION US-33/CR-57				111.00		33.00		2.00		180.00													
1	LOG-33	SLM 12.95 US-33 EB/WB REST AREAS															2800.00	937.00	2428.00			2428.00	3737.00		
1	LOG-33	SLM 15.44 US-33 EB EXIT RAMP TO US-68															650.00		670.00			670.00	650.00		
1	LOG-33	SLM 15.66 US-68 NB ON RAMP TO US-33															658.00		292.00			292.00	658.00		
					PART.	*SUBTOTALS*																			
					1	*348*		*57*	*66*	*4*	*20*	*400*	*8.08*	*9.7*	*9.7*	*0.15*	*4608*	*937*	*4820*		*27.63*	*4820*	*5545*		
		TOTALS CARRIED TO GENERAL SUMMARY				348		57	66	4	20	400	8.08	9.7	9.7	0.15	4608	937	4820		27.63	4820	5545		

LOG-33-10.71

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 9/17/2024 TIME: 9:38:39 AM USER: bcao
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 07\Logan\107476\400-Engineering\Traffic\Sheets\107476_TS002.dgn

DESIGN AGENCY

DESIGNER
BTC

REVIEWER
TMK 4-18-24

PROJECT ID
107476

SHEET P.10 TOTAL 12