

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
LOR-20-12.62

LIMITED ACCESS

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR OF HIGHWAYS IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02, REVISED CODE OF OHIO

1967 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF HIGHWAYS, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

THE RIGHT-OF-WAY FOR THIS IMPROVEMENT WILL BE PROVIDED BY THE STATE OF OHIO

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING OF THE HIGHWAY TO TRAFFIC AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES

APPROVED DATE: 6-21-68 DIVISION DEPUTY DIRECTOR
 APPROVED DATE: 8-2-68 ENGINEER OF BRIDGES
 APPROVED DATE: 8-21-68 ENGINEER OF LOCATION & DESIGN
 APPROVED DATE: 8-21-68 DEPUTY DIRECTOR OF DESIGN & CONSTRUCTION
 APPROVED DATE: 9-10-68 DEPUTY DIRECTOR OF RIGHT-OF-WAY
 APPROVED DATE: 9-9-68 DEPUTY DIRECTOR OF PLANNING & PROGRAMMING
 APPROVED DATE: 9-10-68 FIRST ASSISTANT DIRECTOR
 APPROVED DATE: 9-10-68 DIRECTOR OF HIGHWAYS


CONVENTIONAL SIGNS

TREES AND STUMPS (EXISTING)	⊗ ⊗ ⊗ ⊗ ⊗
TREES (TO BE REMOVED IN NON - L.A. R/W)	⊗ ⊗ ⊗ ⊗ ⊗
FENCE LINE	— — — — —
POLE LINE	— — — — —
COUNTY LINE	— — — — —
TOWNSHIP LINE	— — — — —
SECTION LINE	— — — — —
CORPORATION LINE	— — — — —
CENTER LINE	— — — — —
GUARD RAIL	— — — — —
DRAIN PIPE	— — — — —
RAILROAD	— — — — —
PROPERTY LINE	— — — — —
EXISTING RIGHT OF WAY	— — — — —
PROPOSED RIGHT OF WAY	— — — — —
PROPOSED LIMITED ACCESS RIGHT OF WAY	— — — — —
PROPOSED LIMITED ACCESS AND RIGHT OF WAY	— — — — —
WORK LIMITS	— — — — —

INDEX OF SHEETS


TITLE SHEET	1
SCHEMATIC LAYOUT & DESIGN DESIGNATION	2-4
TYPICAL SECTIONS	5-12
GENERAL NOTES	13-14
TRAFFIC NOTES	14
CALCULATIONS	15-17
SUMMARY OF TABLES	18-22
GENERAL SUMMARY	23-24
SPECIAL CONSTRUCTION & GUARD RAIL DETAILS	25-29-29A-29B
MEDIAN WIDTH TRANSITIONS	30-31
SUPERELEVATION TABLE (USR-20)	32
PLAN AND PROFILE USR-20	33-49
CROSS SECTIONS USR-20	50-91
SR-301 INTERCHANGE INDEX	92
SR-301 INTERCHANGE	92-126
GRAFTON ROAD INTERCHANGE	127-134
SR-57 INTERCHANGE	135-138
INTERCHANGE PAVEMENT QUANTITIES	139
INTERCHANGE SUMMARY OF TABLES	140-141
SIDE ROADS	142-164, 164A, 164B
STRUCTURES 20' SPAN & UNDER	165-178
TRAFFIC CONTROL	179-218
HIGHWAY LIGHTING	219-233, 233A
STRUCTURE OVER 20' SPAN	234-297
RIGHT OF WAY AND FENCE PLAN	298-322

LORAIN COUNTY
CARLISLE AND EATON TOWNSHIPS
GRADE SEPARATION WITH THE BALTIMORE AND OHIO RAILROAD CO.



Sheet 19 23 Rev 12-3-65 H.E.D.

LOCATION MAP




PORTION TO BE IMPROVED
STATE HIGHWAYS
OTHER ROADS
PORTION TO BE IMPROVED
UNDER SEPARATE CONTRACT

SCALES

PLAN PROFILE - HORIZONTAL
PROFILE - VERTICAL
CROSS SECTIONS

1" = 50'
1" = 50'
1" = 10'
1" = 10'

GRAPHIC SCALES




PROJECT	LINE DATA				LENGTH	
	BEGIN STATION	SUSPEND STATION	RESUME STATION	END STATION	LIN. FT.	MILES
LOR-20-12.62	665+00			843+01.58	17,801.58	3.371
TOTAL LENGTH OF PROJECT					17,801.58	3.371

WORK	LINE DATA				LENGTH	
	BEGIN STATION	SUSPEND STATION	RESUME STATION	END STATION	LIN. FT.	MILES
LOR-20-12.62	661+00	843+01.58 BK	802+57.97 AH	806+55	18,598.61	
RELOC. BUTTERNUT RIDGE RD.	664+15.63			695+52.93	3,137.30	
SR-301	654+53			682+50	2,797.00	
Exist. U.S. 20 (Temp. Rd.)	625+92.19	630+64.33	631+25.66	637+94.28	1,070.76	
Ex. U.S. 20 Ex. B'not Ridge Rd.	735+00			742+45.0	750.00	
* Dewhurst E.E. River Rd. Connection					511.00	
* Grafton Rd.					1,000.00	
** Existing S.R. 57					4,090.00	
Total Length of Work					31,954.67	6.052

* Begin Work 668+45
 Suspend " 669+55
 Resume " 672+00
 Suspend " 681+80
 Resume " 685+20
 End " 685+30

STANDARD DRAWINGS								SUPPLEMENTAL SPECIFICATIONS			
BP-1	6-1-65	CB-8	6-6-68	MC-1	10-1-67	BR-1-65 sh.1	11-24-65	801	1-1-67	814	1-1-67
BP-2	1-17-68	F-2	6-1-65	MC-3	5-1-66	RB-1-55	2-2-59	806	3-1-68	832	5-25-67
BP-3	5-1-68	F-3	2-20-68	MC-4	6-1-65	AS-1-67	1-11-68	808	1-13-67	931	5-25-67
BP-4	1-10-67	L-1	6-1-65	MC-6	6-1-65	SD-1-65 sh.1,2,3	11-8-65	811	1-1-67		
BP-5	6-1-65			MC-7	3-1-66	SP-53	6-30-61	815	1-1-67		
BP-6	6-1-65	GR-1	1-1-67	MH-1	6-1-65			816	8-6-65		
BP-7	1-1-66	GR-2A	1-1-67	MH-1A	8-1-66			825	12-19-67		
C.B.2-2A&B	6-1-65	GR-2B	2-15-68	BP-8	11-1-67			828	1-1-67		
C.B.2-3&2-4	6-1-65	GR-6	7-15-68	HL-1	11-1-65			1001	3-21-66		
C.B.2-5&2-6	6-1-65	HW-E	6-1-65	HL-2	11-1-65						
C.B.5	6-6-68	I-2A	6-1-65	HL-3	11-1-65						
C.B.6	6-1-65			HL-4	1-1-66						



PREPARED AND RECOMMENDED BY
SHAFFER, JOHNSTON,
LICHTENWALTER & ASSOCS. INC.
CONSULTING ENGINEERS
MANSFIELD OHIO WOOSTER

** Begin Work 668+20
 Suspend " 668+30
 Resume " 678+40
 Suspend " 719+10
 Resume " 729+95
 End " 730+05

FILE NO.	LORAIN COUNTY
	LOR-20-12.62
	DATE OF LETTING
	CONTRACT NO.

* Begin Work Sta. 50+61
 Suspend " 53+27
 Resume " 55+65
 Suspend " 58+00
 Resume " 59+95
 End " 60+05

MICROFILMED
MAY 23 1986


U.S.G.S. B.M. 200' N. Exist.
U.S.R. 20, 26' W. of & S.R. 301
Elev. 764.003

FED RD DIVISION	STATE	PROJECT	234
2	OHIO		

LOR-20-12.62

CURVE DATA

P.I. Sta. 689+58.58
 $\Delta = 11^\circ 48' 20'' R.$
 $D = 0^\circ 28'$
 $R = 12,277.67'$
 $T = 1269.36'$
 $L = 2529.72'$
 $E = 65.46'$



TYPICAL TRANSVERSE HALF SECTION
*-On Skew

PROPOSED STRUCTURE

TYPE: Continuous steel beam with reinforced concrete deck and sub-structure.
SPANS: 44.50', 63.75', 63.75', 44.50'
ROADWAY: 73'-0" w/ Parapets with 3'-0" raised median.
LOAD FREQUENCY: CF 2000 (57)
SKEW: 25'-00' RF
WEARING SURFACE: 1" Monolithic concrete
APPROACH SLABS: AS-1-67 (25' long mod.)
ALIGNMENT: Tangent
AVERAGE DAILY TRAFFIC: P-9845, C-C60, Total=10,505 S.R.301; P-7655, C-G450, Total=14,105 U.S.R.20 (1983)

FOUNDATION INVESTIGATION LEGEND

⊕ - Indicates core boring location
 • - Indicates rod sounding location


SHAFFER, JOHNSTON, LICHENWALTER AND ASSOCIATES, INC.
 Consulting Engineers
 MANSFIELD OHIO WOOSTER

SITE PLAN
BRIDGE NO. LOR-20-1303
UNDER S.R. 301


LORAIN COUNTY USR 20


STA. 686+74.94

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGC	DGC	RAR	RAK	7-12-68		



PVI Sta. 665+50
 Elev. 784.40'
 LVC = 1100'
 Corr. = -7.865'





GENERAL NOTES

REFERENCE shall be made to Standard Drawings SD-1-65, sheets 1, 2 and 3 (dated 11-8-65); BR-1-65, sheet 1 (revised 11-24-65); RB-1-55 (revised 2-2-59); AS-1-67 (dated 1-11-68); and to Supplemental Specifications 808 (revised 1-13-67), 811 (dated 1-1-67), 825 (dated 12-19-67), 828 (revised 1-1-67), 832 (dated 5-25-67) and 931 (dated 5-25-67).

DESIGN SPECIFICATIONS: This structure conforms to the requirements of "Design Specifications for Highway Structures" of the State of Ohio, Department of Highways, dated 9-1-57, together with current revisions thereof.

DESIGN DATA: Design Loading - CF 2000 (57).

Concrete Class "C" - basic unit stress 1,333 p.s.i.
Concrete Class "E" - basic unit stress 1,133 p.s.i.

Structural Steel - ASTM A36 - basic unit stress 20,000 p.s.i.
Reinforcing Steel - ASTM A15, A16, A160, Deformed, Intermediate or Hard Grade. Basic unit stress 20,000 p.s.i. Except, spiral reinforcement may be plain, Structural Grade with basic unit stress of 18,000 p.s.i.

EXCAVATION QUANTITY includes the removal of fill material required for construction of the abutments.

PILES for the abutments shall be driven to a minimum bearing capacity of 35 tons per pile.


FOUNDATION BEARING PRESSURE: Pier footings are designed for a maximum bearing pressure of 2.3 tons per sq. ft.

MACHINE FINISH: The concrete bridge deck shall be finished by the use of a finishing machine.

UTILITY LINES: All expense involved in relocating the affected utility lines shall be borne by the owners. The Contractor and Owners are requested to cooperate by arranging their work in such a manner that inconvenience to either will be held to a minimum.

PROCEDURE: The embankment shall be placed and compacted up to the finished spill-thru slope and to the level of the subgrade for a distance of 200 feet back of the abutments, after which excavation shall be made for the abutments and the piles driven.


PAINTING of structural steel shall be according to Supplemental Specification 832.

WELDS on secondary stress carrying members are shown thus: 

WELDED ATTACHMENTS: No attachments shall be made by field welding to the top flanges or flange plates of continuous beams or plate girders within a distance of 0.10 of the span length on either side of the interior supports. Welding for attachments to the top flanges at other parts of the spans shall be kept at least 2" from edge of flange.

LIGHTING: For structure grounding see Standard Drawing HL-4.

LIGHT POLE BASE DETAILS: See sheet No. 297A.



ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER.	ABUTS.	PIERS	GEN'L
503	805	Cu.Yds.	Unclassified excavation		350	455	
503	Lump	Sum	Cofferdams, Cribbs and sheeting				Lump
505	Lump	Sum	First test pile				Lump
507	800	Lin.Ft.	12" Cast-in-place reinf. concrete piles		800		
509	227,462	Lbs.	Reinforcing steel	139,474	18,483	69,505	
511	542	Cu.Yds.	Class "C" concrete, superstructure	542			
511	155	Cu.Yds.	Class "C" concrete, piers above footings			155	
511	182	Cu.Yds.	Class "E" concrete, pier footings			182	
511	289	Cu.Yds.	Class "E" concrete, abutments		289		
512	15	Lin.Ft.	Premolded sealing strip		15		
513	384,120	Lbs.	Structural steel	384,120			
517	497.17	Lin.Ft.	Bridge railing, type 1	437.42	59.75		
518	16	Each	Scupper, including supports	16			
518	61	Cu.Yds.	Porous backfill		61		
518	153	Lin.Ft.	6" Helical perforated CMP, 707.06, included specials		153		
518	84	Lin.Ft.	6" Helical CMP, 707.06, non-perforated		84		
601	871	Sq.Yds.	Crushed aggregate slope protection				871
625			See sheet No. 223 for Lighting Quantities				
808	541	Units	Water-reducing, set-retarding admixture	541			
825	2033	Sq.Yds.	Concrete surface treatment	1953	80		
828	150	Lin.Ft.	Joint sealer		150		
832	384,120	Lbs.	Field painting structural steel	384,120			

CHAFFSHAFER, JOHNSTON, STONE & LICHTENWALTER AND ASSOCIATES, INC. Consulting Engineers
MANSFIELD, WOOSTER, OHIO

GENERAL PLAN, GENERAL NOTES AND ESTIMATED QUANTITIES
BRIDGE NO. LOR-20-1303
UNDER S.R. 301
LORAIN COUNTY, OHIO STA. 686+74.94 U.S.R. 20


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGC	RWH	RWH		RAK	7-12-68	

MICROFILMED
MAY 23 1986

FED. RD. DIVISION	STATE	PROJECT	238
2	OHIO		


LOR-20-12.62

@ Pier 1 - Sta. 664+31.38
 @ Pier 2 - Sta. 664+95.13
 @ Pier 3 - Sta. 665+58.88




HALF PLAN PIERS 1 AND 3

HALF PLAN PIER 2




VIEW A-A




SECTION B-B

SECTION C-C




SECTION D-D

SECTION E-E




SECTION F-F

SECTION G-G




HALF ELEVATION PIERS 1 AND 3


HALF ELEVATION PIER 2



SECTION H-H



SECTION J-J



SECTION K-K

PIER NOTES:

CONCRETE: All concrete for pier footings shall be Class "E". All concrete for piers above footings shall be Class "C".

BRIDGE SEAT REINFORCING: Special care shall be taken in placing reinforcing steel in the vicinity of the bridge seat so as to avoid interference with the drilling of anchor bolt holes at Pier 2.

GENERAL NOTES: See sheet 2/8

SHAFER, SHAFER & JOHNSTON, INC. 5/8
 LICHTENWALTER AND ASSOCIATES, INC.
 Consulting Engineers
 MANSFIELD, OHIO WOOSTER, OHIO


PIERS
BRIDGE NO. LOR-20-1303
UNDER S.R. 301
 LORAIN COUNTY U.S.R. 20
 STA. 686 + 74.94

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGC	DGC	RWH	RAK	7-12-68		

MICROFILMED
MAY 23 1986


FED. RD. DIVISION	STATE	PROJECT	239
2	OHIO		

LOR-20-12.62



Note: Structural framing symmetrical by rotation about ⊕ Pier 2 except for location of bolted field splice 'B'.

HALF FRAMING PLAN



Intermediate crossframe angles 3x3x5/16. Weld both sides of vertical leg and top side of horizontal leg to beam with 1/4" continuous fillet weld.

*These are nominal dimensions. The quantity of deck concrete to be paid for shall be based on these dimensions, even though deviation from them may be necessary because the top flange of the beam may not have the exact camber or conformation required to place it parallel to the finished grade. Deduction shall be made for the volume of encased steel plates as per 511.19 of the Construction and Material Specifications.

A typical haunch width of 9" shall be used for computing quantity of concrete. However, the haunch width may vary between 6" and 12" provided that the slope shall be not more than 1:4 for a haunch less than 9" in width.

HALF TRANSVERSE SECTION

SUPERSTRUCTURE NOTES:

END CROSSFRAMES, END DAMS, SCUPPERS, CURB PLATES AND MOMENT PLATES: See Standard Drawing SD-1-65, sheets 1 and 2.

BRIDGE RAILING: See Standard Drawing BR-1-65, sheet 1 of 2; Type 1.



CONCRETE: All superstructure concrete shall be Class "C".

FIELD BOLTED BEAM SPLICES: See Standard Drawing SD-1-65, sheet 3.

RAILING POST, PARAPET EXPANSION JOINT AND SCUPPER SPACING: See sheet 7 | 8

BEARINGS: See Standard Drawing RB-1-55 for the following:
R-75: Abutments
R-150: Piers 1 and 3.
B-175: Pier 2

GENERAL NOTES: See sheet 2 | 8



BOLTED FIELD SPLICE "A"

Bolts shall be 1" diameter high strength. For details not shown and details of splice 'B' see SD-1-65, sheet 3.



SHAFFER, JOHNSON & ASSOCIATES, INC.
Consulting Engineers
MANSFIELD WOOSTER OHIO

SUPERSTRUCTURE-1
BRIDGE NO. LOR-20-1303
UNDER S.R. 301

LORAIN COUNTY U.S.R. 20
STA. 686 + 74.94

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGC	DGC	RWH		RAK	7-12-68	

LOR-20-12.62



CAMBERING of beams is required in accordance with the following table:

Span location →	END SPANS				INTERIOR SPANS			
	1/4	1/2	3/4	C SPLICE "A"	1/4	1/2	3/4	C SPLICE "B"
Deflection due to weight of steel	0	0	0	1/16"	1/16"	1/16"	0	0
Deflection due to remaining dead load	1/8"	3/16"	1/16"	3/16"	3/16"	5/16"	1/16"	1/16"
Adjustment required for vertical curve	1/16"	1/8"	1/16"	1/4"	1/4"	5/16"	1/4"	1/4"
Required shop camber	3/16"	5/16"	1/8"	1/2"	1/2"	11/16"	5/16"	5/16"

DETAIL "A": See sheet 8 / 8

SUPERSTRUCTURE NOTES: See sheet 6 / 8


SHAFFSHAFER, JOHNSTON & LICHENWALTER AND ASSOCIATES, INC.
 Consulting Engineers
 MANSFIELD WOODSTER WOODSTER OHIO

SUPERSTRUCTURE-2
 BRIDGE NO. LOR-20-1303
 UNDER S.R. 301

LORAIN COUNTY U.S.R. 20
 STA. 666 + 74.94




DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGC	DGC	RWH		RAK	7-12-68	

MICROFILMED
MAY 23 1986



ABUTMENTS									
MARK	NO.	LENGTH	TYPE	A	B	C	D	E	WEIGHT
R503	12	4'-2"	5	1'-6"	8"	3/4"			*
R504	8	5'-4"	11	2'-8 1/2"	9"	3/4"	7 3/8"	1'-7"	*
R505	8	15'-0"	Str.						*
R506	8	14'-2"	Str.						*
S503	46	5'-7"	5	2'-2"	8"	0			268
A501	112	8'-3"	3	1'-7"	5'-4"	1'-7"			964
A502	114	6'-9"	3	7 1/2"	6'-3"	0			803
A503	114	6'-4"	3	1'-7"	3'-5"	1'-7"			753
A504	102	21'-2"	Str.						2252
A505	34	22'-11"	Str.						813
A506	32	11'-8"	12	2'-7"	3'-0"				389
A507	22	6'-3"	Str.						143
A508	32	3'-5"	Str.						114
A509	24	Varies	Str.	3'-9" to 4'-6"	Varies 8 each by 4 1/2"				103
A510	54	4'-9"	Str.						268
A511	6	9'-7"	Str.						60
A512	24	3'-1"	9	1'-7"	1'-7"	5 5/8"			77
A513	2	8'-10"	Str.						18
A514	2	7'-4"	Str.						15
A515	12	15'-4"	Str.						192
A516	4	13'-9"	Str.						57
A517	12	4'-3"	3	1'-7"	1'-4"	1'-7"			53
A518	2	3'-11"	Str.						8
A519	2	8'-0"	Str.						17
A520	12	14'-4"	Str.						179
A521	4	10'-2"	Str.						42
A522	6	9'-4"	Str.						58
A523	6	7'-0"	2	3'-0"	2'-7"	7 5/8"	1'-7"	5 5/8"	44
A524	6	5'-7"	2	1'-7"	2'-7"	7 5/8"	1'-7"	5 5/8"	35
A525	12	3'-1"	10	1'-7"	8"	1'-0"	5 5/8"		39
A526	8	4'-2"	3	1'-7"	1'-3"	1'-7"			35
A527	56	②	3	①	1'-4"	①			204
A601	112	13'-10"	3	2'-7"	5'-4"	6'-3"			2327
A602	44	12'-11"	3	5'-11"	1'-5"	5'-11"			854
A603	118	14'-2"	6	4'-7"	1'-5"	5'-11"	11"	2'-0"	2511
A604	22	17'-0"	3	8'-7"	1'-2"	8'-1"			562
A605	10	8'-9"	3	8'-1"	10"	0			131
A801	12	11'-9"	Str.						376
A802	12	12'-3"	Str.						392
A803	42	29'-8"	Str.						3327
TOTAL WEIGHT									18,483


① Varies 10" to 1'-7"; Vary 8 each by 1/2"
 ② Varies 2'-9" to 4'-3"; Vary 8 each by 3"
 *- These railing bars are included with Item 517 for payment.




PIERS									
MARK	NO.	LENGTH	TYPE	A	B	C	D	E	WEIGHT
P401	144	5'-6"	Str.						529
P402	72	6'-0"	Str.						289
P501	24	7'-4"	7	1'-7"	4'-2"	1'-4"			184
P502	6	7'-9"	3	3'-1"	1'-10"	3'-1"			48
P503	6	8'-5"	3	3'-1"	2'-6"	3'-1"			53
P504	12	36'-11"	Str.						462
P505	384	7'-7"	3	2'-7"	2'-8"	2'-7"			3037
P506	12	5'-7"	3	1'-7"	2'-8"	1'-7"			70
P601	144	5'-6"	Str.						1190
P602	72	6'-0"	Str.						649
P901	216	6'-7"	3	5'-7"	1'-3"	0			4835
P902	216	16'-10"	Str.						12,362
P1001	12	12'-3"	3	3'-0"	9'-7"	0			633
P1002	12	35'-3"	Str.						1820
P1003	16	23'-1"	Str.						1589
P1004	100	24'-5"	Str.						10,507
P1005	66	15'-7"	Str.						4426
P1006	66	33'-2"	Str.						9419
P1007	16	18'-3"	Str.						1256
P1101	28	33'-4"	1	31'-9"					4959
P1102	24	12'-6"	1	10'-11"					1594
P1103	16	12'-7"	3	3'-0"	9'-11"	0			1070
P1104	12	10'-6"	Str.						669
P1105	4	11'-6"	Str.						244
P1106	8	23'-3"	Str.						988
P1107	6	35'-7"	Str.						1134
P1108	8	18'-5"	Str.						783
SP401	18	13'-9"	8	4 1/2"	40	2'-8"			4706
TOTAL WEIGHT									63,505

SUPERSTRUCTURE									
MARK	NO.	LENGTH	TYPE	A	B	C	D	E	WEIGHT
R501	98	15'-8"	Str.						*
R502	16	12'-8"	Str.						*
S501	292	4'-11"	4	7'-4"	1'-8"	7 1/2"			1497
S502	292	2'-6"	3	7 1/2"	1'-8"	7 1/2"			761
S503	300	5'-7"	5	2'-2"	8"	0			1747
S504	292	3'-1"	3	1'-2"	1'-0"	1'-2"			939
S601	568	37'-0"	Str.						31,566
S602	952	30'-0"	Str.						42,897
S603	174	28'-0"	Str.						6795
S604	6	5'-0"	Str.						25
S605	6	4'-0"	Str.						25
S606	42	Varies	Str.	35'-4" to 5'-0"	Varies 2 each by 1'-6 3/8"				1272
S607	42	Varies	Str.	34'-3" to 4'-0"	Varies 2 each by 1'-6 3/8"				1200
S608	136	20'-11"	Str.						4273
S701	568	37'-0"	Str.						42,897
S702	6	5'-0"	Str.						25
S703	6	4'-0"	Str.						25
S704	42	Varies	Str.	35'-4" to 5'-0"	Varies 2 each by 1'-6 3/8"				1731
S705	42	Varies	Str.	34'-3" to 4'-0"	Varies 2 each by 1'-6 3/8"				1600
L501	4	9'-5"	14	1'-3"	4'-2"	0			20
L502	4	9'-9"	14	1'-3"	2'-11"	1'-8"			20
L503	4	4'-11"	3	1'-2"	2'-10"	1'-2"			20
L504	4	6'-9"	3	2'-1"	2'-10"	2'-1"			20
TOTAL WEIGHT									139,602

REPLACEMENT BARS			
MARK	NO.	LENGTH	TYPE
RE400	1	6'-3"	13
RE500	1	6'-7"	Str.
RE600	5	6'-11"	Str.
RE700	3	7'-2"	Str.
RE800	1	7'-6"	Str.
RE900	1	7'-10"	Str.
RE1000	2	8'-2"	Str.
RE1100	1	8'-8"	Str.



NOTES:
BAR SIZE is indicated in the bar mark. The first digit where three digits are used, and the first two digits where four are used indicate the bar size number. For example: A300 is a No. 5 size bar and P1102 is a No. 11 size bar.
SPIRAL REINFORCING BARS: The "Length" shown in the steel list for the spiral bars is the distance from the top of the footing to the bottom of the pier cap. The "No. of Turns" shown is the "Length" divided by the pitch, plus 3 turns (total number of closed coils) expressed as nearest whole number. Spiral reinforcing bars shall not have deformations but shall in other respects conform to Item 509. 1 1/2 closed coils shall be provided at the ends of each spiral unit. Four steel channel, tee or angle spacers, weighing approximately 0.68 lbs. per lin. ft. of spacers, shall be provided for each spiral unit. They shall be equally spaced along the periphery of the coil. The number of pounds of these spacers, based on 0.68 lbs. per lin. ft. will be paid for as reinforcing steel and is included in the tabulated quantity of spiral bars.



SHAFER, JOHNSTON, LICHENWALTER AND ASSOCIATES, INC. Consulting Engineers
 MANSFIELD, OHIO REGISTERED
REINFORCING STEEL
 BRIDGE NO. LOR-20-1262 UNDER S.R. 301
 LORAIN COUNTY, OHIO U.S.A.
 STA. 688+74.94
 DESIGNED BY: RAK
 CHECKED BY: RAK
 REVISIONS: RAK 7-12-68

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION

LOR-20-12.59

CARLISLE AND EATON TOWNSHIPS
LORAIN COUNTY

PROJECT DESCRIPTION

GENERAL SAFETY UPGRADING WITH 3" OF OVERLAY, PAVEMENT REPAIR, REMOVAL OF EXISTING RAISED CONCRETE MEDIAN AND REPLACEMENT WITH CONCRETE BARRIER, WIDENING RIGHT PAVED SHOULDER AT RAMPS AND REHABILITATION OF SEVEN STRUCTURE WITH THREE STRUCTURES HAVING NEW AND WIDER DECK

PROJECT DESIGNATION

LOR-20-12.62 APPEARING THROUGHOUT THIS PLAN SHALL BE CONSIDERED TO READ LOR-20-12.59

LIMITED ACCESS


THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE REVISED CODE OF OHIO.

1995 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

UNDER AUTHORITY OF SECTION 4511.21, DIVISION (I) OF THE REVISED CODE OF OHIO, THE REVISED PRIMA FACIE SPEED LIMITS AS INDICATED HEREIN ARE DETERMINED TO BE REASONABLE AND SAFE, AND ARE HEREBY ESTABLISHED FOR THE DURATION OF THIS PROJECT. THE PRIMA FACIE SPEED LIMIT OR LIMITS HEREBY ESTABLISHED SHALL BECOME EFFECTIVE WHEN APPROPRIATE SIGNS GIVING NOTICE THEREOF ARE ERECTED.



USGS QUADRANT NO. N4115-W8200/7.5 GRAFTON, OHIO
LONGITUDE W82° 07' 30" *
LATITUDE N41° 18' 50" *
* LONGITUDE AND LATITUDE AT APPROXIMATE BEGINNING OF PROJECT

PORTION TO BE IMPROVED
STATE & FEDERAL ROUTES
OTHER ROADS

DESIGN DESIGNATION

CURRENT ADT (1996)	9,600
DESIGN YEAR ADT (2016)	13,200
DESIGN HOURLY VOLUME (2016)	1320
DIRECTIONAL DISTRIBUTION	55%
TRUCKS (24 HOUR B&C)	15%
DESIGN SPEED	65M.P.H.
LEGAL SPEED	65M.P.H.

DESIGN FUNCTIONAL CLASSIFICATION - FREEWAY

DESIGN EXCEPTION - SEE SHEET 4 .

UNDERGROUND UTILITIES
TWO WORKING DAYS
BEFORE YOU DIG
CALL 1-800-362-2764 (TOLL FREE)
OHIO UTILITIES PROTECTION SERVICE
NON-MEMBERS
MUST BE CALLED DIRECTLY



INDEX OF SHEETS:

TITLE SHEET	1	PAVEMENT REPAIR DETAILS	78-80, 80A-80E
SCHMATIC PLANS	2-4	APPROACH SLAB & RELIEF JOINT DETAIL	81-85
TYPICAL SECTIONS	5-12, 5A	MISC. BARRIER PLACEMENT DETAILS	85A & 85B
GENERAL NOTES	13-15	CATCH BASIN REPLACEMENT SUBSUMMARY	86
GENERAL NOTES AND MISC.		MISC. CATCH BASIN DETAILS & QUANTITIES	87
CATCH BASIN DETAILS	15A	EDGE DRAIN AND UNDERDRAIN QUANTITIES	88-90, 90A
GENERAL SUMMARY	16-17	SIGNING SHEETS	91-132
SUB-SUMMARY	18-20	PAVEMENT MARKING DETAILS	133-135, 134A
RESURFACING CALCULATIONS	21	RAISED PAVEMENT MARKERS	136
CALCULATION SHEETS	22-24	DELINEATOR PLAN	137-140
STORM WATER POLLUTION PREVENTION PLANS	25-27	MAINTENANCE OF TRAFFIC FENCE PLAN	141-198, 145A, 173A
PLAN SHEETS	28-35, 35A	STRUCTURES OVER 20 FEET	199-212
MISC. MEDIAN DETAIL	36	WEIGH-IN-MOTION SHEETS	213-323
MISC. MEDIAN CROSS SECTIONS	37-71		324-351
MISC. CROSS SECTIONS FOR BRIDGE WIDENINGS	72-77		
MEDIAN GUARDRAIL DETAILS AT BRIDGES	77A		

STANDARD CONSTRUCTION DRAWINGS

NO.	DATE	NO.	DATE	NO.	DATE	NO.	DATE	NO.	DATE	NO.	DATE	NO.	DATE
BP-2.1	10-28-94	GR-3A	2-5-82	MT-95.40	10-1-92	TC-18.26	5-31-79	TC-51.10	1-20-84	HL-30.31	5-1-87	802	3-23-95
BP-2.2	10-28-94	GR-3.1	5-6-91	MT-95.70	2-23-90	TC-21.10	9-1-92	TC-51.11	9-30-94	HL-40.10	3-31-95	811	3-23-95
BP-2.4	2-21-92	GR-3.2	5-6-91	MT-97.10	4-29-88	TC-21.20	9-1-92	TC-52.10	4-3-79	MC-9.1	10-30-92	815	7-17-95
BP-2.5	2-21-92	GR-3.5	1-31-94	MT-98.12	6-24-93	TC-21.31	3-1-79	TC-52.20	4-3-79	LA-1	6-1-79	820	6-14-95
BP-3.1	2-21-92	GR-4.2	5-6-91	MT-98.13	6-24-93	TC-22.10	9-1-92	TC-61.10	4-5-82	A-1-69	6-12-69	845	7-17-95
BP-5.1	10-28-94	GR-5.1	10-30-92	MT-98.14	6-24-93	TC-22.20	9-1-92	TC-65.10	7-7-95	AS-1-81	9-15-94	849	6-14-95
CB-3A	5-1-79	GR-7.1	10-30-92	MT-98.15	6-24-93	TC-31.21	9-1-92	TC-65.11	7-7-95	EXJ-3-82	8-1-84	910	7-17-95
CB-8	11-10-83	GR-8.1	1-31-94	MT-98.16	6-24-93	TC-32.10	9-1-92	TC-65.12	7-7-95	EXJ-4-87	11-12-93	931	7-17-95
F-2	5-1-76	HW-4A	4-1-80	MT-99.20	4-29-88	TC-32.11	9-1-92	TC-71.10	9-10-91	PCB-91	4-24-92	933	7-17-95
F-3	5-1-76	HW-4B	4-1-80	MT-100.00	2-23-90	TC-35.10	8-29-84	TC-72.20	2-26-82	RB-1-55	2-2-59	942	
F-6	5-1-76	I-3A & B	4-1-80	MT-101.60	7-1-92	TC-41.10	8-29-84	TC-82.10	11-24-93	VPF-1-90	3-24-93	944	12-7-95
GR-1.1	5-6-91	MC-9.2	5-6-91	MT-105.10	7-1-92	TC-41.20	6-21-94	HL-10.11	5-1-87	BR-1	12-15-94	949	6-14-95
GR-1.2	10-30-92	MC-9.3	10-30-92	MT-105.11	7-1-92	TC-41.40	6-18-79	HL-10.12	5-1-87	IRJ-8-95	7-6-95	953	6-14-95
GR-1.3	2-21-92	MT-95.30	10-10-88	PCB-91	4-24-92	TC-41.50	6-21-94	HL-10.13	5-1-87	CS-1-93	6-30-95		
GR-2.1	5-6-91	MT-95.31	10-10-88	TC-7.65	3-1-79	TC-42.10	8-19-77	HL-20.14	5-1-87	SD-1-69	6-12-69		
GR-2.2	10-30-92	MT-95.32	8-25-89	TC-12.30	1-20-84	TC-42.20	3-26-79	HL-30.11	5-1-87	BS-1-93	12-19-94		

SUPPLEMENTAL SPECIFICATIONS

APPROVED *Mary Ellen Hendrich, PE, PS*
DATE 12-13-94 DISTRICT DEPUTY DIRECTOR

APPROVED *John H. ...*
DATE 1-13-95 DIRECTOR, DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT NO.
NH-69(135)

PID NO.
4009

CONSTRUCTION PROJECT NO.

RAILROAD INVOLVEMENT
NONE

LOR-20-12.59

DESK FILE: c:\dgm\lorain\201262\F11e.dgn
 WORKSTATION: jschreff
 DATE: 1/3 DEC 96
 970214 LOR-20-12.59
 351PGS
 04-09-97
 DIST. 03

GENERAL NOTES

FHWA REGION	STATE	PROJECT
5	OHIO	

213
351

LORAIN COUNTY
LOR-20-12.62

1. REFERENCE DRAWINGS

REFERENCE SHALL BE MADE TO STANDARD DRAWINGS :

A-1-69	DATED	6/12/69
AS-1-81	DATED	9/15/94 (REV.)
BP-5.1	DATED	10/28/94
EXJ-3-82	DATED	8/1/84 (REV.)
EXJ-4-87	DATED	11/12/93 (REV.)
PCB-91	DATED	4/24/92
RB-1-55	DATED	2/2/59
VPF-1-90	DATED	3/24/93
SD-1-69	DATED	6/12/69

2. SUPPLEMENTAL SPECIFICATIONS

REFERENCE SHALL BE MADE TO SUPPLEMENTAL SPECIFICATIONS :

815	DATED	7/17/95
849	DATED	6/14/95
933	DATED	7/17/95
944	DATED	12/7/95
949	DATED	6/14/95

3. DESIGN DATA

CONCRETE CLASS S - COMPRESSIVE STRENGTH $F'_c = 4,500$ PSI FOR SUPERSTRUCTURE
 CONCRETE CLASS C - UNIT STRESS $F_c = 1,333$ PSI FOR SUBSTRUCTURE
 REINFORCING STEEL - ASTM A615, A616 OR A617
 GRADE 60 MINIMUM YIELD STRENGTH $F_y = 60,000$ PSI.
 STRUCTURAL STEEL - ASTM A36 - YIELD STRENGTH 36,000 PSI.

4. DECK PROTECTION METHOD

- MICRO-SILICA MODIFIED CONCRETE OVERLAY
- SEALING OF CONCRETE SURFACES

5. EXISTING STRUCTURE VERIFICATION

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE. THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO CMS SECTIONS 102.05, 105.02 AND 513.02.

CONTRACT BID PRICES SHALL BE BASED UPON A RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE BY THE CONTRACTOR. HOWEVER, ALL PROJECT WORK SHALL BE BASED UPON ACTUAL DETAILS AND DIMENSIONS WHICH HAVE BEEN VERIFIED BY THE CONTRACTOR IN THE FIELD.

THE PLANS OF THE EXISTING BRIDGES ARE AVAILABLE FOR PERUSAL AT THE OHIO DEPARTMENT OF TRANSPORTATION'S DISTRICT 3 OFFICE, ASHLAND, OHIO.

6. ITEM 202 - PORTIONS OF STRUCTURE REMOVED

THE CONTRACTOR SHALL CAREFULLY REMOVE THE EXISTING RAILING, RAILING POST, PART OF THE EXISTING PARAPET AS SHOWN IN THE PLANS. ALL LOOSE OR UNSOUND CONCRETE SHALL BE REMOVED. ALSO TO BE REMOVED SHALL BE ANY SOUND CONCRETE NECESSARY TO OBTAIN A MINIMUM 4" THICKNESS OF NEW CONCRETE.

THE FINAL CONCRETE REMOVAL SHALL BE PERFORMED USING THIRTY FIVE (35) AND FIFTEEN (15) POUND JACK HAMMERS. A HOE RAM, CONCRETE CRUSHER OR OTHER SIMILAR TYPE IMPACTIVE DEVICE, WILL NOT BE PERMITTED FOR ANY OF THE REMOVAL WORK. EXISTING SMOOTH CONSTRUCTION JOINTS OR SAW CUTS SHALL BE MECHANICALLY SCARIFIED 1/4" DEEP TO ENSURE BONDING OF THE NEW CONCRETE.

DISPOSAL:

ALL MATERIALS REMOVED FROM THE STRUCTURE SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED BY HIM FROM THE SITE. UNDER NO CIRCUMSTANCES SHALL THE MATERIALS BE PERMITTED TO REMAIN ON THE PREMISES, RIGHT-OF-WAY OR STREETS PENDING DISPOSAL OF SAME OR FOR ANY OTHER PURPOSES, UNLESS OTHERWISE APPROVED BY THE ENGINEER.

PAYMENT:

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE LUMP SUM PRICE BID FOR ITEM 202, "PORTIONS OF STRUCTURE REMOVED", WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

7. ITEM 202 - PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, ABUTMENT

THIS ITEM OF WORK SHALL BE USED TO REMOVE PORTIONS OF THE ABUTMENTS AS DESIGNATED IN THE PLAN. THE CONCRETE SHALL BE REMOVED BY A HYDRAULIC SPLITTING METHOD. A LINE OF HOLES SHALL BE DRILLED ALONG THE REMOVAL LINE AND A HYDRAULIC SPLITTER USED AS PER MANUFACTURER'S RECOMMENDATIONS. THIRTY FIVE (35) AND FIFTEEN (15) POUND JACK HAMMERS SHALL BE USED FOR ANY REQUIRED FINISH WORK. HOE RAMS AND/OR CONCRETE CRUSHERS WILL NOT BE PERMITTED TO DO ANY OF THE WORK. NO SAW CUTTING WILL BE ALLOWED. CONCRETE SHALL BE REMOVED IN A MANNER THAT PREVENTS CUTTING, ELONGATING, OR DAMAGING OF THE EXISTING REINFORCING STEEL TO BE PRESERVED. IF EXISTING REINFORCING STEEL DESIGNATED FOR PRESERVATION IS DAMAGED DURING THE REMOVAL OPERATION, DOWELLED REINFORCING STEEL MUST BE ADDED AT THE CONTRACTOR'S EXPENSE. THE LENGTH INTO THE ABUTMENT SHALL BE 6 INCHES. ALL DOWEL HOLES SHALL BE GROUTED AS PER ITEM 510 - DOWEL HOLES WITH NON-SHRINK, NON-METALLIC GROUT. THE GROUT SHALL BE AN EPOXY GROUT.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR ITEM 202, "PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, ABUTMENT" WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

8. ITEM 202 - PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, PARAPET END

THIS ITEM OF WORK SHALL BE USED TO REMOVE PARAPET ENDS AS DESIGNATED IN THE PLAN. THE CONCRETE SHALL BE REMOVED BY A HYDRAULIC SPLITTING METHOD. A LINE OF HOLES SHALL BE DRILLED ALONG THE REMOVAL LINE AND A HYDRAULIC SPLITTER USED AS PER MANUFACTURER'S RECOMMENDATIONS. THIRTY FIVE (35) AND FIFTEEN (15) POUND JACK HAMMERS SHALL BE USED FOR ANY REQUIRED FINISH WORK. HOE RAMS AND/OR CONCRETE CRUSHERS WILL NOT BE PERMITTED TO DO ANY OF THE WORK. NO SAW CUTTING WILL BE ALLOWED. CONCRETE SHALL BE REMOVED IN A MANNER THAT PREVENTS CUTTING, ELONGATING, OR DAMAGING OF THE EXISTING REINFORCING STEEL TO BE PRESERVED. IF EXISTING REINFORCING STEEL DESIGNATED FOR PRESERVATION IS DAMAGED DURING THE REMOVAL OPERATION, DOWELLED REINFORCING STEEL MUST BE ADDED AT THE CONTRACTOR'S EXPENSE. THE LENGTH INTO THE ABUTMENT SHALL BE 6 INCHES. ALL DOWEL HOLES SHALL BE GROUTED AS PER ITEM 510 - DOWEL HOLES WITH NON-SHRINK, NON-METALLIC GROUT. THE GROUT SHALL BE AN EPOXY GROUT.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR ITEM 202, "PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, PARAPET END" WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

9. ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN

UNCLASSIFIED EXCAVATION SHALL BE IN ACCORDANCE WITH 503 EXCEPT THAT THE BACKFILL MATERIAL BEHIND THE ABUTMENTS SHALL BE 203 MATERIAL PLACED IN 6 INCH LIFTS AND COMPACTED IN ACCORDANCE WITH 304.04.

10. ITEM 510 - DOWEL HOLES WITH NON-SHRINK, NON-METALLIC GROUT, AS PER PLAN:

ALL DOWEL HOLES SHALL BE CORED DRILLED AND GROUTED WITH AN EPOXY MORTAR.

PAYMENT FOR ALL OF THE ABOVE SHALL BE INCLUDED IN THE UNIT PRICE BID PER EACH FOR ITEM 510 - DOWEL HOLES WITH NON-SHRINK, NON-METALLIC GROUT, AS PER PLAN WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

11. ITEM 511 - CLASS S CONCRETE, MISC.: PARAPETS

THIS ITEM SHALL BE USED TO RETROFIT THE EXISTING PARAPETS AS PER DETAILS IN THE PLAN.

ALL LOOSE AND UNSOUND CONCRETE IN THE AREA OF THE PARAPET TO BE RETROFITTED, SHALL BE REMOVED. ALL REMAINING SOUND CONCRETE SHALL THEN BE MECHANICALLY SCARIFIED 1/4" DEEP.

NOT MORE THAN 48 HOURS PRIOR TO PLACING THE CONCRETE, ALL EXISTING SURFACES TO WHICH THE CONCRETE IS TO BOND, INCLUDING EXPOSED REINFORCING AND STRUCTURAL STEEL SHALL BE CLEANED BY ABRASIVE BLASTING. THESE SURFACES SHALL BE MADE FREE OF SPALLS, LAITANCE, AND ALL OTHER CONTAMINANTS DETRIMENTAL TO ACHIEVING AN ADEQUATE BOND.

THE CONCRETE SURFACES TO BE RETROFITTED SHALL BE THOROUGHLY DRENCHED WITH CLEAN WATER AND ALLOWED TO DRY TO A DAMP CONDITION JUST BEFORE PLACING THE CONCRETE.

IN LIEU OF THE PROPORTIONING SPECIFIED IN 499.03 AND 511.02, THE FOLLOWING TABLE SHALL BE USED TO ESTABLISH THE QUANTITIES PER CUBIC YARD FOR CONCRETE. THE COARSE AGGREGATE SHALL BE NO. 8 LIMESTONE.

QUANTITIES PER CUBIC YARD				
FINE (LB)	AGGREGATE COARSE (LB)	TOTAL (LB)	CEMENT CONTENT	WATER/CEMENT RATIO
1555	1100	2655	715	0.44

AIR CONTENT = 8% PLUS OR MINUS 2%
TYPE A CHEMICAL ADMIXTURE SHALL BE USED.

EXISTING DEFLECTION JOINTS SHALL BE EXTENDED COMPLETELY THROUGH THE PROPOSED RETROFIT AND SHALL BE MADE BY FORMING OR SAWCUTTING THE HARDENED CONCRETE WITHIN ONE (1) DAY AFTER POURING. THE FORMED JOINTS SHALL BE MADE WITH EITHER 1/4" GRAY SPONGE RUBBER OR 1/4" GRAY CELLULAR POLYVINYL CHLORIDE (PVC) SPONGE. IF RUBBER IS USED, IT SHALL MEET THE REQUIREMENTS OF AASHTO M-153. THE SAWED 1/4" WIDE JOINTS SHALL BE SEALED 3/4" DEEP (MINIMUM) WITH AN IMPREGNATED PRECOMPRESSED EXPANDING FOAM SEALANT TAPE KNOWN AS WILL-SEAL MANUFACTURED BY ILLBRUCK/USA INC., MINNEAPOLIS OR A LOW DENSITY CLOSED CELL, CROSSLINKED ETHYLENE VINYL ACETATE FOAM KNOWN AS EVAZOTE 50, MANUFACTURED BY E-POXY INDUSTRIES INC., RAVENNA, N.Y.

ALL OTHER PROVISIONS OF ITEM 511 SHALL REMAIN IN EFFECT.

CURING SHALL BE IN ACCORDANCE WITH 511.14 TYPE A OR B.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR ITEM 511 "CLASS S CONCRETE, PARAPETS, AS PER PLAN" WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

12. ITEM 511 - CLASS S CONCRETE MISC.: PIER ENCASUREMENT

PIER COLUMNS SHALL BE ENCASED AS PER DETAILS IN THE PLAN. ALL LOOSE AND DISINTEGRATED CONCRETE AND CALCIUM CARBONATE DEPOSITS SHALL BE REMOVED WITH HAND TOOLS. WITHIN FORTY EIGHT (48) HOURS BEFORE PLACING CONCRETE, THE SURFACE OF THE EXISTING PIERS AGAINST WHICH THE CONCRETE SHALL BE PLACED AND THE EXISTING REINFORCING STEEL SHALL BE THOROUGHLY CLEANED BY ABRASIVE BLASTING. THE EXISTING CONCRETE SURFACE AGAINST WHICH CONCRETE WILL BE POURED SHALL BE KEPT WET FOR AT LEAST ONE (1) HOUR BEFORE PLACING CONCRETE, AND BE APPROACHING DRYNESS AT THE TIME OF THE PLACING OF THE CONCRETE TO FACILITATE THE BOND.

IN LIEU OF THE PROPORTIONING SPECIFIED IN 499.03 AND 511.02, THE FOLLOWING TABLE SHALL BE USED TO ESTABLISH THE QUANTITIES PER CUBIC YARD FOR CONCRETE. THE CEMENT USED SHALL BE EXPANSIVE HYDRAULIC CEMENT CONFORMING TO ASTM C845, TYPE K AS PER 701.08.

QUANTITIES PER CUBIC YARD				
FINE (LB)	AGGREGATE COARSE (LB)	TOTAL (LB)	CEMENT CONTENT	WATER/CEMENT RATIO
1300	1275	2575	715	0.50

AIR CONTENT = 8% PLUS OR MINUS 2%
TYPE D CHEMICAL ADMIXTURE SHALL BE USED.

THE SLUMP AT THE TIME OF CONCRETE PLACEMENT SHALL BE BETWEEN 5 AND 7 INCHES.

CURING SHALL BE IN ACCORDANCE WITH 511.14 TYPE A WATER CURING.

A CEMENT COMPANY REPRESENTATIVE SHALL BE ON HAND DURING THE MIXING AND PLACING OPERATION THE FIRST POUR IF THE REDI-MIX PRODUCER HAS NOT HAD PREVIOUS EXPERIENCE WITH TYPE K CEMENT.

REDI-MIX PRODUCERS WHO HAVE HAD PREVIOUS EXPERIENCES SHALL HAVE ON HAND A PERSON WHO HAS BEEN FACTORY TRAINED IN THE USE OF TYPE K CEMENT.

ALL OTHER PROVISIONS OF ITEM 511 SHALL REMAIN IN EFFECT.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR ITEM 511 "CLASS S CONCRETE MISC.: PIER ENCASUREMENT" WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

13. ITEM 511 - CLASS C CONCRETE, ABUTMENT, AS PER PLAN

CLASS C CONCRETE SHALL BE IN ACCORDANCE WITH 511 EXCEPT THAT THE COARSE AGGREGATE SHALL BE NO. 8 LIMESTONE.

14. ITEM 516 - REFURBISH AND RESET BEARING, AS PER PLAN

THIS ITEM SHALL CONSIST OF REFURBISHING AND RESETTING ALL OF THE EXISTING ROCKER BEARINGS AT ABUTMENTS.

REFURBISH BEARING :

THE WORK SHALL INCLUDE ALL WORK NECESSARY TO PROPERLY ALIGN BRIDGE BEARINGS AS WELL AS THEIR CLEANING AND PAINTING. INCLUDED SHALL BE THE DISASSEMBLY OF THE BEARINGS, HAND TOOL CLEANING (GRINDING IF NECESSARY), PAINTING AS REQUIRED BY SYSTEM "OZEU", REPLACEMENT OF ANY DAMAGED SHEET LEAD (711.19), INSTALLATION OF ANY NECESSARY STEEL SHIMS OF THE SAME SIZE AS THE BEARINGS TO PROVIDE A SNUG FIT, REALIGNMENT OF THE UPPER BEARING PLATE BY REMOVING EXISTING WELDS AND REWELDING SO THAT THE BEARING ARE VERTICALLY ALIGNED AT 60 DEGREES F, LUBRICATING SLIDING SURFACES, AND REASSEMBLY OF THE BEARING.

THE CONTRACTOR SHALL BE SURE THAT ALL BEARINGS ARE SHIMMED ADEQUATELY AND THAT NO BEAMS AND/OR BEARING DEVICES ARE "FLOATING". AT THE OPTION OF THE CONTRACTOR AND AT NO ADDITIONAL COST TO THE STATE, NEW BEARINGS OF THE SAME TYPE AS THE EXISTING MAY BE INSTALLED IN PLACE OF REFURBISHING THE BEARINGS. ALL WORKS SHALL BE TO THE SATISFACTION OF THE ENGINEER.

RESET BEARING :

THE FOLLOWING PROCEDURE SHALL BE USED TO RESET THE ROCKER BEARINGS.

1. RAISE THE ENTIRE SUPERSTRUCTURE AT THE ABUTMENT UNTIL THERE IS NO CONTACT BETWEEN THE SOLE PLATES AND THE BEARINGS. MAXIMUM LIFT OF SUPERSTRUCTURE SHALL BE 1". ALL BEAMS SHALL BE RAISED SIMULTANEOUSLY. HOWEVER, BEAMS SHALL NOT BE RAISED AT THE REAR ABUTMENT AND AT THE FORWARD ABUTMENT AT THE SAME TIME.
2. RESET ROCKERS AND/OR BASE PLATES IN FINAL POSITION BY CENTERING THE BASE PLATES UNDER THE SOLE PLATES BOTH IN THE LONGITUDINAL AND TRANSVERSE DIRECTION AT 60° F (+10° F, -0° F).
3. LOWER ENTIRE SUPERSTRUCTURE SIMULTANEOUSLY.

PAYMENT FOR ALL THE ABOVE DESCRIBED LABOR AND MATERIALS WILL BE MADE AT THE CONTRACT PRICE BID FOR ITEM 516 - REFURBISH AND RESET BEARING, AS PER PLAN.

POLYTECH, INC.						1 / 23
CONSULTING ENGINEERS CLEVELAND, OHIO						
GENERAL NOTES						
BRIDGE NO. LOR-20-1303						
BRIDGE NO. LOR-20-1356 L & R						
BRIDGE NO. LOR-20-1380 L & R						
BRIDGE NO. LOR-20-1451 L & R						
LORAIN COUNTY						OHIO
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
PSS	PSS	-	VB	BS	8/96	

GENERAL NOTES

FHWA REGION	STATE	PROJECT	
5	OHIO		

219
351

LORAIN COUNTY
LOR-20-12.62

15. ITEM 516 - JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN

THE WORK SHALL CONSIST OF FURNISHING ALL NECESSARY LABOR, MATERIALS, AND EQUIPMENT TO RAISE OR REPOSITION ANY EXISTING STRUCTURES TO THE DIMENSIONS AND REQUIREMENTS DEFINED IN THE PROJECT PLANS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN, INSTALLATION AND OPERATION OF AN ADEQUATE JACKING SYSTEM, INCLUDING ANY TEMPORARY OR PERMANENT SUPPORTS NECESSARY TO PERFORM THE WORK DESCRIBED IN THE PROJECT PLANS. THREE (3) SETS OF JACKING PLANS, WHICH INCLUDE THE INFORMATION DESCRIBED IN THIS NOTE, SHALL SUBMITTED TO THE DIRECTOR FOR APPROVAL AT LEAST THIRTY (30) DAYS BEFORE ACTUAL WORK IS TO BEGIN. THE PLANS SHALL BE PREPARED AND STAMPED BY A REGISTERED PROFESSIONAL ENGINEER.

JACKING SUBMITTALS SHALL INCLUDE AT LEAST THE FOLLOWING:

1. THE SIGNATURE AND NUMBER, OR PROFESSIONAL SEAL, OF THE REGISTERED PROFESSIONAL ENGINEER WHO PREPARED THE SUBMITTAL.
2. CALCULATIONS AND ANALYSIS OF THE STRUCTURE TO DETERMINE AND DEFINE THE ACTUAL LOADING APPLIED AT THE CONTRACTOR'S SELECTION JACKING POINTS.
3. A DRAWING SHOWING THE PHYSICAL AND DIMENSIONAL POSITION OF THE JACKS WITH RESPECT TO THE STRUCTURE INCLUDING CLEARANCES AND CENTER OF LIFT.
4. A SCHEMATIC LAYOUT OF JACKS, CHECK VALVES, PUMPS WITH 3 WAY RETRACTOR VALVE, PRESSURE GAGES, FLOW CONTROL VALVES, ETC. IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. ALL JACKS FOR EACH ABUTMENT OR PIER SHALL BE CONNECTED TOGETHER. ALL JACKS AT EACH ABUTMENT OR PIER SHALL BE THE SAME SIZE.
5. ANALYSIS AND CALCULATIONS OF STRESSES INDUCED OR CREATED IN THE STRUCTURE AND ANY TEMPORARY OR PERMANENT SUPPORTS. DESIGN CALCULATIONS FOR ANY TEMPORARY OR PERMANENT SUPPORTS.
6. PHYSICAL DIMENSIONS, MATERIALS, AND FABRICATION DETAILS OF ANY TEMPORARY OR PERMANENT SUPPORTS. HORIZONTAL AND VERTICAL MOVEMENT RESTRAINT SHALL BE PROVIDED.
7. A STEP BY STEP PROCEDURE DETAILING ALL STEPS IN THE JACKING OPERATION.
8. METHOD OF ATTACHMENT TO STRUCTURAL MEMBERS. WELDING TO TENSION AREAS WILL NOT BE PERMITTED.

THE ENTIRE SYSTEM INCLUDING JACKS SHALL HAVE 20% MORE CAPACITY THAN REQUIRED BASED ON CALCULATED LOADS.

FOR LIFTS GREATER THAN 1", JACKS SHALL HAVE LOCKING NUTS TO POSITIVELY LOCK AND SUPPORT THE STRUCTURE DURING THE LIFT.

JACKS SHALL HAVE A SWIVEL LOAD CAP, A DOMED PISTON HEAD OR SOME OTHER DEVICE TO PROTECT AGAINST THE EFFECTS OF SIDE LOAD ON THE JACK.

JACKS ALONE SHALL NOT BE USED TO SUPPORT LOADS EXCEPT DURING THE ACTUAL JACKING OPERATION. TEMPORARY SUPPORTS, BLOCKING OR OTHER METHODS APPROVED BY THE DIRECTOR SHALL BE USED.

SINGLE ACTING RAMS WITH NO OVER-TRAVEL PROTECTION SYSTEM SHALL NOT BE USED.

SPARE EQUIPMENT SHALL BE AVAILABLE ON SITE FOR THE REQUIRED STRUCTURE RAISING TO PROCEED IN THE EVENT OF BREAKDOWN. A LIST OF SPARE EQUIPMENT SHALL BE PROVIDED TO THE ENGINEER.

AT A MINIMUM, A JACKING OPERATION SHALL LIFT ALL BEAMS AT ANY ONE ABUTMENT OR PIER SIMULTANEOUSLY. THE ONLY EXCEPTION IS THE SITUATION WHERE THE WORK INVOLVES REPLACING OR REHABILITATING INDIVIDUAL BEARINGS; NO PERMANENT SHIMMING IS REQUIRED AND THE HEIGHT OF THE LIFT SHALL NOT EXCEED 1/4 INCH.

MAXIMUM DIFFERENTIAL JACKING HEIGHT BETWEEN ANY ADJACENT ABUTMENTS OR PIERS SHALL BE 1" OR LESS.

IF, DURING THE JACKING OPERATIONS, ANY DAMAGE TO THE STRUCTURE IS VISUALLY OBSERVED, THE JACKING OPERATION SHALL IMMEDIATELY CEASE AND APPROVED SUPPORTS SHALL BE INSTALLED. THE CONTRACTOR SHALL THEN ANALYZE THE DAMAGE AND SUBMIT A METHOD OF CORRECTION TO THE ENGINEER FOR APPROVAL. COST OF REQUIRED REPAIRS SHALL BE BORNE BY THE CONTRACTOR.

THE CONTRACTOR SHALL DEMONSTRATE TO THE ENGINEER THAT THE BRIDGE BEARINGS ARE FULLY SEATED BETWEEN ALL CONTACT AREAS. IF FULL SEATING IS NOT ATTAINED, SUITABLE MEANS OF REPAIR, SUBJECT TO THE APPROVAL OF THE ENGINEER, WILL BE REQUIRED AT THE CONTRACTOR'S EXPENSE.

THE JACKING OPERATION SHALL BE DIRECTED BY A PROFESSIONAL ENGINEER EMPLOYED BY THE CONTRACTOR. FAILURE TO HAVE A PROFESSIONAL ENGINEER PRESENT SHALL BE CAUSE FOR CEASING JACKING OPERATIONS.

PAYMENT SHALL BE MADE AT THE LUMP SUM PRICE BID FOR ITEM 516, JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN AND SHALL INCLUDE ALL NECESSARY TOOLS, LABOR, EQUIPMENT AND MATERIALS NECESSARY TO COMPLETE THIS ITEM OF WORK.

16. ITEM 516 - VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN A (OR B)

THIS ITEM SHALL INCLUDE ALL THE WORK REQUIRED TO MODIFY THE EXISTING END DAMS AS PER DETAILS IN THE PLAN. THE WORK INCLUDES TRIMMING EXISTING ANGLES, PROVIDE NEW ANGLES WITH ANCHOR PLATES, STEEL RETAINERS, STEEL BARS, STRIP SEAL GLAND, FIELD WELDING AND METALLIZING (AS PER STD.DWG. EXJ-4-87 SHEET 5 OF 5), AND ANY OTHER MATERIALS NEEDED, AS SHOWN ON THE PLANS.

THE STEEL RETAINER AND STRIP SEAL GLAND SHALL PROVIDE A MOVEMENT RATING OF 3" AND SHALL BE PER STANDARD DRAWING EXJ-4-87. THE STEEL RETAINER SHALL BE PROVIDED IN MAXIMUM LENGTHS POSSIBLE TO ALLOW FOR TRAFFIC MAINTENANCE AND SHALL BE WELDED TOGETHER TO FORM A WATERTIGHT JOINT. THE NEOPRENE EXTRUSION SHALL BE ONE CONTINUOUS PIECE. THE NEOPRENE SHALL NOT BE INSTALLED UNTIL ALL OTHER WORK IS COMPLETE UPON THE STRUCTURE. AN ADHESIVE SHALL BE USED TO FACILITATE PLACEMENT OF THE NEOPRENE EXTRUSION. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO FABRICATION.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER LINEAR FOOT FOR ITEM 516 "VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN A (OR B)" WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THE WORK AS DESCRIBED ABOVE.

17. ITEM 516 - HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN

THIS ITEM SHALL INCLUDE ALL THE WORK REQUIRED TO COMPLETE THE MODIFICATION OF EXISTING END DAMS AS PER DETAILS IN THE PLAN. THE WORK INCLUDES EXTENDING STEEL RETAINERS AND STRIP SEAL GLAND INTO THE RETROFIT/NEW PARAPET, PROVIDE CURB PLATES, STUDS, FIELD WELDING AND PAINTING, AND ANY OTHER MATERIALS NEEDED, AS SHOWN ON THE PLANS.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER LINEAR FOOT FOR ITEM 516 "HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN" WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THE WORK AS DESCRIBED ABOVE.

18. ITEM 518 - 6" PERFORATED CORRUGATED PLASTIC PIPE, AS PER PLAN

CORRUGATED PIPE USED IN ABUTMENT DRAINAGE SHALL BE 6 INCH DIAMETER, PLASTIC CORRUGATED AS PER SUPPLEMENTAL SPECIFICATION 944, AASHTO M294, TYPE SP.

18A. ITEM 518 POROUS BACKFILL WITH FILTER FABRIC, AS PER PLAN
THE MATERIAL SHALL BE NO. 57 GRAVEL.

19. ITEM 518 - 6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS, AS PER PLAN

CORRUGATED PIPE USED IN ABUTMENT DRAINAGE SHALL BE 6 INCH DIAMETER, PLASTIC CORRUGATED AS PER SUPPLEMENTAL SPECIFICATION 944, AASHTO M294, TYPE S. THIS ITEM SHALL INCLUDE ALL ELBOWS, TEES, AND END CAPS REQUIRED TO COMPLETE THE ABUTMENT DRAINAGE SYSTEM.

20. ITEM 518 - SCUPPER MODIFICATION, AS PER PLAN

SEE SHEET 20/23 FOR ALL DETAILS AND NOTES.

21. ITEM 518 - STRUCTURE DRAINAGE, MISC.: SCUPPER PLUGGING

SEE SHEET 20/23 FOR ALL DETAILS AND NOTES.

22. ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN

THIS ITEM SHALL CONSIST OF PATCHING EXISTING CONCRETE AT THE LOCATIONS SHOWN IN THE PLANS AND AS DIRECTED BY THE ENGINEER IN ACCORDANCE WITH ITEM 519 AND THE FOLLOWING ADDITIONAL REQUIREMENTS.

- A. SURFACE PREPARATION UNDER 519.04 SHALL INCLUDE THE THOROUGH ABRASIVE BLASTING AND AIR CLEANING OF ALL SURFACES WHICH ARE TO BE IN CONTACT WITH THE PATCHING MATERIAL.
- B. CLEANING SHALL PRECEDE THE APPLICATION OF THE PATCHING MATERIAL OR THE ERECTION OF THE FORMS BY LESS THAN 24 HOURS.
- C. REMOVAL DEPTH SHALL BE 3 INCHES MINIMUM OR TO SOUND CONCRETE.
- D. NO STEEL WIRE FABRIC SHALL BE REQUIRED.
- E. THE CONCRETE MAY BE TROWELLED IN PLACE, PROVIDING THAT AN ACCEPTABLE SMOOTH APPEARANCE CAN BE ACHIEVED AS DETERMINED BY THE ENGINEER.

PAYMENT SHALL BE MADE UNDER THE SQUARE FOOT UNIT PRICE FOR ITEM 519, "PATCHING CONCRETE STRUCTURES, AS PER PLAN".

23. ITEM 815 - FIELD PAINTING OF EXISTING STEEL

ALL FIELD PAINTING OF EXISTING STEEL SHALL BE PERFORMED AS DESCRIBED HEREIN AND IN THE SUPPLEMENTAL SPECIFICATION 815.

THE FIELD PAINTING SHALL BE APPLIED TO ALL EXPOSED SURFACES OF EXISTING STRUCTURAL STEEL INCLUDING ALL BEAMS, CROSS FRAMES, BEARINGS, END DAMS (EXISTING AND NEW) AND SCUPPERS.

ALL EXPOSED SURFACES OF EXISTING STRUCTURAL STEEL SHALL BE CLEANED, PRIMED AND FIELD PAINTED IN CONFORMANCE TO THE SPECIFICATION.

SEE ALSO THE SPECIFICATION FOR SURFACE PREPARATION REQUIREMENTS, APPLICATION RATES, MATERIAL REQUIREMENTS AND APPLICATION PROCEDURES.

24. ITEM SPECIAL - MICRO-SILICA MODIFIED CONCRETE OVERLAY

MICRO-SILICA MODIFIED CONCRETE OVERLAY SHALL BE IN ACCORDANCE WITH THE PROPOSAL NOTE EXCEPT THAT THE COARSE AGGREGATE SHALL BE NO. 8 LIMESTONE.

25. ITEM SPECIAL - KEYWAY DRAIN

HOLES SHALL BE DRILLED IN THE ABUTMENT FOR KEYWAY DRAINS AS SHOWN IN THE PLAN DETAILS. THE HOLES SHALL BE SPACED AT APPROXIMATELY FIVE FOOT CENTERS AS DIRECTED BY THE ENGINEER.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER EACH FOR ITEM SPECIAL, KEYWAY DRAIN WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

26. TEMPORARY FALSEWORK AND PROTECTIVE STRUCTURES

A. GENERAL

THIS WORK SHALL CONSIST OF CONSTRUCTING AND REMOVING RIGID TEMPORARY CONSTRUCTIONS REQUIRED TO COMPLETE THE WORK IN ADDITION TO THE FORMWORK AND ITEMS WHICH ARE SPECIFICALLY INCLUDED ELSEWHERE. THE WORK INCLUDES TEMPORARY PLATFORMS OR OTHER MEANS TO PREVENT LOOSE MATERIALS FROM FALLING DURING REMOVAL, MODIFICATION OF SUPERSTRUCTURE AND FIELD PAINTING OF EXISTING STEEL WORK.

B. REQUIREMENTS

IN ORDER TO PROTECT AGAINST DAMAGE FROM FALLING MATERIAL AND DEBRIS, WHILE SUPERSTRUCTURE CONCRETE IS BEING PLACED OR WHILE WORK IS IN PROGRESS OVERHEAD, THE CONTRACTOR SHALL FURNISH AND ERECT TEMPORARY PROTECTIVE STRUCTURES. THE FLOORING AND SIDING OF THE STRUCTURES SHALL HAVE NO CRACKS OR OPENINGS THROUGH WHICH MATERIAL PARTICLES MAY FALL. THE PROTECTION IN ALL CASES SHALL EXTEND BEYOND THE EXTERIOR STRINGERS A SUFFICIENT DISTANCE TO PROTECT UNDER THE BRIDGE RAILINGS.

AFTER THE TEMPORARY FALSEWORK AND PROTECTIVE STRUCTURES HAVE SERVED THEIR PURPOSE, AND WHEN SO DIRECTED BY THE ENGINEER, THEY SHALL BE REMOVED. ALL MATERIAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE SITE AND DISPOSED OF BY THE CONTRACTOR AT HIS OWN EXPENSE.

DETAILS OF THE TEMPORARY FALSEWORK AND PROTECTIVE STRUCTURES INCLUDING THE PROPOSED TEMPORARY UNDERCLEARANCES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL.

C. PAYMENT

TEMPORARY FALSEWORK AND PROTECTIVE STRUCTURES WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED WITH THE PRICE BID FOR ITEM 202, "PORTIONS OF STRUCTURE REMOVED".

27. CONSTRUCTION JOINT PREPARATION

THE CONCRETE SHALL BE REMOVED TO A ROUGH SURFACE. THE EXISTING REINFORCING STEEL WHERE REQUIRED IN THE PLANS SHALL BE LEFT IN PLACE. INSTALL DOWEL BARS IF SPECIFIED. PRIOR TO CONCRETE PLACEMENT ABRASIVELY CLEAN JOINT SURFACE AND EXPOSED REINFORCEMENT TO REMOVE LOOSE AND DISINTEGRATED CONCRETE AND LOOSE RUST. THE JOINT SURFACE AND EXPOSED REINFORCEMENT SHALL BE THOROUGHLY CLEANED OF ALL DIRT, DUST, OR OTHER FOREIGN MATERIALS BY THE USE OF WATER, AIR UNDER PRESSURE, OR OTHER METHODS THAT PRODUCE SATISFACTORY RESULTS TO THE ENGINEER. CONCRETE BONDING SURFACES SHALL BE WET WITHOUT FREE WATER AS CONCRETE IS PLACED.

28. REPLACEMENT OF EXISTING REINFORCING STEEL

ANY EXISTING REINFORCING BARS WHICH ARE TO BE INCORPORATED INTO THE NEW WORK AND WHICH ARE MADE UNUSABLE BY THE CONTRACTOR'S CONCRETE REMOVAL OPERATIONS SHALL BE REPLACED WITH NEW REINFORCING STEEL INCLUDING DOWEL HOLES (IF NECESSARY) AT HIS COST. ANY EXISTING REINFORCING BARS DEEMED BY THE ENGINEER TO BE UNUSABLE BECAUSE OF CORROSION SHALL BE REPLACED WITH NEW STEEL. AN ALLOWANCE OF 100 POUNDS PER BRIDGE IS INCLUDED IN ITEM 509 FOR THIS PURPOSE. THE DOWEL HOLES IN THE EXISTING CONCRETE TO ACCOMMODATE THE NEW REINFORCEMENT WILL BE PAID SEPARATELY.

29. BAR LAP LENGTHS

UNLESS OTHERWISE SHOWN, BAR LAPS SHALL BE NOT LESS THAN:

BAR NO.	5	6	7	8	9	10
LENGTH FOR EPOXY COATED	2'-0"	2'-5"	3'-0"	3'-11"	5'-0"	6'-4"

POLYTECH, INC.						2 / 23
CONSULTING ENGINEERS						CLEVELAND, OHIO
GENERAL NOTES						
BRIDGE NO. LOR-20-1303						
BRIDGE NO. LOR-20-1356 L & R						
BRIDGE NO. LOR-20-1380 L & R						
BRIDGE NO. LOR-20-1451 L & R						
LORAIN COUNTY						OHIO
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISION
PSS	PSS	-	VB	BS	8/96	

DRAWING = G-NOTE2 DATE = JULY 26, 1996

GENERAL NOTES

FHWA REGION	STATE	PROJECT	
5	OHIO		

215
351

LORAIN COUNTY
LOR-20-12.62

30. DOWEL HOLES AND REINFORCING STEEL

DOWEL HOLES SHALL BE DRILLED WHERE SHOWN IN THE PLANS. REINFORCING STEEL SHALL BE INSTALLED USING NONSHRINK, NONMETALLIC GROUT. ALL EXISTING REINFORCING STEEL BARS IN THE AREA OF THE DOWEL HOLE SHALL BE LOCATED WITH THE AID OF A REINFORCING STEEL BAR LOCATOR (PACHOMETER) PRIOR TO DRILLING THE HOLES. IF AN EXISTING BAR IS ENCOUNTERED AT THE SAME LOCATION AS A PROPOSED DOWEL HOLE, THE DOWEL HOLE SHALL BE MOVED TO EITHER SIDE OF THE EXISTING BAR.

DOWEL HOLES AND GROUTING SHALL BE INCLUDED WITH ITEM 510, "DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT" FOR PAYMENT.

31. MECHANICAL CONNECTORS FOR REINFORCING STEEL

AN APPROVED TYPE OF MECHANICAL CONNECTOR REINFORCING BARS SHALL BE PROVIDED AT THE LOCATIONS SHOWN IN THE PLANS. INSTALLATION OF CONNECTORS SHALL CONFORM WITH MANUFACTURER'S RECOMMENDED PROCEDURES. IF A DOWEL BAR SPLICE TYPE OF CONNECTOR IS FURNISHED, THE MINIMUM DOWEL BAR LENGTH TO BE FURNISHED WITH THE CONNECTOR SHALL BE GIVEN BY THE DIMENSION "L" SHOWN ON THE PLANS.

CONNECTORS AND DOWEL BARS USED WITH EPOXY COATED BARS SHALL BE EPOXY COATED. COATING FOR BOTH CONNECTORS AND BARS SHALL CONFORM TO THE SAME SPECIFICATIONS. COATINGS WHICH HAVE BEEN DAMAGED OR WHICH OTHERWISE DO NOT MEET SPECIFICATIONS WITH RESPECT TO COLOR, CONTINUITY AND UNIFORMITY MAY BE REPAIRED AS DIRECTED BY THE ENGINEER OR THEY SHALL BE REPLACED WITH MATERIAL WHICH MEETS THE SPECIFICATIONS.

CONNECTORS AND DOWEL BAR EXTENSIONS SHALL CONFORM WITH ITEM 509 AND BE INCLUDED IN THE BID PRICE PER POUND FOR ITEM 509.

32. TEMPORARY WEDGE

AFTER THE CONCRETE OVERLAY HAS BEEN PLACED AND BEFORE THE BRIDGE IS OPENED TO TRAFFIC, A TEMPORARY WEDGE WILL BE INSTALLED TO MAINTAIN TRAFFIC IF THE PERMANENT ASPHALT IS NOT IN PLACE. THE TEMPORARY WEDGE WILL BE 404 ASPHALT CONCRETE BUILT AS PER STANDARD DRAWING BP-5, EXCEPT NO TACK COAT WILL BE REQUIRED. THE TEMPORARY WEDGE WILL BE FEATHERED AT ONE INCH PER TWENTY-FIVE FEET OR AS DIRECTED BY THE ENGINEER. THE TEMPORARY WEDGE WILL BE COMPLETELY REMOVED JUST BEFORE ANY NEW ROADWAY ASPHALT IS INSTALLED AND IN NO CASE SHALL TRAFFIC BE ALLOWED TO CROSS A BRIDGE WITHOUT AN APPROVED TEMPORARY WEDGE.

PAYMENT FOR ALL OF THE ABOVE SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614, MAINTAINING TRAFFIC, WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

33. WORK LIMITATIONS

NO CONCRETE DECK OVERLAY SHALL BE PLACED BEFORE APRIL 15. THE CONTRACTOR SHALL SCHEDULE THE WORK SO THAT ALL DECK OVERLAYS ARE PLACED BEFORE OCTOBER 15. IF FOR SOME UNFORSEEN CIRCUMSTANCES THE DECK OVERLAYS OR PORTIONS OF DECK OVERLAY ARE NOT PLACED BY OCTOBER 15, REGARDLESS OF THE WORK REMAINING, THE FULL DEPTH REPAIRS SHALL BE COMPLETED AS PER 511 AND THE UNFINISHED DECK SHALL BE RESURFACED WITH ITEM 404 ASPHALT CONCRETE AND OPENED TO TRAFFIC. THE CONTRACTOR SHALL PLACE AND MAINTAIN AT HIS EXPENSE THE ASPHALT WEARING SURFACE UNTIL REMOVED AT HIS EXPENSE THE FOLLOWING SPRING WHEN THE DECK OVERLAY CAN BE PLACED AFTER APRIL 15.

34. ITEMS NOT INCLUDED IN BRIDGE PLANS

THE FOLLOWING ITEMS ARE NOT INCLUDED IN THE BRIDGE PLANS. SEE ROADWAY PLANS FOR DETAILS.






GRADING, APPROACH SLAB, APPROACH PAVEMENT, AND MAINTENANCE OF TRAFFIC.

35. PROPOSED WORK NOTE

IN GENERAL, THE PROPOSED WORK INCLUDES :

- REMOVING ALL LOOSE AND UNSOUND CONCRETE, SCARIFYING 1/4" DEEP SOUND CONCRETE, LAYING 1 1/2" (MIN.) THICK MICRO-SILICA MODIFIED CONCRETE OVER BRIDGE DECK AND SOME DESIGNATED APPROACH SLABS.
- RETROFITTING/REPLACING EXISTING BRIDGE DEFLECTOR PARAPET.
- REPLACING EXISTING BACKWALL AND INSTALLING POROUS BACKFILL WITH FILTER FABRIC AND OUTLET DRAINAGE PIPE AT SIDES.
- INSTALLING APPROACH SLAB ANCHOR BARS TO THE ABUTMENT BACKWALL.
- MODIFYING EXISTING END DAMS WITH STRIP SEAL FOR STEEL BEAM BRIDGES.
- REFURBISHING AND RESETTING ABUTMENT BEARINGS.
- PLUGGING/RAISING EXISTING SCUPPERS.
- TRIMMING ENDS OF BEAM.
- CONCRETE REPAIR AND SEALING OF PARAPETS AND PIER COLUMNS.
- PAINTING THE STRUCTURAL STEEL.
- ENCASING PIER COLUMNS.

LEGEND

-  REMOVE PORTION OF EXIST. DECK SLAB, SAFETY CURB, APPROACH SLAB, APPROACH CURB, PARAPET AND/OR BRIDGE RAILING
-  TRIM EXIST. BEAM
-  PLUG EXISTING SCUPPER
-  MODIFY EXISTING SCUPPER
-  ENCASE PIER COLUMN

NOTE:

IN THESE PLANS, ALL EXISTING FEATURES ARE SHOWN WITH DASH LINES AND WITH LIGHT PEN WEIGHT WHILE THE PROPOSED WORKS ARE SHOWN WITH FULL LINES AND HEAVY PEN WEIGHT.

ABBREVIATIONS

- N.S. = NEAR SIDE
- F.S. = FAR SIDE
- E.S. = EACH SIDE
- P.E.J.F. = PREFORMED EXPANSION JOINT FILLER
- C.J. = CONSTRUCTION JOINT
- TYP. = TYPICAL
- MIN. = MINIMUM
- EXIST. = EXISTING
- CONC. = CONCRETE
- CL = CENTERLINE
- STD. = STANDARD
- DWG. = DRAWING
- DIA. = DIAMETER
- C/C = CENTER TO CENTER
- F/F = FACE TO FACE
- T/T = TOE TO TOE




DRAWING = G-NOTE3 DATE = JULY 26, 1996

POLYTECH, INC.		3 / 23	
CONSULTING ENGINEERS		CLEVELAND, OHIO	
GENERAL NOTES			
BRIDGE NO. LOR-20-1303			
BRIDGE NO. LOR-20-1356 L & R			
BRIDGE NO. LOR-20-1380 L & R			
BRIDGE NO. LOR-20-1451 L & R			
LORAIN COUNTY		OHIO	
DESIGNED	DRAWN	TRACED	CHECKED
PSS	PSS	-	VB
REVIEWED	DATE	REVISED	
BS	8/96		

FHWA REGION	STATE	PROJECT
5	OHIO	

217
351

LORAIN COUNTY
LOR-20-12.62



NOTE: THE ELASTOMERIC COMPRESSION SEAL SHALL BE TYPE 3W AS MANUFACTURED BY HYDROZO/JEENE INC. OR TYPE 3W-300 AS MANUFACTURED BY WATSON-BOWMAN ACME CORP. OR TYPE SF-225 AS MANUFACTURED BY R.J. WATSON, INC.

EXISTING STRUCTURE

TYPE: FOUR SPAN CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE SLAB AND REINFORCED CONCRETE SUBSTRUCTURE

SPANS: 44'-6", 63'-9", 63'-9" & 44'-6"

ROADWAY WIDTH: 34'-0" F/F CURB, SOUTHBOUND AND NORTHBOUND LANES

ALIGNMENT: TANGENT

SKEW: 25° 00' 00" RIGHT FORWARD

LOAD FREQUENCY: CF 2000 (57)

WEARING SURFACE: 1" MONOLITHIC CONCRETE


APPROACH SLABS: 25'-0" LONG (AS-I-67)

YEAR BUILT: 1970*

STRUCTURE FILE NO.: 4706609

PROPOSED WORK

1. REMOVE THE TOP 1/4" OF SOUND EXISTING CONCRETE SURFACE AND OVERLAY WITH 1 1/2" (MINIMUM) MICRO-SILICA MODIFIED CONCRETE. (SEE NOTE #4 ON SHEET [21/23])
2. RETROFIT EXISTING PARAPET WITH SAFETY SHAPE PARAPET.
3. INSTALL PROTECTIVE FENCE ON PARAPET.
4. RETROFIT EXPANSION JOINT WITH STRIP SEAL.
5. SEAL MEDIAN JOINT WITH COMPRESSION SEAL.
6. PLUG EXISTING SCUPPERS.
7. ENCASE SHOULDER PIER COLUMNS.
8. CONCRETE SEALER ON PIER COLUMNS AND PARAPET.
9. FIELD PAINTING OF EXISTING STEEL.
10. SUBSTRUCTURE PATCHING, SEE SHEET [9A/23].



ESTIMATED QUANTITIES

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
202	11200	LUMP SUM	LUMP	PORTIONS OF STRUCTURE REMOVED			LUMP SUM	
202	11301	3	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, PARAPET END			3	
509	15840	9,029	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60		3,727	5,202	100
510	10001	764	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN			764	
511	34450	30	CU YD	CLASS S CONCRETE, MISC.: PARAPETS			30	
511	34450	34	CU YD	CLASS S CONCRETE, MISC.: PIER ENCASEMENT		34		
SPECIAL	51267504	222	SQ YD	SEALING OF CONCRETE SURFACES (NON-EPOXY)			222	
SPECIAL	51267510	101	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)		101		
516	10900	117	LIN FT	ELASTOMERIC COMPRESSION SEAL			117	
516	10901	218	LIN FT	ELASTOMERIC COMPRESSION SEAL, AS PER PLAN			218	
516	11801	152	LIN FT	VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN B			152	
516	11901	8	LIN FT	HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN			8	

ESTIMATED QUANTITIES (CONTINUED)

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
518	62200	16	EACH	STRUCTURAL DRAINAGE, MISC.: SCUPPER PLUGGING			16	
SPECIAL	51922006	1,722	SQ YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (1 1/2 INCHES THICK)			1,722	
SPECIAL	51922100	36	CU YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS)			36	
SPECIAL	51922300	LUMP SUM	LUMP	TEST SLAB*				LUMP SUM
SPECIAL	60739900	443	LIN FT	VANDAL PROTECTION FENCE, 6' STRAIGHT, COATED FABRIC			443	
815	00050	22,800	SQ FT	SURFACE PREPARATION OF EXISTING STEEL, SYSTEM OZEU			22,800	
815	00056	22,800	SQ FT	FIELD PAINTING OF EXISTING STEEL, PRIME COAT, SYSTEM OZEU			22,800	
815	00060	22,800	SQ FT	FIELD PAINTING OF EXISTING STEEL, INTERMEDIATE COAT, SYSTEM OZEU			22,800	
815	00066	22,800	SQ FT	FIELD PAINTING OF EXISTING STEEL, FINISH COAT, SYSTEM OZEU			22,800	
815	00504	50	MAN HOUR	GRINDING FINES, TEARS, SLIVERS			50	
815	00508	5,100	LIN FT	GRINDING FLANGE EDGES			5,100	

NOTE: THESE QUANTITIES ARE CARRIED TO THE STRUCTURE SUMMARY SHEET [4/23].

SEE PROPOSAL NOTE

MODIFIED STRUCTURE

TYPE: FOUR SPAN CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE SLAB AND REINFORCED CONCRETE SUBSTRUCTURE

SPANS: 44'-6", 63'-9", 63'-9" & 44'-6"

ROADWAY WIDTH: 34'-1" T/T SAFETY SHAPE PARAPET & MEDIAN CURB, SOUTHBOUND AND NORTHBOUND LANES

ALIGNMENT: TANGENT

SKEW: 25° 00' 00" RIGHT FORWARD

LOAD FREQUENCY: CF 2000 (57)

WEARING SURFACE: 1 1/2" (MIN.) MICRO-SILICA MODIFIED CONCRETE

APPROACH SLABS: 25'-0" LONG (AS-I-81)

POLYTECH, INC. 5/23
CONSULTING ENGINEERS CLEVELAND, OHIO



PLAN AND TYPICAL SECTION

BRIDGE NO. LOR-20-1303
UNDER S.R. 301


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISION
PSS	RG	-	VB	BS	8/96	DRA 9/96

DESIGN FILE: c:\dgn\lor20\301p1new.dgn
WORKSTATION: darmstro DATE: 23 SEP 96

LORAIN COUNTY
LOR-20-12.62




PLAN



ELEVATION
(FENCE IS NOT SHOWN)

NOTE:

1. MODIFICATION DETAILS TO LEFT PARAPET IS SHOWN. MODIFICATION DETAILS TO RIGHT PARAPET FOR THIS BRIDGE WILL BE SIMILAR.
2. FOR SECTIONS AND LIMITS OF REMOVAL AREAS, SEE SHEET [7723].
3. FOR GUARDRAIL CONNECTION DETAILS, SEE STD. DWG. GR-3.1 & GR-3.2.
4. 6' STRAIGHT VANDAL PROTECTION FENCE, POST SECTIONS AND DETAILS SHALL BE AS PER STD. DWG. VPF-1-90.
5. FOR REINFORCEMENT SCHEDULE, SEE SHEET [23723].




DRAWING = 301PRPT DATE = AUGUST 2, 1996

POLYTECH, INC.					6 / 23
CONSULTING ENGINEERS CLEVELAND, OHIO					
PARAPET PLAN & ELEVATION					
BRIDGE NO. LOR-20-1303 UNDER S.R. 301					
LORAIN COUNTY					OHIO
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE
PSS	MAC	-	VB	BS	8/96


FHWA REGION	STATE	PROJECT
5	OHIO	

2/9
351


LORAIN COUNTY
LOR-20-12.62



SECTION A-A



SECTION B-B




SECTION C-C


- LIMITS OF REMOVAL

NOTES:


- EXISTING DEFLECTION JOINTS SHALL BE EXTENDED COMPLETELY THROUGH THE PROPOSED RETROFIT AND SHALL BE MADE BY FORMING OR SAWCUTTING THE HARDENED CONCRETE WITHIN ONE (1) DAY AFTER POURING. THE JOINTS SHALL BE MADE WITH EITHER 1/4" GRAY SPONGE RUBBER OR 1/4" GRAY CELLULAR POLYVINYL CHLORIDE (PVC) SPONGE. IF RUBBER IS USED IT SHALL MEET THE REQUIREMENTS OF AASHTO M-153. THE 1/4" WIDE JOINT SHALL BE SEALED 3/4" DEEP (MIN.) WITH AN IMPREGNATED PRECOMPRESSED EXPANDING FOAM SEALANT TAPE KNOWN AS WILL-SEAL MANUFACTURED BY ILLBRUCK/USA INC., MINN. OR A LOW DENSITY CLOSED CELL CROSS-LINKED ETHYLENE VINYL ACETATE FOAM KNOWN AS EVAZOTE 50 MANUFACTURED BY E-POXY INDUSTRIES INC., RAVENA, N.Y..
- THE COST OF PROVIDING THE 1/4" AND 1" PREFORMED EXPANSION JOINT FILLER, JOINT SEALANT AND THE PARAPET TRANSITION SECTIONS SHALL BE INCLUDED WITH THE ITEM 511, "CLASS S CONCRETE, MISC.: PARAPETS" FOR PAYMENT.
- VANDAL PROTECTION FENCE ON PARAPET IS NOT SHOWN ON THIS SHEET. FOR DETAILS, SEE SHEET 23723.
- * SEE NOTE #4 ON SHEET 21723.



SECTION D-D



SECTION E-E



SECTION F-F


DRAWING = 301SEC DATE = JULY 29, 1996

POLYTECH, INC.		7 / 23	
CONSULTING ENGINEERS		CLEVELAND, OHIO	
PARAPET SECTIONS			
BRIDGE NO. LOR-20-1303 UNDER S.R. 301			
LORAIN COUNTY		OHIO	
DESIGNED	DRAWN	TRACED	CHECKED
PSS	RG	-	VB
REVIEWED	DATE	REVISED	
BS	8/96		


FHWA REGION	STATE	PROJECT
5	OHIO	

222
351


LORAIN COUNTY
LOR-20-12.62




PLAN




PLAN




PLAN




ELEVATION
PIER 3, LEFT BRIDGE
LOOKING NORTH




ELEVATION
PIER 1, LEFT BRIDGE
LOOKING NORTH



ELEVATION
PIER 1, RIGHT BRIDGE
LOOKING NORTH



REAR ABUTMENT



FORWARD ABUTMENT

LOCATION	ITEM SPECIAL	ITEM 519
	PATCHING CONCRETE WITH TROWELABLE MORTAR SQ. FT.	PATCHING CONCRETE STRUCTURE, AS PER PLAN SQ. FT.
ABUTMENTS	74	6
PIER COLUMNS	28	-
200% EXPANSION FACTOR	204	12
** PIER CAPS	374	-
* TOTAL	578	18

- ITEM SPECIAL, PATCHING CONCRETE WITH TROWELABLE MORTAR
- ITEM 519, PATCHING CONCRETE STRUCTURE, AS PER PLAN

* THESE QUANTITIES ARE CARRIED TO THE STRUCTURE SUMMARY SHEET [4/23].

DRAWING = 301PATCH DATE = AUGUST 9, 1996

POLYTECH, INC. 9A/23
CONSULTING ENGINEERS CLEVELAND, OHIO

SUBSTRUCTURE PATCHING
BRIDGE NO. LOR-20-1303
UNDER S.R. 301



LORAIN COUNTY OHIO

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
NK	NK	-	VB	BS	8/96	

FHWA REGION	STATE	PROJECT	
5	OHIO		

223
351

LORAIN COUNTY
LOR-20-12.62



EXISTING STRUCTURE

TYPE: THREE SPAN CONTINUOUS REINFORCED CONCRETE SLAB WITH REINFORCED CONCRETE SUBSTRUCTURE

SPANS: 36'-6", 46'-0" & 36'-6"

ROADWAY WIDTH: 38'-0" F/F CURB

ALIGNMENT: TANGENT

SKEW: 18' 20' 00" LEFT FORWARD

LOAD FREQUENCY: CF 2000 (57)

WEARING SURFACE: 1" MONOLITHIC CONCRETE


APPROACH SLABS: 25'-0" LONG (AS-I-67)

YEAR BUILT: 1968* LEFT BRIDGE, 1971* RIGHT BRIDGE

STRUCTURE FILE NO.: 4701089 & 4701119

PROPOSED WORK

- REMOVE THE TOP 1/4" OF SOUND EXISTING CONCRETE SURFACE AND OVERLAY WITH 1 1/2" (MINIMUM) MICRO-SILICA MODIFIED CONCRETE. (SEE NOTE #4 ON SHEET 21/23).
- DRILL HOLES TO DRAIN ABUTMENT KEYWAY.
- RETROFIT EXISTING PARAPET WITH SAFETY PARAPET.
- CONCRETE SEALER ON PIER COLUMNS AND PARAPET.
- PLUG EXISTING SCUPPERS.
- REPLACE EXISTING APPROACH SLAB WITH FULL WIDTH APPROACH SLAB. (SEE ROADWAY PLANS)
- INSTALL APPROACH SLAB DOWEL BARS.
- INSTALL POROUS BACKFILL WITH FILTER FABRIC AND DRAINAGE PIPE.
- SUBSTRUCTURE PATCHING, SEE SHEET 13A/23.



TYPICAL SECTION

NOTE: THESE QUANTITIES ARE CARRIED TO THE STRUCTURE SUMMARY SHEET 4/23.

ESTIMATED QUANTITIES (LOR-20-1356 L)

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
202	11200	LUMP SUM	LUMP	PORTIONS OF STRUCTURE REMOVED				LUMP SUM
202	11301	3	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, PARAPET END			3	
503	21301	LUMP SUM	LUMP	UNCLASSIFIED EXCAVATION, AS PER PLAN				LUMP SUM
509	15840	3,378	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60			3,278	100
510	10001	438	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN			438	
511	34450	16	CU YD	CLASS S CONCRETE, MISC.: PARAPETS			16	
SPECIAL	51267504	107	SQ YD	SEALING OF CONCRETE SURFACES (NON-EPOXY)			107	
SPECIAL	51267510	63	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)		63		
518	21201	29	CU YD	POROUS BACKFILL WITH FILTER FABRIC, AS PER PLAN	29			
518	40001	115	LIN FT	6" PERFORATED CORRUGATED PLASTIC PIPE, AS PER PLAN	115			
518	40011	40	LIN FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS, AS PER PLAN	40			
SPECIAL	51861400	18	EACH	KEYWAY DRAIN	18			
518	62200	16	EACH	STRUCTURAL DRAINAGE, MISC.: SCUPPER PLUGGING			16	
SPECIAL	51922006	511	SQ YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (1 1/2" THICK)			511	
SPECIAL	51922100	11	CU YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS)			11	
SPECIAL	51922300	LUMP SUM	LUMP	TEST SLAB				LUMP SUM

ESTIMATED QUANTITIES (LOR-20-1356 R)

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
202	11200	LUMP SUM	LUMP	PORTIONS OF STRUCTURE REMOVED				LUMP SUM
202	11301	3	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, PARAPET END			3	
503	21301	LUMP SUM	LUMP	UNCLASSIFIED EXCAVATION, AS PER PLAN				LUMP SUM
509	15840	3,378	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60			3,278	100
510	10001	438	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN			438	
511	34450	16	CU YD	CLASS S CONCRETE, MISC.: PARAPETS			16	
SPECIAL	51267504	107	SQ YD	SEALING OF CONCRETE SURFACES (NON-EPOXY)			107	
SPECIAL	51267510	63	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)		63		
518	21201	29	CU YD	POROUS BACKFILL WITH FILTER FABRIC, AS PER PLAN	29			
518	40001	115	LIN FT	6" PERFORATED CORRUGATED PLASTIC PIPE, AS PER PLAN	115			
518	40011	40	LIN FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS, AS PER PLAN	40			
SPECIAL	51861400	18	EACH	KEYWAY DRAIN	18			
518	62200	16	EACH	STRUCTURAL DRAINAGE, MISC.: SCUPPER PLUGGING			16	
SPECIAL	51922006	511	SQ YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (1 1/2" THICK)			511	
SPECIAL	51922100	11	CU YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS)			11	
SPECIAL	51922300	LUMP SUM	LUMP	TEST SLAB				LUMP SUM

MODIFIED STRUCTURE

TYPE: THREE SPAN CONTINUOUS REINFORCED CONCRETE SLAB WITH REINFORCED CONCRETE SUBSTRUCTURE

SPANS: 36'-6", 46'-0" & 36'-6"

ROADWAY WIDTH: 38'-2" T/T SAFETY SHAPE PARAPET

ALIGNMENT: TANGENT

SKEW: 18' 20' 00" LEFT FORWARD

LOAD FREQUENCY: CF 2000 (57)

WEARING SURFACE: 1 1/2" (MIN.) MICRO-SILICA MODIFIED CONCRETE

APPROACH SLABS: 25'-0" LONG, FULL WIDTH (AS-I-81)

POLYTECH, INC. 10/23
CONSULTING ENGINEERS CLEVELAND, OHIO



PLAN AND TYPICAL SECTION
BRIDGE NO. LOR-20-1356 L & R
OVER MIDDLE AVENUE

LORAIN COUNTY	OHIO					
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
PSS	RG	-	VB	BS	8/96	DRA 9/96

* SEE PROPOSAL NOTE

DESIGN FILE: c:\dgn\lor20\midpinew.dgn
WORKSTATION: darmstro DATE: 23 SEP 96

LORAIN COUNTY
LOR-20-12.62




PARAPET LENGTHS


BRIDGE NO.	PARAPET	A	B	C	D	E	F	G	H	I	J	K
LOR-20-1356 L & R OVER MIDDLE AVENUE	LEFT & RIGHT	120'-7"	111'-7"	4'-4"	4'-8"	91'-11 3/8"	0'-7 5/8"	8'-11 1/4"	7	14'-7 1/2"	102'-4 1/2"	9'-3 1/4"

NOTE:

1. MODIFICATION DETAILS TO LEFT PARAPET OF LEFT BRIDGE IS SHOWN. MODIFICATION DETAILS TO OTHER THREE PARAPETS FOR THIS BRIDGE WILL BE SIMILAR.
2. FOR SECTIONS AND LIMITS OF REMOVAL AREAS, SEE SHEET 12/23.
3. FOR GUARDRAIL CONNECTION DETAILS, SEE STD. DWG. GR-3.1 & GR-3.2.
4. FOR REINFORCEMENT SCHEDULE, SEE SHEET 23/23.



POLYTECH, INC.		11 / 23	
CONSULTING ENGINEERS		CLEVELAND, OHIO	
PARAPET PLAN & ELEVATION			
BRIDGE NO. LOR-20-1356 L & R OVER MIDDLE AVENUE			
LORAIN COUNTY		OHIO	
DESIGNED	DRAWN	TRACED	CHECKED
PSS	RG	-	VB
REVIEWED	DATE	REVISION	DATE
BS	8/96	DRA	9/96




PLAN

SEE ROADWAY SECTION FOR CONCRETE MEDIAN BARRIER AT FORWARD APPROACH SLAB

4-EP535 • (N.S.), EP527 (F.S.) & EP528 • (TOP) @ 1'-3" (TYP. AT END PANEL)


4-EP521 • & EP522 • @ 1'-5" (TYP. AT END PANEL)



ELEVATION

* FIELD BEND TO FIT TRANSITION

** TYPICAL AT INTERIOR PANEL UNLESS NOTED OTHERWISE



PARAPET LENGTHS

BRIDGE NO.	PARAPET	A	B	C	D	E	F	G	H	I	J	K
LOR-20-1451 L OVER INDIAN HOLLOW ROAD	RIGHT	120'-7 1/8"	111'-7"	4'-4"	4'-8 1/8"	105'-10 15/16"	0'-8 3/16"	8'-11 1/4"	7	14'-7 1/2"	102'-4 1/2"	9'-3 3/8"

NOTE:

1. MODIFICATION DETAILS TO RIGHT PARAPET OF LEFT BRIDGE IS SHOWN. MODIFICATION DETAILS TO OTHER PARAPETS FOR THESE BRIDGES ARE ON SHEET **11B/23**.
2. FOR SECTIONS AND LIMITS OF REMOVAL AREAS, SEE SHEET **11A/23**.
3. FOR GUARDRAIL CONNECTION DETAILS, SEE STD. DWG. GR-3.1 & GR-3.2.

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE PRODUCTION DEPARTMENT



RIGHT PARAPET PLAN & ELEVATION
BRIDGE NO. LOR-20-1451 L
OVER INDIAN HOLLOW ROAD

LORAIN COUNTY		OHIO	
DESIGNED	DRAWN	TRACED	CHECKED
DM	DRA 9/96		DA4 9/96
REVIEWED	DATE	REVISED	
RDN	9/96		


FHWA REGION	STATE	PROJECT
5	OHIO	

226
351

LORAIN COUNTY
LOR-20-12.62




PLAN



ELEVATION

* FIELD BEND TO FIT TRANSITION

** TYPICAL AT INTERIOR PANEL UNLESS NOTED OTHERWISE



PARAPET LENGTHS

BRIDGE NO.	PARAPET	A	B	C	D	E	F	G	H	I	J	K
LOR-20-145I R OVER INDIAN HOLLOW ROAD	LEFT	120'-7 1/8"	111'-7"	4'-4"	4'-8 1/8"	91'-10 5/16"	0'-8 3/16"	8'-11 1/4"	7	14'-7 1/2"	102'-4 1/2"	9'-3 3/8"
	RIGHT	120'-7 1/8"	111'-7"	4'-4"	4'-8 1/8"	91'-10 5/16"	0'-8 3/16"	8'-11 1/4"	7	14'-7 1/2"	102'-4 1/2"	9'-3 3/8"
LOR-20-145I L OVER INDIAN HOLLOW ROAD	LEFT	120'-7 1/8"	111'-7"	4'-4"	4'-8 1/8"	91'-10 5/16"	0'-8 3/16"	8'-11 1/4"	7	14'-7 1/2"	102'-4 1/2"	9'-3 3/8"

NOTE:

1. MODIFICATION DETAILS TO LEFT PARAPET OF LEFT BRIDGE IS SHOWN. MODIFICATION DETAILS TO LEFT AND RIGHT PARAPETS OF RIGHT STRUCTURE WILL BE SIMILAR.
2. FOR MODIFICATION DETAILS TO RIGHT PARAPET OF LEFT STRUCTURE SEE SHEET 11A/23 FOR DETAILS.
3. FOR SECTIONS AND LIMITS OF REMOVAL AREAS, SEE SHEET 12A/23.
4. FOR GUARDRAIL CONNECTION DETAILS, SEE STD. DWG. GR-3.1 & GR-3.2.

IIB / 23

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE PRODUCTION DEPARTMENT

RIGHT PARAPET PLAN & ELEVATION

BRIDGE NO. LOR-20-145I L&R
OVER INDIAN HOLLOW ROAD


LORAIN COUNTY OHIO

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DM	DRA 9/96		DRA 9/96	RDA	9/96	


FHWA REGION	STATE	PROJECT
5	OHIO	

227
351


LORAIN COUNTY
LOR-20-12.62





SECTION A-A




SECTION B-B



SECTION C-C



SECTION D-D




SECTION E-E

NOTES:


- EXISTING DEFLECTION JOINTS SHALL BE EXTENDED COMPLETELY THROUGH THE PROPOSED RETROFIT AND SHALL BE MADE BY FORMING OR SAWCUTTING THE HARDENED CONCRETE WITHIN ONE (1) DAY AFTER POURING. THE JOINTS SHALL BE MADE WITH EITHER 1/4" GRAY SPONGE RUBBER OR 1/4" GRAY CELLULAR POLYVINYL CHLORIDE (PVC) SPONGE. IF RUBBER IS USED IT SHALL MEET THE REQUIREMENTS OF AASHTO M-153. THE 1/4" WIDE JOINT SHALL BE SEALED 3/4" DEEP (MIN.) WITH AN IMPREGNATED PRECOMPRESSED EXPANDING FOAM SEALANT TAPE KNOWN AS WILL-SEAL MANUFACTURED BY ILLBRUCK/USA INC., MINN. OR A LOW DENSITY CLOSED CELL CROSS-LINKED ETHYLENE VINYL ACETATE FOAM KNOWN AS EVAZOTE 50 MANUFACTURED BY E-POXY INDUSTRIES INC., RAVENA, N.Y..
- THE COST OF PROVIDING THE 1/4" AND 1" PREFORMED EXPANSION JOINT FILLER, JOINT SEALANT AND THE PARAPET TRANSITION SECTIONS SHALL BE INCLUDED WITH THE ITEM 511, "CLASS S CONCRETE, MISC.: PARAPETS" FOR PAYMENT.
- SEE NOTE #4 ON SHEET 21/23.

DRAWING = MIDSEC DATE = JULY 30, 1996


POLYTECH, INC.		12/23	
CONSULTING ENGINEERS		CLEVELAND, OHIO	
PARAPET SECTIONS			
BRIDGE NO. LOR-20-1356 L & R OVER MIDDLE AVENUE			
LORAIN COUNTY			OHIO
DESIGNED	DRAWN	TRACED	CHECKED
PSS	RG	-	VB
REVIEWED	DATE	REVISED	
BS	8/96		




SECTION A-A





SECTION B-B




SECTION C-C



SECTION D-D



SECTION E-E



SECTION F-F

- NOTES:**
- EXISTING DEFLECTION JOINTS SHALL BE EXTENDED COMPLETELY THROUGH THE PROPOSED RETROFIT AND SHALL BE MADE BY FORMING OR SAWCUTTING THE HARDENED CONCRETE WITHIN ONE (1) DAY AFTER POURING. THE JOINTS SHALL BE MADE WITH EITHER 1/4" GRAY SPONGE RUBBER OR 1/4" GRAY CELLULAR POLYVINYL CHLORIDE (PVC) SPONGE. IF RUBBER IS USED IT SHALL MEET THE REQUIREMENTS OF AASHTO M-153. THE 1/4" WIDE JOINT SHALL BE SEALED 3/4" DEEP (MIN.) WITH AN IMPREGNATED PRECOMPRESSED EXPANDING FOAM SEALANT TAPE KNOWN AS WILL-SEAL MANUFACTURED BY ILLBRUCK/USA INC., MINN. OR A LOW DENSITY CLOSED CELL CROSS-LINKED ETHYLENE VINYL ACETATE FOAM KNOWN AS EVAZOTE 50 MANUFACTURED BY E-POXY INDUSTRIES INC., RAVENA, N.Y..
 - THE COST OF PROVIDING THE 1/4" AND 1" PREFORMED EXPANSION JOINT FILLER, JOINT SEALANT AND THE PARAPET TRANSITION SECTIONS SHALL BE INCLUDED WITH THE ITEM 511, "CLASS S CONCRETE, MISC.: PARAPETS" FOR PAYMENT.


DESIGN FILE: c:\dgn\lor20\prp\new.dgn
WORKSTATION: darmsro DATE: 24 SEP 96

STATE OF OHIO DEPARTMENT OF TRANSPORTATION DISTRICT THREE PRODUCTION DEPARTMENT						12A / 23
PARAPET SECTIONS						
BRIDGE NO. LOR-20-1451 L & R OVER INDIAN HOLLOW RD.						
LORAIN COUNTY						OHIO
DESIGNED DM	DRAWN DRA 9/96	TRACED -	CHECKED DRA 9/96	REVIEWED RDN	DATE 946	REVISED

FHWA REGION	STATE	PROJECT	
5	OHIO		



LORAIN COUNTY
LOR-20-12.62



ELEVATION
PIER 2, RIGHT BRIDGE
LOOKING EAST




LOCATION	RIGHT BRIDGE
	ITEM SPECIAL
	PATCHING CONCRETE WITH TROWELABLE MORTAR SQ. FT.
PIER COLUMNS	8
200% EXPANSION FACTOR	16
* TOTAL	24

ITEM SPECIAL, PATCHING CONCRETE WITH TROWELABLE MORTAR

* THIS QUANTITY IS CARRIED TO THE STRUCTURE SUMMARY SHEET 4/23.

DRAWING = MIDPATCH DATE = AUGUST 9, 1996

POLYTECH, INC.		13A/23	
CONSULTING ENGINEERS		CLEVELAND, OHIO	
SUBSTRUCTURE PATCHING			
BRIDGE NO. LOR-20-1356 L & R OVER MIDDLE AVENUE			
LORAIN COUNTY		OHIO	
DESIGNED	DRAWN	TRACED	CHECKED
NK	NK	-	VB
REVIEWED	DATE	REVISED	
BS	8/96		



ESTIMATED QUANTITIES (LOR-20-1380 L) (ALSO SEE SHEET [15/23])

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
202	11200	LUMP SUM	LUMP	PORTIONS OF STRUCTURE REMOVED				LUMP SUM
202	11301	3	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, PARAPET END			3	
202	11301	11	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, ABUTMENT	11			
503	21301	LUMP SUM	LUMP	UNCLASSIFIED EXCAVATION, AS PER PLAN				LUMP SUM
509	15840	4,256	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60	1,072		3,084	100
510	10001	488	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN	20		468	
511	34450	18	CU YD	CLASS S CONCRETE, MISC.: PARAPETS			18	
511	45701	11	CU YD	CLASS C CONCRETE, ABUTMENT, AS PER PLAN	11			
SPECIAL	51267504	127	SQ YD	SEALING OF CONCRETE SURFACES (NON-EPOXY)			127	
513	21000	10	EACH	TRIMMING OF BEAM END			10	
516	10900	24	LIN FT	ELASTOMERIC COMPRESSION SEAL			24	
516	11801	39	LIN FT	VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN A			39	
516	11801	39	LIN FT	VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN B			39	
516	11901	8	LIN FT	HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN			8	
516	46801	10	EACH	REFURBISH AND RESET BEARING, AS PER PLAN	10			

SEE PROPOSAL NOTE

ESTIMATED QUANTITIES (LOR-20-1380 R) (ALSO SEE SHEET [15/23])

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
202	11200	LUMP SUM	LUMP	PORTIONS OF STRUCTURE REMOVED				LUMP SUM
202	11301	3	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, PARAPET END			3	
509	15840	3,184	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60			3,084	100
510	10001	468	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN			468	
511	34450	18	CU YD	CLASS S CONCRETE, MISC.: PARAPETS			18	
SPECIAL	51267504	127	SQ YD	SEALING OF CONCRETE SURFACES (NON-EPOXY)			127	
513	21000	10	EACH	TRIMMING OF BEAM END			10	
516	10900	48	LIN FT	ELASTOMERIC COMPRESSION SEAL			48	
516	11801	78	LIN FT	VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN A			78	
516	11901	8	LIN FT	HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN			8	
516	46801	10	EACH	REFURBISH AND RESET BEARING, AS PER PLAN	10			

FHWA REGION	STATE	PROJECT	
5	OHIO		

LORAIN COUNTY
LOR-20-12.62

231
351

EXISTING STRUCTURE

TYPE: THREE SPAN CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE SLAB AND REINFORCED CONCRETE SUBSTRUCTURE

SPANS: 42'-0", 52'-6" & 42'-0"

ROADWAY WIDTH: 38'-0" F/F CURB

ALIGNMENT: TANGENT

SKEW: 04° 06' 40" RIGHT FORWARD

LOAD FREQUENCY: CF 2000 (57)

WEARING SURFACE: 1" MONOLITHIC CONCRETE

APPROACH SLABS: 25'-0" LONG (AS-I-67)

YEAR BUILT: 1968*

STRUCTURE FILE NO.: 4701143 & 4701178

PROPOSED WORK

- REMOVE THE TOP 1/4" OF SOUND EXISTING CONCRETE SURFACE AND OVERLAY WITH 1 1/2" (MINIMUM) MICRO-SILICA MODIFIED CONCRETE. (SEE NOTE #4 ON SHEET [21/23]).
 - RETROFIT EXISTING PARAPET WITH SAFETY SHAPE PARAPET.
 - RETROFIT EXPANSION JOINT WITH STRIP SEAL.
 - TRIM ENDS OF BEAMS.
 - REPLACE LEFT FORWARD BACKWALL.
 - MODIFY EXISTING SCUPPERS.
 - RESET ABUTMENT BEARINGS.
 - CONCRETE SEALER ON PARAPET.
 - FIELD PAINTING OF EXISTING STEEL.
 - REPLACE EXISTING LEFT FORWARD APPROACH SLAB WITH FULL WIDTH APPROACH SLAB. (SEE ROADWAY PLANS)
 - INSTALL POROUS BACKFILL WITH FILTER FABRIC AND DRAINAGE PIPE.
 - SUBSTRUCTURE PATCHING, SEE SHEET [18A/23]
- NOTE:
THESE QUANTITIES ARE CARRIED TO THE STRUCTURE SUMMARY SHEET [4/23].

MODIFIED STRUCTURE

TYPE: THREE SPAN CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE SLAB AND REINFORCED CONCRETE SUBSTRUCTURE

SPANS: 42'-0", 52'-6" & 42'-0"

ROADWAY WIDTH: 38'-2" T/T SAFETY SHAPE PARAPET

ALIGNMENT: TANGENT

SKEW: 04° 06' 40" RIGHT FORWARD

LOAD FREQUENCY: CF 2000 (57)

WEARING SURFACE: 1 1/2" (MIN.) MICRO-SILICA MODIFIED CONCRETE

APPROACH SLABS: 25'-0" LONG, FULL WIDTH, LEFT FORWARD (AS-I-8)

POLYTECH, INC. 14 / 23
CONSULTING ENGINEERS CLEVELAND, OHIO


PLAN AND TYPICAL SECTION

BRIDGE NO. LOR-20-1380 L & R
OVER C.C.S. RAILROAD


LORAIN COUNTY				OHIO	
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE
PSS	RC	-	VB	BS	8/96
					REVISION
					DRA 9/96

DESIGN FILE: c:\dgn\lor20\vrp\new.dgn
WORKSTATION: darmstro DATE: 23 SEP 96

LORAIN COUNTY
LOR-20-12.62



PLAN



ELEVATION

ESTIMATED QUANTITIES (LOR-20-1380 L) (CONTINUED)

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
516	47001	LUMP SUM	LUMP	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN				LUMP SUM
518	12801	16	EACH	SCUPPER MODIFICATION, AS PER PLAN			16	
518	21201	26	CU YD	POROUS BACKFILL WITH FILTER FABRIC, AS PER PLAN	26			
518	40001	59	LIN FT	6\"/>				

ESTIMATED QUANTITIES (LOR-20-1380 R) (CONTINUED)

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
516	47001	LUMP SUM	LUMP	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN				LUMP SUM
518	12801	16	EACH	SCUPPER MODIFICATION, AS PER PLAN			16	
SPECIAL	51922006	620	SQ YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (1 1/2 INCHES THICK)†			620	
SPECIAL	51922100	17	CU YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS)†			17	
SPECIAL	51922300	LUMP SUM	LUMP	TEST SLAB†				LUMP SUM
815	00050	8,000	SQ FT	SURFACE PREPARATION OF EXISTING STEEL, SYSTEM OZEU			8,000	
815	00056	8,000	SQ FT	FIELD PAINTING OF EXISTING STEEL, PRIME COAT, SYSTEM OZEU			8,000	
815	00060	8,000	SQ FT	FIELD PAINTING OF EXISTING STEEL, INTERMEDIATE COAT, SYSTEM OZEU			8,000	
815	00066	8,000	SQ FT	FIELD PAINTING OF EXISTING STEEL, FINISH COAT, SYSTEM OZEU			8,000	
815	00504	25	MAN HR	GRINDING FINNS, TEARS, SLIVERS			25	

NOTE: THESE QUANTITIES ARE CARRIED TO THE STRUCTURE SUMMARY SHEET 4/23

NOTES:

- MODIFICATION DETAILS SHOWN ARE TYPICAL FOR LEFT BRIDGE PARAPETS. RIGHT BRIDGE PARAPET MODIFICATION DETAILS AT ABUTMENTS SHALL BE SIMILAR TO THOSE SHOWN FOR LEFT BRIDGE REAR ABUTMENT. SEE SHEET 22/23 FOR ADDITIONAL DETAILS.
- FOR SECTIONS AND LIMITS OF REMOVAL AREAS, SEE SHEET 16/23.
- FOR GUARDRAIL CONNECTION DETAILS, SEE STD. DWG. GR-3.1 & GR-3.2.
- FOR REINFORCEMENT SCHEDULE, SEE SHEET 23/23.

POLYTECH, INC. 15 / 23
CONSULTING ENGINEERS CLEVELAND, OHIO

PARAPET PLAN & ELEVATION

BRIDGE NO. LOR-20-1380 L & R
OVER C.C.S. RAILROAD

LORAIN COUNTY OHIO

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
PSS	MR	-	VB	BS	8/96	


DRAWING = RRRPRT DATE = AUGUST 2, 1996

† SEE PROPOSAL NOTE


FHWA REGION	STATE	PROJECT
5	OHIO	

233
351


LORAIN COUNTY
LOR-20-12.62




SECTION A-A




SECTION B-B




SECTION C-C



- LIMITS OF REMOVAL



SECTION D-D









SECTION E-E

NOTES:

- EXISTING DEFLECTION JOINTS SHALL BE EXTENDED COMPLETELY THROUGH THE PROPOSED RETROFIT AND SHALL BE MADE BY FORMING OR SAWCUTTING THE HARDENED CONCRETE WITHIN ONE (1) DAY AFTER POURING. THE JOINTS SHALL BE MADE WITH EITHER 1/4" GRAY SPONGE RUBBER OR 1/4" GRAY CELLULAR POLYVINYL CHLORIDE (PVC) SPONGE. IF RUBBER IS USED IT SHALL MEET THE REQUIREMENTS OF AASHTO M-153. THE 1/4" WIDE JOINT SHALL BE SEALED 3/4" DEEP (MIN.) WITH AN IMPREGNATED PRECOMPRESSED EXPANDING FOAM SEALANT TAPE KNOWN AS WILL-SEAL MANUFACTURED BY ILLBRUCK/USA INC., MINN. OR A LOW DENSITY CLOSED CELL CROSS-LINKED ETHYLENE VINYL ACETATE FOAM KNOWN AS EVAZOTE 50 MANUFACTURED BY E-POXY INDUSTRIES INC., RAVENA, N.Y..
- THE COST OF PROVIDING THE 1/4" AND 1" PREFORMED EXPANSION JOINT FILLER, JOINT SEALANT AND THE PARAPET TRANSITION SECTIONS SHALL BE INCLUDED WITH THE ITEM 511, "CLASS S CONCRETE, MISC.: PARAPETS" FOR PAYMENT.
- * SEE NOTE #4 ON SHEET 21/23.

DRAWING = RRSEC DATE = JULY 30, 1996

POLYTECH, INC.						16 / 23
CONSULTING ENGINEERS						CLEVELAND, OHIO
PARAPET SECTIONS						
BRIDGE NO. LOR-20-1380 L & R OVER C.C.S. RAILROAD						
LORAIN COUNTY						OHIO
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
PSS	RG	-	VB	BS	8/96	



- NOTES**
1. MODIFICATION DETAILS TO THE FORWARD ABUTMENT OF THE LEFT BRIDGE IS SHOWN. MODIFICATION DETAILS TO THE REAR ABUTMENT OF THE LEFT BRIDGE WILL BE SIMILAR TO THE DETAILS SHOWN ON SHEET 18/23.
 2. FOR PARAPET MODIFICATION DETAILS, SEE SHEET 15/23.
 3. THE COST OF REMOVING EXIST. POROUS BACKFILL INCLUDING SAWCUTTING & REMOVING EXIST. 6" C.M.P. AS SHOWN ON SECTION A-A AND PROVIDING GEOTEXTILE FABRIC, TYPE A, PER ITEM 712.09, SHALL BE INCLUDED WITH ITEM 518, "POROUS BACKFILL WITH FILTER FABRIC" FOR PAYMENT.
 4. POROUS BACKFILL WITH FILTER FABRIC, 1'-6" THICK SHALL EXTEND FROM THE ELEVATION SHOWN IN THE PLANS TO THE PLANE OF THE SUBGRADE AND LATERALLY TO THE ENDS OF THE WINGWALLS.
 5. THE 6" PERFORATED CORRUGATED PLASTIC PIPE SHALL BE SLOPED AWAY FROM THE C U.S. 20. FOR THE EXTENSION OF THE NON-PERFORATED CORRUGATED PLASTIC PIPE BEYOND THE ABUTMENT WALL AND ITS TERMINATION DETAILS, SEE STD. DWG. A-1-69.
 6. THE POROUS BACKFILL MATERIAL SHALL BE #57 GRAVEL.
 7. FOR REINFORCEMENT SCHEDULE, SEE SHEET 23/23.






DRAWING = RRABUT-L DATE = JULY 30, 1996

POLYTECH, INC.		17 / 23	
CONSULTING ENGINEERS		CLEVELAND, OHIO	
ABUTMENT MODIFICATION DETAILS			
BRIDGE NO. LOR-20-1380 L OVER C.C.S. RAILROAD			
LORAIN COUNTY		OHIO	
DESIGNED	DRAWN	TRACED	CHECKED
PSS	RG	-	VB
REVIEWED	DATE	REVISED	
BS	8/96		

FHWA REGION	STATE	PROJECT
5	OHIO	

233
351

LORAIN COUNTY
LOR-20-12.62



- NOTES**
1. MODIFICATION DETAILS TO THE REAR ABUTMENT OF THE RIGHT BRIDGE IS SHOWN. MODIFICATION DETAILS TO THE FORWARD ABUTMENT THE RIGHT BRIDGE WILL BE SIMILAR.
 2. FOR PARAPET MODIFICATION DETAILS, SEE SHEET 15/23.


DRAWING = RRABUT-R DATE = JULY 30, 1996

POLYTECH, INC.		18 / 23	
CONSULTING ENGINEERS		CLEVELAND, OHIO	
ABUTMENT MODIFICATION DETAILS			
BRIDGE NO. LOR-20-1380 R OVER C.C.S. RAILROAD			
LORAIN COUNTY		OHIO	
DESIGNED	DRAWN	TRACED	CHECKED
PSS	RG	-	VB
REVIEWED	DATE	REVISED	DATE
BS	8/96		


FHWA REGION	STATE	PROJECT
5	OHIO	

236
351

LORAIN COUNTY
LOR-20-12.62




PLAN




ELEVATION

PIER 1, RIGHT BRIDGE

LOOKING EAST




FORWARD ABUTMENT, RIGHT BRIDGE



REAR ABUTMENT, LEFT BRIDGE

LOCATION	RIGHT BRIDGE	LEFT BRIDGE
	ITEM SPECIAL PATCHING CONCRETE WITH TROWELABLE MORTAR SQ. FT.	ITEM SPECIAL PATCHING CONCRETE WITH TROWELABLE MORTAR SQ. FT.
ABUTMENTS	33	4
PIER COLUMNS	4	-
200% EXPANSION FACTOR	74	8
* TOTAL	111	12

* THESE QUANTITIES ARE CARRIED TO THE
STRUCTURE SUMMARY SHEET 4/23.

 ITEM SPECIAL, PATCHING CONCRETE WITH TROWELABLE MORTAR

DRAWING = RRPATCH DATE = AUGUST 9, 1996

POLYTECH, INC. 18A/23
CONSULTING ENGINEERS CLEVELAND, OHIO

SUBSTRUCTURE PATCHING

BRIDGE NO. LOR-20-1380 L & R
OVER C.C.S. RAILROAD



LORAIN COUNTY OHIO

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
NK	NK	-	VB	BS	8/96	

FHWA REGION	STATE	PROJECT
5	OHIO	



LORAIN COUNTY
LOR-20-12.62



NOTE:
THESE QUANTITIES ARE CARRIED TO THE STRUCTURE SUMMARY SHEET 4/23.

ESTIMATED QUANTITIES (LOR-20-145L)

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
202	11200	LUMP SUM	LUMP	PORTIONS OF STRUCTURE REMOVED				LUMP SUM
202	11301	3	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, PARAPET END			3	
503	21301	LUMP SUM	LUMP	UNCLASSIFIED EXCAVATION, AS PER PLAN				LUMP SUM
509	15840	3,380	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60			3,280	100
510	10001	438	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN			438	
511	34450	16	CU YD	CLASS S CONCRETE, MISC.: PARAPETS			16	
SPECIAL	51267504	107	SQ YD	SEALING OF CONCRETE SURFACES (NON-EPOXY)			107	
SPECIAL	51267510	59	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)		59		
518	21201	26	CU YD	POROUS BACKFILL WITH FILTER FABRIC, AS PER PLAN	26			
518	40001	115	LIN FT	6" PERFORATED CORRUGATED PLASTIC PIPE, AS PER PLAN	115			
518	40011	40	LIN FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS, A.P.P.	40			
SPECIAL	51861400	18	EACH	KEYWAY DRAIN	18			
518	62200	16	EACH	STRUCTURE DRAINAGE, MISC.: SCUPPER PLUGGING			16	
SPECIAL	51922006	511	SQ YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (1/2 INCHES THICK)			511	
SPECIAL	51922100	11	CU YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS)			11	
SPECIAL	51922300	LUMP SUM	LUMP	TEST SLAB				LUMP SUM

ESTIMATED QUANTITIES (LOR-20-145R)

ITEM	ITEM EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER STRUCTURE	GENERAL
202	11200	LUMP SUM	LUMP	PORTIONS OF STRUCTURE REMOVED				LUMP SUM
202	11301	3	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN, PARAPET END			3	
503	21301	LUMP SUM	LUMP	UNCLASSIFIED EXCAVATION, AS PER PLAN				LUMP SUM
509	15840	3,378	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60			3,278	100
510	10001	438	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN			438	
511	34450	16	CU YD	CLASS S CONCRETE, MISC.: PARAPETS			16	
SPECIAL	51267504	107	SQ YD	SEALING OF CONCRETE SURFACES (NON-EPOXY)			107	
SPECIAL	51267510	59	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)		59		
518	21201	26	CU YD	POROUS BACKFILL WITH FILTER FABRIC, AS PER PLAN	26			
518	40001	115	LIN FT	6" PERFORATED CORRUGATED PLASTIC PIPE, AS PER PLAN	115			
518	40011	40	LIN FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS, A.P.P.	40			
SPECIAL	51861400	18	EACH	KEYWAY DRAIN	18			
518	62200	16	EACH	STRUCTURE DRAINAGE, MISC.: SCUPPER PLUGGING			16	
SPECIAL	51922006	511	SQ YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (1/2 INCHES THICK)			511	
SPECIAL	51922100	11	CU YD	MICRO-SILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS)			11	
SPECIAL	51922300	LUMP SUM	LUMP	TEST SLAB				LUMP SUM

EXISTING STRUCTURE

TYPE: THREE SPAN CONTINUOUS REINFORCED CONCRETE SLAB WITH REINFORCED CONCRETE SUBSTRUCTURE
 SPANS: 36'-6", 46'-0" & 36'-6"
 ROADWAY WIDTH: 38'-0" F/F CURB
 ALIGNMENT: TANGENT
 SKEW: 19' 39' 40" LEFT FORWARD
 LOAD FREQUENCY: CF 2000 (57)
 WEARING SURFACE: 1" MONOLITHIC CONCRETE
 APPROACH SLABS: 25'-0" LONG (AS-I-67)
 YEAR BUILT: 1968*
 STRUCTURE FILE NO.: 4701208 & 4701232

PROPOSED WORK

- REMOVE THE TOP 1/4" OF SOUND EXISTING CONCRETE SURFACE AND OVERLAY WITH 1 1/2" (MINIMUM) MICRO-SILICA MODIFIED CONCRETE. (SEE NOTE #4 ON SHEET 21/23).
- DRILL HOLES TO DRAIN ABUTMENT KEYWAY. SEE SHEET 13/23.
- RETROFIT EXISTING PARAPET WITH SAFETY SHAPE PARAPET. FOR DETAILS, SEE SHEET 11/23.
- CONCRETE SEALER ON PIER COLUMNS AND PARAPET.
- PLUG EXISTING SCUPPERS.
- REPLACE EXISTING APPROACH SLAB WITH FULL WIDTH APPROACH SLAB. (SEE ROADWAY PLANS)
- INSTALL APPROACH SLAB DOWEL BARS, SEE SHEET 13/23.
- INSTALL POROUS BACKFILL WITH FILTER FABRIC AND DRAINAGE PIPE, SEE SHEET 13/23.
- SUBSTRUCTURE PATCHING, SEE SHEET 19A/23.

MODIFIED STRUCTURE

TYPE: THREE SPAN CONTINUOUS REINFORCED CONCRETE SLAB WITH REINFORCED CONCRETE SUBSTRUCTURE
 SPANS: 36'-6", 46'-0" & 36'-6"
 ROADWAY WIDTH: 38'-2" T/T SAFETY SHAPE PARAPET
 ALIGNMENT: TANGENT
 SKEW: 19' 39' 40" LEFT FORWARD
 LOAD FREQUENCY: CF 2000 (57)
 WEARING SURFACE: 1 1/2" (MIN.) MICRO-SILICA MODIFIED CONCRETE
 APPROACH SLABS: 25'-0" LONG, FULL WIDTH (AS-I-8)

POLYTECH, INC. 19 / 23
 CONSULTING ENGINEERS CLEVELAND, OHIO

PLAN AND TYPICAL SECTION

BRIDGE NO. LOR-20-145L & R
 OVER INDIAN HOLLOW ROAD


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
PSS	RG	-	VB	BS	8/96	DRA 9/96

DESIGN FILE: c:\dgn\lor20\ip\new.dgn
 WORKSTATION: darmstro DATE: 23 SEP 96


FHWA REGION	STATE	PROJECT	
5	OHIO		

238
351


LORAIN COUNTY
LOR-20-12.62




REAR ABUTMENT, RIGHT BRIDGE



FORWARD ABUTMENT, LEFT BRIDGE



PLAN




ELEVATION

PIER 2, LEFT BRIDGE

LOOKING EAST

LOCATION	RIGHT BRIDGE	LEFT BRIDGE
	ITEM SPECIAL	ITEM SPECIAL
	PATCHING CONCRETE WITH TROWELABLE MORTAR SQ. FT.	PATCHING CONCRETE WITH TROWELABLE MORTAR SQ. FT.
ABUTMENTS	3	5
PIER COLUMNS	-	5
200% EXPANSION FACTOR	6	20
* TOTAL	9	30

 ITEM SPECIAL, PATCHING CONCRETE WITH TROWELABLE MORTAR

* THESE QUANTITIES ARE CARRIED TO THE STRUCTURE SUMMARY SHEET 4/23.

DRAWING = INDPATCH DATE = AUGUST 9, 1996

POLYTECH, INC. 19A/23
CONSULTING ENGINEERS CLEVELAND, OHIO

SUBSTRUCTURE PATCHING

BRIDGE NO. LOR-20-1451 L & R
OVER INDIAN HOLLOW ROAD


LORAIN COUNTY OHIO

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
NK	NK	-	VB	BS	8/96	

FHWA REGION	STATE	PROJECT
5	OHIO	

239
351



LORAIN COUNTY
LOR-20-12.62




DETAIL 1

EXISTING SCUPPER PLUGGING DETAILS
FOR SLAB BRIDGES NO. LOR-20-1356 L & R
AND LOR-20-1451 L & R.

NOTE: THE COST OF FILLING EXISTING SCUPPER WITH MICRO-SILICA MODIFIED CONCRETE, AS SHOWN ABOVE, SHALL BE INCLUDED WITH ITEM 518, "STRUCTURE DRAINAGE, MISC.: SCUPPER PLUGGING" FOR PAYMENT.



PLAN



SECTION A-A


REMOVE 4" OF EXIST. SCUPPER END AND EXTEND TO 8" BELOW BOTTOM OF BEAM FLANGE WITH SAME SIZE STEEL PIPE AS EXISTING

DETAIL 3

EXISTING SCUPPER MODIFICATION DETAILS
FOR BEAM BRIDGE NO. LOR-20-1380 L & R.

NOTE:

1. A 1/2" X 3/8" BAR SHALL BE BENT TO CONFORM WITH SCUPPER EDGE AND WELDED IN PLACE AFTER THE EXISTING SURFACE HAS BEEN CLEANED TO THE ENGINEER'S SATISFACTION. THE SCUPPER EDGE SHALL BE FIELD MEASURED TO DETERMINE THE LENGTH OF THE BENT BAR.
2. ALL SURFACES AGAINST WHICH NEW CONCRETE IS TO BE PLACED SHALL BE CLEANED BY THE CONTRACTOR TO THE ENGINEER'S SATISFACTION.
3. THE ABOVE WORK AND ALSO EXTENDING THE SCUPPER DRAIN PIPE BELOW THE BOTTOM OF THE BEAM AS SHOWN ABOVE SHALL BE INCLUDED WITH THE ITEM 518 "SCUPPER MODIFICATION, AS PER PLAN" FOR PAYMENT.




DETAIL 2

EXISTING SCUPPER PLUGGING DETAILS
FOR BEAM BRIDGE NO. LOR-20-1303.

NOTE: REMOVAL OF EXISTING BULB ANGLE, 1 1/2" X 1/2" BAR, CUTTING & REMOVING 6" SCUPPER DRAIN PIPE 3" BELOW BOTTOM OF EXISTING DECK SLAB, GRINDING WEB AND FILLING SCUPPER DRAIN WITH MICRO-SILICA MODIFIED CONCRETE, AS SHOWN ABOVE SHALL BE INCLUDED WITH ITEM 518, "STRUCTURE DRAINAGE, MISC.: SCUPPER PLUGGING" FOR PAYMENT.


DRAWING = SCUPPER DATE = JULY 30, 1996

POLYTECH, INC.		20 / 23	
CONSULTING ENGINEERS		CLEVELAND, OHIO	
SCUPPER MODIFICATION DETAILS			
BRIDGE NO. LOR-20-1303			
BRIDGE NO. LOR-20-1356 L & R			
BRIDGE NO. LOR-20-1380 L & R			
BRIDGE NO. LOR-20-1451 L & R			
LORAIN COUNTY		OHIO	
DESIGNED	DRAWN	TRACED	CHECKED
PSS	RG	-	VB
REVIEWED	DATE	REVISED	
BS	8/96		



SECTION E-E

(VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN A)
BRIDGE NO. LOR-20-1380 L (FORWARD ABUTMENT)



SECTION A-A

(VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN B)
BRIDGE NO. LOR-20-1303
BRIDGE NO. LOR-20-1380 L (REAR ABUTMENT) AND LOR-20-1380 R

NOTE


1. THE STRIP SEAL GLAND SHALL BE CONTINUOUS AND INSTALLED IN ONE PIECE. THE GLAND SHALL BE TYPE 300L AS MANUFACTURED BY D.S. BROWN COMPANY OR TYPE SE-300 AS MANUFACTURED BY WATSON-BOWMAN & ACME CORPORATION OR EQUAL.
2. PROVIDE A COMPLETE PENETRATION BUTT WELD AT THE ARMOR JOINTS AND A PARTIAL PENETRATION BUTT WELD AROUND THE OUTER PERIPHERY OF THE ABUTTING SURFACES OF THE RETAINER (NOT IN THE AREA IN CONTACT WITH THE GLAND).
3. CARE SHALL BE TAKEN NOT TO DAMAGE EXISTING END CROSSFRAME, EXISTING ANGLE, BEVEL FILL PLATE AND WELDS CONNECTING THEM TO THE BEAM TOP FLANGE.
4. ** TRANSITION THICKNESS OF MICRO-SILICA MODIFIED CONCRETE FROM 1 3/4" TO 1 1/2" THICK 50' ON BRIDGE SIDE. THE EXTRA AMOUNT OF CONCRETE IS INCLUDED IN ITEM "MICRO-SILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS)".

NOTE

FOR LOCATIONS OF SECTION A-A AND SECTION E-E, SEE SHEET 22/23.

BRIDGE NO.	REAR ABUTMENT							FORWARD ABUTMENT								
	STRIP SEAL SIZE (IN.)	DIMENSION "A" AT TIME OF CONSTRUCTION (IN.)							STRIP SEAL SIZE (IN.)	DIMENSION "A" AT TIME OF CONSTRUCTION (IN.)						
		30F	40F	50F	60F	70F	80F	90F		30F	40F	50F	60F	70F	80F	90F
LOR-20-1303	3	1.86	1.79	1.71	1.66	1.57	1.48	1.41	3	1.86	1.79	1.71	1.66	1.57	1.48	1.41
LOR-20-1380 L & R	3	1.81	1.78	1.74	1.71	1.67	1.64	1.61	3	1.86	1.79	1.72	1.65	1.57	1.49	1.43

NOTE: MAXIMUM JOINT OPENING (DIMENSION "A") AT THE TIME OF SEAL GLAND INSTALLATION SHALL NOT BE LESS THAN 1 1/2". IF THE JOINT OPENING IS LESS, INSTALLATION SHALL BE POSTPONED UNTIL THE TEMPERATURE DROPS A SUFFICIENT AMOUNT TO ALLOW THE MINIMUM 1 1/2" OPENING.



DETAIL A

(COMPRESSION SEAL SHALL BE ONE CONTINUOUS PIECE AND SHALL SEAL THE JOINT THE FULL WIDTH OF THE APPROACH SLAB)

* DIMENSIONS SHOWN ARE FOR WATSON BOWMAN ACME INC. WJ-125, STRUCTURAL ACCESSORIES SA1250 OR D.S. BROWN H-1250. USE ANY OF THE ABOVE OR APPROVED EQUAL AS PER 705.11.

† GLUE 1/2" EXPANDED POLYSTYRENE BETWEEN TWO PIECES OF 1/8" MASONITE, INSTALL TOTAL DEPTH OF REPAIRED AREA. THE MASONITE AND POLYSTYRENE SHALL BE IN PLACE BEFORE ANY CONCRETE IS PLACED, AND SHALL BE BELOW THE FINAL ROADWAY GRADE TO FACILITATE FINISHING OF THE CONCRETE ON BOTH SIDES OF THE JOINT.

IF THE CONCRETE ON BOTH SIDES OF THE JOINT IS NOT FINISHED TO THE SAME HEIGHT, THE JOINT SURFACE SHALL BE GROUND SMOOTH AS DIRECTED BY THE ENGINEER.

SAW OUT ENOUGH MASONITE AND POLYSTYRENE TO INSTALL THE COMPRESSION SEAL AFTER THE JOINT HAS BEEN REPAIRED.

PAYMENT FOR ALL MATERIALS, EXCEPT THE CONCRETE, AND LABOR TO REPAIR THE JOINT AS PER DETAILS ON THIS SHEET SHALL BE INCLUDED IN THE UNIT PRICE BID PER LINEAR FOOT OF ITEM 516, "ELASTOMERIC COMPRESSION SEAL".


DRAWING = XJOINT DATE = AUGUST 2, 1996

POLYTECH, INC.					21 / 23
CONSULTING ENGINEERS CLEVELAND, OHIO					
MODIFICATION OF STRUCTURAL EXPANSION JOINT					
BRIDGE NO. LOR-20-1303 BRIDGE NO. LOR-20-1380 L & R					
LORAIN COUNTY OHIO					
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE
PSS	RG	-	VB	BS	8/96


FHWA REGION	STATE	PROJECT
5	OHIO	




LORAIN COUNTY
LOR-20-12.62




PLAN
BRIDGE NO. LOR-20-1303



PLAN
BRIDGE NO. LOR-20-1380 L (REAR ABUTMENT) AND LOR-20-1380 R




SECTION B-B
BRIDGE NO. LOR-20-1303




SECTION C-C
(HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT)
BRIDGE NO. LOR-20-1303

** CONTRACTOR MAY UTILIZE SPLIT RETAINERS AS SHOWN AT HIS OPTION (AT NO ADDITIONAL COST TO THE STATE) IF REQUIRED TO FACILITATE PLACEMENT OF STRIP SEAL.



SECTION D-D
(HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT)
BRIDGE NO. LOR-20-1380 L & R



PLAN
BRIDGE NO. LOR-20-1380 L (FORWARD ABUTMENT)

NOTE
FOR SECTION A-A AND SECTION E-E,
SEE SHEET 21/23.

POLYTECH, INC. 22/23					
CONSULTING ENGINEERS CLEVELAND, OHIO					
MODIFICATION OF STRUCTURAL EXPANSION JOINT					
BRIDGE NO. LOR-20-1303					
BRIDGE NO. LOR-20-1380 L & R					
LORAIN COUNTY OHIO					
DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE
PSS	MAC	-	VB	BS	8/96

DRAWING = XJOINT1 DATE = AUGUST 2, 1996


LORAIN COUNTY
LOR-20-12.62

BRIDGE NO. LOR-20-1356 L									BRIDGE NO. LOR-20-1356 R										
MARK	NO.	LENGTH	TYPE	A	B	C	D	SERIES INCR.	WEIGHT (LBS)	MARK	NO.	LENGTH	TYPE	A	B	C	D	SERIES INCR.	WEIGHT (LBS)
EP521	170	2'-8"	1						473	EP521	170	2'-8"	1						473
EP522	170	3'-8"	2						650	EP522	170	3'-8"	2						650
EP523	10	25'-8"	STR.						268	EP523	10	25'-8"	STR.						268
EP524	28	14'-3"	STR.						416	EP524	28	14'-3"	STR.						416
EP525	28	14'-3"	STR.						416	EP525	28	14'-3"	STR.						416
EP526	16	3'-9"	6						63	EP526	16	3'-9"	6						63
EP527	16	3'-2"	STR.						53	EP527	16	3'-2"	STR.						53
EP528	16	2'-8"	5	10"	1'-3"				45	EP528	16	2'-8"	5	10"	1'-3"				45
EP529	2	4'-8"	STR.						10	EP529	2	4'-8"	STR.						10
EP530	8	9'-1"	3	5"	1'-8"	4'-11"	2 3/4"		76	EP530	8	9'-1"	3	5"	1'-8"	4'-11"	2 3/4"		76
EP531	4	4'-8"	STR.						19	EP531	4	4'-8"	STR.						19
EP532	2	5'-0"	STR.						10	EP532	2	5'-0"	STR.						10
EP533	8	8'-9"	3	5"	1'-8"	4'-8"	2 1/2"		73	EP533	8	8'-9"	3	5"	1'-8"	4'-8"	2 1/2"		73
EP534	4	5'-0"	STR.						21	EP534	4	5'-0"	STR.						21
EA803	54	4'-9"	7						685	EA803	54	4'-9"	7						685
TOTAL									3,278	TOTAL									3,278

BRIDGE NO. LOR-20-1303										
MARK	NO.	LENGTH	TYPE	A	B	C	D	SERIES INCR.	WEIGHT (LBS)	
EP501	360	2'-8"	1						1003	
EP502	360	3'-8"	2						1,377	
EP503	16	29'-0"	STR.						484	
EP504	48	15'-8"	STR.						784	
EP505	48	15'-8"	STR.						784	
EP506	8	13'-5"	STR.						112	
EP507	8	13'-5"	STR.						112	
EP508	10	14'-7"	3	4"	1'-4 1/2"	10'-7 1/2"	5 7/8"		152	
EP509	12	4'-4"	STR.						54	
EP510	16	3'-9"	6						63	
EP511	16	3'-2"	STR.						53	
EP512	16	2'-8"	5	10"	1'-3"				45	
EP513	10	13'-7"	3	4"	1'-4 1/2"	9'-7 1/2"	5 1/4"		142	
EP514	4	5'-5"	9						23	
EP515	4	3'-5"	10						14	
PIER ENCASEMENT									3,727	
TOTAL									8,929	

BRIDGE NO. LOR-20-1380 L									BRIDGE NO. LOR-20-1380 R										
MARK	NO.	LENGTH	TYPE	A	B	C	D	SERIES INCR.	WEIGHT (LBS)	MARK	NO.	LENGTH	TYPE	A	B	C	D	SERIES INCR.	WEIGHT (LBS)
EP541	208	2'-8"	1						579	EP541	208	2'-8"	1						579
EP542	208	3'-8"	2						795	EP542	208	3'-8"	2						795
EP543	8	29'-2"	STR.						243	EP543	8	29'-2"	STR.						243
EP544	32	15'-1"	STR.						503	EP544	32	15'-1"	STR.						503
EP545	32	15'-1"	STR.						503	EP545	32	15'-1"	STR.						503
EP546	12	3'-9"	6						47	EP546	12	3'-9"	6						47
EP547	12	3'-2"	STR.						40	EP547	12	3'-2"	STR.						40
EP548	12	2'-7"	5	10"	1'-3"				32	EP548	12	2'-7"	5	10"	1'-3"				32
EP549	4	2'-10"	STR.						12	EP549	4	2'-10"	STR.						12
EP550	16	8'-8"	3	4"	1'-4 1/2"	4'-10"	2 3/4"		145	EP550	16	8'-8"	3	4"	1'-4 1/2"	4'-10"	2 3/4"		145
EP551	8	4'-4"	STR.						36	EP551	8	4'-4"	STR.						36
EP552	8	1'-10"	4						15	EP552	8	1'-10"	4						15
EP553	8	1'-10"	4						15	EP553	8	1'-10"	4						15
EP554	16	1'-11"	STR.						32	EP554	16	1'-11"	STR.						32
EP555	8	2'-4"	5	10"	11"				19	EP555	8	2'-4"	5	10"	11"				19
EP556	4	0'-7"	STR.						2	EP556	4	0'-7"	STR.						2
EP557	4	1'-0"	STR.						4										4
EP558	2	29'-7"	STR.						62	EP558	2	29'-7"	STR.						123
EA501	20	3'-0"	STR.						63										
EA502	6	20'-1"	STR.						126										
EA503	1	20'-1"	STR.						21										
EA504	1	20'-1"	STR.						21										
EA505	6	18'-1"	STR.						113										
EA506	1	18'-1"	STR.						19										
EA507	1	18'-1"	STR.						19										
EA601	38	4'-6"	5	2'-0"	10"				257										
EA801	27	6'-0"	8						433										
TOTAL									4,156	TOTAL									3,084

BRIDGE NO. LOR-20-1451L									BRIDGE NO. LOR-20-1451R										
MARK	NO.	LENGTH	TYPE	A	B	C	D	SERIES INCR.	WEIGHT (LBS)	MARK	NO.	LENGTH	TYPE	A	B	C	D	SERIES INCR.	WEIGHT (LBS)
EP521	170	2'-8"	1						473	EP521	170	2'-8"	1						473
EP522	170	3'-8"	2						650	EP522	170	3'-8"	2						650
EP523	10	25'-8"	STR.						268	EP523	10	25'-8"	STR.						268
EP524	28	14'-3"	STR.						416	EP524	28	14'-3"	STR.						416
EP525	28	14'-3"	STR.						416	EP525	28	14'-3"	STR.						416
EP526	12	3'-9"	6						47	EP526	16	3'-9"	6						63
EP527	16	3'-2"	STR.						53	EP527	16	3'-2"	STR.						53
EP528	16	2'-8"	5	10"	1'-3"				45	EP528	16	2'-8"	5	10"	1'-3"				45
EP529	2	4'-8"	STR.						10	EP529	2	4'-8"	STR.						10
EP530	8	9'-1"	3	5"	1'-8"	4'-11"	2 3/4"		76	EP530	8	9'-1"	3	5"	1'-8"	4'-11"	2 3/4"		76
EP531	4	4'-8"	STR.						19	EP531	4	4'-8"	STR.						19
EP532	2	5'-0"	STR.						10	EP532	2	5'-0"	STR.						10
EP533	8	8'-9"	3	5"	1'-8"	4'-8"	2 1/2"		73	EP533	8	8'-9"	3	5"	1'-8"	4'-8"	2 1/2"		73
EP534	4	5'-0"	STR.						21	EP534	4	5'-0"	STR.						21
EP535	4	4'-3"	2						18										
EA803	54	4'-9"	7						685	EA803	54	4'-9"	7						685
TOTAL									3,280	TOTAL									3,278



- NOTES:**
- ALL BARS DIMENSIONS ARE GIVEN OUT-TO-OUT.
 - ALL BARS SHALL BE EPOXY COATED.
 - THE BAR SIZE NUMBER IS SPECIFIED ON THE PLANS IN THE BAR MARK COLUMN. THE FIRST DIGIT INDICATES THE BAR SIZE NUMBER.
 - REINFORCING STEEL UTILIZES A MECHANICAL CONNECTOR. BAR LENGTH FOR PAYMENT IS MEASURED TO THE CONSTRUCTION JOINT. EXTRA BAR LENGTH AND/OR BAR END PREPARATION MAY BE NECESSARY DEPENDING UPON THE TYPE OF MECHANICAL CONNECTOR FURNISHED.

POLYTECH, INC. 23/23
CONSULTING ENGINEERS CLEVELAND, OHIO

REINFORCEMENT SCHEDULE

BRIDGE NO. LOR-20-1303
BRIDGE NO. LOR-20-1356 L & R
BRIDGE NO. LOR-20-1380 L & R
BRIDGE NO. LOR-20-1451 L & R

LORAIN COUNTY OHIO


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
PSS	PSS	-	VB	BRS	8/96	DRA 9/96

DESIGN FILE: c:\dgn\lor20\rebarnew.dgn
WORKSTATION: dar.mstro DATE: 23 SEP 96

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION

CRA-30-7.11

VARIOUS COUNTIES



PROJECT DESCRIPTION

REPAIR VARIOUS STRUCTURES WITH HEAT STRAIGHTENING, CROSS FRAME REPLACEMENT AND PAINTING.

PROJECT EARTH DISTURBED AREA = 0 ACRES
 ESTIMATED CONTRACTOR EARTH DISTURBED AREA = 0 ACRES
 NOTICE OF INTENT EARTH DISTURBED AREA = 0 ACRES

INDEX OF SHEETS:

TITLE SHEET	1
GENERAL NOTES	2-3
GENERAL SUMMARY	4
STRUCTURE CRA-30-0711R	5-6
STRUCTURE LOR-20-1303	7-9
STRUCTURE RIC-30-0517	10-11
STRUCTURE RIC-30-1384	12-14

2002 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

APPROVED Thomas M. O'Leary ^{as}
DATE 9/10/03 DISTRICT DEPUTY DIRECTOR

APPROVED London Proctor
DATE 9-29-03 DIRECTOR, DEPARTMENT OF TRANSPORTATION

LOCATION MAP

PORTION TO BE IMPROVED X
 STATE & FEDERAL ROUTES ==
 OTHER ROADS ---

PLAN PREPARED BY:



ENGINEERS SEAL:


SIGNED: David Mollenshott
DATE: 9/8/03

STANDARD CONSTRUCTION DRAWINGS		SUPPLEMENTAL SPECIFICATIONS	
DM-4.3	7-19-02		
DM-4.4	7-19-02		
MT-35.10	4-20-01		
MT-95.30	4-19-02		
MT-97.10	4-19-02		
MT-98.13	4-19-02		
MT-98.14	4-19-02		
MT-105.10	10-18-02		
MT-105.11	10-18-02		
		832	2-12-03
		833	2-12-03

UNDERGROUND UTILITIES
 TWO WORKING DAYS
BEFORE YOU DIG
 CALL 1-800-362-2764 (TOLL FREE)
 OHIO UTILITIES PROTECTION SERVICE
 NON-MEMBERS
 MUST BE CALLED DIRECTLY


FEDERAL PROJECT NO. **NON-FEDERAL**
 PID NO. **25736**
 CONSTRUCTION PROJECT NO. **NONE**
 RAILROAD INVOLVEMENT **NONE**
 CRA-30-7.11

DESIGN FILE: \projects\usr30-7.11\title sheet.dgn
WORKSTATION: dmollens DATE: 09/08/03



ITEM	QUANTITY	UNIT	DESCRIPTION
202	58	EACH	REMOVAL MISC.: REMOVAL OF EXISTING SPLICE PLATE BOLT
SPECIAL	LUMP		HEAT STRAIGHTENING OF DAMAGED STRUCTURAL STEEL
513	58	EACH	STRUCTURAL STEEL MISC.: HIGH STRENGTH BOLT, NUT AND WASHERS
514	LUMP		SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL
514	LUMP		FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT
514	LUMP		FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT
514	LUMP		FIELD PAINTING STRUCTURAL STEEL, FINISH COAT

ALL QUANTITIES CARRIED TO GENERAL SUMMARY SHEET NO. 4

 AREA TO BE HEAT STRAIGHTENED

NOTES:

- THE EXISTING CONCRETE DECK IS NOT SHOWN IN THE PLAN VIEW.
- SECTION A-A IS SHOWN ON SHEET NO. 8
- SECTION B-B AND C-C ARE SHOWN ON SHEET NO. 9.


DESIGN FILE: i:\projects\25736\Struct\details.dgn
 WORKSTATION: dmollens DATE: 09/08/03

DATE 8/03
 REVIEWED RDN
 STRUCTURAL FILE NUMBER 4706609
 DCM
 REVISIONS
 DCM
 CHECKED
 CL

PLAN VIEW
 LOR-20-1303 UNDER S.R. 301

CRA-30-7.11


DESIGN FILE: i:\projects\25736\Struct\details.dgn
WORKSTATION: dmo/lens DATE: 09/08/03




SECTION A-A

DRAWN DCM	CHECKED CL	REVIEWED RDN	DATE 8/03
		STRUCTURAL FILE NUMBER 4706609	
SECTION VIEWS LOR-20-1303 UNDER S.R. 301			
CRA-30-7.11			
8 14			


DESIGN FILE: i:\projects\25736\Struct\details.dgn
WORKSTATION: dml/lens DATE: 09/08/03



SECTION B-B



SECTION C-C

 AREA TO BE PENCIL ABRASIVE BLASTED AND INSPECTED FOR CRACKS AFTER REMOVAL OF THE EXISTING CROSSFRAMES. NON-DESTRUCTIVE TESTING SHALL BE PERFORMED ON BOTH SIDES OF THE OUTSIDE BEAM AND ONE SIDE OF THE ADJACENT BEAM. THESE ITEMS ARE INCIDENTAL TO ITEM SPECIAL.


DATE	8/03
REVIEWED	RDN
STRUCTURAL FILE NUMBER	4706609
DRAWN	DCM
REVISD	
DESIGNED	DCM
CHECKED	CL

SECTION VIEWS
LOR-20-1303 UNDER S.R. 301

CRA-30-7.11


060237 PID - 23581
Dist 3 5/17/2006

MED - SR 301-0.00/0.00/5.48 - Part 1 &



LATITUDE: 041°08'10" LONGITUDE: 082°07'22"

SCALE IN MILES



PORTION TO BE IMPROVED -----
 INTERSTATE & DIVIDED HIGHWAY -----
 UNDIVIDED STATE & FEDERAL ROUTES -----
 OTHER ROADS -----

STATE OF OHIO
 DEPARTMENT OF TRANSPORTATION

MED - 301 - 0.00 - PART 1
LOR - 301 - 0.00 - PART 1

(FOR PART 2, SEE MED-301-5.48)

HOMER TOWNSHIP PENFIELD TOWNSHIP
 SPENCER TOWNSHIP LAGRANGE TOWNSHIP
 CARLISLE TOWNSHIP

INDEX OF SHEETS:

TITLE	1	TRAFFIC CONTROL DETAILS	45
STRAIGHT LINE DIAGRAM	2-3	SIGNAL NOTES AND DETAILS	46-60
DESIGN DESIGNATION	2-3	STRUCTURE MED-301-0677	61-74
ROADWAY GENERAL NOTES	4-8	STRUCTURE MED-301-0679 QUANTITIES AND DETAILS	75-78
DROP-OFFS IN WORK ZONES	9	STRUCTURE SUMMARY	79-82
MAILBOX FACILITIES	10	STRUCTURE GENERAL NOTES	83-86
GENERAL SUMMARY	11-12A	STRUCTURE TREATMENT	87
PAVEMENT DATA	13	STRUCTURE MED-301-0337	88-93
SHOULDER DATA	14	STRUCTURE MED-301-0624	94-96
TYPICAL SECTIONS	15-17	STRUCTURE MED-301-0701	97-100
ROADWAY SUB-SUMMARY	18	STRUCTURE LOR-301-0015	101-102
SMITH ROAD DETAILS	19-23	STRUCTURE LOR-301-0184	103-105
GUARDRAIL GENERAL NOTES	24	STRUCTURE LOR-301-0894	106
GUARDRAIL DETAILS	25-36	STRUCTURE LOR-301-0919	107-108
CURB RAMPS	37-42	STRUCTURE LOR-301-1259	109-110
LOOP DETECTOR NOTES AND DETAILS	43	RIGHT OF WAY	111-114
PAVEMENT MARKING AND RPM SUB-SUMMARY	44		

PROJECT DESCRIPTION

THIS PROJECT WILL INCLUDE PAVEMENT PLANING, PAVEMENT REPAIR, RESURFACING WITH ASPHALT CONCRETE, ADJUSTMENT OF CASTINGS WHERE NECESSARY, GUARDRAIL, PAVEMENT MARKINGS, MINOR BRIDGE REHABILITATION, CULVERT REPLACEMENT, AND NEW TRAFFIC SIGNAL INSTALLATION.

PROJECT EARTH DISTURBED AREA: N/A ACRES
 ESTIMATED CONTRACTOR EARTH DISTURBED AREA: N/A ACRES
 NOTICE OF INTENT EARTH DISTURBED AREA: N/A ACRES

2005 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AS NOTED ON SHEET 63, AND THAT DETOURS WILL BE PROVIDED AS INDICATED ON THE PLANS.

APPROVED *Thomas M. Clew*
 DATE 2-16-06 DISTRICT DEPUTY DIRECTOR

APPROVED *Lynda Parton*
 DATE 3/22/06 DIRECTOR, DEPARTMENT OF TRANSPORTATION

UNDERGROUND UTILITIES


CONTACT BOTH SERVICES
 CALL TWO WORKING DAYS
 BEFORE YOU DIG

CALL
1-800-362-2764
 (TOLL FREE)


OHIO UTILITIES PROTECTION SERVICE
 NON-MEMBERS
 MUST BE CALLED DIRECTLY

OIL & GAS PRODUCERS PROTECTIVE
 SERVICE CALL: 1-800-929-0988


ROADWAY PART I, ENGINEERS SEAL: SIGNAL PART I, ENGINEERS SEAL: STRUCTURE/CULVERT PART I, ENGINEERS SEAL:



SIGNED: *Michael J. Schaff*
 DATE: 2/16/06



SIGNED: *Richard J. Roney*
 DATE: 2-16-06



SIGNED: *David C. Molleshott*
 DATE: 2/16/06

STANDARD CONSTRUCTION DRAWINGS (FOR PART 1 & 2)

NO.	DATE	NO.	DATE	NO.	DATE	NO.	DATE	NO.	DATE	SUPPLEMENTAL SPECIFICATIONS (FOR PART 1 & 2)
BP-3.1	7/18/04	GR-3.3	1/20/06	GSD-1-98	7/18/02	MT-98.20	4/18/02	TC-85.10	1/21/05	800 01-20-08
BP-4.1	7/18/04	GR-3.4	4/18/03	RB-1-88	2/2/88	MT-98.25	4/20/01	TC-85.11	1/21/05	832 04-17-04
		GR-3.6	1/18/04	TBR-81	7/18/02	MT-97.10	4/18/02	TC-71.10	1/21/05	833 02-12-03
CB-1.1	7/15/05	GR-4.1	4/18/03	TST-1-89	10/17/03	MT-97.12	4/18/02	TC-73.10	1/19/01	848 04-15-05
CB-1.2	7/15/05	GR-6.3	1/18/04			MT-98.20m	1/30/95	TC-81.10	5/01/00	872 10-30-03
CB-4.2	7/18/02			HL-10.11	1/18/04	MT-101.20	10/18/02	TC-82.10	4/18/02	
		HW-1.1	1/21/05	HL-10.12	1/21/05	MT-101.60	10/18/02	TC-83.10	5/01/00	
DM-1.1	10/21/05	HW-2.1	1/20/06	HL-20.11	4/18/02	MT-105.10	10/18/02	TC-83.20	1/18/04	
DM-1.4	1/21/05	HW-2.2	7/18/05	HL-30.11	1/21/05	MT-105.11	10/18/02	TC-84.20	5/01/00	
DM-4.3	7/18/02			HL-30.21	4/18/02	MT-120.00	3/01/00	TC-84.21	3/08/00	
DM-4.4	7/18/02	RM-1.1	1/20/06	HL-30.22	1/21/05			TC-85.20	5/01/00	
		RM-3.1	4/18/03			TC-22.10	1/18/01			
GR-1.1	7/18/04	RM-4.2	4/18/03	MT-35.10	4/20/01	TC-41.20	1/18/01			
GR-2.1	1/18/04			MT-85.30	7/18/04	TC-42.20	7/18/04			
GR-3.1	4/18/03	DS-1-92	7/18/03	MT-85.61	4/18/02	TC-52.10	4/20/01			
GR-3.2	4/18/03	EX-4-87	7/18/02	MT-85.10	4/18/02	TC-52.20	4/20/01			

SUPPLEMENTAL SPECIFICATIONS (FOR PART 1 & 2)

PLAN PREPARED BY:



FEDERAL PROJECT NO. E034(150)


PID NO. 23581

CONSTRUCTION PROJECT NO.

RAILROAD INVOLVEMENT NONE

MED - 301 - 0.00
LOR - 301 - 0.00

114



WINGWALLS TO BE SEALED (TYP)
(SEE SHEET 2/2 FOR DETAILS)

PARAPETS TO BE SEALED (TYP)
(SEE SHEET 2/2 FOR DETAILS)

ABUTMENTS TO BE SEALED (TYP)
(SEE SHEET 2/2 FOR DETAILS)

DECK TO BE SEALED

MEDIAN CURB TO BE REPAIRED
(SEE SHEET 2/2 FOR DETAILS)

ITEM	QUANTITY	UNIT	DESCRIPTION
512	1651	SQ YD	TREATING OF CONCRETE BRIDGE DECK WITH SRS





- 1) SEE SHEET 2/2 FOR SEALING DETAILS.
- 2) SEE SHEET 2/2 FOR MEDIAN CURB REPAIR.

ALL QUANTITIES CARRIED TO GENERAL SUMMARY SHEET 82.

DESIGN FILE I:\projects\23581\Structure\LOR301\259\lor30124\ltd.dgn
 WORKSTATION: sdeer DATE 2/16/2006

DISTRICT THREE
 OFFICE OF PRODUCTION
 DATE 02/06
 FILE NUMBER 4706609
 GTS
 DIV
 PLAN VIEW
 LOR-301-1259
 OVER S.R. 20
 MED-301-0.00
 LOR-301-0.00
 1/2
 109
 114

DESIGN FILE I:\projects\23581\STR\LOT\LOR301\259\lor301\24\isc.dgn
 WORKSTATION: sdebr DATE 2/16/2006



ITEM	QUANTITY	UNIT	DESCRIPTION
202	15	CU YD	PORTIONS OF STRUCTURE REMOVED
509	1427	POUND	EPOXY COATED REINFORCING STEEL
511	15	CU YD	CLASS S CONCRETE, SUPERSTRUCTURE, AS PER PLAN
512	675	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)
512	97	SQ YD	TREATING OF CONCRETE BRIDGE DECK WITH SRS

ALL QUANTITIES CARRIED TO GENERAL SUMMARY SHEET 82.

REINFORCING TABLE				
MARK	NUMBER	LENGTH	WEIGHT	TYPE
M501	36	38'	1427	STR.
TOTAL			1427	

DESIGN AGENCY
 DISTRICT 3
 OFFICE OF PRODUCTION

DATE 02/06
 RDN
 STRUCTURE FILE NUMBER 4706609
 DRAWN GTS
 REVISED
 DESIGNED GTS
 CHECKED DJV

SEALING DETAIL
 LOR-301-1259
 OVER US 20

MED-301-0.00
 LOR-301-0.00

2 / 2

110
 114

STATE OF OHIO,
DEPARTMENT OF TRANSPORTATION

LOR-20-8.56

**NEW RUSSIA TOWNSHIP
CARLISLE TOWNSHIP
LORAIN COUNTY**

PROJECT DESCRIPTION
RESURFACING, INCLUDING PAVEMENT PLANING AND REPAIRS,
GUARDRAIL REPAIR, TRAFFIC CONTROL, AND MINOR
STRUCTURE WORK.

PROJECT EARTH DISTURBED AREA: N/A
ESTIMATED CONTRACTOR EARTH DISTURBED AREA: N/A
NOTICE OF INTENT EARTH DISTURBED AREA: N/A

LIMITED ACCESS
THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH
TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS
HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN
ACCORDANCE WITH THE PROVISION OF SECTION 5511.02
OF THE OHIO REVISED CODE

2010 SPECIFICATIONS
THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO,
DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES AND
SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL
SHALL GOVERN THIS IMPROVEMENT.


I HEREBY APPROVE THE PLANS AND DECLARE THAT THE MAKING
OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO
TRAFFIC OF THE HIGHWAY EXCEPT AS NOTED ON SHEETS 12-
13, AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY
OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND
ESTIMATES.

UNDER AUTHORITY OF SECTION 4511.21, DIVISION (H)
OF THE OHIO REVISED CODE, THE REVISED PRIMA
FACIE SPEED LIMITS AS INDICATED HEREIN ARE DE-
TERMINED TO BE REASONABLE AND SAFE, AND ARE
HEREBY ESTABLISHED FOR THE DURATION OF THIS
PROJECT. THE PRIMA FACIE SPEED LIMIT OF LIMITS
HEREBY ESTABLISHED SHALL BECOME EFFECTIVE WHEN
APPROPRIATE SIGNS GIVING NOTICE THEREOF ARE
ERECTED.

APPROVED: *[Signature]*
DATE 11-28-11 DISTRICT DEPUTY DIRECTOR

APPROVED: *[Signature]*
DATE 12-5-11 DIRECTOR, DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT NO. **E033748**
PID NO. **23809**
CONSTRUCTION PROJECT NO. **NONE**
RAILROAD INVOLVEMENT **NONE**
LOR-20-8.56



INDEX OF SHEETS:

TITLE SHEET	1
SCHEMATIC/DESIGN DESIGNATION	2-3
TYPICAL SECTIONS	4-6
GENERAL NOTES	7-8
MAINTENANCE OF TRAFFIC NOTES	9-11, 11 A
RAMP DETOUR DETAIL	12-13
GENERAL SUMMARY	14-16
PAVEMENT AND SHOULDER DATA	17
PAVEMENT REPAIR QUANTITIES	18-20
PAVEMENT TRANSITIONING DETAIL	21-22
GUARDRAIL NOTES	23
GUARDRAIL SUB-SUMMARY	24
GUARDRAIL DETAILS	25-33
WEIGH-IN-MOTION REMOVAL DETAILS	34-36
LOOP DETECTOR NOTES & DETAILS	37-39
OVERHEAD MOUNTED SIGN DETAILS	40
PAVEMENT MARKING / RPM SUB-SUMMARY	41
RUMBLE STRIPES PLAN INSERT SHEET	42
STRUCTURE SHEETS	43-68

LOR - US-20-8.56
120106 PID - 23809
Dist 3 2/23/2012
Contract Proposal available @
www.contracts.dot.state.oh.us/home

<p>STRUCTURAL ENGINEERS SEAL:</p> <p>SIGNED: <i>[Signature]</i> DATE: <u>11/23/11</u></p>	<p>ROADWAY ENGINEERS SEAL:</p> <p>SIGNED: <i>[Signature]</i> DATE: <u>11/23/11</u></p>
--	---

STANDARD CONSTRUCTION DRAWINGS						SUPPLEMENTAL SPECIFICATIONS			
DBR-2-73	7/19/02	GR-1.1	7/18/04	MT-35.10	1/20/07	MT-105.10	1/16/09	SS800	10/21/11
DBR-3-11	7/15/11	GR-2.1	1/16/04	MT-95.30	7/17/09	HL-30.21	10/21/11	SS832	5/5/09
		GR-3.1	10/16/09	MT-95.31	7/17/09			SS836	4/15/05
		GR-4.2	1/19/07	MT-95.32	7/17/09	TC-41.20	1/19/07		
BP-2.1	7/18/08	GR-5.2	4/16/10	MT-95.50	4/17/09	TC-42.10	1/19/07		
BP-2.2	7/18/08	GR-5.3	4/16/10	MT-97.10	10/15/10	TC-42.20	1/21/11		
BP-2.3	7/18/04	GR-6.2	4/16/10	MT-98.10	7/17/09	TC-52.10	1/19/07		
BP-2.5	7/18/08			MT-98.11	7/17/09	TC-52.20	1/19/07		
BP-3.1	10/19/07			MT-98.20	7/17/09	TC-65.10	1/21/05		
BP-9.1	4/15/05	RM-4.5	10/16/09	MT-98.22	7/17/09	TC-65.11	1/21/05		
		RM-4.6	4/16/10	MT-98.28	7/17/09	TC-71.10	1/21/11		
DM-1.2	10/21/05			MT-98.29	7/17/09	TC-72.20	10/16/09		
DM-4.3	4/17/09			MT-99.20	1/16/09	TC-73.10	10/21/11		
DM-4.4	4/17/09			MT-101.60	4/17/09	TC-82.10	1/21/11		
				MT-101.70	4/16/11				
				MT-95.40	7/17/09	MT-101.90	10/21/11		

UNDERGROUND UTILITIES
CONTACT BOTH SERVICES
CALL TWO WORKING DAYS
BEFORE YOU DIG

CALL
1-800-362-2764
(TOLL FREE)
OHIO UTILITIES PROTECTION SERVICE
NON-MEMBERS
MUST BE CALLED DIRECTLY
OIL & GAS PRODUCERS PROTECTIVE
SERVICE CALL: 1-800-925-0988



DESIGN WORKSTATION \$\$\$\$
TERMINAL \$\$\$\$
DATE \$\$\$\$
SPECIFIC \$\$\$\$
FILE \$\$\$\$
CNC \$\$\$\$
DRAWING \$\$\$\$

REFERENCES SHALL BE MADE TO STANDARD BRIDGE DRAWINGS:

DBR-2-73 DATED 7/19/02
 DBR-3-11 DATED 7/15/11

DESIGN SPECIFICATIONS:

THIS STRUCTURE CONFORMS TO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2002, INCLUDING THE 2003, 2004, 2005 AND 2006 SPECIFICATIONS AND THE ODOT BRIDGE DESIGN MANUAL.

EXISTING STRUCTURE VERIFICATION:

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURES HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURES AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURES AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO CMS SECTIONS 102.05, 105.02 AND 513.04.

BASE CONTRACT BID PRICES UPON A RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PRE BID EXAMINATION OF THE EXISTING STRUCTURES. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD.

EXISTING PLANS:

THE ORIGINAL CONSTRUCTION PLANS OF THE EXISTING BRIDGES ARE AVAILABLE UPON REQUEST AT THE DISTRICT 3 OFFICE OF THE OHIO DEPARTMENT OF TRANSPORTATION, ASHLAND, OH.

STRUCTURE #	PLAN NAME	DATE
LOR-20-0868	LOR-20-8.58	1986
LOR-20-0973	LOR-20-8.58	1986
LOR-20-0999	LOR-20-8.58	1986
LOR-20-1056L&R	LOR-20-8.58	1986
LOR-20-1208L&R	LOR-20-8.58	1986
LOR-20-1303	LOR-20-12.62	1968

DESIGN DATA:

CONCRETE CLASS C - COMPRESSIVE STRENGTH 4,000 PSI
 CONCRETE CLASS S - COMPRESSIVE STRENGTH 4,500 PSI
 REINFORCING STEEL - ASTM A615 OR A996 GRADE 60 MINIMUM YIELD STRENGTH 60,000 PSI
 STRUCTURAL STEEL - A709 GRADE 36 - YIELD STRENGTH 36,000 PSI

DECK PROTECTION METHOD:

TYPE 3 WATERPROOFING AND ASPHALT CONCRETE OVERLAY
 SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN

ENVIRONMENTAL COMMITMENTS :

IN STREAM WORK RESTRICTION:

THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO AVOID CONSTRUCTION IN AND/OR LIMIT DEMOLITION DEBRIS FROM ENTERING STREAMS OR WETLANDS. ANY MATERIAL THAT DOES FALL INTO STREAMS OR WETLANDS SHALL BE REMOVED AS SOON AS POSSIBLE.

ALL PROJECTS INVOLVING JURISDICTIONAL WATERS OF THE UNITED STATES (STREAMS, RIVERS, NON-ISOLATED WETLANDS) AND/OR ISOLATED WETLANDS ARE SUBJECT TO REGULATION UNDER SECTIONS 404 AND 401 OF THE CLEAN WATER ACT, AND POSSIBLY OHIO EPA ISOLATED WETLAND LAW. IT IS ANTICIPATED THAT NO IN-STREAM WORK, OR WORK UNDER THE STREAM'S ORDINARY HIGH WATER MARK (OHWM) WILL BE NEEDED. THEREFORE NO WATERWAY PERMITS HAVE BEEN GRANTED FOR THIS PROJECT AND NO IN-STREAM WORK IS ALLOWED.

SHOULD WORK (EITHER TEMPORARY OR PERMANENT) IN THE STREAM IS NEEDED; IT WILL REQUIRE A PERMIT AND AUTHORIZATION BY THE UNITED STATES ARMY CORPS OF ENGINEERS (USACE). THE CONTRACTOR SHALL NOT UTILIZE FILLS BELOW OHWM UNTIL SUCH ACTIVITY IS AUTHORIZED BY THE USACE. DETAILS OF THIS REQUIREMENT ARE DESCRIBED IN ODOT'S SUPPLEMENTAL SPECIFICATION 832.09.

USACE DEFINITION OF OHWM - THE ORDINARY HIGH WATER MARK IS THE LINE ON THE SHORES ESTABLISHED BY THE FLUCTUATIONS OF WATER AND INDICATED BY PHYSICAL CHARACTERISTICS SUCH AS A CLEAR, NATURAL LINE IMPRESSED ON THE BANK; SHELING; CHANGES IN THE CHARACTER OF THE SOIL; DESTRUCTION OF TERRESTRIAL VEGETATION; THE PRESENCE OF LITTER AND DEBRIS; OR THE APPROPRIATE MEANS THAT CONSIDER THE CHARACTERISTICS OF THE SURROUNDING AREAS.

DESIGN FILE:\projects\23809\Struct\strnote.dgn
 WORKSTATION:hyar\yanh DATE:11/23/2011 MODELNAME: Design

DESIGN AGENCY
 ODOT DISTRICT THREE
 OFFICE OF
 PLANNING AND ENGINEERING

DATE 11/11
 REVIEWED DJV
 STRUCTURE FILE NUMBER

DRAWN DCM
 REVISION

DESIGNED DCM
 CHECKED CAL

STRUCTURE NOTES

LOR-20-8.56

CUT LINE CONSTRUCTION JOINT PREPARATION:

SAW CUT BOUNDARIES OF PROPOSED CONCRETE REMOVALS 1 INCH DEEP. REMOVE CONCRETE TO A ROUGH SURFACE. LEAVE THE EXISTING REINFORCING STEEL IN PLACE. PRIOR TO CONCRETE PLACEMENT ABRASIVELY CLEAN JOINT SURFACES AND EXISTING EXPOSED REINFORCEMENT TO REMOVE LOOSE AND DISINTEGRATED CONCRETE AND LOOSE RUST. THOROUGHLY CLEAN THE JOINT SURFACE AND EXPOSED REINFORCEMENT OF ALL DIRT, DUST, RUST OR OTHER FOREIGN MATERIAL BY THE USE OF WATER, AIR UNDER PRESSURE, OR OTHER METHODS THAT PRODUCE SATISFACTORY RESULTS. EXISTING REINFORCING STEEL DOES NOT HAVE TO HAVE A BRIGHT STEEL FINISH, BUT REMOVE ALL PACK AND LOOSE RUST. THOROUGHLY DRENCH EXISTING CONCRETE SURFACES WITH CLEAN WATER AND ALLOW TO DRY TO A DAMP CONDITION BEFORE PLACING CONCRETE.

ITEM 202 - REMOVAL MISC.: ELASTOMERIC COMPRESSION SEAL GLAND:

THIS ITEM SHALL BE USED TO REMOVE THE EXISTING ELASTOMERIC SEAL GLAND.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER FOOT FOR THE ABOVE ITEM, WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 202 - PORTIONS OF STRUCTURE REMOVED, AS PER PLAN:

THIS ITEM SHALL BE USED AT LOCATIONS IN THE PLAN.

THE USE OF EXPLOSIVES, HEADACHE BALLS AND/OR HOE-RAMS WILL NOT BE PERMITTED.

THE EXISTING REINFORCING STEEL SHALL BE PRESERVED AS INDICATED IN THE PLANS. EXISTING CONCRETE SHALL BE REMOVED IN A MANNER THAT WILL NOT CUT, ELONGATE, OR DAMAGE THE EXISTING REINFORCING STEEL TO BE PRESERVED. CHIPPING HAMMERS SHALL NOT BE HEAVIER THAN THE NOMINAL 90 POUND CLASS. PNEUMATIC HAMMERS SHALL NOT BE PLACED IN DIRECT CONTACT WITH REINFORCING STEEL THAT IS TO BE PRESERVED.

ANY AREA LEFT OPEN ON THE DECK, BACKWALL OR APPROACH SLAB SHALL BE PLATED.

REPLACE ALL EXISTING REINFORCING STEEL BARS WHICH ARE TO BE INCORPORATED INTO THE NEW WORK AND ARE DEEMED BY THE ENGINEER TO BE MADE UNUSABLE BY CONCRETE REMOVAL OPERATIONS WITH NEW EPOXY COATED REINFORCING STEEL OF THE SAME SIZE AT NO COST TO THE DEPARTMENT.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR THE ABOVE ITEM, WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 202 - BRIDGE RAILING REMOVED, AS PER PLAN:

THIS ITEM SHALL BE USED AT LOCATIONS IN THE PLAN.

THE BRIDGE RAILING SHALL BE REMOVED. THE EXISTING DEEP BEAM RAIL, TS 8 X 4 TUBING SHALL BE STORED FOR REUSE. THE STEEL POSTS AND HARDWARE SHALL BECOME THE PROPERTY OF THE CONTRACTOR.

THE CONTRACTOR SHALL ONLY REMOVE AS MUCH RAILING AS HE CAN REPLACE IN THE SAME DAY.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER FOOT FOR THE ABOVE ITEM, WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 516 - ELASTOMERIC COMPRESSION SEAL, AS PER PLAN:

COMPRESSION SEAL: FURNISH MATERIAL CONFORMING TO 705.11. THE SEAL CONFIGURATION SHOULD BE SIMILAR TO THE DETAILS SHOWN HEREIN. ACCEPTED MANUFACTURERS ARE: WATSON-BOWMAN-ACME (MODEL WG-400) OR AN APPROVED EQUIVALENT. INSTALL THE SEAL ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS AND UNDER THE SUPERVISION OF THE MANUFACTURER'S DESIGNATED REPRESENTATIVE.

JOINTS IN COMPRESSION SEALS: FURNISH SEALS IN ONE CONTINUOUS PIECE UNLESS OTHERWISE APPROVED BY THE ENGINEER.

ITEM SPECIAL - PATCHING CONCRETE BRIDGE DECK OVERLAY WITH MICRO-SILICA MODIFIED CONCRETE:

SEE PROPOSAL NOTE 511 "PATCHING CONCRETE BRIDGE DECK OVERLAYS WITH MICRO-SILICA MODIFIED CONCRETE" FOR DETAILS.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID FOR THE ABOVE ITEM WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 511 - CLASS C CONCRETE, ABUTMENT, AS PER PLAN (REPAIR):

ITEM 511 - CLASS S CONCRETE, MISC.: RAISED MEDIAN REPAIR:

ITEM 511 - CLASS S CONCRETE, SUPERSTRUCTURE, AS PER PLAN (REPAIR):

THESE ITEMS SHALL BE USED AT LOCATIONS INDICATED IN THE PLAN.

THE COARSE AGGREGATE SHALL BE #8 LIMESTONE.

TYPE A WATERPROOFING IS INCIDENTAL.

ALL EXISTING SURFACES TO WHICH THE CONCRETE IS TO BOND SHALL BE CLEANED BY ABRASIVE BLASTING. THESE SURFACES SHALL BE MADE FREE OF SPALLS, LAITANCE AND OTHER CONTAMINANTS DETRIMENTAL TO ACHIEVING AN ADEQUATE BOND.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CUBIC YARD FOR EACH OF THE ABOVE WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

DESIGN FILE: \projects\23809\Struct\strnote.dgn
WORKSTATION: yaryanh DATE: 11/23/2011
MODELNAME: Design

DESIGN AGENCY
ODOT DISTRICT THREE
OFFICE OF
PLANNING AND ENGINEERING

DATE
11/11
REVIEWED
DJV
STRUCTURE FILE NUMBER

DRAWN
DCM
REVISED

DESIGNED
DCM
CHECKED
CAL

STRUCTURE NOTES

LOR-20-8.56

ITEM 517 - RAILING (DEEP BEAM RETROFIT RAILING):

THIS ITEM SHALL BE USED AT LOCATIONS IN THE PLAN.

THE RETROFIT SHALL BE AS PER STANDARD DRAWING DBR-3-11 AND THE DETAILS AND NOTES IN THE PLAN.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER FOOT FOR THE ABOVE ITEM, WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 517 - RAILING (DEEP BEAM RAIL WITH STEEL TUBULAR BACKUP AND TYPE 2 STEEL POSTS), AS PER PLAN:

THIS ITEM SHALL BE USED AT LOCATIONS IN THE PLAN.

THE BRIDGE RAILING SHALL BE INSTALLED USING THE EXISTING DEEP BEAM RAIL, TS 8 X 4 TUBING WITH NEW TYPE 2 POST AND HARDWARE ON THE EXISTING ANCHORS AS DETAILED IN THE PLAN.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER FOOT FOR THE ABOVE ITEM, WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 516 - VERTICAL EXTENSION OF STRUCTURAL EXPANSION JOINT, AS PER PLAN:

THIS ITEM SHALL BE USED AT LOCATIONS IN THE PLAN. THE VERTICAL EXTENSION OF THE STRUCTURAL EXPANSION JOINT SHALL BE AS DETAILED IN THE PLAN.


PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER FOOT FOR THE ABOVE ITEM, WHICH WILL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 519 - PATCHING CONCRETE STRUCTURES, AS PER PLAN:


PRIOR TO THE SURFACE CLEANING SPECIFIED IN 519.04 AND WITHIN 24 HOURS OF PLACING PATCHING MATERIAL, BLAST CLEAN ALL SURFACES TO BE PATCHED INCLUDING THE EXPOSED REINFORCING STEEL. ACCEPTABLE METHODS INCLUDE HIGH-PRESSURE WATER BLASTING WITH OR WITHOUT ABRASIVES IN THE WATER, ABRASIVE BLASTING WITH CONTAINMENT, OR VACUUM ABRASIVE BLASTING

DESIGN FILE:\projects\23809\Struct\strnote.dgn
WORKSTATION:hyar.yanh DATE:11/23/2011
MODELNAME: Design

DESIGN AGENCY ODOT DISTRICT THREE OFFICE OF PLANNING AND ENGINEERING	
DATE 11/11	STRUCTURE FILE NUMBER
REVIEWED DJV	
DRAWN DCM	REVISED
DESIGNED DCM	CHECKED CAL
STRUCTURE NOTES	
LOR-20-8.56	
/	
45 68	



PLAN VIEW



RAISED MEDIAN REPAIR DETAIL
 221'-6"± MEDIAN REPAIR

ITEM	QUANTITY	UNIT	DESCRIPTION
202	7	CU YD	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN
202	120	FT	REMOVAL MISC.: ELASTOMERIC COMPRESSION SEAL GLAND
511	7	CU YD	CLASS S CONCRETE, MISC.: RAISED MEDIAN REPAIR
512	1750	SQ YD	SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN
516	219	FT	ELASTOMERIC COMPRESSION SEAL, AS PER PLAN
516	118	FT	JOINT SEALER
SPECIAL	17	SQ YD	PATCHING CONCRETE BRIDGE DECK OVERLAY WITH MICRO-SILICA MODIFIED CONCRETE



ALL QUANTITIES CARRIED TO STRUCTURE SUMMARY SHEET

DESIGN FILE: \projects\23809\Struct\LOR-20-1303.dgn
 WORKSTATION: yaryanh DATE: 11/23/2011
 MODEL NAME: Design

2020
 D03 - BH FY2021 (A)
 210121 PID - 100077
 Dist 3 2/25/2021

Contract Proposal available @
 www.contracts.dot.state.oh.us

I:\ProjectData\100077\Design\Roadway\Sheets\100077_G1001.dgn



STATE OF OHIO
 DEPARTMENT OF TRANSPORTATION

D03-BH-FY2021(A)

CARLISLE TOWNSHIP
 EATON TOWNSHIP
 LORAIN COUNTY

PROJECT DESCRIPTION

THIS PROJECT INVOLVES THE REHABILITATION OF SEVERAL STRUCTURES THROUGHOUT DISTRICT THREE BY MEANS OF RESETTING BEARINGS, CONCRETE PATCHING, DECK & PARAPET SEALING, AND VARIOUS OTHER REHABILITATIVE MEASURES.

EARTH DISTURBED AREAS

PROJECT EARTH DISTURBED AREA: N/A - MAINTENANCE PROJECT
 ESTIMATED CONTRACTOR EARTH DISTURBED AREA: N/A - MAINTENANCE PROJECT
 NOTICE OF INTENT EARTH DISTURBED AREA: N/A - MAINTENANCE PROJECT

DESIGN DESIGNATIONS

CURRENT ADT (2023)	33,000	26,000	26,500	32,000
DESIGN YEAR ADT (2043)	42,000	30,000	35,500	34,500
DESIGN HOURLY VOLUME	4,200	3,600	4,600	4,100
DIRECTIONAL DISTRIBUTION	52%	50%	53%	100%
TRUCKS (24 HOUR B&C)	16%	10%	7%	20%
DESIGN & LEGAL SPEED (MPH)	65	65	65	65
NHS PROJECT	YES	YES	YES	YES

DESIGN FUNCTIONAL CLASSIFICATIONS:
 LOR-10-0.00 --- FREEWAYS AND EXPRESSWAYS
 LOR-20-13.02 --- FREEWAYS AND EXPRESSWAYS
 LOR-20-15.33 --- FREEWAYS AND EXPRESSWAYS
 LOR-20-15.86 --- FREEWAYS AND EXPRESSWAYS

DESIGN EXCEPTIONS

NONE


UNDERGROUND UTILITIES
 Contact Two Working Days Before You Dig

OHIO811, 8-1-1, or 1-800-362-2764
 (Non-members must be called directly)

INDEX OF SHEETS:

TITLE SHEET	1
GENERAL NOTES	2
MAINTENANCE OF TRAFFIC	3 - 4
GENERAL SUMMARY	5
STRUCTURE DETAILS	
LOR-301-1241	6
LOR-20-1533R	7
LOR-10-0010L	8
LOR-20-1587R	9

ENGINEERS SEAL:



SIGNED: Nicholas R Foster
 DATE: 11/19/2020

STANDARD CONSTRUCTION DRAWINGS				SUPPLEMENTAL SPECIFICATIONS		SPECIAL PROVISIONS	
DM-4.3	1/15/16	MT-105.10	1/17/20	800	1/15/21		
DM-4.4	1/15/16			821	4/20/12		
		TC-41.20	10/18/13	830	7/19/19		
MT-95.30	7/19/19	TC-42.20	10/18/13	832	10/19/18		
MT-95.31	7/19/19	TC-52.10	10/18/13	921	4/20/12		
MT-95.32	4/19/19	TC-52.20	7/20/18				
MT-95.40	1/17/20						
MT-95.50	7/21/17						
MT-97.10	4/19/19						
MT-98.10	1/17/20						
MT-98.11	1/17/20						
MT-98.20	4/19/19						
MT-98.22	1/17/20						
MT-101.70	1/17/20						
MT-101.75	1/17/20						
MT-101.90	7/17/20						

PLANS PREPARED BY:



2019 SPECIFICATIONS


THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS AND CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS OF THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE ASS SET FORTH ON THE PLANS AND ESTIMATES.


APPROVED:
 DATE: 1/16/2021 ROBERT WEAVER, PE, PS
 DISTRICT DEPUTY DIRECTOR

APPROVED: _____
 DATE: _____ JACK MARCHBANKS, PhD, DIRECTOR
 DEPARTMENT OF TRANSPORTATION


FEDERAL PROJECT NO. E190634
 PID NO. 100077
 CONSTRUCTION PROJECT NO. _____
 RAILROAD INVOLVEMENT NONE
 D03-BH-FY2021(A)
 19



PLAN VIEW
STRUCTURE LOR-301-1241
CARRYING SR 301 OVER US 20



FORWARD ABUTMENT ELEVATION
BEAMS, JOINT SEAL, AND DECK NOT SHOWN FOR CLARITY



HALF ELEVATION PIER 2
FOOTING, BEARINGS, & BEAMS NOT SHOWN FOR CLARITY
(SYMMETRIC ABOUT CENTERLINE)

NOTES

ITEM 519 - PATCHING CONCRETE STRUCTURE
PATCHING CONCRETE STRUCTURE WORK AT THE FORWARD ABUTMENT SHALL BE COMPLETED WHEN THE STRUCTURE IS TEMPORARILY SUPPORTED FOR THE BEARING RESET DUE TO THE PROXIMITY OF THE PATCHES TO THE BEARINGS. THE EXISTING REINFORCING STEEL LOCATED WITHIN THE AREAS AFFECTED BY THESE ITEMS IS TO REMAIN IN PLACE AT ALL TIMES. TAKE CARE WHEN PERFORMING THIS WORK TO NOT DAMAGE THE EXISTING REINFORCING STEEL. SHOULD ANY REINFORCING STEEL BE DAMAGED IN THE COURSE OF COMPLETING THIS WORK, REPAIR OR REPLACE THE DAMAGED REINFORCING STEEL AT THE DIRECTION AND TO THE SATISFACTION OF THE ENGINEER. REPLACE ANY REINFORCING STEEL FOUND TO NOT BE SALVAGEABLE DUE TO EXTENSIVE CORROSION OR PREEXISTING DAMAGE AT THE DIRECTION AND TO THE SATISFACTION OF THE ENGINEER. COAT ANY NEW AND ALL EXPOSED REINFORCING STEEL WITH AN APPROVED EPOXY MATERIAL AND ALLOW A FULL CURE OF THE EPOXY PRIOR TO PLACING ANY CONCRETE OVER THE STEEL. ALL LISTED WORK SHALL BE CONSIDERED INCIDENTAL TO THE ABOVE LISTED ITEMS IN THEIR RESPECTIVE WORK AREAS AS SHOWN ON THIS SHEET.

DO NOT BLOCK WEEP HOLES IN THE EXISTING ABUTMENT FACE AT ANY TIME. MAINTAIN THE FLOWABILITY OF THE EXISTING WEEP HOLES.

ESTIMATED QUANTITIES

ITEM	QUANTITY	UNIT	DESCRIPTION
202	150	FT	REMOVAL MISC.: ELASTOMERIC COMPRESSION SEAL GLAND
512	62.8	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)
512	1652	SY	TREATING OF CONCRETE BRIDGE DECK WITH SRS
516	150	FT	PREFORMED ELASTOMERIC COMPRESSION JOINT SEAL
516	LUMP		JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE
516	2	EACH	RESET BEARING, AS PER PLAN
519	24.7	SY	PATCHING CONCRETE BRIDGE DECK OVERLAY WITH MICRO-SILICA MODIFIED CONCRETE
519	25	SF	PATCHING CONCRETE STRUCTURE

ALL QUANTITIES CARRIED TO GENERAL SUMMARY

DESIGN AGENCY: ODOT DISTRICT THREE OFFICE OF ENGINEERING
 DATE: 10/2020
 REVIEWED: KCK
 STRUCTURE FILE NUMBER: 4706609
 DRAWN: NRF
 CHECKED: KAK
 DESIGNED: NRF
 STRUCTURE DETAILS: STRUCTURE LOR-301-1241 (LOR-20-1303) CARRYING SR 301 OVER US 20
 D03-BH-FY2021(A)
 PID No. 100077
 1/1