

$$\text{LOR/MED-18/301-(0.00)(1.69)/8.189}$$

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/20/2026 TIME: 9:42:04 AM PLTDRY: OHDOT_PDF.pltcrfg PENTBL: OHDOT_Pen.tbl USER: Adam.Mellen@dot.ohio.gov WORKSPACE: OHDOTCEv02 WORKSET: 124016 PRODUCT: OpenRoadsDesigner 24.00.00.2005
 www\ohiodot-pw.bentley.com\ohiodot-pw\02\Documents\01 Active Projects\District 03\Lorain\124016\400-Engineering\Roadway\Sheets\124016_GG0001.dgn

SHEET NUMBER							PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
5	6	7	9	10			01/NHS	02/STR						
													ROADWAY	
1								1	623	39501	1	EACH	MONUMENT ASSEMBLY ADJUSTED TO GRADE, AS PER PLAN	5
1								1	623	39601	1	EACH	MONUMENT ASSEMBLY RECONSTRUCTED TO GRADE, AS PER PLAN	5
LS								LS	623	51000	LS		POST CONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
													EROSION CONTROL	
							1,000	500	832	30000	1,500	EACH	EROSION CONTROL	
													DRAINAGE	
8							8		611	98630	8	EACH	CATCH BASIN ADJUSTED TO GRADE	
2							2		611	99150	2	EACH	INLET ADJUSTED TO GRADE	
													PAVEMENT	
	336						240	96	251	01043	336	CY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE), AS PER PLAN (LONGITUDINAL)	6
	84						60	24	251	01043	84	CY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE), AS PER PLAN (TRANSVERSE)	6
	34						24	10	253	02001	34	CY	PAVEMENT REPAIR, AS PER PLAN (LONGITUDINAL)	6
	8						6	2	253	02001	8	CY	PAVEMENT REPAIR, AS PER PLAN (TRANSVERSE)	6
			122,856				95,235	27,621	421	10000	122,856	SY	MICROSURFACING, SURFACE COURSE (FR)	
			122,856				95,235	27,621	421	10020	122,856	SY	MICROSURFACING, LEVELING COURSE	
			10.74				10.74		618	41000	10.74	MILE	RUMBLE STRIPES, EDGE LINE (ASPHALT CONCRETE)	
			5.37				5.37		618	43000	5.37	MILE	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	
			6,304				6,304		SPECIAL	69098300	6,304	SY	MALTENE BASED LONGITUDINAL JOINT STABILIZER	6A
			918				651	267	897	01010	918	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A (TAPER 0" TO 0.5")	
			12				8	4	897	02000	12	SY	PATCHING PLANED SURFACE	
													TRAFFIC CONTROL	
				491			356	135	621	00100	491	EACH	RPM	
				485			353	132	621	54000	485	EACH	RAISED PAVEMENT MARKER REMOVED	
				15.04			11.04	4	642	00104	15.04	MILE	EDGE LINE, 6" , TYPE 1	
				7.52			5.52	2	642	00300	7.52	MILE	CENTER LINE, TYPE 1	
				15.04			11.04	4	642	30030	15.04	MILE	REMOVAL OF PAVEMENT MARKING (EDGE LINE)	
				7.52			5.52	2	642	30030	7.52	MILE	REMOVAL OF PAVEMENT MARKING (CENTER LINE)	
				318			203	115	644	00500	318	FT	STOP LINE	
				2			2		644	01000	2	EACH	RAILROAD SYMBOL MARKING	
				318			203	115	644	30000	318	FT	REMOVAL OF PAVEMENT MARKING (STOP LINE)	
				2			2		644	30020	2	EACH	REMOVAL OF PAVEMENT MARKING (RAILROAD SYMBOL MARKING)	
													MAINTENANCE OF TRAFFIC	
		58					36	22	614	12460	58	EACH	WORK ZONE MARKING SIGN	
		6					4	2	614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	7
			22.56				16.56	6	614	21550	22.56	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
			954				609	345	614	26610	954	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
			6				6		614	32210	6	EACH	WORK ZONE RAILROAD SYMBOL MARKING, CLASS III, 642 PAINT	
													INCIDENTALS	
							LS	LS	614	11000	LS		MAINTAINING TRAFFIC	
							LS	LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
							LS	LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY	
DISTRICT 3	
	
ENGINEERING TEAM ONE	
DESIGNER	
SMH	
REVIEWER	
ACM 01-30-26	
PROJECT ID	
124016	
SHEET	TOTAL
P.8	10

LOR/MED-18/301-(0.00)/(1.69)/8.189

[illegible]