SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	6									01/NFA/PV								
																		ROADWAY	
		592									592			202	23500	592	SY	WEARING COURSE REMOVED	
12,300											12,300			SPECIAL	20301890	12,300	SY	SOIL STERILANT	3
		4									4			209	60501	4	MILE	LINEAR GRADING, AS PER PLAN	3
																		DRAINAGE	
1											1			611	98630	1	EACH	CATCH BASIN ADJUSTED TO GRADE	
1											1			611	98634	1	EACH	CATCH BASIN RECONSTRUCTED TO GRADE	
2											2			611	99654	2	EACH	MANHOLE ADJUSTED TO GRADE	
2											2			611	99660	2	EACH	MANHOLE RECONSTRUCTED TO GRADE	
1											1			623	39500	1	EACH	MONUMENT BOX ADJUSTED TO GRADE	
18											18			638	10800	18	EACH	VALVE BOX ADJUSTED TO GRADE	
																		PAVEMENT	
840											840			253	01000	840	SY	PAVEMENT REPAIR	
		2,260									2,260			407	20000	2,260	GAL	NON-TRACKING TACK COAT	
100		739									839			424	12001	839	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, AS PER PLAN	3
		808									808			875	10000	808	LB	LONGITUDINAL JOINT ADHESIVE	
																		TRAFFIC CONTROL	
		1.85									1.85			642	00104	1.85	MILE	EDGE LINE, 6", TYPE 1	
		0.89									0.89			642	00300	0.89	MILE	CENTER LINE, TYPE 1	
		10									10			644	01630	10	EACH	BIKE LANE SYMBOL MARKING	
																		MAINTENANCE OF TRAFFIC	
	2										2			614	12460	2	EACH	WORK ZONE MARKING SIGN	
	0.96										0.96			614	21400	0.96	MILE	WORK ZONE CENTER LINE, CLASS II	
	2										2			614	12500	2	EACH	REPLACEMENT SIGN	
	5										5			614	12600	5	EACH	REPLACEMENT DRUM	
																		INCIDENTALS	
											LS			614	11000	LS		MAINTAINING TRAFFIC	
											LS			623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS			624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

MAUMEE BAY STATE PARK

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 5/11/2021 TIME: 1:47:24 PM USER: j2ems
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 02\Lucas\109330\400-Engineering\Roadway\Sheets\109330_GG001.dgn

DESIGN AGENCY

DESIGNER JWZ

REVIEWER JMF MM-DD-YY

PROJECT ID 109330

SHEET 5 TOTAL 16