


US-20 - McCord

E. FISHER

11-20-2019

ODOT

C. W. USDA



BS	HI	FS	Elev	PT ID
4.0958	104.0958	5.4039	98.6918	604
5.2271	103.9189	4.8524	99.0665	605
5.6590	104.7255	2.717	102.0085	606
4.8596	106.8682	6.2887	100.5795	815
6.5127	107.0922	5.0821	102.0101	606
2.6931	104.7032	5.6372	99.0660	605
4.6859	103.7519	5.0602	98.6917	604
5.1175	103.8092	1.3036	99.9953	100
5.2508	105.2462	4.3566	100.8895	TT1
4.4231	105.3126	4.0426	101.2701	601
4.0418	105.3119	3.9588	101.3531	602
4.1266	105.4797	7.0884	98.3914	603

> SHOT AS 1
> CP 605
> CP 606
> BM 815
> CP 601
> CP 602
> CP 603

BS	H±	FS	ELEV	PTID
7.2658	105,6572	4,0165	101.6406	600 c
4.1337	105,7743	4.9547	100,8197	TT2
4.3119	105,1316	5,1381	99.9934	100

> CP 101 AKA NGS MC 1799 AKA McCORD

> CP 100 (100.00)

OPUS SESSION : 1.197 m
POSSIBLY ADD: 0.36 m (FOR ADAPTER)

HOLD : 198.742 m or 652.039' us

ADJUSTED ELEVATION @ 100 TO 652.011' us
TO MATCH EXISTING MONUMENTATION

