

SHEET NUM.												PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.	
P.7	P.8	P.24	P.25	P.43	P.52	P.56	P.68				OFFICE CALCS	01/SAF/OT	EXT	TOTAL					
<b>ROADWAY</b>																			
LS						1,328					633	LS	201	11000	LS	CLEARING AND GRUBBING			
		6,937											202	23000	1,961	SY	PAVEMENT REMOVED		
						115					2,811		202	30000	6,937	SF	WALK REMOVED		
							1						202	58700	1	EACH	MANHOLE ABANDONED		
		95											95	35100	95	FT	PIPE REMOVED, 24" AND UNDER		
		10											10	58100	10	EACH	CATCH BASIN REMOVED		
	100												100	98200	100	FT	REMOVAL MISC.:CONDUIT	P.8	
120				263	328	74							785	203	10000	785	CY	EXCAVATION	
				92	26								118	203	20000	118	CY	EMBANKMENT	
						925					1,519		204	10000	2,444	SY	SUBGRADE COMPACTION		
				873	554								204	13000	1,427	CY	EXCAVATION OF SUBGRADE		
				873	554								204	30010	1,427	CY	GRANULAR MATERIAL, TYPE B		
2													2	45000	2	HOUR	PROOF ROLLING		
				2,142	1,326								204	50000	3,468	SY	GEOTEXTILE FABRIC		
		9,860											608	10000	9,860	SF	4" CONCRETE WALK		
		1,036											608	52000	1,036	SF	CURB RAMP		
1													1	623	12010	1	EACH	PRIMARY PROJECT CONTROL MONUMENT, TYPE B	
3		1											4	623	39500	4	EACH	MONUMENT BOX ADJUSTED TO GRADE	
1													1	623	40000	1	EACH	MONUMENT ASSEMBLY REMOVED AND RESET	
<b>EROSION CONTROL</b>																			
1													1	659	00100	1	EACH	SOIL ANALYSIS TEST	
185													185	659	00300	185	CY	TOPSOIL	
				1,110	549								1,659	659	00500	1,659	SY	SEEDING AND MULCHING, CLASS 1	
83													83	659	14000	83	SY	REPAIR SEEDING AND MULCHING	
83													83	659	15000	83	SY	INTER-SEEDING	
0.23													0.23	659	20000	0.23	TON	COMMERCIAL FERTILIZER	
0.34													0.34	659	31000	0.34	ACRE	LIME	
9													9	659	35000	9	MGAL	WATER	
				LS									LS	832	15000	LS		STORM WATER POLLUTION PREVENTION PLAN	
				LS									LS	832	15002	LS		STORM WATER POLLUTION PREVENTION INSPECTIONS	
				LS									LS	832	15010	LS		STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE	
				10,000									10,000	832	30000	10,000	EACH	EROSION CONTROL	
<b>DRAINAGE</b>																			
		2,408											2,408	605	11110	2,408	FT	6" SHALLOW PIPE UNDERDRAINS WITH GEOTEXTILE FABRIC	
	100												100	605	13300	100	FT	6" UNCLASSIFIED PIPE UNDERDRAINS	
	100												300	611	00510	300	FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	
		12											12	611	01101	12	FT	6" CONDUIT, TYPE C, AS PER PLAN	P.8
		467											467	611	04401	467	FT	12" CONDUIT, TYPE B, AS PER PLAN	P.8
													120	611	04601	120	FT	12" CONDUIT, TYPE C, AS PER PLAN	P.8
													15	611	05901	15	FT	15" CONDUIT, TYPE B, AS PER PLAN	P.8
													120	611	96601	120	FT	CONDUIT, BORED OR JACKED, AS PER PLAN, 12" TYPE B	P.8
	100												100	611	97400	100	FT	CONDUIT, MISC.:TYPE B, FOR DRAINAGE DISCHARGE CONTINUANCE	P.8
	100												100	611	97400	100	FT	CONDUIT, MISC.:TYPE C, FOR DRAINAGE DISCHARGE CONTINUANCE	P.8
	100												100	611	97400	100	FT	CONDUIT, MISC.:TYPE E, FOR DRAINAGE DISCHARGE CONTINUANCE	P.8
	100												100	611	97400	100	FT	CONDUIT, MISC.:TYPE F, FOR DRAINAGE DISCHARGE CONTINUANCE	P.8
		2											2	611	98150	2	EACH	CATCH BASIN, NO. 3	
		19											19	611	98180	19	EACH	CATCH BASIN, NO. 3A	
		3											3	611	98370	3	EACH	CATCH BASIN, NO. 6	
	3	5											8	611	98630	8	EACH	CATCH BASIN ADJUSTED TO GRADE	
		1											1	611	99574	1	EACH	MANHOLE, NO. 3	
		1											1	611	99580	1	EACH	MANHOLE, NO. 3 WITH 84" BASE I.D. AND 6" WEIR	
	4	20					12						36	611	99654	36	EACH	MANHOLE ADJUSTED TO GRADE	
	500	500											1,000	SPECIAL	61199820	1,000	LB	MISCELLANEOUS METAL	P.8
		1											1	895	10010	1	EACH	MANUFACTURED WATER QUALITY STRUCTURE, TYPE 1	

GENERAL SUMMARY

DESIGN AGENCY  
**ARCADIS**  
 1111 SUPERIOR AVENUE SUITE 1300  
 CLEVELAND, OHIO 44114  
 (216) 781-8177  
 www.arcadis.com

DESIGNER  
**TB**

REVIEWER  
**BRO 01/08/20**

PROJECT ID  
**110495**

SHEET TOTAL  
 P.18 | 103