

**LOCATION MAP**  
NOT TO SCALE

# STATE OF OHIO DEPARTMENT OF TRANSPORTATION

## LUC/OTT SIGN FY2025

### LUCAS & OTTAWA COUNTY

### SYSTEMATIC EXTRUSHEET SIGN REPLACEMENT

**INDEX OF SHEETS:**

TITLE SHEET	1
GENERAL NOTES	2-3
MAINTENANCE OF TRAFFIC NOTES	4-6
GENERAL SUMMARY	7-8
SIGNING SUMMARY-GROUND MOUNTED	9-14
SIGNING SUMMARY-CANTILEVER MOUNTED	15
SIGNING SUMMARY-TRUSS MOUNTED	16
GUARDRAIL SUMMARY	17
SIGNING PLAN SHEETS	18-55
TRAFFIC ELEVATION VIEW SHEETS	56-88

**FEDERAL PROJECT NUMBER**

NON-FEDERAL

**RAILROAD INVOLVEMENT**

NONE

**PROJECT DESCRIPTION**

THIS PROJECT WILL REPLACE ALL EXTRUSHEET SIGNS IN OTTAWA COUNTY AND REMOVE OVERHEAD SIGNS ON IR 475 IN LUCAS COUNTY.

**EARTH DISTURBED AREAS**

PROJECT EARTH DISTURBED AREA:	N/A ACRES
ESTIMATED CONTRACTOR EARTH DISTURBED AREA:	N/A ACRES
NOTICE OF INTENT EARTH DISTURBED AREA:	N/A ACRES

**2023 SPECIFICATIONS**

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS, CHANGES LISTED IN THE PROPOSAL, AND THE SUPPLEMENTAL SPECIFICATION 800 VERSION INDICATED ON THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.

*Pat McColley, PE*  
 Pat McColley, P.E., S.I.  
 District 02 Deputy Director

*Jack Marchbanks, PhD*  
 Jack Marchbanks, PhD  
 Director, Department of Transportation

**DESIGN EXCEPTIONS**

NONE REQUIRED

**ADA DESIGN WAIVERS**

NONE REQUIRED

<b>UNDERGROUND UTILITIES</b>
Contact Two Working Days Before You Dig
OHIO811, 8-1-1, or 1-800-362-2764 (Non members must be called directly)

PLAN PREPARED BY:  
OHIO DEPT. OF TRANSPORTATION  
DISTRICT 2  
BOWLING GREEN, OHIO

STANDARD CONSTRUCTION DRAWINGS								SUPPLEMENTAL SPECIFICATIONS	SPECIAL PROVISIONS
MGS-1.1	7/16/21	MT-98.11	1/17/20	TC-9.11	1/19/24	TC-51.12	1/15/16	800	1/19/24
MGS-2.1	1/19/18	MT-98.20	4/19/19	TC-9.31	7/21/23	TC-52.10	10/18/13	832	7/15/22
MGS-4.2	7/19/13	MT-98.21	7/21/23	TC-12.31	4/15/22	TC-52.20	1/15/21		
MGS-4.3	1/18/13	MT-98.22	1/17/20	TC-15.116	1/19/24	TC-61.30	7/19/19		
MGS-5.2	7/15/16	MT-98.28	1/17/20	TC-16.22	7/21/23				
MGS-5.3	7/15/16	MT-98.29	1/17/20	TC-21.11	7/16/21				
		MT-98.30	7/16/21	TC-21.21	1/20/23				
MT-95.30	7/19/19	MT-99.60	1/19/24	TC-21.50	4/17/20				
MT-95.40	7/21/23	MT-101.70	4/21/23	TC-22.20	1/17/14				
MT-95.41	7/21/23	MT-101.75	7/21/23	TC-41.10	7/19/13				
MT-95.45	7/21/23	MT-101.80	1/17/20	TC-41.20	10/18/13				
MT-95.50	7/21/17	MT-105.10	1/17/20	TC-41.30	4/21/23				
MT-95.61	4/19/19			TC-41.40	10/18/13				
MT-97.10	4/19/19	RM-4.4	7/21/23	TC-42.10	10/18/23				
MT-97.20	4/19/19			TC-42.20	10/18/23				
MT-98.10	1/17/20			TC-51.11	1/15/16				

**ENGINEER'S SEAL**  
TRAFFIC CONTROL


TITLE SHEET

DESIGN AGENCY	
DESIGNER	ZAP
REVIEWER	CDW
DATE	11/03/23
PROJECT ID	114413
SHEET	1
TOTAL	88



SHEET NUM.				PART.	ALT	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
14	15	16	17	01/NFP/21	(X)						
										<b>TRAFFIC CONTROL (CONTINUED)</b>	
102	8			110		630	86102	110	EACH	REMOVAL OF GROUND MOUNTED STRUCTURAL BEAM SUPPORT AND DISPOSAL	
2	7	23		32		630	87400	32	EACH	REMOVAL OF OVERHEAD MOUNTED SIGN AND DISPOSAL	
1	2	6		9		630	89702	9	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL	
2	2	4		8		630	97700	8	EACH	SIGNING, MISC.:SIGN SUPPORT ASSEMBLY, POLE MOUNTED	2
210.5				210.5		630	97900	210.5	FT	SIGNING, MISC.:4"X6" WOOD POST, AS PER PLAN	2
210.5				210.5		630	97900	210.5	FT	SIGNING, MISC.:4"X6" WOOD POST, AS PER PLAN	2
779.1				779.1		630	97900	779.1	FT	SIGNING, MISC.:6"x8" WOOD POST, AS PER PLAN	2
	1			1		631	94250	1	EACH	REMOVAL OF LUMINAIRE	
	1			1		631	94406	1	EACH	REMOVAL OF SIGNS WIRED	
	1			1		631	94450	1	EACH	REMOVAL OF BALLAST	
	1			1		631	97700	1	EACH	SIGN LIGHTING MISC.: REMOVAL OF SIGN SERVICE AND DISPOSAL, AS PER PLAN	2
										<b>ROADWAY</b>	
		180		180		202	30700	180	FT	CONCRETE BARRIER REMOVED	
			125	125		202	38000	125	FT	GUARDRAIL REMOVED	
			9	9		202	42206	9	EACH	ANCHOR ASSEMBLY REMOVED	
			0.414	0.414		209	15050	0.41	MILE	RESHAPING UNDER GUARDRAIL	
			1650	1650		606	15050	1,650	FT	GUARDRAIL, TYPE MGS	
			8	8		606	26150	8	EACH	ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016	
			4	4		606	26550	4	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
		180		180		622	10060	180	FT	CONCRETE BARRIER, SINGLE SLOPE, TYPE B	
			24	24		626	00116	24	EACH	BARRIER REFLECTOR, TYPE 5, BIDIRECTIONAL	
			107.84	107.84		659	00300	107.84	CY	TOPSOIL	
			971.52	971.52		659	10000	971.52	SY	SEEDING AND MULCHING	
			48.58	48.58		659	14000	48.58	SY	REPAIR SEEDING AND MULCHING	
			48.58	48.58		659	15000	48.58	SY	INTER-SEEDING	
			0.13	0.13		659	20000	0.13	TON	COMMERCIAL FERTILIZER	
			5.25	5.25		659	35000	5.25	MGAL	WATER	
										<b>INCIDENTALS</b>	
				LS		614	11000	LS		MAINTAINING TRAFFIC	
				200		614	11111	200	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE, AS PER PLAN	6
				4		614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6
				LS		623	10001	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	3
				LS		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY  
  
 DESIGNER  
 ZAP  
 REVIEWER  
 CDW 11/03/23  
 PROJECT ID  
 114413  
 SHEET TOTAL  
 8 | 88

