

F:\Jobs\1006 - MAD-62\102577_MAD-62-2.79\Design\Roadway\Sheets\102577_G0002.dgn 11/19/2020 2:25:28 PM LBaker

SHEET NUM.										PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
6	6A				42	43				01/STR/BR		EXT	TOTAL			
STRUCTURE OVER 20 FOOT SPAN (MAD-62-2.79, SFN 4902131)																
						LS				LS	202	11003	LS		STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	42
						84				84	202	22900	84	SY	APPROACH SLAB REMOVED	
						875				875	202	23500	875	SY	WEARING COURSE REMOVED	
						LS				LS	503	11100	LS		COFFERDAMS AND EXCAVATION BRACING	
						LS				LS	503	21300	LS		UNCLASSIFIED EXCAVATION	
						LS				LS	505	11100	LS		PILE DRIVING EQUIPMENT MOBILIZATION	
						800				800	507	00500	800	FT	12" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN	
						960				960	507	00550	960	FT	12" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED	
						1,080				1,080	507	00700	1,080	FT	16" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN	
						1,200				1,200	507	00750	1,200	FT	16" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED	
						105,854				105,854	509	10000	105,854	LB	EPOXY COATED REINFORCING STEEL	
						301				301	511	21522	301	CY	CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE	
						73				73	511	33418	73	CY	CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE	
						174				174	511	40512	174	CY	CLASS QC1 CONCRETE WITH QC/QA, PIER ABOVE FOOTINGS	
						145				145	511	43512	145	CY	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING	
						88				88	511	46510	88	CY	CLASS QC1 CONCRETE, FOOTING	
						950				950	512	10050	950	SY	SEALING OF CONCRETE SURFACES (NON-EPOXY)	
						31				31	512	10300	31	SY	SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN	
						12				12	515	15080	12	EACH	DRAPED STRAND PRESTRESSED CONCRETE BRIDGE I-BEAM MEMBERS, LEVEL 3, TYPE WF42-49, L=93'-8"	
						27				27	515	20000	27	EACH	INTERMEDIATE DIAPHRAGMS	
						131				131	516	13200	131	SF	1/2" PREFORMED EXPANSION JOINT FILLER	
						242				242	516	13600	242	SF	1" PREFORMED EXPANSION JOINT FILLER	
						93				93	516	14014	93	FT	INTEGRAL ABUTMENT EXPANSION JOINT SEAL	
						24				24	516	44101	24	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) 2.88" X 14" X 20" WITH 15" X 21" LOAD PLATE, AS PER PLAN	54
						579				579	517	70000	579	FT	RAILING (TWIN STEEL TUBE)	
						86				86	518	21200	86	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	
						706				706	SPECIAL	51822300	706	FT	STEEL DRIP STRIP	
						115				115	518	40000	115	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	
						53				53	518	40010	53	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	
						2				2	523	20000	2	EACH	DYNAMIC LOAD TESTING	
						4				4	523	20500	4	EACH	RESTRIKE	
						178				178	526	25000	178	SY	REINFORCED CONCRETE APPROACH SLABS (T=15")	
						69				69	526	90010	69	FT	TYPE A INSTALLATION	
						645				645	601	32110	645	CY	ROCK CHANNEL PROTECTION, TYPE B WITH AGGREGATE FILTER	
					LS					LS	SPECIAL	69071000	LS		ASBESTOS ABATEMENT (MAD-62-2.79 STRUCTURE)	42
						530				530	407	20000	530	GAL	MAINTENANCE OF TRAFFIC NON-TRACKING TACK COAT	
						260				260	441	50000	260	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
	16					16				16	614	11110	16	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
						LS				LS	614	12420	LS		DETOUR SIGNING	
						41				41	614	13000	41	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
	7					7				7	616	10000	7	MGAL	WATER	
						150				150	617	10100	150	CY	COMPACTED AGGREGATE	
						2				2	617	25000	2	MGAL	WATER	
						2.12				2.12	642	00300	2.12	MILE	CENTER LINE, TYPE 1	
						LS				LS	103	05000	LS		INCIDENTALS	
						LS				LS	614	11000	LS		PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYMENT BOND	
						9				9	619	16010	9	MNTH	MAINTAINING TRAFFIC	
						LS				LS	623	10000	LS		FIELD OFFICE, TYPE B	
						LS				LS	624	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
															MOBILIZATION	

CALCULATED COM CHECKED DTB	GENERAL SUMMARY	MAD-62-2.79
-------------------------------------	-----------------	-------------

F:\Jobs\1006 - MAD-62-102577_MAD-62-2.79\Design\Structures\MAD062_0279C_Sheets\062_0279C_S0001.dgn 11/19/2020 1:59:36 PM L.Baker

ESTIMATED QUANTITIES									
CALC BY: <u>AJM</u>					CHK'D BY: <u>MMP</u>				
ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	ABUTMENTS	PIERS	SUPER-STRUCTURE	GENERAL	AS PER PLAN SHEET NUMBERS
202	11003	LUMP		STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN				LUMP	2
202	22900	84	SY	APPROACH SLAB REMOVED				84	
202	23500	875	SY	WEARING COURSE REMOVED			875		
503	11100	LUMP		COFFERDAMS AND EXCAVATION BRACING				LUMP	
503	21300	LUMP		UNCLASSIFIED EXCAVATION	267 CY *	247 CY *			
505	11100	LUMP		PILE DRIVING EQUIPMENT MOBILIZATION				LUMP	
507	00500	800	FT	12" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN	800				
507	00550	960	FT	12" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED	960				
507	00700	1080	FT	16" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN		1080			
507	00750	1200	FT	16" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED		1200			
509	10000	105,854	POUND	EPOXY COATED REINFORCING STEEL	9,967	19,051	76,848		
511	21522	301	CY	CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE			301		
511	33418	73	CY	CLASS QC2 CONCRETE WITH QC/QA, SUPERSTRUCTURE			73		
511	40512	174	CY	CLASS QC1 CONCRETE WITH QC/QA, PIER ABOVE FOOTING		174			
511	43512	145	CY	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING	145				
511	46510	88	CY	CLASS QC1 CONCRETE, FOOTING		88			
512	10050	950	SY	SEALING CONCRETE SURFACES (NON-EPOXY)	34	260	656		
512	10300	31	SY	SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN			31		
515	15080	12	EACH	DRAPED STRAND PRESTRESSED CONCRETE BRIDGE I-BEAM MEMBERS, LEVEL 3, TYPE WF42-49, L=93'-8"			12		
515	20000	27	EACH	INTERMEDIATE DIAPHRAGMS			27		
516	13200	131	SF	1/2" PREFORMED EXPANSION JOINT FILLER	131				
516	13600	242	SF	1" PREFORMED EXPANSION JOINT FILLER	242				
516	14014	93	FT	INTEGRAL ABUTMENT EXPANSION JOINT SEAL			93		
516	44101	24	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) 2.88" X 14" X 20" WITH 15" X 21" LOAD PLATE, AS PER PLAN	8	16			14
517	70000	579	FT	RAILING (TWIN STEEL TUBE)			579		
518	21200	86	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC				86	
SPECIAL	51822300	706	FT	STEEL DRIP STRIP			706		
518	40000	115	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	115				
518	40010	53	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	53				
523	20000	2	EACH	DYNAMIC LOAD TESTING				2	
523	20500	4	EACH	RESTRIKE				4	
526	25000	178	SY	REINFORCED CONCRETE APPROACH SLABS (T=15')				178	
526	90010	69	FT	TYPE A INSTALLATION				69	
601	32110	645	CY	ROCK CHANNEL PROTECTION, TYPE B WITH AGGREGATE FILTER				645	
SPECIAL	69071000	LUMP		ASBESTOS ABATEMENT				LUMP	

* UNCLASSIFIED EXCAVATION QUANTITIES ARE INCLUDED FOR INFORMATIONAL PURPOSES ONLY.

ESTIMATED QUANTITIES
MAD-62-02.79 BRIDGE
OVER DEER CREEK

MAD-62-2.79
PID No. 102577

3 / 16

43
66

DESIGN AGENCY
EUTHEMICS INC.
CONSULTING ENGINEERS

DESIGNED
LAB
CHECKED
AJM

DRAWN
VMB
REVISED
MMP

REVIEWED
RAB
STRUCTURE FILE NUMBER
4902131

DATE
06/20/19