

**ITEM 622 - PORTABLE BARRIER, 50', AS PER PLAN**

THIS WORK SHALL CONSIST OF FURNISHING, MAINTAINING, AND SUBSEQUENTLY REMOVING A 50-INCH PORTABLE BARRIER AT THE LOCATIONS SHOWN ON THE PLANS. FOR DETAILS SEE, SCD RM-4.1.

PORTABLE STEEL BARRIER IS AN APPROVED ALTERNATIVE TO PORTABLE CONCRETE BARRIER. FOR INFORMATION ON APPROVED VENDORS, SEE THE APPROVED PRODUCTS LIST MAINTAINED BY THE OFFICE OF ROADWAY ENGINEERING.

PORTABLE BARRIER, 32 INCHES HIGH WITH AN 18-INCH MINIMUM HEIGHT GLARE SCREEN MAY BE USED AT THE OPTION OF THE CONTRACTOR. THE GLARE SCREEN SHALL BE CONSTRUCTED USING ONE OF THE SCREENS PROVIDED ON THE APPROVED LIST, AVAILABLE ON THE OFFICE OF ROADWAY ENGINEERING WEBSITE.

PADDLE OR INTERMITTENT TYPE GLARE SCREENS SHALL BE DESIGNED USING A 20 DEGREE CUT-OFF ANGLE BASED ON TANGENT ALIGNMENT. THAT SPACING SHALL BE USED THROUGHOUT THE BARRIER LENGTH WITHOUT REGARD TO BARRIER CURVATURE.

THE GLARE SCREEN SYSTEM SHALL BE SECURELY FASTENED TO THE 32-INCH PORTABLE BARRIER USING THE HARDWARE AND PROCEDURES SPECIFIED BY THE MANUFACTURER.

FOR DIRECTIONS ON HOW TO INSTALL THE GLARE SCREEN AND THE BARRIER, SEE THE MANUFACTURER'S INSTRUCTIONS.

PAYMENT SHALL INCLUDE ALL LABOR, MATERIAL, AND EQUIPMENT NECESSARY TO PERFORM THE WORK AND SHALL BE PAID FOR AT THE CONTRACT PRICE PER FOOT FOR ITEM 622, PORTABLE BARRIER, 50", AS PER PLAN.

**WORK ZONE EGRESS WARNING SYSTEM**

THE CONTRACTOR SHALL FURNISH, INSTALL, AND MAINTAIN AN APPROVED WORK ZONE EGRESS WARNING SYSTEM (WZEWS) AS PER SUPPLEMENTAL SPECIFICATION 829.

THE PROBABLE INITIAL LOCATIONS OF THE WZEWS DEVICES ARE SHOWN ON P. 19-20 OF THE PLAN. IT IS EXPECTED THAT THESE LOCATIONS WILL VARY BASED ON PLANNED OR UNPLANNED PHASE AND TRAFFIC PATTERN CHANGES. PLACEMENT, OPERATION, AND MAINTENANCE AND ALL ACTIVATION OF THE DEVICES BY THE CONTRACTOR SHALL BE DIRECTED BY THE ENGINEER.

WZEWS SHALL BE USED IN ACCORDANCE WITH MT-103.10. THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 829, WORK ZONE EGRESS WARNING SYSTEM 40 SIGN MONTH ASSUMING 4 WORK ZONE EGRESS WARING SYSTEM(S) FOR 10 MONTH(S).

**SEQUENCE OF CONSTRUCTION**

PRE-PHASE 1:

PRIOR TO THE START OF PHASE 1, THE SOUTHTHBOUND OUTSIDE SHOULDER AND PORTIONS OF THE SOUTHBOUND INSIDE SHOULDERS MUST BE RECONSTRUCTED IN ORDER TO CARRY SHIFTED PHASE 1 AND PHASE 2 TRAFFIC.

ANY PRE-PHASE 1 WORK THAT IMPACTS TRAVEL LANES SHALL BE COMPLETED BY UTILIZING NIGHTTIME LANE CLOSURES PER ODOT SCD MT-95.30. THE LANE CLOSURES MAY ONLY BE IMPLEMENTED DURING HOURS ALLOWED AS LISTED IN THIS PLAN.

PHASE 1:

SHIFT SOUTHBOUND LANES ONTO OUTSIDE SHOULDER AND OUTSIDE LANE MATCHING THE PART 1 PLANS.

I-71 NORTHBOUND SHALL REMAIN IN EXISTING CONFIGURATION.

CONSTRUCT PROPOSED AREA OF SOUTHBOUND I-71 ALONG WITH TEMPORARY PAVEMENT REQUIRED FOR PHASE 2 SHIFTED TRAFFIC AS SHOWN IN THE PLANS.

WINTER 2023:

TRAFFIC SHALL BE SHIFTED INTO PHASE 2 CONFIGURATION BY OCTOBER 1, 2023 WHICH SHALL CONSTITUTE AN INTERIM COMPLETION DATE. TO PROVIDE ADDITIONAL SPACE FOR MOTORIST DURING THE WINTER, THE PHASE 2 PORTABLE BARRIER SHALL NOT BE SET IN THE FOLLOWING LOCATIONS UNTIL APRIL 1, 2024 UNLESS APPROVED BY THE ENGINEER:

STA. 425+00 TO STA. 444+85

IN LEUI OF PORTABLE BARRIER IN THESE LOCATIONS, DRUMS SHALL BE PLACED ALONG THE EDGE OF TRAVEL WAY. TEMPORARY IMPACT ATTENUATORS SHALL BE USED TO PROTECT THE ENDS OF THE PORTABLE BARRIER. THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY AS PAYMENT FOR THIS WORK:

ITEM 614 - WORK ZONE IMPACT ATTENUATOR, 24" WIDE - 1 EA

WORK ON PHASE 2 MAY CONTINUE IN AREAS ADEQUATELY PROTECTED BY PORTABLE BARRIER.

EMERGENCY PULL-OFF SHOWN IN THE PLANS SHALL REMAIN OPEN OVER THE WINTER. ADDITIONALLY, A TEMPORARY PULL-OFF SHALL BE CREATED USING EXISTING PAVEMENT ON THE WEST SIDE OF THE SOUTHBOUND LANES AT STA. 425+00 TO 438+20 PER THE DETAILS SHOWN ON SHEET P.20A. THE LOCATION OF THE TEMPORARY PULL-OFF MAY BE ADJUSTED AT THE DIRECTION OF THE ENGINEER. THE COSTS FOR ALL SIGNING, MATERIALS, AND EQUIPMENT NECESSARY TO PLACE THE TEMPORARY PULL-OFF SHALL BE INCLUDED IN THE LUMP SUM BID FOR ITEM 614 - MAINTAINING TRAFFIC.

PHASE 2:

SHIFT I-71 SOUTHBOUND LANES ONTO COMPLETED INSIDE LANE AND SHOULDER OF SOUTHBOUND I-71 CONSTRUCTED DURING PHASE 1 MATCHING PART 1 PLANS.

DYER ROAD SHALL BE CLOSED TO TRAFFIC AND DETOURED AS SHOWN IN THE PLANS FOR THE DURATION OF PHASES 1 AND 2.

I-71 NORTHBOUND SHALL REMAIN IN EXISTING CONFIGURATION.

CONSTRUCT PROPOSED AREA OF I-71 SOUTHBOUND AS SHOWN IN THE PLANS.

WINTER 2024:

THE PROJECT SHALL ENTER A WINTERIZATION PHASE BY OCTOBER 1, 2024 WHICH SHALL CONSTITUTE AN INTERIM COMPLETION DATE. NORTHBOUND TRAFFIC SHALL REMAIN IN EXISTING CONFIGURATION. SOUTHBOUND TRAFFIC SHALL BE RECONFIGURED TO THE PROPOSED THREE LANE CONFIGURATION. NORTHBOUND RAMPS SHALL REMAIN IN EXISTING CONFIGURATION. SOUTHBOUND RAMPS SHALL BE OPENED IN FINAL CONFIGURATION.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY IN ORDER TO COMPLETE THIS WORK:

ITEM 614 - WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN - 264 EACH  
ITEM 648 - EDGE LINE, WHITE, 6" - 3.00 MILES  
ITEM 648 - EDGE LINE, YELLOW, 6" - 3.00 MILES  
ITEM 648 - LANE LINE, 6" - 6.00 MILES

PRE-PHASE 3:

PRIOR TO THE START OF PHASE 3, THE NORTHBOUND MEDIAN CROSSOVERS AND NORTHBOUND INSIDE SHOULDER RECONSTRUCTION MUST BE COMPLETE IF NOT PREVIOUSLY COMPLETED.

ANY PRE-PHASE 3 WORK THAT IMPACTS TRAVEL LANES SHALL BE COMPLETED BY UTILIZING NIGHTTIME LANE CLOSURES PER ODOT SCD MT-95.30. THE LANE CLOSURES MAY ONLY BE IMPLEMENTED DURING HOURS ALLOWED AS LISTED IN THIS PLAN.

PHASE 3:

I-71 SOUTHBOUND LANES SHALL BE SHIFTED ONTO THE OUTSIDE SHOULDER AND LANE MATCHING PART 1 PLANS.

CROSSOVER EXISTING I-71 NORTHBOUND LANES ONTO NEWLY CONSTRUCTED I-71 SOUTHBOUND INSIDE SHOULDER AND LANES.

DYER ROAD SHALL BE CLOSED TO TRAFFIC AND DETOURED AS SHOWN IN THE PLANS FOR THE DURATION OF PHASE 3.

CONSTRUCT PROPOSED AREAS OF I-71 NORTHBOUND AS SHOWN IN THE PLANS.

WINTER 2025:

THE PROJECT SHALL ENTER A WINTERIZATION PHASE BY OCTOBER 1, 2025 WHICH SHALL CONSTITUTE AN INTERIM COMPLETION DATE. ALL TRAFFIC SHALL BE OPENED IN FINAL CONFIGURATION AND MAINTAINED ON INTERMEDIATE COURSE. PAVEMENT MARKINGS SHALL BE PLACED IN THEIR FINAL LOCATIONS PER THE TRAFFIC CONTROL PLAN.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY IN ORDER TO COMPLETE THIS WORK:

ITEM 614 - WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN - 536 EACH  
ITEM 648 - EDGE LINE, WHITE, 6" - 6.10 MILES  
ITEM 648 - EDGE LINE, YELLOW, 6" - 6.10 MILES  
ITEM 648 - LANE LINE, 6" - 12.20 MILES

SHOULD WORK DELAY AND FULL COMPLETION OF PHASE 3 WORK FOR PART 1 AND PART 2 NOT BE ACHIEVABLE, THE CONTRACTOR MAY IMPLEMENT A CROSSOVER NEAR THE SOUTHERN LIMIT OF PART 1 AT THE APPROVAL OF THE ENGINEER. THE CROSSOVER WILL RETURN NORTHBOUND TRAFFIC FROM PHASE 3 TO THE COMPLETED NORTHBOUND PAVEMENT. SEE PART 1 FOR DETAILS.

PHASE 4:

AT THE CONCLUSION OF THE 2025 WINTER PHASE, COMPLETE ANY REMAINING FULL DEPTH RECONSTRUCTION WORK. THE REMAINING EXISTING I-71 PAVEMENT THAT IS TO BE RESURFACED (OUTSIDE THE FULL DEPTH LIMITS) SHALL BE MILLED TO THE DEPTH SPECIFIED IN THE PLANS. THE FINAL WEARING COURSE OF BOTH NEWLY CONSTRUCTED AND EXISTING MILLED PAVEMENTS SHALL THEN BE INSTALLED. ONCE COMPLETED, FINAL PAVEMENT MARKINGS SHALL BE APPLIED PER THE TRAFFIC CONTROL PLANS. THIS WORK SHALL BE COMPLETED BY UTILIZING ODOT SCD MT-97.11. IN ADDITION TO THIS WORK, THE MEDIAN CABLE BARRIER SHALL BE INSTALLED PER THE ROADWAY PLANS AND TEMPORARY PAVEMENT SHALL BE REMOVED BY UTILIZING ODOT SCD MT-95.45 EXCEPT DRUMS MAY BE USED IN THE PLACE OF PCB AS LONG AS DROP-OFF REQUIREMENTS ARE MET (PER ODOT SCD MT-101.90).

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY IN ORDER TO COMPLETE THIS WORK:

ITEM 614 - WORK ZONE EDGE LINE, WHITE, 6", CLASS III, 642 PAINT - 6.10 MILES  
ITEM 614 - WORK ZONE EDGE LINE, YELLOW, 6", CLASS III, 642 PAINT - 6.10 MILES  
ITEM 614 - WORK ZONE LANE LINE, 6" , CLASS III, 642 PAINT - 12.20 MILES

OVERHEAD STRUCTURE CONSTRUCTION:

OVERHEAD BRIDGE CONSTRUCTION SHALL OCCUR AT ANY TIME DURING THE PROJECT. SIDE ROADS SHALL BE CLOSED AND DETOURED AS SHOWN IN THE PLANS. THE CONTRACTOR SHALL COORDINATE MAINTENANCE OF TRAFFIC NEEDS ALONG I-71 WITH THE RESPECTIVE PHASE OF I-71 MAINTENANCE OF TRAFFIC.

DESIGN AGENCY



E.L. ROBINSON ENGINEERING  
1466 West 9th St, Suite 800  
Cleveland, Ohio  
950 Goodale Blvd, Suite 180  
Grandview Heights, Ohio

DESIGNER  
TDP

REVIEWER  
MJC 04/26/22

PROJECT ID  
107630

SHEET TOTAL  
P.14 458

SHEET NUM.									PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
287	312	313						08/IMS/11	09/IMS/10							
<b>STRUCTURE OVER 20 FOOT SPAN (MAD-71-0631R) CONT.</b>																
153								105	48	516	13600	153	SF	1" PREFORMED EXPANSION JOINT FILLER		
392								267	125	518	21200	392	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC		
362								247	115	518	40000	362	FT	6" PERFORATED CORRUGATED PLASTIC PIPE		
68								47	21	611	70001	68	FT	CONDUIT, TYPE A, PRECAST REINFORCED CONCRETE THREE SIDED FLAT TOPPED CULVERT, AS PER PLAN (33'-4" SPAN X 10'-0" RISE)	285	
4								3	1	623	38501	4	EACH	MONUMENT ASSEMBLY, TYPE C, AS PER PLAN	286	
<b>STRUCTURE OVER 20 FOOT SPAN (MAD-71-0668L)</b>																
LS								LS	LS	202	11203	LS		PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	310, 314, 315, 317-320	
247								168	79	202	22900	247	SY	APPROACH SLAB REMOVED		
LS								LS	LS	503	11101	LS		COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN	310, 317	
624								425	199	503	21100	624	CY	UNCLASSIFIED EXCAVATION		
1,337								910	427	504	11101	1,337	SF	STEEL SHEET PILING LEFT IN PLACE, AS PER PLAN	317	
LS								LS	LS	505	11100	LS		PILE DRIVING EQUIPMENT MOBILIZATION		
3,100								2,108	992	507	00200	3,100	FT	STEEL PILES HP12X53, FURNISHED		
2,780								1,891	889	507	00250	2,780	FT	STEEL PILES HP12X53, DRIVEN		
112,592								76,563	36,029	509	10000	112,592	LB	EPOXY COATED STEEL REINFORCEMENT		
38,262								26,019	12,243	509	10001	38,262	LB	EPOXY COATED STEEL REINFORCEMENT, AS PER PLAN	331, 344	
6,711								4,564	2,147	509	30020	6,711	FT	NO. 4 DEFORMED GFRP REINFORCEMENT		
335								228	107	511	34446	335	CY	CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK		
66								45	21	511	34451	66	CY	CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET), AS PER PLAN	353	
159								109	50	511	40513	159	CY	CLASS QC1 CONCRETE WITH QC/QA, PIER ABOVE FOOTINGS, AS PER PLAN	331	
140								96	44	511	43512	140	CY	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING		
134								92	42	511	46512	134	CY	CLASS QC1 CONCRETE WITH QC/QA, FOOTING		
1,090								742	348	512	10100	1,090	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)		
30								21	9	512	33000	30	SY	TYPE 2 WATERPROOFING		
222,000								150,960	71,040	513	10241	222,000	LB	STRUCTURAL STEEL MEMBERS, LEVEL 2, AS PER PLAN	345	
4,120								4,120	1,958	513	20000	4,120	EACH	WELDED STUD SHEAR CONNECTORS		
970								660	310	514	00061	970	SF	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, AS PER PLAN	338	
970								660	310	514	00067	970	SF	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS PER PLAN	338	
114								78	36	516	10010	114	FT	ARMORLESS PREFORMED JOINT SEAL		
100								68	32	516	13200	100	SF	1/2" PREFORMED EXPANSION JOINT FILLER		
117								80	37	516	13600	117	SF	1" PREFORMED EXPANSION JOINT FILLER		
45								31	14	516	13900	45	SF	2" PREFORMED EXPANSION JOINT FILLER		
138								94	44	516	14014	138	FT	INTEGRAL ABUTMENT EXPANSION JOINT SEAL		
16								11	5	516	44100	16	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (11.5"x17"x2.049")		
16								11	5	516	44101	16	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), AS PER PLAN (10"x14"x2.499" W/LOAD PLATE ASSEMBLY)	335	
10								7	3	518	12301	10	EACH	SCUPPERS, INCLUDING SUPPORTS, AS PER PLAN	344, 345	
117								80	37	518	21200	117	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC		
164								112	52	518	40000	164	FT	6" PERFORATED CORRUGATED PLASTIC PIPE		
80								55	25	518	40011	80	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS, AS PER PLAN	324, 328	
2								2		523	20000	2	EACH	DYNAMIC LOAD TESTING		
330								225	105	526	25011	330	SY	REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=15"), AS PER PLAN	353	
114								78	36	526	90031	114	FT	TYPE C INSTALLATION, AS PER PLAN	353	
283								193	90	601	32100	283	CY	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER		
<b>STRUCTURE OVER 20 FOOT SPAN (MAD-71-0668R)</b>																
LS								LS	LS	202	11203	LS		PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	310, 314, 315, 317-320	
247								168	79	202	22900	247	SY	APPROACH SLAB REMOVED		
LS								LS	LS	503	11101	LS		COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN	310, 317	
633								431	202	503	21100	633	CY	UNCLASSIFIED EXCAVATION		
LS								LS	LS	505	11100	LS		PILE DRIVING EQUIPMENT MOBILIZATION		
3,100								2,108	992	507	00200	3,100	FT	STEEL PILES HP12X53, FURNISHED		
2,780								1,891	889	507	00250	2,780	FT	STEEL PILES HP12X53, DRIVEN		
140,733								95,699	45,034	509	10000	140,733	LB	EPOXY COATED STEEL REINFORCEMENT		
9,592								6,523	3,069	509	10001	9,592	LB	EPOXY COATED STEEL REINFORCEMENT, AS PER PLAN	333	
6,711								4,564	2,147	509	30020	6,711	FT	NO. 4 DEFORMED GFRP REINFORCEMENT		

GENERAL SUMMARY

DESIGN AGENCY  
  
**E.L. ROBINSON**  
 ENGINEERING  
 1466 West 9th St, Suite 800  
 Cleveland, Ohio  
 959 Goodale Blvd, Suite 180  
 Grandview Heights, Ohio

DESIGNER  
**KRF**

REVIEWER  
**MJC 04/26/22**

PROJECT ID  
**107630**

SHEET TOTAL  
**P.59 458**

SHEET NUM.								PART.				ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
9	10	11	12	13	14	23	313	06/IMS/04	07/IMS/03	08/IMS/11	09/IMS/10						
<b>STRUCTURE OVER 20 FOOT SPAN (MAD-71-0668R) CONT.</b>																	
							335			228	107	511	34446	335	CY	CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK	
							66			45	21	511	34451	66	CY	CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET), AS PER PLAN	353
							159			109	50	511	40513	159	CY	CLASS QC1 CONCRETE WITH QC/QA, PIER ABOVE FOOTINGS, AS PER PLAN	333
							140			96	44	511	43512	140	CY	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING	
							134			92	42	511	46512	134	CY	CLASS QC1 CONCRETE WITH QC/QA, FOOTING	
							1,090			742	348	512	10100	1,090	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
							20			14	6	512	33000	20	SY	TYPE 2 WATERPROOFING	
							222,000			150,960	71,040	513	10241	222,000	LB	STRUCTURAL STEEL MEMBERS, LEVEL 2, AS PER PLAN	345
							6,120			4,162	1,958	513	20000	6,120	EACH	WELDED STUD SHEAR CONNECTORS	
							970			660	310	514	00061	970	SF	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, AS PER PLAN	338
							970			660	310	514	00067	970	SF	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS PER PLAN	338
							114			78	36	516	10010	114	FT	ARMORLESS PREFORMED JOINT SEAL	
							100			68	32	516	13200	100	SF	1/2" PREFORMED EXPANSION JOINT FILLER	
							117			80	37	516	13600	117	SF	1" PREFORMED EXPANSION JOINT FILLER	
							45			31	14	516	13900	45	SF	2" PREFORMED EXPANSION JOINT FILLER	
							138			94	44	516	14014	138	FT	INTEGRAL ABUTMENT EXPANSION JOINT SEAL	
							16			11	5	516	44100	16	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (11.5"x17"x2.049" W/LOAD PLATE)	
							16			11	5	516	44101	16	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), AS PER PLAN (10"x14"x2.499" W/LOAD PLATE ASSEMBLY)	335
							117			80	37	518	21200	117	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	
							164			112	52	518	40000	164	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	
							50			34	16	518	40011	50	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS, AS PER PLAN	326, 330
							330			225	105	526	25011	330	SY	REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=15"), AS PER PLAN	353
							114			78	36	526	90031	114	FT	TYPE C INSTALLATION, AS PER PLAN	353
							283			193	90	601	32100	283	CY	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER	
<b>MAINTENANCE OF TRAFFIC</b>																	
							1,238			842	396	411	10000	1,238	CY	STABILIZED CRUSHED AGGREGATE	
				750			510			240		614	11110	750	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
			500				340			160		614	11630	500	FT	INCREASED BARRIER DELINEATION	
							275			88		SPECIAL	61412200	275	FT	WORK ZONE GUARDRAIL	13
					1	1	2					614	12380	2	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)	
							LS	LS				614	12420	LS		DETOUR SIGNING	
	21						15	6				614	12484	21	EACH	WORK ZONE INCREASED PENALTIES SIGN	
							4	1				614	12500	5	EACH	REPLACEMENT SIGN	
		5					102	48				614	12600	150	EACH	REPLACEMENT DRUM	
		150					1					614	12756	1	EACH	WORK ZONE CROSSOVER LIGHTING SYSTEM	
							1,491	701				614	12801	2,192	EACH	WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN	11
			1,392			800	842	396				614	13310	1,238	EACH	BARRIER REFLECTOR, TYPE 1, (ONE WAY)	
							36	16				614	13312	52	EACH	BARRIER REFLECTOR, TYPE 2, (ONE WAY)	
							447	209				614	13350	656	EACH	OBJECT MARKER, ONE WAY	
							214	100				614	13360	314	EACH	OBJECT MARKER, TWO WAY	
							49	23				614	18601	72	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	11
							72					614	22056	24.4	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 807 PAINT	
						24.4	17	7.4				614	20066	11.3	MILE	WORK ZONE LANE LINE, CLASS I, 6", 807 PAINT	
						11.3	8	3.3				614	20560	12.2	MILE	WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT	
						12.2	9	3.2				614	22360	12.2	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
						12.2	9	3.2				614	23410	4,412	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 12", 807 PAINT	
						4,412	2,797	1,315				614	24102	1,115	FT	WORK ZONE DOTTED LINE, CLASS I, 6", 807 PAINT	
						1,115	759	356				614	32658	15	EACH	WORK ZONE SPEED MEASUREMENT MARKING, CLASS I, 642 PAINT	
							11	4				615	10000	LS		ROADS FOR MAINTAINING TRAFFIC	
							11,892	8,087	3,805			615	20000	11,892	SY	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A	
							19,617	13,340	6,277			615	20001	19,617	SY	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A, AS PER PLAN	9
							254	173	81			616	10000	254	MGAL	WATER	
							12.1	9	3.1			618	41000	12.1	MILE	RUMBLE STRIPES, EDGE LINE (ASPHALT CONCRETE)	
							45,382	30,860	14,522			622	41011	45,382	FT	PORTABLE BARRIER, 50", AS PER PLAN	14
							607	413	194			622	41110	607	FT	PORTABLE BARRIER, ANCHORED	
							152	104	48			808	18700	152	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY	
						40	28	12				829	00100	40	SNMT	WORK ZONE EGRESS WARNING SYSTEM	
<b>INCIDENTALS</b>																	
	LS						LS	LS	LS	LS		614	11000	LS		MAINTAINING TRAFFIC	
							LS	LS	LS	LS		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
							LS	LS	LS	LS		624	10000	LS		MOBILIZATION	
							878					878	25000	LS		INSPECTION AND COMPACTION TESTING OF UNBOUND MATERIALS	

GENERAL SUMMARY

DESIGN AGENCY  
  
**E.L. ROBINSON**  
 ENGINEERING  
 1466 West 9th St, Suite 800  
 Cleveland, Ohio  
 950 Goodale Blvd, Suite 150  
 Grandview Heights, Ohio

DESIGNER  
**KRF**

REVIEWER  
**MJC 04/26/22**

PROJECT ID  
**107630**

SHEET TOTAL  
**P.60 458**

MADE BY: DTA/GA		DATE: 10/6/2022		ESTIMATED QUANTITIES - LEFT BRIDGE						STRUCTURAL FILE NUMBER: 4903332			
CHECKED BY: BCW/MRV		DATE: 10/6/2022		ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIER	SUPER.	GEN.	REFERENCE SHEET NO.
202	11203	LUMP						PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN				LUMP	4, 8, 9, 11, 12, 13, AND 14 OF 52
202	22900	247	SY					APPROACH SLAB REMOVED				247	
503	11101	LUMP						COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN				LUMP	4 AND 11 OF 52
503	21100	624	CY					UNCLASSIFIED EXCAVATION	187	437			
504	11101	1,337	SF					STEEL SHEET PILING LEFT IN PLACE, AS PER PLAN (ELASTIC SECTION MODULUS = 18.1 CU IN/FT)				1,337	11 OF 52
505	11100	LUMP						PILE DRIVING EQUIPMENT MOBILIZATION				LUMP	
507	00200	3,100	FT					STEEL PILES HP12X53, FURNISHED	900	2,200			
507	00250	2,780	FT					STEEL PILES HP12X53, DRIVEN	800	1,980			
509	10000	112,592	LB					EPOXY COATED REINFORCING STEEL	14,934	28,336	69,322		
509	10001	38,262	LB					EPOXY COATED REINFORCING STEEL, AS PER PLAN		9,592	28,670		25 AND 38 OF 52
509	30020	6,711	FT					NO. 4 GFRP DEFORMED BARS			6,711		
511	34446	335	CY					CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK			335		
511	34451	66	CY					CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET), AS PER PLAN			66		47 OF 52
511	40513	159	CY					CLASS QC1 CONCRETE WITH QC/QA, PIER ABOVE FOOTINGS, AS PER PLAN		159			25 OF 52
511	43512	140	CY					CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING	140				
511	46512	134	CY					CLASS QC1 CONCRETE WITH QC/QA, FOOTING		134			
512	10100	1,090	SY					SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	86	501	409	94	
512	33000	30	SY					TYPE 2 WATERPROOFING	30				
513	10241	222,000	LB					STRUCTURAL STEEL MEMBERS, LEVEL 2, AS PER PLAN			222,000		39 OF 52
513	20000	6,120	EACH					WELDED STUD SHEAR CONNECTORS			6,120		
514	00061	970	SF					FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, AS PER PLAN			970		32 OF 52
514	00067	970	SF					FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS PER PLAN			970		32 OF 52
516	10010	114	FT					ARMORLESS PREFORMED JOINT SEAL				114	
516	13200	100	SF					1/2" PREFORMED EXPANSION JOINT FILLER	100				
516	13600	117	SF					1" PREFORMED EXPANSION JOINT FILLER	100		17		
516	13900	45	SF					2" PREFORMED EXPANSION JOINT FILLER	45				
516	14014	138	FT					INTEGRAL ABUTMENT EXPANSION JOINT SEAL	138				
516	44100	16	EACH					ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (11.5"x17"x2.049")		16			
516	44101	16	EACH					ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), AS PER PLAN (10"x14"x2.499" W/LOAD PLATE ASSEMBLY)	16				29 OF 52
518	12301	10	EACH					SCUPPERS, INCLUDING SUPPORTS, AS PER PLAN			10		38 AND 39 OF 52
518	21200	117	CY					POROUS BACKFILL WITH GEOTEXTILE FABRIC	117				
518	40000	164	FT					6" PERFORATED CORRUGATED PLASTIC PIPE	164				
518	40011	80	FT					6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS, AS PER PLAN	80				18 AND 22 OF 52
523	20000	2	EACH					DYNAMIC LOAD TESTING				2	
526	25011	330	SY					REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=15"), AS PER PLAN				330	47 OF 52
526	90031	114	FT					TYPE C INSTALLATION, AS PER PLAN				114	47 OF 52
601	32100	283	CY					ROCK CHANNEL PROTECTION, TYPE B WITH FILTER	283				

ESTIMATED QUANTITIES - LEFT BRIDGE  
 BRIDGE NO. MAD-00071-06.680L&R  
 IR 71 OVER BRADFORD CREEK

SFN	4903332
SFN	4903367
DESIGNER	GA
CHECKER	MRV
REVIEWER	DFT 04/05/22
PROJECT ID	107630
SUBSET	6
TOTAL	52
SHEET	P.312
TOTAL	458



MADE BY: DTA/GA		DATE: 10/6/2022		ESTIMATED QUANTITIES - RIGHT BRIDGE						STRUCTURAL FILE NUMBER: 4903367	
CHECKED BY: BCW/MRV		DATE: 10/6/2022									
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION			ABUT.	PIER	SUPER.	GEN.	REFERENCE SHEET NO.
202	11203	LUMP		PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN						LUMP	4, 8, 9, 11, 12, 13, AND 14 OF 52
202	22900	247	SY	APPROACH SLAB REMOVED						247	
503	11101	LUMP		COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN						LUMP	4 AND 11 OF 52
503	21100	633	CY	UNCLASSIFIED EXCAVATION			196	437			
505	11100	LUMP		PILE DRIVING EQUIPMENT MOBILIZATION						LUMP	
507	00200	3,100	FT	STEEL PILES HP12X53, FURNISHED			900	2,200			
507	00250	2,780	FT	STEEL PILES HP12X53, DRIVEN			800	1,980			
509	10000	140,733	LB	EPOXY COATED REINFORCING STEEL			14,924	28,078	97,731		
509	10001	9,592	LB	EPOXY COATED REINFORCING STEEL, AS PER PLAN				9,592			27 OF 52
509	30020	6,711	FT	NO. 4 GFRP DEFORMED BARS					6,711		
511	34446	335	CY	CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK					335		
511	34451	66	CY	CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET), AS PER PLAN					66		47 OF 52
511	40513	159	CY	CLASS QC1 CONCRETE WITH QC/QA, PIER ABOVE FOOTINGS, AS PER PLAN				159			27 OF 52
511	43512	140	CY	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING			140				
511	46512	134	CY	CLASS QC1 CONCRETE WITH QC/QA, FOOTING				134			
512	10100	1,090	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)			86	501	409	94	
512	33000	20	SY	TYPE 2 WATERPROOFING			20				
513	10241	222,000	LB	STRUCTURAL STEEL MEMBERS, LEVEL 2, AS PER PLAN					222,000		39 OF 52
513	20000	6,120	EACH	WELDED STUD SHEAR CONNECTORS					6,120		
514	00061	970	SF	FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT, AS PER PLAN					970		32 OF 52
514	00067	970	SF	FIELD PAINTING STRUCTURAL STEEL, FINISH COAT, AS PER PLAN					970		32 OF 52
516	10010	114	FT	ARMORLESS PREFORMED JOINT SEAL						114	
516	13200	100	SF	1/2" PREFORMED EXPANSION JOINT FILLER			100				
516	13600	117	SF	1" PREFORMED EXPANSION JOINT FILLER			100		17		
516	13900	45	SF	2" PREFORMED EXPANSION JOINT FILLER			45				
516	14014	138	FT	INTEGRAL ABUTMENT EXPANSION JOINT SEAL			138				
516	44100	16	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (11.5"x17"x2.049" W/LOAD PLATE)				16			
516	44101	16	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), AS PER PLAN (10"x14"x2.499" W/LOAD PLATE ASSEMBLY)			16				29 OF 52
518	21200	117	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC			117				
518	40000	164	FT	6" PERFORATED CORRUGATED PLASTIC PIPE			164				
518	40011	50	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS, AS PER PLAN			50				20 AND 24 OF 52
526	25011	330	SY	REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=15"), AS PER PLAN						330	47 OF 52
526	90031	114	FT	TYPE C INSTALLATION, AS PER PLAN						114	47 OF 52
601	32100	283	CY	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER			283				

ESTIMATED QUANTITIES - RIGHT BRIDGE  
 BRIDGE NO. MAD-00071-06.680L&R  
 IR 71 OVER BRADFORD CREEK

SFN 4903332  
 SFN 4903367  
 DESIGN AGENCY  
  
**E.L. ROBINSON**  
 ENGINEERING  
 1488 West 9th St, Suite 800  
 Cleveland, Ohio 44115  
 950 Goodale Blvd, Suite 160  
 Grandview Heights, Ohio 44131  
 DESIGNER CHECKER  
 GA MRV  
 REVIEWER  
 DFT 04/05/22  
 PROJECT ID  
 107630  
 SUBSET TOTAL  
 7 52  
 SHEET TOTAL  
 P.313 458