


Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245

---



**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

**Table of Contents**

I.	Executive Summary .....	1
II.	Background.....	1
III.	Purpose and Need.....	2
IV.	Study Area.....	2
V.	Analysis Years.....	5
VI.	Alternatives Considered.....	5
VII.	Existing Conditions .....	5
VIII.	Traffic Volumes .....	6
IX.	Traffic Analysis.....	6
X.	Cost Estimate.....	13
XI.	Environmental Impacts.....	15
XII.	Recommendations .....	16

**Figures**

Figure 1	Location Map
Figure 2	Opening Day Build Configuration
Figure 3	Design Year Build Configuration

**Tables**

Table 1	HCS Freeway Section LOS
Table 2	HCS Merge LOS
Table 3	HCS Diverge LOS
Table 4	HCS Intersection Levels of Service of SR 29 at the IR-70 WB Ramps
Table 5	HCS Intersection Levels of Service of SR 29 at the IR-70 EB Ramps
Table 6	Queue Lengths for Intersection of SR 29 at the IR-70 WB Ramps
Table 7	Queue Lengths for Intersection of SR 29 at the IR-70 EB Ramps
Table 8	Turn Lane Lengths for Ramp Intersections
Table 9	Phase 1 Cost Estimate
Table 10	Phase 2 Cost Estimate

**Appendices**

Appendix A	Certified Traffic
Appendix B	Opening Day and Design Year Figures
Appendix C	HCS Freeway Section Analyses
Appendix D	HCS Merge and Diverge Analyses
Appendix E	HCS Intersection Analyses
Appendix F	Sidra Intersection Analyses
Appendix G	Turn Lane Length Analyses

**Interchange Modification Study**  
**IR-70 at SR 29**  
**MAD-70-10.27**  
**PID 83245**

---

**I. Executive Summary:**

The goal of this study is to demonstrate the impacts to mainline IR-70 resulting from the needed improvements of the interchange at SR 29. Proposed commercial development on the SR 29 corridor will cause degradation to the SR 29 interchange ramp intersections. This project originated as a permit for site drive improvements along SR 29 and thus is privately funded by the developers who own property along the corridor. ODOT has participated thru a cooperative effort to identify the most economical solution for mitigation of the development traffic based upon the resulting traffic volumes.

In order to facilitate a timely response to the increased traffic using the interchange while considering the funds available, the Department has opted to build the project in two phases. Opening Day (Phase I) conditions will include construction of a single lane roundabout at the westbound ramp intersection, addition of a left turn lane on the eastbound off ramp and relocation of a local road intersection (Snyder Road) with SR 29. The final build condition will include construction of dual lane roundabouts at both ramp intersections and widening of the SR 29 structure over IR-70. Both build conditions are shown in Figures 2 and 3 in Appendix B.

**II. Background:**

The proposed project originated as an access permit application submitted to ODOT by the Village of West Jefferson to install a traffic signal and turn lane at the intersection of State Route 29 and Commerce Parkway. Two Traffic Impacts Studies were completed in 2007 by private developers owning 879 acres of land located on the south side of SR 29 with existing or planned warehouse and distribution facilities. In order to assess the impacts to State Route 29 and the adjacent Interstate 70 and State Route 29 interchange, ODOT requested these traffic studies be combined in order to fully evaluate the impacts to this interchange. The combined Traffic Impact Study included placeholder traffic to address traffic generated by an approximately 120 acre parcel on the north side of SR 29, adjacent to the interchange. Existing warehouse/logistics facilities currently exist within the proposed project area for Target Stores, Restoration Hardware, Fed Ex, Kellogg Company, Staples/Quill, BST, Inc. Electric U.S. Inc., Gramag and others. The TIS is available in electronic format upon request.

**Interchange Modification Study**  
**IR-70 at SR 29**  
**MAD-70-10.27**  
**PID 83245**

---

The Mid-Ohio Regional Planning Commission completed the 2030 Thoroughfare Plan for the Village of West Jefferson. This thoroughfare plans show that the land use around the interchange will be warehouse and distribution facilities. Traffic congestion will result from the development around the interchange and the vicinity of West Jefferson if nothing is done.

An agreement between ODOT and two private developers who own land along State Route 29 allocated \$3.5 million to mitigate the impacts of the increased traffic from the existing and proposed warehouse developments. This funding is set to expire in August of 2012. Therefore this project is being constructed in two phases. Phase I is fundable based upon the monies available from the developers and meets the traffic needs of opening day conditions.

### **III. Purpose and Need:**

The purpose of this project is to accommodate existing and future traffic demands generated by existing and committed development occurring near the Interstate 70 and State Route 29 interchange.

The project is needed because approximately 1,000 acres of land adjacent to the Interstate 70 and State Route 29 interchange have or will be developed into warehouse/distribution facilities. The resulting increase in traffic will result in a failing Level of Service at the ramp intersections if no improvements are built<sup>1</sup>.

### **IV. Study Area:**

SR 29 in Madison County crosses the county in a south-easterly direction and is classified as a major rural collector throughout. The route is a 2 lane facility which has a posted speed of 55 MPH and terminates at US 40 just southeast of the interchange at IR-70. The interchange is at milepost 10.27 of Interstate 70 and milepost 10.61 of SR 29 and lies just northwest of the Village of West Jefferson. SR 29 provides the main access into the Village of West Jefferson from the interstate and also services the growing industrial area that the Village has worked to grow.

---

<sup>1</sup> Text for Background and Purpose and Need provided by District 6, Environmental Section, Planning and Engineering

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

Included in the Study Area are the adjacent interchanges. They are US 142 to the east and US 42 to the west along IR-70. Refer to Figure 1.

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---



**Figure 1 – Location Map**

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

**V. Analysis Years:**

Opening Year for the project is 2010 with the Design Year established as 2030. The No Build condition for this study is defined as the existing diamond interchange which includes ramps that operate under stop control. The Opening Day build condition is presented in Figure 2 and consists of a single lane roundabout at the westbound ramps intersection and the addition of a left turn lane at the eastbound ramps. The Design Year Build condition is a two-lane roundabout at both ramp intersections, referred to as double roundabouts, and is presented in Figure 3. Construction of the Design Year Build Condition requires widening of the SR 29 structure over IR-70.

**VI. Alternatives Considered:**

The interchange solutions that were considered were a diamond interchange and the double roundabout interchange. Both options require a modification to the existing 2-lane bridge. The expanded diamond would have required the bridge to be widened for the opening day build condition as side by side left turn lanes are required on the structure. The projected cost of the diamond interchange is approximately \$10M. Conversely, the roundabout option allows for an affordable phased design which works with the existing 2-lane bridge, will mitigate the additional traffic for opening day operations and provide a long term solution when the traffic volumes necessitate. The roundabout will be based upon design speeds of 35 MPH and will be lit.

No other solutions were examined given the constraints of the cost of expanding the 2-lane bridge.

**VII. Existing Conditions:**

**a. Road Geometry & Access Locations**

SR 29 is a northwest - southeast roadway with a posted speed of 55 MPH. The facility is a 2-lane major collector highway originating in West Jefferson at US 40. The roadway connects to Mechanicsburg and other parts of western Ohio. Both ramp intersections are stop controlled.

**Interchange Modification Study**  
**IR-70 at SR 29**  
**MAD-70-10.27**  
**PID 83245**

---

IR-70 is a major east – west facility spanning the entire state. The speed limit on this section of interstate is 65 MPH. The interstate is a 6-lane principal arterial interstate.

**b. Crash Data**

Crash mitigation is not part of the purpose and need of this project. An examination of ODOT's Safety Hot Spots did not identify any areas of high crashes within the projects limits.

**c. Land Use**

The land use in the immediate study area is mostly warehousing space, especially to the south of the interchange. There are numerous existing and future developments which are in burgeoning states of development.

**d. Environmental Conditions**

The closest noteworthy environmental area is the Big Darby watershed. This project will not impact the boundary of the watershed.

**VIII. Traffic Volumes:**

Certified traffic was provided by the ODOT Office of Technical Services. As mentioned previously, the opening year for this traffic is 2010, and the design year is 2030. Refer to Appendix A for a copy of the certified traffic.

**IX. Traffic Analysis:**

Based upon Certified Traffic, Highway Capacity Software (HCS) was used to analyze the mainline IR-70 operations and the ramp intersection operations at the SR 29 interchange. The proposed roundabouts were analyzed utilizing Sidra Software.

**a. Freeway Section Analysis**

Five sections of IR-70 mainline were analyzed for the AM and PM peak hour volumes in both directions. The mainline sections were analyzed from US 42 to SR 142. The results of these analyses are summarized in Table 1. The traffic analyses were run for the Opening Day and Design Year demand volumes since phased improvements are proposed.



**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

Since the ramp intersections are currently operating under stop control there can be no existence of constrained traffic. Therefore the No Build and Build mainline traffic volumes are identical and are unaffected by the ramp intersection operations when comparing the mainline No Build Condition to the Build Condition. The mainline operations exhibit a Level of Service (LOS) of D at two locations in the Design Year. However, this section of the interstate has recently been improved thru an add lane project and consists of three lanes in each direction. To obtain a LOS of C would require tens of millions of dollars and would increase the cost and scope of this project beyond the current purpose and need.

**Table 1: HCS Freeway Section Levels of Service**

Location	AM		PM	
	2010	2030	2010	2030
EB IR-70 Middle of US 42 (#2)	A	B	B	B
EB IR-70 East of US 42 (#4)	B	B	B	C
EB IR-70 Middle of SR 29 (#6)	A	B	B	B
EB IR-70 East of SR 29 (#8)	B	B	B	C
EB IR-70 Middle of SR 142 (#10)	B	B	B	C
WB IR-70 Middle of SR 142 (#13)	A	B	C	D
WB IR-70 East of SR 29 (#15)	A	B	C	D
WB IR-70 Middle of SR 29 (#17)	A	A	B	C
WB IR-70 East of US 42 (#19)	A	A	C	C
EB IR-70 Middle of US 42 (#21)	A	A	B	C

Please refer to Appendix C for the Freeway Section HCS Analyses. The freeway operations will not be degraded with the recommended improvements on SR 29.

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

**b. Ramp Junction Analysis**

Merge and diverge analyses were conducted for all ramps associated with the SR 29, US 42, and SR 142 interchanges along IR-70. Please refer to Tables 2 and 3 for a summary of these analyses.

**Table 2: HCS Merge Levels of Service**

Location	AM		PM	
	2010	2030	2010	2030
EB IR-70 & US 42 (#3)	B	C	B	C
EB IR-70 & SR 29 (#7)	B	B	C	C
EB IR-70 & SR 142 (#11)	B	C	B	C
WB IR-70 & SR 142 (#14)	B	B	C	D
WB IR-70 & SR 29 (#18)	B	B	C	C
WB IR-70 & US 42 (#22)	B	B	B	C

**Table 3: HCS Diverge Levels of Service**

Location	AM		PM	
	2010	2030	2010	2030
EB IR-70 & US 42 (#1)	B	B	B	C
EB IR-70 & SR 29 (#5)	B	C	B	C
EB IR-70 & SR 142 (#9)	B	B	B	C
WB IR-70 & SR 142 (#12)	B	B	C	D
WB IR-70 & SR 29 (#16)	B	B	C	D
WB IR-70 & US 42 (#20)	B	B	C	D

Please refer to Appendix D for HCS Merge and Diverge Analyses.

**c. Ramp Intersection Analysis**

The intersections of the IR-70 Ramps at SR 29 were analyzed using HCS and Sidra software. These analyses are summarized in Tables 4 and 5.

The Opening Day build condition includes a single lane “expandable” roundabout at the IR-70 westbound ramp intersection and the addition of a right turn lane on the eastbound off ramp. As can be seen by the No Build intersection analyses, the westbound ramp exhibits the highest delay, thus it was selected as the critical intersection for applying mitigative measures.

**Interchange Modification Study**  
**IR-70 at SR 29**  
**MAD-70-10.27**  
**PID 83245**

---

The proposed IR-70 westbound ramp single lane roundabout will operate extremely well under the Opening Day traffic volumes. The eastbound IR-70 eastbound off ramp is improved over the no build condition for Opening Day traffic volumes and indicates marked improvement for the off ramp heavy right turning volumes.

The Design Year build condition includes dual lane roundabouts at both ramp intersections which will necessitate the expansion of the SR 29 Bridge. The Design Year build condition operates at acceptable or better levels of service.

Please refer to Appendix E and F for the HCS and Sidra Intersection Analyses, respectively.

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

**Table 4: HCS Intersection Levels of Service of SR 29 at the IR-70 WB Ramps**

Condition	WB IR-70 Off Ramp (LOS/Delay)			SR 29 (LOS/Delay)				Critical Approach or Total Intersection (LOS/Delay)
	WBL	WBT	WBR	NBL	NBT	SBT	SBR	
2010 AM No Build	F/160.1	F/160.1	F/160.1	A/8.5	A/8.5	N/A	N/A	F/160.1
2010 AM Build	B/14.8	B/14.8	N/A	A/5.2	A/5.2	C/22.9	C/22.9	C/15.2
2010 PM No Build	F/531.3	F/531.3	F/531.3	A/8.7	A/8.7	N/A	N/A	F/531.3
2010 PM Build	C/18.1	C/18.1	N/A	A/8.1	A/8.1	C/15.6	C/15.6	B/11.0
2030 AM No Build	F/748.1	F/748.1	F/748.1	A/8.8	A/8.8	N/A	N/A	F/748.1
2030 AM Build	C/27.8	C/27.8	N/A	A/4.1	A/4.1	B/14.0	B/13.7	B/18.9
2030 PM No Build	F/2950	F/2950	F/2950	A/9.7	A/9.7	N/A	N/A	F/2950
2030 PM Build	C/33.8	C/33.8	N/A	A/5.8	A/5.8	B/12.8	B/12.5	B/14.9

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

**Table 5: HCS Intersection Levels of Service of SR 29 at the IR-70 EB Ramps**

Condition	EB IR-70 Ramp (LOS/Delay)			SR 29 (LOS/Delay)				Critical Approach or Total Intersection (LOS/Delay)
	EBL	EBT	EBR	NBR	NBT	SBT	SBL	
2010 AM No Build	E/44.0	E/44.0	E/44.0	N/A	N/A	A/8.6	A/8.6	E/44.0
2010 AM Build	D/30.3	D/30.3	D/28.9	N/A	N/A	A/8.6	A/8.6	D/29.0
2010 PM No Build	D/27.4	D/27.4	D/27.4	N/A	N/A	B/11.9	B/11.9	D/27.4
2010 PM Build	E/42.7	E/42.7	C/16.4	N/A	N/A	B/11.9	B/11.9	C/18.5
2030 AM No Build	F/430.9	F/430.9	F/430.9	N/A	N/A	A/9.5	A/9.5	F/430.9
2030 AM Build	A/7.6	A/7.6	C/34.5	A/7.0	A/5.9	A/8.2	A/8.2	B/13.5
2030 PM No Build	F/494.2	F/494.2	F/494.2	N/A	N/A	C/21.2	C/21.2	F/494.2
2030 PM Build	A/6.4	A/6.4	B/18.6	C/29.5	B/12.6	A/7.6	A/7.6	B/16.6

**d. Turn Lane Length Determination**

Tables 6 and 7 provide the queue lengths based upon the ODOT Location and Design Manual, Figure 401-10 and the Sidra output files as appropriate. The opening day queue for the eastbound off ramp is based upon an unsignalized condition. The opening day queue length for the westbound ramp and the design year queue lengths for both ramps are taken from the Sidra output files.

At the eastbound off ramp, the longest queue length occurs for the opening day condition and shall be constructed as such and will remain for the final build condition. Conversely, the queue length at the westbound off ramp occurs under design year conditions. However, the design year condition will be used to determine the bypass lane length for the opening day condition. This will be done to lessen future construction impacts to the off ramps. Providing more storage than necessary will not adversely affect the opening day operations. Table 8 provides the turn lane lengths for the exit ramp

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

intersections. All turn lane lengths include the 50 foot taper. Refer to Appendix G for the queuing and turn lane length calculations.

**Table 6: Queue Lengths for Intersection of SR 29 at the IR-70 WB Ramps**

Condition	Off Ramp (FT)		SR 29 (FT)	
	WBL/T	WBR	NB	SB
<b>No Build Available Storage</b>	1425 (ramp length)		1260*	615*
<b>Opening Day AM</b>	80	Free	0	107
<b>Opening Day PM</b>	91	Free	0	50
<b>Design Year AM</b>	178**	Free	0	37
<b>Design Year PM</b>	169	Free	0	27

\*Distance to adjacent intersection/driveway

\*\*Controls

**Table 7: Queue Lengths for Intersection of SR 29 at the IR-70 EB Ramps**

Condition	Off Ramp (FT)		SR 29 (FT)	
	EBL/T	EBR	SB	NB
<b>No Build Available Storage</b>	1320 (ramp length)		1260*	688*
<b>Opening Day AM</b>	50	200**	N/A	N/A
<b>Opening Day PM</b>	50	175	N/A	N/A
<b>Design Year AM</b>	3	112	0	31
<b>Design Year PM</b>	3	70	0	372

\*Distance to adjacent intersection/driveway

\*\*Controls

**Table 8: Turn Lane Lengths for Ramp Intersections**

Location	Left/Thru (FT)	Right (FT)
<b>WB Off Ramp</b>	N/A	230
<b>EB Off Ramp</b>	250	N/A

**e. Summary of Results**

In summation, the recommended improvements will not cause degradation of the mainline as defined in the ODOT Location and Design Manual, Section 550.1. The modifications that are recommended will provide the necessary capacity and storage improvements required to mitigate the impacts of the proposed development traffic.

**Interchange Modification Study**  
**IR-70 at SR 29**  
**MAD-70-10.27**  
**PID 83245**

---

**f. Relocation/Closure of Roadways**

Two roadways adjacent to the interchange will need to be modified to promote good access management. Snyder Lane will be relocated to meet the recommended drive spacing of ODOT's Location and Design Manual Volume 1, Section 801.2. The bypass lane which is being proposed on the IR-70 westbound ramp roundabout in the northbound direction will be merging downstream. The relocation will provide adequate distance for the merge to occur prior to the access point.

Byerly Road to the south of the eastbound ramp intersection is under the control of the Madison County Engineer's Office. Byerly Road has access to US 40 at the other end so this roadway shall be closed as part of the final phase of the project in order for the eastbound ramp roundabout to operate efficiently.

**X. Cost Estimate:**

The cost of construction for Phase 1 is estimated at roughly \$3.4 million. The Right-of-Way costs for Phase I are an additional \$600,000. The funds secured thru the developer agreement are \$3.5 million. The District has available 629 State Funds for any funding shortfalls, if they exist. Phase II has been estimated at approximately \$8.4 million. Phase II is currently planned to be constructed by capturing the future value of development. The detailed cost itemization for both phases is included in Tables 9 and 10.

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

**Table 9: Phase 1 Cost Estimate**

<b>Category</b>	<b>Qty</b>	<b>Unit</b>	<b>\$/Unit</b>	<b>\$</b>
Pavement	1	Lump	1,066,776.77	1,066,777.00
Curb & Gutter, Type 2	6212	Ft	14.00	86,968.00
Earthwork				
Excavation	22848	Cu Yd	6.75	154,224.00
Embankment	21322	Cu Yd	5.50	117,271.00
Drainage				
Closed System	2000	Ft	200.00	400,000.00
Erosion Control (1)	1	Lump	105,000.00	105,000.00
Lighting	4	Each	32,500.00	130,000.00
Traffic Control	1	Lump	261,363.00	261,363.00
Utility Relocation (2)	1	Lump	41,000.00	41,000.00
Maintenance of Traffic (3)	1	Lump	70,878.09	70,879.00
Design Contingency (4)	1	Lump	365,022.30	365,023.00
Construction Inspection (5)	1	Lump	279,850.50	279,851.00
Inflation (6)	1	Lump	317,071.00	317,071.00
<b>Total</b>				<b>\$3,395,427.00</b>

(1) Includes seeding & mulching, erosion control, soil analysis, water, BMP's etc.

(2) Taken from original cost estimate

(3) 3% of total cost

(4) 15% of total cost

(5) 10% of total cost

(6) 10.3% of total cost (assumed construction mid-point of July, 2013)



**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

**Table 10: Phase 2 Cost Estimate**

<b>Category</b>	<b>Qty</b>	<b>Unit</b>	<b>\$/Unit</b>	<b>\$</b>
Pavement	1	Lump	719,299.77	719,299.77
Curb & Gutter, Type 2	6930	Ft	14.00	97,020.00
Earthwork				
Excavation	18307	Cu Yd	7.00	128,149.00
Embankment	11173	Cu Yd	6.00	67,038.00
Drainage				
Closed System	2000	Ft	200.00	400,000.00
Erosion Control (1)	1	Lump	45,000.00	95,000.00
Lighting	4	Each	32,500.00	130,000.00
Traffic Control	1	Lump	262,919.00	262,919.00
Bridge (2)	22880	Sq Ft	180.00	4,118,400.00
Maintenance of Traffic (3)	1	Lump	180,534.77	180,535.00
Design Contingency (4)	1	Lump	821,859.15	821,860.00
Construction Inspection (5)	1	Lump	620,390.10	620,391.00
Inflation (6)	1	Lump	786,984.00	786,984.00
<b>Total</b>				<b>\$8,427,596.00</b>

- (1) Includes seeding & mulching, erosion control, soil analysis, water, BMP's etc.
- (2) Includes approach slabs
- (3) 3% of total cost
- (4) 15% of total cost
- (5) 10% of total cost
- (6) 10.3% of total cost (assumed construction mid-point of July 2013)
- (7) Assumed all utility relocations completed in Phase 1

## **XI. Environmental Impacts:**

There are no significant environmental impacts identified for the full build condition of this project. The only substantial right-of-way being acquired for this project is for the relocation of Snyder Lane which will be aligned on a small portion of an existing disturbed farm field. The Draft Categorical Exclusion Level 3 Document is based upon the full Build condition and is subject to ongoing public coordination. The CE Level 3 is being prepared by ODOT's District 6 environmental team.

**Interchange Modification Study**  
**IR-70 at SR 29**  
**MAD-70-10.27**  
**PID 83245**

---

**XII. Recommendations:**

Due to funding constraints, there is need for a phased improvement plan for the interchange. As already stated, the Department and the Village of West Jefferson have worked to secure funding from the developers involved. The Opening Day build condition includes construction of a single lane roundabout at the westbound ramp as this ramp exhibits the greatest delay if no improvements are constructed. At this time, ODOT and the Village have obtained the necessary funds from the developers to move forward.

ODOT has committed that another bridge will be added to provide two lanes in each direction on SR 29. This will also require that the roundabout on the north side of the interchange will be expanded along with a new roundabout on the south side of the interchange. Funding for this phase will need to be determined. The northern roundabout has been sized to accommodate conversion to a dual lane roundabout. As part of the Phase 1 construction project, Snyder Lane will be relocated approximately 700 feet north of the roundabout.

Based on the analyses, the recommended improvements to the ramps do not degrade freeway operations within the study area. The SR 29 corridor will need to be monitored in the future years to assure that the ramp terminals are operating adequately.

The Opening Day improvements will be implemented in 2013.

# Appendix A

## Certified Traffic

# INTER-OFFICE COMMUNICATION

**TO:** James Young, P.E., Office of Roadway Engineering Services

**FROM:** Leigh A. Oesterling, Project Analyses Admin., Office of Technical Services

**SUBJECT:** MAD-70-10.27 (SR 29 IMS) PID 83245

**DATE:** November 8, 2007

In reply to a request dated September 4, 2007, attached are a set of plates showing ADT, A.M. and P.M. design hour volumes for the subject project. If needed K and D factors can be derived from the attached plates.

Please use the following truck factors.

	<u>w/o US 42</u>	<u>w/o SR 29</u>	IR 70 <u>w/o SR 142</u>	<u>e/o SR 142</u>	<u>n/o IR 70</u>	SR 29 <u>s/o IR 70</u>
T24:	0.39	0.36	0.34	0.32	0.11	0.20
TD AM:	0.33	0.31	0.29	0.27	0.07	0.17
TD PM:	0.23	0.22	0.20	0.19	0.07	0.12

RAMPS				
IR 70 @ SR 142				
	<u>WB Off</u>	<u>WB on</u>	<u>EB Off</u>	<u>EB on</u>
T24:	0.05	0.10	0.10	0.04
TD AM:	0.06	0.10	0.04	0.02
TD PM:	0.02	0.01	0.05	0.03

IR 70 @ SR 29				
	<u>WB Off</u>	<u>WB on</u>	<u>EB Off</u>	<u>EB on</u>
T24:	0.23	0.16	0.18	0.21
TD AM:	0.29	0.20	0.20	0.15
TD PM:	0.18	0.04	0.07	0.15

IR 70 @ US 42				
	<u>WB Off</u>	<u>WB on</u>	<u>EB Off</u>	<u>EB on</u>
T24:	0.28	0.45	0.48	0.27
TD AM:	0.32	0.44	0.49	0.23
TD PM:	0.18	0.33	0.45	0.18


If you have any questions, please contact me at (614) 752-5747.

*LAO*

LAO:lo


c: J. McQuirt, OTS-P. Siddle, OTS-File

Build




MAD-70-10.27 PID-83245 IMS	
2010/2030 ADT	
OHIO DEPARTMENT OF TRANSPORTATION	
OFFICE OF TECHNICAL SERVICES	
NOVEMBER 8, 2007	NOT TO SCALE

Build



MAD-70-10.27	PID-83245	IMS
2010/2030 AM DHV		
OHIO DEPARTMENT OF TRANSPORTATION		
OFFICE OF TECHNICAL SERVICES		
NOVEMBER 8, 2007	NOT TO SCALE	

Build



MAD-70-10.27	PID-83245	IMS
2010/2030 PM DHV		
OHIO DEPARTMENT OF TRANSPORTATION		
OFFICE OF TECHNICAL SERVICES		
NOVEMBER 8, 2007	NOT TO SCALE	

## Appendix B

# Opening Day and Design Year Figures





PREPARED BY:  
ODOT  
OFFICE OF ROADWAY ENGINEERING

# PRELIMINARY CONCEPT S.R. 29 & I.R. 70 INTERCHANGE IMPROVEMENTS




**FIGURE 2:  
OPENING DAY LAYOUT**

SCALE IN FEET



PREPARED BY:  
ODOT  
OFFICE OF ROADWAY ENGINEERING

# PRELIMINARY CONCEPT S.R. 29 & I.R. 70 INTERCHANGE IMPROVEMENTS



SR 29  
INTERCHANGE

ROUNDAABOUT

EXISTING  
STRUCTURE

PROPOSED  
STRUCTURE

ROUNDAABOUT



**FIGURE 3:  
DESIGN YEAR LAYOUT  
INTERCHANGE ROUNDAABOUTS**

0 125 250 500

SCALE IN FEET

# Appendix C

## HCS Freeway Mainline Analyses



**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

# 2010 AM Freeway HCS Analyses

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #21  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w US 42  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	970	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	269	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	404	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	404	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	5.8	pc/mi/ln

Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #19  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w US 42 and SR 29  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1330	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	369	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	554	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	554	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	7.9	pc/mi/ln



Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #17  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w SR 29  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1240	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	344	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	517	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	517	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	7.4	pc/mi/ln

Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #15  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w SR 142 and SR 29  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1710	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	475	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	713	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	713	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	10.2	pc/mi/ln

Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #13  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w SR 142  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1590	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	442	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	663	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	663	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	9.5	pc/mi/ln

Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

Phone:  
E-mail:

Fax:

---

Operational Analysis

---

Analyst: point #10  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 142  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1920	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	533	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	800	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	800	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	11.4	pc/mi/ln



Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst:  
Agency or Company: ODOT  
Date Performed: 10/21/2009  
Analysis Time Period: AM Peak  
Freeway/Direction: I-70 EB  
From/To: b/w SR 29 and SR 142  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2040	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	567	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	850	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	850	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	12.1	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst:  
Agency or Company: ODOT  
Date Performed: 10/21/2009  
Analysis Time Period: AM Peak  
Freeway/Direction: I-70 EB  
From/To: b/w SR 29  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1750	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	486	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	729	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	729	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	10.4	pc/mi/ln

Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #4  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w US 42 and SR 29  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2030	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	564	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	846	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	846	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	12.1	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst:  
Agency or Company: ODOT  
Date Performed: 10/21/2009  
Analysis Time Period: AM Peak  
Freeway/Direction: I-70 EB  
From/To: b/w US 42  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1430	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	397	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	596	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	596	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	8.5	pc/mi/ln



Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

# 2010 PM Freeway HCS Analyses

Phone:  
E-mail:

Fax:

---

Operational Analysis

---

Analyst: point #21  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w US 42  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2440	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	678	v
Trucks and buses	23	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.897	
Driver population factor, fp	1.00	
Flow rate, vp	1008	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1008	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	14.4	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #19  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w US 42 and SR 29  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	3080	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	856	v
Trucks and buses	22	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.901	
Driver population factor, fp	1.00	
Flow rate, vp	1266	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1266	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	18.1	pc/mi/ln

Level of service, LOS

C

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst:  
Agency or Company: ODOT  
Date Performed: 10/21/2009  
Analysis Time Period: PM Peak  
Freeway/Direction: I-70 WB  
From/To: b/w SR 29  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2790	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	775	v
Trucks and buses	22	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.901	
Driver population factor, fp	1.00	
Flow rate, vp	1147	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1147	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	16.4	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.



Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #15  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w SR 142 and SR 29  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	3330	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	925	v
Trucks and buses	20	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.909	
Driver population factor, fp	1.00	
Flow rate, vp	1357	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1357	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	19.4	pc/mi/ln

Level of service, LOS

C

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #13  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w SR 142  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	3190	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	886	v
Trucks and buses	20	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.909	
Driver population factor, fp	1.00	
Flow rate, vp	1300	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1300	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	18.6	pc/mi/ln

Level of service, LOS

C

Overall results are not computed when free-flow speed is less than 55 mph.

Phone:  
E-mail:

Fax:

---

Operational Analysis

---

Analyst: Point #10  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 142  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2620	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	728	v
Trucks and buses	20	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.909	
Driver population factor, fp	1.00	
Flow rate, vp	1067	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1067	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	15.2	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point # 8  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 29 and SR 142  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2770	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	769	v
Trucks and buses	20	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.909	
Driver population factor, fp	1.00	
Flow rate, vp	1129	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1129	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	16.1	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.



Phone:  
E-mail:

Fax:

---

Operational Analysis

---

Analyst: Point #6  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 29  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2100	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	583	v
Trucks and buses	22	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.901	
Driver population factor, fp	1.00	
Flow rate, vp	863	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	863	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	12.3	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #4  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w US 42 and SR 29  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2360	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	656	v
Trucks and buses	22	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.901	
Driver population factor, fp	1.00	
Flow rate, vp	970	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	970	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	13.9	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone:  
E-mail:

Fax:

---

Operational Analysis

---

Analyst: Point #2  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w US 42  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1930	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	536	v
Trucks and buses	23	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.897	
Driver population factor, fp	1.00	
Flow rate, vp	797	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	797	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	11.4	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

# 2030 AM Freeway HCS Analyses

Phone:  
E-mail:

Fax:

---

Operational Analysis

---

Analyst: Point #21  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w US 42  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1350	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	375	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	563	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	563	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	8.0	pc/mi/ln



Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #19  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w US 42 and SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1830	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	508	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	763	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	763	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	10.9	pc/mi/ln

Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

Phone:  
E-mail:

Fax:

---

Operational Analysis

---

Analyst: Point #17  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1700	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	472	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	708	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	708	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	10.1	pc/mi/ln

Level of service, LOS

A

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #15  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w SR 142 and SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2450	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	681	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	1021	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1021	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	14.6	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #13  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction:  
 From/To: b/w SR 142  
 Jurisdiction:  
 Analysis Year:  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2180	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	606	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	908	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	908	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	13.0	pc/mi/ln



Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #10  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 142  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2510	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	697	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	1046	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1046	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	14.9	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #8  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 29 and SR 142  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2810	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	781	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	1171	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1171	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	16.7	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #6  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2360	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	656	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	983	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	983	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	14.0	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: Point #4  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w US 42 and SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2790	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	775	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	1163	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1163	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	16.6	pc/mi/ln



Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone:  
E-mail:

Fax:

---

Operational Analysis

---

Analyst: Point #2  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: AM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w US 42  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	1960	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	544	v
Trucks and buses	25	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.889	
Driver population factor, fp	1.00	
Flow rate, vp	817	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	817	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	11.7	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

# 2030 PM Freeway HCS Analyses

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #21  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w US 42  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	3370	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	936	v
Trucks and buses	23	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.897	
Driver population factor, fp	1.00	
Flow rate, vp	1392	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1392	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	19.9	pc/mi/ln

Level of service, LOS

C

Overall results are not computed when free-flow speed is less than 55 mph.

Phone:  
E-mail:

Fax:

---

Operational Analysis

---

Analyst: point #17  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	3810	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	1058	v
Trucks and buses	22	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.901	
Driver population factor, fp	1.00	
Flow rate, vp	1566	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1566	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	69.6	mi/h
Number of lanes, N	3	
Density, D	22.5	pc/mi/ln

Level of service, LOS

C

Overall results are not computed when free-flow speed is less than 55 mph.



Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #15  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w SR 142 and SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	4670	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	1297	v
Trucks and buses	20	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.909	
Driver population factor, fp	1.00	
Flow rate, vp	1903	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1903	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	66.5	mi/h
Number of lanes, N	3	
Density, D	28.6	pc/mi/ln

Level of service, LOS

D

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #13  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction:  
 From/To: b/w SR 142  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	4390	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	1219	v
Trucks and buses	20	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.909	
Driver population factor, fp	1.00	
Flow rate, vp	1789	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1789	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	68.0	mi/h
Number of lanes, N	3	
Density, D	26.3	pc/mi/ln

Level of service, LOS

D

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #10  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 142  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	3550	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	986	v
Trucks and buses	20	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.909	
Driver population factor, fp	1.00	
Flow rate, vp	1446	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1446	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	69.9	mi/h
Number of lanes, N	3	
Density, D	20.7	pc/mi/ln

Level of service, LOS

C

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #8  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 29 and SR 142  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	3860	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	1072	v
Trucks and buses	20	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.909	
Driver population factor, fp	1.00	
Flow rate, vp	1573	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1573	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	69.6	mi/h
Number of lanes, N	3	
Density, D	22.6	pc/mi/ln

Level of service, LOS

C

Overall results are not computed when free-flow speed is less than 55 mph.



Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #6  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2870	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	797	v
Trucks and buses	22	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.901	
Driver population factor, fp	1.00	
Flow rate, vp	1180	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1180	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	16.9	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #4  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w US 42 and SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	3260	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	906	v
Trucks and buses	22	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.901	
Driver population factor, fp	1.00	
Flow rate, vp	1340	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1340	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	19.1	pc/mi/ln

Level of service, LOS

C

Overall results are not computed when free-flow speed is less than 55 mph.

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #2  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 EB  
 From/To: b/w US 42  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	2680	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	744	v
Trucks and buses	23	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.897	
Driver population factor, fp	1.00	
Flow rate, vp	1107	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1107	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	70.0	mi/h
Number of lanes, N	3	
Density, D	15.8	pc/mi/ln

Level of service, LOS

B

Overall results are not computed when free-flow speed is less than 55 mph.

## Appendix D

# HCS Merge and Diverge Analyses

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

# 2010 AM Merge HCS Analyses



Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #22  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: US 42 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	970	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	350	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	970	350		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	269	97		v
Trucks and buses	25	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	1213	438	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 717 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	1651	7200	No
v <sub>3 or av34</sub>	496 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 717		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	717	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 11.1 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.298	
Space mean speed in ramp influence area,	S <sub>R</sub> = 61.6	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 70.0	mph
Space mean speed for all vehicles,	S = 63.9	mph

---

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #18  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: SR 29 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	1240	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	90	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1240	90		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	344	25		v
Trucks and buses	25	20		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.909	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	1550	110	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
 EQ  
 P = 0.591 Using Equation 1  
 FM  
 $v_{12} = v_F (P_{FM}) = 917 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	1660	7200	No
v <sub>3 or av34</sub>	633 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 917		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	917	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 10.3 \text{ pc/mi/ln}$   
 Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.297	
Space mean speed in ramp influence area,	S <sub>R</sub> = 61.7	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 69.5	mph
Space mean speed for all vehicles,	S = 64.5	mph

---

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #14  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: SR 142 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	1590	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	120	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1590	120		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	442	33		v
Trucks and buses	25	10		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.952	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	1988	140	pcph

Estimation of V12 Merge Areas

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 1176 \text{ pc/h}$

Capacity Checks

	Actual	Maximum	LOS F?
v <sub>FO</sub>	2128	7200	No
v <sub>3 or av34</sub>	812 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 1176		(Equation 25-8)	

Flow Entering Merge Influence Area

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	1176	4600	No

Level of Service Determination (if not F)

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 12.5 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

Speed Estimation

Intermediate speed variable,	M = 0.301	
Space mean speed in ramp influence area,	S <sub>R</sub> = 61.6	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 68.9	mph
Space mean speed for all vehicles,	S = 64.2	mph

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #11  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: SR 142 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	1920	vph	

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	640	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1920	640		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	533	178		v
Trucks and buses	25	2		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.990	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2400	718	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)

EQ

P = 0.591 Using Equation 1

FM

$v_{12} = v_{F \text{ FM}} = 1420 \text{ pc/h}$

12 F FM

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v	3118	7200	No
FO			
v	980 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v	> 2700 pc/h?	No	
3 or av34			
Is v	> 1.5 v /2	No	
3 or av34	12		
If yes, v	= 1420	(Equation 25-8)	
12A			

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v	1420	4600	No
R12			

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 18.7 \text{ pc/mi/ln}$

Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.319	
	S	
Space mean speed in ramp influence area,	S = 61.1	mph
	R	
Space mean speed in outer lanes,	S = 68.3	mph
	0	
Space mean speed for all vehicles,	S = 63.2	mph

---



Phone:  
E-mail:

Fax:

---

Merge Analysis

---

Analyst: Point #7  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: SR 29 On Ramp  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	1750	vph	

---

On Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	290	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1750	290		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	486	81		v
Trucks and buses	25	15		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.930	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2188	346	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_{F \text{ FM}} = 1294 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v	2534	7200	No
FO			
v	894 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v > 2700 pc/h?		No	
3 or av34			
Is v > 1.5 v /2		No	
3 or av34	12		
If yes, v = 1294		(Equation 25-8)	
12A			

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v	1294	4600	No
R12			

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 15.0 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.306	
Space mean speed in ramp influence area,	S = 61.4	mph
Space mean speed in outer lanes,	S = 68.6	mph
Space mean speed for all vehicles,	S = 63.8	mph

---

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #3  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: US 42 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	1430	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	600	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1430	600		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	397	167		v
Trucks and buses	25	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	1788	750	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 1058 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	2538	7200	No
v <sub>3 or av34</sub>	730 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 1058		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	1058	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 16.1 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.310	
Space mean speed in ramp influence area,	S <sub>R</sub> = 61.3	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 69.2	mph
Space mean speed for all vehicles,	S = 63.4	mph

---

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

# 2010 PM Merge HCS Analyses

Phone:  
E-mail:

Fax:

---

Merge Analysis

---

Analyst: Point #22  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 WB  
 Junction: US 42 On Ramp  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2440	vph	

---

On Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	390	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2440	390		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	678	108		v
Trucks and buses	23	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.897	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3023	488	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
 EQ  
 P = 0.591 Using Equation 1  
 FM  
 $v_{12} = v_{F \text{ FM}} = 1788 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v	3511	7200	No
FO			
v	1235 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v > 2700 pc/h?		No	
3 or av34			
Is v > 1.5 v /2		No	
3 or av34	12		
If yes, v = 1788		(Equation 25-8)	
12A			

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v	1788	4600	No
R12			

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 19.9 \text{ pc/mi/ln}$   
 Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.324	
Space mean speed in ramp influence area,	S = 60.9	mph
Space mean speed in outer lanes,	S = 67.4	mph
Space mean speed for all vehicles,	S = 63.0	mph

---

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #18  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: SR 29 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	2790	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	290	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2790	290		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	775	81		v
Trucks and buses	22	4		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		



Heavy vehicle adjustment, fHV	0.901	0.980	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3441	329	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_{F \text{ FM}} = 2035 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v	3770	7200	No
FO			
v	1406 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v	> 2700 pc/h?	No	
3 or av34			
Is v	> 1.5 v /2	No	
3 or av34	12		
If yes, v	= 2035	(Equation 25-8)	
12A			

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v	2035	4600	No
R12			

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 20.6 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	M = 0.327	
Space mean speed in ramp influence area,	S = 60.8	mph
Space mean speed in outer lanes,	S = 66.7	mph
Space mean speed for all vehicles,	S = 62.9	mph

---

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #14  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: SR 142 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	3190	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	140	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	3190	140		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	886	39		v
Trucks and buses	20	1		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.909	0.995	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3899	156	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)

EQ

P = 0.591 Using Equation 1

FM

v = v (P ) = 2306 pc/h

12 F FM

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v	4055	7200	No
FO			
v	1593 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v v > 2700 pc/h?		No	
3 or av34			
Is v v > 1.5 v /2		No	
3 or av34	12		
If yes, v = 2306		(Equation 25-8)	
12A			

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v	2306	4600	No
R12			

---

Level of Service Determination (if not F)

---

Density, D = 5.475 + 0.00734 v + 0.0078 v - 0.00627 L = 21.5 pc/mi/ln

R R 12 A

Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	M = 0.332	
	S	
Space mean speed in ramp influence area,	S = 60.7	mph
	R	
Space mean speed in outer lanes,	S = 66.1	mph
	0	
Space mean speed for all vehicles,	S = 62.7	mph

---

Phone:  
E-mail:

Fax:

---

Merge Analysis

---

Analyst: Point #11  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: SR 142 On Ramp  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2620	vph	

---

On Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	260	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2620	260		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	728	72		v
Trucks and buses	19	2		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.913	0.990	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3188	292	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)

EQ

P = 0.591 Using Equation 1

FM

v = v (P ) = 1886 pc/h

12 F FM

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v	3480	7200	No
FO			
v	1302 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v v > 2700 pc/h?		No	
3 or av34			
Is v v > 1.5 v /2		No	
3 or av34	12		
If yes, v = 1886		(Equation 25-8)	
12A			

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v	1886	4600	No
R12			

---

Level of Service Determination (if not F)

---

Density, D = 5.475 + 0.00734 v + 0.0078 v - 0.00627 L = 19.2 pc/mi/ln

R R 12 A

Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.320	
	S	
Space mean speed in ramp influence area,	S = 61.0	mph
	R	
Space mean speed in outer lanes,	S = 67.1	mph
	0	
Space mean speed for all vehicles,	S = 63.2	mph

---

Phone:  
E-mail:

Fax:

---

Merge Analysis

---

Analyst: Point #7  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: SR 29 On Ramp  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2100	vph	

---

On Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	670	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2100	670		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	583	186		v
Trucks and buses	22	15		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.901	0.930	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2590	800	pcph

Estimation of V12 Merge Areas

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 1532$  pc/h

Capacity Checks

	Actual	Maximum	LOS F?
v <sub>FO</sub>	3390	7200	No
v <sub>3 or av34</sub>	1058 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 1532		(Equation 25-8)	

Flow Entering Merge Influence Area

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	1532	4600	No

Level of Service Determination (if not F)

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 20.2$  pc/mi/ln  
Level of service for ramp-freeway junction areas of influence C

Speed Estimation

Intermediate speed variable,	M = 0.326	
Space mean speed in ramp influence area,	S <sub>R</sub> = 60.9	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 68.0	mph
Space mean speed for all vehicles,	S = 62.9	mph

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #3  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: US 42 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	1930	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	430	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1930	430		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	536	119		v
Trucks and buses	23	18		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		



Heavy vehicle adjustment, fHV	0.897	0.917	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2391	521	pcph

Estimation of V12 Merge Areas

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 1414 \text{ pc/h}$

Capacity Checks

	Actual	Maximum	LOS F?
v <sub>FO</sub>	2912	7200	No
v <sub>3 or av34</sub>	977 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 1414		(Equation 25-8)	

Flow Entering Merge Influence Area

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	1414	4600	No

Level of Service Determination (if not F)

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 17.2 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

Speed Estimation

Intermediate speed variable,	M = 0.313	
Space mean speed in ramp influence area,	S <sub>R</sub> = 61.2	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 68.3	mph
Space mean speed for all vehicles,	S = 63.4	mph

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

# 2030 AM Merge HCS Analyses

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #22  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: US 42 On Ramp  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	1350	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	470	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1350	470		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	375	131		v
Trucks and buses	25	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	1688	588	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 998 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	2276	7200	No
v <sub>3 or av34</sub>	690 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 998		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	998	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 14.4 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.305	
Space mean speed in ramp influence area,	S <sub>R</sub> = 61.5	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 69.3	mph
Space mean speed for all vehicles,	S = 63.6	mph

---

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #18  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: SR 29 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	1700	vph	

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	130	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1700	130		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	472	36		v
Trucks and buses	25	20		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.909	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2125	159	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 1257 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	2284	7200	No
v <sub>3 or av34</sub>	868 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 1257		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	1257	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 13.3 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.302	
Space mean speed in ramp influence area,	S <sub>R</sub> = 61.5	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 68.7	mph
Space mean speed for all vehicles,	S = 64.1	mph

---

Phone: Fax:  
E-mail:

---

Merge Analysis

---

Analyst: Point #14  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: SR 142 On Ramp  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2180	vph	

---

On Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	270	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2180	270		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	606	75		v
Trucks and buses	25	10		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.952	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2725	315	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 1612 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	3040	7200	No
v <sub>3 or av34</sub>	1113 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 1612		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	1612	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D_R = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 17.2 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.313	
Space mean speed in ramp influence area,	S <sub>R</sub> = 61.2	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 67.8	mph
Space mean speed for all vehicles,	S = 63.5	mph

---



Phone:  
E-mail:

Fax:

---

Merge Analysis

---

Analyst: Point #11  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: SR 142 On Ramp  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2510	vph	

---

On Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	860	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2510	860		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	697	239		v
Trucks and buses	25	2		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.990	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3138	965	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
 EQ  
 P = 0.591 Using Equation 1  
 FM  
 $v_{12} = v_F (P_{FM}) = 1856 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	4103	7200	No
v <sub>3 or av34</sub>	1282 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 1856		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	1856	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 23.9 \text{ pc/mi/ln}$   
 Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	M = 0.351	
Space mean speed in ramp influence area,	S <sub>R</sub> = 60.2	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 67.2	mph
Space mean speed for all vehicles,	S = 62.2	mph

---

Phone:  
E-mail:

Fax:

---

Merge Analysis

---

Analyst: Point #7  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: SR 29 On Ramp  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2360	vph	

---

On Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	450	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2360	450		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	656	125		v
Trucks and buses	25	15		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.930	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2950	537	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 1745 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	3487	7200	No
v <sub>3 or av34</sub>	1205 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 1745		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	1745	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 19.9 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	M = 0.324	
Space mean speed in ramp influence area,	S <sub>R</sub> = 60.9	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 67.5	mph
Space mean speed for all vehicles,	S = 63.0	mph

---

Phone: Fax:  
 E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #3  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: US 42 On Ramp  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	1960	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	830	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1960	830		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	544	231		v
Trucks and buses	25	23		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.897	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2450	1028	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
 EQ  
 P = 0.591 Using Equation 1  
 FM  
 $v_{12} = v_F (P_{FM}) = 1449 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	3478	7200	No
v <sub>3 or av34</sub>	1001 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 1449		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	1449	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 21.2 \text{ pc/mi/ln}$   
 Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	M = 0.332	
Space mean speed in ramp influence area,	S <sub>R</sub> = 60.7	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 68.2	mph
Space mean speed for all vehicles,	S = 62.7	mph

---

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

# 2030 PM Merge HCS Analyses

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #22  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: US 42 On Ramp  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	3370	vph	

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	530	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	3370	530		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	936	147		v
Trucks and buses	23	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		



Heavy vehicle adjustment, fHV	0.897	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	4175	663	pcph

Estimation of V12 Merge Areas

L = (Equation 25-2 or 25-3)

EQ

P = 0.591 Using Equation 1

FM

v = v (P ) = 2470 pc/h

12 F FM

Capacity Checks

	Actual	Maximum	LOS F?
v	4838	7200	No
FO			
v	1705 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v v > 2700 pc/h?		No	
3 or av34			
Is v v > 1.5 v /2		No	
3 or av34	12		
If yes, v = 2470		(Equation 25-8)	
12A			

Flow Entering Merge Influence Area

	Actual	Max Desirable	Violation?
v	2470	4600	No
R12			

Level of Service Determination (if not F)

Density, D = 5.475 + 0.00734 v + 0.0078 v - 0.00627 L = 26.5 pc/mi/ln

R R 12 A C

Level of service for ramp-freeway junction areas of influence C

Speed Estimation

Intermediate speed variable,	M = 0.375	
	S	
Space mean speed in ramp influence area,	S = 59.5	mph
	R	
Space mean speed in outer lanes,	S = 65.7	mph
	0	
Space mean speed for all vehicles,	S = 61.5	mph

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #18  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: SR 29 On Ramp  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	3810	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	420	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	3810	420		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	1058	117		v
Trucks and buses	22	4		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.901	0.980	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	4699	476	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_{F \text{ FM}} = 2779 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v	5175	7200	No
FO			
v	1920 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v > 2700 pc/h?		No	
3 or av34			
Is v > 1.5 v /2		No	
3 or av34	12		
If yes, v = 2779		(Equation 25-8)	
12A			

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v	2779	4600	No
R12			

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 27.5 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	M = 0.387	
	S	
Space mean speed in ramp influence area,	S = 59.2	mph
	R	
Space mean speed in outer lanes,	S = 64.9	mph
	0	
Space mean speed for all vehicles,	S = 61.2	mph

---

Phone: Fax:  
E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #14  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: SR 142 On Ramp  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	4390	vph

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	280	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	4390	280		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	1219	78		v
Trucks and buses	20	1		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.909	0.995	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	5366	313	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)

EQ

P = 0.591 Using Equation 1

FM

$v_{12} = v_{F, FM} = 3174 \text{ pc/h}$

12 F FM

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v	5679	7200	No
FO			
v	2192 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v > 2700 pc/h?		No	
3 or av34			
Is v > 1.5 v /2		No	
3 or av34	12		
If yes, v = 3174		(Equation 25-8)	
12A			

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v	3174	4600	No
R12			

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 29.4 \text{ pc/mi/ln}$

Level of service for ramp-freeway junction areas of influence D

---

Speed Estimation

---

Intermediate speed variable,	M = 0.413	
	S	
Space mean speed in ramp influence area,	S = 58.4	mph
	R	
Space mean speed in outer lanes,	S = 63.9	mph
	0	
Space mean speed for all vehicles,	S = 60.4	mph

---

Phone: Fax:  
 E-mail:

\_\_\_\_\_Merge Analysis\_\_\_\_\_

Analyst: Point #11  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: SR 142 On Ramp  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	3550	vph	

\_\_\_\_\_On Ramp Data\_\_\_\_\_

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	350	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	3550	350		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	986	97		v
Trucks and buses	20	3		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.909	0.985	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	4339	395	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 2567 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	4734	7200	No
v <sub>3 or av34</sub>	1772 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 2567		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	2567	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 25.3 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	M = 0.361	
Space mean speed in ramp influence area,	S <sub>R</sub> = 59.9	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 65.4	mph
Space mean speed for all vehicles,	S = 61.8	mph

---

Phone: Fax:  
E-mail:

---

Merge Analysis

---

Analyst: Point #7  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: SR 29 On Ramp  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Merge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2870	vph	

---

On Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-flow speed on ramp	35.0	mph	
Volume on ramp	990	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent Ramp		vph	
Position of adjacent Ramp			
Type of adjacent Ramp			
Distance to adjacent Ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2870	990		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	797	275		v
Trucks and buses	22	15		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		



Heavy vehicle adjustment, fHV	0.901	0.930	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3540	1182	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
EQ  
P = 0.591 Using Equation 1  
FM  
 $v_{12} = v_F (P_{FM}) = 2094 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v <sub>FO</sub>	4722	7200	No
v <sub>3 or av34</sub>	1446 pc/h	(Equation 25-4 or 25-5)	
Is v <sub>3 or av34</sub> > 2700 pc/h?		No	
Is v <sub>3 or av34</sub> > 1.5 v <sub>12</sub> / 2		No	
If yes, v <sub>12A</sub> = 2094		(Equation 25-8)	

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v <sub>R12</sub>	2094	4600	No

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 27.3 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	M = 0.389	
Space mean speed in ramp influence area,	S <sub>R</sub> = 59.1	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 66.6	mph
Space mean speed for all vehicles,	S = 61.2	mph

---

Phone: Fax:  
 E-mail:

Merge Analysis

Analyst: Point #3  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: US 42 On Ramp  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Merge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	2680	vph

On Ramp Data

Side of freeway	Right	
Number of lanes in ramp	1	
Free-flow speed on ramp	35.0	mph
Volume on ramp	580	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No	
Volume on adjacent Ramp		vph
Position of adjacent Ramp		
Type of adjacent Ramp		
Distance to adjacent Ramp		ft

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2680	580		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	744	161		v
Trucks and buses	23	18		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	%	%	%	%
Length	mi	mi	mi	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.897	0.917	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3320	702	pcph

---

Estimation of V12 Merge Areas

---

L = (Equation 25-2 or 25-3)  
 EQ  
 P = 0.591 Using Equation 1  
 FM  
 $v_{12} = v_{F \text{ FM}} = 1964 \text{ pc/h}$

---

Capacity Checks

---

	Actual	Maximum	LOS F?
v	4022	7200	No
FO			
v	1356 pc/h	(Equation 25-4 or 25-5)	
3 or av34			
Is v > 2700 pc/h?		No	
3 or av34			
Is v > 1.5 v /2		No	
3 or av34	12		
If yes, v = 1964		(Equation 25-8)	
12A			

---

Flow Entering Merge Influence Area

---

	Actual	Max Desirable	Violation?
v	1964	4600	No
R12			

---

Level of Service Determination (if not F)

---

Density,  $D = 5.475 + 0.00734 v_R + 0.0078 v_{12} - 0.00627 L_A = 22.8 \text{ pc/mi/ln}$   
 Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	M = 0.342	
	S	
Space mean speed in ramp influence area,	S = 60.4	mph
	R	
Space mean speed in outer lanes,	S = 66.9	mph
	0	
Space mean speed for all vehicles,	S = 62.5	mph

---

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

# 2010 AM Diverge HCS Analyses

Phone: Fax:  
E-mail:

---

Diverge Analysis

---

Analyst: Point #20  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: 70 WB US 42 Off  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	1330	vph	

---

Off Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	360	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1330	360		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	369	100		v
Trucks and buses	25	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	1663	450	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.698 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 1296 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{Fi} = v_F$	1663	7200	No
$v_{FO} = v_F - v_R$	1213	7200	No
$v_R$	450	2000	No
$v_{3 \text{ or } av34}$	367 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 1296$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	1296	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_R - 0.009 L_D = 10.9 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.469	
Space mean speed in ramp influence area,	S = 56.9	mph
Space mean speed in outer lanes,	S = 76.8	mph
Space mean speed for all vehicles,	S = 60.3	mph

---

Phone:  
E-mail:

Fax:

---

Diverge Analysis

---

Analyst: Point #16  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 WB  
 Junction: 70 WB SR 29 Off  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	1710	vph

---

Off Ramp Data

---

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	470	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1710	470		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	475	131		v
Trucks and buses	25	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2138	588	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.680 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 1641 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	2138	7200	No
$v_{FO} = v_F - v_R$	1550	7200	No
$v_R$	588	2000	No
$v_{3 \text{ or } av34}$	497 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 1641$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	1641	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 13.9 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.481	
Space mean speed in ramp influence area,	S <sub>R</sub> = 56.5	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 76.8	mph
Space mean speed for all vehicles,	S = 60.2	mph

---



Phone: Fax:  
E-mail:

---

Diverge Analysis

---

Analyst: Point #12  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: 70 WB SR 142 Off  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	1770	vph	

---

Off Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	180	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1770	180		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	492	50		v
Trucks and buses	25	6		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.971	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2213	206	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.695 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 1601 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	2213	7200	No
$v_{FO} = v_{FO} - v_{R3}$	2007	7200	No
$v_{R3}$	206	2000	No
$v_{3 \text{ or } av34}$	612 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 1601$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	1601	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L = 13.5 \text{ pc/mi/ln}$   
R 12 D  
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.447	
Space mean speed in ramp influence area,	S = 57.5	mph
Space mean speed in outer lanes,	S = 76.8	mph
Space mean speed for all vehicles,	S = 61.8	mph

---

Phone:  
E-mail:

Fax:

---

Diverge Analysis

---

Analyst: Point #9  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: 70 EB SR 142 Off  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2040	vph	

---

Off Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	120	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2040	120		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	567	33		v
Trucks and buses	25	4		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.980	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2550	136	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.690 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 1802 \text{ pc/h}$   
12 R F R FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	2550	7200	No
$v_{FO} = v_{FO} - v_{R}$	2414	7200	No
$v_{R}$	136	2000	No
$v_{3 \text{ or } av34}$	748 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 1802$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	1802	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 15.2 \text{ pc/mi/ln}$   
R 12 D  
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.440	
Space mean speed in ramp influence area,	S = 57.7	mph
Space mean speed in outer lanes,	S = 76.8	mph
Space mean speed for all vehicles,	S = 62.2	mph

---

Phone:  
E-mail:

Fax:

---

Diverge Analysis

---

Analyst: Point #5  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: 70 EB SR 29 Off  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2030	vph	

---

Off Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	280	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2030	280		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	564	78		v
Trucks and buses	25	20		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.909	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2538	342	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.681 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 1837 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	2538	7200	No
$v_{FO} = v_F - v_R$	2196	7200	No
$v_R$	342	2000	No
$v_{3 \text{ or } av34}$	701 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 1837$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	1837	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_R - 0.009 L_D = 15.6 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.459	
Space mean speed in ramp influence area,	S = 57.2	mph
Space mean speed in outer lanes,	S = 76.8	mph
Space mean speed for all vehicles,	S = 61.5	mph

---

Phone:  
E-mail:

Fax:

---

Diverge Analysis

---

Analyst: Point #1  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: 70 EB SR 42 Off  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	1720	vph	

---

Off Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	290	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1720	290		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	478	81		v
Trucks and buses	25	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2150	363	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.690 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 1595 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	2150	7200	No
$v_{FO} = v_F - v_R$	1787	7200	No
$v_R$	363	2000	No
$v_{3 \text{ or } av34}$	555 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 1595$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	1595	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L = 13.5 \text{ pc/mi/ln}$   
R 12 D  
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.461	
Space mean speed in ramp influence area,	S = 57.1	mph
Space mean speed in outer lanes,	S = 76.8	mph
Space mean speed for all vehicles,	S = 61.1	mph

---



**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

# 2010 PM Diverge HCS Analyses

Phone:  
E-mail:

Fax:

---

Diverge Analysis

---

Analyst: Point #20  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 WB  
 Junction: 70 WB US 42 Off  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	3080	vph

---

Off Ramp Data

---

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	640	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	3080	640		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	856	178		v
Trucks and buses	22	18		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.901	0.917	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3799	775	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.629 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2678$  pc/h  
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	3799	7200	No
$v_{FO} = v_F - v_R$	3024	7200	No
$v_R$	775	2000	No
$v_{3 \text{ or } av34}$	1121 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700$ pc/h?		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2678$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2678	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 22.8$  pc/mi/ln  
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	D = 0.498	
Space mean speed in ramp influence area,	S <sub>R</sub> = 56.1	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 76.3	mph
Space mean speed for all vehicles,	S = 60.8	mph

---

Phone:  
E-mail:

Fax:

---

Diverge Analysis

---

Analyst: Point #16  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 WB  
 Junction: 70 WB SR 29 Off  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	3330	vph	

---

Off Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	540	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway		Ramp		Adjacent Ramp
Volume, V (vph)	3330		540		vph
Peak-hour factor, PHF	0.90		0.90		
Peak 15-min volume, v15	925		150		v
Trucks and buses	20		18		%
Recreational vehicles	0		0		%
Terrain type:	Level		Level		
Grade	0.00	%	0.00	%	%
Length	0.00	mi	0.00	mi	mi
Trucks and buses PCE, ET	1.5		1.5		
Recreational vehicle PCE, ER	1.2		1.2		

Heavy vehicle adjustment, fHV	0.909	0.917	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	4070	654	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.628 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2800 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	4070	7200	No
$v_{FO} = v_F - v_R$	3416	7200	No
$v_R$	654	2000	No
$v_{3 \text{ or } 34}$	1270 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } 34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } 34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2800$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2800	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 23.8 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	D = 0.487	
Space mean speed in ramp influence area,	S <sub>R</sub> = 56.4	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 75.7	mph
Space mean speed for all vehicles,	S = 61.3	mph

---

Phone: Fax:  
E-mail:

Diverge Analysis

Analyst: Point #12  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: 70 WB SR 142 Off  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	3720	vph

Off Ramp Data

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	530	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	3720	530		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	1033	147		v
Trucks and buses	25	6		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00 %	0.00 %		%
Length	0.00 mi	0.00 mi		mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.971	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	4650	607	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.616 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 3097 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	4650	7200	No
$v_{FO} = v_F - v_R$	4043	7200	No
$v_R$	607	2000	No
$v_{3 \text{ or } 34}$	1553 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } 34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } 34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 3097$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	3097	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 26.4 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	D = 0.483	
Space mean speed in ramp influence area,	S <sub>R</sub> = 56.5	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 74.6	mph
Space mean speed for all vehicles,	S = 61.5	mph

---

Phone: Fax:  
E-mail:

Diverge Analysis

Analyst: Point #9  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: 70 EB SR 142 Off  
Jurisdiction:  
Analysis Year: 2010  
Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	2770	vph

Off Ramp Data

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	150	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2770	150		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	769	42		v
Trucks and buses	20	5		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00 %	0.00 %		%
Length	0.00 mi	0.00 mi		mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		



Heavy vehicle adjustment, fHV	0.909	0.976	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3386	171	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.667 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2317 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	3386	7200	No
$v_{FO} = v_F - v_R$	3215	7200	No
$v_R$	171	2000	No
$v_{3 \text{ or } av34}$	1069 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2317$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2317	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 19.7 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.443	
Space mean speed in ramp influence area,	S <sub>R</sub> = 57.6	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 76.5	mph
Space mean speed for all vehicles,	S = 62.5	mph

---

Phone:  
E-mail:

Fax:

---

Diverge Analysis

---

Analyst: Point #5  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: 70 EB SR 29 Off  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	2360	vph

---

Off Ramp Data

---

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	260	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2360	260		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	656	72		v
Trucks and buses	22	7		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.901	0.966	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2911	299	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.673 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2058 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	2911	7200	No
$v_{FO} = v_F - v_R$	2612	7200	No
$v_R$	299	2000	No
$v_{3 \text{ or } av34}$	853 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2058$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2058	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_R - 0.009 L_D = 17.5 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.455	
Space mean speed in ramp influence area,	S <sub>R</sub> = 57.3	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 76.8	mph
Space mean speed for all vehicles,	S = 61.9	mph

---

Roadway Engineering Services  
 ODOT  
 1980 West Broad Street

Phone: 614-387-1622  
 E-mail:

Fax:

Diverge Analysis

Analyst: Point #1  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: 70 EB SR 42 Off  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2320	vph	

Off Ramp Data

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	390	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2320	390		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	644	108		v
Trucks and buses	23	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.897	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2874	488	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.666 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2076 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	2874	7200	No
$v_{FO} = v_F - v_R$	2386	7200	No
$v_R$	488	2000	No
$v_{3 \text{ or } av34}$	798 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2076$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2076	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 17.6 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.472	
Space mean speed in ramp influence area,	S <sub>R</sub> = 56.8	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 76.8	mph
Space mean speed for all vehicles,	S = 61.2	mph

---

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

## 2030 AM Diverge HCS Analyses

Phone: Fax:  
 E-mail:

\_\_\_\_\_Diverge Analysis\_\_\_\_\_

Analyst: Point #20  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 WB  
 Junction: 70 WB US 42 Off  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	1830	vph

\_\_\_\_\_Off Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	480	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	1830	480		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	508	133		v
Trucks and buses	25	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2288	600	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)

EQ

P = 0.675 Using Equation 5

FD

$v_{12} = v_R + (v_F - v_R) P = 1740$  pc/h

12 R F R FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	2288	7200	No
$v_{FO} = v_F - v_R$	1688	7200	No
$v_R$	600	2000	No
$v_{3 \text{ or } av34}$	548 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700$ pc/h?		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 1740$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	1740	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 14.7$  pc/mi/ln

Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.482	
Space mean speed in ramp influence area,	S <sub>R</sub> = 56.5	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 76.8	mph
Space mean speed for all vehicles,	S = 60.3	mph

---



Phone: Fax:  
E-mail:

Diverge Analysis

Analyst: Point #16  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: 70 WB SR 29 Off  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	2450	vph

Off Ramp Data

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	750	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2450	750		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	681	208		v
Trucks and buses	25	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3063	938	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.640 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2299$  pc/h  
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{Fi} = v_F$	3063	7200	No
$v_{FO} = v_F - v_R$	2125	7200	No
$v_R$	938	2000	No
$v_{3 \text{ or } av34}$	764 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700$ pc/h?		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2299$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2299	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_R - 0.009 L_D = 19.5$  pc/mi/ln  
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.512	
Space mean speed in ramp influence area,	S = 55.7	mph
Space mean speed in outer lanes,	S = 76.8	mph
Space mean speed for all vehicles,	S = 59.8	mph

---

Phone:  
E-mail:

Fax:

---

Diverge Analysis

---

Analyst: Point #12  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: AM Peak  
 Freeway/Dir of Travel: I-70 WB  
 Junction: 70 WB SR 142 Off  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	2450	vph	

---

Off Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	270	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2450	270		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	681	75		v
Trucks and buses	25	6		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.971	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3063	309	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.669 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2152 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	3063	7200	No
$v_{FO} = v_F - v_R$	2754	7200	No
$v_R$	309	2000	No
$v_{3 \text{ or } av34}$	911 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2152$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2152	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_R - 0.009 L_D = 18.3 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.456	
Space mean speed in ramp influence area,	S = 57.2	mph
Space mean speed in outer lanes,	S = 76.8	mph
Space mean speed for all vehicles,	S = 61.9	mph

---

Phone: Fax:  
E-mail:

Diverge Analysis

Analyst: Point #9  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: 70 EB SR 142 Off  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	2810	vph

Off Ramp Data

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	300	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2810	300		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	781	83		v
Trucks and buses	25	4		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.980	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3513	340	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.657 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2423 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{Fi} = v_F$	3513	7200	No
$v_{FO} = v_F - v_R$	3173	7200	No
$v_R$	340	2000	No
$v_{3 \text{ or } av34}$	1090 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2423$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2423	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 20.6 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	D = 0.459	
Space mean speed in ramp influence area,	S <sub>R</sub> = 57.2	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 76.4	mph
Space mean speed for all vehicles,	S = 62.0	mph

---

Phone: Fax:  
E-mail:

Diverge Analysis

Analyst: Point #5  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: 70 EB SR 29 Off  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	2790	vph

Off Ramp Data

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	430	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2790	430		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	775	119		v
Trucks and buses	25	20		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.909	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3488	526	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.649 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2447$  pc/h  
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	3488	7200	No
$v_{FO} = v_F - v_R$	2962	7200	No
$v_R$	526	2000	No
$v_{3 \text{ or } av34}$	1041 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700$ pc/h?		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2447$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2447	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 20.8$  pc/mi/ln  
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	D = 0.475	
Space mean speed in ramp influence area,	S <sub>R</sub> = 56.7	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 76.6	mph
Space mean speed for all vehicles,	S = 61.5	mph

---



Phone: Fax:  
E-mail:

Diverge Analysis

Analyst: Point #1  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: AM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: 70 EB US 42 Off  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	2360	vph

Off Ramp Data

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	400	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	2360	400		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	656	111		v
Trucks and buses	25	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.889	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	2950	500	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.663 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2125 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	2950	7200	No
$v_{FO} = v_F - v_R$	2450	7200	No
$v_R$	500	2000	No
$v_{3 \text{ or } av34}$	825 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2125$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2125	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L = 18.0 \text{ pc/mi/ln}$   
R 12 D  
Level of service for ramp-freeway junction areas of influence B

---

Speed Estimation

---

Intermediate speed variable,	D = 0.473	
Space mean speed in ramp influence area,	S = 56.8	mph
Space mean speed in outer lanes,	S = 76.8	mph
Space mean speed for all vehicles,	S = 61.2	mph

---

**Interchange Modification Study  
IR-70 at SR 29  
MAD-70-10.27  
PID 83245**

---

2030 PM Diverge HCS Analyses

Phone: Fax:  
 E-mail:

\_\_\_\_\_Diverge Analysis\_\_\_\_\_

Analyst: Point #20  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 WB  
 Junction: 70 WB US 42 Off  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	4230	vph

\_\_\_\_\_Off Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	860	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	4230	860		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	1175	239		v
Trucks and buses	22	18		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.901	0.917	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	5217	1042	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.582 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 3470$  pc/h  
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	5217	7200	No
$v_{FO} = v_F - v_R$	4175	7200	No
$v_R$	1042	2000	No
$v_{3 \text{ or } 34}$	1747 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } 34} > 2700$ pc/h?		No	
Is $v_{3 \text{ or } 34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 3470$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	3470	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 29.6$  pc/mi/ln  
Level of service for ramp-freeway junction areas of influence D

---

Speed Estimation

---

Intermediate speed variable,	D = 0.522	
Space mean speed in ramp influence area,	S <sub>R</sub> = 55.4	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 73.9	mph
Space mean speed for all vehicles,	S = 60.5	mph

---

Phone: Fax:  
E-mail:

---

Operational Analysis

---

Analyst: point #19  
 Agency or Company: ODOT  
 Date Performed: 10/21/2009  
 Analysis Time Period: PM Peak  
 Freeway/Direction: I-70 WB  
 From/To: b/w US 42 and SR 29  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

---

Flow Inputs and Adjustments

---

Volume, V	4230	veh/h
Peak-hour factor, PHF	0.90	
Peak 15-min volume, v15	1175	v
Trucks and buses	22	%
Recreational vehicles	0	%
Terrain type:	Level	
Grade	0.00	%
Segment length	0.00	mi
Trucks and buses PCE, ET	1.5	
Recreational vehicle PCE, ER	1.2	
Heavy vehicle adjustment, fHV	0.901	
Driver population factor, fp	1.00	
Flow rate, vp	1739	pc/h/ln

---

Speed Inputs and Adjustments

---

Lane width	12.0	ft
Right-shoulder lateral clearance	6.0	ft
Interchange density	0.50	interchange/mi
Number of lanes, N	3	
Free-flow speed:	Measured	
FFS or BFFS	70.0	mi/h
Lane width adjustment, fLW	0.0	mi/h
Lateral clearance adjustment, fLC	0.0	mi/h
Interchange density adjustment, fID	0.0	mi/h
Number of lanes adjustment, fN	3.0	mi/h
Free-flow speed, FFS	70.0	mi/h
	Urban Freeway	

---

LOS and Performance Measures

---

Flow rate, vp	1739	pc/h/ln
Free-flow speed, FFS	70.0	mi/h
Average passenger-car speed, S	68.5	mi/h
Number of lanes, N	3	
Density, D	25.4	pc/mi/ln

Level of service, LOS

C

Overall results are not computed when free-flow speed is less than 55 mph.

Phone:  
E-mail:

Fax:

\_\_\_\_\_Diverge Analysis\_\_\_\_\_

Analyst: Point #16  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 WB  
Junction: 70 WB SR 29 Off  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	4670	vph	

\_\_\_\_\_Off Ramp Data\_\_\_\_\_

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	860	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	4670	860		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	1297	239		v
Trucks and buses	20	18		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		



Heavy vehicle adjustment, fHV	0.909	0.917	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	5708	1042	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)

EQ

P = 0.569 Using Equation 5

FD

$v_{12} = v_R + (v_F - v_R) P = 3699$  pc/h

12 R F R FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	5708	7200	No
$v_{FO} = v_F - v_R$	4666	7200	No
$v_R$	1042	2000	No
$v_{3 \text{ or } 34}$	2009 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } 34} > 2700$ pc/h?		No	
Is $v_{3 \text{ or } 34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 3699$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	3699	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_R - 0.009 L_D = 31.6$  pc/mi/ln

Level of service for ramp-freeway junction areas of influence D

---

Speed Estimation

---

Intermediate speed variable,	D = 0.522	
Space mean speed in ramp influence area,	S <sub>R</sub> = 55.4	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 72.9	mph
Space mean speed for all vehicles,	S = 60.5	mph

---

Phone:  
E-mail:

Fax:

---

Diverge Analysis

---

Analyst: Point #12  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 WB  
 Junction: 70 WB SR 142 Off  
 Jurisdiction:  
 Analysis Year: 2010  
 Description: MAD-70-10.27 PID 83245

---

Freeway Data

---

Type of analysis	Diverge		
Number of lanes in freeway	3		
Free-flow speed on freeway	70.0	mph	
Volume on freeway	5160	vph	

---

Off Ramp Data

---

Side of freeway	Right		
Number of lanes in ramp	1		
Free-Flow speed on ramp	35.0	mph	
Volume on ramp	770	vph	
Length of first accel/decel lane	500	ft	
Length of second accel/decel lane		ft	

---

Adjacent Ramp Data (if one exists)

---

Does adjacent ramp exist?	No		
Volume on adjacent ramp		vph	
Position of adjacent ramp			
Type of adjacent ramp			
Distance to adjacent ramp		ft	

---

Conversion to pc/h Under Base Conditions

---

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	5160	770		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	1433	214		v
Trucks and buses	19	2		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00 %	0.00 %		%
Length	0.00 mi	0.00 mi		mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.913	0.990	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	6278	864	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.563 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 3914$  pc/h  
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	6278	7200	No
$v_{FO} = v_F - v_R$	5414	7200	No
$v_R$	864	2000	No
$v_{3 \text{ or } av34}$	2364 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700$ pc/h?		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 3914$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	3914	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 33.4$  pc/mi/ln  
Level of service for ramp-freeway junction areas of influence D

---

Speed Estimation

---

Intermediate speed variable,	D = 0.506	
Space mean speed in ramp influence area,	S <sub>R</sub> = 55.8	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 71.5	mph
Space mean speed for all vehicles,	S = 60.9	mph

---

Phone: Fax:  
E-mail:

Diverge Analysis

Analyst: Point #9  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: 70 EB SR 142 Off  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	3860	vph

Off Ramp Data

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	310	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	3860	310		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	1072	86		v
Trucks and buses	20	5		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.909	0.976	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	4718	353	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)

EQ

P = 0.626 Using Equation 5

FD

$v_{12} = v_R + (v_F - v_R) P = 3085$  pc/h

12 R F R FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	4718	7200	No
$v_{FO} = v_{FO} - v_{R3}$	4365	7200	No
$v_{R3}$	353	2000	No
$v_{3 \text{ or } av34}$	1633 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700$ pc/h?		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 3085$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	3085	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 26.3$  pc/mi/ln

Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	D = 0.460	
Space mean speed in ramp influence area,	S <sub>R</sub> = 57.1	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 74.3	mph
Space mean speed for all vehicles,	S = 62.1	mph

---

Phone: Fax:  
 E-mail:

\_\_\_\_\_Diverge Analysis\_\_\_\_\_

Analyst: Point #5  
 Agency/Co.: ODOT  
 Date performed: 10/21/2009  
 Analysis time period: PM Peak  
 Freeway/Dir of Travel: I-70 EB  
 Junction: 70 EB SR 29 Off  
 Jurisdiction:  
 Analysis Year: 2030  
 Description: MAD-70-10.27 PID 83245

\_\_\_\_\_Freeway Data\_\_\_\_\_

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	3260	vph

\_\_\_\_\_Off Ramp Data\_\_\_\_\_

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	390	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

\_\_\_\_\_Adjacent Ramp Data (if one exists)\_\_\_\_\_

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

\_\_\_\_\_Conversion to pc/h Under Base Conditions\_\_\_\_\_

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	3260	390		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	906	108		v
Trucks and buses	22	7		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00	%	0.00	%
Length	0.00	mi	0.00	mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		

Heavy vehicle adjustment, fHV	0.901	0.966	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	4021	448	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.639 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2731 \text{ pc/h}$   
12 R F R FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_{12}$	4021	7200	No
$v_{FO} = v_{FO} - v_{R}$	3573	7200	No
$v_{R}$	448	2000	No
$v_{3 \text{ or } av34}$	1290 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2731$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2731	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L = 23.2 \text{ pc/mi/ln}$   
R 12 D  
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	D = 0.468	
Space mean speed in ramp influence area,	S = 56.9	mph
Space mean speed in outer lanes,	S = 75.7	mph
Space mean speed for all vehicles,	S = 61.8	mph

---

Phone: Fax:  
E-mail:

Diverge Analysis

Analyst: Point #1  
Agency/Co.: ODOT  
Date performed: 10/21/2009  
Analysis time period: PM Peak  
Freeway/Dir of Travel: I-70 EB  
Junction: 70 EB US 42 Off  
Jurisdiction:  
Analysis Year: 2030  
Description: MAD-70-10.27 PID 83245

Freeway Data

Type of analysis	Diverge	
Number of lanes in freeway	3	
Free-flow speed on freeway	70.0	mph
Volume on freeway	3210	vph

Off Ramp Data

Side of freeway	Right	
Number of lanes in ramp	1	
Free-Flow speed on ramp	35.0	mph
Volume on ramp	530	vph
Length of first accel/decel lane	500	ft
Length of second accel/decel lane		ft

Adjacent Ramp Data (if one exists)

Does adjacent ramp exist?	No	
Volume on adjacent ramp		vph
Position of adjacent ramp		
Type of adjacent ramp		
Distance to adjacent ramp		ft

Conversion to pc/h Under Base Conditions

Junction Components	Freeway	Ramp	Adjacent Ramp	
Volume, V (vph)	3210	530		vph
Peak-hour factor, PHF	0.90	0.90		
Peak 15-min volume, v15	892	147		v
Trucks and buses	23	25		%
Recreational vehicles	0	0		%
Terrain type:	Level	Level		
Grade	0.00 %	0.00 %		%
Length	0.00 mi	0.00 mi		mi
Trucks and buses PCE, ET	1.5	1.5		
Recreational vehicle PCE, ER	1.2	1.2		



Heavy vehicle adjustment, fHV	0.897	0.889	
Driver population factor, fP	1.00	1.00	
Flow rate, vp	3977	663	pcph

---

Estimation of V12 Diverge Areas

---

L = (Equation 25-8 or 25-9)  
EQ  
P = 0.630 Using Equation 5  
FD  
 $v_{12} = v_R + (v_F - v_R) P = 2751 \text{ pc/h}$   
FD

---

Capacity Checks

---

	Actual	Maximum	LOS F?
$v_{12} = v_F$	3977	7200	No
$v_{FO} = v_F - v_R$	3314	7200	No
$v_R$	663	2000	No
$v_{3 \text{ or } av34}$	1226 pc/h	(Equation 25-15 or 25-16)	
Is $v_{3 \text{ or } av34} > 2700 \text{ pc/h?}$		No	
Is $v_{3 \text{ or } av34} > 1.5 v_{12} / 2$		No	
If yes, $v_{12A} = 2751$		(Equation 25-18)	

---

Flow Entering Diverge Influence Area

---

	Actual	Max Desirable	Violation?
$v_{12}$	2751	4400	No

---

Level of Service Determination (if not F)

---

Density,  $D = 4.252 + 0.0086 v_{12} - 0.009 L_D = 23.4 \text{ pc/mi/ln}$   
Level of service for ramp-freeway junction areas of influence C

---

Speed Estimation

---

Intermediate speed variable,	D = 0.488	
Space mean speed in ramp influence area,	S <sub>R</sub> = 56.3	mph
Space mean speed in outer lanes,	S <sub>0</sub> = 75.9	mph
Space mean speed for all vehicles,	S = 61.2	mph

---

# Appendix E

## HCS Intersection Analyses















TWO-WAY STOP CONTROL SUMMARY

Analyst: ODOT  
 Agency/Co.:  
 Date Performed: 1/15/2010  
 Analysis Time Period: PM No Build  
 Intersection: I-70 WB Ramps/SR 29  
 Jurisdiction:  
 Units: U. S. Customary  
 Analysis Year: 2030  
 Project ID: MAD-70-10.27  
 East/West Street: I-70 WB Ramps  
 North/South Street: SR 29  
 Intersection Orientation: NS Study period (hrs): 0.25

Vehicle Volumes and Adjustments

Major Street:	Approach Movement	Northbound				Southbound			
		1 L	2 T	3 R	4   L	5 T	6 R		
Volume		400	210			250	20		
Peak-Hour Factor, PHF		0.90	0.90			0.90	0.90		
Hourly Flow Rate, HFR		444	233			277	22		
Percent Heavy Vehicles		12	--	--		--	--		
Median Type/Storage		Undivided				/			
RT Channelized?									
Lanes Configuration		0	1			1	0		
Upstream Signal?		No				No			

Minor Street:	Approach Movement	Westbound				Eastbound			
		7 L	8 T	9 R	10   L	11 T	12 R		
Volume		560	1	300					
Peak Hour Factor, PHF		0.90	0.90	0.90					
Hourly Flow Rate, HFR		622	1	333					
Percent Heavy Vehicles		18	18	18					
Percent Grade (%)		0				0			
Flared Approach: Exists?/Storage		No				/			
Lanes Configuration		0	1	0					
		LTR							

Delay, Queue Length, and Level of Service

Approach Movement	NB	SB	Westbound				Eastbound			
			1	4	7	8	9	10	11	12
Lane Config	LT					LTR				
v (vph)	444					956				
C(m) (vph)	1207					129				
v/c	0.37					7.41				
95% queue length	1.71					106.73				
Control Delay	9.7					2950				
LOS	A					F				
Approach Delay						2950				
Approach LOS						F				

TWO-WAY STOP CONTROL SUMMARY

Analyst: ODOT  
 Agency/Co.:  
 Date Performed: 1/15/2010  
 Analysis Time Period: AM No Build  
 Intersection: I-70 WB Ramps/SR 29  
 Jurisdiction:  
 Units: U. S. Customary  
 Analysis Year: 2030  
 Project ID: MAD-70-10.27  
 East/West Street: I-70 WB Ramps  
 North/South Street: SR 29  
 Intersection Orientation: NS Study period (hrs): 0.25

Vehicle Volumes and Adjustments

Major Street:	Approach Movement	Northbound				Southbound			
		1 L	2 T	3 R	4   L	5 T	6 R		
Volume		120	80			350	10		
Peak-Hour Factor, PHF		0.90	0.90			0.90	0.90		
Hourly Flow Rate, HFR		133	88			388	11		
Percent Heavy Vehicles		17	--	--		--	--		
Median Type/Storage		Undivided				/			
RT Channelized?									
Lanes Configuration		0	1			1	0		TR
Upstream Signal?			No			No			

Minor Street:	Approach Movement	Westbound				Eastbound			
		7 L	8 T	9 R	10   L	11 T	12 R		
Volume		680	1	70					
Peak Hour Factor, PHF		0.90	0.90	0.90					
Hourly Flow Rate, HFR		755	1	77					
Percent Heavy Vehicles		29	29	29					
Percent Grade (%)			0			0			
Flared Approach: Exists?/Storage				No	/			/	
Lanes Configuration		0	1	0					LTR

Delay, Queue Length, and Level of Service

Approach Movement	NB	SB	Westbound				Eastbound			
			1	4	7	8	9	10	11	12
Lane Config	LT					LTR				
v (vph)	133					833				
C(m) (vph)	1083					322				
v/c	0.12					2.59				
95% queue length	0.42					68.44				
Control Delay	8.8					748.1				
LOS	A					F				
Approach Delay						748.1				
Approach LOS						F				

TWO-WAY STOP CONTROL SUMMARY

Analyst: ODOT  
 Agency/Co.:  
 Date Performed: 1/15/2010  
 Analysis Time Period: PM No Build  
 Intersection: I-70 WB Ramps/SR 29  
 Jurisdiction:  
 Units: U. S. Customary  
 Analysis Year: 2010  
 Project ID: MAD-70-10.27  
 East/West Street: I-70 WB Ramps  
 North/South Street: SR 29  
 Intersection Orientation: NS Study period (hrs): 0.25

Vehicle Volumes and Adjustments

Major Street:	Approach Movement	Northbound				Southbound			
		1 L	2 T	3 R	4   L	5 T	6 R		
Volume		280	100			190	10		
Peak-Hour Factor, PHF		0.90	0.90			0.90	0.90		
Hourly Flow Rate, HFR		311	111			211	11		
Percent Heavy Vehicles		12	--	--		--	--		
Median Type/Storage		Undivided				/			
RT Channelized?									
Lanes		0	1			1	0		
Configuration		LT				TR			
Upstream Signal?		No				No			

Minor Street:	Approach Movement	Westbound				Eastbound			
		7 L	8 T	9 R	10   L	11 T	12 R		
Volume		340	1	200					
Peak Hour Factor, PHF		0.90	0.90	0.90					
Hourly Flow Rate, HFR		377	1	222					
Percent Heavy Vehicles		18	18	18					
Percent Grade (%)		0				0			
Flared Approach: Exists?/Storage		No				/			
Lanes		0	1	0					
Configuration		LTR							

Delay, Queue Length, and Level of Service

Approach	NB	SB	Westbound				Eastbound			
			1	4   7	8	9   10	11	12		
Movement	1	4	7	8	9	10	11	12		
Lane Config	LT			LTR						
v (vph)	311			600						
C(m) (vph)	1290			287						
v/c	0.24			2.09						
95% queue length	0.95			44.21						
Control Delay	8.7			531.3						
LOS	A			F						
Approach Delay				531.3						
Approach LOS				F						

---

 TWO-WAY STOP CONTROL SUMMARY
 

---

Analyst: ODOT  
 Agency/Co.:  
 Date Performed: 1/15/2010  
 Analysis Time Period: AM No Build  
 Intersection: I-70 WB Ramps/SR 29  
 Jurisdiction:  
 Units: U. S. Customary  
 Analysis Year: 2010  
 Project ID: MAD-70-10.27  
 East/West Street: I-70 WB Ramps  
 North/South Street: SR 29  
 Intersection Orientation: NS Study period (hrs): 0.25

---

 Vehicle Volumes and Adjustments
 

---

Major Street:	Approach Movement	Northbound				Southbound		
		1 L	2 T	3 R	4   L	5 T	6 R	
Volume		80	60			330	10	
Peak-Hour Factor, PHF		0.90	0.90			0.90	0.90	
Hourly Flow Rate, HFR		88	66			366	11	
Percent Heavy Vehicles		17	--	--		--	--	
Median Type/Storage		Undivided				/		
RT Channelized?								
Lanes		0	1			1	0	
Configuration		LT				TR		
Upstream Signal?		No				No		

Minor Street:	Approach Movement	Westbound				Eastbound		
		7 L	8 T	9 R	10   L	11 T	12 R	
Volume		400	1	70				
Peak Hour Factor, PHF		0.90	0.90	0.90				
Hourly Flow Rate, HFR		444	1	77				
Percent Heavy Vehicles		29	29	29				
Percent Grade (%)		0				0		
Flared Approach: Exists?/Storage				No	/		/	
Lanes		0	1	0				
Configuration		LTR						

---

 Delay, Queue Length, and Level of Service
 


---

Approach Movement	NB 1	SB 4	Westbound			Eastbound		
			7	8	9	10	11	12
Lane Config	LT			LTR				
v (vph)	88			522				
C(m) (vph)	1104			417				
v/c	0.08			1.25				
95% queue length	0.26			22.02				
Control Delay	8.5			160.1				
LOS	A			F				
Approach Delay				160.1				
Approach LOS				F				

---

## Appendix F

# Sidra Intersection Analyses



# MOVEMENT SUMMARY

Site: 2030 PM WB Ramp

2030 PM WB Ramp (Dual Lanes)  
 Roundabout  
 Design Life Analysis (Practical Capacity): Results for 0 years

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: NB SR 29											
3L	L	435	12.0	0.286	5.8	LOS A	0.0	0.0	0.00	0.75	30.2
8T	T	228	12.0	0.286	5.8	LOS A	0.0	0.0	0.00	0.46	41.5
Approach		663	12.0	0.286	5.8	LOS A	0.0	0.0	0.00	0.65	33.1
East: I-70 WB Off Ramp											
1L	L	609	18.0	0.870	33.8	LOS C	5.9	168.2	0.74	1.14	18.0
6T	T	1	18.0	0.870	33.8	LOS C	5.9	168.2	0.74	1.04	18.5
6R	R	326	18.0	0.227	0.0	X	X	X	X	0.43	34.7
Approach		936	18.0	0.870	22.0	LOS C	5.9	168.2	0.48	0.90	21.4
North: SB SR 29											
4T	T	272	7.0	0.315	12.8	LOS B	1.0	26.6	0.70	0.86	29.8
4R	R	22	7.0	0.315	12.5	LOS B	1.0	25.9	0.69	0.87	26.5
Approach		293	7.0	0.315	12.8	LOS B	1.0	26.6	0.69	0.86	29.5
All Vehicles		1892	14.2	0.870	14.9	LOS B	5.9	168.2	0.35	0.81	25.6

X: Not applicable for Continuous movement.

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Signalised Intersections.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.


# LEVEL OF SERVICE SUMMARY

Site: 2030 PM WB Ramp

2030 PM WB Ramp (Dual Lanes)

Roundabout

Design Life Analysis (Practical Capacity): Results for 0 years



	South	East	North	West	Intersection
LOS	A	C	B	NA	B

X: Not applicable for Continuous lane.

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Signalised Intersections.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 2010).

HCM Delay Model used. Geometric Delay not included.



Processed: Tuesday, December 20, 2011 8:47:08 AM  
SIDRA INTERSECTION 5.1.8.2059

Copyright © 2000-2011 Akcelik and Associates Pty Ltd  
www.sidrasolutions.com

Project: X:\STUDIES\Projects\MAD-70-10.27; PID 83245\Revised IMS - HLM\SIDRA Revisions  
\MAD\_70\_SR29\_IMS\_Final - HLM.sip  
8000751, OHIO DEPARTMENT OF TRANSPORTATION, SINGLE



# MOVEMENT SUMMARY

Site: 2030 AM WB Ramp

2030 AM WB Ramp (Dual Lanes)

Roundabout

Design Life Analysis (Practical Capacity): Results for 0 years

Movement Performance - Vehicles												
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph	
South: NB SR 29												
3L	L	130	17.0	0.098	4.1	LOS A	0.0	0.0	0.00	0.74	30.2	
8T	T	87	17.0	0.098	4.1	LOS A	0.0	0.0	0.00	0.47	41.5	
Approach		217	17.0	0.098	4.1	LOS A	0.0	0.0	0.00	0.63	33.6	
East: I-70 WB Off Ramp												
1L	L	739	29.0	0.858	27.8	LOS C	5.8	177.3	0.52	0.86	19.4	
6T	T	1	29.0	0.858	27.8	LOS C	5.8	177.3	0.52	0.67	20.3	
6R	R	76	29.0	0.057	0.0	X	X	X	X	0.43	34.8	
Approach		816	29.0	0.858	25.2	LOS C	5.8	177.3	0.47	0.82	20.2	
North: SB SR 29												
4T	T	380	7.0	0.396	14.0	LOS B	1.4	36.6	0.70	0.87	29.1	
4R	R	11	7.0	0.396	13.7	LOS B	1.4	35.6	0.69	0.88	26.0	
Approach		391	7.0	0.396	14.0	LOS B	1.4	36.6	0.70	0.87	29.0	
All Vehicles		1425	21.1	0.858	18.9	LOS B	5.8	177.3	0.46	0.81	23.5	

X: Not applicable for Continuous movement.

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Signalised Intersections.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.


# LEVEL OF SERVICE SUMMARY

Site: 2030 AM WB Ramp

2030 AM WB Ramp (Dual Lanes)

Roundabout

Design Life Analysis (Practical Capacity): Results for 0 years



	South	East	North	West	Intersection
LOS	A	C	B	NA	B

X: Not applicable for Continuous lane.

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Signalised Intersections.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 2010).


HCM Delay Model used. Geometric Delay not included.

Processed: Tuesday, December 20, 2011 8:47:06 AM  
SIDRA INTERSECTION 5.1.8.2059

Copyright © 2000-2011 Akcelik and Associates Pty Ltd  
www.sidrasolutions.com

Project: X:\STUDIES\Projects\MAD-70-10.27; PID 83245\Revised IMS - HLM\SIDRA Revisions  
\MAD\_70\_SR29\_IMS\_Final - HLM.sip  
8000751, OHIO DEPARTMENT OF TRANSPORTATION, SINGLE





# MOVEMENT SUMMARY

Site: 2010 PM WB Ramp

2010 PM WB Ramp (Single Lane)  
 Roundabout  
 Design Life Analysis (Practical Capacity): Results for 20 years

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: NB SR 29											
3L	L	304	12.0	0.409	8.1	LOS A	0.0	0.0	0.00	0.79	30.2
8T	T	109	12.0	0.409	8.1	LOS A	0.0	0.0	0.00	0.42	41.6
Approach		413	12.0	0.409	8.1	LOS A	0.0	0.0	0.00	0.69	32.4
East: I-70 WB Off Ramp											
1L	L	370	18.0	0.615	18.1	LOS C	3.2	90.5	0.66	0.97	22.1
6T	T	1	18.0	0.615	18.1	LOS C	3.2	90.5	0.66	0.83	23.5
6R	R	217	18.0	0.152	0.0	X	X	X	X	0.44	34.7
Approach		588	18.0	0.615	11.4	LOS B	3.2	90.5	0.42	0.78	25.3
North: SB SR 29											
4T	T	207	7.0	0.448	15.6	LOS C	1.8	48.7	0.68	0.88	28.3
4R	R	11	7.0	0.448	15.6	LOS C	1.8	48.7	0.68	0.90	25.1
Approach		217	7.0	0.448	15.6	LOS C	1.8	48.7	0.68	0.88	28.1
All Vehicles		1218	14.0	0.615	11.0	LOS B	3.2	90.5	0.32	0.77	27.9

X: Not applicable for Continuous movement.

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).


Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

# LEVEL OF SERVICE SUMMARY

Site: 2010 PM WB Ramp

2010 PM WB Ramp (Single Lane)  
 Roundabout  
 Design Life Analysis (Practical Capacity): Results for 20 years



	South	East	North	West	Intersection
LOS	A	B	C	NA	B

X: Not applicable for Continuous lane.

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 2010).

HCM Delay Model used. Geometric Delay not included.

Processed: Tuesday, December 20, 2011 8:47:05 AM  
SIDRA INTERSECTION 5.1.8.2059

Copyright © 2000-2011 Akcelik and Associates Pty Ltd  
www.sidrasolutions.com

Project: X:\STUDIES\Projects\MAD-70-10.27; PID 83245\Revised IMS - HLM\SIDRA Revisions  
\MAD\_70\_SR29\_IMS\_Final - HLM.sip  
8000751, OHIO DEPARTMENT OF TRANSPORTATION, SINGLE





# MOVEMENT SUMMARY

Site: 2010 AM WB Ramp

2010 AM WB Ramp (Single Lane)  
 Roundabout  
 Design Life Analysis (Practical Capacity): Results for 20 years

Movement Performance - Vehicles												
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph	
South: NB SR 29												
3L	L	87	17.0	0.158	5.2	LOS A	0.0	0.0	0.00	0.84	30.2	
8T	T	65	17.0	0.158	5.2	LOS A	0.0	0.0	0.00	0.43	41.6	
Approach		152	17.0	0.158	5.2	LOS A	0.0	0.0	0.00	0.67	34.0	
East: I-70 WB Off Ramp												
1L	L	435	29.0	0.595	14.8	LOS B	2.6	79.4	0.45	0.72	23.2	
6T	T	1	29.0	0.595	14.8	LOS B	2.6	79.4	0.45	0.49	25.2	
6R	R	76	29.0	0.057	0.0	X	X	X	X	0.44	34.7	
Approach		512	29.0	0.595	12.6	LOS B	2.6	79.4	0.38	0.68	24.4	
North: SB SR 29												
4T	T	359	7.0	0.680	22.9	LOS C	4.1	107.0	0.77	0.98	24.5	
4R	R	11	7.0	0.680	22.9	LOS C	4.1	107.0	0.77	1.02	22.2	
Approach		370	7.0	0.680	22.9	LOS C	4.1	107.0	0.77	0.98	24.5	
All Vehicles		1034	19.4	0.680	15.2	LOS C	4.1	107.0	0.46	0.79	25.5	

X: Not applicable for Continuous movement.

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).


Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.

# LEVEL OF SERVICE SUMMARY

Site: 2010 AM WB Ramp

2010 AM WB Ramp (Single Lane)  
 Roundabout  
 Design Life Analysis (Practical Capacity): Results for 20 years



	South	East	North	West	Intersection
LOS	A	B	C	NA	C

X: Not applicable for Continuous lane.

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Sign Control.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 2010).

HCM Delay Model used. Geometric Delay not included.

Processed: Tuesday, December 20, 2011 8:47:03 AM  
SIDRA INTERSECTION 5.1.8.2059

Copyright © 2000-2011 Akcelik and Associates Pty Ltd  
www.sidrasolutions.com



Project: X:\STUDIES\Projects\MAD-70-10.27; PID 83245\Revised IMS - HLM\SIDRA Revisions  
\MAD\_70\_SR29\_IMS\_Final - HLM.sip  
8000751, OHIO DEPARTMENT OF TRANSPORTATION, SINGLE

# MOVEMENT SUMMARY

Site: 2030 PM EB Ramps

2030 PM EB Ramp (Dual Lane)

Roundabout

Design Life Analysis (Practical Capacity): Results for 0 years

Movement Performance - Vehicles											
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph
South: NB SR 29											
8T	T	641	12.0	0.631	12.6	LOS B	3.9	105.5	0.52	0.56	26.5
8R	R	913	12.0	0.899	29.5	LOS C	13.5	371.1	0.84	0.89	18.8
Approach		1554	12.0	0.899	22.5	LOS C	13.5	371.1	0.71	0.75	21.3
North: SB SR 29											
7L	L	163	12.0	0.444	7.6	LOS A	0.0	0.0	0.00	0.93	26.1
4T	T	913	12.0	0.444	7.6	LOS A	0.0	0.0	0.00	0.22	29.8
Approach		1076	12.0	0.444	7.6	LOS A	0.0	0.0	0.00	0.33	29.1
West: I-70 EB Off Ramp											
5L	L	22	7.0	0.038	6.4	LOS A	0.1	2.5	0.54	0.85	25.0
2T	T	1	7.0	0.038	6.4	LOS A	0.1	2.5	0.54	0.65	27.7
2R	R	402	7.0	0.641	18.6	LOS B	2.6	69.1	0.72	0.94	22.2
Approach		425	7.0	0.641	18.0	LOS B	2.6	69.1	0.71	0.93	22.3
All Vehicles		3055	11.3	0.899	16.6	LOS B	13.5	371.1	0.46	0.63	23.8

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Signalised Intersections.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.

HCM Delay Model used. Geometric Delay not included.


# LEVEL OF SERVICE SUMMARY

Site: 2030 PM EB Ramps

2030 PM EB Ramp (Dual Lane)

Roundabout

Design Life Analysis (Practical Capacity): Results for 0 years



	South	East	North	West	Intersection
LOS	C	NA	A	B	B

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Signalised Intersections.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.


LOS F will result if v/c > irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 2010).

HCM Delay Model used. Geometric Delay not included.

Project: X:\STUDIES\Projects\MAD-70-10.27; PID 83245\Revised IMS - HLM\SIDRA Revisions  
\MAD\_70\_SR29\_IMS\_Final - HLM.sip  
8000751, OHIO DEPARTMENT OF TRANSPORTATION, SINGLE





# MOVEMENT SUMMARY

Site: 2030 AM EB Ramp

2030 AM EB Ramp (Dual Lane)

Roundabout

Design Life Analysis (Practical Capacity): Results for 20 years

Movement Performance - Vehicles												
Mov ID	Turn	Demand Flow veh/h	HV %	Deg. Satn v/c	Average Delay sec	Level of Service	95% Back of Queue Vehicles veh	Queue Distance ft	Prop. Queued	Effective Stop Rate per veh	Average Speed mph	
South: NB SR 29												
8T	T	196	17.0	0.208	5.9	LOS A	0.7	19.8	0.36	0.47	30.7	
8R	R	283	17.0	0.300	7.0	LOS A	1.1	30.9	0.39	0.57	27.3	
Approach		478	17.0	0.300	6.5	LOS A	1.1	30.9	0.38	0.53	28.5	
North: SB SR 29												
7L	L	207	17.0	0.475	8.2	LOS A	0.0	0.0	0.00	0.89	26.1	
4T	T	913	17.0	0.475	8.2	LOS A	0.0	0.0	0.00	0.22	29.8	
Approach		1120	17.0	0.475	8.2	LOS A	0.0	0.0	0.00	0.35	29.0	
West: I-70 EB Off Ramp												
5L	L	22	20.0	0.044	7.6	LOS A	0.1	2.8	0.56	0.85	24.5	
2T	T	1	20.0	0.044	7.6	LOS A	0.1	2.8	0.56	0.67	27.1	
2R	R	446	20.0	0.823	34.5	LOS C	3.9	112.0	0.78	1.11	17.6	
Approach		468	20.0	0.823	33.2	LOS C	3.9	112.0	0.77	1.10	17.9	
All Vehicles		2066	17.7	0.823	13.5	LOS B	3.9	112.0	0.26	0.56	25.4	

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Signalised Intersections.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 2010).

Roundabout Capacity Model: US HCM 2010.


HCM Delay Model used. Geometric Delay not included.



# LEVEL OF SERVICE SUMMARY

Site: 2030 AM EB Ramp

2030 AM EB Ramp (Dual Lane)  
 Roundabout  
 Design Life Analysis (Practical Capacity): Results for 20 years



	South	East	North	West	Intersection
LOS	A	NA	A	C	B

Level of Service (LOS) Method: Delay & v/c (HCM 2010).

Roundabout LOS Method: Same as Signalised Intersections.

Lane LOS values are based on average delay and v/c ratio (degree of saturation) per lane.

LOS F will result if v/c > irrespective of lane delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all lanes (v/c not used as specified in HCM 2010).

HCM Delay Model used. Geometric Delay not included.

Project: X:\STUDIES\Projects\MAD-70-10.27; PID 83245\Revised IMS - HLM\SIDRA Revisions  
MAD\_70\_SR29\_IMS\_Final - HLM.sip  
8000751, OHIO DEPARTMENT OF TRANSPORTATION, SINGLE



## Appendix G

# Turn Lane Length Analyses

## Queue Analysis for EB Off Ramp, L&D Manual, Figure 401-10

### AM Conditions

- 2010 (Opening Day) Volumes for EB Off Ramp: 20 L, 260 R
- Unsignalized stop, assume 60 cycles/hour

#### Left Turn Analysis:

- Avg. vehicles/cycle =  $20 \text{ vehicles/hour} \times 1 \text{ hour}/60 \text{ cycles}$   
= 1 vehicles/cycle
- Using Figure 401-10, the queue length is 50 feet

#### Right Turn Analysis:

- Avg. vehicles/cycle =  $260 \text{ vehicles/hour} \times 1 \text{ hour}/60 \text{ cycles}$   
= 5 vehicles/cycle
- Using Figure 401-10, the queue length is 200 feet\* Controls

### PM Conditions

- 2010 (Opening Day) Volumes for EB Off Ramp: 20 L, 240 R
- Unsignalized stop, assume 60 cycles/hour

#### Left Turn Analysis:

- Avg. vehicles/cycle =  $20 \text{ vehicles/hour} \times 1 \text{ hour}/60 \text{ cycles}$   
= 1 vehicles/cycle
- Using Figure 401-10, the queue length is 50 feet

#### Right Turn Analysis:

- Avg. vehicles/cycle =  $240 \text{ vehicles/hour} \times 1 \text{ hour}/60 \text{ cycles}$   
= 4 vehicles/cycle
- Using Figure 401-10, the queue length is 175 feet

## Turn Lane Length Determination for EB Off Ramp, L&D Manual, Figure 401-9

### Conditions:

- Use AM conditions (controlling condition)
- Unsignalized Stopped Crossroad
- Condition A (ramp, provide storage only)
- Design for Left turn lane as per L&D Manual, Section 503.7 (minor movement)

Turn Lane Length = 50' (taper) + Storage Length = 50' + 50' = 100 feet

However, to avoid blockage from Right turn lane queue, Left turn lane length will need to provide 200' of storage.

**Left Turn Lane Length = 50' (taper) + 200' = 250 feet**

## Turn Lane Length Determination for WB Off Ramp, Sidra Output

### Conditions:

- Use maximum queue (opening day vs. design year) to provide maximum storage on opening day and minimize future ramp construction.
- From Sidra, the maximum left turn queue is 178 feet. Round to 180 feet.

**Bypass Lane Length = Left Lane Queue + 50' = 180' + 50' = 230 feet**