SHEET NUM.												PART.		ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
				3	4	5	7	8	13	14		01/S>2/PV/YOUN	02/S>2/OT/YOUN		EXT	TOTAL			
																		ROADWAY	
							3,581	1,237					4,818	202	30000	4,818	SF	WALK REMOVED	
							16						16	202	32000	16	FT	CURB REMOVED	
				40									40	203	10000	40	CY	EXCAVATION (FOR PAVEMENT REPAIR)	
							484	50					534	608	10000	534	SF	4" CONCRETE WALK	
							3,097	1,187					4,284	608	52000	4,284	SF	CURB RAMP	
				4								4		623	39501	4	EACH	MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN	3
																		EROSION CONTROL	
												3,000		832	30000	3,000	EACH	EROSION CONTROL	
																		DRAINAGE	
				5								5		611	98630	5	EACH	CATCH BASIN ADJUSTED TO GRADE	
							3	1					4	611	99654	4	EACH	MANHOLE ADJUSTED TO GRADE	
				30								30		611	99655	30	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	3
																		PAVEMENT	
				1,500									1,500	251	01000	1,500	SY	PARTIAL DEPTH PAVEMENT REPAIR (441)	
				1,200									1,200	252	01500	1,200	FT	FULL DEPTH PAVEMENT SAWING	
				200									200	253	01000	200	SY	PAVEMENT REPAIR	
									58,781			58,781		254	01000	58,781	SY	PAVEMENT PLANING, ASPHALT CONCRETE (T = 2 1/2")	
				40									40	304	20000	40	CY	AGGREGATE BASE (FOR PAVEMENT REPAIR)	
									7,643			7,643		407	20000	7,643	GAL	NON-TRACKING TACK COAT	
									1,633			1,633		424	12001	1,633	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, AS PER PLAN	3
									2,450			2,450		826	10500	2,450	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448), FIBER TYPE C	
																		WATER WORK	
							1						1	638	10800	1	EACH	VALVE BOX ADJUSTED TO GRADE	
				20								20		638	10801	20	EACH	VALVE BOX ADJUSTED TO GRADE, AS PER PLAN	3
																		TRAFFIC CONTROL	
										1.72		1.72		646	10110	1.72	MILE	LANE LINE, 6"	
										2.38		2.38		646	10200	2.38	MILE	CENTER LINE	
										1,370		1,370		646	10300	1,370	FT	CHANNELIZING LINE, 8"	
										175		175		646	10400	175	FT	STOP LINE	
										289		289		646	10500	289	FT	CROSSWALK LINE	
										41		41		646	20300	41	EACH	LANE ARROW	
										50		50		646	20504	50	FT	DOTTED LINE, 6"	
																		TRAFFIC SIGNALS	
						5						5		632	26501	5	EACH	DETECTOR LOOP, AS PER PLAN	5
																		MAINTENANCE OF TRAFFIC	
					200							200		614	11110	200	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
					40							40		614	12460	40	EACH	WORK ZONE MARKING SIGN	
					10							10		614	13000	10	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
						12						12		614	18601	12	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	5
					3.44							3.44		614	20100	3.44	MILE	WORK ZONE LANE LINE, CLASS I, 4", 642 PAINT	
					1.72							1.72		614	20550	1.72	MILE	WORK ZONE LANE LINE, CLASS III, 4", 642 PAINT	
					4.76							4.76		614	21100	4.76	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
					2.38							2.38		614	21550	2.38	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
					2,570							2,570		614	23200	2,570	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 8", 642 PAINT	
					1,285							1,285		614	23680	1,285	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT	
					350							350		614	26200	350	FT	WORK ZONE STOP LINE, CLASS I, 642 PAINT	
					175							175		614	26610	175	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
																		INCIDENTALS	
												LUMP		614	11000	LS		MAINTAINING TRAFFIC	
												6		619	16010	6	MNTH	FIELD OFFICE, TYPE B	
												LUMP		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
												LUMP		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER MJP

REVIEWER MAC 6-8-21

PROJECT ID 106537

SHEET P.6 TOTAL 14

MAH-62/7-13.15/11.26

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 9/28/2021 TIME: 2:46:44 PM USER: mpallagan
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 04\Mahoning\106537\400-Engineering\Roadway\Sheets\106537_GG001.dgn