ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS

USE OF LAW ENFORCEMENT OFFICERS (LEOS) BY CONTRACTORS OTHER THAN THE USES SPECIFIED BELOW WILL NOT BE PERMITTED AT PROJECT COST. LEOS SHOULD NOT BE USED WHERE THE OMUTCD INTENDS THAT FLAGGERS BE USED.

IN ADDITION TO THE REQUIREMENTS OF C&MS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHALL BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS:

DURING THE ENTIRE ADVANCE PREPARATION AND CLOSURE SEQUENCE WHERE COMPLETE BLOCKAGE OF TRAFFIC IS REQUIRED.

IN ADDITION TO THE REQUIREMENT OF C&MS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHOULD BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS AS APPROVED BY THE ENGINEER:

FOR LANE CLOSURES: DURING INITIAL SET-UP PERIODS, TEAR DOWN PERIODS, SUBSTANTIAL SHIFTS OF A CLOSURE POINT OR WHEN NEW LANE CLOSURE ARRANGEMENTS ARE INITIATED FOR LONG-TERM LANE CLOSURES/SHIFTS (FOR THE FIRST AND LAST DAY OF MAJOR CHANGES IN TRAFFIC CONTROL SETUP).

IN GENERAL, LEOS SHOULD BE POSITIONED IN ADVANCE OF AND ON THE SAME SIDE AS THE LANE RESTRICTION (OR AT THE POINT OF ROAD CLOSURE), AND TO MANUALLY CONTROL TRAFFIC MOVEMENTS THROUGH SIGNALIZED INTERSECTIONS IN WORK ZONES.

LEOS SHOULD NOT FORGO THEIR TRAFFIC CONTROL RESPONSIBILITIES TO APPREHEND MOTORISTS FOR ROUTINE TRAFFIC VIOLATIONS. HOWEVER, IF A MOTORIST'S ACTIONS ARE CONSIDERED TO BE RECKLESS, THEN PURSUIT OF THE MOTORIST IS APPROPRIATE.

THE LEOS WORK AT THE DIRECTION OF THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE SERVICES OF THE LEOS WITH THE APPROPRIATE AGENCIES AND COMMUNICATING THE INTENTIONS OF THE PLANS WITH RESPECT TO DUTIES OF THE LEOS. THE ENGINEER SHALL HAVE FINAL CONTROL OVER THE LEOS' DUTIES AND PLACEMENT, AND WILL RESOLVE ANY ISSUES THAT MAY ARISE BETWEEN THE TWO PARTIES.

ENSURE PROVIDED LEOS HAVE BEEN TRAINED APPROPRIATE TO THE JOB DECISIONS THEY ARE REQUIRED TO MAKE WHILE ON THE PROJECT, IN ACCORDANCE WITH C&MS 614.03.

THE LEO SHALL REPORT IN TO THE CONTRACTOR PRIOR TO THE START OF THE SHIFT, IN ORDER TO RECEIVE INSTRUCTIONS REGARDING SPECIFIC WORK ASSIGNMENTS DURING HIS/HER SHIFT. THE LEO IS EXPECTED TO STAY AT THE PROJECT SITE FOR THE ENTIRE DURATION OF HIS/HER SHIFT. THE LEO SHALL REPORT TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT. SHOULD IT BE NECESSARY TO LEAVE THE PROJECT SITE, THE LEO SHALL NOTIFY THE ENGINEER. THE CONTRACTOR SHALL PROVIDE THE LEO WITH A TWO-WAY COMMUNICATION DEVICE THAT SHALL BE RETURNED TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT.

LEOS (WITH PATROL CAR) REQUIRED BY THE TRAFFIC MAINTENANCE TASKS ABOVE SHALL BE PAID FOR ON A UNIT PRICE (HOURLY) BASIS UNDER ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE 300 HOURS

THE HOURS PAID SHALL INCLUDE ANY MINIMUM SHOW-UP TIME REQUIRED BY THE LAW ENFORCEMENT AGENCY INVOLVED.

ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE) INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES OF A LEO ARE INCLUDED WITH THE BID UNIT PRICE FOR ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE.

WORK ZONE INCREASED PENALTIES SIGN (R11-H5A)

R11-H5A-48 SIGNS SHALL BE FURNISHED, ERECTED, AND MAINTAINED IN GOOD CONDITION AND/OR REPLACED AS NECESSARY AND SUBSEQUENTLY REMOVED BY THE CONTRACTOR. SIGNS SHALL BE MOUNTED AT THE APPROPRIATE OFFSETS AND ELEVATIONS AS PRESCRIBED BY THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. THEY SHALL BE MAINTAINED ON SUPPORTS MEETING CURRENT SAFETY CRITERIA.

THE SIGNS MAY BE ERECTED OR UNCOVERED NO MORE THAN FOUR HOURS BEFORE THE ACTUAL START OF WORK. THE SIGNS SHALL BE REMOVED OR COVERED NO LATER THAN FOUR HOURS FOLLOWING RESTORATION OF ALL LANES TO TRAFFIC WITH NO RESTRICTIONS. OR SOONER AS DIRECTED BY THE ENGINEER. TEMPORARY SIGN COVERING AND UNCOVERING DUE TO TEMPORARY LANE RESTORATIONS SHALL BE GUIDED BY THE FOUR-HOUR LIMITATIONS STATED ABOVE. SUCH LANE RESTORATIONS SHOULD BE EXPECTED TO REMAIN IN EFFECT FOR 30 OR MORE CONSECUTIVE CALENDAR DAYS, SUCH AS DURING WINTER SHUT-DOWNS.

THE SIGNS ON THE MAINLINE SHALL BE DUAL MOUNTED UNLESS NOT PHYSICALLY POSSIBLE. THE FIRST SIGN SHALL BE PLACED BETWEEN THE ROAD WORK AHEAD (W20-1) SIGN AND THE NEXT SIGN IN THE SEQUENCE. SIGNS SHALL BE ERECTED ON EACH ENTRANCE RAMP AND EVERY 2 MILES THROUGH THE CONSTRUCTION WORK LIMITS. SIGNS ON THE MAINLINE SHALL BE R11-H5A-48. SIGNS USED ON THE RAMPS SHALL BE R11-H5A-24. R11-H5A-24 SIGNS MAY BE USED IN THE MEDIAN IN LIEU OF R11-H5A-48 SIGNS IF IT IS NOT PHYSICALLY POSSIBLE TO PROVIDE R11-H5A-48 SIGNS IN THE MEDIAN.

THE R11-H5A-48 SIGNS SHALL BE MOUNTED ON 2 NO. 3 POSTS WHEN LOCATED WITHIN CLEAR ZONES.

THE CONTRACTOR MAY USE SIGNS AND SUPPORTS IN USED, BUT GOOD, CONDITION PROVIDED THE SIGNS MEET CURRENT ODOT SPECIFICATIONS. SIGN FACES SHALL BE RETROREFLECTORIZED WITH TYPE G SHEETING COMPLYING WITH THE REQUIREMENTS OF C&MS 730.19.

WORK ZONE INCREASED PENALTIES SIGNS AND SUPPORTS WILL BE MEASURED AS THE NUMBER OF SIGN INSTALLATIONS, INCLUDING THE SIGN AND NECESSARY SUPPORTS. IF A SIGN AND SUPPORT COMBINATION IS REMOVED AND REERECTED AT ANOTHER LOCATION AS DIRECTED BY THE ENGINEER, IT SHALL BE CONSIDERED ANOTHER UNIT.

PAYMENT FOR ACCEPTED QUANTITIES, COMPLETE, IN PLACE WILL BE MADE AT THE CONTRACT UNIT PRICE. PAYMENT SHALL BE FULL COMPENSATION FOR ALL MATERIALS, LABOR, INCIDENTALS AND EQUIPMENT FOR FURNISHING, ERECTING, MAINTAINING, COVERING DURING SUSPENSION OF WORK, AND REMOVAL OF THE SIGN AND SUPPORT.

3 EACH

ITEM 614, WORK ZONE INCREASED PENALTIES SIGN

WORK ZONE INCREASED PENALTIES SIGNS WILL BE PLACED AT THE **FOLLOWING LOCATIONS:**

- IN ADVANCE OF THE WORK ZONE ON IR-680 NB - IN ADVANCE OF THE WORK ZONE ON IR-680 NB ENTRANCE RAMP FROM US-224 WB (RAMP W)

DUST CONTROL

THE CONTRACTOR SHALL FURNISH AND APPLY WATER FOR DUST CONTROL AS DIRECTED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED FOR DUST CONTROL PURPOSES:

ITEM 616, WATER <u>50</u> M. GAL.

ITEM 614, WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN

WORK ZONE RAISED PAVEMENT MARKERS, AS PER PLAN, AND THEIR INSTALLATION SHALL CONFORM TO C&MS 614 OR C&MS 621 AS SPECIFIED HEREIN.

RAISED PAVEMENT MARKERS IN USE DURING THE SNOW-PLOWING SEASON SHALL CONFORM TO 621.

RAISED PAVEMENT MARKERS IN USE DURING THE NON-SNOW-PLOW SEASON SHALL CONFORM TO EITHER 614 OR TO 621.

THE SNOW-PLOWING SEASON SHALL RUN FROM OCTOBER 15 THROUGH MARCH 31.

IF PROJECT DELAYS, NOT THE FAULT OF ODOT, CAUSE THE WORK TO EXTEND INTO THE SNOW-PLOWING SEASON, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACING WORK ZONE RAISED PAVEMENT MARKERS (WZRPMS) CONFORMING TO C&MS 614, WITH RAISED PAVEMENT MARKERS CONFORMING TO 621, AS DETERMINED BY THE ENGINEER, AT THE CONTRACTOR'S EXPENSE.

THIS ITEM SHALL INCLUDE PURCHASE, INSTALLATION AND REMOVAL OF ITEM 614 WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN, INCLUDING FILLING OF ANY DEPRESSIONS CREATED IN THE PAVEMENT AS PER C&MS 621.08.

PERMITTED LANE CLOSURE SCHEDULE (PLCS)

LANE CLOSURE(S) SHALL CONFORM TO THE PLCS. PUBLISHED PLCS INFORMATION CAN BE FOUND ON THE ODOT WEBSITE.

THE MONTHLY PUBLISHED SCHEDULES REQUIRED TO BE USED, FOR EACH PLCS SEGMENT WITHIN THE PROJECT AREA, ARE THOSE THAT COMPRISE THE CONSECUTIVE 12-MONTH PERIOD BEGINNING 15 MONTHS PRIOR TO THE MONTH AND YEAR OF SALE AND ENDING 4 MONTHS PRIOR TO THE MONTH AND YEAR OF SALE. THESE SAME 12 MONTHS APPLY FOR THE LIFE OF THE PROJECT AND SHALL BE APPLIED TO EACH RESPECTIVE MONTH OF CONSTRUCTION (MONTH OF LANE CLOSURE(S) SHALL MATCH MONTH OF PLCS USED). LANE CLOSURE(S) IN PLACE FOR MULTIPLE MONTHS SHALL ALWAYS COMPLY WITH THE CURRENT RESPECTIVE MONTH.

(FOR EXAMPLE: IF THE SALE DATE FOR THE PROJECT WAS MARCH OF 2021, THE MONTHLY PUBLISHED SCHEDULES FOR EACH APPLICABLE PLCS SEGMENT WOULD BE DECEMBER 2019 TO NOVEMBER 2020. IF THIS WAS A THREE-YEAR PROJECT, YEAR THREE WOULD STILL BE USING THE DECEMBER 2019 TO NOVEMBER 2020 MONTHLY SCHEDULES. IF THE PROJECT DESIRED TO CLOSE TWO LANES IN JUNE 2021, REFERENCE WOULD BE MADE TO THE JUNE 2020 SCHEDULE(S) FOR THE RESPECTIVE PLCS SEGMENT(S). IF THE SAME TWO LANES WERE DESIRED TO BE CLOSED AGAIN IN JULY 2021, REFERENCE WOULD BE MADE TO THE JULY 2020 SCHEDULE(S) FOR THE RESPECTIVE PLCS SEGMENT(S).)

ALLOWABLE LANE CLOSURE HOURS FOR FACILITIES NOT COVERED BY THE PLCS, IF ANY, SHALL BE AS SPECIFIED ELSEWHERE IN THE PLANS.

ESIGN AGENCY

a ESIGNER JMK

REVIEWER IDH 05-30-24 ROJECT ID

110931 P.11 183

/2\ 09-09-24: ADDENDUM R2 - REVISED PLCS NOTE

SHEET NUM. GRAND PART. ITEM SEE SHEET ITEM UNIT **DESCRIPTION** TOTAL EXT 01/IMS/44 P.21 P.22 P.25 **ROADWAY** LS LS 201 11001 LS CLEARING AND GRUBBING, AS PER PLAN 77 202 30700 77 77 CONCRETE BARRIER REMOVED 662 202 662 662 38000 GUARDRAIL REMOVED 12 12 202 38500 12 FT BRIDGE RAILING REMOVED 5,114 5,114 202 FENCE REMOVED 5,114 75000 202 EACH REMOVAL MISC.: INSPECTION WELL 98100 5 98200 25 25 202 25 REMOVAL MISC.: CONDUIT 203 2,690 2,258 432 2,690 10000 CY EXCAVATION 1,854 203 1,854 20000 1,854 CY EMBANKMENT 50 50 203 50 20001 EMBANKMENT, AS PER PLAN 260 203 ROADWAY, MISC.: TEMPORARY OVER-STEEPENED FILL 260 98000 260 204 2,504 2,504 2,504 SUBGRADE COMPACTION 10000 SY 204 45000 HOUR PROOF ROLLING 209 60201 LINEAR GRADING, AS PER PLAN 100 GUARDRAIL, TYPE MGS 100 100 15050 606 ANCHOR ASSEMBLY, MGS TYPE E (MASH 2016) 26150 606 35002 EACH MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1 **SUMMARY** 607 77 77 77 23000 FT FENCE, TYPE CLT 5,114 607 5,114 98000 5,114 FENCE, MISC.: TEMPORARY FENCE 38 38 609 24510 38 FT CURB, TYPE 4-C $\frac{1}{2}$ 3,450 90000 3,450 3,450 BARRIER, MISC.:CONCRETE BARRIER, 81" SSB 90200 139 EACH BARRIER, MISC.:CONCRETE BARRIER, 81" SSB, END ANCHORAGE, REINFORCED 19 GENERAL 622 90200 EACH BARRIER, MISC.:CONCRETE BARRIER, 81" SSB, WINDOW SECTION 622 90200 BARRIER, MISC.:CONCRETE BARRIER, 81" SSB, END SECTION, AS PER PLAN 622 90200 2 BARRIER, MISC.:CONCRETE BARRIER, 81" SSB, END SECTION, 32" TO 81" 138 LS LS **SPECIAL** LS AS-BUILT CONSTRUCTION PLANS 69091000 **SPECIAL** 69098400 LS LS LS SURVEY CONTROL VERIFICATION **EROSION CONTROL** 10 74 601 21050 84 TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT 1,384 1,384 32100 1,384 ROCK CHANNEL PROTECTION, TYPE B WITH FILTER ROCK CHANNEL PROTECTION, TYPE C WITH FILTER 32200 SOIL ANALYSIS TEST 659 00100 EACH 2 659 00300 5,008 TOPSOIL 4,576 432 5,008 CY 41,224 41,224 41,224 659 10000 SEEDING AND MULCHING 2,062 659 14000 2,062 REPAIR SEEDING AND MULCHING 2,062 2,062 659 15000 2,062 SY INTER-SEEDING 5.75 5.75 20000 5.75 COMMERCIAL FERTILIZER 659 8.52 ACRE 8.52 659 8.52 31000 LIME MGAL 229 229 659 35000 229 WATER 3,878 3,878 670 SLOPE EROSION PROTECTION 3,878 00500 LS LS 832 15000 STORM WATER POLLUTION PREVENTION PLAN LS LS 832 15002 LS STORM WATER POLLUTION PREVENTION INSPECTIONS STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE 15010 LS 832 LS LS ABATEMEN 143,689 832 EACH **EROSION CONTROL** 143,689 30000 DRAINAGE 602 1.89 1.89 CONCRETE MASONRY 4,842 ESIGN AGENCY 13300 4,892 4,892 50 605 6" UNCLASSIFIED PIPE UNDERDRAINS **A**ARCADIS 50 605 31100 50 AGGREGATE DRAINS NOISE 00510 6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS 25 301 611 301 276 06100 611 15" CONDUIT, TYPE C 141 141 141 FT 30 86 86 611 06700 86 FT 15" CONDUIT, TYPE F 25 25 611 97400 25 CONDUIT, MISC.: TYPE B FOR DRAINAGE DISCHARGE CONTINUANCE 9 25 25 611 25 CONDUIT, MISC.: TYPE C FOR DRAINAGE DISCHARGE CONTINUANCE 97400 CONDUIT, MISC.: TYPE E FOR DRAINAGE DISCHARGE CONTINUANCE 25 25 611 97400 25 MAH-680 REVIEWER JDH 05-30-24 ROJECT ID 110931 09-09-24: ADDENDUM R2 - REVISED UNDERDRAINS TO UNCLASSIFIED - REVISED CONCRETE BARRIER LENGTH P.19 183

A W
\triangleleft
\geq
\leq
S
$\mathbf{\Omega}$
\supset
S

					UNDERDRAIN SUE	BSUMMA	RY							
								601	605	611	611	BENDS	AND BRA	NCHES
REF. NO.	SHEET NO.	STATION	SIDE	OFFSET	STATION	SIDE	OFFSET	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT	6" UNCLASSIFIED BASE PIPE UNDERDRAINS	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	PRECAST REINFORCED CONCRETE OUTLET	FOR INF	45 DEGREE BEND OITAM	ON ONLY
		FROM			TO			SY '	FT FT	FT	EACH	NO.	NO.	
				NOISE \										
UD-1	P.35 - P.36	4000+00.00	RT	2.00	4004+82.00	RT	2.00		482	12		1	2	
EC-11	P.35	588+71.48, IR 680	RT	101.09				2		_	1			
UD-2	P.36 - P.37	4004+92.00	RT	2.00	4007+26.00	RT	2.00	_	234	25		1	2	
EC-12	P.36	•	593+62.92, IR 680 RT 111.22					2			1			
UD-3	P.37	4007+36.00	RT	2.00	4010+69.00	RT	2.00		333	18		1	2	
EC-14	P.37	599+53.32, IR 680	RT	123.14	4040 06 00			2	242	40	1			
UD-4	P.37 - P.38	4010+79.00	RT	2.00	4013+96.93	RT	2.00		318	19	4	1	2	
EC-15	P.38	602+81.82, IR 680	RT	118.02	4047.20.00	DT	2.00	2	247	10	1			
UD-5	P.38 - P.39	4014+11.07	RT	2.00	4017+28.00	RT	2.00		317	10		1	1	
UD-6	P.40	NOISE WALL 7 700+00.00 RT 2.00 701+25.93					2.00		126	21		1	2	
EC-17	P.40	608+28.32, IR 680	RT	123.07	/01+25.55	RT	2.00	2	120	21	1	-		
UD-7	P.40	701+40.07	RT	2.00	702+95.00	RT	2.00	2	155	10	1	1	1	
UD-7A	P.40 - P.41	701+40.07	RT	2.00	705+88.00	RT	2.00		276	21		1	2	
EC-18A	P.40	609+98.53, IR 680	RT	124.49	703100.00	IX I	2.00	2	270	21	1	-		
UD-8	P.41 - P.42	705+98.00	RT	2.00	709+53.00	RT	2.00	_	355	17		1	2	
EC-23	P.42	616+48.23, IR 680	RT	128.66	700.00.00			2			1	-		
UD-9	P.42	709+63.00	RT	2.00	712+57.93	RT	2.00		295	28	_	1	2	
UD-10	P.42 - P.43	712+72.07	RT	2.00	714+82.00	RT	2.00		205	10		1	1	
EC-26	P.42	619+53.16, IR 680	RT	117.30				2			1			
UD-11	P.43 - P.44	714+92.00	RT	2.00	719+91.00	RT	2.00		499	27		1	2	
EC-30	P.44	626+87.28, IR 680	RT	129.11				2			1			
UD-12	P.44 - P.45	720+01.00	RT	2.00	724+95.00	RT	2.00		494	11		1	2	
EC-32	P.45	632+10.83, IR 680	RT	146.32				2			1			
UD-13	P.45	725+05.00	RT	2.00	726+31.93	RT	2.00		127	19		1	2	
UD-14	P.45 - P.46	726+46.07	RT	2.00	730+03.00	RT	2.00		356	10		1	1	
EC-33	P.45	633+54.84, IR 680	RT	156.37				2			1			
UD-15	P.46	730+13.00	RT	2.00	732+83.00	RT	2.00		270	18	_	1	2	
EC-34	P.46	638+60.05, IR 680	RT	545.06			<u> </u>	2			1			
		TOTALS CA	RRIED TO	GENERALS	SUMMARY			24	4842	276	12	16	28	

MAH-680-9.30 NOISE ABATEMENT

		EROSION (CONTROL SUBSUMI	MARY			
					601	601	601
REF. NO.	SHEET NO.	STATION	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT	ROCK CHANNEL PROTECTION, TYPE B WITH FILTER	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER		
		FROM	ТО		SY	CY	CY
		81" SSB 1		_			
EC-1	P.27	539+28.21, IR 680		RT	24		
EC-2	P.29	112+00.00		RT			2
EC-3	P.31	118+50.00		RT			2
EC-4	P.31	121+00.00		RT			2
EC-5		NOT US					
EC-6		NOT U					
EC-7							
		81" SSB 4 / NOISE W	ALL 4				
EC-8		NOT U					
EC-9	P.35	417+00.00		RT	17		
EC-10	P.35	589+81.75, IR 680		RT	9		
EC-13	P.36	4004+80.00	4005+04.00	LT/RT		23	
EC-16	P.38	4015+84.00	4016+08.00	LT		20	
		NOISE WALL 7		1			
EC-18	P.40	702+27.00	702+75.00	LT/RT		223	
EC-19	P.40	702+99.00	703+71.00	LT/RT		334	
EC-20	P.41	706+05.00	706+29.00	LT/RT		107	
EC-21	P.41	707+01.00	707+25.00	LT/RT		58	
EC-22	P.41	707+73.00	707+97.00	LT/RT		112	
EC-24	P.42	709+65.00	709+89.00	LT/RT		89	
EC-25	P.42	709+89.00	710+13.00	LT/RT		89	
EC-27	P.42	712+53.00	712+77.00	LT/RT		23	
EC-28	P.43	716+91.00	717+15.00	LT/RT		123	
EC-29	P.43	717+39.00	717+63.00	LT/RT		123	
EC-31	P.44	720+51.00	720+75.00	LT/RT		60	
	TOTAL	S CARRIED TO GEN	ERAL SUMMARY		50	1384	6

09-09-24: ADDENDUM R2 - ADDED LINE ITEM FOR SAWCUTTING
- REVISED CONCRETE BARRIER LENGTH

	- REVISED CONCRETE BARRIER LENGTH
1	08-29-24: ADDENDUM R1 - UPDATED QUANTITY VALU FOR ITEM 452 TO SY FROM CY

í 																										
								/2	\		NO	ISE ABATEN	1ENT ST	RUCTUR	E SUBSU	JMMAR'	Υ									
<u></u>						202	204	204	255	304	407	441	452	517	602	606	606	611	611	611	622	622	622	622	622	659
REF. NO.		SHEET NO	-	STAT	ΓΙΟΝ	BRIDGE RAILING REMOVED	SUBGRADE COMPACTION	PROOF ROLLING	FULL DEPTH PAVEMENT SAWING	AGGREGATE BASE (6")	NON-TRACKING TACK COAT (APPLIED AT 0.06 GAL/SY)	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64- 22 (1.5")	9" NON-REINFORCED CONCRETE PAVEMENT, CLASS	RAILING, CONCRETE, AS PER PLAN	CONCRETE MASONRY	SPECIAL - NOISE BARRIER (REFLECTIVE)	SPECIAL - NOISE BARRIER (REFLECTIVE WITH ICON)	15" CONDUIT, TYPE C	15" CONDUIT, TYPE F	INLET, MISC.: INLET NO. 3 FOR 81" SINGLE SLOPE BARRIER	BARRIER, MISC.: CONCRETE BARRIER, 81" SSB	BARRIER, MISC.: CONCRETE BARRIER, 81" SSB, END ANCHORAGE, REINFORCED	BARRIER, MISC.: CONCRETE BARRIER, 81" SSB, WINDOW SECTION	BARRIER, MISC.: CONCRETE BARRIER, 81" SSB, END SECTION, AS PER PLAN	BARRIER, MISC.: CONCRETE BARRIER, 81" SSB, END SECTION, 32" TO 81"	SEEDING AND MULCHING
				FROM	TO	FT	SY	HOUR	FT (CY	GAL	CY	SY	FT	CY	SF	SF	FT	FT	EACH	FT	EACH	EACH	EACH	EACH	SY
				81" 9	SSB 1				\									111	86		\sim					
B-1	P.	.27 -	P.31	100+00.00	121+85.66	12	1351	1	2186	226	74	11	1230	12	1.62					6	(1784 ⁾	12		1	1	3835
				81" SSB 4 / N	IOISE WALL 4				}				}								>					
B-4	P.	.32 -	P.35	400+00.00	418+64.00		1153	1	\$ 1864	193	63	9	1049	<i>)</i>)	0.27			30		1	1666	₹ 7	1		1	1726
W-4	P.	.35 -	P.39	4000+00.00	4017+28.00				}				})		20880	1560				>	1				12142
				NOISE	WALL 7				}													V2\				
w-7	P.	.40 -	P.46	700+00.00	733+00.00				}				})		40533	2832				\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \					23521
T	ATC	LS C	ARRIE	D TO GENERAL	. SUMMARY	12	2504	2	4050	419	137	20	2279)) 12	1.89	61413	4392	141	86	7	3450	19	1	1	2	41224
									\mathcal{A}				~~~													

NOTE: SEEDING AND MULCHING QUANTITY CALCULATED USING CAD GENERATED AREAS. QUANTITY SHOWN ON THIS SHEET CARRIED TO P.7

DESIGN AGENCY

S101 NORTH HIGH ST SUITE 100

BESIGNER

JMK

REVIEWER

(614) 818-4900

www.arcadis.com

PROJECT ID

110931

SHEET TOTAL P.22 183