STATE OF OHIO
DEPARTMENT OF HIGHWAYS

I-680-9(1)222

FED. RD.	STATE	PROJECT	
2	OHIO	I-680-9()222	

1/492

MAHONING COUNTY
MAH-18-17.20

YOUNGSTOWN EXPRESSWAY SYSTEM

THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR OF HIGHWAYS IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 REVISED CODE OF OHIO.

MAR 10 1964
GROUND PHOTOLAB

MAH-18-17.20
MAHONING COUNTY
CITY OF YOUNGSTOWN

LIMITED ACCESS

PART I - STEEL STREET TO HAYES AVENUE

CONVENTIONAL SIGNS

Center Line
Corporation Line
Fence Line
Guard Rail (proposed)
Railroad
Power Poles
Telephone Poles
Trees or Stumps (Existing)

-INDEX OF SHEETS-

Title Sheet	1	Oakwood St. Improvement	226 - 230
Location Map	2	Silliman St. " "	231 - 233
Typical Sections	3-6	Steel St. & Glenwood Ave. " "	234 - 235
General Notes	7-14	Salt Springs Rd. Improvement	236 - 243
Maintenance of Traffic	15-16	Park Rd. " "	244 - 247
Computations	17-18	Marshall St. Improvement	248 - 260
Summary of Quantities	19-31	Edwards St. " "	261 - 267
Superelevation Tables	32-35	Burns St. & Hall Ct. Access Rd.	268 - 271
Plan & Profile MAH-18-17.20	36-47	High St. Improvement	272 - 286
Plan & Profile Ramps	48-62	Oakhill Ave. "	287 - 291
Details Ramps	63-69	Pike St. Relocation	292 - 295
Intersection Details of Ramps	70-73	Woodlawn Ave. East Imp.	296 - 300
Interchange With Mahoning West - Federal Expressway	74-77	Woodlawn Ave. West. Imp.	301 - 306
Grading Plan - Ramps "F & H"	78	Lighting Plans	307 - 310
Storm Sewer Profiles	79-83	Retaining Walls	311 - 327
Utility Relocations	84-104	Approach Slabs	328 - 331 & 331A
Manhole Details	105-106	Structures over 20'	332 - 466
Miscellaneous Details	107-111	Right-of-Way	467 - 492
Roadway Culverts	112-121		
Cross Sections - Expressway	122-181		
Cross Sections - Ramps	182-216		
Cross Sections - Interchange Mahoning West - Federal Expy.	217-225		


333-349-383-421-425, REV. 7-28-60

-LINE DATA-

Begin Project & I-680-9(1)222 Sta. 925+28.90
End Project & I680-9(1)222 Sta. 1034+91.44
Net Length of Project - 10,962.54 Lin. Ft. = 2.076 Mile

Add for Approaches = 11,660.77 Lin. Ft.
Total Length of Work = 22,623.31 Lin. Ft. = 4.284 Mile

(See Sheet Nº 8)



LOCATION MAP

SCALE OF FEET
2000 0 2000 4000 6000

Portion to be improved
Future Construction

Sheet 354 revised 9-1-60.
Sheets 181 & 184 Revised 11-18-60 REC.
Sheets 17, 19, 24, 25, 26, 28, 29, & 112 revised 11-23-60 REC.
Sheets 361 & 391 revised 1-12-61.

SCALE

Plan 1" = 50'
Profile : Horizontal 1" = 50'
Profile : Vertical 1" = 5'

The standard specifications of the State of Ohio, Department of Highways, including changes and supplemental specifications listed in the proposal shall govern this improvement.

The right of way for this improvement will be provided by the State of Ohio.

I hereby approve these plans and declare that the making of this improvement will not require the closing to traffic of the highway and that provisions for the maintenance and safety of traffic will be as set forth on these plans and estimates.

Approved Paul Kostyshak
Date 4-28-60 Division Deputy Director

Approved Guy E Nesper
Date 5-20-60 Deputy Director of Planning & Programming

Approved C W Merriman
Date 5-12-60 Engineer of Bridges

Approved [illegible]
Date 5-17-60 Engineer of Location & Design

Approved C W McCaughey
Date 5-18-60 Deputy Director of Design & Construction

Approved G A Berry
Date 5-20-60 First Assistant Director

Approved [illegible]
Date 5-20-60 Director of Highways

Approved J Phillip Richley
Date 4-27-60 Commissioner of Engineering, City of Youngstown

PREPARED AND RECOMMENDED BY
BEISWENGER, HOCH & ASSOCIATES and ROBERT J. SCHOMER
CONSULTING ENGINEERS
AKRON, OHIO YOUNGSTOWN, OHIO

File No. MAH-18-17.20
Date of Letting _____ 19__
Contract No. _____

Supplemental Prints of Standard Construction Drawings						
BT 50-10-TIE Nº1	10-1-47	I-8 MH Nº1A	1-26-59	S-27 PC-3	2-20-45	I-15 Nº6 7-1-59
BT TIE	3-2-53	I-8 MH Nº2	1-26-59	S-27 PC-4	1-4-54	I-8 CB Nº4 7-1-58
F-1	9-1-58	I-12	T-1-54	T-35	1-2-56	I-8 CB Nº5 7-1-58
F-3	9-1-58	I-14B	1-22-52	TJ	5-1-56	
G-7.01	6-1-56	I-15 Nº1	5-21-59			
I-1,2,3,4,&5	4-24-58	I-15 Nº2A	5-21-59			
I-8, CB 2-2A&B	3-2-59	I-21-23	8-1-56	AS-1-54	12-1-54	
I-8, CB 2-3&2-4	1-26-59	L-1	4-1-50	CSB-2-56, SHTS 2&3	2-2-59	
I-8, CB Nº6	1-26-59	L-3	4-1-50	RB-1-55	2-2-59	
I-8I Nº2	4-23-59	L-3A	4-1-50	AA-1-57	2-2-59	
I-8I, Nº2A	4-23-59	LJ Nº1	7-1-55	CS-2-54	2-2-59	
I-8 MH Nº1	1-26-59	R1-1	7-15-56	P-1-54	2-2-59	

Supplemental Specifications	
B-213	R. 3-12-59
I-124	1-11-56
S-101	12-2-59
M-106.6(d)	R. 4-1-58
M-206.14	7-15-59
18	R. 6-15-59

MICROFILMED
SEP 18 1963

MAR 10 1964
GROUND PHOTOLAB

DEPARTMENT OF COMMERCE
BUREAU OF PUBLIC ROADS

APPROVED

_____ Division Engineer _____ Date

FED. RD.	STATE	PROJECT	
	OHIO		

2/432

MAH-18-17.20

℄ CURVE Nº 1 DATA
Δ = 43°-47'-40"
Dc = 5°-30'
Rc = 1041.74'
Ls = 400'
Θs = 11°-00'
Lc = 796.26'
Ts = 621.04'
Es = 87.89'

℄ CURVE Nº 2 DATA
Δ = 54°-44'-10"
Dc = 5°-30'
Rc = 1041.74'
Ls = 400'
Θs = 11°-00'
Lc = 995.20'
Ts = 742.31'
Es = 138.49'

℄ CURVE Nº 3 DATA
Δ = 60°-43'-03"
Dc = 5°-30'
Rc = 1041.74'
Ls = 400'
Θs = 11°-00'
Lc = 703.95'
Ts = 813.68'
Es = 172.95'

℄ CURVE Nº 4 DATA
Δ = 74°-52'-50"
Dc = 2°-45'
Rc = 2083.48'
Ls = 300'
Θs = 4°-07'-30"
Lc = 2422.93'
Ts = 1746.61'
Es = 542.86'

℄ CURVE Nº 5 DATA
Δ = 53°-49'-25"
Dc = 5°-45'
Ls = 400'
Rc = 996.45'
Θs = 11°-30'
Lc = 536.06'
Ts = 708.91'
Es = 128.51'

LEGEND

- EXPRESSWAY CONSTRUCTION, FEDERAL PARTICIPATION
- CITY STREET IMPROVEMENT, 100% CITY
- FUTURE EXPRESSWAY

MICROFILMED
SEP 19 1985

GENERAL PLAN


FED. RD.	STATE	PROJECT	
2	OHIO		

3
492

MAH - 18 - 17.20

TYPICAL SECTIONS

TYPE - T - 71




NORMAL SECTION
16 FT. MEDIAN


SCALE 1/4" = 1'-0"

Limiting Stations

	929+99.42	- 937+46.56
	951+41.76	- 954+73.06
	969+77.01	- 979+19.25
	980+79.75	- 986+75.45
Right Lane	1016+98.42	- 1021+55.38
Left Lane	1019+17.15	-




THROUGH LANE CURB DETAIL



GUARD RAIL TREATMENT OF CENTER PIER

Varies 6' To 16.02' — Sta. 925+28.90 To Sta. 929+99.42

6' Normal



SUPERELEVATED SECTION
16 FT. MEDIAN

SCALE 1/4" = 1'-0"

Limiting Stations

	925+28.90	- 929+99.42
	937+46.56	- 951+41.76
	954+73.06	- 962+48.25
	968+46.93	- 969+77.01
	986+75.45	- 1005+07.87
	1006+87.22	1015+84.50 Left Lane
		1016+98.42 Right Lane
	1021+55.38	- 1034+91.44


NOTE : "A"

UNDERCUT REQ'D. BETWEEN

STA.	918+50	TO	STA. 928+00
STA.	932+00	TO	STA. 943+00
STA.	974+50	TO	STA. 976+00
STA.	989+50	TO	STA. 991+00
STA.	1015+00	TO	STA. 1016+50
STA.	1024+00	TO	STA. 1032+00

¼" Expansion Joint Material around Posts shall be included for payment with Item I-21.

NOTE: Backfill around Guard Rail Posts in Median shall be Granular Material.



JOINT DETAIL AT GUARD RAIL POSTS IN CONCRETE MEDIAN

(1) T-71 10" Reinforced Portland Cement Concrete Pavement

(2) I-22 Subbase (Variable Depth)

(3) I-18 5" Stabilized Crushed Aggregate

(4) T-31 Bituminous Surface Treatment Consisting of One Application of .008 C.Y. No. 6 Aggregate And 0.25 Gal. Bituminous Material. (See Note in Proposal.)

(5) B-219 3" Waterproofed Aggregate Base Course

(6) Standard Longitudinal Joint

(7) I-4 6" Pipe Underdrain

(8) I-12 Standard Type 6 Curb

(9) I-21. 4" Standard Type 1 Portland Cement Concrete Median Pavement

(10) I-15 ST'D. Barrier Rail, Steel Beam (Deep)

(11) I-15 ST'D. Guard Rail, Steel Beam (Deep)


CODE - 7221

TYPICAL SECTIONS

FED. RD.	STATE	PROJECT	
2	OHIO		


4 / 492

MAH - 18 - 17.20




GRADING SECTION

STA. 922+50 TO STA. 925+28.90 (S.R. 18)
STA. 806+00 TO STA. 806+88.34 (S.R. 7)



SHOULDER CONSTRUCTION


STA. 934+28.90 TO STA. 937+46.56



SHOULDER CONSTRUCTION


STA. 939+37 TO STA. 941+46.56

② — I-22 SUBBASE (VARIABLE DEPTH)
③ — I-18 5" STABILIZED CRUSHED AGGREGATE
④ — T-31 BITUMINOUS SURFACE TREATMENT
⑤ — B-219 3" WATERPROOFED AGGREGATE BASE COURSE



GRADING SECTION

RAMP-A_3 STA. 3+57.88 TO STA. 9+45.66
RAMP-B_3 STA. 4+08.93 TO STA. 11+70.58
RAMP-C_3 STA. 4+05.43 TO STA. 10+57.54



GRADING SECTION

LIMITING STATIONS

MAHONING - WEST FEDERAL EXPRESSWAY - STA. 0+00 TO STA. 4+55
RAMP C_3 - D_3 STA. 9+21.73 TO STA. 14+43.71


TYPICAL SECTIONS

FED. RD.	STATE	PROJECT	
2	OHIO		


5 / 492

MAH. - 18 - 17.20


TYPE - T-71
For limiting Stations See Ramp Plan & Profile Sheets.




NORMAL FILL SECTION




SUPERELEVATED FILL SECTION




NORMAL CUT SECTION



SUPERELEVATED CUT SECTION



TYPICAL SECTION
UTILITY ACCESS BENCH
LIMITING STATIONS
STA. 954+00 TO STA. 956+50



RAMP SHOULDER SUPERELEVATED TO LEFT

NOTE "A"

UNDERCUT REQ'D. BETWEEN;

RAMP 'A' STA. 0+00 TO STA. 12+00 - STA. 16+00 TO STA. 20+00
RAMP 'B' STA. 12+00 TO STA. 16+00
RAMP 'D' STA. 0+00 TO STA. 15+00
RAMP 'E' STA. 0+00 TO STA. 7+00
RAMP 'H' STA. 6+00 TO STA. 9+00
RAMP 'J' STA. 13+50 TO STA. 16+50
RAMP 'K' STA. 0+00 TO STA. 4+00 - STA. 9+50 TO STA. 18+50
RAMP 'M' STA. 11+00 TO STA. 17+00
RAMP 'N' STA. 8+00 TO STA. 12+00

(1) T-71 9" Reinforced Portland Cement Concrete Pavement
(2) I-22 Subbase (Variable Depth)
(3) I-18 Stabilized Crushed Aggregate
(4) T-31 Bituminous Surface Treatment Consisting of One Application of .008 C.Y. No. 6 Aggregate 0.25 Gal. Bituminous Material. (See Note in Proposal.)
(5) B-219 3" Waterproofed Aggregate Base Course
(6) Standard Longitudinal Joint
(7) I-4 6" Pipe Underdrain
(22) I-10 Dumped Rock Fill as Per Plan
Material For This Item Shall Be Bank Run Slag. Grading Requirements Are Hereby Waived. However, The Material Shall Be Such That It Can Be Placed In Two Foot Lifts.
(11) I-15 Std. Guard Rail, Steel Beam (Deep)

CODE - 7221


RAMP TYPICAL SECTIONS

TYPICAL SECTIONS

FED. RD.	STATE	PROJECT	
2	OHIO		


MAH-18-17.20

6
492




RAMP "E" & "G"


LIMITING STATIONS
RAMP "E" - STA. 2+45.54 TO STA. 9+64.68
RAMP "G" - STA. 2+37.36 TO STA. 5+26.45




PARK ROAD TYPICAL SECTION




PIKE ST. TYPICAL SECTION




RELOCATED SALT SPRINGS ROAD






RAMP CURB DETAILS



RAMP ALONG WALL OR ABUTMENT



RAMP WITH CURB & PAVED GUTTER

(1) T-71 9" Reinforced Portland Cement Concrete Pavement
(2) I-22 Subbase (Variable Depth)
(3) I-18 Stabilized Crushed Aggregate
(4) T-31 Bituminous Surface Treatment
(5) B-219 3" Waterproofed Aggregate Base Course
(6) Standard Longitudinal Joint
(7) I-4 6" Underdrain
(8) I-12 Standard Type 6 Curb
(9) I-21 Standard Type 1 Concrete Median
(11) I-15 Standard Guardrail, Steel Beam (Deep)
(12) I-13 5" Concrete Sidewalk
(13) I-12 Standard Type 2-A Concrete Curb
(14) B-19 8" Aggregate Base Course.
(15) T-35 1¼" Asphaltic Concrete Surface Course. Type 'C' (70-85)
(16) B-35 1¾" Asphaltic Concrete Leveling Course. (70-85)
(18) B-35 1¾" Asphaltic Concrete Leveling Course. (70-85)
(19) T-35 1¼" Asphaltic Concrete Surface Course. Type 'C' (70-85)
(20) I-14 Standard Type 1 Paved Gutter
(21) B-35 6" Asphaltic Concrete Base Course (70-85) (2-3" Courses)

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH - 18 - 17.20

7
492

GENERAL NOTES

ROAD NAME SIGNS:

ALL COUNTY, TOWNSHIP, CITY OR VILLAGE ROAD OR STREET NAME SIGNS THAT WILL BE DISTURBED BY THE CONSTRUCTION SHALL BE CAREFULLY REMOVED AND STORED BY THE CONTRACTOR FOR DISPOSAL BY THEIR RESPECTIVE OWNERS. PAYMENT FOR THIS OPERATION SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ROADWAY EXCAVATION.

FIELD OFFICE

THE CONTRACTOR SHALL PROVIDE A SUITABLE FIELD OFFICE FOR THE EXECUTIVE USE OF THE STATE EMPLOYEES, IN ACCORDANCE WITH SEC. S-0.01 (b) HAVING A MINIMUM OF 500 SQUARE FEET OF FLOOR SPACE. THE CONTRACTOR SHALL HAVE A TELEPHONE INSTALLED AND MAINTAINED IN THE FIELD OFFICE DURING THE CONSTRUCTION OF THIS PROJECT.

DESIGN SPEED:

THE GEOMETRICS FOR THIS PROJECT HAVE BEEN PLANNED FOR A DESIGN SPEED OF 50 MILES PER HOUR.

UTILITIES

THE CONTRACTOR SHALL NOTIFY AT LEAST 48 HOURS BEFORE BREAKING GROUND ALL PUBLIC SERVICE CORPORATIONS HAVING WIRE, POLES, PIPE, CONDUITS, MANHOLES OR OTHER STRUCTURES THAT MAY BE AFFECTED BY THIS OPERATION, INCLUDING ALL STRUCTURES WHICH ARE AFFECTED AND NOT SHOWN ON THESE PLANS. ANY AND ALL WORK REQUIRED FOR PUBLIC OR PRIVATE UTILITIES WILL BE DONE BY AND AT THE EXPENSE OF THEIR RESPECTIVE OWNERS, UNLESS OTHERWISE NOTED ON THESE PLANS.

R/W MONUMENTS, FEDERAL PROJECT MARKERS, AND SECTION MARKERS:

EXISTING R/W MONUMENTS, BENCH MARKS, FEDERAL PROJECT MARKERS AND SECTION MARKERS THAT WILL BE REMOVED BY CONSTRUCTION, SHALL BE PROTECTED BY THE CONTRACTOR AS PER SECTION G-7.09 UNTIL THEY CAN BE WITNESSED, REFERENCED AND RESET BY THE CONSTRUCTION CREWS.

ELEVATION DATUM:

ALL ELEVATIONS ARE BASED ON U. S. G. S. DATUM.

SPECIAL DITCHES

FOR SPECIAL DITCH GRADES, SEE CROSS SECTIONS.

PIPE FOR SUBGRADE DRAINAGE

10 LIN. FT. OF 8" CORRUGATED METAL PIPE, SEC. M-6.4(a), SHALL BE FURNISHED AND PLACED BY THE CONTRACTOR, IN MANHOLES, CATCH BASINS AND INLETS FOR EACH SUBGRADE DRAIN, WHERE, AND AS DIRECTED BY THE ENGINEER. PAYMENT FOR EACH SHALL BE MADE AT THE PRICE BID FER LINEAL FOOT OF PIPE UNDERDRAIN OUTLETS.

SUBGRADE COMPACTION FOR DRIVEWAYS

THE SUBGRADE FOR DRIVEWAYS FAVED WITH T-71 MATERIAL SHALL BE COMPACTED FOR A DEPTH OF SIX (6) INCHES TO THE DENSITY REQUIREMENTS SHOWN IN TABLE III, ITEM E-1. PAYMENT FOR SUBGRADE COMPACTION, AS SPECIFIED ABOVE, SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM E-1, ROADWAY EXCAVATION.

REMOVAL & STORAGE OF CURB & SIDEWALK

EXISTING STONE CURB AND FLAGSTONE SIDEWALK SHALL REMAIN THE PROPERTY OF THE CITY OF YOUNGSTOWN AND SHALL BE STORED WITHIN THE RIGHT-OF-WAY LIMITS.

HEAVY EQUIPMENT

THE CONTRACTOR SHALL EXERCISE CARE IN THE OPERATION OF HEAVY EQUIPMENT OVER FINISHED WORK AND WILL BE REQUIRED TO REMOVE AND REPLACE ANY COMPLETED WORK DESTROYED THEREBY. CULVERTS SHALL BE BACKFILLED TO A HEIGHT OF FOUR FEET BEFORE LOADED EARTH-MOVING EQUIPMENT IS PERMITTED TO CROSS THE TRENCH. HEAVY EQUIPMENT SHALL NOT BE OPERATED OVER ANY COMPLETED LAYER OF EMBANKMENT COMPACTED SUBGRADE OR SUBBASE IF SUCH OPERATION TENDS TO DESTROY THE SOIL STRUCTURE OR PIPE UNDERDRAINS; HOWEVER, IF SUCH OPERATION CANNOT BE AVOIDED, THE CONTRACTOR WILL BE REQUIRED TO REDUCE THE SIZE OF LOADS TO AN EXTENT THAT DAMAGE DOES NOT OCCUR. ANY ADDITIONAL FILL AND SUBSEQUENT EXCAVATION REQUIRED TO PROVIDE THE MINIMUM SHALL BE MADE AT NO ADDITIONAL COST TO THE STATE.

GUARD RAIL POST ANCHORS

AT LOCATIONS WHERE PIER FOOTINGS INTERFERE WITH INSTALLATION OF FULL LENGTH GUARD RAIL POSTS, SHORT POSTS SHALL BE PROVIDED AND SHALL BE ANCHORED IN ACCORDANCE WITH STANDARD DRAWING I-15 NO. 6. COST OF PROVIDING AND INSTALLING NECESSARY ANCHORS SHALL BE INCLUDED IN THE UNIT PRICE BID PER LINEAL FOOT OF GUARD RAIL.

GUARD RAIL PARAPET ANCHORS:

THE CONTRACTOR SHALL PROVIDE ONE ADDITIONAL GUARDRAIL POST IN THE CENTER OF THE FIRST PANEL OF DEEP STEEL BEAM GUARDRAIL ADJACENT TO THE PARAPET, COST OF WHICH SHALL BE INCLUDED IN THE UNIT PRICE BID PER LINEAL FEET OF GUARDRAIL.

ITEMS L-10, SODDING I-10 DUMPED ROCK CHANNEL PROTECTION, I-14 PAVED GUTTER.

THESE ITEMS ARE PROVIDED ON THE PLANS FOR EROSION CONTROL. THE ENGINEER SHALL CHECK AND MAKE ADJUSTMENTS IN LOCATION AND QUANTITIES FOR THESE ITEMS WHERE INDICATED BY FIELD CONDITIONS DURING CONSTRUCTION.

L-9 COMMERCIAL FERTILIZER

ALL AREAS TO BE SEEDED UNDER ITEM L-9 OR SODDED UNDER ITEM L-10 SHALL HAVE COMMERCIAL FERTILIZER 12-12-12, APPLIED AT THE RATE OF TWENTY (20) POUNDS PER 1,000 SQUARE FEET.

SEEDING AND PROTECTING

QUANTITIES FOR SEEDING ITEM L-9 ARE CALCULATED FOR ALL AREAS WITHIN RIGHT-OF-WAY LIMITS SEED SHALL BE SOWN AT THE RATE OF 3 POUNDS PER 1,000 SQUARE FEET EXCEPT AS OTHERWISE NOTED IN THE PLANS. SEEDING FORMULA FOR ALL SEEDED AREAS SHALL BE IN ACCORDANCE WITH THE FOLLOWING:

65% KENTUCKY BLUEGRASS
25% KENTUCKY 31 FESCUE
5% REDTOP
5% WHITE DUTCH CLOVER

REMOVAL OF TREES AND STUMPS

THE SIZE AND NUMBER OF TREES AND STUMPS SHOWN BELOW FOR REMOVAL UNDER THE CONSTRUCTION AS DETAILED ON THESE PLANS, ARE AS NEARLY CORRECT AS AVAILABLE INFORMATION PERMITS. THE STATE OF OHIO WILL NOT BE RESPONSIBLE FOR ANY VARIATIONS FOUND DURING CONSTRUCTION. THE LUMP SUM BID FOR ITEM E-9 REMOVAL OF TREES AND STUMPS, SHALL CONSTITUTE FULL PAYMENT FOR THIS ITEM, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED. ALL TREES AND STUMPS WITHIN THE CONSTRUCTION LIMITS AND SUCH TREES AS MARKED BY THE ENGINEER SHALL BE REMOVED UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

THE NUMBER OF TREES ARE ESTIMATED TO BE 1400.

FLARING OF GUARD RAIL AT BRIDGE

GUARD RAIL SHALL BE FLARED TO MEET THE BRIDGE RAILING IN SUCH A MANNER THAT THE CHANGE IN ALIGNMENT OF THE GUARD RAIL SHALL NOT EXCEED 1:20.

REPLACEMENT

THE CONTRACTOR SHALL REPLACE AT HIS OWN EXPENSE ANY ITEM NOT SPECIFICALLY LISTED FOR REMOVAL THAT IS DAMAGED OR DESTROYED BY HIS OPERATIONS.

I-22 UNDER APPROACH SLABS

THE AREA BETWEEN THE BOTTOM SURFACE OF THE APPROACH SLAB AND THE SUBGRADE SHALL BE BACKFILLED WITH ITEM I-22 6" SUBBASE.

CONTRACTION AND EXPANSION JOINTS

ALTHOUGH SPECIFIC LOCATIONS OF CERTAIN EXPANSION AND CONTRACTION JOINTS HAVE BEEN DETAILED ON THIS PLAN, NO WAIVER OF THE SPECIFICATIONS IS INTENDED. PROVISION OF EXPANSION JOINTS AT ALL MAJOR STRUCTURES AND THE MAXIMUM SPACING BETWEEN CONTRACTION JOINTS SHALL IN ALL CASES BE IN ACCORDANCE WITH STANDARD CONSTRUCTION DRAWING T.J.

PERMITS, LAWS AND REGULATIONS

THE CONTRACTOR SHALL SECURE, ALL NECESSARY PERMITS FROM THE MUNICIPAL OR OTHER PUBLIC AUTHORITIES & SHALL GIVE ALL NOTICES REQUIRED BY LAW OR MUNICIPAL ORDINANCES.

GUARD RAIL

THE LENGTHS OF INDIVIDUAL RUNS OF GUARD RAIL SHALL BE ADJUSTED AT THE TIME OF CONSTRUCTION TO ACCOMMODATE STANDARD PANEL LENGTHS.

UTILITIES

FOLLOWING IS A LIST OF THE UTILITIES WITHIN THE LIMITS OF THIS PROJECT:

EAST OHIO GAS CO.
OHIO EDISON CO.
MAHONING VALLEY SANITARY DISTRICT
OHIO BELL TELEPHONE CO.
BALTIMORE AND OHIO RAILROAD
CITY OF YOUNGSTOWN WATER DEPT.
CITY OF YOUNGSTOWN SEWER DEPT.
AMERICAN TELEPHONE & TELEGRAPH

DRAIN PIPES

EXISTING DRAIN PIPES ENCOUNTERED DURING CONSTRUCTION ARE TO BE ADJUSTED OR REPLACED AS DIRECTED BY THE ENGINEER. PAYMENT FOR ADJUSTING EXISTING DRAIN PIPES WILL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR LINEAR FEET OF CURB. PAYMENT FOR REPLACEMENT OF DRAIN PIPES WILL BE AS NOTED BELOW FOR NEW DRAIN PIPES:

I-2 4" PIPE FOR STORM SEWERS M-6.8(a)
-- 1000 LIN. FT.

THE ABOVE QUANTITY IS PROVIDED FOR NEW DRAIN PIPES AND CURB OPENINGS AT LOCATIONS DESIGNATED BY THE ENGINEER. IT SHALL INCLUDE THE CURB OPENING, FURNISHING AND INSTALLING THE PIPE, AND OTHER INCIDENTALS NECESSARY TO SATISFACTORILY COMPLETE THIS ITEM. THE SPECIFIC LOCATION AND USAGE OF ESTIMACED QUANTITIES SET UP ON THIS PLAN TO BE USED AS DIRECTED BY THE ENGINEER SHALL BE MADE A MATTER OF RECORD BY INCORPORATION INTO THE FINAL CHANGE ORDER GOVERNING COMPLETION OF THIS PROJECT.

FILLING BASEMENTS OUTSIDE NORMAL WORK LIMITS:
IN ADDITION TO THE GENERAL REMOVAL REQUIREMENTS OF SEC. E-1.03(C), ALL BASEMENTS OR PORTIONS THEREOF WITHIN THE RIGHT-OF-WAY ON THIS PROJECT BUT BEYOND THE NORMAL SLOPE LINES SHALL BE FILLED TO SURROUNDING GROUND ELEVATION AS DIRECTED BY THE ENGINEER. PRIOR TO FILLING WITHIN THIS AREA, THE BASEMENT FLOORS AND WALLS SHALL BE BROKEN UP OR REMOVED AS PROVIDED UNDER SEC. E-1.03(C) (AND ALL HOUSE DRAINS NOT REMOVED SHALL BE PLUGGED AS PROVIDED ELSEWHERE IN THESE NOTES.)
WHERE BASEMENTS EXTEND BEYOND THE RIGHT-OF-WAY LINE, BUT ARE WITHIN SLOPE EASEMENT OR WORK AGREEMENT LINES, THEY SHALL BE FILLED TO THE ELEVATION OF THE SURROUNDING GROUND AS DIRECTED BY THE ENGINEER BUT THE REQUIREMENTS OF SEC. E-1.03(C) FOR REMOVALS BELOW THE PROPOSED FINISHED SURFACE SHALL BE WAIVED FOR THE PORTIONS EXTENDING BEYOND THE RIGHT-OF-WAY LINE.
PAYMENT FOR ALL OF THE ABOVE, EXCEPT PLUGGING, SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ROADWAY EXCAVATION, ITEM E-1.

CONSTRUCTION LAYOUT STAKES

SEE NOTE IN PROPOSAL DESCRIBING THE WORK INCLUDED IN THIS LUMP SUM PAY ITEM.

DRIVEWAY RECONSTRUCTION:

THE CONTRACTOR WILL REMOVE WHERE NECESSARY AT THE LOCATIONS DESIGNATED ON THE PLANS, EXISTING DRIVEWAYS WHICH ARE TO BE RE-GRADED. THESE DRIVEWAYS ARE TO BE REPLACED IN KIND AND PAYMENT SHALL BE AT THE UNIT BID PRICE FOR THE SPECIFIC TYPE OF MATERIAL TO BE REPLACED. SEE SHEET NO. 107 . CHART "A"

FED. RD.	STATE	PROJECT	
2	OHIO		

8
492

MAH - 18 - 17.20

GENERAL NOTES

BERMS AND SLOPES

BERMS, SLOPES AND ROUNDING SHALL BE FINISHED IN ACCORDANCE WITH STANDARD DRAWING RI-1 EXCEPT WHERE OTHERWISE SHOWN ON THE TYP. SECTION. ALL SLOPES IN TRANSITION FROM CUT TO FILL SHALL BE MADE IN A MANNER TO BLEND WITH THE SURROUNDING TERRAIN AS DIRECTED BY THE ENGINEER.

THE GRADING TOLERANCE AS NOTED IN SECTION E-1.10 OF THE SPECIFICATIONS SHALL BE MODIFIED AS FOLLOWS. THE FINISHED GRADED AND SEEDED SECTION IN THE AREAS OF LAWNS OR RESIDENCES SHALL NOT DEVIATE MORE THAN ONE INCH VERTICALLY BELOW THE GRADE AND LINES AS SHOWN IN THESE PLANS. THESE AREAS ARE TO BE IN SMOOTH CONTOUR AND FREE FROM STICKS, STONES AND OTHER DEBRIS. CARE SHALL BE EXERCISED, AS DIRECTED BY THE ENGINEER, TO ASSURE THAT PROPER SURFACE DRAINAGE IS OBTAINED IN THE AREAS INVOLVED AS WELL AS ADJACENT TO OR ACROSS ANY DRIVEWAYS THAT MAY BE LOCATED IN THE AREAS. PAYMENT FOR ANY ADDITIONAL TOOLS, LABOR INCLUDING HANDRAKING IF NECESSARY, INCIDENTALS AND OPERATIONS NECESSARY TO ACCOMPLISH THIS SHALL BE INCLUDED IN THE PRICE BID FOR ITEM E-1 ROADWAY EXCAVATION.

CURBS ON APPROACH SLABS

THE HEIGHT AND FACE OF CURBS ON APPROACH SLABS SHALL BE TRANSITIONED FROM THE STANDARD SECTION USED ON THE APPROACH PAVEMENT TO THE SECTION USED ON THE BRIDGE CURBING WITHIN THE LIMITS OF THE APPROACH SLAB.

PLACING SOD IN DITCHES

ALL SOD PLACED IN DITCHES SHALL BE LAID WITH THE LONG EDGES OF THE STRIPS PERPENDICULAR TO THE FLOW LINE OF THE DITCH. SUCCESSIVE STRIPS SHALL BE NEATLY MATCHED AND ALL JOINTS STAGGERED OR BROKEN. THE SOD SHALL BE STAKED SECURELY WITH STAKES PLACED ON MAXIMUM TWO (2) FOOT CENTERS IN ROWS NOT MORE THAN TWO (2) FT. APART. STAKES IN ADJACENT ROWS SHALL BE STAGGERED. THE STAKES SHALL BE WOOD FROM 1/2"x3/4"x12" TO 1"x1"x24" AS REQUIRED TO HOLD THE SOD AND SHALL BE DRIVEN FLUSH WITH THE TOP OF THE SOD.

GLENWOOD AVE. STONE WALL

STONE REMOVED FROM THE STONE RETAINING WALL AT GLENWOOD AVE., SHOWN ON SHEET NO. 235 ITEM S-24 SHALL REMAIN THE PROPERTY OF THE CITY AND SHALL BE STORED WITHIN THE R/W.

CONCRETE STEPS

REMOVAL OF EXISTING STEPS SHALL BE INCLUDED UNDER THE UNIT PAICE BID PER LIN. FT. OF ITEM I-13 "CONCRETE STEPS". RISER HEIGHT MAY BE VARIED IN THE FIELD AT THE DIRECTION OF THE ENGINEER.

NATURAL SAND AND GRAVEL SUBGRADE

NATURAL SAND & GRAVEL WILL BE ENCOUNTERED AT SUBGRADE ELEVATION IN MANY CUT SECTIONS. IN AREAS WHERE THIS MATERIAL CONTAINS NOT MORE THAN 15% PASSING A NO. 200 SIEVE, EXCAVATION OF THIS MATERIAL AND REPLACEMENT WITH I-22 SHALL BE NON-PERFORMED AS DIRECTED BY THE ENGINEER.

I-13 5" SIDEWALKS BETWEEN APPROACH SLAB CURBS & ABUTMENTS

1/2" PREMOULDED EXPANSION JOINT FILLER SHALL BE USED BETWEEN THE FACES OF THE ABUTMENT & SIDEWALK AND THE APPROACH SLAB CURB & SIDEWALK. THE COST OF THE EXPANSION JOINT FILLER SHALL BE INCLUDED UNDER THE UNIT PRICE BID PER SQ. FT. FOR ITEM I-13 5" PORTLAND CEMENT CONCRETE SIDEWALK.

SS-18 RIGHT OF WAY FENCE:
RIGHT OF WAY FENCE SHALL BE ERECTED 2' INSIDE THE LIMITED ACCESS LINE UNLESS OTHERWISE SHOWN ON THE PLANS.

12" I-22 COURSE THROUGH SILT AREAS

IN THE FOLLOWING AREAS OF A-1a AND A-1b SILT A 12" THICKNESS OF I-22 SHALL BE USED UNDER THE CONCRETE PAVEMENT AND SHOULDERS CUT TO THE I-N LINE.

MAIN LINE STATION
918 + 50 — 922 + 00
932 + 00 — 942 + 00
974 + 50 — 976 + 00
988 + 50 — 991 + 00
1015 + 00 — 1016 + 50
1021 + 00 — 1032 + 00

RAMP A
0 + 00 — 12 + 00
16 + 00 — 20 + 00

RAMP B
12 + 00 — 16 + 00

RAMP D
0 + 00 - 15 + 00

RAMP E
0 + 00 - 7 + 00

RAMP H
6 + 00 - 9 + 00

RAMP K
0 + 00 - 4 + 00
9 + 50 - 18 + 50

RAMP M
11 + 00 - 17 + 00

RAMP N
8 + 00 - 12 + 00

COMPACTION USING A HEAVY PNEUMATIC TIRED ROLLER

THERE ARE SEVERAL AREAS OF EXISTING RANDOM FILL BETWEEN STATIONS 1006 + 00 1020 + 00. WHERE THESE DEPOSITS OCCUR IN THE SUBGRADE FOR PAVEMENT OR FOUNDATION FOR FILL THEY SHALL BE ROLLED WITH A 50 TON PNEUMATIC TIRED ROLLER (SEE PROPOSAL). THE APPROXIMATE AREAS OF ROLLING ARE SHOWN ON SHEET NO. 167 & 169. THESE AREAS MAY BE VARIED AS DIRECTED BY THE ENGINEER. BETWEEN STATIONS 1008 TO 1012 WHERE THE RANDOM FILL FORMS THE FOUNDATION FOR EMBANKMENT IT WILL BE NECESSARY TO EXCAVATE THE RANDOM FILL SLOPE TO FORM WORKING BENCHES FOR THE PNEUMATIC TIRED ROLLER. THE EXCAVATION NECESSARY SHALL BE PAID FOR UNDER ITEM E-1 "ROADWAY EXCAVATION - METHOD B". IN CUT AREAS THE EXCAVATION SHALL BE COMPLETED TO APPROXIMATE SUBGRADE ELEVATION BEFORE ROLLING IS BEGUN. ROLLING SHALL BE DONE FOR THE FULL ROADWAY WIDTH BETWEEN DITCHES; OR WHERE EMBANKMENT IS REQUIRED; FOR THE FULL WIDTH ON WHICH THE EMBANKMENT IS TO REST. THE FOLLOWING QUANTITY IS ESTIMATED FOR THE ROLLING OPERATION.

ITEM SPECIAL 40 HOURS FILL COMPACTION USING A HEAVY PNEUMATIC TIRED ROLLER — GRANULAR BORROW MEETING THE REQUIREMENTS OF ITEM T-1.02 "GRANULAR MATERIAL" AND IN ADDITION MEETING THE REQUIREMENT OF AT LEAST 75% BY WEIGHT OF GRAINS OR PARTICLES RETAINED ON A NO 200 SIEVE; SHALL BE USED TO LEVEL UP RUTS THAT DEVELOPE AS ROLLING PROGRESSES. THE FOLLOWING QUANTITY IS ESTABLISHED FOR THIS PURPOSE.

ITEM E-N 1575 CY SPECIAL BORROW USING GRANULAR MATERIAL SECTION E-1.02; AS PER PLAN.

GENERAL NOTES

DRAINAGE

1. WHERE ABANDONED SEWER PIPES OR WATER MAINS ARE ENCOUNTERED DURING CONSTRUCTION; THE PIPES SHALL BE CUT AND PLUGGED IN ACCORDANCE WITH METHODS OUTLINED IN SECTION I-16.03. PAYMENT FOR CUTTING AND PLUGGING AND THE REMOVAL OF THE PIPE WITHIN THE LIMITS OF CONSTRUCTION SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM E-1 " ROADWAY EXCAVATION - METHOD B"

2. THE CONTRACTOR SHALL CONDUCT HIS OPERATION THAT THE FLOW OF ALL EXISTING SEWERS WILL BE MAINTAINED AT ALL TIMES. ANY ADDITIONAL LABOR OR COST INVOLVED IN MAINTAINING THIS FLOW BY PUMPING OR BY ANY OTHER APPROVED METHOD WHICH IS NECESSARY FOR THE COMPLETION OF THIS PROJECT SHALL BE INCLUDED IN THE PRICE BID FOR ITEM I-2 "STORM SEWERS".

3. AT PLACES WHERE THE PLANS PROVIDE FOR PROPOSED DRAINAGE PIPE TO CONNECT TO EXISTING PIPES; IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE THE EXISTING PIPE AS TO LINE AND GRADE BEFORE HE STARTS TO LAY THE PROPOSED SEWER. THE COST OF THIS OPERATION SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE PERTINENT PIPE ITEM.

RELOCATED PIKE STREET

Subsequent to the completion of these plans the City of Youngstown advised that they propose to let a contract to construct a sewer line in relocated Pike Street starting at the junction of existing 68" and 54" combination sewers (See sheet 292) and extending easterly on relocated Pike St. This work proposes a new junction chamber at the intersection of the existing 68" and 54" lines with manholes at approximate Pike St. stations 7+16 and 9+35 and will eliminate the need for 18" line P-82 and manholes B-1 and A-75.

When the Youngstown Sewer Contract becomes effective the overlapping work on this contract shall be non-performed.

The Contractor on this project shall cooperate with the contractor on the sewer project so as not to unduly inconvenience his operations.

LINE DATA CALCULATIONS FOR STREETS & APPROACHES

SALT SPRINGS ROAD:
BEGIN WORK - STA. 0+00
END WORK - STA. 7+44.52
NET LENGTH OF WORK = 744.52 L.F.

WOODLAND AVE. (EAST)
BEGIN WORK - STA. 1+20.96
END WORK - STA. 8+66.06
NET LENGTH OF WORK = 745.10 L.F.

MARSHALL ST.
BEGIN WORK - STA. 0+00
END WORK - STA. 22+50
NET LENGTH OF WORK = 2250 L.F.

EDWARDS ST.
BEGIN WORK - STA. 0+63.31
SUSPEND WORK - STA. 6+20
RESUME WORK - STA. 7+04.13
END WORK - STA. 9+90.32
NET LENGTH OF WORK = 851.88 L.F.

HIGH ST.
BEGIN WORK - STA. 14+59.16
END WORK - STA. 34+00
NET LENGTH OF WORK = 1940.84 L.F.

OAKWOOD AVE.
BEGIN WORK - STA. 0+10
END WORK - STA. 6+41.66
NET LENGTH OF WORK = 631.66 L.F.

RELOC. BURNS ST. & HALL COURT
BEGIN WORK - 0+23.20
END WORK - 3+94.80
NET LENGTH OF WORK = 371.51 L.F.

OAKHILL AVE.
BEGIN WORK - STA. 48+25
END WORK - STA. 51+65.14
NET LENGTH OF WORK = 340.14 L.F.

WOODLAND AVE. (WEST)
BEGIN WORK - STA. 0+32
END WORK - STA. 7+50
NET LENGTH OF WORK = 718 L.F.

SILLIMAN ST.
BEGIN WORK - STA. 0-47
END WORK - STA. 5+91.01
NET LENGTH OF WORK = 638.01 L.F.

PIKE ST. RELOCATION:
BEGIN WORK - STA. 0+18
END WORK - STA. 9+90
NET LENGTH OF WORK = 972 L.F.

PARK ROAD:
BEGIN WORK - STA. 0+00
END WORK - STA. 9+34.87
NET LENGTH OF WORK = 934.87 L.F.

MAIN LINE APPROACHES:
BEGIN WORK - STA. 921+75
BEGIN PROJECT - STA. 925+28.90
LENGTH OF WORK 353.90 L.F.
END PROJECT - STA. 806+88.34
END WORK - STA. 805+20
EQUATION - 1034+91.44 BACK, EQUALS 806+88.34 AHEAD
LENGTH OF WORK - 168.34 L.F.
NET LENGTH OF WORK (APPROACHES) = 522.24 L.F.

TOTAL LENGTH OF STREETS & APPROACHES = 11660.77 LIN.FT.

GENERAL NOTES

UTILITIES RELOCATION

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

9/432

GENERAL:

CONSTRUCTION PLANS INCLUDE RELOCATING LINES AND APPURTENCES OF THREE UTILITY FACILITIES DISRUPTED BY CONSTRUCTION OF EXPRESSWAY. THIS RELOCATION WORK TO BE PERFORMED IN CONNECTION WITH AND BY THE CONTRACTOR OF YOUNGSTOWN EXPRESSWAY WORK IN ORDER THAT UTILITIES RELOCATIONS CAN BE CLOSELY COORDINATED WITH EXPRESSWAY WORK AND WITH EACH OTHER.

THE THREE FACILITIES ARE:

CITY OF YOUNGSTOWN SEWER DEPARTMENT; (C.O.Y. SEWER DEPT.) RELOCATION OF VARIOUS LATERAL AND INTERCEPTOR SEWERS.

CITY OF YOUNGSTOWN WATER DEPARTMENT; (C.O.Y. WATER DEPT.) RELOCATION OF VARIOUS SERVICE MAINS AND THE 36 INCH PRESTRESSED REINFORCED CONCRETE AND 30 INCH CAST IRON PIPE SUPPLY MAINS IN PLUM STREET.

MAHONING VALLEY SANITARY DISTRICT: (M.V.S.D.): RELOCATION OF 42 INCH FEEDER MAIN OAKWOOD AVE. SECTION, RUNNING EAST FROM STEEL ST. AT OAKWOOD AVE. (M.V.S.D. STA. 67+00) TO A CROSS CONNECTION VALVE VAULT AT SALT SPRINGS ROAD (M.V.S.D. STA. 86+23) THEN RUNNING SOUTH IN SALT SPRINGS ROAD UNDER MAHONING AVE. BRIDGE AT PRICE ROAD (M.V.S.D. STA. 107+50). THIS RELOCATION WORK OCCURS BETWEEN EXPRESSWAY STATION 930+00 AND STATION 959+00.

THE LOCATIONS OF THESE UNDERGROUND UTILITIES SHOWN ON THE PLANS HAVE BEEN OBTAINED BY DILIGENT FIELD CHECKS AND SEARCHES OF AVAILABLE RECORDS. THE LOCATION, TYPE, DEPTH, AND SIZE OF ALL EXISTING PIPES ARE SHOWN AS NEAR EXACT AS THE ABAILABLE INFORMATION WILL PERMIT. IT IS BELIEVED THAT THEY ARE ESSENTIALLY CORRECT, BUT THE STATE OF OHIO MAKES NO GUARANTEES AS TO THEIR ACCURACY OR COMPLETENESS. THE STATE WILL NOT BE RESPONSIBLE FOR ANY VARIATIONS FOUND DURING CONSTRUCTION.

THERE WILL BE NO SEPERATE PAYMENT FOR EXCAVATION FOR WATER AND SEWER LINES. REQUIRED EXCAVATION OVER AND ABOVE THAT INDICATED FOR ROADWAY EXCAVATION SHALL BE INCLUDED IN THE APPROPRIATE UNIT PRICE FOR SEWERS ETC..

SHEETING AND BRACING ORDERED LEFT IN PLACE SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE BID PER SQUARE FOOT UNDER ITEM E-2 "SHEET PILING LEFT IN PLACE."

WHERE CONCRETE ENCASED SEWER OR WATER PIPES ARE REQUIRED SUCH ENCASEMENT WILL BE INCLUDED IN UNIT PRICE BID FOR FURNISHING AND LAYING PIPE, ITEM 1-2 COMBINED SEWERS CONCRETE ENCASED OR ITEM 1-12H NEW WATER MAINS, CONCRETE ENCASED. SEE SHEET 102 FOR DETAILS.

WHERE CONCRETE ENCASEMENT IS REQUIRED FOR EXISTING WATER LINES IT SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE BID PER LINEAL FOOT UNDER ITEM 1-12H ENCASEMENT OF EXISTING WATER MAINS. SEE SHEET 102 FOR DETAILS.

THE CONSTRUCTION OR RELOCATED WATER MAINS OWNED BY THE CITY OF YOUNGSTOWN AND THE MAHONING VALLEY SANITARY DISTRICT WILL BE SUBJECT TO THE INSPECTION AND APPROVAL OF THE CITY AND DISTRICT AS SEPARATELY AFFECTED.

THE CONTRACTOR SHALL NOTIFY CITY OF YOUNGSTOWN WATER DEPARTMENT OR MAHONING VALLEY SANITARY DISTRICT 48 HOURS IN ADVANCE OF BREAKING GROUND ON EACH WATER MAIN RELOCATION. HE WILL OBTAIN PERMISSION FROM APROPRIATE AUTHORITY BEFORE TAKING ANY WATER MAIN OUT OF SERVICE. HE WILL ARRANGE WORK AND MATERIALS IN ADVANCE SO THAT ANY WATER MAIN WILL BE OUT OF SERVICE A MINIMUM PERIOD OF TIME.

ALL CONSTRUCTION ON WATER MAINS SHALL CONFORM TO STATE OF OHIO DEPARTMENT OF HIGHWAYS SUPPLEMENTAL SPECIFICATION 1-12H, AS AMENDED HEREIN.

NO SEPERATE PAYMENT WILL BE MADE FOR CONCRETE ANCHORAGES OR CONCRETE THRUST BLOCKS REQUIRED IN LAYING WATER LINES. THE COST FOR SUCH CONCRETE SHALL BE INCLUDED IN UNIT PRICE BID FOR ITEM 1-12H "NEW WATER MAINS."

THE DRAWINGS SHOW THE LOCATION AND PROFILE OF THE LINE TO BE LAID, AND TYPICAL DETAILS OF THE PIPING AND STRUCTURES. DEPENDING UPON THE TYPE OF PIPE TO BE USED, THE LINE AND GRADE OF THE WATER PIPE MAY BE MODIFIED SLIGHTLY SO THAT CURVATURE MAY BE MADE INSOFAR AS PROPER AT THE JOINTS WITHOUT USE OF SPECIAL FITTINGS. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR THE PARTICULAR TYPE OF PIPE CHOSEN AT THE AWARD OF CONTRACT. ALL PROPOSED MODIFICATIONS FROM THE PIPE PROFILE SHOWN ON THE DRAWINGS SHALL BE SUBMITTED IN DETAIL TO THE ENGINEER FOR APPROVAL BEFORE ANY MATERIAL IS ORDERED.

WHERE ABANDONED SEWER PIPES OR WATER MAINS ARE ENCOUNTERED DURING CONSTRUCTION; THE PIPES SHALL BE CUT AND PLUGGED IN ACCORDANCE WITH METHODS OUTLINED IN SECTION 116.03. PAYMENT FOR CUTTING AND PLUGGING AND REMOVAL OF THE PIPE WITHIN THE LIMITS OF CONSTRUCTION SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM E-1 "ROADWAY EXCAVATION METHOD "B"

PROPOSED SEWERS AND WATER MAINS UNDER EXISTING PAVEMENT:

REPLACEMENT OF EXISTING PAVEMENT FOR CONSTRUCTION OF PROPOSED SEWERS AND WATER MAINS SHALL BE AS SHOWN ON SHEET #30. REMOVAL AND REPLACEMENT OF EXISTING PAVEMENT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE BID FOR ITEM B-70 "PORTLAND CEMENT CONCRETE BASE COURSE FOR PAVEMENT REPLACEMENT," AND ITEM T-35 "ASPHALTIC CONCRETE SURFACE COURSE FOR PAVEMENT REPLACEMENT"

WHERE REFERENCE IS MADE TO ITEMS BY MEANS OF TRADE NAMES OR MANUFACTURERS, IT SHALL BE UNDERSTOOD THAT SUCH REFERENCE IS MADE FOR THE PURPOSE OF ESTABLISHING A STANDARD, AND THAT OTHER PRODUCTS WHICH CAN BE PROVEN FULLY EQUAL WILL BE EQUALLY ACCEPTABLE. BIDDERS WISHING TO OFFER SUBSTITUTIONS FOR THE STANDARDS NAMED SHALL SO INDICATE IN THEIR PROPOSAL. OTHERWISE BIDS WILL BE CONSTRUED TO BE BASED ON THE STANDARD, WHICH SHALL BE INSTALLED. IF SUBSTITUTIONS OFFERED ARE DEEMED NOT EQUAL, THE CONTRACTOR MAY BE REQUIRED TO PROVIDE THE STANDARD OR ITS EQUAL AT NO CHANGE FROM BID PRICE.

REMOVAL OF EXISTING 42" FEEDER MAIN:

ALL EXISTING 42" MAHONING VALLEY SANITARY DISTRICT FEEDER MAIN, WHICH IS REPLACED BY THE RELOCATED MAIN, WILL BE REMOVED BY THE CONTRACTOR. WHERE EXISTING MAIN IS UNCOVERED BY ROADWAY EXCAVATION THE PAYMENT FOR REMOVAL SHALL BE INCLUDED IN THE PRICE BID PER CU.YD. FOR ITEM E-1 ROADWAY EXCAVATION. ANY EXISTING MAIN WHICH HAS TO BE UNCOVERED OUTSIDE THE LIMITS OF ROADWAY EXCAVATION AND REMOVAL SHALL BE PAID FOR UNDER THE UNIT PRICE BID FOR ITEM E-12 42" PIPE REMOVAL.

CITY OF YOUNGSTOWN SEWER RELOCATIONS:

THE CONTRACTOR SHALL CONDUCT HIS OPERATION THAT THE FLOW OF ALL EXISTING SEWERS WILL BE MAINTAINED AT ALL TIMES. ANY ADDITIONAL LABOR OR COST INVOLVED IN MAINTAING THIS FLOW BY PUMPING OR BY ANY OTHER APPROVED METHOD WHICH IS NECESSARY FOR THE COMPLETION OF THIS PROJECT SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 1-2 "COMBINED SEWERS".

AT PLACES WHERE THE PLANS PROVIDE FOR PROPOSED SEWER PIPE TO CONNECT TO EXISTING PIPES; IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO LOCATE THE EXISTING PIPE AS TO LINE AND GRADE BEFORE HE STARTS TO LAY THE PROPOSED SEWER. THE COST OF THIS OPERATION SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE PERTINENT PIPE ITEM.

PAYMENT FOR REMOVAL AND/OR ABANDONING OF PIPE OUTLETS NECESSITATED BY THE ABANDONING OF EXISTING CATCH BASINS OR MANHOLES, SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 1-16 "MANHOLES, CATCH BASINS, OR INLETS ABANDONED" UNLESS PAYMENT IS OTHERWISE AUTHORIZED SPECIFICALLY UNDER OTHER ITEMS IN THE PLANS.

WHERE IT IS NECESSARY UNDER ITEM 1-8 "MANHOLES ADJUSTED TO GRADE" TO REPLACE UNSATISFACTORY MANHOLE FRAME AND COVER CASTINGS, PAYMENT FOR THE NEW CASTINGS SHALL BE MADE AT THE CONTRACT UNIT PRICE BID PER EACH FOR ITEM 1-8 "MANHOLE FRAME AND COVER FURNISHED AND PLACED". PAYMENT SHALL CONSTITUTE FULL COMPENSATION FOR FURNISHING, HAULING AND PLACING ALL CASTINGS AND INCIDENTALS NECESSARY TO COMPLETE THE ITEM TO THE SATISFACTION OF THE ENGINEER.

REMOVAL OF EXISTING HOUSE DRAINS:

NO SEPARATE PAYMENT WILL BE MADE FOR THE REMOVAL, FROM ABANDONED SITES, OF HOUSE CONNECTIONS, INCLUDING SANITARY, YARD, ROOF, BASEMENT OR OTHER SIMILAR PIPE DRAINS WITHIN THE ROADWAY CONSTRUCTION LIMITS, UNLESS SPECIFICALLY OTHERWISE ITEMIZE FOR PAYMENT ON THE PLANS.

WHERE AN EXISTING SEWER IS REPLACED BY A RELOCATED SEWER, NO SEPARATE PAYMENT WILL BE MADE FOR THE COST OF EXTENDING HOUSE CONNECTIONS TO THE NEW SEWER. THIS WORK SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 1-2 "COMBINED SEWERS". SEE SHEET # FOR CONNECTION DETAILS.

REINF. CONC. COMBINATION STORM AND SANITARY SEWER SHALL CONFORM TO ITEM 1-2 "COMBINATION SEWERS UNDER PAVEMENT AND APPROACHES", AS AMENDED HEREIN.

JOINTS SHALL BE OF THE SPIGOT AND SHOULDER TYPE UTILIZING A RUBBER GASKET RETAINED BETWEEN THE GROOVED CONCRETE SPIGOT AND THE CONCRETE SHOULDER, INSTALLED ACCORDING TO MANUFACTURERS RECOMMENDATIONS. EXTERIOR JOINT RECESS AND INTERIOR RECESS, FOR PIPE 30" AND LARGER, SHALL BE POINTED WITH CEMENT MORTAR.

PIPE SHALL BE COATED INSIDE WITH TWO COATS OF COAL TAR PITCH PAINT AT A RATE OF NOT MORE THAN 180 SQUARE PER GALLON PER COAT. WATERPROOFING MATERIAL SHALL CONSIST OF "INERTOL STANDARD THICK", "KAPPERS SUPER SERVICE", "PITT.-CHEM 103", OR EQUAL.

CITY OF YOUNGSTOWN WATER MAIN RELOCATIONS:

ALL WATER MAINS BELONGING TO THE CITY OF YOUNGSTOWN AND OVER 8 INCHES IN DIAMETER WILL BE REMOVED AND STORED ON THE RIGHT OF WAY FOR DISPOSAL BY THE CITY. THIS WORK WILL BE PERFORMED UNDER ITEM E-12 "PIPE REMOVAL FOR STORAGE".

ALL CAST IRON PIPE AND APPURTANCES USED IN WATER MAIN CONSTRUCTION WILL CONFORM TO OHIO SUPPLEMENTAL SPECIFICATION 1-124 AND SHALL BE OF MECHANICAL JOINT TYPE AND FITTED WITH LUGS FOR TIED OR HARNESSED JOINTS AT ALL BENDS WITH DEFLECTION GREATER THAN 5°

GATE VALVES: TO CONFORM TO A.W.W.A. SPECIFICATION. C-500 WITH THE FOLLOWING SUPPLEMENTAL SPECIFICATIONS. VALVE WILL BE: OF MECHANICAL JOINT; DOUBLE DISC, PARALLEL SEATS; NON-RISING STEM; CAST IRON STUFFING BOX AND SOLID BRASS GLAND; DISC TO BE CAST IRON WITH BRASS FACES; 16 INCH DIAMETER AND LARGER VALVES TO BE SUPPLIED WITH BY-PASSES, BEVEL GEARING, OPEN AND CLOSED INDICATOR WITH TRACKS, ROLLERS AND SCRAPERS OF HIGH GRADE BRONZE; VALVES ARRANGED TO OPEN BY TURNING TO RIGHT, CLOCKWISE; AND AN ARROW ON WRENCH NUT WILL SHOW DIRECTION OF TURN TO OPEN; WITH VALVE STEMS OF HIGH GRADE MANGANESE BRONZE.

FIRE HYDRANTS TO CONFORM TO A.W.W.A. SPECIFICATION C-502, WITH THE FOLLOWING SUPPLEMENTAL SPECIFICATION: FIRE HYDRANTS SHALL BE OF COMPRESSION TYPE, VALVES OPEN AGAINST PRESSURE; 6 INCH DIAMETER INLET CONNECTION TO FIT MECHANICAL JOINT AND WITH HARNESSING LUGS; BE FURNISHED WITH 2 HOSE NOZZLES 2½ INCH I.D. NAT. THD. FIRE HOSE COUPLING SCREW THREAD AND 1 PUMPER NOZZLE 4½ INCH I.D. YOUNGSTOWN STD. THD., SEE DETAIL, AND MATCHING CAPS; HAVE BURY LENGTH 5½ FEET; LEATHER NOZZLE CAP GASKET; DRAIN OPENING WITH LEATHER FACED VALVE; LEATHER FACED INLET VALVE NOT LESS THAN 5 INCH DIAMETER; BRONZE STUFFING BOX AND GLAND; OPERATING AND CAP NUTS BE OF BRASS OR BRONZE, SQUARE SHAPED, FINISHED WITH SLIGHT TAPER 27/32 INCH SQUARE ON TOP TO 29/32 INCH SQUARE ON BOTTOM AND STAND PIPE EXPOSED ABOVE SIDE WALK BE PAINTED FEDERAL ORANGE. SEE THREAD DETAIL SHEET #92.

VALVE BOXES WILL BE SIZE "B" WITH NO 6 ROUND BASE, ADJUSTABLE SCREW TYPE, SHAFT NOT LESS THAN 5¼ INCH DIAMETER. DROP COVER TO HAVE "WATER" CAST THERE ON AND RECESSED FOR EASE OF REMOVAL.

36 INCH PRESSURE PIPE DESCRIPTION:

THE CONTRACTOR SHALL FURNISH, DELIVER, STRING AND INSTALL, IN TRENCH, COMPLETE AND READY FOR SERVICE, INCLUDING TESTING, THE 36 INCH PRESSURE PIPE LINE IN PLUM STREET. PIPE MATERIALS AND TYPES OF CONSTRUCTION SHALL BE LIMITED TO REINFORCED CONCRETE PIPE, STEEL CYLINDER TYPE, PRESTRESSED, PRESSURE CLASS 150 P.S.I.

WATER METER BOXES:

THE CITY WATER WORKS DEPARTMENT WILL RELOCATE ALL PRIVATELY OWNED WATER METER BOXES AND THIS ITEM WILL NOT BE INCLUDED AS PART OF THE WORK TO BE PERFORMED BY THE STATE CONTRACTOR.

SPECIAL ATTENTION IS DIRECTED TO RELOCATION OF 36" AND 30 INCH SUPPLY MAINS IN PLUM STREET. THESE MAINS SUPPLY THE SOUTH WESTERLY SECTION OF YOUNGSTOWN WHICH HAS STORAGE FACILITIES SUFFICIENT FOR APPROXIMATELY FIVE (5) HOURS, (3,000,000 GAL.) PRIOR TO REMOVING THESE LINES FROM SERVICE THE CONTRACTOR SHALL: (1) ACCOMPLISH ALL POSSIBLE RELOCATION WORK; (2) HAVE ALL SUBSEQUENT NECESSARY MATERIALS AND EQUIPMENT AVAILABLE; (3) OBTAIN PERMISSION FROM CITY OF YOUNGSTOWN WATER DEPARTMENT TO TAKE LINE OUT OF SERVICE; (4) BREAK LINE AND ACCOMPLISH CONNECTIONS DURING PERIOD OF MINIMUM WATER DEMAND WHICH IS 11:00 P.M. TO 5:00 A.M.

EXISTING WATER MAIN CUT AND PLUGGED OUTSIDE ROAD WAY CONSTRUCTION LIMITS SHALL BE PAID FOR UNDER ITEM 1-12H NEW WATER MAIN AT CONTRACT UNIT PRICE BID PER EACH "CUT AND PLUG".

GENERAL NOTES
UTILITIES RELOCATION

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

10
492

MAHONING VALLEY SANITARY DISTRICT RELOCATIONS

MAHONING VALLEY SANITARY DISTRICT MANHOLES IN 42" FEEDER MAIN RELOCATION WORK WILL BE CONSTRUCTED AS SHOWN ON THE DETAILED DRAWINGS. THESE MANHOLES WILL BE CONSTRUCTED UNDER ITEM I-8 "MANHOLES SPECIAL" AS AMENDED FOR THIS CONTRACT. SEE DETAIL SHEET NO. 98.

42" FEEDER MAIN RELOCATION EAST OF STEEL STREET WILL REQUIRE SPECIAL PROTECTION AND SUPPORTS FOR MAINTAINING SERVICE IN EXISTING MAIN DURING RELOCATION WORK UNDER EXISTING MAIN.

42" FEEDER MAIN RELOCATION SOUTH OF VALVE VAULT IN SALT SPRINGS ROAD AREA WILL REQUIRE CAREFULL COORDINATION WITH 33 INCH SEWER RELOCATION IN THIS AREA. 33 INCH RELOCATION MUST BE COMPLETED BEFORE 42" WATER MAIN RELOCATION CAN BE ACCOMPLISHED AT STA. 114+60 VICINITY.

THE 42" FEEDER MAIN PROVIDES THE WATER SUPPLY FOR THE CITY OF YOUNGSTOWN. THIS LINE SHALL BE OUT OF SERVICE FOR THE SHORTEST POSSIBLE TIME. PRIOR TO REMOVING THIS LINE FROM SERVICE THE CONTRACTOR SHALL: (1) ACCOMPLISH ALL FOSSILBE RELOCATION WORK; (2) HAVE ALL SUBSEQUENT NECESSARY MATERIALS AND EQUIPMENT AVAILABLE; (3) OBTAIN PERMISSION FROM MAHONING VALLEY SANITARY DISTRICT TO TAKE THE LINE OUT OF SERVICE; (4) BREAK LINE AND ACCOMPLISH CONNECTIONS DURING PERIOD OF MINIMUM WATER DEMAND WHICH IS 11:00 P.M. TO 3:00 A.M.

CAST IRON PIPE, VALVES, AND APPURTENANCES SHALL CONFORM TO THE REQUIREMENTS STIPULATED UNDER CITY OF YOUNGSTOWN WATER MAIN RELOCATIONS, HEREINBEFORE.

ALL EXISTING 42" PIPE, REPLACED BY RELOCATION, SHALL BE REMOVED WITH NO ATTEMPT TO SALVAGE FOR MAHONING VALLEY SANITARY DISTRICT.

42 INCH PRESSURE PIPE
DESCRIPTION:

THE CONTRACTOR SHALL FURNISH, DELIVER, STRING AND INSTALL IN THE TRENCH, COMPLETE AND READY FOR SERVICE, INCLUDING TESTING, THE 42 INCH PRESSURE PIPE LINE OF THE TYPE AND MATERIAL SELECTED FROM THE SEVERAL ALTERNATE MATERIALS AND TYPES OF CONSTRUCTION OFFERED IN THE PROPOSAL.

IT IS INTENDED THAT THE TYPE AND MATERIAL OF THE PIPE WILL BE UNIFORM THROUGHOUT THIS SECTION OF THE RELOCATION.

THE ALTERNATE PIPE MATERIALS AND TYPES OF CONSTRUCTION SHALL BE AS SPECIFIED HEREIN AND SHALL BE LIMITED TO THE FOLLOWING:

(1) WELDED STEEL PIPE WITH COUPLED JOINTS

(2) REINFORCED CONCRETE PIPE, STEEL CYLINDER TYPE, PRESTRESSED, PRESSURE CLASS 150 PSI.

GENERAL SPECIFICATIONS FOR WATER LINES:

THIS ITEM CONSISTS OF FURNISHING ALL MATERIALS, EXCAVATION, AND BACKFILLING, CONSTRUCTING ALL NECESSARY JOINST AND CONNECTIONS, HYDROSTATIC TESTING, DISINFECTION, PROVIDING PROTECTIVE COATING, AND DISPOSAL OF ALL SURPLUS EXCAVATION AND DISCARDED MATERIAL WHICH MAY BE REQUIRED TO COMPLETE THIS ITEM. IN ACCORDANCE WMTH SPECIFICATIONS I-124 AS AMENDED HEREIN, SEE SECTION I-124.13 FOR BASIS OF PAYMENT.

EXCAVATION AND BACKFILL

EXCAVATION SHALL INCLUDE THE REMOVAL, HANDLING, REHANDLING, REFILL AND DISPOSAL OF ANY AND ALL MATERIALS ENCOUNTERED IN THE WORK AND SHALL INCLUDE ALL PUMPING, BAILING, DRAINAGE AND TEMPORARY SHEETING AND BRACING. THE WORK OF EXCAVATION SHALL ALSO INCLUDE THE RESPONSIBILITY FOR ADDED EXPENSE OR OTHER LIABILITY WHICH MAY ARISE FROM QUICKSAND, OBSTICLES OR CONDITIONS, FORESEEN AND UNFORESEEN, AND ENCOUNTERED IN THE WORK OF THIS CONTRACT.

THE USE OF EXCAVATING MACHINERY WILL BE PERMITTED EXCEPT IN PLACES WHERE OPERATION OF SAME WILL CAUSE DAMAGE TO ADJACENT PROPERTY, STRUCTURES OR COMPLETED WORK, IN WHICH CASE HAND METHODS SHALL BE EMPLOYED.

MAINTANENCE OF EXCAVATIONS:

THE CONTRACTOR SHALL MAINTAIN ALL EXCAVATIONS IN GOOD ORDER DURING THE CONSTRUCTION SO AS NOT TO HINDER OR INJURE THE PIPE LAYING, MASONRY WORK OR OTHER WORK. HE SHALL TAKE ALL REASONABLE PRECAUTIONS TO PREVENT MOVEMENT OF THE SIDES OF SUCH EXCAVATIONS, AND SHALL REMOVE AT HIS OWN EXPENXE ANY MATERIAL SLIDING INTO THE EXCAVATION.

THE CONTRACTOR SHALL FURNISH AND PUT IN PLACE SUCH SHEETING AND BRACING AS MAY BE REQUIRED TO SUPPORT THE SIDES OF ALL TRENCHES OR OTHER EXCAVATIONS, AND SHALL REMOVE SUCH SHEETING AND BRACING AS THE TRENCH OR EXCAVATION IS FILLED UP, UNLESS THE ENGINEER SHALL ORDER IT LEFT IN PLACE.

EXCLUSION OR REMOVAL OF WATER:

THE CONTRACTOR SHALL AT ALL TIMES DURING CONSTRUCTION, PROVIDE PROPER AND SATISFACTORY MEANS AND DEVICES FOR THE EXCLUSION OR REMOVAL OF WATER ENTERING THE EXCAVATION, AND SHALL REMOVE ALL SUCH WATER AS FAST AS IT MAY COLLECT IN SUCH A MANNER AS SHALL NOT INTERFERE WITH THE PROSECUTION OF THE WORK.

PROTECTION OF PIPES AND DRAINS, ETC.:

THE CONTRACTOR SHALL PROVIDE SUITABLE TEMPORARY CHANNELS OF FLOW FOR ALL WATER COURSES AND SHALL HOLD THE DISTRICT AND CITY HARMLESS AGAINST ALL CLAIMS FOR DAMAGES GROWING OUT OF OBSTRUCTIONS TO THE FLOW OF SEWERS, DRAINS, DITCHES OR GUTTERS, OR BECAUSE OF INJURY TO OIL, GAS, WATER OR OTHER PIPES OR CONDUITS OR FIXTURES RELATING TO THE SAME, AND HE SHALL GIVE WRITTEN NOTICE TO THE OWNER (OR OWNERS) OF SUCH PIPES OR FIXTURES IN TIME TO PERMIT SUCH OWNERS TO CO-OPERATE WITH HIM IN PROTECTING THEIR PROPERTY.

SURPLUS EXCAVATED MATERIAL, OVER AND ABOVE THAT REQUIRED FOR BACKFILLING, MOUNDING OVER THE PIPE AND MAKING OTHER FILLS AND EMBANKMENTS TO THE FINISHED LINES AND GRADES INDICATED ON THE DRAWINGS OR DIRECTED BY THE ENGINEER, SHALL BE DISPOSED OF BY DUMPING AT SUCH LOCATIONS AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SEEING THAT THE MATERIAL IS DUMPED IN AN ORDERLY MANNER WITHIN THE LIMITS DESIGNATED.

BACKFILLING SHALL BE DONE FIRST OVER THE MIDDLE PORTION OF EACH LENGTH OF PIPE, LEAVING ALL FIELD JOINTS EXPOSED. THE FIELD JOINTS SHALL BE LEFT IN THIS CONDITION UNTIL AFTER THE PIPE HAS BEEN TESTED FOR TIGHTNESS. AFTER THE PIPE HAS BEEN TESTED AND ACCEPTED BY THE ENGINEER, BACKFILLING SHALL BE COMPLETED AT THE JOINTS.

FILLING AGAINST THE WALLS OF STRUCTURES SHALL BE DONE AS ORDERED, AND NOT UNTIL THE WALLS HAVE ACQUIRED SUFFICIENT STRENGTH AND ARE SUFFICIENTLY CURED AND REINFORCED BY THE ADJACENT MASONRY TO TAKE THE THRUST SAFELY.

IF ANY OF THE REFILLS SHALL SETTLE SO AS TO BE BELOW THE REQUIRED LEVELS FOR THE PROPOSED FINISHED SURFACE AT ANY PLACE, BEFORE THE FINAL ACCEPTANCE OF THE WORK TO BE DONE UNDER THIS CONTRACT, THE CONTRACTOR SHALL, AT HIS OWN EXPENSE AND COST, SUPPLY ADDITIONAL MATERIALS AND BUILD UP THE LOW PLACES AS DIRECTED.

SPECIFICATIONS FOR WELDED STEEL PIPE:

THE WELDED STEEL PIPE FURNISHED AND LAID SHALL BE MANUFACTURED, TESTED, MARKED, HANDLED AND DELIVERED IN CONFORMITY WITH THE AMERICAN WATER WORKS ASSOCIATION STANDARD SPECIFICATION FOR ELECTRIC FUSION WELDED STEEL WATER PIPE OF SIZES 30 INCHES AND OVER (AMERICAN WATER WORKS ASSOCIATION NUMBER C 201), WITH A WALL THICKNESS OF NOT LESS THAN 1/2 INCH, AND MAY BE DELIVERED IN STANDARD LENGTHS OF 20 FEET, 30 FEET, OR 40 FEET, AS THE CONTRACTOR MAY ELECT. ALL PIPE TO BE LAID SHALL BE CAPABLE OF WITHSTANDING WATER WORKING PRESSURES OF 150 PSI (300 PSI SHOP TEST). GIRTH SEAMS SHALL BE NOT LESS THAN 5 FEET APART.

THE EXTERIOR AND INTERIOR SURFACE OF ALL WELDED STEEL PIPE SHALL BE CLEANED AND COATED AS FOLLOWS:

THE INTERIOR SURFACE OF THE PIPE SHALL RECEIVE A COAT OF COAL-TAR PRIMER FOLLOWED BY A HOT COAT OF COAL-TAR ENAMEL APPLIED BY MECHANICAL MEANS.

THE EXTERIOR SURFACE OF THE PIPE SHALL RECIEVE A COAT OF COAL-TAR PRIMER FOLLOWED BY A HOT COAT OF COAL-TAR ENAMEL. AN ASBESTOS COAL-TAR SATURATION BELT WRAPPING SHALL THEN BE APPLIED, AND SHALL BE FOLLOWED BY A SURFACE COAT OF WATER-RESISTANT WHITE-WASH.

ALL PIPE COATING MATERIALS SHALL BE BITUMINOUS JET SET PRIMER AND BITUMASTIC 70-B ENAMEL AS MANUFACTURED BY THE KOPPERS COMPANY, INC., PITTSBURGH, PENNSYLVANIA, OR EQUAL, AND SHALL CONFORM TO MATERIAL SPECIFICATIONS AND SHALL BE APPLIED AND TESTED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR COAL-TAR ENAMEL PROTECTIVE COATINGS FOR STEEL WATER PIPE, SIZES 30 INCH AND OVER (A.W.W.A. C203-51).

FOR PIPE COATING TEST PURPOSES, THE CONTRACTOR SHALL FURNISH A PORTABLE ENGINE-GENERATOR UNIT TO PROVIDE A SOURCE OF 110 VOLT A.C. ELECTRIC CURRENT. THE CONTRACTOR SHALL FURNISH ALL FUEL AND SHALL MAINTAIN THE UNIT IN SATISFACTORY OPERATING CONDITION FOR AS LONG A PERIOD OF TIME AS NECESSARY TO COMPLETE THE PIPE COATING TESTS. THE UNIT SHALL REMAIN THE PROPERTY OF THE CONTRACTOR.

THE FIELD JOINTS IN THE STEEL PIPE LINE SHALL BE MADE UP WITH DRESSER OR EQUAL MECHANICAL COUPLINGS. PIPE ENDS SHALL BE PREPARED WITH PLAIN ENDS FOR MECHANICAL COUPLINGS AND, IN ADDITION, ANY SPECIAL ENDS REQUIRED FOR APPURTENANCES.

THE ENDS OF THE PIPE WHERE DRESSER TYPE COUPLINGS ARE USED SHALL BE NOT MORE THAN ONE THIRTY-SECOND (1/32) OF AN INCH SMALLER THAN THE NOMINAL OUTSIDE DIAMETER OF THE PIPE FOR A DISTANCE OF TWELVE (12) INCHES FROM THE ENDS OF THE PIPE, AND SHALL PERMIT THE PASSING FOR THAT DISTANCE OF A GAUGE RING WHICH HAS AN INTERNAL BORE OF THREE THIRTY-SECOND (3/32) OF AN INCH LARGER THAN THE NOMINAL OUTSIDE DIAMETER OF THE PIPE. THE OUTSIDE DIAMETER OF THE PIPE IS TO BE DETERMINED BEFORE SHIPMENT BY THE USE OF A STEEL TAPE CIRCUMFERENTIALLY APPLIED TO PREVENT THE COATING AND SHIPMENT OF UNDERSIZED PIPE, OR USE OF PIPE WHICH, MEASURED DIAMETRICALLY THE LONG WAY, MIGHT APPEAR TO BE UP TO SIZE.

SPECIAL SECTIONS, CLOSURE PIECES, FABRICATED STEEL FITTINGS, AND ADAPTORS, SHALL BE OF THE SAME MATERIALS AND FABRICATION, STRENGTHS AND COATINGS, AS THE PIPE LINE IN WHICH INSTALLED. WHEN CLOSURE PIECES ARE REQUIRED IN THE FIELD FOR STEEL PIPE, THE CONTRACTOR WILL BE REQUIRED TO MAKE MEASUREMENTS FOR THE SAME AND HE SHALL BE RESPONSIBLE FOR THE CORRECTNESS OF THE PIECES.

WHERE PIPE IS CUT WITH AN ACETYLENE TORCH OF SIMILAR METHOD, THE BURNED EDGES SHALL BE GROUND OR CHIPPED SMOOTH BEFORE MAKING JOINTS. WHERE REQUIRED, LONGITUDINAL WELDS SHALL BE GROUND OR CHIPPED TO THE PIPE SURFACE TO CLEAR DRESSER COUPLINGS. THE PIPE COATING AND WRAPPING DAMAGED IN CUTTING OFF THE ENDS OF CLOSURE PIECES OR OTHERWISE SHALL BE REPAIRED AS SET FORTH IN APPLICABLE SECTIONS OF THE AMERICAN WATER WORKS ASSOCIATION SPECIFICATIONS C203.

UPON DEMAND OF THE ENGINEER, THE MANUFACTURER SHALL PERFORM SUCH ADDITIONAL NUMBER OF TESTS AS HE MAY DEEM NECESSARY TO ESTABLISH THE QUALITY OF THE MATERIAL OFFERED FOR USE. THE ENGINEER SHALL BE FURNISHED WITH CERTIFIED RECORDS OR REPORTS OF THE RESULTS OF ALL TESTS, SUCH RECORDS OR REPORTS TO CONTAIN A SWORN STATEMENT THAT THE TESTS HAVE BEEN MADE AS SPECIFIED. THE ENGINEER SHALL BE AT LIBERTY AT ALL TIMES TO INSPECT THE PIPE AND MATERIAL AT THE PLANT INCLUDING THE COATING OF THE PIPES. THE SIZES, UNIFORMITY AND CONDITION OF ALL PIPES HEREIN REFERRED TO SHALL BE SUBJECT TO HIS INSPECTION AND APPROVAL AND HE MAY REJECT WITHOUT PROVING, ANY PIPE WHICH IS NOT IN CONFORMITY WITH THE SPECIFICATIONS OR DRAWINGS.

SPECIFICATIONS FOR REINFORCED CONCRETE PIPE:

THE REINFORCED CONCRETE PIPE TO BE FURNISHED AND LAID SHALL BE OF MATERIALS AND FABRICATION IN CONFORMITY WITH THE AMERICAN WATER WORKS ASSOCIATION STANDARD SPECIFICATIONS FOR REINFORCED CONCRETE WATER PIPE, STEEL CYLINDER TYPE, PRESTRESSED (A.W.W.A. C301-58) WITH NON-EMBEDDED STEEL CYLINDER, HAVING MINIMUM THICKNESSES NOT LESS THAN THOSE TABULATED FOR 42 INCH PIPE AND FOR 36 INCH PIPE AND SHALL BE DELIVERED IN STANDARD LENGTHS OF 16 FEET. ALL PIPE TO BE LAID SHALL BE CAPABLE OF WITHSTANDING WATER WORKING PRESSURES UP TO 150 PSI (275 PSI SHOP TEST).

IN ADDITION TO THE TESTS REQUIRED UNDER A.W.W.A. SPECIFICATIONS C301, THE PIPE SHALL BE TESTED AT THE PLACE OF MANUFACTURE IN ACCORDANCE WITH THE FOLLOWING SPECIFICATIONS:

THE PIPE MANUFACTURER WILL BE REQUIRED TO MANUFACTURE ONE (1) SAMPLE OF EACH CLASS 150 PIPE OF 42" DIAMETER AND OF 36" DIAMETER MADE IN ACCORDANCE WITH THE TENTATIVELY APPROVED DESIGN FOR TESTS UNDER THE SUPERVISION OF THE ENGINEER.

THE ENGINEER SHALL SUPERVISE THE FABRICATION AND MANUFACTURE OF THE SAMPLE OF EACH PIPE AND RECORD THE MATERIALS USED, THE DATES OF MANUFACTURE AND PERIODS OF CURING AND ESTABLISH THE DATES FOR CONDUCTING THE REQUIRED TESTS.

THE METHOD OF TESTING SHALL BE THE SAME AS THAT USED FOR REINFORCED CONCRETE CULVERT PIPE AND SHALL, IN ALL RESPECTS CONFORM TO THE REQUIREMENTS OF THE SPECIFICATIONS FOR REINFORCED CONCRETE CULVERT PIPE (A.S.T.M. DESIGNATION: C76).

THE SAMPLE OF EACH PIPE SHALL SUPPORT WITHOUT RUPTURE OR INJURIOUS CRACKS OR DAMAGE FOR THIRTY (30) MINUTES A SUPERIMPOSED LOAD OF 11,000 LBS. PER LINEAL FOOT. A CRACK OF .01 INCH OR MORE IN WIDTH FOR A LENGTH OF ONE (1) FOOT OR MORE SHALL BE CONSIDERED INJURIOUS AND RENDER THE PIPE UNACCEPTABLE WHEN IT OCCURS AT 75% OR LESS OF THE ABOVE ULTIMATE CRUSHING LOAD (11,000 LB/FT.).

A LENGTH OF THE CLASS 150 OF EACH SAMPLE PIPE SHALL THEN BE SUBJECTED TO AN INTERNAL PRESSURE OF 275 PSI FOR AT LEAST THIRTY (30) MINUTES WITHOUT DAMAGE, RUPTURE, CRACKS, OR LEAKAGE. THE PIPE SHALL ALSO BE REQUIRED TO SUPPORT AN INTERNAL PRESSURE OF 550 PSI WITHOUT BURSTING.

EACH PIECE OF PIPE MANUFACTURED SHALL BE STAMPED OR MARKED TO SHOW THE FOLLOWING:

1. DATE OF MANUFACTURE
2. NUMBER OF UNITS MANUFACTURED THAT DATE FOR THIS CONTRACT.

FAILURE OF PIPE AS TESTED SHALL BE CONSIDERED AS JUST CAUSE TO REJECT ALL PIPE IDENTIFIED OR MARKED AS MANUFACTURED SAME DATE AS SAMPLE.

THE YARD TEST OF 275 PSI SHALL BE APPLIED TO ONE (1) LENGTH OUT OF EACH ONE THOUSAND (1,000) FEET OF PIPE FABRICATED FOR THE JOB AND SHALL BE SELECTED BY THE ENGINEER AT RANDOM FROM THE SUPPLIER'S FABRICATION YARD AFTER THE PIPE HAS REACHED ITS DESIGNED AGE (APPROXIMATELY 28 DAYS). THE PIPE MUST WITHSTAND THIS TEST WITHOUT CRACKING & WITHOUT LEAKAGE.

UPON DEMAND OF THE ENGINEER, THE MANUFACTURER SHALL PERFORM SUCH ADDITIONAL NUMBER OF TESTS AS HE MAY DEEM NECESSARY TO ESTABLISH THE QUALITY OF THE MATERIAL OFFERED FOR USE. THE ENGINEER SHALL BE FURNISHED WITH CERTIFIED RECORDS OR REPORTS OF THE RESULTS OF ALL TESTS, SUCH RECORDS OR REPORTS TO CONTAIN A SWORN STATEMENT THAT THE TESTS HAVE BEEN MADE AS SPECIFIED.

SPECIAL SECTIONS, CLOSURE PIECES, BENDS, ADAPTERS AND OTHER SPECIAL FITTINGS SHALL BE OF THE SAME MATERIALS AND FABRICATION AS THE PIPE LINE IN WHICH INSTALLED.

SPECIFICATIONS FOR HANDLING OF PIPE

MARKING ALL PIPE:

EACH SECTION OF PIPE AND EACH SPECIAL SHALL HAVE CONSPICUOUSLY PAINTED ON THE INSIDE THE DATE OF MANUFACTURE AND SERIAL NUMBER FOR IDENTIFICATION AND THE WORKING PRESSURE FOR WHICH INTENDED. ALL SPECIALS SHALL HAVE THE TOP CENTERLINE CONSPICUOUSLY MARKED ON THE INSIDE AND THE OUTSIDE OF THE PIPE. THE CONTRACTOR SHALL FURNISH THE ENGINEER WITH FIELD SKETCHES AND SCHEDULES SHOWING WHERE EACH NUMBERED PIPE AND SPECIAL GOES IN THE LINE.

DELIVERY:

THE ORDER AND DESTINATION OF DELIVERY OF THE VARIOUS PIECES OF PIPE AND SPECIALS SHALL BE DETERMINED BY THE CONTRACTOR, SUBJECT TO THE APPROVAL OF THE ENGINEER, AND THE MANUFACTURER SHALL RECEIVE SHIPPING INSTRUCTIONS FROM THE CONTRACTOR.

NO CONCRETE PIPE SHALL BE SHIPPED UNTIL THE STRENGTH OF THE CONCRETE HAS REACHED 4500 PSI.

HANDLING:

ALL PIPE SHALL BE HANDLED AND TRANSPORTED AT ALL TIMES WITH THE SUITABLE CARE AND PRECAUTIONS REQUIRED FOR THE PARTICULAR MATERIAL AND CONSTRUCTION OF THE PIPE.

ALL COATED PIPE SHALL BE HANDLED, STACKED AND STORED IN SUCH MANNER AS NOT TO DAMAGE THE COATING ON EITHER INSIDE OR OUTSIDE OF PIPE. STEEL PIPE WITH COAL-TAR EXTERIOR FELT WRAPPED COATINGS SHALL BE HANDLED AT ALL TIMES WITH PROPER EQUIPMENT, SUCH AS STOUT WIDE CANVAS SLINGS AND WIDE PADDED SKIDS DESIGNED TO PREVENT DAMAGE TO THE COATINGS. ALL PIPES WITH COAL-TAR PROTECTIVE TREATMENT SHALL BE HANDLED WITH SUCH EQUIPMENT AND TOOLS AS WILL NOT SERIOUSLY ABRADE, CHIP, INDENT OR REMOVE THE INTERIOR OR EXTERIOR COATING. DUMPING OF PIPE FROM TRUCK OR CONVEYOR WILL NOT BE PERMITTED.

DELIVERY INSPECTION:

EACH PIPE SECTION WILL BE INSPECTED AS IT IS DELIVERED ON THE JOB EITHER AT THE CAR UNLOADING POINT OR AT THE POINT OF UNLOADING FROM THE TRUCKS IN STRINGING ALONG THE LINE. ANY PIPE SECTION OR SPECIAL SECTION THAT SHOWS DENTS, KINKS, ABRUPT CHANGES OF CURVATURE OTHER THAN DETAILED OR SPECIFIED, AND/OR ANY OTHER INJURIES AT THE DELIVERY POINT, MAY BE REJECTED. ANY PIPE SECTION OR SPECIAL SECTION THAT HAS BEEN DROPPED FROM A TRUCK OR CRANE OR HAS OTHERWISE RECEIVED A DAMAGING SHOCK PRIOR TO COMPLETION OF DELIVERY WILL BE REJECTED.

REJECTED SECTIONS OF PIPE MAY BE REPAIRED OR RECONDITIONED OR SECTIONS THEREFROM MAY BE SALVAGED ON THE APPROVAL AND UNDER THE DIRECTIONS AND SUPERVISION OF THE ENGINEER AND SUBJECT TO HIS COMPLETE SATISFACTION AND RETESTING BOTH PHYSICALLY AND UNDER HYDRAULIC PRESSURE.

STORAGE:

EACH SECTION OF STEEL PIPE, AS IT IS DELIVERED ALONG THE LINE OF THE WORK, SHALL BE STORED ON TIMBERS NOT LESS THAN 3 FEET LONG WHICH SHALL REMAIN UNDER THE PIPE UNTIL IT IS MOVED INTO THE TRENCH. CONCRETE PIPE SHALL BE STORED DIRECTLY ON THE GROUND AND WEDGED TO PREVENT THE PIPE FROM ROLLING.

GENERAL NOTES
UTILITIES RELOCATION

FED. RD	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

11
492

SPECIFICATIONS FOR INSTALLATION

LAYING:

WHILE THE PIPE IS SUSPENDED, IN BEING PLACED IN TRENCH, IT SHALL BE CAREFULLY INSPECTED AND ALL ABRASIONS OF COATING ON EXTERIOR SURFACE THAT WILL BE INACCESSIBLE AFTER LAYING SHALL BE SATISFACTORILY REPAIRED.

WHERE PIPE IS TO BE SURROUNDED OR CRADLED WITH CONCRETE, IT SHALL BE LAID ON SUITABLE WOODEN BLOCKING TO MAINTAIN IT AT GRADE UNTIL THE CONCRETE IS PLACED; THE BLOCKING SHALL BE REMOVED FROM TIME TO TIME AS THE WORK OF CONCRETING PROCEEDS.

NO PIPE SHALL BE LAID IN WATER, OR WHEN THE TRENCH CONDITIONS OR THE WEATHER IS UNSUITABLE FOR SUCH WORK, EXCEPT BY PERMISSION OF THE ENGINEER.

WHENEVER NECESSARY TO DEFLECT PIPE FROM A STRAIGHT LINE, EITHER IN THE VERTICAL OR HORIZONTAL PLANE THE DEGREE OF DEFLECTION PER JOINT SHALL BE AS APPROVED BY THE ENGINEER.

WORKMEN SHALL NOT ENTER STEEL COATED PIPE AT ANY TIME WITHOUT WEARING RUBBERS, RUBBER BOOTS, OR SOFT SLIPPERS AND CARE SHALL BE TAKEN AT ALL TIMES TO PREVENT DAMAGE TO THE INTERIOR PROTECTIVE LINING.

FIELD JOINTS IN STEEL PIPE:

ALL FIELD JOINTS BETWEEN SECTIONS OF STEEL PIPE SHALL BE MADE WITH MECHANICAL COUPLINGS EQUAL TO DRESSER STYLE NO. 38, AS MANUFACTURED BY THE MANUFACTURING DIVISION OF THE DRESSER INDUSTRIES, BRADFORD, PA.

THE PIPE COUPLINGS SHALL BE OF A GASKETED, SLEEVE TYPE, WITH DIAMETER TO PROPERLY FIT THE PIPE. EACH COUPLING SHALL CONSIST OF TWO FOLLOWER FLANGES, ONE STEEL MIDDLE RING, TWO MOULDED RUBBER GASKETS, AND SUFFICIENT ROLLED THREAD, TRACK HEADED BOLTS TO PROPERLY COMPRESS THE GASKETS. THE MIDDLE RING OF THE COUPLINGS SHALL BE NOT LESS THAN THE THICKNESS OF PIPE AND SHALL BE EIGHT (8) INCHES IN LENGTH. THE STEEL MIDDLE RING SHALL BE JOINED BY A WELD OF UNIFORM STRENGTH MADE BY AN APPROVED ELECTRICAL PROCESS. THE RING SHALL DEVELOP THE FULL TENSILE STRENGTH OF THE PLATE. THE MIDDLE RING SHALL BE TESTED FOR POROSITY BY COMPRESSED AIR AND FOR STRENGTH BY STRESSING TO THE YIELDING POINT DURING THE SIZING OPERATION.

THE STEEL FOLLOWER FLANGES SHALL BE EITHER PRESSED FROM SOLID PLATE OR MADE OF BAR STOCK WELDED AS ABOVE. THEY SHALL ALSO BE STRENGTH TESTED AND ACCURATELY SIZED IN THE SAME MANNER AS THE MIDDLE RING.

THE MOULDED RUBBER GASKETS SHALL BE APPROXIMATELY ONE-EIGHTH(1/8) INCH SMALLER IN DIAMETER THAN THE THEORETICAL OUTSIDE DIAMETER OF THE PIPE AND SHALL BE OF A GRADE HAVING SATISFACTORY RECORD OF PERFORMANCE IN ACTUAL AND COMPARABLE SERVICE.

ALL METAL PARTS OF THE COUPLINGS INCLUDING BOLTS AND NUTS SHALL BE COATED AT THE SHOP WITH ONE (1) COAT OF BITUMINOUS PRIMER FURNISHED BY THE SAME MANUFACTURER WHO FURNISHED COATING FOR THE MAIN BODY OF THE PIPE.

AFTER EACH SECTION OF LINE HAS BEEN SATISFACTORILY TESTED, THE CONTRACTOR SHALL COMPLETELY COVER ALL MECHANICAL COUPLINGS AND PORTIONS OF THE PIPE WHICH ARE UNCOATED AND UNWRAPPED BY ENCLOSING THE ENDS OF THE PIPE AND THE COUPLINGS WITH A TIGHT CANVAS OR OTHER FABRICATION OR WITH LIGHT GAUGE METAL AND SHALL POUR THE SPACE INCLUDING THE COUPLINGS FULL OF COMPOUND OF THE SAME TYPE AS USED BY THE MANUFACTURER OF THE PIPE FOR THE ENAMEL COATING.

WITH MECHANICAL COUPLINGS ON THE PIPE ENDS, THE INTERIOR COATING WILL NOT BE DAMAGED AT THE JOINTS AND WILL NOT REQUIRE FIELD COATING EXCEPT TO REPAIR DAMAGE DISCOVERED ON FINAL INSPECTION.

DRESSER TYPE COUPLINGS WITH MIDDLE RING STOPS REMOVED SHALL BE SUPPLIED FOR USE AT CLOSURES.

FIELD JOINTS IN REINFORCED CONCRETE

BEFORE LAYING REINFORCED CONCRETE CYLINDER PIPE, THE PIPE ENDS SHALL BE MADE SMOOTH BY FILING, OR OTHER MEANS, WIRE BRUSHED AND WIPED CLEAN AND DRY. PIPE ENDS SHALL BE KEPT CLEAN UNTIL JOINTS ARE MADE. AFTER CLEANING AND DRYING, ALL CONTACT SURFACES OF THE GASKETS AND STEEL JOINT RINGS SHALL BE COATED WITH AN APPROVED VEGETABLE SOAP AND THE GASKET SNAPPED INTO THE GROOVE JUST BEFORE INSERTING THE SPIGOT END INTO THE SOCKET. IMMEDIATELY AFTER THE JOINT IS PULLED TOGETHER WITH WINCH CABLE AND "STRONG BACK", THE GASKET RING CHECKED AND THE PIPE BLOCKED IN PLACE, A HEAVY MUSLIN BAND 6" WIDE SHALL BE INSTALLED AROUND THE OUTSIDE OF THE PIPE JOINT AND SECURED THERE WITH WIRE TIES. THEN EARTH SHALL BE CAREFULLY TAMPED UNDER AND ON EACH SIDE OF THE PIPE UP TO THE SPRINGLINE OF THE PIPE. ALL BLOCKING SHALL BE REMOVED WHEN BACKFILLING HAS REACHED THE SPRINGLINE OF THE PIPE. THE ANNULAR SPACE OF THE JOINT UNDER THE MUSLIN STRIP SHALL THEN BE FILLED WITH THIN CEMENT GROUT OF PROPER CONSISTENCY. THE MUSLIN BAND SHALL BE LEFT IN PLACE AND, BEFORE THE GROUT HAS SET, THE UPPER PORTION OF THE JOINT SHALL BE MADE WITH 1:2 CEMENT MORTAR. THE INTERNAL RECESSES OF THE JOINT SHALL BE CAREFULLY FILLED WITH 1:2 CEMENT MORTAR WELL PRESSED AND CAULKED INTO PLACE BY HAND AND PROPERLY SMOOTHED OFF TO MAKE A FLUSH JOINT FOLLOWING THE APPROVAL OF THE FIELD TEST BY THE ENGINEER.

SPECIFICATIONS FOR FIELD TESTING

GENERAL:

AFTER THE PIPE IS LAID AND JOINTS MADE UP, THE MIDDLE PORTION OF EACH LENGTH MAY BE BACKFILLED, LEAVING THE JOINTS EXPOSED, AND THE PIPE LINE SHALL BE TESTED IN CONVENIENT LENGTHS. THE TEST PRESSURE TO BE APPLIED SHALL BE EQUIVALENT TO A HEAD OF WATER HAVING A FREE WATER SURFACE AT THE MID-POINT OF THE SECTION TESTED.

THE CONTRACTOR SHALL FURNISH THE NECESSARY CLEAN WATER, PUMPS, PIPES, CONNECTIONS AND TEMPORARY HEADS TO MAKE THESE TESTS. THE SPECIFIED PRESSURE SHALL BE MAINTAINED UNTIL ALL JOINTS CAN BE INSPECTED AND ALL LEAKS IN THE PIPE LINE UNDER TEST ARE PROPERLY MADE TIGHT TO THE SATISFACTION OF THE ENGINEER.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE TRENCH, PIPING OR ANY OF THE APPURTENANCES FURNISHED BY HIM; AND ANY PIPE, SPECIALS OR APPURTENANCES BROKEN BY SAID TEST SHALL BE AT ONCE REPLACE BY THE CONTRACTOR.

LEAKAGE TEST:

BEFORE FINAL ACCEPTANCE, THE LEAKAGE IN THE ENTIRE LINE OR APPROVED SECTIONS THEREOF SHALL BE MEASURED UNDER MAXIMUM OPERATING PRESSURE BY FILLING THE PIPE LINE AND MAINTAINING THE PRESSURE FOR ONE HOUR BY PUMPING ADDITIONAL WATER INTO THE MAIN AS MAY BE NECESSARY. THE QUANTITY OF WATER THUS PUMPED INTO THE MAIN MULTIPLIED BY TWENTY FOUR SHALL BE TAKEN AS THE LEAKAGE PER DAY.

THE PERMITTED LEAKAGE PER DAY UNDER THIS TEST SHALL NOT EXCEED ONE THOUSAND GALLONS PER MILE OF LENGTH WHEN SUBJECTED TO THE TEST PRESSURES OR TO THE MAXIMUM OPERATING PRESSURES PLUS 50 PSI. ALLOWANCE MAY BE MADE FOR ANY LEAKAGE AT VALVES, PLUGS, BULKHEADS, ETC. AS AGREED ON AND MEASURED DURING THE TEST. (IN GENERAL, THESE PRESSURES WILL RANGE FROM 150 PSI TO 50 PSI).

IF THE ACTUAL LEAKAGE IS GREATER THAN THE AMOUNT PERMITTED, THE LINE JOINTS SHALL BE TIGHTENED AS REQUIRED AND THE LEAKAGE TEST REPEATED UNTIL THE LINE MEETS THE REQUIREMENTS.

THE CONTRACTOR SHALL LEAVE THE TRENCH OPEN AT THE JOINTS UNTIL SATISFACTORY COMPLETION OF LEAKAGE TEST.

FED. RD.	STATE	PROJECT	
2	OHIO		

112
4-92

MAH-18-17.20

GENERAL NOTES

I-8 MANHOLE SPECIALS

UNDER THE PROVISIONS OF ITEM I-8 MANHOLES, CATCH BASINS, INLETS, MONUMENT ASSEMBLIES OR MONUMENT BOXES THE CONTRACTOR WILL CONSTRUCT THE NECESSARY MANHOLES REQUIRED IN THE RECONSTRUCTION OF THE 42" FEEDER WATER MAIN OWNED BY THE MAHONING VALLEY SANITARY DISTRICT AND SPECIAL MANHOLES FOR THE CITY OF YOUNGSTOWN. THE FOLLOWING SPECIFICATIONS ARE INTENDED TO SUPPLEMENT THE APPLICABLE PORTIONS OF ITEM I-8 FOR DEFINITION OF THE ADDITIONAL AND/OR SPECIAL CHARACTERISTICS OF THE MANHOLES.

THE FOLLOWING ITEM DESIGNATIONS ARE ASSIGNED TO THE SPECIAL MANHOLES REQUIRED:

ITEM I-8	MANHOLE	SPECIAL ACCESS MANHOLE	M.V S.D.
ITEM I-8	MANHOLE	SPECIAL AIR VALVE MANHOLE	M.V.S.D.
ITEM I-8	MANHOLE	SPECIAL COMBINATION AIR VALVE & ACCESS MANHOLE	M.V.S.D.
ITEM I-8	MANHOLE	SPECIAL BLOW OFF MANHOLE	M.V.S.D.
ITEM I-8	MANHOLE	SPECIAL BLOW OFF SETTING	M.V.S.D.
ITEM I-8	MANHOLE	SPECIAL YOUNGSTOWN STANDARD SEWER MANHOLES TYPE: Y-A; Y-B; Y-C; Y-D	C.O.Y.
ITEM I-8	MANHOLE	SPECIAL SEWAGE REGULATOR CHAMBER	C.O.Y.

PAYMENT FOR EACH OF THE ABOVE SPECIAL MANHOLES WILL BE AT THE PRICE BID PER EACH AND SAID PAYMENT SHALL CONSTITUTE FULL COMPENSATION FOR THE TOTAL CONSTRUCTION OF THE MANHOLE STRUCTURE, INCLUDING ALL EXCAVATION AND BACKFILL, FURNISHING AND HAULING AND PLACING ALL CASTINGS, REINFORCING STEEL, CONCRETE MASONRY, ALL PIPE AND SPECIALS, INCLUDING SPECIAL VALVES, PIPING AND INCIDENTALS EITHER DEFINED HEREIN OR DETAILED ON THE CONTRACT PLANS, ALL CONNECTIONS AND OTHER MATERIALS, ETC., AND FOR ALL LABOR, EQUIPMENT, TOOLS AND INCIDENTALS NECESSARY TO COMPLETE THIS ITEM. PIPING AND APPURTENANCES SHALL CONFORM TO THE APPLICABLE STANDARDS OF SPECIFICATION I-124 AND HEREINAFTER.

GENERAL

MAHONING VALLEY SANITARY DISTRICT SPECIAL MANHOLES ARE IN CONJUNCTION WITH RELOCATIONS OF 42" FEEDER MAIN BELONGING TO MAHONING VALLEY SANITARY DISTRICT. THE FOLLOWING SPECIFICATION SUPPLEMENTS APPLY ONLY TO THESE MAHONING VALLEY SANITARY DISTRICT ITEMS.

(1) IRON CASTINGS

ALL IRON CASTINGS SHALL MEET THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS FOR GRAY IRON CASTINGS (A.S.T.M. DESIGNATION: A-48), WHICH REQUIREMENTS, EXCEPT AS MODIFIED HEREIN, ARE HEREBY MADE A PART OF THESE SPECIFICATIONS. THE CASTINGS SHALL BE SMOOTH, CLEAN AND FREE FROM SCALES, LUMPS, BLISTERS AND OTHER DEFECTS AND SHALL BE OUT OF WIND. NO PLUGGING OR FILLING WILL BE ALLOWED.

ALL CASTINGS SHALL BE MADE ACCURATELY TO THE DIMENSIONS SHOWN, AND, WHERE NECESSARY TO SECURE PERFECTLY FLAT AND TRUE SURFACES, THEY SHALL BE PLANED, BUT ALLOWANCES SHALL BE MADE IN THE PATTERNS SO THAT THE SPECIFIED THICKNESS WILL NOT BE REDUCED BY SUCH PLANING.

THE TOP OF EACH CAST IRON MANHOLE COVER SHALL BE CHECKERED. AROUND THE OUTSIDE EDGE, THE TOP OF THE PLATE FOR A WIDTH OF ONE INCH SHALL BE LEFT PLAIN AND FLUSH WITH THE TOP OF THE CHECKERING.

(2) PATTERNS

MANHOLE CASTINGS SHALL BE THOSE MANUFACTURED BY THE FLOCKHART COMPANY OF NEWARK, NEW JERSEY, OR EQUAL. ALL MANHOLE CASTINGS SHALL BE CIRCULAR, WALKWAY, DOUBLE COVER TYPE, WITH SEALED AND LOCKED INNER COVERS.

ALL 24-INCH MANHOLE FRAMES AND COVERS SHALL BE FLOCKHART SLAB-TYPE 601-RA, NO. 62335, FOR INSTALLATION IN THE TOP SLABS OF CHAMBERS, OR PIT-TYPE 601-A, NO. 62331, FOR INSTALLATION ON TOP OF BRICK MASONRY MANHOLE OPENINGS, AS INDICATED ON THE DRAWINGS. THE 30 INCH CASTINGS FOR THE AIR VALVE MANHOLES SHALL BE SLAB-TYPE 601-RA, NO. 62355.

THE DIMENSIONS OF THE SECTIONS OF CASTINGS MUST BE AT LEAST AS GREAT AS THOSE INDICATED, AND ANY MARKED DEVIATION OF THE DESIGN FROM THESE TYPES MUST RECIEVE THE APPROVAL OF THE ENGINEER.

(3) VENT PIPES

ALL 6-INCH FLANGED CAST-IRON VENT PIPING SHALL CONFORM TO THE REQUIREMENTS OF A.W.W.A. SPECIFICATIONS C 102 AND SHALL BE THICKNESS CLASS I, 0.43 INCH SHELL THICKNESS. FLANGES AND FLANGED FITTINGS SHALL CONFORM TO ASA SPECIFICATIONS B16.1. ALL VENT OPENINGS SHALL BE COVERED WITH 3/8-INCH SQUARE MESH, NO. 16 GAUGE WOVEN WIRE SCREENS.

(4) MANHOLE STEPS

MANHOLE STEPS SHALL BE MADE OF GENUINE WROUGHT IRON, BENT HOT, AND SHALL BE HOT-DIP GALVANIZED ACCORDING TO THE REQUIREMENTS OF STANDARD SPECIFICATIONS FOR HOT GALVANIZED COATINGS ON STRUCTURAL STEEL SHAPES, PLATES AND BARS AND THEIR PRODUCTS (A.S.T.M. DESIGNATION: A123).

(5) SHOP PAINTING

THE IRON WORK SHALL BE THOROUGHLY CLEANED IN THE SHOP. PARTS TO BE SET IN THE CONCRETE SHALL NOT BE OILED OR PAINTED, BUT IMMEDIATELY BEFORE BEING EMBEDDED IN THE CONCRETE THEY SHALL BE THOROUGHLY CLEANED AND ALL DIRT, DUST AND ADHERING SUBSTANCES REMOVED. ALL OTHER PARTS NOT GALVANIZED, SHALL BE GIVEN A SHOP COAT OF APPROVED PAINT.

(6) FINISH PAINTING

THE CONTRACTOR SHALL FURNISH ALL MATERIALS FOR AND SHALL DO ALL THE FINISH PAINTING OF ALL EXPOSED MISCELLANEOUS WORK FURNISHED.

ALL EXPOSED MANHOLE FRAMES AND COVERS AND THE CAST PIPE VENTS SHALL BE THOROUGHLY CLEANED OF ALL DUST, DIRT AND OTHER SUBSTANCES. THE SHOP COAT SHALL BE TOUCHED UP AND TWO FINISH COATS OF DU PONT DULUX METAL PROTECTIVE BLACK SHALL BE APPLIED.

NO PAINTING WILL BE REQUIRED FOR GALVANIZED GENUINE WROUGHT IRON WORK.

AIR VALVE INSTALLATIONS IN AIR VALVE MANHOLES

(1) DESCRIPTION:

THE CONTRACTOR SHALL FURNISH AND INSTALL ALL OF THE AIR VALVE INSTALLATIONS AS INDICATED ON THE CONTRACT DRAWINGS.

THESE INSTALLATIONS SHALL BE COMPLETE, INCLUDING THE AIR VALVE, GATE VALVE, FLANGED PIPE SADDLE AND ALL ACCESSORY PIPING AND APPURTENANCES AS SHOWN OR AS REQUIRED TO MAKE A PROPER FUNCTIONING AIR VALVE OF THE TYPE REQUIRED.

TWO ALTERNATE TYPES OF AIR VALVES MAY BE REQUIRED, DEPENDING ON THE TYPE OF PIPE USED IN THE PIPE LINE. IF REINFORCED-CONCRETE PIPE IS USED, A SIMPLE AIR-RELEASE TYPE AIR VALVE WILL BE REQUIRED; BUT, IF STEEL PIPE IS USED, A COMBINATION OF AIR-INLET AND AIR-RELEASE VALVES WILL BE REQUIRED IN EACH AIR VALVE INSTALLATION.

THE CONTRACTOR SHALL FURNISH AND INSTALL THE COMBINATION OF AIR-RELEASE AND AIR-INLET VALVES NECESSARY IF STEEL PIPE IS USED IN THE PIPE LINE.

THE CONTRACTOR SHALL FURNISH AND INSTALL THE SIMPLE AIR-RELEASE VALVE NECESSARY IF REINFORCED CONCRETE PIPE IS USED IN THE PIPE LINE.

ALL AIR VALVES SHALL BE DESIGNED FOR A WATER WORKING PRESSURE OF 150 PSI (300 PSI TEST).

ALL MATERIALS SHALL BE OF THE BEST OBTAINABLE FOR THE PURPOSE, AND THE WORKMANSHIP SHALL CONFORM TO THE BEST MODERN METHODS AND LATEST APPROVED STANDARDS.

(2) COMBINATION OF AIR-INLET AND AIR-RELEASE VALVES FOR STEEL PIPE:

IF STEEL PIPE IS USED IN THE PIPE LINE, THE CONTRACTOR SHALL FURNISH AND INSTALL, FOR EACH AIR VALVE INSTALLATION, A COMBINATION OF A SIMPLEX TYPE VAC 6-INCH AIR AND VACUUM VALVE WITH A SIMPLEX TYPE AGFD STANDARD AIR-RELEASE VALVE, AS MANUFACTURED BY THE SIMPLEX VALVE AND METER COMPANY, OR APPROVED EQUAL.

THE COMBINED AIR-INLET AIR-RELEASE VALVES SHALL BE DESIGNED AND CONSTRUCTED TO PERMIT THE ESCAPE OF AIR AUTOMATICALLY FROM THE PIPE LINE WHILE IT IS BEING FILLED, AUTOMATICALLY TO PERMIT AIR TO ENTER THE PIPE LINE WHILE IT IS BEING EMPTIED, AND AUTOMATICALLY TO PERMIT THE ESCAPE OF AIR THAT ACCUMULATES UNDER PRESSURE IN THE PIPE LINE AT THE HIGH POINTS.

THE VALVE BODIES AND COVERS SHALL BE MADE OF CAST IRON CONFORMING TO THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS FOR GRAY IRON CASTINGS(A.S.T.M. DESIGNATION: A48) CLASS 25. THE OPERATING MECHANISMS SHALL BE BRONZE OR OTHER SUITABLE NON-CORRODIBLE MATERIAL AND SHALL BE ATTACHED TO AND REMOVABLE AS A UNIT WITH THE COVERS. THE VALVES SHALL BE CONTROLLED BY NON-COLLAPSIBLE, BUOYANT METAL FLOATS, THE TOPS OF WHICH SHALL FORM THE VALVES AND SHALL CLOSE AGAINST BRONZE VALVE SEATS.

THE VALVES SHALL BE SIMPLE AND RUGGED IN CONSTRUCTION AND THE WORKING PARTS SHALL BE ARRANGED TO PERMIT A FULL CLEAR PASSAGE FOR AIR. THE VALVES MUST POSITIVELY CLOSE UNDER LOW OR HIGH WATER PRESSURE AND MUST NOT BLOW SHUT WHILE DISCHARGING AIR REGARDLESS OF VELOCITY. THERE SHALL BE A BLOW-OFF CONNECTION IN THE COVER AND A DRAIN PLUG PROVIDED NEAR THE BOTTOM OF EACH VALVE.

THE AIR-VALVE SHALL BE ADJUSTABLE BY MEANS OF A LEVER AND COUNTER-WEIGHT SYSTEM AND SHALL BE SET SO THAT, AFTER THE PIPE LINE IS PLACED IN OPERATION, THE VALVE WILL BE ACTIVATED PERMITTING THE INGRESS OF AIR WHEN THE PRESSURE IN THE PIPE LINE DROPS SUFFICIENTLY TO CREATE A DIFFERENTIAL PRESSURE ACROSS THE VALVE OF 0.10 PSI.

(3) AIR RELEASE VALVE FOR REINFORCED CONCRETE PIPE:

IF REINFORCED CONCRETE PIPE IS USED IN THE PIPE LINE, THE CONTRACTOR SHALL FURNISH AND INSTALL, FOR EACH AIR VALVE INSTALLATION, A SIMPLEX TYPE AV AUTOMATIC AIR RELEASE VALVE, AS MANUFACTURED BY THE SIMPLEX VALVE AND METER COMPANY, OR APPROVED EQUAL.

THE AIR-RELEASE VALVES SHALL BE DESIGNED AND CONSTRUCTED TO AUTOMATICALLY PERMIT THE ESCAPE OF AIR THAT ACCUMULATES IN THE HIGH POINTS OF THE PIPE LINE. THE VALVE BODY AND COVER SHALL BE MADE OF CAST IRON (A.S.T.M.-A48, CLASS 25). THE OPERATING MECHANISM SHALL BE BRONZE OR OTHER SUITABLE NON-CORRODIBLE MATERIAL, AND SHALL BE ATTACHED TO AND REMOVABLE WITH THE COVER. THE FLOAT SHALL BE SEAMLESS COPPER AND SUFFICIENTLY STRONG TO WITHSTAND AN EXTERNAL TEST PRESSURE OF 600 PSI WITHOUT COLLAPSING. THERE SHALL BE A BLOWOFF CONNECTION IN THE COVER.

(4) SHUTOFF GATE VALVES

AHEAD OF EACH AIR VALVE THERE SHALL BE INSTALLED A GATE VALVE, AS SHOWN ON THE DRAWINGS, THE FULL SIZE OF THE PIPE CONNECTION. THESE SHUTOFF VALVES SHALL BE STANDARD IRON BODY BRONZE MOUNTED GATE VALVES CONFORMING TO THE A.W.W.A. STANDARD SPECIFICATIONS FOR GATE VALVES FOR ORDINARY WATER SERVICE (A.W.W.A. -C500).

(5) INSTALLATION

THE AIR VALVES SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER WITH ALL AUXILIARY AND CONNECTING PIPING IN A NEAT ASSEMBLY. THREADED JOINTS SHALL BE MADE UP WITH SUITABLE JOINT COMPOUND AND SHALL BE DROP-TIGHT. FLANGED JOINTS SHALL BE AMERICAN 125 POUND STANDARD WITH FULL GASKETS OF APPROVED MATERIAL AND STANDARD SIZED WROUGHT-IRON BOLTS WITH SQUARE HEADS AND SEMI-FINISHED HEXAGON NUTS.

ON TEST, ALL JOINTS SHALL BE INSPECTED AND MADE TIGHT AGAINST LEAKAGE.

(6) PAINTING

AFTER EACH INSTALLATION HAS BEEN COMPLETED AND TESTED, ALL EXPOSED IRON AND STEEL SURFACES OF THE VALVES AND PIPING INSIDE THE AIR VALVE MANHOLE SHALL BE CLEANED, PRIMED WITH BITUMASTIC PRIMER, AND GIVEN ONE COAT OF BITUMASTIC ENAMEL APPLIED HOT, AND OF SUFFICIENT THICKNESS TO PROVIDE COMPLETE PROTECTION.

ACCESS MANHOLE INSTALLATIONS IN ACCESS MANHOLES

(1) DESCRIPTION

THE CONTRACTOR SHALL FURNISH AND INSTALL THE ACCESS MANHOLE INSTALLATIONS IN THE PIPE LONE AT THE POINTS SHOWN ON THE CONTRACT DRAWINGS. EACH ACCESS MANHOLE INSTALLATION SHALL INCLUDE THE PRESSURE MANHOLE AND RING CONNECTION PIECE TO THE PIPE AS DETAILED TO SUIT THE TYPE OF PIPE IN WHICH INSTALLED AND THE ACCESSORIES AND APPURTENANCES INVOLVED IN THE PRESENCE OF AN ACCESS MANHOLE IN THE PIPE LINE.

(2) FABRICATION DETAILS:

EACH ACCESS MANHOLE SHALL HAVE A CLEAR ELLIPTICAL OPENING 14 INCHES BY 16 INCHES IN SIZE. THE RING CONNECTION PIECE AND CLAMPS SHALL BE CAST STEEL MEETING THE REQUIREMENTS OF TENTATIVE SPECIFICATIONS FOR MEDIUM-STRENGTH STEEL CASTINGS (A.S.T.M. DESIGNATION: A27). THE COVER SHALL BE CAST IRON CONFORMING TO THE STANDARD SPECIFICATIONS FOR GRAY IRON CASTINGS (A.S.T.M. DESIGNATION: A48).

THE VARIOUS SECTIONS OF THE ACCESS MANHOLE CASTINGS SHALL BE OF SUFFICIENT THICKNESS AND SHALL BE ADEQUATELY STIFFENED BY RIBBING, SO AS TO WITHSTAND THE HYDROSTATIC TEST PRESSURES TO WHICH THE PIPE LINE WILL BE SUBJECTED, WITHOUT CRACKING OR WARPING. A GASKET OF NEOPRENE RUBBER, OR OTHER APPROVED MATERIAL, SHALL BE INSERTED BETWEEN THE FACES OF THE COVER AND SADDLE PIECE SO THAT THE ACCESS MANHOLE IS DROP-TIGHT UNDER TEST.

IN GENERAL, THE FABRICATION OF THE ACCESS MANHOLE SHALL SUIT THE MATERIAL AND TYPE OF CONSTRUCTION OF THE PIPE IN WHICH IT IS TO BE INSTALLED. WHETHER STEEL PIPE OR REINFORCED CONCRETE CYLINDER PIPE IS USED IN THE PIPE LINE, THE CONNECTION PIECE OF THE ACCESS MANHOLE SHALL BE WELDED TO THE STEEL SHELL IN A CONTINOUS WATERTIGHT JOINT.

THE MAIN PIPE SHELL SHALL BE REINFORCED TO COMPENSATE FOR THE METAL REMOVED IN MAKING THE MANHOLE OPENING, AND THE PIPE SECTION WITH THE MANHOLE OPENING SHALL HAVE A BURSTING STRENGTH AND A STIFFNESS AGAINST EXTERNAL LOAD AT LEAST EQUAL TO A TYPICAL PIPE SECTION WITHOUT AN OPENING.

(3) INSTALLATION:

THE ACCESS MANHOLES SHALL BE FABRICATED AND INSTALLED IN THE SHOP BEFORE SHIPMENT OF THE SECTION IN WHICH INSTALLED.

EACH SECTION OF PIPE IN WHICH AN ACCESS MANHOLE IS LOCATED SHALL BE INSTALLED SO THAT THE ACCESS MANHOLE IS EXACTLY ON THE TOP OF THE CENTERLINE OF THE PIPE. IT WILL BE ENCLOSED BY A SMALL CONCRETE CHAMBER WITH CAST IRON MANHOLE FRAME AND COVER, AND PROVISIONS SHALL BE MADE TO PERMIT CONSTRUCTION OF THIS CHAMBER AT EACH ACCESS MANHOLE INSTALLATION.

(4) PAINTING:

ALL EXPOSED METAL PARTS OF THE ACCESS MANHOLES BOTH INSIDE AND OUTSIDE SHALL BE GIVEN TWO COATS OF APPROVED COAL-TAR ENAMEL IN THE SHOP BEFORE SHIPMENT AND TWO ADDITIONAL FINISH COATS IN THE FIELD AFTER INSTALLATION. THIS COATING SHALL BE EQUAL TO INERTOL 66 OR KOPPERS' BITUMASTIC 50.

HOSE VALVE

(1) DESCRIPTION: THE HOSE VALVE SHALL BE A 3/4 INCH BRASS ANGLE HOSE VALVE SIMILAR TO CRANE NO. 117 OR EQUAL. THE VALVE SHALL BE SUITABLE FOR OPERATION AT WATER WORKING PRESSURE OF NOT LESS THAN 250 PSI. THE VALVE SHALL BE OF THE RISING STEM TYPE, AND THE OUTLET SHALL HAVE HOSE THREADS OF TYPE AND SIZE TO BE DESIGNATED BY THE ENGINEER. A BRASS CAP AND CHAIN SHALL BE FURNISHED TO PROTECT THE OUTLET WHEN NOT IN USE.

(2) INSTALLATION:

THE HOSE VALVE CONNECTION SHALL BE INSTALLED IN THE MANHOLES AT THE LOCATIONS SHOWN. THE VALVE SHALL BE SET VERTICALLY, PLUMB AND TRUE AT THE TOP CENTER OF THE PIPE. THE COMPLETED INSTALLATION SHALL BE TESTED FOR LEAKS AT THE SAME HYDROSTATIC PRESSURE AS THE SECTION OF PIPE IN WHICH IT IS LOCATED, AND ANY LEAKS OR DEFECTS WHICH MAY BE FOUND UPON TEST SHALL BE REMEDIED IN A SATISFACTORY MANNER. THE COST OF THE HOSE VALVE SHALL BE INCLUDED IN THE BID PRICE FOR THE SPECIAL MANHOLE IN WHICH IT IS INSTALLED.

SPECIAL BLOWOFF MANHOLES

(1) BLOW-OFF MANHOLES SHALL BE CONSTRUCTED TO THE DETAIL SHOWN ON THE PLANS AND SHALL INCLUDE THE INLET AND OUTLET PIPING CONNECTION.

SPECIAL BLOWOFF SETTING

(1) DESCRIPTION:

THE CONTRACTOR SHALL FURNISH AND INSTALL THE BLOWOFF INSTALLATIONS IN THE PIPE LINE AT THE LOW POINT AS SHOWN ON THE DRAWINGS. EACH BLOW OFF INSTALLATION SHALL INCLUDE THE BLOWOFF FITTINGS, GATE VALVE AND PIPING TO END OF CONCRETE SUPPORT.

THE CONCRETE CRADLES OR SUPPORTS AT THE BLOWOFF INSTALLATIONS SHALL BE FURNISHED AS A PART OF THE INSTALLATION.

(2) BLOWOFF VALVES:

THE BLOWOFF VALVES SHALL BE STANDARD IRON-BODY, BRONZE-MOUNTED GATE VALVES OF THE SIZE SHOWN AND OF DOUBLE-DISC, NON-RISING STEM TYTE, SUITABLE FOR WATER WORKING PRESSURE OF 150 PSI (300 PSI TEST). THESE VALVES SHALL CONFORM TO THE STANDARD SPECIFICATIONS OF THE AMERICAN WATER WORKS ASSOCIATION FOR GATE VALVES FOR ORDINARY WATER SERVICE (A.W.W.A. C500). EACH VALVE SHALL BE SUPPLIED WITH AN ADJUSTIBLE CAST IRON KEY BOX WITH LOCKED COVER EXTENDING TO THE FINISHED GROUND SURFACE. THREE (3) OPERATING KEYS OF SUITABLE LENGTH SHALL BE FURNISHED.

CAST-IRON PIPE AND FITTINGS

(1) ALL BELL AND SPIGOT STRAIGHT CAST IRON PIPE SHALL BE CENTRIFUGALLY CAST IN CONFORMITY WITH THE AMERICAN STANDARD SPECIFICATIONS FOR CAST IRON PIPE CENTRIFUGALLY CAST (A.W.W.A. C106 OR A.W.W.A. C108). ALL 8 INCH BELL AND SPIGOT PIPE SHALL BE THICKNESS CLASS 25, 0.52 INCH SHELL THICKNESS.

ALL FLANGED STRAIGHT CAST IRON PIPE SHALL BE MANUFACTURED IN CONFORMITY WITH THE STANDARD SPECIFICATIONS FOR CAST IRON PIT CAST PIPE FOR WATER OF THE AMERICAN WATER WORKS ASSOCIATION (A.W.W.A. C102) INSOFAR AS THEY APPLY. ALL 8 INCH FLANGED PIPE SHALL BE THICKNESS CLASS 4, 0.58 INCH SHELL THICKNESS.

ALL CAST IRON BELL AND SPIGOT FITTINGS SHALL BE MANUFACTURED IN ACCORDANCE WITH THE TENTATIVE STANDARD SPECIFICATIONS FOR CAST IRON PRESSURE FITTINGS OF THE AMERICAN WATER WORKS ASSOCIATION (A.W.W.A. C100-54T) INSOFAR AS THEY APPLY.

FED.RD	STATE	PROJECT	
2	OHIO		

13
492

MAH-18-17.20

GENERAL NOTES

I-8 MANHOLE SPECIALS

CAST IRON PIPE AND FITTINGS CONT'D.

ALL CAST IRON FLANGES AND FLANGED FITTINGS SHALL BE MANUFACTURED IN ACCORDANCE WITH ASA SPECIFICATIONS B 16.1 -1948. ALL FLANGES SHALL BE FACED AND DRILLED AND SPOT FACED ON THE BACK TO UNIFORM THICKNESS AROUND THE BOLT HOLES.

ALL CAST IRON PIPE AND FITTINGS SHALL HAVE STANDARD TAR DIP COATING ON EXTERIOR AND INTERIOR SURFACES.

(7) BOLTS AND GASKETS:

THE CONTRACTOR SHALL FURNISH ALL BOLTS AND GASKETS NECESSARY FOR THE MAKING UP OF FLANGED JOINTS. ALL BOLT SHALL BE OF BEST QUALITY HOT GALVANIZED LOW CARBON STEEL OR TONCAN METAL, DUCTILE, TOUGH, FIBROUS AND UNIFORM IN CHARACTER. THE MATERIALS SHALL HAVE AN ULTIMATE TENSIL STRENGTH OF NOT LESS THAN 45,000 POUNDS PER SQUARE INCH, AND ELASTIC LIMIT OF NOT LESS THAN 25,000 POUNDS PER SQUARE INCH, AND AN ELONGATION OF AT LEAST 20% IN 8 INCHES. GASKETS SHALL BE GARLOCK RED RUBBER NO. 22, 1/8 INCH THICK, OR EQUAL; THEY SHALL BE CUT TO FIT FULL FACE THE JOINTS FOR WHICH THEY ARE INTENDED. BOLTS SHALL HAVE U.S. STANDARD THREADS AND HEXAGONAL NUTS.

(3) LAYING:

PROPER AND SUITABLE TOOLS AND APPLIANCES FOR THE SAFE AND CONVENIENT HANDLING AND LAYING OF THE PIPES AND FITTINGS SHALL BE USED, GREAT CARE SHALL BE TAKEN TO PREVENT THE PIPE COATING FROM BEING DAMAGED PARTICULARLY ON THE INSIDE OF THE PIPES AND FITTINGS, AND ANY SUCH DAMAGE SHALL BE REMEDIED AS DIRECTED. ALL PIPES AND FITTINGS SHALL BE CAREFULLY EXAMINED BY THE CONTRACTOR FOR DEFECTS JUST BEFORE LAYING AND NO PIPE OR FITTING SHALL BE LAID WHICH IS KNOWN TO BE DEFECTIVE.

IF ANY DEFECTIVE PIPE IS DISCOVERED AFTER HAVING BEEN LAID, IT SHALL BE REMOVED AND REPLACED WITH A SOUND PIPE OR FITTING IN A SATISFACTORY MANNER, BY THE CONTRACTOR AT HIS OWN EXPENSE. ALL PIPES AND FITTINGS SHALL BE THOROUGHLY CLEANED BEFORE THEY ARE LAID AND SHALL BE KEPT CLEAN UNTIL THEY ARE USED IN THE COMPLETED WORK. WHEN LAID, THE PIPE SHALL CONFORM TO THE LINES AND GRADES GIVEN BY THE ENGINEER. OPEN ENDS OF PIPE SHALL BE KEPT PLUGGED WITH A BULKHEAD DURING CONSTRUCTION. PIPE LAID IN TRENCH SHALL BE LAID TO A FIRM AND EVEN BEARING FOR ITS FULL LENGTH.

(4) PIPE JOINT:

JOINTS FOR BELL AND SPIGOT PIPE SHALL BE POURED WITH LEAD AND THOROUGHLY CAULKED. THE SPIGOT OF EACH PIPE SHALL BE PROPERLY SEATED IN THE BELL OF ITS COMPANION PIECE AND SHALL BE ADJUSTED FOR LINE AND GRADE AND FOR CONTINUITY OF INTERIOR SURFACE. THE JOINT SHALL BE CAULKED FIRMLY WITH APPROVED PREFABRICATED MATERIAL TO SUCH A DEPTH AS WILL AFFORD A POURED JOINT TWO AND ONE-HALF INCHES DEEP.

LEAD FOR JOINTING SHALL BE PURE PIG LEAD. THE MELTING POT SHALL BE KEPT NEAR TO THE JOINT TO BE POURED AND SHALL BE KEPT CLEAR OF DROSS. EACH JOINT SHALL BE MADE IN ONE POUR AND THOROUGHLY CAULKED BY SKILLED WORKMEN SO AS TO BE TIGHT WITHOUT OVERSTRESSING THE BELL OF THE PIPE.

FLANGED JOINTS SHALL BE MADE UP IN ACCORDANCE WITH STANDARD PRACTICE AND THE MANUFACTURER'S INSTRUCTIONS.

(5) TESTING:

AFTER THE PIPING HAS BEEN PLACED, AND BEFORE THE TRENCHES ARE BACKFILLED, THE PIPES SHALL BE TESTED BY THE CONTRACTOR IN THE PRESENCE OF THE ENGINEER AND TESTS SHALL BE CONTINUED UNTIL ALL LEAKS HAVE BEEN MADE TIGHT TO THE SATISFACTION OF THE ENGINEER. THE CONTRACROR SHALL FURNISH ALL NECESSARY PUMPS, GAGES, BULKHEADS AND OTHER MATERIAL, PIPES, OR APPLIANCES NECESSARY TO CONDUCT THE TESTS AS HEREINAFTER DESCRIBED:

THE 8-INCH FLANGED PIPING UP TO THE GATE VALVE SHALL BE TESTED TO THE SAME HYDROSTATEC PRESSURE AS THAT SPECIFIED FOR THE SECTION OF THE PIPE LINE IN WHICH THE PARTICULAR BLOWOFF CONNECTION IS LOCATED.

THE 8-INCH BELL AND SPIGOT CONNECTION FROM THE GATE VALVE TO THE BLOWOFF MANHOLE WILL NOT BE SUBJECT TO A HYDROSTATIC TEST BUT ALL JOINTS WILL BE CAREFULLY INSPECTED BEFORE BEING APPROVED.

THE FOLLOWING SUPPLEMENTAL SPECIFICATIONS PERTAIN ONLY TO CITY OF YOUNGSTOWN SEWER DEPARTMENT WORK.

SPECIAL SEWAGE REGULATOR CHAMBER AND REGULATOR EQUIPMENT INSTALLATION

(1) WORK INCLUDED:

THE CONTRACTOR SHALL FURNISH AND INSTALL THE SEWAGE REGULATOR , INCLUDING ALL BRACKETS, I-BEAMS, ANCHOR BOLTS AND OTHER APPURTENANT ACCESSORIES INCIDENTAL TO A COMPLETE INSTALLATION, AS CALLED FOR ON THE DRAWINGS AND AS SPECIFIED HEREIN. IT SHALL ALSO INCLUDE EXCAVATION AND BACKFILL, CONCRETE, STEEL REINFORCEMENT, MANHOLE FRAMES AND COVERS AND STEPS.

(2) QUALIFICATIONS OF MANUFACTURER:

REGULATOR EQUIPMENT TO BE FURNISHED SHALL BE MANUFACTURED BY A COMPANY HAVING MANUFACTURED REGULATOR EQUIPMENT OF COMPARABLE SIZE FOR THE CONDITIONS REQUIRED HEREIN, FOR A PERIOD OF FIVE YEARS

(3) TYPE AND SIZE:

REGULATOR EQUIPMENT SHALL BE SMMILAR OR AT LEAST EQUAL TO THAT MANUFACTURED BY BROWN & BROWN, INC., LIMA, OHIO. THE TYPE REGULATOR AND THE SIZE OF REGULATING GATES, FLOATS, AND APPURTENANCES SHALL BE SUITABLE FOR INSTALLATION AND OPERATION UNDER THE CONDITIONS SHOWN ON THE PLANS AND SHALL BE CONSTRUCTED TO FACILITATE EASY ADJUSTMENT FOR CHANGING FLOWS.

(4) MATERIALS AND WORKMANSHIP:

SPECIFICATIONS FOR STRUCTURAL STEEL AND MISCELLANEOUS STEEL, WROUGHT IRON AND NON-FERROUS METAL WORK, SHALL INSOFAR AS THEY APPLY BE CONSIDERED AND ARE HEREBY MADE A PART OF THE SPECIFICATION FOR REGULATOR EQUIPMENT.

CAST IRON SHALL BE TESTED UNDER AND SHALL CONFORM TO THE REQUIREMENTS OF A.S.T.M. DESIGNATION A48, FOR GRAY IRON CASTINGS. REGULATOR GATE WALL CASTINGS, GATE BODIES, SHUTTERS, FLOATS, TRANSMISSION WHEELS, WALL BRACKETS, RADIAL HINGE ARMS, AND FLOAT TRAVEL LIMIT COLLARS SHALL BE CLASS 40. OUTBOARD SUPPORTS, PILLOW BLOCK CASES , CAPS AND ROLLER CAGES AND SECTIONAL COUNTER-WEIGHTS SHALL BE CLASS 20.

WROUGHT IRON FOR THE TRANSMISSION SHAFTS, ANCHOR BOLTS, TRANSMISSION ASSEMBLY BOLTS AND FLOAT GUIDES SHALL BE TESTED UNDER AND SHALL CONFORM TO THE REQUIREMENTS OF A.S.T.M. DESIGNATION A189 -GRADE B.

COIL CHAINS SHALL BE OF SILICON BRONZE METAL.

WIRE ROPE SHALL BE 7 X 7 X 7 STAINLESS STEEL.

STEEL I-BEAMS AND STEEL PLATES SHALL BE NEW STOCK OF THE SIZE AND LENGTHS AS SPECIFIED, SHOWN ON THE DRAWINGS OR AS DIRECTED AND SHALL IN ALL RESPECTS CONFORM TO THE STANDARD SPECIFICATIONS FOR STRUCTURAL STEEL AND BUILDINGS, A.S.T.M. DESIGNATION A7.

ALL ANCHOR BOLTS AND TRANSMISSION ASSEMBLY BOLTS SHALL BE GALVANIZED.

ALL GALVANIZING WORK SHALL CONFORM TO THE REQUIREMENTS OF A.S.T.M. DESIGNATION A153, FOR ZINC COATING (HOT DIP) FOR IRON AND STEEL HARDWARE.

BRASS CASTINGS FOR RADIAL HINGE ARM NUTS, ADJUSTING BUCKLES AND WEATHER PROOFING GLANDS FOR PILLOW BLOCKS SHALL BE TESTED UNDER AND SHALL CONFORM TO THE REQUIREMENTS OF A.S.T.M. DESIGNATION B30, FOR COPPER-BASE ALLOYS IN INGOT FORM FOR SAND CASTINGS, COMPOSITION NO. 4.

ALL STUDS, NUTS, SCREWS, FACES FOR REGULATOR GATE NOZZLE AND SHUTTER, TRANSMISSION ROPE CONNECTING BOLTS, ADJUSTING BUCKLE PARTS, AND ALL BOLTS NOT OTHERWISE SPECIFIED SHALL BE S.A.E. 73 TOBIN BRONZE. ALL BOLTS SHALL HAVE FORGED HEXAGON HEADS AND ALL NUTS SHALL BE HEXAGONAL.

THE REGULATING GATE AND WALL CASTING SHALL BE ASSEMBLED INTEGRALLY. THE WALL CASTING SHALL BE FLANGED TO SUIT THE COMPANION FLANGE ON THE REGULATOR GATE BODY. THE INTAKE OF THE WALL CASTING TUBE SHALL BE BELLED TO APPROXIMATE THE "VENA CONTRACTA" OF THE INFLOWING STREAM. THE LENGTH OF THE WALL CASTING SHALL BE EQUAL TO THE WALL THICKNESS. FLANGES SHALL BE ACCURATELY FACED, TAPPED AND STUDDED TO SUIT REGULATOR GATE FLANGES. THICKNESS OF METAL SHALL BE THE SAME AS FLANGED CAST IRON PIPE FOR COMPARABLE SIZES.

THE REGULATOR GATE SHALL BE OF THE ARC OR SECTOR TYPE, AND SHALL INCLUDE A TUBE SECTION OF SIZE AS CALLED FOR ON THE PLANS WITH FLANGED ENDS, AN ARC OR SECTOR SHAPED SHUTTER SECTION WHICH SHALL SWING CONCENTRICALLY ALONG THE TUBE SECTION FLANGE BY MEANS OF RADIAL HINGE ARMS ATTACHED TO THE GATE TUBE. THE BACK FLANGE SHALL BE ACCURATELY MACHINED AND FITTED TO THE COMPANION FLANGE ON THE WALL CASTING WITH A SUITABLE GASKET BETWEEN. THE FLANGE AND THE HINGE ARM BEARINGS OR TRUNNIONS SHALL BE CAREFULLY AND ACCURATELY MACHINED CONCENTRICALLY.

THE GATE SHUTTER SHALL BE A WELL-RIBBED CASTING, ACCURATELY MACHINED TO INSURE CLOSE FITTING, WELL BALANCED AND SO CONSTRUCTED THAT THE TENSION IN THE TRANSMISSION CONNECTION SHALL BE CONSTANT REGARDLESS OF THE POSITION OF THE SHUTTER WITHIN ITS WORKING RANGE.

THE COMPANION FACES ON GATE TUBE AND SHUTTER SHALL BE FACED WITH BRONZE BARS NOT LESS THAN 1/4" THICK AND 2-1/2" WIDE. THE BARS SHALL BE EXTRUDED OR CAREFULLY FORMED TO FIT THE SURFACES TO WHICH THEY ARE ATTACHED. THEY SHALL BE ATTACHED WITH BRONZE SCREWS NOT LESS THAN 3/8" IN DIAMETER AND 1" LONG WITH COUNTERSUNK HEADS OF SUCH DESIGN THAT THE HEADS MAY BE MACHINED AFTER SCREWS ARE INSERTED AND SUBSTANTIAL HEADS REMAIN. PLASTIC GASKET MATERIAL SHALL BE APPLIED BETWEEN THE BRONZE FACES AND FINISHED SURFACES TO WHICH THEY ARE ATTACHED TO PRECLUDE THE POSSIBILITY OF WATER ENTERING TO CAUSE CXIDATION. PLASTIC GASKET MATERIAL SHALL BE SUCH THAT IT WILL PERMANENTLY HARDEN WITHOUT CONTRACTION WITHIN 12 TO 24 HOURS AFTER APPLICATION. AFTER BRONZE FACES HAVE BEEN APPLIED AND THE GASKET MATERIAL HAS PERMANENTLY SET THE COMPANION FACES SHALL BE RE MACHINED, GROUND AND LAPPED SO THAT WHEN THE GATE IS CLOSED IT SHALL BE WATERTIGHT.

RADIAL HINGE ARMS SHALL BE DESIGNED TO PERMIT MICROMETER ADJUSTMENTS OF THE CLEARANCE BETWEEN THE COMPANION FACES.

SUITABLE OUTBOARD SUPPORTING MEANS SHALL BE PROVIDED FOR THE REGULATOR GATE IN ORDER TO RELIEVE THE CHAMBER WALL OF ANY STRAIN DUE TO OVERHANG. THE REGULATOR GATE SHALL BE PROVIDED WITH STOPS TO LIMIT THE DOWNWARD TRAVEL OF THE SHUTTER.

THE FLOAT SHALL BE A HOLLOW CAST IRON CASTING OR FABRICATED OF GALVANIZED WELDED STRUCTURAL STEEL PLATES OF SUCH DIMENSIONS THAT A CHANGE OF NOT MORE THAN 1/2" IN SUBMERGENCE WILL REVERSE THE DIRECTION OF GATE SHUTTER TRAVEL. A SMALL CIRCULAR OPENING SHALL BE CAST IN TOP OF THE HEAD AND COVERED WITH A SUITABLE COVERPLATE AND SUITABLE GASKET INSERTED BETWEEN HEAD AND PLATE. FLOAT SHALL HAVE LUGS CAST OR WELDED ON OPPOSITE SIDES OF SHELL TO PROPERLY ENGAGE THE FLOAT GUIDES. FLOATS SHALL BE CAST IN ONE PIECE AND SHALL BE TESTED HYDROSTATICALLY AND PROVEN WATERTIGHT UNDER 30 PSI PRESSURE.

FLOAT GUIDES SHALL BE WROUGHT IRON TUBES OF APPROXIMATELY 3-INCH OUTSIDE DIAMETER WITH A WALL THICKNESS OF NOT LESS THAN 1/4 INCH. GUIDES SHALL BE GROUTED INTO INSERTS SET FLUSH WITH THE BOTTOM OF THE FLOAT COMPARTMENT AND SHALL BE EXACTLY PARALLEL AND VERTICAL.

ADJUSTIBLE CAST IRON GUIDE COLLARS SHALL BE ATTACHED TO THE FLOAT GUIDES TO LIMIT THE UPWARD AND DOWNWARD TRAVEL OF THE FLOAT.

THE TRANSMISSION UNIT SHALL CONSIST OF AN OVERHEAD SHAFT EXTENDING ABOVE THE GATE AND FLOAT WITH GROOVED WHEELS. TO THESE WHEELS COIL CHAINS SHALL BE ATTACHED FOR CONNECTION TO THE REGULATOR GATE SHUTTER AND THE FLOAT.

THE TRANSMISSION SHAFT SHALL BE MACHINE FINISHED AND SHALL REST IN TWO UNIVERSAL TYPE WEATHER-PROOF ROLLER BEARING PILLOW BLOCKS SUPPORTED BY GALVANIZED STEEL I-BEAMS RESTING ON CAST IRON BRACKETS MOUNTED UPON THE CHAMBER WALLS WITH ANCHOR BOLTS CAST IN THE CONCRETE. THE TRANSMISSION WHEELS SHALL BE CAST IRON AND ACCURATELY BORED, FACED AND KEYED TO SHAFT. THE PERIPHERAL GROOVES SHALL BE MACHINE FINISHED.

THE TRANSMISSION CHAINS SHALL BE EQUIPPED WITH AN ADJUSTABLE BUCKLE IN EACH CHAIN TO PERMIT ADJUSTMENTS IN LENGTH. SECTIONAL CAST COUNTERWEIGHTS SUPPORTED BY A CARRIER SHALL BE INSERTED IN THE PROPER TRANSMISSION CHAIN TO ACCURATELY BALANCE THE GATE SHUTTER AND FLOAT.

GATE SHUTTER, FLOAT AND TRANSMISSION SHALL BE IN PERFECT BALANCE SO THAT THE GATE SHUTTER TRAVEL WILL CONTINUE IN FIXED PROPORTION TO THE RISE OR FALL OF WATER IN THE FLOAT COMPARTMENT AFTER SHUTTER TRAVEL HAS BEGUN.

AMERICAN BUREAU OF STANDARDS CLASS 2 FITS SHALL AFPLY TO ALL SCREWS.

LUBRICATION OF THE TRANSMISSION SHAFT AND GATE TRUNNIONS SHALL BE PROVIDED FOR BY MEANS OF BRONZE ALEMITE GREASE FITTINGS. ONE APPROVED GREASE COMPRESSOR SHALL BE FURNISHED.

(5) GENERAL DESCRIPTION

EACH SEWAGE REGULATOR SHALL CONSIST OF A REGULATOR GATE AND FLOAT ASSEMBLY INTER-CONNECTED BY A TRANSMISSION UNIT. THE FLOAT TRAVEL SHALL BE ACTUATED THROUGH CHANGING LEVELS IN THE FLOAT CHAMBER EFFECTED BY FLOW THROUGH FLOW DEPTH IN THE INTERCEPTING SEWER AND DEPTH OF FLOW IN THE COMBINED SEWERS.

(6) INSTALLATION:

PRIOR TO THE MANUFACTURE OF ANY EQUIPMENT THE DIMENSIONS OF THE STRUCTURE SHALL BE CAREFULLY VERIFIED BY THE CONTRACTOR IN THE FIELD, SO AS TO INSURE THE FITTING OF THE EQUIPMENT AS FURNISHED. THIS VERIFICATION SHALL TAKE PLACE EVEN THOUGH CERTAIN DIMENSIONS HAVE BEEN INDICATED ON THE CONTRACT DRAWINGS.

ELEVATIONS SHOWN ON THE PLANS FOR THE INVERTS OF THE EXISTING OUTFALL SEWERS AT THE REGULATOR CHAMBERS HAVE BEEN CALCULATED FROM CITY RECORDS AND FROM FIELD SURVEYS AND IN MOST CASES HAVE BEEN FIELD CHECKED. HOWEVER, IN SOME CASES IT MAY BE NECESSARY AS THE WORK PROGRESSES TO MODIFY SLIGHTLY THE ELEVATION OF SOME OF THESE STRUCTURES. IN THAT EVENT, THE DRAWINGS WILL BE REVISED AND THE RELATIVE DIFFERENCE IN ELEVATION BETWEEN THE PARTS OF THE REGULATORS AND STRUCTURES THAT CONTROL OR AFFECT THE FLOW OF SEWAGE SHALL BE MAINTAINED IN THEIR SAME RELATIVE POSITIONS TO EACH OTHER.

THE CONTRACTOR SHALL UNCOVER OR EXPOSE ALL EXISTING OUTFALL SEWERS WHERE THEY CROSS THE INTERCEPTING SEWER WELL IN ADVANCE OF PIPE LAYING OR OTHER TYPES OF SEWER CONSTRUCTION, AS DIRECTED BY THE ENGINEER, SO THAT THE ENGINEER MAY CHECK THE LOCATION AND ELEVATION OF THE OUTFALL SEWERS AND MAKE ANY NECESSARY REVISIONS IN THE DETAILS OF THE DRAWINGS.

THE SEWAGE REGULATORS SHALL BE INSTALLED AS SHOWN ON THE PLANS.

THE REGULATOR GATE WALL CASTINGS SHALL BE CAREFULLY AND ACCURATELY SET IN THE REGULATOR CHAMBER WALL FORMS AND PROPERLY SUPPORTED UNTIL THE CONCRETE HAS BEEN PLACED AROUND IT. THE FLOAT BASE AND FLOAT GUIDES SHALL BE FASTENED TO THE FLOOR OF THE REGULATOR CHAMBER BY SUITABLE BOLTS CAST IN THE CONCRETE FLOOR OF THE CHAMBER AT THE EXACT POSITION SHOWN ON THE PLANS. ANCHOR BOLTS FOR SUPPORTING THE WALL BRACKETS THAT SUPPORT THE TRANSMISSION UNIT SHALL BE CAST IN THE CONCRETE WALL OF THE REGULATOR CHAMBER. ALL ANCHOR BOLTS SHALL BE ACCURATELY SET BY THE USE OF SUITABLE TEMPLATES.

THE TRANSMISSION UNIT SHALL BE ERECTED BY CLAMPING THE STEEL I-BEAMS TO THE WALL BRACKETS AND CLAMPING THE PILLOW BLOCK OF THE SHAFT BEARINGS TO THE I-BEAMS. THESE UNITS SHALL BE CAREFULLY POSITIONED SO THAT THE TRANSMISSION CHAINS ARE EXACTLY PERPENDICULAR WHEN ERECTED AND THE FLOAT AND REGULATOR GATE MOVE FREELY WITHOUT BINDING.

ALL ERECTION WORK SHALL BE CAREFULLY AND ACCURATELY DONE BY SKILLED CRAFTSMEN. INSTRUCTIONS AND RECOMMENDATIONS OF THE EQUIPMENT MANUFACTURER SHALL BE FOLLOWED IN HANDLING AND INSTALLING THE REGULATORS.

AFTER THE EQUIPMENT HAS BEEN INSTALLED, IT SHALL BE LUBRICATED AND CAREFULLY ADJUSTED TO THE CAPACITY DIRECTED BY THE ENGINEER.

(7) TESTING, INSPECTION AND MAINTAINCE:

ALL BASIC MATERIALS SPECIFIED HEREIN FOR SEWAGE REGULATORS SHALL BE TESTED AND INSPECTED BY AN APPROVED COMMERCIAL TESTING LABORATORY PRIOR TO FABRICATION. CERTIFIED COPIES, IN DUPLICATE, OF THE INSPECTION AND ACCEPTANCE REPORTS OF THE TESTING LABORATORY SHALL BE SUPPLIED TO THE ENGINEER PRIOR TO USE OF THE MATERIALS. THE COST OF INSPECTING AND TESTING MATERIALS SHALL BE BORNE BY THE CONTRACTOR AS AN INCIDENTAL PART OF THE WORK. WHERE THE MANUFACTURER HAS LABORATORY AND TESTING FACILITIES SATISFACTORY TO THE ENGINEER, THE USE OF THESE FACILITIES MAY BE SUBSTITUTED FOR THE COMMERCIAL TESTING LABORATORY SPECIFIED ABOVE PROVIDED THE WRITTEN APPROVAL OF THE ENGINEER OF THE MANUFACTURER'S FACILITIES IS SECURED BEFORE THE DELIVERY OF ANY OF THESE MATERIALS.

AFTER DELIVERY TO THE SITE, ANY MATERIAL WHICH HAS BEEN DAMAGED IN TRANSIT OR FOUND OTHERWISE DEFECTIVE WILL BE REJECTED AND THE CONTRACTOR SHALL REMOVE SUCH MATERIAL FROM THE SITE.

AFTER THE EQUIPMENT HAS BEEN COMPLETELY INSTALLED, IT SHOULD BE ACCURATELY ADJUSTED TO PROVIDE FOR MAXIMUM AND MINIMUM FLOWS, AND FOR THE OPERATING RANGE DESIGNATED BY THE ENGINEER. IF SO ORDERED BY THE ENGINEER, THE MANUFACTURER SHALL FURNISH AN ENGINEER TO SUPERVISE THE INSTALLATION AND/OR ADJUSTMENT OF THE EQUIPMENT AT THE CONTRACTOR'S EXPENSE.

THE SEWAGE FLOW REGULATORS SHALL BE MAINTAINED BY THE CONTRACTOR UNTIL SUCH TIME AS THE ENTIRE WORK HAS BEEN COMPLETED AND ACCEPTED BY THE ENGINEER.

(8) DETAILED DRAWINGS:

THE CONTRACTORS ATTENTION IS CALLED TO THE SUBMISSION OF DETAILED DRAWINGS FOR THE APPROVAL OF THE ENGINEER PRIOR TO THE MANUFACTURE OR FABRICATION OF ANY MATERIAL OR EQUIPMENT. THESE DRAWINGS SHALL SHOW IN DETAIL THE DIMENSIONS AND ARRANGEMENT OF ALL EQUIPMENT TOGETHER WITH THE METHODS OF SUPPORTING AND ANCHORING ALL STRUCTURAL WORK, AND SHALL BE ACCOMPANIED WITH SUCH SPECIFICATIONS AS ARE NECESSARY TO SUPPLEMENT THOSE HEREIN. THE CONTRACTOR SHALL ALSO SUBMIT THE MANUFACTURER'S DETAILED COMPUTATIONS SHOWING THAT THE EQUIPMENT HE INTENDS FURNISHING HAS THE REQUIRED CAPACITY UNDER THE HYDRAULIC CONDITIONS SHOWN ON THE DRAWINGS.

GENERAL NOTES
I-8 MANHOLE SPECIALS

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

14
492

(5) PAINTING:

ALL OPERATING GEAR SHALL BE CLEANED, FILLED AND PAINTED WITH A HIGH GRADE PAINT AT THE POINT OF MANUFACTURE. ALL CASTINGS, FRAMES AND OTHER METALS NOT CONSTRUCTED OF BRONZE, BRASS OR FINISHED STEEL SHALL BE COATED AT THE POINT OF MANUFACTURE IN ACCORDANCE WITH THE A.W.W.A. STANDARD SPECIFICATIONS FOR CAST IRON PIPE AND FITTINGS, EXCEPT MACHINED SURFACES WHICH SHALL BE GIVEN A COATING OF GREASE OR OTHER SUITABLE MATERIAL.

CITY OF YOUNGSTOWN MANHOLES TYPES YA, YB, YC, & YD

(1) WATERPROOFING


MANHOLES SHALL BE COATED INSIDE WITH TWO COATS OF COAL TAR PITCH PAINT, APPLIED AT A RATE OF NOT MORE THAN 150 SQ. FT. PER GALLON PER COAT. PAYMENT SHALL BE INCLUDED UNDER THE CONTRACT PRICE BID PER EACH FOR ITEM I-8 CITY OF YOUNGSTOWN MANHOLE TYPES YA, YB, YC, & YD.
WATERPROOFING MATERIAL SHALL CONSIST OF "INERTOL STANDARD THICK" "KOPPERS SUPER SERVICE", "PITT-CHEM 103", OR EQUAL.

MAINTENANCE OF TRAFFIC

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

15
492



DETAIL "A"

DETAIL "B"

TRAFFIC ON MAHONING AVE.

MAHONING AVE. MAY BE CLOSED TO TRAFFIC FOR THE CONSTRUCTION OF THE MAHONING AVE. BRIDGE, (MAH.-18-1815) AND TRAFFIC DETOURED AS SHOWN IN DETAIL "A". TRAFFIC WILL BE DETOURED OVER RAMP "E", THE MILL CREEK BRIDGE (STRUCTURE MAH.-18-1823) RAMP "G", MARSHALL ST., AND EDWARDS ST. PRIOR TO REMOVING THE MAHONING AVE. BRIDGE FROM SERVICE FOR RECONSTRUCTION. THE NECESSARY CONSTRUCTION TO MAINTAIN MAHONING AVE. TRAFFIC INCLUDES THE FOLLOWING ITEMS-

(a) RAMP "E" COMPLETE CONSTRUCTION INCLUDING McKINLEY AVE. INTERSECTION FROM STA. 0+00 TO STA. 3+64.69
(b) MAIN LINE PAVING FROM STA. 960+75 TO MILL CREEK. STRUCTURE STA. 962+23.25
(c) MILL CREEK STRUCTURE No 1823 INCLUDING APPROACH SLABS
(d) RUNAROUND PAVEMENT FROM EXPRESSWAY STA. 969+75 TO 970+50 AND STA. 2+37.36 TO 3+37.36
(e) MAIN LINE PAVING FROM MILL CREEK STRUCTURE STA 968+71.96 TO STA. 972+00
(f) RAMP "G" COMPLETE CONSTRUCTION FROM STA. 0+00 TO STA. 6+77.30
(g) MARSHALL ST. COMPLETE CONSTRUCTION FROM GLENWOOD TO EDWARDS.
(h) GLENWOOD AVE. STRUCTURE No MAH.-18-1835
(J) GLENWOOD AVE. IMPROVEMENT.

PAYMENT FOR THE PLACEMENT AND REMOVAL OF THE RUNAROUND PAVEMENT ON RAMP "G" AND THE RUNAROUND PAVEMENT BETWEEN EXPRESSWAY STA. 969+75 AND STA. 970+50 SHALL BE INCLUDED UNDER ITEM S-15 TEMPORARY RUNAROUND CLASS "A" MAHONING AVE.

TRAFFIC ON GLENWOOD AVE.


GLENWOOD AVE. MAY BE CLOSED TO TRAFFIC DURING THE CONSTRUCTION OF THE GLENWOOD AVE. BRIDGE AND APPROACHES AND TRAFFIC DETOURED OVER HIGH ST. AND EDWARDS ST. TO MAHONING AVE.-THE MARSHALL ST. IMPROVEMENT MUST BE COMPLETE PRIOR TO THE CLOSING OF GLENWOOD AVE.-TWO WAY TRAFFIC WILL BE MAINTAINED ON MARSHALL ST. DURING THE TIME THAT GLENWOOD AVE. IS CLOSED FOR CONSTRUCTION. THE EDWARDS ST. INPROVEMENT MUST BE COMPLETE & OPEN TO TRAFFIC PRIOR TO THE CLOSING OF GLENWOOD AVE.

TRAFFIC ON MARSHALL ST.

MARSHALL ST. MAY BE CLOSED TO TRAFFIC FROM GLENWOOD AVE. TO ISALY DRIVEWAY APPROACH AT STA. 4+94.5 DURING THIS PERIOD TWO WAY TRAFFIC WILL BE MAINTAINED FROM THE ISALY DRIVEWAY APPROACH AT STA. 4+94.5 TO EDWARDS ST.- UPON COMPLETION OF CONSTRUCTION OF THE MARSHALL ST. IMPROVEMENT FROM GLENWOOD AVE. TO STA. 4+94.5, MARSHALL ST. MAY BE CLOSED FROM STA. 4+94.5 TO EDWARDS ST. AND TWO WAY TRAFFIC MAINTAINED OVER THE COMPLETED MARSHALL ST. CONSTRUCTION FROM GLENWOOD AVE. TO THE ISALY DRIVEWAY APPROACH AT STA. 4+94.5. PART WIDTH CONSTRUCTION SHALL BE EMPLOYED AND ONE WAY TRAFFIC MAINTAINED FROM EDWARDS ST. TO THE END OF CONSTRUCTION STA. 22+50. THE CONTRACTOR SHALL COOPERATE TO MAINTAIN ACCESS TO WAREHOUSES ON THE NORTH SIDE OF MARSHALL ST. AS DIRECTED BY THE ENGINEER

TRAFFIC ON EDWARDS ST.

EDWARDS MAY BE CLOSED TO TRAFFIC DURING THE CONSTRUCTION OF THE EDWARDS ST. IMPROVEMENT AND TRAFFIC DETOURED OVER HIGH ST. AND GLENWOOD AVE. - GLENWOOD AVE. SHALL NOT BE CLOSED DURING THE PERIOD THAT EDWARDS ST. IS CLOSED. EDWARDS ST. SHALL NOT BE CLOSED FROM MARSHALL ST. TO MAHONING AVE. DURING THE TIME THAT MARSHALL ST. IS CLOSED FROM GLENWOOD AVE. TO THE ISALY DRIVEWAY APPROACH AT STA. 4+94.5.



DETAIL "C"

MAINTENANCE OF TRAFFIC

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

16
492

GENERAL:

1. WHERE ANY OF THE WORK CALLED FOR UNDER THIS CONTRACT INVOLVES CLOSING OF EXISTING STREETS AND/OR THE REROUTING OF TRAFFIC, THE CONTRACTOR SHALL PROSECUTE TO THE FULLEST EXTENT THE WORK INVOLVED SO AS TO REDUCE TO A MINIMUM THE LENGTH OF TIME THAT THE STREETS CONCERNED SHALL BE CLOSED TO TRAFFIC.

2. PRIOR TO THE CLOSING OF ANY STREET THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A SCHEDULE OF CONSTRUCTION OPERATIONS. UPON RECIEPT OF APPROVAL OF THE SCHEDULE OF CONSTRUCTION OPERATIONS FROM THE ENGINEER AND THE CITY OF YOUNGSTOWN THE STREET MAY BE CLOSED.

3. THE CONTRACTOR SHALL PROVIDE LIGHTS, SIGNS AND BARRICADES AT THE LOCATIONS SPECIFIED UNDER THE MAINTENANCE OF TRAFFIC AND AT SUCH OTHER LOCATIONS AS DEEMED NECESSARY BY THE ENGINEER. BARRICADES SHALL MEET THE REQUIREMENTS FOR MOVABLE GATE DETAILED ON STANDARD CONSTRUCTION DRAWING No. G-7.01. LIGHTS SHALL MEET THE REQUIREMENTS OF SEC. G-7.07 OF THE SPECIFICATIONS. STANDARD "ROAD CLOSED" SIGNS SHALL BE 40"x 24" IN SIZE. THE CONTRACTOR SHALL FURNISH, ERECT, MAINTAIN AND REMOVE BARRICADES, LIGHTS AND SIGNS: COST OF WHICH SHALL BE INCLUDED IN THE LUMP SUM BID FOR MAINTAINING TRAFFIC.

4. THE CONTRACTOR MAY SUBMIT ALTERNATES TO THE SUGGESTED MAINTENANCE OF TRAFFIC PLANS. SUCH ALTERNATES SHALL BE SUBMITTED IN WRITING TO THE ENGINEER AND SHALL REQUIRE THE WRITTEN APPROVAL OF THE DIRECTOR AND THE CITY OF YOUNGSTOWN BEFORE BEING PLACED INTO OPERATION.

MAINTAINING LOCAL TRAFFIC:

THE FOLLOWING QUANTITIES ARE INCLUDED FOR MAINTAINING LOCAL TRAFFIC.

- T-10 TRAFFIC COMPACTED SURFACE COURSE ..... 500 CU. YDS.
- M-10 CALCIUM CHLORIDE ..... 10.0 TONS
- T-35 ASPHALTIC CONCRETE SURFACE COURSE OR APPROVED BITUMINOUS PREMIXED SURFACE COURSE FOR MAINTAINING TRAFFIC ..... 75 CU. YDS.

SPECIFIC LOCATION AND USAGE OF ESTIMATED QUANTITIES SET UP IN THIS PLAN TO BE USED AS DIRECTED BY THE ENGINEER SHALL BE MADE A MATTER OF RECORD BY THE INCORPORATION INTO THE FINAL CHANGE ORDER GOVERNING COMPLETION OF THIS PROJECT.

PEDESTRIAN TRAFFIC

ADEQUATE PROVISION FOR PEDESTRIAN TRAFFIC SHALL BE MAINTAINED DURING THE CONSTRUCTION OF THE PROJECT.

PROTECTION OF TRAFFIC

THE CONTRACTOR SHALL SAFEGUARD THE TRAVELING PUBLIC BY PROVIDING PLATFORMS, NETS, OR OTHER SUITABLE PROTECTION ABOVE THE TRAVELED LANES. PAYMENT FOR THIS PROTECTION SHALL BE INCLUDED IN THE LUMP SUM BID PRICE FOR "MAINTAINING TRAFFIC."

TRAFFIC ON STEEL ST.

STEEL ST. MAY BE CLOSED TO TRAFFIC DURING THE CONSTRUCTION OF THE STEEL ST. BRIDGE (MAH-18-1761) AND APPROACHES AND TRAFFIC DEOURED OVER EXISTING STREETS.

TRAFFIC ON SILLIMAN ST.

SILLIMAN ST. MAY BE CLOSED TO TRAFFIC DURING THE CONSTRUCTION OF THE SILLIMAN ST. IMPROVEMENT AND TRAFFIC DETOURED OVER EXISTING CITY STREETS.

TRAFFIC ON OAKWOOD AVE.

OAKWOOD AVE. MAY BE CLOSED TO TRAFFIC DURING THE CONSTRUCTION OF THE OAKWOOD AVE. IMPROVEMENT AND TRAFFIC DETOURED OVER EXISTING CITY STREETS.

TRAFFIC ON SALT SALT SPRINGS RD.

SALT SPRINGS RD. IS VACATED FROM BRIDGE ST. TO THE MAHONING AVE. BRIDGE. THE CONTRACTOR WILL, HOWEVER, COOPERATE TO MAINTAIN TWO WAY TRAFFIC ON THIS ROAD THE MAXIMUM LENGTH OF TIME. PART WIDTH CONSTRUCTION SHALL BE EMPLOYED ON THE CONSTRUCTION OF THE SALT SPRINGS RD. IMPROVEMENT AND TWO WAY TRAFFIC MAINTAINED.

TRAFFIC ON HIGH ST.


HIGH ST. MAY BE CLOSED DURING THE CONSTRUCTION OF THE HIGH ST. IMPROVEMENT AND THE TRAFFIC DETOURED OVER EXISTING CITY STREETS. PART WIDTH CONSTRUCTION SHALL BE EMPLOYED IN THE EDWARDS ST. - HIGH ST. INTERSECTION AND TWO WAY TRAFFIC MAINTAINED.

TRAFFIC ON OAK HILL AVE.

PART WIDTH CONSTRUCTION SHALL BE EMPLOYED AND TWO WAY TRAFFIC MAINTAINED DURING THE CONSTRUCTION OF THE OAK HILL AVE. IMPROVEMENT AND THE CONSTRUCTION OF THE EXPRESSWAY STRUCTURE (MAH-18-1904) OVER OAK HILL AVE.

TRAFFIC ON PIKE ST.

PIKE ST. MAY BE CLOSED TO TRAFFIC DURING THE CONSTRUCTION OF THE EXPRESSWAY AND THE PIKE ST. RELOCATION. THE CONSTRUCTION OF THE PIKE ST. RELOCATION SHALL BE PURSUED DILIGENTLY TO REDUCE TO THE MINIMUM THE LENGTH OF TIME PIKE ST. IS CLOSED TO TRAFFIC.



DETAIL "A"

TRAFFIC ON MARKET ST.

TWO WAY TRAFFIC WILL BE MAINTAINED ON MARKET ST. DURING THE CONSTRUCTION OF THE MARKET STREET BRIDGE (MAH-18-1950) AND APPROACHES AS SHOWN ON DETAIL "A". MARKET ST. SOUTHBOUND TRAFFIC WILL BE DETOURED OVER WEST WOODLAND, WILLIAMS, AND HUGHS STREETS WHICH WILL BE MADE ONE WAY TO ACCOMODATE THE TRAFFIC IN THE FOLLOWING MANNER.

WEST WOODLAND - MARKET TO WILLIAMS - ONE WAY, WEST BOUND
WILLIAMS - WEST WOODLAND TO HUGHS - ONE WAY, SOUTH BOUND
HUGHS - WILLIAMS TO MARKET - ONE WAY, EAST BOUND

MARKET ST. NORTH BOUND TRAFFIC WILL BE DETOURED OVER THE RUNAROUND ROAD, HAYES AVE. AND EAST WOODLAND AVE. WHICH WILL BE MADE ONE WAY TO ACCOMODATE THIS TRAFFIC IN THE FOLLOWING MANNER:

RUNAROUND ROAD - MARKET TO HAYES, ONE WAY NORTHBOUND.
HAYES AVE. - RUNAROUND RUNAROUND ROAD TO EAST WOODLAND AVE., ONE WAY NORTHBOUND.
EAST WOODLAND AVE. - HAYES AVE. TO MARKET ST., ONE WAY WESTBOUND.

PAYMENT FOR PLACEMENT & REMOVAL OF THE RUNAROUND ROAD SHALL BE INCLUDED UNDER ITEM S-15 TEMPORARY RUNAROUND ROAD - TYPE "A" MARKET ST.

TRAFFIC ON WEST WOODLAND AVE.

WEST WOODLAND AVE. FROM MARKET ST. TO THE END OF WORK STA. 7+50 MAY BE CLOSED TO TRAFFIC DURING THE CONSTRUCTION OF THE WOODLAND AVE. BRIDGE (MAH-18-1941) AND WOODLAND AVE. IMPROVEMENT. TWO WAY TRAFFIC WILL BE MAINTAINED ON MARKET ST. DURING THE PERIOD THAT WEST WOODLAND AVE. IS CLOSED FOR CONSTRUCTION.

TRAFFIC ON WILLIAMS ST.

WILLIAMS ST. MAY BE CLOSED TO TRAFFIC DURING THE CONSTRUCTION OF THE WOODLAND AVE. BRIDGE (MAH-18-1941) AND THE WOODLAND AVE. - WILLIAMS ST. INTERSECTION. ACCESS WILL BE MAINTAINED TO THE GENERAL ELECTRIC DRIVE STA. 8+62.

TRAFFIC ON EAST WOODLAND


PART WIDTH CONSTRUCTION WILL BE EMPLOYED AND TWO WAY TRAFFIC MAINTAINED ON WOODLAND AVE. (EAST) DURING THE CONSTRUCTION OF THE WOODLAND AVE. (EAST) IMPROVEMENT.


TRAFFIC ON HAYES AVE.

TWO WAY TRAFFIC SHALL BE MAINTAINED ON HAYES AVE. UNTIL THE COMPLETION OF CONSTRUCTION OF THE MARKET ST. BRIDGE (MAH-18-1950)

TRAFFIC ON RIDGE AVE.

RIDGE AVE. MAY BE CLOSED TO TRAFFIC DURING THE CONSTRUCTION OF THE RIDGE AVE. BRIDGE (MAH-18-1934) AND APPROACHES AND TRAFFIC DETOURED OVER EXISTING STREETS.





COMPUTATIONS

FED. RD.	STATE	PROJECT	
2	OHIO		

17
492

MAH - 18 - 17.20

EARTHWORK ANALYSIS

	EXCAVATION	EMBANKMENT
MAH. - 18 - 17.20		
STA. 922+50 TO STA. 930+00	120,957	0
STA. 930+00 TO STA. 940+00	168,837	0
STA. 940+00 TO STA. 950+00	93,429	71,068
STA. 950+00 TO STA. 960+00	66,322	102,687
STA. 960+00 TO STA. 970+00	68,894	958
STA. 970+00 TO STA. 980+00	137,006	16,570
STA. 980+00 TO STA. 990+00	6,612	101,858
STA. 990+00 TO STA. 1000+00	38,064	48,134
STA. 1000+00 TO STA. 1010+00	1,277	111,244
STA. 1010+00 TO STA. 1020+00	52,031	82,435
STA. 1020+00 TO STA. 1030+00	140,901	264
STA. 1030+00 TO STA. 805+20	132,670	0
RAMP - A	5,246	43
RAMP - B	24,188	0
RAMP - C	130,149	35,818
RAMP - D	151	11,082
RAMP - E	29,561	0
RAMP - F	16,141	2,270
RAMP - H	69,534	0
RAMP - L	11,159	26
RAMP - K	673	0
RAMP - M	42,139	0
RAMP - N	41,345	0
INTERCHANGE WITH MAHONING-W. FEDERAL EXPRESSWAY		
MAHONING-W. FEDERAL EXPRESSWAY	231	174,512
RAMP - B_3	20	58,898
RAMP - C_3	33,433*	21,173
PIKE STREET	1,648	7,466
BURNS STREET AND HALL COURT	943	53
TOTALS	1,433,561	846,559
EMB. + 20%		1,015,870
SURPLUS = ROADWAY EXC. + EXC. FOR STRUCTURES + CHANNEL EXC. - (EMBANKMENT + 20%)		
1,433,561 + 248 + 63 - 1,015,870 = 418,002 C.Y.		

PARTICIPATING FUNDS

* 10 F. and P. Participation

	EXCAVATION	EMBANKMENT
OAKWOOD AVENUE	252	5
SILLIMAN STREET	507	13
SALT SPRINGS ROAD	1,805	433
PARK ROAD	35,155	0
MARSHALL STREET	6,083	29
EDWARDS STREET	2,312	1
HIGH STREET	991	38
OAKHILL AVENUE	136	104
EAST WOODLAND AVENUE	958	0
WEST WOODLAND AVENUE	1,017	48
RAMP - "M"	12,913	0
RAMP - "D" 10+00 TO END	1,199	30,546
TOTALS	63,328	31,217
EMB. + 20%		37,460
SURPLUS = EXC. - (EMB. + 20%) = 25,868		

NON-PARTICIPATING FUNDS

PAVEMENT & BASE

	ITEM-T-71 10" PORTLAND CEMENT CONCRETE PAV'T. S.Y.		ITEM-T-71 9" PORTLAND CEMENT CONCRETE S.Y.		ITEM-1-18 5" STABILIZED CRUSHED AGGREGATE C.Y.		ITEM-I-22 SUBBASE C.Y.		ITEM-T-31 BITUMINOUS SURFACE TREATMENT No 6 AGGREGATE C.Y.		ITEM-T-31 BITUMINOUS SURFACE TREATMENT BITUMINOUS MAT'L.-GAL.		ITEM-B-219 WATERPROOFED AGGREGATE BASE COURSE C.Y.			
	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS
STA. 925+28.90 TO STA. 930+00	2,512				139		749		8		246		82			
STA. 930+00 TO STA. 940+00	6,557				439		1,940		25		772		257			
STA. 940+00 TO STA. 950+00	5,333				474		1,787		27		833		278			
STA. 950+00 TO STA. 960+00	5,886				330		1,726		19		589		196			
STA. 960+00 TO STA. 970+00	2,331				133		681		8		238		79			
STA. 970+00 TO STA. 980+00	5,960				408		1,786		23		730		243			
STA. 980+00 TO STA. 990+00	4,773				366		1,555		21		657		219			
STA. 990+00 TO STA. 1000+00	5,840				396		1,778		23		707		236			
STA. 1000+00 TO STA. 1010+00	4,793				329		1,464		19		587		196			
STA. 1010+00 TO STA. 1020+00	5,363				325		1,551		19		580		193			
STA. 1020+00 TO STA. 1030+00	6,107				352		1,770		20		630		210			
STA. 1030+00 TO STA. 1034+91.44	2,685				175		819		10		312		104			
RAMP - A	556		1,426		88		409		5		147		45			
RAMP - B	1,082		1,442		121		562		7		215		72			
RAMP - C	373		3,299		170		809		10		302		101			
RAMP - D	1,223		1,015	2,136	113	66	476	427	7	4	201	110	67	37		
RAMP - E	105		1,936		63		406									
RAMP - F	763		952		68		366		4		122		41			
RAMP - G	462		1,502		72		414									
RAMP - H			2063		106		470		6		190		63			
RAMP - J	1,312		1,776		118		645		7		211		70			
RAMP - K	1,011		2050		126		660		7		226		75			
RAMP - L	222		1,140		48		284		3		85		29			
RAMP - M	1041		2353		125		714		7		223		74			
RAMP - N	400		1693		66		421		4		117		39			
SALT SPRINGS ROAD				4,091				710								
MARSHALL STREET				8,609				1,497								
EDWARDS STREET			1,075	2,887			142	547								
PIKE STREET			2,015	650			360	105								
WEST WOODLAND AVENUE			761				108									
RAMPS "F" & "H" INTERSECTION			1573		32		319		2		53		18			
TOTAL	66,690		28,071	18,373	5,177	66	25,171	3,286	291	4	8973	110	2987	37		

	ITEM-B-19 AGGREGATE BASE COURSE C.Y.		ITEM-B-35 ASPHALTIC CONC. PRE-LEVELING COURSE C.Y.		ITEM-I-22 SUBBASE C.Y.		ITEM-B-70 9" PORTLAND CEMENT BASE COURSE S.Y.		ITEM-T-30 BITUMINOUS PRIME COAT GAL.		ITEM-B-35 ASPHALTIC CONC. LEVELING COURSE C.Y.		ITEM-T-35 ASPHALTIC CONC. SURFACE COURSE TYPE "C" C.Y.		ITEM-B-35-4" ASPHALTIC CONC. BASE COURSE C.Y.	
	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS
OAKWOOD STREET						229		1039		213		118		59		
SILLIMAN STREET				46.5		158		553		242.5		134.8		67.4		
STEEL STREET							49				26		13			
SALT SPRINGS ROAD												5				
PARK ROAD		585		105										105		
GLENWOOD AVENUE					50		267				14.8		7.4			
MARSHALL STREET																
EDWARDS STREET																
HIGH STREET				24		352		844		641		356		178		
OAKHILL AVENUE				37		62		220		169		110		55		
WEST WOODLAND AVENUE				101		143		663		189		106	53			
EAST WOODLAND AVENUE				24		202		771		300		166		83		
RAMPS "F" & "H"			8.5				135		13.5		29.6		14.8			
STA. 920+00 TO STA. 930+00	5		1.6								1.0					
ISALY DAIRY		63												37		
RAMPS 'E' & 'G'											70.0		30.0		240	
BURNS ST. AND HALL CT.	218										54.6		27.3			
TOTAL	223	648	10.1	337.5	50	1146	451	4090	13.5	1,754.5	195.0	995.8	165.5	584.4	240	

Rev 11-2-60 RE

COMPUTATIONS

FED. RD.	STATE	PROJECT	
2	OHIO		

18
492

MAH-18-17.20

H10 DUMPED ROCK FILL AS PER PLAN CU. YDS.	
RAMP-"D" PARTICIPATING FUNDS	5,414
RAMP-"D" NON-PARTICIPATING FUNDS	1,429
TOTAL	6,843

ITEM E-1 COMPACTED SUBGRADE - S.Y.		
	P. FUNDS	N.P. FUNDS
EXPRESSWAY PAVEMENT APPROACH SLABS & PAVED SHOULDERS	88,507	
RAMPS PAVEMENT & PAVED SHL'DR.	42,053	2,576
SALT SPRINGS ROAD		4,140
MARSHALL STREET		8,609
EDWARDS STREET	1,075	2,887
PIKE STREET	2,665	
PARK ROAD		2,828
W. WOODLAND AVE.	761	
BURNS STREET & HALL COURT	983	
TOTAL	136,044	21,040

E-11 WATER $\frac{5}{1000}$ x (EMBANKMENT + I·22 + B·13 (M. GAL.)		
	P. FUNDS	N.P. FUNDS
$\frac{5}{1000}$ x (846,506 + 25,276 + 5)	4,359	
$\frac{5}{1000}$ x (28,592 + 3,181 + 585)		162
TOTAL	4,359	162

PAVEMENT REPLACEMENT FOR SEWER & WATER LINE CONSTRUCTION

	ITEM·B·70 PORTLAND CEMENT BASE COURSE FOR PAV'T. REPL.		ITEM·T·35 ASPALTIC CONC. SURFACE COURSE FOR PAV'T. REPL. TYPE "C"	
	N.P. FUNDS	P. FUNDS	N.P. FUNDS	P. FUNDS
SILLIMAN STREET	187	47		2.0
OAKWOOD STREET	60	85		3.5
STEEL STREET		35		
MAHONING AVENUE		93		3.9
GLENWOOD AVENUE		205		6.6
ROCKVIEW AVENUE		343		11.9
EDWARDS STREET		6		
PLUM STREET		52		2.2
WEST STREET		124		3.8
SMITH STREET		34		1.3
HILKER STREET		8		0.2
OAKHILL AVENUE	79	21		0.1
PIKE STREET		10		
RIDGE STREET		23		0.9
WOODLAND AVENUE	180	201		
WILLIAMS STREET				
MARKET STREET		575		24.0
HAYES AVENUE		13		0.5
HIGH STREET	154			
TOTAL	660	1,875		60.9

ITEM L-9 SEEDING & FERTILIZER

	ITEM L-9 SEEDING S.Y.		ITEM L-9 FERTILIZER TONS (20#/1000 S.F.)	
	P. FUNDS	N.P. FUNDS	P. FUNDS	N.P. FUNDS
STA. 922+50 TO STA. 930+00	13,502		1.215	
STA. 930+00 TO STA. 940+00	16,777		1.510	
STA. 940+00 TO STA. 950+00	19,047		1.714	
STA. 950+00 TO STA. 960+00	18,703		1.683	
STA. 960+00 TO STA. 970+00	3,604		.324	
STA. 970+00 TO STA. 980+00	17,848		1.606	
STA. 980+00 TO STA. 990+00	13,558		1.220	
STA. 990+00 TO STA. 1000+00	17,743		1.597	
STA. 1000+00 TO STA. 1010+00	13,726		1.235	
STA. 1010+00 TO STA. 1020+00	20,932		1.884	
STA. 1020+00 TO STA. 1030+00	8,006		.721	
STA. 1030+00 TO STA. 1034+91.44	6,985		.629	
RAMP - A	3,070		.276	
RAMP - B	5,924		.533	
RAMP - C	26,280		2.401	
RAMP - D	1,262	5,910	.114	.532
RAMP - E	6,621		.596	
RAMP - F	6,415		.577	
RAMP - H	10,388		.935	
RAMP - K	522		.047	
RAMP - L	2,403		.216	
RAMP - M	7,202		.648	
RAMP - N	5,222		.470	
INTERCHANGE WITH MAH.W.FED.EXP.				
MAHONING W. FEDERAL	7,728		.696	
RAMP·B_3	7,673		.691	
RAMP·C_3 & D_3	4,953		.446	
M.V.S.D. EASEMENT		6,000		.540
OAKWOOD STREET		580		.052
SILLIMAN STREET		700		.063
SALT SPRINGS ROAD		5,000		.450
PARK ROAD		7,229		.651
GLENWOOD AVENUE		50		.005
MARSHALL STREET		760		.068
EDWARDS STREET		412		.037
HIGH STREET		1,420		.128
OAKHILL AVENUE		342		.031
PIKE STREET		2,977		.268
WEST WOODLAND AVE.		490		.044
EAST WOODLAND AVE.		300		.027
STEEL STREET		33		.003
TOTAL	266,496	26,203	23.984	2.899

QUANTITY SUMMARY
ROADWAY

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

19
492

	ITEM	8	16	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	70	PARTICIPATING FUNDS	NON-PARTICIPATING FUNDS	SUB-TOTAL ITEM	SUB-TOTAL QUANTITY	SUB-TOTAL UNIT	DESCRIPTION
	E-1			SEE SHEET Nº 17																												~~1,400,128~~ 1,433,568	~~96,761~~ 63,328	E-1	1,496,889	C.Y.	ROADWAY EXCAVATION - METHOD "B", AS PER PLAN
	E-1			SEE SHEET Nº 18																												136,044	21,040	E-1	157,084	S.Y.	COMPACTED SUBGRADE
	E-8			1252					844	1331	1393	1820	1060	430	2490							467			1000	305								E-8	12392	S.Y.	REMOVAL & DISPOSAL OF EXISTING RIGID PAVEMENT
	E-8			1120							287					224	960													356	2947			E-8	2947	S.Y.	REMOVAL & DISPOSAL OF EXISTING NON-RIGID PAVEMENT
	E-8																																	E-8		S.Y.	REMOVAL & DISPOSAL OF EXISTING WEARING COURSE
	E-8			8190					7370	4910	8860	9040	5300	1730	6780	2180	2085					1850			5000	1050	3720				76	68141		E-8	68,141	S.F.	REMOVAL & DISPOSAL OF EXISTING SIDEWALK
	E-8																																	E-8		S.F.	REMOVAL & STORAGE OF EXISTING SIDEWALK
	E-8			1876					726	718	1450	1820	1060	430	992	340	770					190			710	220	345				225	11872		E-8	11,872	L.F.	REMOVAL & DISPOSAL OF EXISTING CURB, CURB & GUTTER OR HEADER CURB
	E-8																																	E-8		L.F.	REMOVAL & STORAGE OF EXISTING STONE CURB
	E-4	1575																													1575			E-4	1575	C.Y.	SPECIAL BORROW USING GRANULAR MATERIAL AS PER PLAN
	E-9																														LUMP			E-9	LUMP	LUMP	REMOVAL OF TREES & STUMPS
P NP	E-11			SEE SHEET Nº 18																											4359	LUMP 162		E-11	4521	M. GALS.	WATER
P NP	I-10			SEE SHEET Nº 18																											5414	1429		I-10	6843	C.Y.	DUMPED ROCK FILL AS PER PLAN
	I-8			1	1	3	3	2	1	2	2	2	2	1	2																22			I-8	22	EACH	MONUMENT ASSEMBLIES, STANDARD
	I-13																										3720	1624	1002	45	2781	9172		I-13	9172	S.F.	5" PORTLAND CEMENT CONC. SIDEWALKS INCLUDING 5" CINDER BASE
	I-13																																	I-13		L.F.	CONCRETE STEPS
	I-15			275	450		375	400	450	925	650	1425	1375	350	125	275	87.5	1050	262.5	1100	1300	137.5	550		50	900	775	275	500			14062.5			I-15	14062.5	L.F.	GUARD RAIL, ST'D TYPE, DEEP
	I-15			462.5	912.5	1000	925	300	925	925	1000	825	1000	825	525																9625			I-15	9,625	L.F.	GUARD RAIL, BARRIER TYPE, DEEP
P NP	L-5			SEE SHEET Nº 18																											266,496			L-5	292,699	S.Y.	SEEDING & PROTECTION AS PER PLAN
P NP	L-5			SEE SHEET Nº 18																											24	26,203 3		L-5	27	TONS	COMMERCIAL FERTILIZER (12-12-12)
	L-10			106	285	306	172		148	36	278	267	78	56		18	684	142		152	237	333	287	139	289	162		146	200	217	4738			L-10	4738	S.Y.	SODDING
	SS-18																																	SS-18		L.F.	FENCE TYPE "C"
	SS-18																																	SS-18		L.F.	FENCE TYPE "A"
	SPECIAL	40																													40			SPECIAL	40	HOURS	FILL COMPACTION USING HEAVY PNEUMATIC TIRED ROLLER
	T-35		75																												75			T-35	75	C.Y.	ASPHALTIC CONC. SURFACE COURSE OR APPROVED BITUMINOUS PRE-MIXED SURFACE COURSE FOR MAINTAINING LOCAL TRAFFIC
	T-10		500																												500			T-10	500	C.Y.	TRAFFIC COMPACTED SURFACE COURSE FOR MAINTAINING LOCAL TRAFFIC
	M-10		10																												10			M-10	10	TONS	CALCIUM CLORIDE FURNISHED AND APPLIED FOR MAINTAINING LOCAL TRAFFIC
	S-15																														LUMP			S-15	LUMP	LUMP	TEMPORARY RUNAROUND - CLASS "A" MAHONING AVE.
	S-15																														LUMP			S-15	LUMP	LUMP	TEMPORARY RUNAROUND - CLASS "A" MARKET ST.
	S-1																																	S-1		C.Y.	CLASS "C" CONC. FOR RETAINING WALLS (RESIDENTIAL)
	S-4																																	S-4		LBS.	REINFORCING STEEL FOR RETAINING WALLS (RESIDENTIAL)
	S-29																																	S-29		C.Y.	POROUS BACKFILL
	S-24										LUMP																				LUMP			S-24	LUMP	LUMP	REMOVAL OF EXISTING RETAINING WALL W-1
	S-24										LUMP																				LUMP			S-24	LUMP	LUMP	REMOVAL OF EXISTING RETAINING WALL W-2

P = PARTICIPATING NP = NON-PARTICIPATING FUND

Rev 11-23-60

QUANTITY SUMMARY
ROADWAY

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

20
492

	ITEM	71	227	232	234	235	236	249	250	253	262	273	274	288	297	302	244	268	293	SUB-TOTAL FROM SHEET 19	PARTICIPATING FUNDS	NON-PARTICIPATING FUNDS	BID ITEM	BID QUANTITY	BID UNIT	DESCRIPTION
	E-1																			1,496,880			E-1	1,496,880	C.Y.	ROADWAY EXCAVATION - METHOD "B", AS PER PLAN
	E-1																			157,084			E-1	157,084	S.Y.	COMPACTED SUBGRADE
P.	E-8	645																		12,392	645		E-8	29,533	S.Y.	REMOVAL & DISPOSAL OF EXISTING RIGID PAVEMENT
N.P.	E-8		864		349	438	3910	3814	2836		2574			258		1453						16,456				
	E-8																			2,947			E-8	2947	S.Y.	REMOVAL & DISPOSAL OF EXISTING NON-RIGID PAVEMENT
P.	E-8	404																		0	404		E-8	3959	S.Y.	REMOVAL & DISPOSAL OF EXISTING WEARING COURSE
N.P.	E-8		592	100	137								1613		1113							3,555				
P.	E-8	2520																226		68,141	2,746		E-8	159,112	S.F.	REMOVAL & DISPOSAL OF EXISTING SIDEWALK
N.P.	E-8		4510	4794	3144	3120	400	13884	10105	260	9010	11672	7302	3354	6960	9510						88,225				
P.	E-8																			0			E-8	5000	S.F.	REMOVAL & STORAGE OF EXISTING STONE SIDEWALK
N.P.	E-8																					5000				
P.	E-8	715																57		11,872	772		E-8	18,461	L.F.	REMOVAL & DISPOSAL OF EXISTING CURB, CURB & GUTTER OR HEADER CURB
N.P.	E-8		1147	1241			45							353	1469	1562						5,817				
P.	E-8																			0			E-8	11,012	L.F.	REMOVAL & STORAGE OF EXISTING STONE CURB
N.P.	E-8				630	529		2205	1825		1777	2546	1500									11,012				
																				1,575			E-4	1575	C.Y.	SPECIAL BORROW USING GRANULAR MATERIAL AS PER PLAN
	E-9																				LUMP		E-9	LUMP	LUMP	REMOVAL OF TREES & STUMPS
	E-11																			4,521		LUMP	E-11	4521	M. GALS.	WATER
	I-8																			6,843			I-10	6,843	C.Y.	DUMPED ROCK FILL AS PER PLAN
	I-8																			22			I-8	22	EACH	MONUMENT ASSEMBLIES, STANDARD
P.	I-13	2156																1260		5,172	3,416		I-13	66,557	S.F.	5" PORTLAND CEMENT CONC. SIDEWALKS INCLUDING 5" CINDER BASE
N.P.	I-13		4040	1762	612	360	4250	5271	3140	260	7352	6979	3553	3518	7710	5162						53,969				
P.	I-13																			0			I-13	57.65	L.F.	CONCRETE STEPS
N.P.	I-13		6.25									7	6.5		37.9							57.65				
	I-15																			14,062.5			I-15	14,062.5	L.F.	GUARD RAIL, ST'D TYPE, DEEP
	I-15																									
	I-15																			2,625			I-15	2,625	L.F.	GUARD RAIL, BARRIER TYPE, DEEP
																				292,699			L-5	292,699	S.Y.	SEEDING & PROTECTION AS PER PLAN
																				27			L-5	27	TONS	COMMERCIAL FERTILIZER (12-12-12)
																				4,738			L-10	4,738	S.Y.	SODDING
									335													335	SS-18	335	L.F.	FENCE TYPE "C" REMOVED AND REBUILT
																				0	21,808		SS-18	21,808	L.F.	FENCE TYPE "C"
P.	SS-18																			0	207		SS-18	442	L.F.	FENCE TYPE "A"
N.P.	SS-18								235													235				
	SPECIAL																			40			SPECIAL	40	HOURS	FILL COMPACTION USING HEAVY PNEUMATIC TIRED ROLLER
																							L-7	614	S.Y.	HAND LAID - STONE RIP-RAP
																614						614				
																				75			T-35	75	C.Y.	ASPHALTIC CONC. SURFACE COURSE OR APPROVED BITUMINOUS PRE-MIXED SURFACE COURSE FOR MAINTAINING LOCAL TRAFFIC
																				500			T-10	500	C.Y.	TRAFFIC COMPACTED SURFACE COURSE FOR MAINTAINING LOCAL TRAFFIC
																				10			M-10	10	TONS	CALCIUM CLORIDE FURNISHED AND APPLIED FOR MAINTAINING LOCAL TRAFFIC
	S-15																			LUMP			S-15	LUMP	LUMP	TEMPORARY RUNAROUND - CLASS "A" - MAHONING AVE.
	S-15																			LUMP			S-15	LUMP	LUMP	TEMPORARY RUNAROUND - CLASS "A" - MARKET ST.
P.	S-22																	LUMP			LUMP		S-22	LUMP	LUMP	REMOVAL OF PORTION OF EXISTING CONC. COAL BIN
N.P.	S-22																	LUMP				LUMP	S-22	LUMP	LUMP	REMOVAL OF PORTION OF EXISTING HOUSE
P.	S-24																						S-24	LUMP	LUMP	REMOVAL OF EXISTING STONE WALL
N.P.	S-24					LUMP																LUMP				
P.	S-1																						S-1	22.5	C.Y.	CLASS "C" CONC. FOR RETAINING WALLS (SEE SHEET 226)
N.P.	S-1											5			17.5							22.5				
P.	S-4																						S-4	921		REINFORCING STEEL FOR RETAINING WALLS (SEE SHEET 226)
N.P.	S-4											210			711							921				
P.	S-29																			0			S-20	19		POROUS BACKFILL (SEE SHEET 226)
N.P.	S-29											3			16							19				
	S-24																			LUMP			S-24	LUMP	LUMP	REMOVAL OF EXISTING RETAINING WALL W-1
	S-24																			LUMP			S-24	LUMP	LUMP	REMOVAL OF EXISTING RETAINING WALL W-2
												LUMP										LUMP	S-24	LUMP	LUMP	REMOVAL OF EXISTING CONC. BLK. RETAINING WALL
															LUMP					LUMP		LUMP	S-24	LUMP	LUMP	REMOVAL OF EXISTING RETAINING WALL
P.	SS-18																						SS-18	335	L.F.	REMOVAL & REUSE OF EXISTING FENCE & POSTS
N.P.	SS-18								335													335				
P.	T-10																						T-10	45	C.Y.	TRAFFIC COMPACTED SURFACE COURSE
N.P.	T-10								45													45				

P. = PARTICIPATING FUNDS N.P. = NON-PARTICIPATING FUNDS

FED. RD.	STATE	PROJECT	
2.	OHIO		

21
492

MAH.-18-17.20

QUANTITY SUMMARY
ROADWAY

PARTICIPATING FUNDS

BID ITEM	QUANTITY	UNIT	DESCRIPTION
S-24	LUMP	LUMP	2½ STY. BR. HSE. & FR. GAR. PARCEL 28 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~1 STY. FR. HSE. PARCEL 40 LA~~
S-24	LUMP	LUMP	2 STY. FR. HSE. & BR. GAR. PARCEL 51 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. ~~& FR. GAR.~~ PARCEL 74 LA
S-24	LUMP	LUMP	2 STY. BR. 4 APTS & STORE BLDG; TILE GAR. PARCEL 112 LA
S-24	LUMP	LUMP	2 STY. BR. TAVERN & APT. BLDG. - FR. GAR. PARCEL 97 LA
S-24	LUMP	LUMP	2 STY. BR. HSE. & FR. GAR. PARCEL 96 LA
S-24	LUMP	LUMP	2 STY. BR. STORE & APT. BLDG. - BR. GAR. PARCEL 113 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. SHED PARCEL 118 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 121 LA~~
S-24	LUMP	LUMP	ST. MICHAEL'S CHURCH & BL. BLDG. CONC. BL. PAVILION PARCEL 133 LA
S-24	LUMP	LUMP	2 STY. BR. OFFICE BLDG. & SCALES PARCEL 140 LA
S-24	LUMP	LUMP	1 STY. BL. OFFICE & SHOP BLDG. PARCEL 146 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~R.R. SIDING - B & O R.R. (LIN. FT.) PARCEL 144 LA~~
S-24	LUMP	LUMP	1 STY. BL. BLDG. PARCEL 147 LA
S-24	LUMP	LUMP	1 STY. BL. BLDG. PARCEL 148 LA
S-24	LUMP	LUMP	1 STY. BL. & STONE BLDG. PARCEL 151 LA
S-24	LUMP	LUMP	1 STY. FR. SHED PARCEL 149 LA
S-24	LUMP	LUMP	1 STY. BL. BLDG. & 1 CONC. FDN. PARCEL 150 LA
S-24	LUMP	LUMP	1- STY. BL. BLDG. PARCEL 155 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~1 STY. FR. HSE. PARCEL 138 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 BILL BOARDS - GEN. OUTDOOR ADV. PARCEL 159 LA~~
S-24	LUMP	LUMP	2½ STY. FR. HSE. PARCEL 160 LA
S-24	LUMP	LUMP	2 STY. FR. OFFICE BLDG. & VARIOUS FR. SHEDS PARCEL 161 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE'S PARCEL 158 LA~~
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 192 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. & BL. GAR. PARCEL 218 LA~~
S-24	LUMP	LUMP	2 STY. FR. TAVERN BLDG. PARCEL 217A LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 218 LA
S-24	LUMP	LUMP	2 STY. BR. APT. BLDG. - 3 UNITS PARCEL 217 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 253P-A
S-24	LUMP	LUMP	2 STY. BR. CHURCH PARCEL 253H-A
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 253J-A
S-24	LUMP	LUMP	2 STY. FR. HSE. CONC. BL. GAR. PARCEL 234 A
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 241 A~~
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 250 -A
S-24	LUMP	LUMP	~~2 STY. FR. HSE.~~ - FR. GAR. ~~& SHED~~ PARCEL 251A-A
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 255 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE & BL. GAR. PARCEL 253D-A~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 253F-A~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 253G-A~~
S-24	LUMP	LUMP	1 STY. ~~BL. &~~ STUCCO HSE. FR. HSE. PARCEL 253L-A
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 253M-A~~
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 262 C LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 262 F LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. FR. GAR. & SHED PARCEL 261 D LA~~
S-24	LUMP	LUMP	3 STY. FR. APT. BLDG. (6 UNITS) PARCEL 397 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. & TILE GAR. PARCEL 395 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 393 LA~~
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 369 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. & FR. GAR. PARCEL 368 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 393 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. & BL. GAR. PARCEL 367 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2½ STY. FR. HSE. & FR. GAR. PARCEL 366 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2½ STY. FR. HSE. & FR. GAR. PARCEL 390 LA~~
S-24	LUMP	LUMP	2½ STY. FR. HSE. PARCEL 390 A LA
S-24	LUMP	LUMP	2 STY. FR. DUPLEX PARCEL 364 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 365 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 391 A LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 406 B LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 391 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 406 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 392 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. DUPLEX PARCEL 394 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 - 2 STY. FR. HSE'S PARCEL 407 LA~~
S-24	LUMP	LUMP	3 STY. BR. & FR. STORE & APT. PARCEL 425 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 425 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 426 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 428 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 430 LA~~
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 431 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 433 LA~~
S-24	LUMP	LUMP	2 STY. BR. WAREHOUSE PARCEL 433 A LA
S-24	LUMP	LUMP	2 STY. STUCCO HSE. PARCEL 263 LA
S-24	LUMP	LUMP	2 STY. STUCCO HSE. PARCEL 265 LA
S-24	LUMP	LUMP	2 STY. STUCCO HSE. PARCEL 265 A LA
S-24	LUMP	LUMP	2 STY. STUCCO HSE. PARCEL 265 B LA
S-24	LUMP	LUMP	2 STY. STUCCO HSE. PARCEL 266 LA
S-24	LUMP	LUMP	2 STY. STUCCO HSE. PARCEL 266 B LA
S-24	LUMP	LUMP	2 STY. STUCCO HSE. PARCEL 266 C LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 271 LA~~

PARTICIPATING FUNDS

BID ITEM	QUANTITY	UNIT	DESCRIPTION
~~S-24~~	~~LUMP~~	~~LUMP~~	~~1 STY. FR. HSE. PARCEL 272 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 273 C LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 275 LA~~
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 273 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 277 LA~~
S-24	LUMP	LUMP	1 STY. BL. BLDG. PARCEL 280 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 285 A LA
S-24	LUMP	LUMP	FR. SHED PARCEL 287 B LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 287 C LA
S-24	LUMP	LUMP	CHURCH BLDG. & SHED PARCEL 310 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 312 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 311 LA~~
S-24	LUMP	LUMP	1 STY. BL. BLDG. - 2 FR. BLDGS. & TRUCK SCALE PARCEL 313 B A
S-24	LUMP	LUMP	1 STY. BL. OFFICE BLDG. & THREE SHEDS. PARCEL 313 LA
S-24	LUMP	LUMP	1 STY. FR. BLDG., FR. GAR. & CON. BL. GAR. PARCEL 316 LA
S-24	LUMP	LUMP	3-2 STY. FR. HSE. - 1-2 STY. BR. HSE. & 1-3 STY. LAB. BLDG. PARCEL 318 LA
S-24	LUMP	LUMP	FR. GAR. ~~& BL. BLDG.~~ PARCEL 320 A LA
S-24	LUMP	LUMP	~~FR. GAR.~~ STUCCO GAR. PARCEL 323 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. 1 STY. FR. HSE. & FR. SHED PARCEL 322 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 327 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 328 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. & FR. GAR. PARCEL 328 A LA~~
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 330 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2½ STY. FR. HSE. PARCEL 331 LA~~
S-24	LUMP	LUMP	2½ STY. FR. APT. HSE. & BL. GAR. PARCEL 332 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 351 LA-A
S-24	LUMP	LUMP	2 STY. FR. HSE. ~~& STY. BRICK BLDG. & FR. GAR.~~ PARCEL 352 LA
S-24	LUMP	LUMP	2 - 2 STY. FR. HSE'S PARCEL 348 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 342 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 341 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 350 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2½ STY. FR. HSE. PARCEL 347 LA~~
S-24	LUMP	LUMP	2½ STY. FR. HSE. ~~& FR. GAR.~~ PARCEL 340 LA
S-24	LUMP	LUMP	2½ STY. FR. HSE. & FR. GAR. PARCEL 339 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. ~~& FR. SHED.~~ PARCEL 334 LA
S-24	LUMP	LUMP	FR. GAR. PARCEL 333 A LA
S-24	LUMP	LUMP	1 STY. FR. BLDG. PARCEL 353 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & FR. GAR. PARCEL 358 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 359 LA~~
S-24	LUMP	LUMP	2 STY. FR. STORE & APT. BLDG. PARCEL 361 C LA
S-24	LUMP	LUMP	1 STY. BL. OFFICE BLDG. ~~& 2 STY. BL. BLDG.~~ PARCEL 363 LA
S-24	LUMP	LUMP	2 STY. BR. APT. BLDG. (10 UNITS) PARCEL 362 LA
S-24	LUMP	LUMP	1 STY. BR. WAREHOUSE PARCEL 370 LA
S-24	LUMP	LUMP	3 STY. BR. SCHOOL BLDG. PARCEL 387 LA
S-24	LUMP	LUMP	2 STY. FR. DUPLEX PARCEL 379 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. PARCEL 383 LA~~
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. & BL. GAR. PARCEL 383 B LA~~
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 384 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. & BL. GAR. PARCEL 384 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 384 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 384 LA
S-24	LUMP	LUMP	2 STY. FR. & BL. BLDG. PARCEL 384 LA
S-24	LUMP	LUMP	2 STY. FR. HSE., FR. GAR. & FR. SHED. PARCEL 315 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2½ STY. FR. HSE. & FR. GAR. PARCEL 376 LA~~
S-24	LUMP	LUMP	2 STY. FR. DUPLEX & FR. GAR. PARCEL 378 LA
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 374 LA
S-24	LUMP	LUMP	2½ STY. FR. HSE. PARCEL 373 LA
~~S-24~~	~~LUMP~~	~~LUMP~~	~~2 STY. FR. HSE. & FR. SHED PARCEL 372 LA~~
S-24	LUMP	LUMP	2 STY. FR. HSE. PARCEL 371 LA
S-24	LUMP	LUMP	FR. SHED PARCEL 4 LA
S-24	LUMP	LUMP	1 STY. FR. HSE. & FR. SHED PARCEL 37 LA
S-24	LUMP	LUMP	FR. SHED PARCEL 52 LA
S-24	LUMP	LUMP	2 STY. FR. HSE., FR. SHED, & FR. GAR. PARCEL 53 LA
S-24	LUMP	LUMP	2 STY. FR. HSE., BR. GAR. & CON. BL. SHED PARCEL 124 LA
S-24	LUMP	LUMP	2 STY. FR. HSE., CON. BL. GAR. & CON. BL. SHED PARCEL 125 LA
S-24	LUMP	LUMP	BR. GAR. (BURNED OUT) WALLS REMAINING PARCEL 127 LA
S-24	LUMP	LUMP	4 STY. FR. BLDG., & 4 FR. SHEDS. PARCEL 170 LA, 170 ALA, 170 BLA
S-24	LUMP	LUMP	STONE SPRING HOUSE FOUNDATION PARCEL 267 LA
S-24	LUMP	LUMP	1½ STY. FR. HSE. PARCEL 283 BLA
S-24	LUMP	LUMP	1 STY. TILE WHSE. WITH ATTACHED STEEL BLDG PARCEL 314 LA
S-24	LUMP	LUMP	CON. BL. BLDG. & FR. GAR. PARCEL 321 LA
S-24	LUMP	LUMP	1 STY BR. BLDG. PARCEL 326 LA
S-24	LUMP	LUMP	4 STY. FR. APT. BLDG. PARCEL 360 LA

PARTICIPATING FUNDS EXCEPT AS NOTED

TYPE CODE 7221

BID ITEM	QUANTITY	UNIT	DESCRIPTION
S-24	LUMP	LUMP	
S-24	LUMP	LUMP	
S-24	LUMP	LUMP	
S-24	LUMP	LUMP	
S-24	LUMP	LUMP	
S-24	LUMP	LUMP	
S-24	LUMP	LUMP	
			"LIGHTING QUANTITIES"
S-25	57	EACH	STANDARD 27'-0" POLE WITH 15' BRACKET
S-25	55 *	EACH	STANDARD 27'-0" POLE WITH 10' BRACKET
S-25	3	EACH	TWIN STANDARD 27'-0" POLE WITH 1-10' & 1-15' BRACKET
S-25	7	EACH	BRIDGE STANDARD 27'-0" POLE WITH 10' BRACKET
S-25	900	LIN.FT.	CONCRETE ENCASED 3" ASBESTOS-CEMENT CONDUIT
S-25	1400	LIN.FT.	CONCRETE ENCASED 2" ASBESTOS-CEMENT CONDUIT
S-25	74 ≠	EACH	LUMINAIRE-21,500 LUMEN TYPE III
S-25	51 ≠	EACH	LUMINAIRE-21,500 LUMEN TYPE II
S-25	56,750 ≠	LIN.FT.	#6-5000 VOLT LIGHTING SINGLE COND. CABLE
S-25	35,500 ≠	LIN.FT.	#2-600 VOLT GRD. GRID SINGLE COND. CABLE
S-25	250 ≠	LIN.FT.	#8-1000 VOLT SEC. SINGLE COND. CABLE
S-25	115 ≠	EACH	5/8" X 8'-0" GROUND RODS
S-25	150 ≠	EACH	24" SQUARE CONCRETE PULL BOX
S-25	2 ≠	EACH	LUMINAIRE-7000 LUMEN TYPE V
			* - 3 UNITS ARE NON-PARTICIPATING
			≠ - 100% NON-PARTICIPATING
			"RETAINING WALLS"
			HIGH STREET-MAINLINE STA. 1005+22.23 TO STA. 1005+47.59
			RAMP "L" STA. 6+28.66 TO STA. 7+98
			WOODLAND TO MARKET STA. 1025+65.85 TO STA. 1029+73.06
			RAMP "K" STA. 11+77.82 TO STA. 15+81
			RAMP "M" STA. 5+83.03 TO STA. 9+07.87
			HILKER STREET
			"ESTIMATED QUANTITIES"
E-2	12228	C.Y.	UNCLASSIFIED EXCAVATION
S-1	2192	C.Y.	CLASS "E" CONCRETE (FOOTINGS)
S-1	2237	C.Y.	CLASS "E" CONCRETE (WALLS)
S-3	1024	LIN.FT.	WATERPROOFING-12"X 1/2" PREMOLDED SEALING STRIP
S-4	334526	LBS.	REINFORCING STEEL
S-9	815	S.F.	1" PREFORMED EXPANSION JOINT FILLER SEC. M-10.02
S-16	LUMP	LUMP	FIRST TEST PILE
S-18	15850	LIN.FT.	12" CAST IN PLACE REINFORCED CONCRETE PILES
S-29	1432	C.Y.	POROUS BACKFILL
E-2	9912	SQ.FT.	STEEL SHEET PILING LEFT IN PLACE
E-2	LUMP	LUMP	COFFERDAMS, CRIBS AND SHEETING
S-18	411	LIN.FT.	CORRUGATED STEEL SHEET PILING

QUANTITY SUMMARY
PAVEMENT

FED.RD.	STATE	PROJECT	
2	OHIO		

22
492

MAH-18-17.20

PARTICIPATING FUNDS / NON-PARTICIPATING FUNDS

	ITEM	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	54	55	56	57	58	59	60	61	62	70	71	227	232			SUB-TOTAL ITEM	SUB-TOTAL QUANTITY	SUB-TOTAL UNIT	DESCRIPTION
P.	I-7																																	I-7		S.Y.	REINFORCED CONCRETE APPROACH SLABS (T=13")
P.	I-12													200			200		200			200			200		200					1200		I-12	1200	L.F.	SPECIAL CONCRETE CURB, AS PER PLAN
P.	I-12																						536	371	276	173	283	837	405			2881		I-12	2881	L.F.	ST'D. TYPE 2A CONCRETE CURB
P.	I-12																								53		80	172				305		I-12	2361	L.F.	ST'D. TYPE 2 COMBINATION CURB AND GUTTER
N.P.																														997	1059		2056				
P.	I-12	1037	1974	1974	1967	856	2007	1807	1978	1618	1800	2329	1076		578			206	106	206	206		306	1236	369	938	364	104	1402			27044		I-12	27044	L.F.	ST'D. TYPE 6 CONCRETE CURB
N.P.																																					
	I-18	SEE SHEET Nº17																														5177		I-18	5243	C.Y.	STABILIZED CRUSHED AGGREGATE - SHOULDERS & APPROACHES
P.	I-21	603	658	658	656	248	606	606	660	548	545	662	323																			6779	66	I-21	6779	S.Y.	4" PORTLAND CEMENT CONC. MEDIAN PVM'T., STD. TYPE 1
	I-21														45			22		31			27	18		25						168		I-21	168	S.Y.	4" PORTLAND CEMENT CONC. MEDIAN PAVEMENT.
P.	I-22	SEE SHEET Nº17																														25221		I-22	29,653	C.Y.	SUBBASE
P.	I-23																																4432	I-23		EACH	ST'D PRECAST PORTLAND CEMENT CONCRETE TRAFFIC DIVIDERS
P.	B-21D	SEE SHEET Nº17																														2387		B-21D	3024	C.Y.	WATERPROOFED AGGREGATE BASE COURSE
	B-15	SEE SHEET Nº17																														223	37	B-15	871	C.Y.	AGGREGATE BASE COURSE
	B-35	SEE SHEET Nº17																													1	196	648	B-35	1182	C.Y.	ASPHALTIC CONCRETE LEVELING COURSE (70-85)
	B-35	SEE SHEET Nº17																														10	986	B-35	348	C.Y.	ASPHALTIC CONCRETE PRE-LEVELING COURSE (70-85)
	B-70	SEE SHEET Nº17																														451	338	B-70	4591	S.Y.	9" PORTLAND CEMENT CONCRETE BASE COURSE
	B-70	SEE SHEET Nº 18																														1875	4140	B-70	2335	S.Y.	9" PORTLAND CEMENT CONC. BASE COURSE FOR PVM'T. REPLACEMENT
	T-30	SEE SHEET Nº17																														14	660	T-30	1768	GALS.	BITUMINOUS PRIME COAT SEC. M-5.7 RT-2 OR RT-3
	B-35	SEE SHEET Nº17																														240	1754	B-35	240	C.Y.	ASPHALTIC CONCRETE BASE COURSE (70-85)
	T-31	SEE SHEET Nº17																														291		T-31	295	TONS	BITUMINOUS SURFACE TREATMENT - Nº 6 AGGREGATE
P. N.P.	T-31	SEE SHEET Nº17																														8973	4	T-31	9083	GALS.	BITUMINOUS SURFACE TREATMENT - BITUMINOUS MATERIAL
	T-35																																110				
	T-35	SEE SHEET Nº17																														166		T-35	750	C.Y.	ASPHALTIC CONCRETE SURFACE COURSE - TYPE C (70-85)
P.	T-35																																584	T-35	3	C.Y.	ASPHALTIC CONC. SURFACE COURSE-TYPE C FOR DRIVEWAYS (70-85)
N.P.	T-35																													3			3				
	T-35	SEE SHEET Nº18																														61		T-35	61	C.Y.	ASPHALTIC CONC. SURFACE COURSE-TYPE C FOR PVM'T. REPLACEMENT (70-85)
P.	T-70																																	T-71	109	S.Y.	5" REINF. PORTLAND CEMENT CONC. PVM'T. FOR DRIVEWAY APPROACHES AS PER PLANS
N.P.	T-70																													49	60		109				
P.	T-71																																	T-70	115	S.Y.	5" PORTLAND CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS
N.P.	T-71																													41	78		119				
	T-71	SEE SHEET Nº17																														28071		T-71	46444	S.Y.	9" REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
																																18373				
	T-71	SEE SHEET Nº17																														66690		T-71	66690	S.Y.	10" REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT

* P-Denotes Participating Funds

* N.P.-Denotes Non-Participating Funds

QUANTITY SUMMARY
PAVEMENT

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

23
492

TYPE CODE 7221

	ITEM	234	235	236	238	249	250	253	262	273	274	288	292	297	302	SUB-TOTAL FROM SHEET 22	PARTICIPATING FUNDS	NON-PARTICIPATING FUNDS	BID ITEM	BID QUANTITY	BID UNIT	DESCRIPTION
P.	I-7																2,843		I-7	2,843	S.Y.	REINFORCED CONCRETE APPROACH SLABS (T=13")
P.	I-12															1,200			I-12	1,200	L.F.	SPECIAL CONCRETE CURB, AS PER PLAN
P.	I-12			2168	651	2111	1675		1674				1978		341	7,881	1,978		I-12	13,479	L.F.	STD. TYPE 2A CONCRETE CURB
N.P.	I-12																	8,620				
P.	I-12		106							2310	1500	348		1373	508	2,361		6,205	I-12	8,566	L.F.	ST'D. TYPE 2 COMBINATION CURB AND GUTTER
N.P.	I-12																					
P.	I-12	103			22		100					236			760	27,044	760		I-12	28,265	L.F.	ST'D. TYPE 6 CONCRETE CURB
N.P.	I-12																	4461				
P	I-18															5,243			I-18	5,243	C.Y.	STABILIZED CRUSHED AGGREGATE, SHOULDERS & APPROACHES
P.	I-21															6,779			I-21	6,999	S.Y.	4" PORTLAND CEMENT CONC. MEDIAN PVM'T., STD. TYPE 1
N.P.	I-21			220														220				
																168			I-21	168	S.Y.	4" PORTLAND CEMENT CONC. MEDIAN PVM'T. as per plan.
P.	I-22															296.53			I-22	29,653	C.Y.	SUBBASE
P.	I-23															0			I-23	9	EACH	ST'D. PRECAST PORTLAND CEMENT CONCRETE TRAFFIC DIVIDERS
N.P.	I-23			9														9				
P.	B-19															871			B-19	940	C.Y.	AGGREGATE BASE COURSE.
N.P.	B-19							65		5	1							69				
P.	B-219															3,024			B-219	3024	C.Y.	WATERPROOFED AGGREGATE BASE COURSE
P.	B-19																					
P.	B-35															1,182			B-35	1182	C.Y.	ASPHALTIC CONCRETE LEVELING COURSE (70-85)
																348			B-35	348	C.Y.	ASPHALTIC CONCRETE PRE-LEVELING COURSE (70-85)
P.	B-70															4,501			B-70	4,501	S.Y.	9" PORTLAND CEMENT CONCRETE BASE COURSE
P.	B-70															2,535			B-70	2,535	S.Y.	9" PORTLAND CEMENT CONC. BASE COURSE FOR PVM'T. REPLACEMENT
P.	T-30															1,768			T-30	1,768	GALS.	BITUMINOUS PRIME COAT SEC. M-5.7 RT-2 OR RT-3
																240			B-35	240	C.Y.	ASPHALTIC CONCRETE BASE COURSE (70-85)
P.	T-31															295			T-31	295	C.Y.	BITUMINOUS SURFACE TREATMENT - No 6 AGGREGATE
P.	T-31															9,083			T-31	9083	GALS.	BITUMINOUS SURFACE TREATMENT - BITUMINOUS MATERIAL
P.	T-35																					
P.	T-35															750			T-35	787	C.Y.	ASPHALTIC CONCRETE SURFACE COURSE - TYPE C (70-85)
N.P.	T-35							37										37				
P.	T-35															3			T-35	3	C.Y.	ASPHALTIC CONC. SURFACE COURSE-TYPE C FOR DRIVEWAYS (70-85)
P.	T-35															61			T-35	61	C.Y.	ASPHALTIC CONC. SURFACE COURSE-TYPE C FOR PVM'T. REPLACEMENT (70-85)
P.	T-70															109			T-71	1,698	S.Y.	5" PORTLAND CEMENT CONC. PVM'T. FOR DRIVEWAY APPROACHES AS PER PLANS
N.P.	T-70					302	266		699	173	18			77	54			1589				
P.	T-70															119			T-70	212	S.Y.	5" PORTLAND CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS
N.P.	T-70									8				19	66			93				
P.	T-71															46,444			T-71	46,444	S.Y.	9" REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
P.	T-71															66,690			T-71	66,690	S.Y.	10" REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT

* P- Denotes Participating Funds. * N.P.- Denotes Non-Participating Funds.

QUANTITY SUMMARY
DRAINAGE

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH - 18 - 17.20

24
492

ITEM	7	9	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	53	54	55	56	57	58	59	60	61	62			76	84	PARTICIPATING FUNDS	NON-PARTICIPATING FUNDS	SUB-TOTAL ITEM	SUB-TOTAL QUANTITY	SUB-TOTAL UNIT	DESCRIPTION
E-2					280													412												280			E-2	280	C.Y.	EXCAVATION FOR STRUCTURES
E-2		10,000																												10,000			E-2	10,000	SQ.FT.	SHEET PILING LEFT IN PLACE
E-3																																	E-3		C.Y.	CHANNEL EXCAVATION
E-12																																	E-12		L.F.	PIPE REMOVED UNDER 15"
E-12																																	E-12		L.F.	PIPE REMOVED 15" TO 42"
I-2	1000																													300		700	I-2	1000	L.F.	4" ___ STORM SEWERS M-6.8 (4)
I-2												180																		180			I-2	180	L.F.	8" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2			286	196	179	322	181	522	118	98	185	100	491	205			117		152	52	22	46	312	408	177	32	119				4324			I-2	4324	L.F.	12" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2			75				146		155	458		316	221				84						64			48				1567			I-2	1567	L.F.	15" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2					102		52			43		658		60																813 ~~915~~	102	I-2	915	L.F.	18" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2														137																137			I-2	137	L.F.	21" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2										57																				57			I-2	57	L.F.	21" CLASS "B" STORM SEWERS U P OR A SEC. M-6.6(b) OR SEC M-6.8(b)
I-2										246																				246			I-2	246	L.F.	24" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2											136																			136			I-2	136	L.F.	27" CLASS "B" STORM SEWERS U P OR A SEC. M-6.6 (c)
I-2										284	40			146																470			I-2	470	L.F.	27" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2			156											136																292			I-2	292	L.F.	27" CLASS "B" STORM SEWERS U P OR A SEC. M-6.6 (b) OR SEC. M-6.8 (b)
I-2			344	48																										392			I-2	392	L.F.	30" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2				252																										252			I-2	252	L.F.	33" CLASS "B" STORM SEWERS U P OR A. SEC. M-6.6(b) OR SEC. M-6.8(b)
I-2				684	123																									807			I-2	807	L.F.	33" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2											205																			205			I-2	205	L.F.	33" CLASS "B" STORM SEWERS U P OR A SEC. M-6.6(c)
I-2					354																									354			I-2	354	L.F.	33" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES M-6.6(d)
I-2											222																			222			I-2	222	L.F.	36" CLASS "B" STORM SEWERS U P OR A SEC. M-6.6(b) OR SEC M-6.8(b)
I-2																																	I-2		L.F.	36" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES M-6.6(d)
I-2								97			84															47				228			I-2	228	L.F.	12" CLASS "B" STORM SEWERS
I-2								97			54															137				191			I-2	191	L.F.	15" CLASS "B" STORM SEWERS
																													63	63			I-2	63	L.F.	12" CLASS "A" STORM SEWERS M-6.5(a) - M-6.8(b)
I-2				42					27		60	73																		202			I-2	202	L.F.	12" CLASS "A" STORM SEWERS M-6.4c
I-2						84						78																		162			I-2	162	L.F.	18" CLASS "A" STORM SEWERS M-6.4c
I-2									125																					125			I-2	125	L.F.	15" CLASS "A" STORM SEWERS
I-2											178																			178			I-2	178	L.F.	18" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d
I-2																																	I-2		L.F.	8" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.8 b
I-2																																	I-2		L.F.	12" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.8 b
I-2																													492	492			I-2	492	L.F.	15" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.8 b
I-2																																					
I-2																																	I-2		L.F.	15" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d
I-2																																	I-2		L.F.	18" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.8 b
I-2																																					
I-2																																	I-2		L.F.	18" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d
I-2																																	I-2		L.F.	21" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d
I-2																																					
I-2																																	I-2		L.F.	24" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6 b or M-6.8 b
I-2																																	I-2		L.F.	24" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6 c
I-2																																	I-2		L.F.	24" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d
I-2																																	I-2		L.F.	27" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6 b. OR M-6.8 b
I-2																																	I-2		L.F.	27" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6 b CONCRETE ENCASED
I-2																																	I-2		L.F.	27" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6 b

* AS PER PLAN

Rev 11-22-60 RE

QUANTITY SUMMARY
DRAINAGE

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

25
492

TYPE CODE 7221

	ITEM		86	87	90	93	94	96	98	99	101	112	114	120	227	232	235	236	244	251	263	275	288	292	297	302	116	97
	E-2											130	51	67													40	
	E-3											10	53														400	
P.	E-12																											
N.P.	E-12																	15										
	E-12		1013	1677	152				472																			
	I-2																											
	I-2																											
P.	I-2			15																				136				
N.P.	I-2																	446										
P.	I-2																							65				
N.P.	I-2																											
P.	I-2																											
N.P.	I-2																		96									
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-2																											
	I-1																											
	I-2																											
	I-2																											
	I-2																											
P.	I-2																											
N.P.	I-2																		26									
	I-2																											
	I-2																											
P.	I-2																							526				
N.P.	I-2																											
P.	I-2																											
N.P.	I-2																60											
P.	I-2																											
N.P.	I-2																277	26			372	278	79					
	I-2									39																		
P.	I-2				20		170	470																				
N.P.	I-2															109				277				76	245			
	I-2		185							14																		
	I-2																											
	I-2				27						24																	
	I-2									482																		
P.	I-2									186																		
N.P.	I-2																			84								
	I-2				65																							
	I-2				336					447																		
	I-2		186	269																								
	I-2			30																								

	SUB-TOTAL FROM SHEET 24	PARTICIPATING FUNDS	NON-PARTICIPATING FUNDS
E-2	280	288	
	10,000		
E-3	0	463	
E-12	0		
E-12	0	3,314	
I-2	1,000		
I-2	180		
I-2	4,324	151	
I-2			446
I-2	1,567	65	
I-2			
I-2	915		
I-2			96
I-2	137		
I-2	57		
I-2	246		
I-2	136		
I-2	470		
I-2	292		
I-2	392		
I-2	252		
I-2	807		
I-2	205		
I-2	354		
I-2	222	141	
I-2	~~286~~	286	
I-1			
I-2	228		
I-2	191		
I-2	63		
I-2	202		
I-2			26
I-2	162		
I-2	125		
I-2	178	526	
I-2	0		
I-2	0		60
I-2	0		1032
I-2	0	49	
I-2	0	669	
I-2	492	213	711
	0		
I-2	0	313	
I-2	0	51	
I-2	0	482	
I-2	0	186	
I-2			84
I-2	0	65	
I-2	0	783	
I-2	0	455	
I-2	0	30	

ITEM	QUANTITY	UNIT	DESCRIPTION
E-2	568	C.Y.	EXCAVATION FOR STRUCTURES
E-2	10,000	SQ. FT.	SHEET PILING LEFT IN PLACE
E-3	463	C.Y.	CHANNEL EXCAVATION
E-12	15	L.F.	PIPE REMOVED (UNDER 15")
E-12	3314	L.F.	PIPE REMOVED (15" TO 42")
I-2	1000	L.F.	4" STORM SEWERS M-6.8(a)
I-2	180	L.F.	8" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2	4321	L.F.	12" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2	1632	L.F.	15" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2	1011	L.F.	18" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2	137	L.F.	21" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2	57	L.F.	21" CLASS "B" STORM SEWERS U.P.O.R.A. SEC. M-6.6(b) OR M-6.8(b)
I-2	246	L.F.	24" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2	136	L.F.	27" CLASS "B" STORM SEWERS U.P.O.R.A. SEC. M-6.6(c)
I-2	470	L.F.	27" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2	292	L.F.	27" CLASS "B" STORM SEWERS U.P.O.R.A. SEC. M-6.6(b) OR SEC. M-6.8(b)
I-2	392	L.F.	30" CLASS "B" STORM SEWERS U.P.O.R.A. SEC. M-6.6(b) OR SEC. M-6.8(b)
I-2	252	L.F.	33" CLASS "B" STORM SEWERS U.P.O.R.A. SEC. M-6.6(b) OR SEC. M-6.8(b)
I-2	807	L.F.	33" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES
I-2	205	L.F.	33" CLASS "B" STORM SEWERS U.P.O.R.A. SEC. M-6.6(c)
I-2	354	L.F.	33" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES M-6.6(d)
I-2	363	L.F.	36" CLASS "B" STORM SEWERS U.P.O.R.A. SEC. M-6.6(b) OR SEC. M-6.8(b)
I-2	286	L.F.	36" CLASS "B" STORM SEWERS U.P.O.R.A. SEC. M-6.6(d)
I-2	228	L.F.	12" CLASS "B" STORM SEWERS
I-2	191	L.F.	15" CLASS "B" STORM SEWERS
I-2	63	L.F.	12" CLASS "A" STORM SEWERS M-6.5(a) & M-6.8(a)
I-2	228	L.F.	12" CLASS "A" STORM SEWERS M-6.4c
I-2	162	L.F.	18" CLASS "A" STORM SEWERS M-6.4c
I-2	125	L.F.	15" CLASS "A" STORM SEWERS
I-2	704	L.F.	18" CLASS "B" STORM SEWERS UNDER PAVEMENT & APPROACHES M-6.6d
I-2	60	L.F.	10" STORM SEWER UNDER PAVEMENT & APPROACHES M-6.8b
I-2	1032	L.F.	12" STORM SEWER UNDER PAVEMENT & APPROACHES M-6.8b
I-2	49	L.F.	8" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6b
I-2	1380	L.F.	12" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.8b
I-2	705	L.F.	15" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.8b
I-2	313	L.F.	15" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6d
I-2	51	L.F.	18" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.8b
I-2	482	L.F.	18" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6d
I-2	270	L.F.	21" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6d
I-2	65	L.F.	24" COMBINATION * SEWERS U.P.O.R.A. SEC. M-6.8(b) OR SEC. M-6.6b
I-2	783	L.F.	24" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6d
I-2	455	L.F.	27" COMBINATION * SEWERS U.P.O.R.A. SEC. M-6.8(b) OR SEC. M-6.6b
I-2	30	L.F.	27" COMBINATION * SEWERS UNDER PAVEMENT & APPROACHES M-6.6b CONCRETE ENCASED

* AS PER PLAN

Rev. 11-23-07 REC

QUANTITY SUMMARY
DRAINAGE

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

26
492

PARTICIPATING FUNDS / NON-PARTICIPATING FUNDS

ITEM	9	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	74	76	86			SUB-TOTAL ITEM	SUB-TOTAL QUANTITY	SUB-TOTAL UNIT	DESCRIPTION
I-2																															308	308		I-2	308	L.F.	27" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 c *
I-2																															132	132		I-2	132	L.F.	27" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 c * CONCRETE ENCASED
I-2																															275	275		I-2	275	L.F.	27" COMBINATION SEWERS M-6-6 c *
I-2																																		I-2		L.F.	30" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 b *
I-2																																		I-2		L.F.	30" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d *
I-2																															24	24		I-2	24	L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 b * RADIUS PIPE
I-2																																		I-2		L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 b *
I-2																																				L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 b *
I-2																																		I-2		L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d *
I-2																																		I-2		L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d * CONCRETE ENCASED
I-2																																					
I-2																																		I-2		L.F.	48" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 b *
I-2																																		I-2		L.F.	48" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 c *
I-2																																		I-2		L.F.	48" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d *
I-2																																		I-2		L.F.	48" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 d * CONCRETE ENCASED
I-2																																					
I-2																																		I-2		L.F.	54" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-106.6(d) * CONCRETE ENCASED
I-4		570	2782	2057	1616	772	2548	2340	1901	1648	986	1746	983	1435	1566	1001	883	1633	1031	1127	976	707	1812	862	2230	888	1216	1178	302			38886		I-4	38886	L.F.	6" UNDERDRAINS
I-4		60	40	50	50	30	30	60	40	42	10	30	60	10	20	30	10	10	10	20	20	10		10	20	10		28	10			720		I-4	720	L.F.	8" PIPE OUTLETS FOR UNDERDRAINS M-6.4 a
I-5		1	2	3		2	1	2	1	7			3	1	3	3	3	1	2	4	2	3	2	2	1	1	2	2	1			55		I-5	55	EACH	6" PIPE SPECIALS FOR UNDERDRAINS
I-5											20																					20		I-5	20	EACH	8" PIPE SPECIALS FOR STORM SEWER
I-5						1																				1						2		I-5	2	EACH	12" PIPE SPECIALS FOR STORM SEWER
I-5					2			2		2																						6		I-5	6	EACH	12" PIPE SPECIALS M-6.4 a FOR STORM SEWER
I-5											3																					3		I-5	3	EACH	15" PIPE SPECIALS FOR STORM SEWER
I-5											22																					22		I-5	22	EACH	18" PIPE SPECIALS FOR STORM SEWER
I-5						2																										2		I-5	2	EACH	18" PIPE SPECIALS M-6.4 a FOR STORM SEWER
I-5																																		I-5		EACH	24" PIPE SPECIALS FOR STORM SEWER
I-5			1																													1		I-5	1	EACH	33" PIPE SPECIALS FOR STORM SEWER
I-5																																		I-5		EACH	48" PIPE SPECIALS FOR STORM SEWER
I-8																							4									4		I-8	4	EACH	MANHOLES ADJUSTED TO GRADE
I-8	10																															10		I-8	10	EACH	YOUNGSTOWN MANHOLE COVER FURNISHED & PLACED AS PER PLAN
I-8		3	2	1		2	2	2	3	4	2	2	3			1										1	1		1			30		I-8	30	EACH	ST'D. NUMBER 1 MANHOLE
I-8			1							1			1																		3		I-8	3	EACH	ST'D. NUMBER 2 MANHOLE WITHOUT DROP PIPE
I-8		4	3	1		3	2	2	2	4	3	2	2			1								4	2	1	3	1		2	(41) ~~42~~	1	I-8	42	EACH	ST'D. NUMBER 2-2A CATCH BASIN
I-8		1																														1		I-8	1	EACH	ST'D. NUMBER 4 CATCH BASIN
I-8						1	2		2		1															2		1				9		I-8	9	EACH	ST'D. NUMBER 6 CATCH BASIN
I-8		1	1	2	2	1	1			2			1												1							12		I-8	12	EACH	ST'D. NUMBER 2A-6 PAVED SHOULDER INLET

* As per plan

Rev. 11-23-60 NEC

QUANTITY SUMMARY
DRAINAGE

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

27
492

TYPE CODE 7221

ITEM	87	90	93	97	06	08	09	101	227	232	235	236	244	251	263	275	288	292	297	302	SUB-TOTAL FROM SHEET 26	PARTICIPATING FUNDS	NON-PARTICIPATING FUNDS	BID ITEM	BID QUANTITY	BID UNIT	DESCRIPTION
I-2																					308			I-2	308 ✓	L.F.	27" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES, M-6.6c *
I-2																					132			I-2	132 ✓	L.F.	27" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6 c * [CONCRETE ENCASED]
I-2																					275			I-2	275 ✓	L.F.	27" COMBINATION SEWERS, M-6.6 c *
I-2		50																				50		I-2	50 ✓	L.F.	30" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6b *
I-2		297																				297		I-2	297 ✓	L.F.	30" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6c *
I-2																					24			I-2	24 ✓	L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES (RADIUS PIPE) M-6.6 b *
I-2	525																					525		I-2	525 ✓	L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6b *
I-2		295																				295		I-2	295 ✓	L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6c *
I-2	763																					763		I-2	763 ✓	L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6d *
I-2	62																					62		I-2	62 ✓	L.F.	33" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6d * [CONCRETE ENCASED]
I-2			1118					32														1150		I-2	1150 ✓	L.F.	48" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6b *
I-2			57					38														95		I-2	95 ✓	L.F.	48" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6c *
I-2			200					703														903		I-2	903 ✓	L.F.	48" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6d *
I-2						377																377		I-2	377 ✓	L.F.	54" COMBINATION SEWERS UNDER PAVEMENT & APPROACHES M-6.6.d * [CONCRETE ENCASED]
I-2															175								175	I-2	175 ✓	L.F.	15" STORM SEWER UNDER PAVEMENT & APPROACHES M-6.8(b)
I-2															326								326	I-2	326 ✓	L.F.	21" STORM SEWER UNDER PAVEMENT & APPROACHES M-6.8(b)
I-4												16									38,886		16	I-4	38,902 ✓	L.F.	6" UNDERDRAINS
I-4												10									720		10	I-4	730 ✓	L.F.	8" PIPE OUTLETS FOR UNDERDRAINS M-6.4a
I-5																					55			I-5	55 ✓	EACH	6" PIPE SPECIALS FOR UNDERDRAINS
I-5			1			2															20	3		I-5	23 ✓	EACH	8" PIPE SPECIALS FOR STORM SEWERS
I-5		2		1																	2	3		I-5	5 ✓	EACH	12" PIPE SPECIALS FOR STORM SEWERS
I-5																					6			I-5	6 ✓	EACH	12" PIPE SPECIALS M-6.4a FOR STORM SEWERS
I-5			1			2															3	3		I-5	6 ✓	EACH	15" PIPE SPECIALS FOR STORM SEWERS
I-5			3					2													22	5		I-5	27 ✓	EACH	18" PIPE SPECIALS FOR STORM SEWERS
I-5																					2			I-5	2 ✓	EACH	18" PIPE SPECIALS M-6.4a FOR STORM SEWERS
I-5		2																			0	2		I-5	2 ✓	EACH	24" PIPE SPECIALS FOR STORM SEWERS
I-5																					1			I-5	1 ✓	EACH	33" PIPE SPECIALS FOR STORM SEWERS
I-5			3					2													0	5		I-5	5 ✓	EACH	48" PIPE SPECIALS FOR STORM SEWERS
P. I-8																					4			I-8	45 ✓	EACH	MANHOLES ADJUSTED TO GRADE
N.P. I-8									2	2	2	6		3	2	8	4		4	2			41				
I-8																					10			I-8	10 ✓	EACH	YOUNGSTOWN MANHOLE COVER FURNISHED & PLACED AS PER PLAN
P. I-8																		1			30	1		I-8	39 ✓	EACH	ST'D. NUMBER 1 MANHOLES
N.P. I-8										2					4	2							8				
I-8															1			1			3	1	1	I-8	5 ✓	EACH	ST'D. NUMBER 2 MANHOLES WITHOUT DROP PIPE
P. I-8																		1			42	1		I-8	48 ✓	EACH	ST'D. NUMBER 2-2A CATCH BASINS
N.P. I-8													3	2									5				
I-8																					1			I-8	1 ✓	EACH	ST'D. NUMBER 4 CATCH BASIN
I-8																					9			I-8	9 ✓	EACH	ST'D. NUMBER 6 CATCH BASINS
I-8																					12			I-8	12 ✓	EACH	ST'D. NUMBER 2A-6 PAVED SHOULDER INLETS

* As per plan

QUANTITY SUMMARY
DRAINAGE

FED.RD.	STATE	PROJECT	
2	OHIO		

28
492

MAH-18-17.20

ITEM	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	53	54	55	56	57	58	59	60	61	62	76	84	85	116	PARTICIPATING FUNDS	NONPARTICIPATING FUNDS	SUB-TOTAL ITEM	SUB-TOTAL QUANTITY	SUB-TOTAL UNIT	DESCRIPTION
I-8				2	1				1		2	1											2							5			I-8	5	EACH	ST'D. NUMBER 2A-8 PAVED SHOULDER INLET
I-8	1		1					2																						4			I-8	4	EACH	ST'D. NUMBER 2A-10 PAVED SHOULDER INLET
I-8										1	1																			2			I-8	2	EACH	ST'D. NUMBER 2A-12 PAVED SHOULDER INLET
I-8																						1								1			I-8	1	EACH	ST'D. NUMBER 2A-16 PAVED SHOULDER INLET
I-8			1														1													2			I-8	2	EACH	ST'D. NUMBER 2-4 CATCH BASIN
I-8						1	1																							2			I-8	2	EACH	NUMBER 2-6 MEDIAN INLET MODIFIED AS PER PLAN
I-8		1					1			1																				3			I-8	3	EACH	NUMBER 2-8 MEDIAN INLET MODIFIED AS PER PLAN
I-8															2			3												5			I-8	5	EACH	CITY OF YOUNGSTOWN TYPE-1 INLET
I-8																			1	1	2	2	2	1	1	2				12			I-8	12	EACH	CITY OF YOUNGSTOWN TYPE-2 INLET
I-8																												6		6			I-8	6	EACH	CITY OF YOUNGSTOWN TYPE-YA MANHOLE
I-8																																	I-8		EACH	CITY OF YOUNGSTOWN TYPE-YB MANHOLE
I-8																																	I-8		EACH	CITY OF YOUNGSTOWN TYPE-YC MANHOLE
I-8																																	I-8		EACH	CITY OF YOUNGSTOWN TYPE-YD MANHOLE
I-8																																	I-8		EACH	SPECIAL SEWAGE REGULATOR CHAMBER-AS PER PLAN
																																	I-8		EACH	CITY OF YOUNGSTOWN TYPE-YA MANHOLE (MODIFIED)
SPECIAL																																	SPECIAL		LUMP	SPECIAL- JUNCTION CHAMBER, AS PER PLAN
I-10	58	273	23	65	41		1	38								71					79								(650) ~~653~~	3		I-10	653	C.Y.	DUMPED ROCK CHANNEL PROTECTION
I-14	65		145	250				52	240	900			27	255							44	213	403	238	353	250	450			3329			I-14	3329	L.F.	ST'D. PAVED GUTTER TYPE-1
I-14			42																											42			I-14	42	L.F.	ST'D. PAVED GUTTER TYPE-2
I-14	30	40	30		40	20	20	20	60	40	40	40			30							60	20	20	40	20	20			590			I-14	590	L.F.	PAVED GUTTER-TYPE-1 MODIFIED, AS PER PLAN
I-16																												5	2	7			I-16	7	EACH	MANHOLES ABANDONED
I-16																					2							4		6			I-16	6	EACH	INLETS ABANDONED
S-1			2.3	1.8	0.8		0.3										0.8													(5.5) ~~5.8~~	0.3		S-1	5.8	C.Y.	CLASS "E" CONCRETE FOR STRUCTURES
S-4																														60.7	60.7		S-1	60.7	C.Y.	CLASS "C" CONCRETE FOR STRUCTURES
S-24																														7420	7420		S-4	7420	LB'S.	REINFORCING STEEL
																																	S-24			REMOVAL OF EXISTING HEADWALL
S-27			252																											252			S-27	252	L.F.	42" PIPE FOR ROADWAY CULVERT M-6.4 d 10 GA. OR M-6.6 (d)
S-27																	133															133	S-27	133	L.F.	42" PIPE FOR ROADWAY CULVERT M-6.6 b & M-6.4 d 12 GA.
S-27																	261													261			S-27	261	L.F.	42" PIPE FOR ROADWAY CULVERT M-6.4 d 8 GA.

Rev-11-23-07 RE

QUANTITY SUMMARY
DRAINAGE

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

29
492

TYPE CODE 7221

	ITEM	SUB-TOTAL FROM SHEET 28	86	87	90	92	93	94	96	98	99	101	103	112	114	120	227	232	235	236	244	249	250	251	263	275	288	292	97	297	302	PARTICIPATING FUNDS	NON-PARTICIPATING FUNDS	BID ITEM	BID QUANTITY	BID UNIT	DESCRIPTION
	I-8	9																																I-8	9	EACH	ST'D. NUMBER 2A-8 PAVED SHOULDER INLET
	I-8	4																																I-8	4	EACH	ST'D. NUMBER 2A-10 PAVED SHOULDER INLET
	I-8	2																																I-8	2	EACH	ST'D. NUMBER 2A-12 PAVED SHOULDER INLET
	I-8	1																																I-8	1	EACH	ST'D. NUMBER 2A-16 PAVED SHOULDER INLET
	I-8	2																																I-8	2	EACH	ST'D. NUMBER 2-4 CATCH BASIN
	I-8	2																																I-8	2	EACH	ST'D NUMBER 2-6 MEDIAN INLET MODIFIED AS PER PLAN
	I-8	3																																I-8	3	EACH	ST'D NUMBER 2-8 MEDIAN INLET MODIFIED AS PER PLAN
P.	I-8	5							3									2		7				2	8						3	19	I-8	27	EACH	CITY OF YOUNGSTOWN TYPE-1 INLET
N.P.	I-8																																				
P.	I-8	12							3																			4			7	61	I-8	80	EACH	CITY OF YOUNGSTOWN TYPE-2 INLET
N.P.	I-8																6	4	1	7				9		13	6			6	9						
	I-8	6	2	6	9				2		6		2																			27		I-8	33	EACH	CITY OF YOUNGSTOWN TYPE-YA MANHOLE
	I-8	0					5			1		5																			11		I-8	11	EACH	CITY OF YOUNGSTOWN TYPE-YB MANHOLE
	I-8	0									2																				2		I-8	2	EACH	CITY OF YOUNGSTOWN TYPE-YC MANHOLE
	I-8	0			2		3					3																1			8		I-8	8	EACH	CITY OF YOUNGSTOWN TYPE-YD MANHOLE
	I-8	0	1																												1		I-8	1	EACH	SPECIAL SEWAGE REGULATOR CHAMBER
	I-8			1																											1		I-8	1	EACH	CITY OF YOUNGSTOWN TYPE YA MANHOLE (MODIFIED)
	SPECIAL	0		LUMP																											LUMP		SPECIAL	LUMP	LUMP	MANHOLE EXTENSION, AS PER PLAN
	SPECIAL	0										LUMP																			LUMP		SPECIAL	LUMP	LUMP	SPECIAL- JUNCTION CHAMBER, AS PER PLAN
	I-10	653												12	40	35															87		I-10	740	C.Y.	DUMPED ROCK CHANNEL PROTECTION
P.	I-14	3823																																I-14	5899	L.F.	ST'D. PAVED GUTTER TYPE-1
N.P.	I-14																				1214	76	680									1,970					
	I-14	42																																I-14	42	L.F.	ST'D. PAVED GUTTER TYPE-2
P.	I-14	580																									10				10			I-14	650	L.F.	ST'D PAVED GUTTER - TYPE-1 MODIFIED, AS PER PLAN
N.P.	I-14																				30		20									50					
	I-16	7	6	9	4	1	1	2	1	2	3	1	2															2			34		I-16	47	EACH	MANHOLES ABANDONED
P.	I-16	6					2	4		2	6	2	2															4		6	22	6	I-16	76	EACH	INLETS ABANDONED
N.P.	I-16																	1	1	7				15	3	11	5			5		48					
P.	S-1	5.8												1.0	0.8	0.8															2.6		S-1	8.7	C.Y.	CLASS "E" CONCRETE FOR STRUCTURES
N.P.	S-1																				0.3											0.3					
	S-4	7420																																S-4	7420	LB'S.	REINFORCING STEEL
	S-24		LUMP																												LUMP		S-24	LUMP	LUMP	REMOVAL OF EXISTING HEADWALL
	S-24			LUMP																												LUMP	S-24	LUMP	LUMP	REMOVAL OF EXISTING 4'x4' CONCRETE BOX CULVERT
	S-27													408																	228	408 180	S-27	408	L.F.	18" PIPE FOR ROADWAY CULVERTS M-6.6 (a)
	S-27														152																	152	S-27	152	L.F.	24" PIPE FOR ROADWAY CULVERTS M-6.6 (c)
	S-27	252																															S-27	252	L.F.	42" PIPE FOR ROADWAY CULVERTS M-6.4 (d) 10 GA. or M-6.6 (d)
	S-27 *	133																															S-27	133	L.F.	42" PIPE FOR ROADWAY CULVERTS M-6.6 (b) M-6.4 (d) 12-GA.
	S-27	261																															S-27	261	L.F.	42" PIPE FOR ROADWAY CULVERTS M-6.4 (d) 8-GA.
	S-27															247															247		S-27	247	L.F.	24" PIPE FOR ROADWAY CULVERTS M-6.6 (d)
	S-1	60.7																															S-1	60.7	C.Y.	CLASS "C" CONCRETE FOR STRUCTURES

* NON-PARTICIPATING

Rev. 11-23-66

QUANTITY SUMMARY
WATER LINES

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH - 18 - 17.20

30
492

TYPE CODE 7221

ITEM	84	85	87	90	92	94	97	98	99	101	103	232	251	96	PARTICIPATING FUNDS	NON-PARTICIPATING FUNDS	BID ITEM	BID QUANTITY	BID UNIT	DESCRIPTION
																				~MAHONING VALLEY SANITARY DISTRICT RELOCATION~
E-12		376	1330	214											1920		E-12	1920	L.F.	42" PIPE REMOVAL - STEEL
I-124		988	494	340											1822		I-124	1822	L.F.	42" NEW WATER MAIN C 201 OR C 301
I-124		338	716												1054		I-124	1054	L.F.	42" NEW WATER MAIN C 201 OR C 301 CONCRETE ENCASED
I-124		300	10	35											345		I-124	345	L.F.	8" NEW WATER MAIN CL 23
I-124		1													1		I-124	1	EA.	8" FITTINGS CL 250
I-8		2	3												5		I-8	5	EA.	MVSD ACCESS MANHOLE - SPECIAL AS PER PLAN
I-8			1												1		I-8	1	EA.	MVSD AIRVALVE MANHOLE
I-8			1												1		I-8	1	EA.	MVSD BLOWOFF MANHOLE
I-8		1	1	1											3		I-8	3	EA.	MVSD BLOWOFF SETTING - SPECIAL AS PER PLAN
I-8		1													1		I-8	1	EA.	MVSD COMBINATION AIRVALVE & ACCESS MANHOLE - SPECIAL AS PER PLAN
I-16			2												2		I-16	2	EA.	ACCESS MANHOLE ABANDONED
I-16			1												1		I-16	1	EA.	AIRVALVE & MANHOLE ABANDONED
I-16			1												1		I-16	1	EA.	BLOWOFF & MANHOLE ABANDONED
																				~CITY OF YOUNGSTOWN WATER LINES~
E-12	267			427		350										1044	E-12	1044	L.F.	12" TO 36" PIPE REMOVED FOR STORAGE - CAST IRON
E-12						253										253	E-12	253	L.F.	36" PIPE REMOVED FOR STORAGE - PRESTRESSED CONCRETE
E-12	1					2	3	3	2	1	2					14	E-12	14	EA.	FIRE HYDRANT REMOVED FOR STORAGE
E-12	1					300	3	3	3	3	1	2		1	300	17	E-12	300	L.F.	12" TO 36" PIPE REMOVED
														186	186		I-124	186	L.F.	VALVES REMOVED FOR REUSE OR STORAGE
I-124	20				362	26	23	35	112	66	45			135	824		I-124	824	L.F.	4" NEW WATER MAIN CL 22
I-124									297						297		I-124	297	L.F.	6" NEW WATER MAIN CL 22
I-124								990							990		I-124	990	L.F.	6" NEW WATER MAIN CL 22 CONCRETE ENCASED
I-124				174					234						408		I-124	408	L.F.	8" NEW WATER MAIN CL 23
I-124				295					166						461		I-124	461	L.F.	8" NEW WATER MAIN CL 23 CONCRETE ENCASED
I-124	104														104		I-124	104	L.F.	12" NEW WATER MAIN CL 23
I-124	240														240		I-124	240	L.F.	12" NEW WATER MAIN CL 23 CONCRETE ENCASED
I-124				174		19									193		I-124	193	L.F.	16" NEW WATER MAIN CL 25
I-124				296		373									669		I-124	669	L.F.	16" NEW WATER MAIN CL 25 CONCRETE ENCASED
I-124						16									16		I-124	16	L.F.	30" NEW WATER MAIN CL 26
I-124						62									62		I-124	62	L.F	30" NEW WATER MAIN CL 26 CONCRETE ENCASED
I-124						11									11		I-124	11	L.F.	36" NEW WATER MAIN C 301
I-124						249									249		I-124	249	L.F.	36" NEW WATER MAIN C 301 CONCRETE ENCASED
P. I-124											1	5			6		I-124	6	EA.	FIRE HYDRANTS - REMOVE & RESET
N.P. I-124														1	1		I-124	1	EA.	2" VALVE & BOX CL 150
I-124	2					2	2	1	3	2	4			2	18		I-124	18	EA.	FIREHYDRANTS
I-124	2				1	2	2	3	5	2	4			1	1		I-124	1	EA.	4" VALVES & BOXES CL 150
I-124				2										3	24		I-124	24	EA.	6" VALVES & BOXES CL 150
I-124	1														2		I-124	2	EA.	16" VALVES & BOXES CL 150
I-124				1				1	1						1		I-124	1	EA.	12" VALVES & BOXES CL 150
I-124															3		I-124	3	EA.	8" VALVES & BOXES CL 150
I-124																	I-124		EA.	30" VALVES & BOXES CL 150
I-124						1									1		I-124	1	EA.	30" VALVES & BOXES CL 200

QUANTITY SUMMARY
WATER LINES

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH - 18 - 17.20

31
492

PARTICIPATING FUNDS / NON PARTICIPATING FUNDS

TYPE CODE 7221

ITEM	84	90	92	93	94	97	98	99	101	103	227	251	275	96	PARTICIPATING	NON PARTICIPATING
														2	2	
I-124	2		3		2	2	3	13		4				6	35	
I-124		9					13	11	4						37	
I-124	8														8	
I-124		9			4										13	
I-124					3										3	
I-124					3										3	
I-124				2	2	1	1							2	8	
I-124					87										87	
I-124					300										300	
I-124					328										328	
P. I-124	1														1	
N.P. I-124											1	7	12			20
SPECIAL					LUMP										LUMP	
P. I-124																
N.P. I-124												686				686
I-8					1										1	
SPECIAL															LUMP	LUMP


BID ITEM	QUANTITY	UNIT	DESCRIPTION
			CITY OF YOUNGSTOWN WATER LINES (CONTINUED)
I-124	2	EACH	4" FITTINGS CL 250
I-124	35	EACH	6" FITTINGS CL 250
I-124	37	EACH	8" FITTINGS CL 250
I-124	8	EACH	12" FITTINGS CL 250
I-124	13	EACH	16" FITTINGS CL 150
I-124	3	EACH	30" FITTINGS CL 150
I-124	3	EACH	36" FITTINGS CL 301
I-124	8	EACH	CUT & PLUG EXISTING WATER MAIN
I-124	87	L.F.	CONCRETE ENCASEMENT OF EXISTING 16" WATER MAIN AS PER PLAN
I-124	300	L.F.	CONCRETE ENCASEMENT OF EXISTING 30" WATER MAIN AS PER PLAN
I-124	328	L.F.	CONCRETE ENCASEMENT OF EXISTING 36" WATER MAIN AS PER PLAN
I-124	21	EACH	VALVE BOX ADJUSTED TO GRADE
SPECIAL	LUMP	LUMP	VALVE BOX - AS PER PLAN
I-124	686	L.F.	LOWERING WATER LINE AS PER PLAN
I-8	1	EACH	MANHOLES ADJUSTED TO GRADE
SPECIAL	LUMP	LUMP	CONSTRUCTION LAYOUT STAKES.

STRUCTURES OVER 20' SPAN


MAH-18-1761	STEEL ST.	OVER S.R.18	SEE SHEET NO. 333
MAH-18-1776	RAMP "C"	" "	" " 341
MAH-18-1815	MAHONING AVE.	" "	" " 340
MAH-18-1823	S.R.18	OVER PRICE RD.	" " 361
MAH-18-1835	GLENWOOD	OVER S.R.18	" " 383
MAH-18-1855	S.R.18	" EDWARDS	" " 395
MAH-18-1904	" "	" OAK HILL	" " 413
MAH-18-1923	" "	"	" " 418
MAH-18-1934	RIDGE RD.	" S.R.18	" " 425
MAH-18-1941	W. WOODLAND AVE.	" "	" " 439
MAH-18-1950	MARKET ST.	" " "	" " 456

FED. RD.	STATE	PROJECT	
2	OHIO		


MAH - 18 - 17.20



LEFT LANE



RIGHT LANE



LEFT LANE RIGHT LANE

SUPERELEVATION TABLE
CURVE Nº 2
Δ = 54° 44' 10" RT.


℄ STATION	LEFT LANE			PROFILE GRADE	RIGHT LANE		
	LEFT EDGE	℄	RIGHT EDGE		LEFT EDGE	℄	RIGHT EDGE
935+88.24				900.28	900.49	900.68	900.49
936+00				899.94	900.12	900.31	900.12
936+25				899.23	899.35	899.54	899.35
936+40.32				898.79	898.87	899.06	898.87
936+50				898.51	898.58	898.75	898.56
936+72.31	898.08	898.27	898.08	897.87			
936+75	898.02	898.20	898.01	897.80	897.85	897.98	897.79
937+00	897.36	897.48	897.29	897.08	897.11	897.20	897.01
937+25	896.72	896.77	896.58	896.37	896.39	896.42	896.23
937+46.56	896.15	896.15	895.96	895.75	895.75	895.75	895.56
937+50	896.07	896.05	895.86	895.65	895.65	895.63	895.44
937+75	895.48	895.34	895.15	894.94	894.89	894.78	894.59
937+83.67	895.27	895.09	894.90	894.69			
937+94.22				894.39	894.31	894.12	893.94
938+00	894.89	894.66	894.43	894.22	894.14	893.94	893.74
938+25	894.30	894.01	893.72	893.51	893.41	893.15	892.89
938+50	893.71	893.35	893.00	892.79	892.66	892.34	892.03
938+75	893.13	892.70	892.29	892.08	891.92	891.55	891.18
939+00	892.54	892.05	891.57	891.36	891.18	890.75	890.32
939+07.38	892.36	891.86	891.36	891.15			
939+25	891.96	891.42	890.88	890.65	890.45	889.96	889.47
939+29.73				890.51	890.31	889.80	889.30
939+50	891.36	890.77	890.18	889.93	889.70	889.16	888.61
939+75	890.77	890.13	889.49	889.22	888.97	888.37	887.76
940+00	890.18	889.48	888.79	888.50	888.22	887.56	886.90
940+25	889.60	888.84	888.10	887.79	887.49	886.77	886.05
940+50	889.00	888.20	887.40	887.07	886.75	885.97	885.19
940+75	888.42	887.57	886.71	886.36	886.01	885.18	884.34
941+00	887.83	886.93	886.02	885.64	885.27	884.38	883.48
941+25	887.25	886.30	885.33	884.93	884.53	883.59	882.65
941+46.56	886.73	885.73	884.73	884.31	883.89	882.89	881.89
941+50	886.63	885.60	884.63	884.21	883.79	882.79	881.79
941+75	885.93	884.93	883.93	883.51	883.09	882.09	881.09
942+00	885.28	884.28	883.28	882.86	882.44	881.44	880.44
942+25	884.63	883.63	882.63	882.21	881.79	880.79	879.79
942+50	884.01	883.01	882.01	881.59	881.17	880.17	879.17
942+75	883.41	882.41	881.41	880.99	880.57	879.57	878.57
943+00	882.85	881.85	880.85	880.43	880.01	879.01	878.01
943+25	882.29	881.29	880.29	879.87	879.45	878.45	877.45
943+50	881.77	880.77	879.77	879.35	878.93	877.93	876.93
943+75	881.27	880.27	879.27	878.85	878.43	877.43	876.43
944+00	880.79	879.79	878.79	878.37	877.95	876.95	875.95
944+25	880.34	879.34	878.34	877.92	877.50	876.50	875.50
944+50	879.91	878.91	877.91	877.49	877.07	876.07	875.07
944+75	879.50	878.50	877.50	877.08	876.66	875.66	874.66

℄ STATION	LEFT LANE			PROFILE GRADE	RIGHT LANE		
	LEFT EDGE	℄	RIGHT EDGE		LEFT EDGE	℄	RIGHT EDGE
945+00	879.12	878.12	877.12	876.70	876.28	875.28	874.28
945+25	878.76	877.76	876.76	876.34	875.92	874.92	873.92
945+50	878.43	877.43	876.43	876.01	875.59	874.59	873.59
945+75	878.11	877.11	876.11	875.69	875.27	874.27	873.27
946+00	877.83	876.83	875.83	875.41	874.99	873.99	872.99
946+25	877.57	876.57	875.57	875.15	874.73	873.73	872.73
946+50	877.33	876.33	875.33	874.91	874.49	873.49	872.49
946+75	877.11	876.11	875.11	874.69	874.27	873.27	872.27
947+00	876.92	875.92	874.92	874.50	874.08	873.08	872.08
947+25	876.76	875.76	874.76	874.34	873.92	872.92	871.92
947+41.76	876.61	875.65	874.65	874.23	873.81	872.89	871.81
947+50	876.54	875.58	874.60	874.19	873.78	872.84	871.91
947+75	876.31	875.39	874.46	874.07	873.69	872.76	871.84
948+00	876.09	875.22	874.34	873.97	873.61	872.74	871.88
948+25	87 .89	875.07	874.24	873.90	873.56	872.76	871.95
948+50	875.72	874.94	874.17	873.85	873.54	872.79	872.04
948+75	875.56	874.84	874.12	873.82	873.53	872.84	872.15
949+00	875.54	874.77	874.10	873.82	873.56	872.92	872.29
949+25	875.33	874.72	874.10	873.84	873.60	873.03	872.45
949+50	875.25	874.68	874.12	873.88	873.66	873.15	872.63
949+58.59				873.90	873.69	873.19	872.69
949+75	875.20	874.69	874.18	873.96	873.77	873.31	872.85
949+80.94	875.18	874.68	874.18	873.97			
950+00	875.16	874.71	874.26	874.05	873.88	873.48	873.07
950+25	875.15	874.77	874.38	874.17	874.03	873.68	873.33
950+50	875.16	874.83	874.51	874.30	874.18	873.89	873.60
950+75	875.21	874.94	874.68	874.47	874.37	874.14	873.91
950+94.10				874.61	874.53	874.34	874.16
951+00	875.26	875.06	874.86	874.65	874.58	874.42	874.23
951+04.65	875.28	875.09	874.90	874.69			
951+25	875.35	875.27	875.08	874.87	874.84	874.78	874.59
951+41.76	875.47	875.42	875.23	875.02	875.02	875.02	874.83
951+50	875.48	875.50	875.31	875.10	875.11	875.12	874.93
951+75	875.66	875.74	875.55	875.34	875.36	875.43	875.24
952+00	875.82	875.97	875.78	875.57	875.61	875.72	875.53
952+16.01	875.93	876.12	875.93	875.72			
952+25				875.81	875.87	876.03	875.84
952+48				876.02	876.10	876.29	876.10
952+50				876.04	876.13	876.32	876.13
952+75				876.28	876.43	876.62	876.43
953+00				876.51	876.72	876.91	876.72
953+00.08				876.51	876.72	876.91	876.72

FED. RD.	STATE	PROJECT	
2	OHIO		

33
492

MAH - 18 - 17.20



SUPERELEVATION TABLE
CURVE Nº 3
Δ = 60°43'03" LT.


℄ STATION	LEFT LANE			PROFILE GRADE	RIGHT LANE		
	LEFT EDGE	℄	RIGHT EDGE		LEFT EDGE	℄	RIGHT EDGE
953+14.74	876.86	877.05	876.86	876.65			
953+25	876.92	877.11	876.92	876.74			
953+50	877.10	877.29	877.10	876.98			
953+66.82	877.22	877.41	877.22	877.14			
953+75	877.28	877.47	877.29	877.22			
953+98.81				877.44	877.65	877.84	877.65
954+00	877.45	877.64	877.51	877.45	877.66	877.85	877.66
954+25	877.61	877.80	877.72	877.68	877.89	878.08	877.96
954+50	877.79	877.98	877.94	877.92	878.13	878.32	878.26
954+73.06	877.95	878.14	878.14	878.14	878.35	878.54	878.54
954+75	877.96	878.15	878.16	878.16	878.37	878.56	878.57
955+00	878.05	878.24	878.35	878.39	878.60	878.79	878.92
955+10.17				878.49	878.70	878.89	879.07
955+20.72	878.13	878.31	878.50	878.58	878.79	879.00	879.21
955+25	878.15	878.34	878.54	878.62	878.83	879.05	879.27
955+50	878.25	878.50	878.75	878.86	879.07	879.35	879.64
955+75	878.35	878.65	878.97	879.10	879.31	879.65	880.01
956+00	878.44	878.80	879.17	879.33	879.54	879.95	880.37
956+25	878.53	878.95	879.38	879.56	879.77	880.24	880.73
956+33.88				879.65	879.86	880.36	880.86
956+50	878.63	879.11	879.60	879.80	880.02	880.55	881.09
956+56.23	878.65	879.15	879.65	879.86	880.09	880.63	881.18
956+75	878.72	879.26	879.80	880.03	880.27	880.86	881.44
957+00	878.81	879.42	880.02	880.27	880.54	881.18	881.81
957+25	878.91	879.57	880.22	880.50	880.79	881.49	882.17
957+50	879.01	879.72	880.44	880.74	881.05	881.80	882.54
957+75	879.11	879.88	880.66	880.98	881.31	882.11	882.90
958+00	879.20	880.03	880.86	881.21	881.56	882.41	883.26
958+25	879.29	880.18	881.07	881.44	881.81	882.72	883.61
958+50	879.39	880.34	881.28	881.68	882.08	883.03	883.98
958+73.06	879.48	880.48	881.48	881.90	882.32	883.32	884.32
958+75	879.50	880.50	881.50	881.92	882.34	883.34	884.34
959+00	879.73	880.73	881.73	882.15	882.57	883.57	884.57
959+25	879.96	880.96	881.96	882.38	882.80	883.80	884.80
959+50	880.20	881.20	882.20	882.62	883.04	884.04	885.04
959+75	880.44	881.44	882.44	882.86	883.28	884.28	885.28
960+00	880.67	881.67	882.67	883.09	883.51	884.51	885.51
960+25	880.90	881.90	882.90	883.32	883.74	884.74	885.74
960+50	881.14	882.14	883.14	883.56	883.98	884.98	885.98
960+75	881.38	882.38	883.38	883.80	884.22	885.22	886.22
961+00	881.61	882.61	883.61	884.03	884.45	885.45	886.45
961+25	881.84	882.84	883.84	884.26	884.68	885.68	886.68
961+50	882.08	883.08	884.08	884.50	884.92	885.92	886.92
961+75	882.32	883.32	884.32	884.74	885.16	886.16	887.16
962+00	882.55	883.55	884.55	884.97	885.39	886.39	887.39
962+25	882.78	883.78	884.78	885.20	885.62	886.62	887.62
962+50	883.02	884.02	885.02	885.44	885.86	886.86	887.86


℄ STATION	LEFT LANE			PROFILE GRADE	RIGHT LANE		
	LEFT EDGE	℄	RIGHT EDGE		LEFT EDGE	℄	RIGHT EDGE
962+75	883.26	884.26	885.26	885.68	886.10	887.10	888.10
963+00	883.49	884.49	885.49	885.91	886.33	887.33	888.33
963+25	883.72	884.72	885.72	886.14	886.56	887.56	888.56
963+50	883.96	884.96	885.96	886.38	886.80	887.80	888.80
963+75	884.20	885.20	886.20	886.62	887.04	888.04	889.04
964+00	884.43	885.43	886.43	886.85	887.27	888.27	889.27
964+25	884.66	885.66	886.66	887.08	887.50	886.50	889.50
964+50	884.90	885.90	886.90	887.32	887.74	888.74	889.74
964+75	885.14	886.14	887.14	887.56	887.98	888.98	889.98
965+00	885.37	886.37	887.37	887.79	888.22	889.22	890.22
965+25	885.60	886.60	887.60	888.02	888.44	889.44	890.44
965+50	885.84	886.84	887.84	888.26	888.68	889.68	890.68
965+75	886.08	887.08	888.08	888.50	888.92	889.92	890.92
965+77.01	886.09	887.09	888.09	888.51	888.93	889.93	890.93
966+00	886.47	887.40	888.33	888.73	889.13	890.08	891.03
966+25	886.81	887.70	888.59	888.96	889.33	890.23	891.13
966+50	887.19	888.02	888.85	889.20	889.55	890.40	891.25
966+75	887.57	888.34	889.12	889.44	889.77	890.56	891.36
967+00	887.94	888.65	889.37	889.67	889.98	890.72	891.47
967+25	888.31	888.97	889.62	889.90	890.19	890.88	891.57
967+50	888.69	889.29	889.89	890.14	890.41	891.05	891.68
967+75	889.07	889.61	890.15	890.38	890.62	891.21	891.79
967+93.84	889.34	889.84	890.34	890.55			
968+00	889.44	889.92	890.41	890.61	890.83	891.36	891.90
968+16.19				890.76	890.97	891.47	891.97
968+25	889.81	890.23	890.66	890.84	891.05	891.53	892.00
968+50	890.18	890.55	890.92	891.08	891.29	891.70	892.12
968+75	890.56	890.87	891.18	891.32	891.53	891.88	892.23
969+00	890.93	891.19	891.44	891.55	891.76	892.05	892.34
969+25	891.31	891.50	891.70	891.78	891.99	892.21	892.44
969+29.35	891.38	891.56	891.75	891.83	892.04	892.26	892.46
969+39.90				891.92	892.13	892.32	892.50
969+50	891.68	891.87	891.98	892.02	892.23	892.42	892.55
969+75	892.06	892.25	892.26	892.26	892.47	892.66	892.6
969+77.01	892.08	892.27	892.27	892.27	892.48	892.67	892.6
970+00	892.36	892.55	892.51	892.49	892.70	892.89	892.83
970+25	892.65	892.84	892.76	892.72	892.93	893.12	892.99
970+50	892.95	893.14	893.01	892.96	893.17	893.36	893.17
970+51.26				892.97	893.18	893.37	893.18
970+75	893.26	893.45	893.27	893.20			
970+83.25	893.35	893.54	893.35	893.27			
971+00	893.56	893.75	893.56	893.43			
971+25	893.84	894.03	893.84	893.66			
971+35.33	893.97	894.16	893.97	893.76			


FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

SUPERELEVATION TABLE
CURVE Nº 4
Δ = 74° 52' 50" RT.








℄ STATION	LEFT LANE			PROFILE GRADE	RIGHT LANE		
	LEFT EDGE	℄	RIGHT EDGE		LEFT EDGE	℄	RIGHT EDGE
985+17.17				903.11	903.32	903.51	903.32
985+25				902.99	903.18	903.37	903.18
985+50				902.58	902.71	902.89	902.71
985+69.25				902.23	902.31	902.50	902.31
985+75				902.12	902.19	902.37	902.18
986+00				901.61	901.67	901.80	901.61
986+01.24	901.79	901.98	901.79	901.58			
986+25	901.32	901.45	901.26	901.05	901.09	901.18	900.99
986+50	900.76	900.83	900.64	900.43	900.45	900.49	900.30
986+75	900.16	900.17	899.98	899.77	899.77	899.77	899.58
986+75.49	900.15	900.15	899.96	899.75	899.75	899.75	899.56
987+00	899.58	899.46	899.27	899.06	899.02	898.92	898.74
987+13.26	899.24	899.06	898.87	898.66			
987+22.43				898.36	898.28	898.09	897.91
987+25	898.95	898.73	898.51	898.30	898.22	898.02	897.83
987+50	898.30	898.02	897.74	897.53	897.42	897.17	896.92
987+75	897.65	897.31	896.97	896.76	896.63	896.32	896.01
988+00	897.00	896.60	896.20	895.99	895.84	895.47	895.10
988+25	896.36	895.89	895.43	895.22	895.04	894.62	894.19
988+39.17	895.99	895.49	894.99	894.78			
988+50	895.71	895.18	894.67	894.45	894.25	893.76	893.28
988+55.90				894.26	894.05	893.55	893.05
988+75	895.07	894.49	893.92	893.68	893.45	892.91	892.37
989+00	894.42	893.79	893.17	892.91	892.66	892.05	891.45
989+25	893.78	893.10	892.42	892.14	891.86	891.20	890.54
989+50	893.13	892.40	891.67	891.37	891.07	890.35	889.63
989+75	892.48	891.70	890.92	890.60	890.28	889.50	888.72
989+75.49	892.48	891.70	890.92	890.59	890.26	889.48	888.70
990+00	891.72	890.94	890.16	889.83	889.50	888.72	887.94
990+50	890.18	889.40	888.62	888.29	887.96	887.18	886.40
991+00	888.64	887.86	887.06	886.75	886.42	885.64	884.86
991+50	887.10	886.32	885.54	885.21	884.88	884.10	883.32
992+00	885.56	884.78	884.00	883.67	883.34	882.56	881.78
992+50	884.02	883.24	882.46	882.13	881.80	881.02	880.24
993+00	882.48	881.70	880.92	880.59	880.26	879.48	878.70
993+50	880.94	880.16	879.38	879.05	878.72	877.94	877.16
994+00	879.40	878.62	877.84	877.51	877.18	876.40	875.62
994+50	877.86	877.08	876.30	875.97	875.64	874.86	874.08
995+00	876.32	875.54	874.76	874.43	874.10	873.32	872.54
995+50	874.78	874.00	873.22	872.89	872.56	871.78	871.00
996+00	873.24	872.46	871.68	871.35	871.02	870.24	869.46
996+50	871.70	870.92	870.14	869.81	869.48	868.70	867.92
997+00	870.16	869.38	868.60	868.27	867.94	867.16	866.38
997+50	868.62	867.84	867.06	866.73	866.40	865.62	864.84
997+75	867.88	867.10	866.32	865.99	865.66	864.88	864.10
998+00	867.21	866.43	865.65	865.32	864.99	864.21	863.43
998+25	866.61	865.83	865.05	864.72	864.39	863.61	862.83
998+50	866.07	865.29	864.51	864.18	863.85	863.07	862.29
998+75	865.60	864.82	864.04	863.71	863.38	862.60	861.82
999+00	865.19	864.41	863.63	863.30	862.97	862.19	861.41
999+25	864.85	864.07	863.29	862.96	862.63	861.85	861.07
999+50	864.57	863.79	863.01	862.68	862.35	861.57	860.79
999+75	864.36	863.58	862.80	862.47	862.14	861.36	860.58
1000+00	864.22	863.44	862.66	862.33	862.00	861.22	860.44
1000+25	864.14	863.36	862.58	862.25	861.92	861.14	860.36
1000+50	864.14	863.36	862.58	862.25	861.92	861.14	860.36
1000+75	864.19	863.41	862.63	862.30	861.97	861.19	860.41
1000+00	864.31	863.53	862.75	862.42	862.09	861.31	860.53

℄ STATION	LEFT LANE			PROFILE GRADE	RIGHT LANE		
	LEFT EDGE	℄	RIGHT EDGE		LEFT EDGE	℄	RIGHT EDGE
1001+25	864.50	863.72	862.94	862.61	862.28	861.50	860.72
1001+50	864.75	863.97	863.19	862.86	862.53	861.75	860.97
1001+75	865.08	864.30	863.52	863.19	862.86	862.08	861.30
1002+00	865.46	864.68	863.90	863.57	863.24	862.46	861.68
1002+25	865.92	865.14	864.36	864.03	863.70	862.92	862.14
1002+50	866.52	865.74	864.96	864.63	864.30	863.52	862.74
1002+75	867.02	866.24	865.46	865.13	864.80	864.02	863.24
1003+00	867.66	866.88	866.10	865.77	865.44	864.66	863.88
1003+25	868.38	867.60	866.82	866.49	866.16	865.38	864.60
1003+50	869.16	868.38	867.60	867.27	866.94	866.16	865.38
1004+00	870.79	870.01	869.23	868.90	868.57	867.79	867.01
1004+50	872.42	871.64	870.86	870.53	870.20	869.42	868.64
1005+00	874.05	873.27	872.49	872.16	871.83	871.05	870.27
1005+50	875.68	874.90	874.12	873.79	873.46	872.68	871.90
1006+00	877.31	876.53	875.75	875.42	875.09	874.31	873.53
1006+50	878.94	878.16	877.38	877.05	876.72	875.94	875.16
1007+00	880.57	879.79	879.01	878.68	878.35	877.57	876.79
1007+50	882.20	881.42	880.64	880.31	879.98	879.20	878.42
1008+00	883.83	883.05	882.27	881.94	881.61	880.83	880.05
1008+50	885.46	884.68	883.90	883.57	883.24	882.46	881.68
1009+00	887.09	886.31	885.53	885.20	884.87	884.09	883.31
1009+50	888.72	887.94	887.16	886.83	886.50	885.72	884.94
1010+00	890.35	889.57	888.79	888.46	888.13	887.35	886.57
1010+50	891.98	891.20	890.42	890.09	889.76	888.98	888.20
1011+00	893.61	892.83	892.05	891.72	891.39	890.61	889.83
1011+50	895.24	894.46	893.68	893.35	893.02	892.24	891.46
1012+00	896.87	896.09	895.31	894.98	894.65	893.87	893.09
1012+50	898.50	897.72	896.94	896.61	896.28	895.50	894.72
1013+00	900.13	899.35	898.57	898.24	897.91	897.13	896.35
1013+50	901.76	900.98	900.20	899.87	899.54	898.76	897.98
1013+98.42	903.34	902.56	901.78	901.45	901.12	900.34	899.56
1014+00	903.38	902.60	901.82	901.50	901.18	900.41	899.63
1014+25	904.07	903.35	902.62	902.32	902.02	901.31	900.59
1014+50	904.76	904.08	903.41	903.13	902.86	902.20	901.54
1014+75	905.45	904.83	904.21	903.95	903.70	903.10	902.50
1015+00	906.14	905.57	905.00	904.76	904.53	903.99	903.45
1015+18.01				905.34	905.13	904.63	904.13
1015+25	906.83	906.32	905.80	905.58	905.38	904.89	904.41
1015+34.74	907.10	906.60	906.10	905.89			
1015+50	907.52	907.06	906.60	906.39	906.21	905.79	905.37
1015+75	908.21	907.82	907.42	907.21	907.06	906.69	906.33
1016+00	908.90	908.56	908.23	908.02	907.89	907.59	907.28
1016+25	909.60	909.32	909.05	908.84	908.74	908.49	908.24
1016+50	910.29	910.07	909.86	909.65	909.57	909.38	909.19
1016+51.48				909.67	909.59	909.40	909.22
1016+60.65	910.58	910.40	910.21	910.00			
1016+75	910.99	910.87	910.68	910.47	910.43	910.34	910.15
1016+98.42	911.63	911.63	911.44	911.23	911.23	911.23	911.04
1017+00	911.67	911.68	911.49	911.28	911.28	911.28	911.09
1017+25	912.43	912.50	912.31	912.10	912.12	912.17	911.98
1017+50	913.18	913.31	913.12	912.91	912.95	913.04	912.85
1017+72.67	913.86	914.05	913.86	913.65			
1017+75				913.73	913.78	913.92	913.73
1018+00				914.54	914.61	914.79	914.60
1018+04.66				914.69	914.77	914.96	914.77
1018+25				915.36	915.49	915.68	915.49
1018+50				916.17	916.36	916.55	916.36
1018+56.74				916.39	916.60	916.79	916.60

FED. RD.	STATE	PROJECT	
2	OHIO		

35
492

MAH - 18 - 17.20




LEFT LANE

NOTE:

INSERT SHORT VERTICAL CURVES WHERE NECESSARY

RIGHT LANE



LEFT LANE RIGHT LANE

SUPERELEVATION TABLE
CURVE Nº 5
Δ = 53° 49' 25" LT.

℄ STATION	LEFT LANE			PROFILE GRADE	RIGHT LANE		
	LEFT EDGE	℄	RIGHT EDGE		LEFT EDGE	℄	RIGHT EDGE
1019+97.06	921.17	921.36	921.17	920.96			
1020+00	921.26	921.35	921.26	921.06			
1020+25	922.02	922.21	922.02	921.88			
1020+49.14	922.74	922.93	922.74	922.66			
1020+50	922.76	922.95	922.77	922.69			
1020+75	923.52	923.71	923.57	923.51			
1020+81.13				923.70	923.91	924.10	923.91
1021+00	924.27	924.46	924.36	924.32	924.53	924.72	924.56
1021+25	925.03	925.21	925.16	925.14	925.35	925.54	925.44
1021+50	925.77	925.96	925.95	925.95	926.16	926.35	926.32
1021+55.38	925.94	926.13	926.13	926.13	926.34	926.53	926.53
1021+75	926.47	926.66	926.74	926.77	926.98	927.17	927.27
1021+92.49				927.34	927.55	927.74	927.92
1022+00	927.14	927.33	927.51	927.58	927.79	927.99	928.20
1022+03.04	927.23	927.41	927.60	927.68			
1022+25	927.81	928.05	928.28	928.38	928.59	928.86	929.12
1022+50	928.41	928.70	929.00	929.12	929.33	929.66	929.99
1022+75	928.96	930.56	929.67	929.82	930.03	930.43	930.82
1023+00	929.48	929.89	930.30	930.47	930.68	931.14	931.60
1023+16.20				930.87	931.08	931.58	932.08
1023+25	929.95	930.42	930.89	931.08	931.30	931.81	932.33
1023+38.55	930.17	930.67	931.17	931.38			
1023+50	930.36	930.89	931.41	931.63	931.87	932.44	933.01
1023+75	930.74	931.32	931.91	932.15	932.41	933.03	933.65
1024+00	931.06	931.70	932.34	932.61	932.89	933.57	934.24
1024+25	931.34	932.04	932.74	933.03	933.33	934.06	934.78
1024+50	931.56	932.31	933.07	933.39	933.71	934.49	935.27
1024+75	931.75	932.56	933.38	933.72	934.06	934.89	935.72
1025+00	931.89	932.76	933.64	934.00	934.37	935.25	936.13
1025+25	931.99	932.91	933.84	934.23	934.62	935.55	936.49
1025+50	932.0	933.02	934.00	934.41	934.82	935.81	936.80
1025+55.38	932.0	933.04	934.02	934.44	934.86	935.86	936.86
1025+75	932.13	933.13	934.13	934.55	934.97	935.97	936.97
1026+00	93 .22	933.22	934.22	934.64	935.06	936.06	937.06
1026+25	932.26	933.26	934.26	934.68	935.10	936.10	937.10
1026+50	932.26	933.26	934.26	934.68	935.10	936.10	937.10
1026+75	932.21	933.21	934.21	934.63	935.05	936.05	937.05
1027+00	932.12	933.12	934.12	934.54	934.96	935.96	936.96
1027+25	931.97	932.97	933.97	934.39	934.81	935.81	936.81
1027+50	931.78	932.78	933.78	934.20	934.62	935.62	936.62
1027+75	931.55	932.55	933.55	933.97	934.39	935.39	936.39
1028+00	931.27	932.27	933.27	933.69	934.11	935.11	936.11
1028+25	930.94	931.94	932.94	933.36	933.78	934.78	935.78
1028+50	930.56	931.56	932.56	932.98	933.40	934.40	935.40
1028+75	930.14	931.14	932.14	932.56	932.98	933.98	934.98

℄ STATION	LEFT LANE			PROFILE GRADE	RIGHT LANE		
	LEFT EDGE	℄	RIGHT EDGE		LEFT EDGE	℄	RIGHT EDGE
1029+00	929.67	930.67	931.67	932.09	932.51	933.51	934.51
1029+25	929.15	930.15	931.15	931.57	931.99	932.99	933.99
1029+50	928.59	929.59	930.59	931.01	931.43	932.43	933.43
1029+75	927.98	928.98	929.98	930.40	930.82	931.82	932.82
1030+00	927.32	928.32	929.32	929.74	930.16	931.16	932.16
1030+25	926.67	927.67	928.67	929.09	929.51	930.51	931.51
1030+50	926.08	927.08	928.08	928.50	928.92	929.92	930.92
1030+75	925.55	926.55	927.55	927.97	928.39	929.39	930.39
1030+91.44	925.27	926.25	927.23	927.65	928.07	929.07	930.07
1031+00	925.13	926.11	927.09	927.50	927.91	928.89	929.87
1031+25	924.86	925.78	926.71	927.09	927.48	928.40	929.33
1031+50	924.64	925.50	926.37	926.73	927.10	927.97	928.85
1031+75	924.49	925.30	926.10	926.44	926.78	927.61	928.43
1032+00	924.40	925.15	925.90	926.21	926.53	927.31	928.08
1032+25	924.36	925.05	925.74	926.03	926.33	927.05	927.77
1032+50	924.39	925.02	925.66	925.92	926.20	926.87	927.53
1032+75	924.48	925.06	925.63	925.87	926.13	926.74	927.35
1033+00	924.62	925.14	925.65	925.87	926.10	926.67	927.23
1033+08.27	924.68	925.18	925.68	925.89			
1033+25	924.83	925.29	925.75	925.94	926.15	926.66	927.17
1033+30.62				925.96	926.17	926.67	927.17
1033+50	925.08	925.49	925.89	926.06	926.27	926.72	927.17
1033+75	925.40	925.75	926.10	926.24	926.45	926.84	927.23
1034+00	925.79	926.08	926.37	926.49	926.70	927.02	927.35
1034+25	926.23	926.46	926.69	926.79	927.00	927.26	927.52
1034+43.78	926.60	926.78	926.97	927.05			
1034+50	926.73	926.92	927.08	927.15	927.36	927.56	927.75
1034+54.33				927.22	927.43	927.62	927.80
1034+75	927.30	927.49	927.55	927.58	927.79	927.98	928.06
1034+91.44	927.69	927.88	927.88	927.88	928.09	928.28	928.28
806+88.34	927.69	927.88	927.88	927.88	928.09	928.28	928.28
806+75	928.00	928.19	928.17	928.16	928.37	928.56	928.53
806+50	928.62	928.81	928.74	928.71	928.92	929.11	929.02
806+25	929.29	929.48	929.37	929.32	929.53	929.72	929.56
806+14.09				929.61	929.82	930.01	929.82
806+00	930.00	930.19	930.03	929.97			
805+82.10	930.59	930.78	930.59	930.51			
805+75	930.83	931.02	930.83	930.72			
805+53.28	931.58	931.77	931.58	931.37			

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

36
492

MAH-18-17.20

ESTIMATED QUANTITIES I-5 GUARDRAIL & BARRIER RAIL

CODE	LOCA.	TYPE 2-A GR (L.F.)	TYPE 2A B.R. (L.F.)
R-1	SILLIMAN 9+06	75	
R-2	SILLIMAN 12+25	125	
R-3	℄	75	462.5
SHT. TOTAL		275	462.5

ESTIMATED QUANTITIES I-12 CONCRETE CURB (L.F.)

CODE	LOCA.	TYPE 6	
G-1	SILLIMAN	48	
G-3	925+00025 to 930+00	989	
SHT. TOTAL		1037	

ESTIMATED QUANTITIES I-21 PORTLAND CEMENT CONCRETE MEDIAN (SQ. YDS.)


CODE	FROM	TO	QUANT.
N-1	925+00025	930+00	603
SHEET TOTAL			603

ESTIMATED QUANTITIES E-8 REMOVAL ITEMS

CODE	FROM	TO	CURB OR COMB. CURB & GUTTER (L.F.)	PAVEMENT (S.Y.) RIGID	PAVEMENT (S.Y.) NON-RIGID	SIDEWALK (S.F.)
B-1	G-1	R-2				5200
B-2	ML-1	ML-2				2990
X-1	G-1	R-2	1040			
X-2	ML-1	ML-2	836	1252		
K-1	G-1	R-2				
K-2	ML-1	ML-2			1120	
SHEET TOTAL			1876	1252	1120	8190


PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
FIL. OF PLAT CHECKED
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
PLOTTED
CROSS SECS. CHECKED
E. M.'s NOTED
NO.
STRUCTURE NO'S AT M'S CHKD.
BY
DATE



ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS


CODE	LOCATION ℄ STATION	#4 C.B. MOD. EACH	#1 M.H. EACH	2-2A C.B. EACH	24-6 INLET EACH	24-10 INLET EACH	I-14 TYPE-1 PAVED GUTTER MOD. LIN. FT.
A-1	924+90 ℄	1					
A-2	926+50 9.5' RT.		1				
A-3	926+25 54.5' RT.			1			10
A-4	926+26.9 41.7' LT.		1				
A-5	926+26.9 44.7' LT.				1		
A-6	925+00 67.0' LT.			1			10
A-7	929+65 6.0' RT.		1				
A-8	929+58 1.5' RT.					1	
A-9	929+50 49.2' LT.			1			
A-10	RAMP "B" 8+19.54 19.0' LT. ℄			1			10
SHEET TOTAL		1	3	4	1	1	30



G-1 Section X-X

℄ CURVE DATA № 1

Δ = 43°47'40"	P = 6,392'
D_c = 5°30'	K = 199.756'
R_c = 1041.74'	X = 398.528
L_s = 400'	Y = 25.532'
Θ_s = 11°00'	L.T. = 267.184'
L_c = 396.26'	S.T. = 133.804'
T_s = 621.043'	L.C. = 399.344'
E_s = 87.89'	



ESTIMATED QUANTITIES I-2 PIPES

CODE	LOCATION FROM	LOCATION TO	CL. 'B' STORM SEWER UNDER PAVT. OR APPR. LIN. FT. 27"	30"	12"	15"
P-1	A-1	A-2	156'			
P-2	A-2	A-7		311'		
P-3	A-3	A-2			52'	
P-4	A-4	A-2				75'
P-5	A-6	A-4			98	
P-6	A-5	A-4			24	
P-7	A-10	A-4			48	
P-8	A-8	A-7			9	
P-9	A-9	A-8			55	
P-10	A-7	930+00		33		
SHEET TOTAL			156'	344	286	75'

I-4 PIPE UNDERDRAIN LIN. FT.

CODE	LOCATION FROM	LOCATION TO	DEEP - SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 a	I-5 PIPE SPEC. EACH 6"-60° BEND
U-1	925+29	A-7	D	120	50	1
U-2	924+36	A-8	S	450	10	
U-3	925+29	A-5	D			
SHEET TOTAL				570'	60'	1

EROSION CONTROL

CODE	LOCATION FROM	LOCATION TO	L-10 SOD SQ. YDS.	I-10 DUMP ROCK CHANNEL PROT. C.Y.	I-14 PVD. GUTTER TYPE L LIN. FT.
E-1	923+50	925+40	106		
E-2	921+90	—		58	
E-3	925+40	926+05			65
SHEET TOTAL			106'	58'	65'

PLATE I — PLAN - PROFILE O. P. R. & R. E. STANDARD
201 FIR-3 AGEPROOF FILM MADE AND PRINTED IN U. S. A.
EUGENE DIETZGEN CO., CHICAGO


STA. 920+00 To 930+00

MICROFILMED
SEP 19 1985

FED. RD	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

37
492



ESTIMATED QUANTITIES I-15 GUARDRAIL & BARRIER RAIL			
CODE	LOCA.	G.R.(L.F.)	B.R.(L.F.)
R-4	℄	175	912.5
R-4A	LT.	137.5	
R-4B	RT.	137.5	
SHT. TOTAL		450.0	912.5

ESTIMATED QUANTITIES I-12 CONCRETE CURB				
CODE	LOCATION FROM	TO	TYPE	L.F.
G-4	930+00	940+00	6	1974

ESTIMATED QUANTITIES I-21 P.C.C. MEDIAN			
CODE	LOCATION FROM	TO	S.Y.
N-2	930+00	940+00	658

B.M.#5 TOP STEM OF HYDT. N.E. COR. STEEL & 3RD. ST. ELEV. 945.457


B.M.# 3-A R.R. SPIKE IN E. SIDE 20" POPLAR 60' LT. ℄ SILLIMAN @ APPROX. STA. 7+70 ELEV. 923.72

ESTIMATED QUANTITIES I-8 MANHOLES & CATCH BASINS							I-14 PAVED GUTTER MODIFIED TYPE-1 (LIN. FT.)
CODE	LOCATION ℄ STATION	#2 M.H. WITHOUT DROP PIPE EACH	# 1 M.H. EACH	#2-2A C.B. EACH	#2A-G INLET EACH	#2-8 INLET MOD. EACH	
A-11	930+50 6.0' RT.	1					
A-12	933+06 6.0' RT.		1				
A-13	933+00 66.0' RT.			1			10
A-14	933+00 66.0' LT.			1			10
A-15	933+00 1.25' RT.				1		
A-16	936+19 ℄					1	
A-17	937+20 6.0' RT.		1				
A-18	937+20 66.0' LT.			1			20
SHEET TOTAL		1	2	3	1	1	40

ESTIMATED QUANTITIES I-2 PIPES							I-5 PIPE SPECIALS	
CODE	LOCATION		CLASS "B" STORM SEWERS UNDER PAV'T OR APPROACH LIN. FT.				CLASS "B" STORM SEWER UNDER PAV'T OR APPR. - EACH	
	FROM	TO	30"	18"	33"	12"	18"30° BEND	33"-12" WYE
P-10	930+00	A-11	48					
P-11	A-11	A-12			252	*		
P-12	A-14	A-12				69		
P-13	A-13	A-12				57		
P-14	A-15	A-12				5		
P-15	A-12	A-17			406			
P-16	A-18	A-17				60		
P-17	A-17	940+00			278			
P-18	A-16	936+22				5		1
SHEET TOTAL			48		684	196		1

* M-6.6 & or M-6.8 b

℄ CURVE DATA № 2
Δ = 54°44'10"
Dc = 5°30'
Ls = 400'
Θs = 11°00'
Rc = 1041.74'
Lc = 595.20'
Ts = 742.31'
Es = 138.49'
P = 6.392'
K = 199.756'
x = 398.528'
Y = 25.532'
L.T. = 267.184'
S.T. = 133.804'
L.C. = 399.344'



I-4 PIPE UNDERDRAIN LIN. FT.						
CODE	LOCATION FROM	TO	DEEP - SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 a	I-5 PIPE SPEC EACH
U-1	932+00	A-13	S	120	10	1
U-2	930+20	A-14	S	310	10	1
U-3	930+00	A-15	S	288	10	-
U-4	933+04	940+00	D	696	-	-
U-5	933+06	A-16	S	297	10	-
U-6	936+25	940+00	S	375	-	-
U-7	933+06	940+00	D	696	-	-
SHEET TOTAL				2782	40	2

EROSION CONTROL				
CODE	LOCATION FROM	TO	I-10 SOD S.Y.	I-10 DUMPROCK CHAN.PROC C.Y.
E-1	931+00	932+50	106	
E-2	935+00	937+10	117	
E-3	938+80	940+00	62	
E-5	933+50			83
E-6	933+00			72
E-7	936+62			118
SHEET TOTAL			285	273

STA. 930+00 to 940+00

PLATE 1 — PLAN - PROFILE O. P. R. & R. E. STANDARD
201 FM-3 AGEPROOF FILM MADE AND PRINTED IN U.S.A.
EUGENE DIETZGEN CO., CHICAGO

PLAN / PROFILE
SURVEYED
PLANS PLOTTED
GRADES CHECKED
S. R. NOTED
STRUCTURE NOTATNS CK'ED.
NOTE BOOK
NO.
ALIGNMENT CHECKED
RT. OF WAY CHECKED
BY
DATE

FED. RD.	STATE	PROJECT	
2	OHIO		

38
492

MAH-18-17.20

FOR FUTURE CONSTRUCTION
SEE SHEET Nº 74&75

RAMP A3 & B3 ARE TO BE ROUGH GRADED ONLY FOR CONSTRUCTION
DETAILS SEE SH'T. Nº 4&74

STA. 943+92.72 ℄ RT. 18 EXP.
0100 ℄ MAH.-WEST FED. EXP.

℄ MAHONING-WEST FEDERAL EXPWAY.

NOSE STATIONS
RAMP A3
940+25.66 M.L.

SC 941+46.56

BEGIN SHEET – STA. 940+00

RAMP A3

SPUR-LINE (TO BE REMOVED BY OTHERS)
RAMP B3

CS 947+41.76

END SHEET – STA. 950+00

#872.51
945+23
6°-90° BEND

6" I-4
945+82 90° BEND

#869.43
946+80-6"PVC

#869.06
947+55
6°-22½° BEND

405.43 NOSE STA. RAMP C3
945+77.39 M.L.

40' OUTLET INV. 862.01 DITCH

12"x18"

3'x5'

NOTE: 2-2A C.B.@ STA. 947+00 (69.0' RT. ℄) SHALL BE MODIFIED TO INCLUDE A THIRD WINDOW; OPENING TO THE EAST.

℄ REFERENCE MONUMENTS
STA. 941+46.56
STA. 944+50
STA. 947+41.76

30' OPEN CHANNEL FOR CONSTRUCTION
DETAILS SEE SHEET Nº 114

S-27 18" CULVERT
SEE SHEET Nº 112

FOR DETAILS & QUANTITIES OF RAMP C3 SEE SHEET Nº 4,74&75

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS							I-14 PAVED GUTTER TYPE-I MOD. L.F.
CODE	LOCATION ℄ STATION	#1 M.H. EACH	#2-4 C.B. EACH	#2-2A C.B. EACH	#2A-10 INLET EACH	#2A-6 INLET EACH	
A-19	941+25 6.0' RT.	1					
A-20	945+73 136.0' LT.		1				10
A-22	945+25 1.25' RT.				1		
A-24	947+00 69.0' RT.			1			20
A-25	948+00 1.25' LT.					1	
A-26	948+90 1.25' LT.					1	
SHEET TOTAL		1	1	1	1	2	30

ESTIMATED QUANTITIES I-15 GUARD RAIL & BARRIER RAIL			
CODE	LOCA.	GR.(L.F.)	B.R.(L.F.)
R-5	℄		1000

ESTIMATED QUANTITIES I-12 CONCRETE CURB (L.F.)			
CODE	FROM	TO	TYPE G
G-5	940+00	950+00	1974
SH'T TOTAL			1974

ESTIMATED QUANTITIES I-2 PIPES						
CODE	LOCATION		CLASS "B" STORM SEWERS UNDER PAV'T & APPR. (LIN. FT.)			
	FROM	TO	33"	33" M-6.6(d)	18"	12"
P-17	940+00	A-19	123			
P-19	A-19	H-7		354		
P-23	A-22	H-6				64
P-25	H-3	A-24			102	
P-26	H-4	A-25				57
P-27	H-5	A-26				58
SHEET TOTAL			123	354	102	179

ESTIMATED QUANTITIES I-21 PORTLAND CEMENT CONCRETE MEDIAN (SQ. YDS.)			
CODE	FROM	TO	QUANT.
N-3	940+00	950+00	658
SHEET TOTAL			658

ESTIMATED QUANTITIES CULVERTS				
CODE	LOCATION		42"S-27 PIPE M-C.4.d GAGE 10 LIN. FT.	E-2 EXCAVATION CU. YDS.
	FROM	TO		
C-20	H-1	A-20	252	280

℄ CURVE DATA Nº 2
Δ = 54°44'10"
Dc = 5°30'
Ls = 400'
Θs = 11°00'
Rc = 1041.74'
Lc = 595.20'
Ts = 742.31'
Es = 138.49'
P = 6.392'
K = 199.756'
x = 398.528'
y = 25.532'
L.T. = 267.184'
S.T. = 133.804'
L.C. = 399.344'

I-4 UNDERDRAINS LIN. FT.						I-5 PIPE SPEC. EACH	
CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	6" OUTLET PIPE M-6.4 a	6" 30° BEND	6" 90° BEND
U-1	940+00	A-22	S	515	10		
U-2	A-19	950+00	D	468	10		1
U-3	940+00	944+25	D	445	10		1
U-4	940+30	945+25	D	509	10		1
U-5	946+80	947+85	S	120	10		
SHEET TOTAL				2057	50		3

P-C 4 ENDWALLS			
CODE	LOCATION		S-1 CONC. CL. "E" CU. YDS.
H-1	944+79.80	106' RT. ℄	0.76
H-3	946+00	116.0' RT. ℄	0.30
H-4	948+00	55.5' RT. ℄	0.23
H-5	948+90	56.5' RT. ℄	0.23
H-6	945+25	66' LT. ℄	0.23
H-7	944+87	114' RT ℄	0.55
	SHEET TOTAL		2.30

EROSION CONTROL						
CODE	LOCATION FROM	LOCATION TO	L-10 SOD S.Y.	I-10 DUMPED ROCK C.Y.	I-14 PAVED GUTTER L.F. TYPE-I	TYPE-II
E-1	940+00	944+25 RT.	236			
E-2	944+25	944+32 RT.			40	
E-3	944+32	944+79 RT.				42
E-4	H-3			3		
E-5	944+50	945+20	70			
E-6	945+20	945+73 LT.			105	
E-7	944+87	945+00		20		
	SHEET	TOTAL	306	23	145	42

FOR PROFILES OF PROPOSED I-2 NOT SHOWN THIS SHEET SEE SHEET Nº 75&80 C-82

A-21
STA. 945+67
I-8 Nº 2-2A C.B. (136.0' LT. ℄)
WINDOW EL. 851.45
12" I-2 848.75

A-20
STA. 945+73
I-8 Nº 2-4 C.B. (136.0' LT. ℄)
WINDOW ELEV. 855.50
42" S-27 844.30

A-19
STA. 941+25 (6.0' RT. ℄)
I-8 Nº 1 M.H.
COVER ELEV. 885.00
33" I-2 878.42
1000' V.C.

A-22
STA. 945+25 (1.5' RT. ℄)
I-8 Nº 2A-10 INLET
TOP OF CURB – 876.84
WINDOW ELEV. (LT.) 876.17
12" I-2 872.76
12" I-2 @ DITCH 869.22

A-24
STA. 948+00 (1.5' LT. ℄)
I-8 Nº 2-6 INLET
TOP CURB – 874.47
WINDOW ELEV. 873.80
LT. LANE ONLY
12" I-2 870.39

A-25
STA. 948+90 (1.5' LT. ℄)
I-8 Nº 2-6 INLET
TOP CURB – 874.32
WINDOW ELEV. 873.61
LT. LANE ONLY
12" I-2 870.24

404'-33" I-2 @ 0.25%

-2.86%

EL. 884.58

#884.92

#880.51

#872.51

#872.18

#869.45

#869.42

#869.06

#870.81

#870.47

#869.43

#869.06

P.V.I. STA. 946+37.28
ELEV. 870.28

P-17

P-19
(SEE SHEET Nº 82)

U-1 U-2 U-3 U-4 U-5

C-20 C-21 C-22

E-1 E-2 E-3 E-4 E-5 E-6 E-7

H-1 H-2 H-3 H-4 H-5 H-6 H-7

N-3

R-5

P-23 P-25 P-26 P-27

TOP CURB

See Sheet 79

STA. 940+00 to 950+00

PLATE 1 — PLAN - PROFILE O. P. R. & R. E. STANDARD
261 FIM-3 AGEPROOF FILM MADE AND PRINTED IN U. S. A.
EUGENE DIETZGEN CO., CHICAGO

PLAN
NOTE BOOK
NO.
SURVEYED
PLOTTED
ALIGNMENT CHECKED
RIGHT-OF-WAY CHECKED
BY
DATE

PROFILE
NOTE BOOK
NO.
SURVEYED
PLOTTED
GRADES CHECKED
R.R. CROSSING
STRUCTURE NOTATIONS CH'KD.
BY
DATE

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

39
492

BANK RUN SLAG - FOR CONSTRUCTION DETAILS SEE SHEET Nº 5 & X-SECTIONS

MAHONING RIVER

℄ SALT SPRINGS RD. - STA. 950+00

BEGIN SHEET

END SHEET

FOR DETAIL & QUANTITIES OF RAMP 'B' SEE SHEET Nº 74

FOR DETAIL & QUANTITIES OF RAMP 'D' SEE SHEET Nº 52 53 & 64

FOR DETAILS OF S-27 24" CULVERT LT. & RT. STA. 955+50 SEE SHEET Nº 120 & 121

TO BE REMOVED BY OTHERS.

FACE OF ABUTMENT

℄ EXPRESSWAY

TANG. 32.50'

40'

958+83.99 REF. PINS SET 100' E. & W. OF ℄ EXPY. ON MAHONING AVE. BRIDGE ℄

958+73.00

℄ MAHONING AVE.

1000' V.C.

26°48'42" TANG. LOCATE

RAMP B

RAMP "C"

RAMP "D"

NOSE STA. RAMP "D" 18+95.07 B.L. 953+93.85 M.L.

STA. 954+73.06 P.I. STA. 955+96.97 M.L.

FOR DETAIL & QUANTITIES OF RAMP 'C' SEE SHEET Nº 51 & 64

STA. 20+63.26 RAMP "C" QUANTITIES

STA. 955+75.00 MAINLINE QUANTITIES

RELOC. 16" WATER

RELOC. 8" WATER

RELOC. 8" ST. SEW.

MAJOR ST. SEW.

STA. 958+83.99 STRUCTURE MAH-18-1815

FOR CONSTRUCTION DETAILS & QUANTITIES OF RELOC. WATER & ST. SEWER LINES SEE SHEET Nº 90 & 91

RAMP "C" SEE SHEET Nº 51

4°07'48"

IRON PIN POINT ON RANDOM LINE

R.R. SPIKE 2.25' S. OF S.W. COR. - GAS STA.

R.R. SPIKE 2.8' W. OF FENCE 12 JOINT

41.32'

47.51'

53.69'

37.08'

38.04' RANDOM LINE

ANGLE POINT

38.23'

T. HUB BY W. GATE POST LUMBER YARD

T. HUB N.E. CORNER RETAINING WALL HOUSE #1357

℄ MAHONING

℄ REFERENCE MONUMENTS
STA. 951 + 41.76
STA. 954 + 73.06
STA. 959 + 50

℄ CURVE DATA Nº 3

Δ = 60°43'03	P = 6.39'
Dc = 5°30'	K = 199.76'
Rc = 1041.74'	X = 398.53'
Ls = 400'	Y = 25.53'
Θs = 11°00'	L.T. = 267.18'
Lc = 703.95'	S.T. = 133.80'
Ts = 813.68'	L.C. = 399.34'
Es = 172.95'	

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS

CODE	LOCATION ℄ STATION	*2A-8 INLET EACH	*2A-6 INLET EACH	
A-27	950+00 1.25' LT.	1		
A-28	952+75 1.25' LT.		1	
A-29	955+00 1.25' LT.	1		
A-31	957+50 1.25' RT.		1	
SHEET TOTAL		2	2	

ESTIMATED QUANTITIES I-5 GUARDRAIL & BARRIER RAIL

CODE	LOCA	G.R.(L.F.)	B.R.(L.F.)
R-6	℄	150	925
R-6A	RT.	125	
SH'T. TOTAL		375	925

ESTIMATED QUANTITIES I-12 CONCRETE CURB (L.F.)

CODE	FROM	TO	TYPE G
G-6	950+00	960+00	1067
SHEET TOTAL	—		1067

ESTIMATED QUANTITIES I-2 PIPES L.F. — I-5

CODE	LOCATION FROM	TO	STORM SEWER CL. B "STORM" CL. SEWER UNDER "A" PAV'T OR APPR. 12"			PIPE SPEC. EACH 12" M-6.4 C	18" x 30" BEND M-6.4 A
P-28	A-27	H-6	60				
P-29	A-28	H-7	104				
P-30	A-29	H-8	55			42	2
P-31	A-31	H-9	100				
P-32	A-31	A-30	3				
SHEET TOTAL			322	~	—	42	2

ESTIMATED QUANTITIES I-21 PORTLAND CEMENT CONCRETE MEDIAN (SQ. YDS.)

CODE	FROM	TO	QUANT.
N-4	950+00	960+00	656
SHEET TOTAL			656

ENDWALLS

CODE	LOCATION	3-1 CONC. CL. "E" C.Y.	TYPE
H-6	950+00 60.5' RT. ℄	0.23	PC-4
H-7	953+00 104' RT. ℄	0.23	PC-4
H-8	955+00 99' RT. ℄	0.23	PC-4
H-9	957+50 90' RT. ℄	0.90	PC-1
SHEET TOTAL		1.59	—

EROSION CONTROL

CODE	LOCATION FROM	TO	L-10 SOD S.Y.	I-10 DUMPROCK CHANNEL PROTECTION C.Y.	I-14 PAVED GUTTER TYPE I (L.F.)
E-1	H-7	H-8	89		
E-2	H-8			1.95	
E-3	H-8	E-4	83		
E-4	956+50	957+50			100
E-5	958+50	960+00			150
E-6	957+00	140' LT.		67.00	
SHEET TOTAL			172	68.95	250

I-4 UNDERDRAINS L.F.

CODE	LOCATION FROM	TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.6 A
U-1	950+00	952+69	S	259	10
U-2	A-28	954+96	S	211	10
U-3	A-29	957+44	S	234	10
U-4	A-31	960+00	S	240	10
U-5	952+00	955+57	S	312	10
U-6	950+00	953+60	S	360	10
SHEET TOTAL				1616'	50

PROPOSED STRUCTURE MAH-18-1815
TYPE: 3-WEST SPANS CONTINUOUS STEEL BEAM - EAST SPAN - SINGLE SPAN STEEL BEAM WITH REINFORCED CONCRETE DECK & SUBSTRUCTURE
SPANS: 64'-0", 80'-0", 81'-9", 40'-9" ℄/℄ BRGS.
ROADWAY: 32'-11" C/C
LOAD FREQUENCY: C.F. 2000. ADEQUATE FOR A.A.S.H.O. ALTERNATE LOADING.
SKEW: 43°11'21" L.F.
APPROACH SLAB: 25'-0" LONG.
WEARING SURFACE: -1" MONOLITHIC.
ALIGNMENT: SAME AS EXISTING STRUCTURE
TRAFFIC COUNT: 20,900 ADT 1959

FOR PROFILES OF PROPOSED I-2 NOT SHOWN ON THIS SHEET SEE SHEET Nº 80

A-27
STA. 950+00 (1.25' LT.)
I-8 Nº 2A-8 INLET
TOP OF CURB 874.55
WINDOW ELEV. (LT.) 873.88
℄ 12" I-2 870.48

A-28
STA. 952+75 (1.25' LT. ℄)
I-8 Nº 2A-6 INLET
TOP OF CURB 876.78
WINDOW ELEV. (LT.) 876.11
℄ 12" I-2 872.71
℄ 8" I-4 873.04

A-29
STA. 955+00 (1.25' LT.)
I-8 Nº 2A-8 INLET
TOP OF CURB 878.89
WINDOW ELEV. 878.22
℄ 12" I-2 874.82
℄ 8" I-4 875.15

A-31
STA. 957+50 (1.25' LT.)
I-8 Nº 2A-6 INLET
TOP OF CURB 881.24
WINDOW ELEV. 880.57
℄ 12" I-2 877.17
℄ 8" I-4 877.50

STA. 955+50 S-27 24" CULVERT ℄ 852.21

STA. 959+14 PROPOSED RELOC. 30" STORM SEWER ℄ ELEV. 873.39 - 1.0' CONC. ENCASEM'T.

STA. 959+20 PROPOSED 24" STORM SEWER ℄ ELEV. 873.24 - 1.0' CONC. ENCASEM'T.

STA. 959+32 PROPOSED 16" C.I. WATER MAIN ℄ ELEV. 877.00 - 1.0' CONC. ENCASEM'T.

STA. 959+36 PROPOSED RELOC. 8" WATER MAIN ℄ ELEV. 876.80 - 1.0' CONC. ENCASEM'T.

℄ STRUCTURE

℄ ELEV. ℄ 879.51

STA. 950+00 to 960+00

FED. RD.	STATE	PROJECT	
2	OHIO		

40 / 492

MAH-18-17.20

I-12 CONC. CURB - TYPE G			
CODE	STATION FROM	TO	L.F.
C-1	968+64	969+77	113

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS							I-14 TYPE-1 PAVED GUTTER MOD. LIN. FT.
CODE	LOCATION & STATION	#1 M.H. EACH	#2-2A C.B. EACH	#2A-6 INLET EACH	#2A-8 INLET EACH	#6 C.B. EACH	
A-33	8+00 RAMP "E" 19.0' RT. ℄		1				20
A-34	8+00 RAMP "E" 19.0' LT. ℄					1	
A-35	968+69 52' LT. ℄			1			
A-36	969+00 6.0' LT. ℄	1					
A-37	968+85 67.0' RT. ℄		1				10
A-38	969+00 1.25' RT. ℄				1		
A-39	969+93 66.0' LT. ℄		1				10
A-40	969+93 6.0' LT. ℄	1					
SHEET TOTAL		2	3	1	1	1	40

ESTIMATED QUANTITIES I-2 PIPES			STORM SEWER (L.F.)				I-5 PIPE SPEC. EA.
CODE	LOCATION FROM	TO	CL "B" UNDER PAV'T OR APPR. 15"	12"	CL "A" 18"	CL "A" 15" M-6.4b	CL "B" ST. SW U.P. & 12"x45° BEND M-6.4b
P-33	A-34	H-12		135			
P-34	A-33	A-34		36			1
P-36	A-35	H-10				40	1
P-37	A-36	A-35			50		
P-38	A-37	H-11				44	1
P-39	A-36	A-40	89				
P-40	A-36	A-38		5			
P-41	970+00	A-40		5			
P-42	A-39	A-40	57				
SHEET TOTAL			146	181	52	84	1 2

ESTIMATED QUANTITIES I-5 GUARDRAIL & BARRIER RAIL			
CODE	LOCA.	G.R.(L.F.)	B.R.(L.F.)
R-7	℄		225
R-8	℄	150	75
R-9	RT.	112.5	
R-10	LT.	137.5	
SHEET TOTAL		400.0	300


ESTIMATED QUANTITIES I-12 CONCRETE CURB (L.F.)			
CODE	FROM	TO	TYPE G
G-7	960+00	962+23.25	446
G-8	968+46.93	970+00	279
SHEET TOTAL			743


ESTIMATED QUANTITIES I-21 PORTLAND CEMENT CONCRETE MEDIAN (SQ. YDS.)			
CODE	FROM	TO	QUANT.
N-5	960+00	962+23.25	149
N-6	968+46.93	970+00	99
SHEET TOTAL			248

I-1 PIPE UNDERDRAINS LIN. FT.						
CODE	LOCATION FROM	TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4a	I-5 PIPE SPEC. EACH 6"x90°
U-1	960+00	962+44	S	244		
U-2	961+25	962+44	S	119		
U-3	968+69	970+00	S	130	10	1
U-4	968+85	970+00	S	114	10	1
U-5	969+00	970+00	S	90	10	
U-6	961+25	960+50	D	75		
SHEET TOTAL				772	30	2

EROSION CONTROL					
CODE	LOCATION FROM	TO	I-10 SOD S.Y.	I-10 DUMPED ROCK C.Y.	
E-1	967+89.5	968+42		23	
E-2	967+82	968+24		18	
SHEET TOTAL				41	

P.C. 4 ENDWALLS			
CODE	LOCATION		S-1 CONC. CL."E" C.Y.
H-10	968+23.85	52' LT. ℄	0.30
H-11	968+40	67' RT. ℄	0.30
H-12	960+50	68' LT. ℄	0.23
SHEET TOTAL			0.83





A-33
STA. 8+00 RAMP "E"
19.0' R.T. ℄
I-8 Nº 2-2A C.B.
WINDOW ELEV. 882.93
℄ 12" I-2 880.26

A-34
STA. 8+00 RAMP "E"
19.0' LT. ℄
I-8 Nº G C.B.
GRATE ELEV. 886.32
℄ 12" I-2 879.26

A-35
STA. 968 + 68.85 (54.0' LT. ℄)
I-8 Nº 2A-G INLET
TOP OF CURB 890.36
WINDOW ELEV. 889.67
℄ 18" I-2 884.62
℄ 8" I-4 885.45

A-37
STA. 968 + 85 (67.0' RT. ℄)
I-8 Nº 2-2A C.B.
WINDOW ELEV. 889.62
℄ 18" I-2 886.95
℄ 8" I-4 887.78

A-39
STA. 969 + 93 (66.0' LT. ℄)
I-8 Nº 2-2A C.B.
WINDOW ELEV. 889.52
GRATE ELEV. 887.10

A-38
STA. 969+00 (1.25' RT. ℄)
I-8 Nº 2A-8 INLET
TOP OF CURB 892.05
WINDOW ELEV. 891.38
℄ 12" I-2 887.97
℄ 8" I-4 888.30

A-36
STA. 969 + 00 (6.0' LT. ℄)
I-8 Nº 1 M.H.
COVER ELEV. 891.48
℄ 12" I-2 885.56
℄ 15" I-2 885.31
℄ 18" I-2 885.06

A-40
STA. 969 + 93 (6.0' LT. ℄)
I-8 Nº 1 M.H.
COVER ELEV. 892.54
℄ 12" I-2 886.63
℄ 15" I-2 886.38

℄ REFERENCE MONUMENTS
STA. 965+77.01
STA. 969+77.01

Δ = 60°43'03"
Dc = 5° 30'
Rc = 1041.74'
Ls = 400'
θs = 11°00'
Lc = 703.95'
Ts = 813.68'
Es = 172.95'

P = 6.39'
X = 199.76'
Y = 398.53'
Y = 25.53'
L.T. = 267.18'
S.T. = 133.80'
L.C. = 399.34'

FED. RD.	STATE	PROJECT	
2	OHIO		

41 / 492

MAH.-18-17.20

24'-0"

COBBLESTONE SURFACE STONE CURB

TYPICAL SECTION EXISTING ROCKVIEW

FOR MARSHALL ST. IMPROVEMENT SEE SHEET Nº 248 - 260

℄ - MARSHALL STREET

BEGIN SHEET - STA. 970+00

END SHEET - STA. 980+00

℄ - EDWARDS ST.

℄ - ROCKVIEW

℄ - ORANGE AVE.

RAMP G SEE SHEET Nº

9' PAVED SHOULDER

24" TYPE G CURB

STA. 971+19 6" I-4 PLUG

STA. 974+34 6" I-4 PLUG

STA. 976+68.30

STA. 979+10 6" I-4 PLUGS

STA. 979+99.50

BEGIN APPROACH SLAB STA. 978 + 94.25

END CURB & MEDIAN 979+19.25

STRUCTURE Nº MAH-18-1855

PROPOSED 15" STORM SEWER

EXISTING 15" COMB. SEWER

MARSHALL ST. INLET. SEE SHEET Nº 249

EDWARDS ST. IMPROVEMENT SEE SHEET Nº 262 - 263

EDWARDS ST. INLET.

S 84°47'24"-E

G-9 SEEDING TO CURB.

PROPOSED 48" COMBINED SEWER FOR DETAILS SEE SHEET Nº 93

REMOVE EXIST. S.W.

FOR SUMMARY OF EDWARDS ST. REMOVAL ITEMS SEE SHEET 25

LIMIT OF EDWARDS ST. QUANTITIES.

T. HUB BY JOG IN FENCE — IRON PIN 3'W. N.W. COR. HSE #27 — ℄ MARSHALL — ON M.H. COVER — ℄ ROCKVIEW — THUB W. OF 12" TREE — ℄ EXP'Y 976+68.30

IRON PIN AT S.W. COR. HSE #30 — R.R. SPIKE AT S.W. COR. WAREHOUSE — EXISTING ℄ MARSHALL — P.K. NEAREST D. RIM OF M.H. — ℄ EDWARDS — ℄ EXP'Y 979+99.50

THUB BY N.E. COR. HSE #30

IRON PIN BY STONE RET. WALL — THUB S.W. COR. PORCH HSE #133 — PNT ON M.H. COVER EXISTING ORANGE — THUB S. SIDE ℄ MAPLE

ITEM G-11 REMOVE EXISTING STONE CURB AT DRIVES & REPLACE WITH TYPE G CURB. RE-MOVE DRIVEWAY APPROACH, BACKFILL & SEED.

B.M.# 12 TOP OF HYDT. N.E. COR. GLENWOOD & MARSHALL ST. ELEV. 903.57

B.M.# 22 TOP OF STEM ON HYDT. N. SIDE ORANGE AVE. 100' FROM GLENWOOD. ELEV. 931.84

B.M.# 23 TOP OF STEM ON HYDT. N. SIDE ORANGE AVE. 350' FROM GLENWOOD. ELEV. 931.69

B.M.# 24 TOP OF BOLT @ PT OF ARROW ON W. SIDE OF HYDT. N.W. COR. ORANGE & ROCKVIEW. ELEV. 927.30

℄ REFERENCE MONUMENTS STA. 978+50

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS

CODE	LOCATION ℄ STATION	#1 M.H. EACH	#2-2A C.B. EACH	#6 C.B. EACH	#2A-6 INLET EACH	2-6 MOD INLET EACH
A-41	971+25 6' LT. ℄	1				
A-42	971+25 1.25' LT. ℄				1	
A-43	971+30.71 38' LT. ℄			1		
A-44	971+84.50 42.5' LT. ℄			1		
A-45	975+00 6' LT. ℄	1				
A-46	975+00 ℄					1
A-47	978+75 106' LT. ℄		1			
A-48	979+50 84' RT. ℄		1			
SHEET TOTAL		2	2	2	1	1

ESTIMATED QUANTITIES I-2 PIPES

CODE	LOCATION FROM	LOCATION TO	CL'B' STORM SEWER UNDR PAVT. APPRS. 12" L.F.	CLASS 'B' STORM SEWERS 12" L.F.
P-41	A-41	970+00	123	
P-43	A-42	A-41	2	
P-44	A-43	A-41	28	
P-45	A-44	A-43	52	
P-46	A-45	A-41	371	
P-47	A-46	A-45	2	
P-48	A-47	10+3249 MARSHALL		70
P-49	A-48	4+44.84 EDWARDS		27
SHEET TOTAL			522	97

ESTIMATED QUANTITIES I-15 GUARDRAIL & BARRIER RAIL

CODE	LOCA.	G.R (L.F.)	BR. (L.F.)
R-9	℄		925
R-9A	LT.	400	
R-10	LT.	50	
SHT. TOTAL		450	925

ESTIMATED QUANTITIES I-12 CONCRETE CURB (L.F.)

CODE	FROM	TO	TYPE G
G-9	970+00	979+19.25	1816
G-10	ROCKVIEW	—	55
G-11	DRIVES	—	136
SHEET TOTAL			2007

ESTIMATED QUANTITIES I-21 PORTLAND CEMENT CONCRETE MEDIAN (SQ. YDS.)

CODE	FROM	TO	QUANT.
N-7	970+00	979+19.25	606
SHEET TOTAL			606

ESTIMATED QUANTITIES E-8 REMOVAL ITEMS

CODE	LOCATION FROM	LOCATION TO	CURB (L.F.)	PAVEMENT RIGID (S.Y.)	SIDEWALK (S.F.)
B-1	ORANGE	MARSHALL			2880
B-2	GLENWOOD	EDWARDS			4490
K-1	ORANGE	MARSHALL	590		
K-1	ORANGE	MARSHALL		787	
G-11	GLENWOOD	EDWARDS	136	57	
SHEET TOTAL			726	844	7370

I-4 PIPE UNDERDRAINS LIN. FT.

CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4a	I-5 SPECIAL 6" 30° BENDS EACH
U-1	977+00	971+32	D	558	10	
U-2	979+10	977+00	S	210		
U-3	971+19	970+00	S	119		
U-4	974+34	971+25	S	357	10	1
U-5	979+10	975+04	S	396	10	
U-6	970+25	970+00	S	25		
U-7	977+00	970+25	D	675		
U-8	979+10	977+00	S	210		
SHEET TOTAL				2548	30	1

EROSION CONTROL

CODE	LOCATION FROM	LOCATION TO	L-10 SOD SQ.YDS.	I-14 TYPE I PAVED GUTTER (MOD) L.F.
E-1	976+50	978+65	119.7	
E-2	978+75	979+40	28.9	
E-3	978+75	—		10
E-4	979+50	—		10
SHEET TOTAL			1486	20

A-42
STA. 971+25
1.25' LT. ℄
I-8 Nº 2A-6 INLET
WINDOW EL. 893.49
℄ 12" I-2 890.08

A-43
STA. 971+30.71
38' LT. ℄
I-8 Nº 6 C.B.
GRATE 893.72
℄ 12" I-2 890.45

A-44
STA. 971+84.50
42.5' LT. ℄
I-8 Nº 6 C.B.
GRATE EL. 894.13
℄ 12" I-2 890.88

A-46
STA. 975+00 ℄
I-8 Nº 2-6 MODIFIED INLET
WINDOW ℄ (LT & RT.) 897.02
℄ 12" I-2 893.61
℄ 8" I-4 893.77

A-41
STA. 971+25
6' LT. ℄
I-8 Nº 1 M.H.
COVER EL. 893.76
℄ 12" I-2 887.84
℄ 8" I-4 888.17

A-45
STA. 975+00
I-8 Nº 1 M.H. (6.0' LT. ℄)
COVER ELEV. 897.31
℄ 12" I-2 891.39
℄ 12" I-2 893.55

A-48
STA. 979+50
I-8 Nº 2-2A C.B. (84' RT. ℄)
WINDOW ELEV. 887.20
℄ 12" I-2 885.03

A-47
STA. 978+75
I-8 Nº 2-2A C.B. (106' LT. ℄)
WINDOW ELEV. 870.33
℄ 12" I-2 868.16

FOR PROFILES OF PROP. I-2 NOT SHOWN THIS SHEET SEE SHEET # 80

STA. 976+58 PROPOSED 48" COMBINATION SEWER ℄ 882.23 1.00' CONC. ENCASEMENT

℄ EDWARDS ST. STRUCTURE

P-41 125'-12" I-2 @ 0.005 ft

P-46 375'-12" I-2 @ 0.0047

+0.94%

STA. 970+00 TO 980+00

PROPOSED STRUCTURE MAH-18-1855
TYPE: CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE DECK & SUBSTRUCTURE.
SPANS: 48', 60', 48' C/C BRGS.
ROADWAY: 100'-0" F/F PARAPETS.
LOADING FREQUENCY: C.F. 2000 ADEQUATE FOR A.A.S.H.O. ALTERNATE LOADING.
SKEW: 0°16'06" R.F. BRIDGE SQUARE
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLAB: 25' LONG AS-1-54
SUPERELEVATION: NONE
TRAFFIC COUNT: 3400 ADT 1979
ALIGNMENT: STRAIGHT TANGENT.

PRINTED IN U.S.A. BY R. R. DONNELLEY & SONS CO. FOR FHWA AND OHIO DEPT. OF HIGHWAYS
PHOENIX LITHOTYPE CO., CHICAGO

FED. RD.	STATE	PROJECT	
2	OHIO		

42 / 492

MAH-18-17.20

SEE SHEET 248 249 FOR MARSHALL ST. IMPROVEMENT

℄ - MARSHALL ST.

BEGIN SHEET – STA. 980+00

END SHEET – STA. 990+00

NOTE 114 PAVED GUTTER TO BE INCLUDED IN THE MARSHALL ST. QUANTITIES

END APPROACH SLAB STA. 981+04.75

BEGIN MEDIAN & CURB STA. 980+73.75

EXIST. 36" C.I.P. FOR DETAILS SEE SHEET № 94

EXIST. 30" C.I.P. FOR DETAILS SEE SHEET № 94

PAVED SHOULDER

S-84°47'24"-E

STA. 983+27 6"I-4 PLUGS

TYPE 6 CURB

STA. 983+23 6"I-4 PLUGS

STA. 984+45 6"I-4 PLUG

STA. 985+66 6"I-4 PLUG

STA. 980+90 6"I-4 PLUGS

BRIDGE № MAH-18-P-56

44° EXP. STRUCTURE RAMP "F" STA. 5+60

FOR CONSTRUCTION DETAILS & ALIGNMENT OF RAMP "H" SEE SHEET № 55 & 65

SEE SHEET № 55 RAMP "F"

IRON PIN-S.W. CORNER H'SE #824

P.K. NAIL

THUB BY FENCE H'SE # 830

IRON PIN 2' INSIDE COR. OF STONE WALL

R.R. SPIKE IN WALK 8" N. OF S.E. COR. YOA BLDG.

THUB BY SIDE GATE H'SE # 817

T. HUB AT S. SIDE OF DRIVE

MARSHALL

LOC. TAN.

℄ EXP.

FOR SUMMARY OF EDWARD'S ST. REMOVAL ITEMS SEE SHEET 262

℄ PLUM ST.

℄ WEST AVE.

PROPOSED RELOCATED 16" C.I.P. FOR DETAILS SEE SHEET № 94

MATCH LINE-3 RAMP "H" REMOVAL QUANTITIES

MATCH LINE-4 RAMP "H" REMOVAL QUANTITIES

RAMP "H"

RAMP "J"

COBBLESTONE OR BRICK CEMENT WEARING SURFACE

NO CURB: CONCRETE GUTTER

EXISTING SECTION PLUM ST.

BRICK – CONCRETE WEARING SURFACE

STONE CURB

EXISTING SECTION WEST AVE.

℄ REFERENCE MONUMENTS
986+75.49
989+75.49

NOTE: THE ℄ OF EDWARDS IS AT STA. 979+99.5 SAID ℄ IS NOT PARALLEL TO THE MATCH LINE.

B.M. # 18-A R.R. SPIKE IN 34" MAPLE 105' S. OF INT. HIGH & EDWARDS & 18' W. OF ℄ EDWARDS. ELEV. 929.55

B.M. # 19-A R.R. SPIKE IN W. SIDE 18" W. CHERRY 140' S. OF INT. HIGH & PLUM, LOCA. 18' E. OF ℄ PLUM ST. ELEV. 932.18

B.M. # 20-A R.R. SPIKE IN E. SIDE 18" MAPLE LOCA. 42' E. OF HIGH & WEST ST. INT. & 21' S. OF ℄ HIGH ST. ELEV. 933.70

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS					
CODE	LOCATION ℄ STATION	# 1 M.H. EACH	2-2A C.B. EACH	#2-6/#2-8 MOD. INLET	#2-6/#2-8 MOD. INLET
A-49	981+07 ℄			1	
A-50	981+07 84' RT. ℄	1			
A-51	981+50 85' RT. ℄		1		
A-53	985+60 ℄				1
A-54	989+00 6' LT. ℄	1			
A-55	989+ 54' RT. ℄		1		
SHEET TOTAL		2	2	1	1

ESTIMATED QUANTITIES I-2 PIPES LIN. FT.						I-5 PIPE SPEC. EACH 12"-45° BENDS M-64(6)
CODE	LOCATION FROM	TO	CL. 'B' STORM SEWER UNDER PAVT. OR APPR. 12"	15"	CLASS 'A' STORM SEWER 12" M-64(6)	15"
P-50	A-49	A-50	55		27	2
P-51	A-51	A-50				40
P-53	A-53	H-1	63			
P-54	A-55	A-54		57		
P-55	A-54	990+00		98		
P-56	A-50	4+44.84 EDWARDS				85
SHEET TOTAL			118'	155	27	125 2

ESTIMATED QUANTITIES I-21 PCC MEDIAN			
CODE	LOCATION FROM	TO	S.Y.
N-8	980+79.75	990+00	606

PC-4 ENDWALLS		
CODE	LOCATION	21" CLASS 'B' CONC. CU. YDS.
H-1	985+60 66' LT.	0.23

℄ CURVE DATA № 4

Δ = 74° 52' 50"
Dc = 2° 45'
Rc = 2083.48'
Ls = 300'
Θs = 4° 07' 30"
Lc = 2422.93'
Ts = 1746.61'
Es = 542.86'

P = 1.80'
K = 149.97'
x = 299.84'
y = 7.197'
L.T. = 200.06'
S.T. = 100.05'
L.C. = 299.93'

FOR PROFILES OF PROP. I-2 NOT SHOWN THIS SHEET SEE SHEET № 81 80 & 82

℄ PLUM ST.

P.V.I. STA. 984+66.12 ELEV. 903.66

ESTIMATED QUANTITIES I-15 GUARD RAIL & BARRIER RAIL			
CODE	LOCATION	BARRIER RAIL	GUARD RAIL
R-10	℄	925	
R-10A	LT.		925
R-10B	RT.		
SHEET TOTAL		925'	925'

+0.94%

-3.08%

500' V.C.

EL. 903.92

EL. 898.57

A-49
STA. 981+07 ℄
I-8 № 2-G MODIFIED INLET
WINDOW EL. 902.73
℄ 12" I-2 898.78
℄ 8" I-4 899.11

A-50
STA. 981+07
84' RT. ℄
I-8 № 1 M.H.
COVER EL. 890.10
℄ 12" I-2 884.14
℄ 15" I-2 883.89

A-51
STA. 981+50
85' RT. ℄
I-8 № 2-2A C.B.
WINDOW EL. 889.30
℄ 15" I-2 886.86
℄ 8" I-4 887.44

A-53
STA. 985+60 ℄
I-8 № 2-8 MODIFIED INLET
WINDOW EL. 902.23
℄ 12" I-2 898.82
℄ 4" I-4 899.49

A-55
STA. 986+00
54' RT. ℄
I-8 № 2-2A C.B.
WINDOW EL. 888.70
℄ 12" I-2 886.53

STA. 986+78.5
EXIST. 36" R.C.P.
℄ 879.00
TO BE ENCASED
1' CONCRETE

986+90
EXIST. 30" C.I.P.
℄ 878.8
TO BE ENCASED
1.0 CONCRETE

A-54
STA. 989+00
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 892.06
℄ 15" I-2 885.98

STA. 989+31
PROP. 16" C.I.P.
℄ 881.75
1.0' CONC. ENCASEMENT

P-55
100'-15" I-2
@ .03G2

I-4 PIPE UNDERDRAINS LIN. FT.						I-5 PIPE SPECIALS EACH	
CODE	LOCATION FROM	TO	6" PIPE	DEEP OR SHALLOW	8" OUTLET PIPE M-6.4a	6" 30° BEND	6"x8" TEE
U-1	980+90	981+50	58	D			1
U-2	981+05	A-49		D	30		
U-3	980+90 981+50	A-49	33	D	20		
U-4	980+90	981+11.06	21	D			
U-5	981+50	983+23	173	S			
U-6	981+50	983+23	173	S			
U-7	983+27	988+50	523	S			
U-8	983+27	A-52	220	S	10	1	
U-9	984+45	988+50	405	S			
U-10	988+50	990+00	150	D			
U-11	985+66	990+00	434	S			
U-12	988+50	990+00	150	D			
SHEET TOTAL			2340'		60'	1	1

EROSION CONTROL					
CODE	LOCATION FROM	TO	L-10 SOD S.Y.	I-10 DUMPED ROCK CU. YDS.	I-14 TYPE I PAVED GUTTER (MOD.) LIN. FT.
E-1	985+60	986+25	36		
E-2	985+60	–		1	
E-3	985+90	986+00			10
E-4	981+50	981+60			10
SHEET TOTAL			36'	1	20'

ESTIMATED QUANTITIES I-12 CONCRETE CURB			
CODE	LOCATION FROM	TO	TYPE 6 L.F.
G-11	980+79.75	990+00	1807'

ESTIMATED QUANTITIES E-8 REMOVABLE ITEMS						
CODE	LOCATION FROM	TO	CURB L.F.	RIGID PAV'T. S.Y.	SIDEWALK S.F.	GUTTER L.F.
B-1	ML-3	MARSHALL			2560	
B-2	ML-4	RAMP "J"			2350	
X-1	ML-4	RAMP "J"	468			
K-1	ML-3	MARSHALL		707		
K-2	ML-4	RAMP "J"		624		
S-1	ML-3	MARSHALL				250
SHEET TOTAL			468	1331	4910	250

STA. 980+00 TO 990+00

PLOTTED 10/27/71 PLOTTED BY R.E.S. DRAWING SUBMITTED BY
PROFILE
THIS SHEET
THIS ROAD
PRINTED IN U.S.A. THE RIGHT TO USE THIS IMAGE AND PRINT IT IN ANY PROCESS, INTENDED OR, CHICAGO

FOR MARSHALL ST. IMPROVEMENT
SEE SHEET Nº 248 260

FOR CONSTRUCTION DETAILS ~ NOSE RAMP "J" & MAINLINE SEE SHEET Nº 58 & 67

PROPOSED 15" COMB. SEWER - FOR DETAILS SEE SHEET Nº 97 —

FOR WALL DETAILS SEE SHEETS ___ TO ___

T. HUB S.W. COR. HSE Nº 514
10.93
ANGLE POINT R.R. SPIKE & HILKER
54.78
51.54'
T. HUB S.W. COR. HSE Nº 509
IRON PIN BY N.W. COR. PARKING LOT FENCE

ESTIMATED QUANTITIES 5.24 REMOVAL OF EXIST. STRUCTURES		
CODE	TYPE	QUANTITY
W-1	WALL	1
W-2	WALL	1

FED. RD.	STATE	PROJECT	
2	OHIO		

43
492

MAH-18-17.20

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS

CODE	LOCATION ℄ STATION	#1 M.H. EACH	2-2A C.B. EACH	#6 C.B. EACH	2A-10 INLET EACH
A-56	994+50 1.25' LT. ℄				1
A-57	994+60 6' LT. ℄	1			
A-58	994+50 54' RT. ℄		1		
A-59	13+80 RAMP 'H' 19' RT. ℄		1		
A-60	997+00.41 46' LT. ℄			1	
A-61	997+10 6' LT. ℄	1			
A-62	996+86.03 38' RT. ℄			1	
A-63	999+50 6' LT. ℄	1			
A-64	999+50 1.25' LT. ℄				1
SHEET TOTAL		3	2	2	2

℄ REFERENCE MONUMENTS
995+00
1000+00

ESTIMATED QUANTITIES I-2 PIPES LIN. FT.

CODE	LOCATION FROM	TO	CLASS "B" STORM SEWERS UNDER PAV'T OR APPR. 12"	15"	18"	21"	24"	27"
P-55	990+00	A-57		458				
P-57	A-56	A-57	9					
P-58	A-58	A-57				57		
P-59	A-59	A-58			43			
P-60	A-57	A-61					246	
P-61	A-60	A-61	39					
P-62	A-62	A-61	48					
P-63	A-61	A-63						236
P-64	A-63	1000+00						48
P-65	A-64	A-63	2					
SHEET TOTAL			98	458	43	57	246	284

WALTER ST.
BRICK CEMENT
STONE CURBS

HILKER ST.
SMITH TO ℄ PT.
BITUMINOUS SURFACE
MACADAM BASE

SMITH ST.
HIGH TO HILKER
BRICK CEMENT
STONE GUTTERS

SMITH ST.
HILKER TO MARSHALL
BITUMINOUS SURFACE
COBBLESTONE BASE
STONE GUTTERS

℄ CURVE DATA Nº 4

Δ = 74° 52' 50"
Dc = 2° 45'
Rc = 2083.48'
Ls = 300'
Θs = 4° 07' 30"
Lc = 2422.93'
Ts = 1746.61'
Es = 542.86'

P = 1.80'
K = 149.97'
x = 299.84'
y = 7.197'
L.T. = 200.06'
S.T. = 100.05'
L.C. = 299.93'

ESTIMATED QUANTITIES I-21 P.C.C. MEDIAN

CODE	LOCATION FROM	TO	S.Y.
N-9	990+00	1000+00	655.5

ESTIMATED QUANTITIES I-12 CONCRETE CURB

CODE	LOCATION FROM	TO	TYPE-6 L.F.
G-12	990+00	1000+00	1078

FOR CONSTRUCTION DETAILS NOSE RAMP "H" & MAINLINE SEE SHEET Nº 57 & 66

B.M.#15 TOP OF STEM ON HYDT. N. SIDE OF MARSHALL @ SMITH ELEV. 848.78

B.M.# 21 TOP OF STEM ON HYDT. N.W. COR. HIGH & SMITH ELEV. 926.02

DETAIL "A"

FOR PROFILES OF PROPOSED I-2 NOT SHOWN THIS SHEET SEE SHEET Nº 81.

A-57
STA. 994+60
6' LT. ℄
I-8 Nº 1 M.H.
COVER EL. 875.86
℄ 12" I-2 872.21
℄ 15" I-2 865.70
℄ 21" I-2 865.20
℄ 24" I-2 864.95

A-61
STA. 997+10
6' LT. ℄
I-8 Nº 1 M.H.
COVER EL. 868.16
℄ 12" I-2 863.07
℄ 12" I-2 866.85
℄ 24" I-2 859.95
℄ 21" I-2 859.70

A-63
STA. 999+50
6' LT. ℄
I-8 Nº 1 M.H.
COVER EL. 862.88
℄ 12" I-2 859.02
℄ 24" I-2 855.15
℄ 27" I-2 854.90

A-56
STA. 994+50
1.25' LT. ℄
I-8 Nº 2A-10 INLET
WINDOW EL. 875.80
℄ 12" I-2 872.39
℄ 8" I-4 872.72

A-60
STA. 997+00.41
46' LT. ℄
I-8 Nº 6 C.B.
GRATE EL. 870.42
℄ 12" I-2 867.67

A-58
STA 994+50
54' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 870.91
℄ 18" I-2 866.67
℄ 21" I-2 866.42

A-62
STA. 996+86.03
38' RT. ℄
I-8 Nº 6 C.B.
GRATE EL. 866.38
℄ 12" I-2 863.58
℄ 8" I-4 863.91

A-59
RAMP "H" STA. 13+80
19' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 870.32
℄ 18" I-2 867.61

A-64
STA. 999+50
1.25' LT. ℄
I-8 Nº 2A-10 INLET
WINDOW EL. 862.51
℄ 12" I-2 859.10
℄ 8" I-4 859.43

STA. 995+38
PROPOSED VIT. PIPE COMBINATION SEWER
℄ 15" 855.92
1.0' CONC. ENCASEMENT

I-4 UNDERDRAINS

CODE	LOCATION FROM	TO	DEEP OR SHALLOW	6" PIPE	8" PIPE OUTLET M-6.4a	I-5 PIPE SPECIALS EACH 6" 90° BEND
U-1	990+00	991+00	D	157	10	1
U-2	990+00	994+00	S	440	10	
U-3	990+00	992+25	D	225		
U-4	992+25	996+86	S	451	10	
U-5	994+56	999+50	S	484	10	
U-6	999+56	1000+00	S	44		
U-7	999+00	1000+00	S	100		
SHEET TOTAL				1901	40	1

EROSION CONTROL

CODE	LOCATION FROM	TO	L-10 SOD S.Y.	I-10 DUMPED ROCK CU.YDS.	I-14 TYPE I PAVED GUTTER (MOD.) LIN. FT.	I-14 TYPE I PAVED GUTTER LIN. FT.
E-1	995+00	1000+00	278			
E-2	995+72	—				52
E-3	995+75			38		
E-4	RAMP 'H' 15+80				20	
SHEET TOTAL			278	38	20	52

ESTIMATED QUANTITIES I-15 GUARD RAIL & BARRIER RAIL

CODE	LOCATION FROM	TO	BARRIER RAIL (L.F.)	GUARD RAIL (L.F.)
R-11	990+00 ℄	1000+00 ℄	1000	
R-11-A	990+00 LT.	995+50 LT.		550
R-12	SMITH			50
R-13	SMITH			50
SHEET TOTAL			1000	650

ESTIMATED QUANTITIES E-8 REMOVABLE ITEMS

CODE	LOCATION FROM	TO	CURB	RIGID PAV'T.	NON RIGID PAV'T.	SIDEWALK	GUTTERS
B-1	SOUTH R/W	NORTH R/W				3000	
B-2	SMITH	1000+00				4160	
B-3	SMITH	WALL				1700	
X-1	SMITH	1000+00	850				
K-1	SOUTH R/W	NORTH R/W		533			
K-2	SMITH	1000+00		860			
K-3	SMITH	WALL			287		
S-1							600
SHEET TOTAL			850	1393	287	8860	600

STA. 990+00 to 1000+00

NOTE: ADJUST COVER OF M.H. A-69 TO CONFORM TO 2:1 SLOPE.

FOR STORM SEWER PROFILES FROM A-65 TO A-70 SEE SHEET Nº 81

FOR OAK HILL IMPROVEMENT SEE SH'T. Nº 286

FOR STORM SEWER PROFILE FROM A-10 TO B-1 SEE SHEET Nº 98

℄ REFERENCE MONUMENTS
STA. 1005+00
STA. 1010+00

FOR DETAIL & QUANTITIES OF RAMP 'J' SEE SHEET Nº 52 & 6

FOR HIGH ST. IMPROVEMENT SEE SHEET Nº 272 - 286

FOR PIKE ST. IMPROVEMENT SEE SH'T. Nº 292

FOR DETAILS & QUANTITIES OF RELOC. PIKE ST. SEE SHEET Nº 292

FOR SPECIAL COMPACTION SEE CROSS SECTIONS & GEN. NOTES SH. Nº 8

PROPOSED 54" SEWER SEE SHEET Nº 98

BRICK CEMENT STONE CURB
TYPICAL SECTION
EXIST. WALTER ST.

STONE CURB
ASPHALT SURFACE
BRICK CEMENT BASE
TYPICAL SECTION
EXIST. PIKE ST.

FED. RD.	STATE	PROJECT	
2	OHIO		

44
192

MAH-18-17.20

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS

CODE	LOCATION & STATION	#1-M.H. EACH	#2A-6 INLET EACH	#2-2 A C.B. EACH	#2A-8 INLET EACH	# 2 M.H. EACH
A-65	1000+41.48 6' LT. ℄	1				
A-66	1000+41.48 1.25' LT. ℄		1			
A-67	1001+50 6' LT. ℄	1				
A-68	1001+50 1.25' LT. ℄		1			
A-69	1001+50 88' LT. ℄	1				
A-70	0+05 PIKE ST. ℄					1
A-72	1003+50 100' LT. ℄	1				
A-73	1003+50 115.5' LT. ℄			1		
A-74	1003+50 81.5' RT. ℄			1		
A-76	1006+30 107' LT. ℄			1		
A-77	1007+50 92' RT. ℄			1		
A-78	1007+10 1.25' RT. ℄				1	
SHEET TOTAL		4	2	4	1	1

ESTIMATED QUANTITIES I-21 PORTLAND CEMENT CONCRETE MEDIAN (SQ. YDS.)

CODE	FROM	TO	QUANT.
N-10	1000+00	1005+01.81	333
N-11	1006+87.22	1010+00	215
SHEET TOTAL			548

ESTIMATED QUANTITIES I-12 CONCRETE CURB (L.F.)

CODE	FROM	TO	TYPE 6
G-15	1000+00	1005+01.81	1002
G-16	1006+87.22	1010+00	616
SHEET TOTAL			1618

ESTIMATED QUANTITIES I-15 GUARDRAIL & BARRIER RAIL

CODE	LOCA.	G.R.(L.F.)	B.R.(L.F.)
R-14	℄		512.5
R-14A	LT.	325	
R-14B	RT.	500	
R-15	℄		312.5
R-15A	LT.	325	
R-15B	RT.	275	
SHT. TOTAL		1425'	825.0

ESTIMATED QUANTITIES E-8 REMOVAL ITEMS

CODE	FROM	TO	CURB (L.F.)	PAVEMENT RIGID (S.Y.)	SIDEWALK (S.F.)
B-1	1000+00	OAKHILL			5600
B-2	OAKHILL	1010+00			3440
X-1	1000+00	OAKHILL	1110		
X-2	OAKHILL	1010+00	710		
K-1	1000+00	OAKHILL		1110	
K-2	OAKHILL	1010+00		710	
SHEET TOTAL			1820	1820	9040

B.M.# 39-A R.R. SPIKE IN N. SIDE OF 28" MAPLE, 24' S. OF INT. PIKE & OAKHILL AND LOCA. 80' W. OF ℄ OAKHILL AVE.
ELEV. 861.87

B.M.# 31 TOP OF STEM ON HYDT. N. SIDE OF WALTER ST.
ELEV. 845.71

B.M.# 40 TOP OF BOLT WEST SIDE OF HYDT. ON SOUTH SIDE OF PIKE ST. @ ANGLE PT.
ELEV. 846.45

EROSION CONTROL

CODE	LOCATION FROM	LOCATION TO	L-10 SOD S.Y.	I-14 TYPE-1 PAVED GUTTER L.F.
E-1	1000+00	1003+40	189	
E-2	1003+60	1005+00	78	
E-3	1007+60	1010+00		240
SHEET TOTAL			267	240

I-4 UNDERDRAINS LIN. FT.

CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" OUT. PIPE M-6.4 a	I.S PIPE SPECIALS 6'-30° BEND	I.S PIPE SPECIALS 6'x6' TEE
U-1	1000+00	1000+41.48	S	30	10	1	
U-2	1000+00	1001+00	D	114	10		1
U-3	1005+13	1001+00	S	413			
U-4	1005+01	1000+41.48	S	447	10	1	
U-5	1007+10	1010+00	S	340	10	2	1
U-6	1006+95	1010+00	S	304	2		1
SHEET TOTAL				1648	42'	4	3

EROSION CONTROL

CODE	LOCATION	
	FROM	TO
E-4		20
E-5		20
E-6		10
E-7		10

℄ CURVE DATA Nº 4

Δ = 74° 52' 50"	P = 1.80'
D_c = 2° 45'	K = 149.97'
R_c = 2083.48'	x = 299.84'
L_s = 300'	y = 7.197'
Θ_s = 4° 07' 30"	L.T. = 200.06'
L_c = 2422.93'	S.T. = 100.05'
T_s = 1746.61'	L.C. = 299.93'
E_s = 542.86'	

ESTIMATED QUANTITIES - I-2 PIPES

CODE	LOCATION FROM	LOCATION TO	CLASS 'B' STORM SEWER UNDER PAVEMENT & APPROACHES 12"	27"	33"	18" M-6.6d	36" M-6.6 b M-6.8 b	CL. 'B' STORM SEWER 15"	12"	CL 'A' STORM SEWER 12" M-6.4 c	I.S PIPE M-6.4 c SPECIALS 12"x30° BEND EACH
P-64	1000+00	A-65		40							
P-66	A-67	A-65	105								
P-67	A-66	A-65	2								
P-68	A-68	A-67	2								
P-69	A-65	A-69		*136							
P-70	A-69	A-72			205						
P-71	A-72	A-70					222				
P-74	A-76	A-80							72		
P-75	A-77	54" SEWER						54			
P-76	A-73	A-72							12		
P-77	A-74	A-72				178					
P-83	A-78	A-71	80							60	2
SHEET TOTAL			189'	4	205	178	222	54'	84'	60'	2'

A-65
STA. 1000+41.48
6' LT. ℄
I-8 Nº 1 M.H.
COVER EL. 862.45
FE. 12" I-2 854.78
FE. 12" I-2 858.60
FE. 27" I-2 853.53
FE. 8" I-4 858.62

A-67
STA. 1001+50
6' LT. ℄
I-8 Nº 1 M.H.
COVER EL. 863.06
FE. 12" I-2 857.14
FE. 12" I-2 859.21

A-69
STA. 1001+50
88' LT. ℄
I-8 Nº 1 M.H.
COVER EL. 849.00
FE. 27" I-2 837.67
FE. 33" I-2 837.17

A-70
STA. 0+05 PIKE ST. ℄
I-8 Nº2 M.H.
COVER EL. 848.91
FE. 36" I-2 834.68

A-72
STA. 1003+50
100' LT. ℄
I-8 Nº 1 M.H.
COVER EL. 848.00
FE 33" I-2 836.09
FE. 36" I-2 835.84
FE. 12" I-2 837.84
FE. 18" I-2 837.34

A-73
STA. 1003+50
115.5' LT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 840.17
FE. 12" I-2 838.00

A-74
STA. 1003+50
81.5' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 848.20
FE. 18" I-2 845.49

A-66
STA. 1000+41.48
1.25' LT. ℄
I-8 Nº 2A-6 INLET
WINDOW EL. 862.08
FE. 12" I-2 858.67

A-68
STA. 1001+50
1.25' LT. ℄
I-8 Nº 2A-6 INLET
WINDOW EL. 862.63
FE. 12" I-2 859.28

A-76
STA. 1006+90
107' LT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 850.50
FE. 12" I-2 848.33

A-77
STA. 1007+50
92' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 854.80
FE. 15" I-2 852.34
FE. 8" I-4 852.67

A-78
STA. 1007+10
1.25' LT. ℄
I-8 Nº 2A-8
TOP OF CURB 879.34
WINDOW EL. 878.67
FE. 12" I-2 874.26

PROPOSED STRUCTURE MAH-18-1904
TYPE: STEEL BEAM WITH REINFORCED CONCRETE DECK & SUBSTRUCTURE
SPANS: 49'-0", 70'-0", 56'-0" C/C BRGS.
ROADWAY: 88'-0" F/F PARAPETS
LOAD FREQUENCY: C.F. 2000 ADEQUATE FOR A.A.S.H.O. ALTERNATE LOADING
SKEW: 23° 54' 16" R.F.
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLAB: 25' LONG AS-1-54
SUPERELEVATION: .065 "/'
ALIGNMENT: 2°45'00" RT.
TRAFFIC COUNT: 26,000 ADT. 1979

STA. 0+54.83 PIKE ST. (RELOC.)
I-8 YNGST. TYPE II INLET
12.0' RT. ℄ PIKE ST.
TOP OF CURB 848.73
WINDOW EL. 847.98
FE 12" I-2 844.67
FE. 12" I-2 844.23
FE. INLET 842.98

STA. 1006+90
I-8 Nº 2-2A C.B.
107' LT. ℄
WINDOW EL. 850.50
FE. 12" I-2 848.33

STA. 1007+50
I-8 Nº 2-2A C.B.
WINDOW EL. 854.80
FE. 8" I-4 852.67
FE. 15" I-2 852.34

SEWER PROFILES
HORIZ. 1" = 20'
VERT. 1" = 5'

STA. 1000+00 TO 1010+00

FED. RD.	STATE	PROJECT	
2	OHIO		

45/492

MAH-18-17.20

18'-0"

ASPHALT SURFACE
BRICK CEMENT BASE
STONE CURB

TYPICAL SECTION
EXIST. PIKE ST.

FOR DETAILS & QUANTITIES OF RELOC., PIKE ST. SEE SHEET Nº 29&295

NOTE:
FOR DETAIL OF SCUPPER DRAINS SEE SHEET Nº 82

RENNER BREWERY

EXIST. 68" COMBINATION SEWER FOR DETAILS SEE SHEET Nº 96

PROPOSED RELOC. 54" COMBINATION SEWER - FOR DETAILS SEE SHEET Nº

BEGIN SHEET — STA. 1010+00

END SHEET — STA. 1020+00

℄ PIKE ST.

RELOC. PIKE ST. STA. 9+90

"M" CELLAR

EMPTY BOTTLE STORAGE B'L'D'G.

TRUCK GARAGE

FOR DETAIL & QUANTITIES OF RAMP 'L' SEE SHEET Nº 6G & 6B

FOR CURB & MEDIAN QUANTITIES LT. OF ℄ BETWEEN APPROACH SLABS, SEE SHEET Nº STRUCTURE Nº MAH-18-1023

BEGIN APPROACH SLAB 1019+18.75

END APPROACH SLAB 1015+83.75

BEGIN TAPER STA. 1014+30 OF RAMP 'L' STA. 1013+70 ℄ EXP.

STA. 8+83.47 ℄ RAMP 'L' STA. 1013+17.15 ℄ EXP.

RAMP 'L'

RAMP 'K'

STA. 1013+98.42 RAMP 'K' STA. 0+00 ℄ EXP.

STA. 1016+98.42 RAMP 'K' STA. 1018+25 ℄ EXP.

FOR DETAIL & QUANTITIES OF RAMP 'K' SEE SHEET Nº 5B & 6B

FOR SPECIAL COMPACTION SEE CROSS SECTIONS & GEN. NOTES SH. Nº 8

BITUMINOUS SURFACED PARKING AREA

HOSPITAL SERVICE B'L'D'GS

B.M.#41 TOP OF STEM ON HYDT. @ S. SIDE OF PIKE ST. W. OF RENNER BREWERY. ELEV. 850.67

B.M.#42 TOP OF STEM ON HYDT. @ SOUTH SIDE OF PIKE ST. IN FRONT OF BREWERY. ELEV. 852.80

P-84 P-85 P-86 P-87 P-88 P-90 P-91 P-92 P-93

S-9°54'34"-E

B-1 K-1 X-1 R-17A R-17B R-16 N-12 U-1 U-2 G-18 G-17 A-84 A-85 A-86 A-87 A-88 E-1 E-2 E-3 E-4 E-5 E-6 E-7 A-90 N-13 A-91 N-14 G-19 A-92

ESTIMATED QUANTITIES I-21 PORTLAND CEMENT CONCRETE MEDIAN (SQ. YDS.)

CODE	FROM	TO	QUANT.
N-12	1010+00	1015+84.50	385.5
N-13	1015+84.50	1019+18	111
N-14	1019+18	1020+00	48.8
SHEET TOTAL			545.3

ESTIMATED QUANTITIES E-8 REMOVAL ITEMS

CODE	FROM	TO	CURB (L.F.)	PAVEMENT RIGID (S.Y.)	SIDEWALK (S.F.)
B-1	1010+00	9+90			5300
X-1	1010+00	9+90	1060		
K-1	1010+00	9+90		1060	
SHEET TOTAL			1060	1060	5300

ESTIMATED QUANTITIES I-12 CONCRETE CURB (L.F.)

CODE	FROM	TO	TYPE G
G-17	1010+00	1020+00	990.7
G-18	1010+00	1015+84.5	571.2
G-19	1019+18	1020+00	73.5
G-17A	1012+30	1013+95	165
SHEET TOTAL			1800.4

ESTIMATED QUANTITIES I-15 GUARDRAIL & BARRIER RAIL

CODE	LOCA.	G.R. (L.F.)	B.R. (L.F.)
R-16	℄		1000
R-17	R.T.	600	
R-17A	LT.	575	
R-17B	RT.	200	
SH'T. TOTAL		1375'	1000'

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS

CODE	LOCATION & STATION	#2A-12 INLET EACH	#1 M.H. EACH	#2-2A C.B. EACH	#6 C.B. EACH	#2-8 MOD. INLET EACH
A-84	1010+50 1.25' LT. ℄	1				
A-85	1010+50 60' RT. ℄		1			
A-86	1015+50 6.0' RT. ℄		1			
A-87	1015+50 63.0' RT. ℄			1		
A-88	1015+50 132.0' RT. ℄			1		
A-90	1017+25 4.5' RT. ℄				1	
A-91	1019+25 ℄					1
A-92	1019+30.6 61.0' LT. ℄			1		
SHEET TOTAL		1	2	3	1	1

ESTIMATED QUANTITIES I-2 PIPES LIN. FT. — I-5 PIPE SPEC.

CODE	LOCATION FROM	LOCATION TO	C.L. "B" ST. SEWER UNDER PVM'T. OR APPR. 12"	8"	15"	C.L. "A" STORM SEWER L.F. 18"	12"M-G.4(6)	18"M-G.4(6)	12"x15" TEE EACH	12"x15" WYE EACH	18" 30° BEND M-G.4(6) EACH	8" 30° BEND EACH	8"x18" TEE EACH
P-84	B-1	A-85				108		78			2		
P-85	A-85	A-86				496							
P-86	A-84	A-85	7										
P-87	A-88	A-87					73						
P-88	A-87	A-86				54							
P-85	1015+88	1019+23		180								2.0	
P-90	A-90	P-91	2										
P-91	A-86	1020+00			316				1	2			2.0
P-92	A-91	A-92	87										
P-93	A-91	P-90	4										
SHEET TOTAL			100	180	316	658	73	78	1	2	2	2.0	2.0

℄ REFERENCE MONUMENTS
STA. 1013 + 98.42
STA. 1016 + 98.42

℄ CURVE DATA Nº 4

Δ	= 74°52'50"	P	= 1.80'
D_C	= 2°45'	K	= 149.97'
R_C	= 2083.48'	X	= 299.84
L_S	= 300'	Y	= 7.157'
Θ_S	= 4°01'30"	L.T.	= 200.06'
L_C	= 2422.93	S.T.	= 100.05
T_S	= 1746.61	L.C.	= 299.93
E_S	= 542.86		

A-84
STA. 1010 + 50
I-8 Nº 2A-12 (1.25' LT. ℄)
TOP OF CURB 890.55
WINDOW EL. 889.92
FE 12" I-2 886.51

A-85
STA. 1010 + 50
I-8 Nº 1 M.H. (6.0' RT. ℄)
COVER EL. 889.89
FE 18" I-2 883.43
FE 12" I-2 886.11

A-86
STA. 1015 + 50
I-8 Nº 1 M.H. (6.0' RT. ℄)
COVER EL. 906.29
FE 15" I-2 899.03
FE 18" I-2 898.78

A-87
STA. 1015 + 50
I-8 Nº 2-2A C.B.
WINDOW EL.
FE 15" I-2.

A-88
STA. 1015 + 50
I-8 Nº 2-2A C.B.
WINDOW EL. 930.25
FE 15" I-2 M-G.4(c) 928.08

A-89
STA. 1015 + 88.5
I-8 Nº 2A-10 INLET (1.25' LT. ℄)
TOP OF CURB 908.12
WINDOW EL. 907.45
FE 12" I-2 904.04

A-90
STA. 1017 + 25
I-8 Nº G C.B. (4.5' RT. ℄)
GRATE EL. 912.03
FE 12" I-2 908.36

A-91
STA. 1019 + 25
I-8 Nº 2-8 INLET (MODIFIED)
TOP OF CURB 919.12
WINDOW EL. 918.45
FE 12" I-2 915.04
FE 8" I-4 915.37

A-92
STA. 1019 + 30.6
I-8 Nº 2-2A C.B. (61.0' LT. ℄)
GRATE EL. 919.31
FE 12" I-2 917.14

FOR PROFILES OF PROPOSED I-2 NOT SHOWN ON THIS SHEET SEE SHEET Nº 83

P-85: 500'-18" I-2 @ .0306; +3.26%; FE 884.88; FE 889.74

P-91: 500'-15" I-2 @ .0358; +3.26%; FE 911.97; FE 918.40

PROPOSED STRUCTURE MAH-18-1923
TYPE: CONTINUOUS CONC. SLAB DECK WITH CAPPED PILE SUBSTRUCTURE.
SKEW: 0°00'
SPANS: SEE BRIDGE, SHEET Nº 417
ROADWAY: 41'-10" F/C CURBS WESTBOUND LANE
LOAD FREQUENCY: C.F. 2000 ADEQUATE FOR AASHO OR ALTERNATE.
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLABS: 25' LONG
ALIGNMENT: SAME AS ROADWAY (SUBSTRUCTURE STRAIGHT)
SUPERELEVATION: VARIES

EROSION CONTROL

CODE	LOCATION FROM	LOCATION TO	L-10 SOD S.Y.	I-14 PAVED GUTTER L.F. TYPE I	TYPE I (MOD)
E-1	1015+60	1018+50		290	
E-2	1015+60	1017+00	78		
E-3	1010+00	1014+00		400	
E-4	1012+30	1015+40		210	
E-5					10
E-6					10
E-7					20
	TOTAL		78'	900	40

I-4 UNDERDRAINS LIN. FT.

CODE	LOCATION FROM	LOCATION TO	DEED OR SHALLOW	6" PIPE	8" OUTLET PIPE M-G.4(a)
U-1	1010+00	1018+21	S	821	
U-2	1018+25	1020+00	S	65	10
SHEET TOTAL				886	10'

STA. 1010+00 to 1020+00

FED. RD.	STATE	PROJECT		
2	OHIO			

46
492

MAH-18-17.20

Note:
FOR RIDGE AVE. STRUCTURE
SEE SHEET Nº 424

Note:
FOR WOODLAND AVE. STRUCTURE
SEE SHEET Nº 438

ESTIMATED QUANTITIES I-21 P.C.C. MEDIAN			
CODE	LOCATION FROM	LOCATION TO	S.Y.
N-15	1020+00	1030+00	662.2

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS						
CODE	LOCATION & STATION	#1 M.H. EACH	#2-A-12 INLET EACH	#2-2A C.B. EACH	#2-A-8 INLET EACH	
A-93	1021+00 6.0'RT.	1				
A-94	1021+15 1.25'RT.		1			
A-95	1022+50 61.0' LT.	1				
A-96	1021+90 88.0'RT.			1		
A-97	1023+00 43.5'RT.				1	
A-98	1023+00 57.0'LT.			1		
A-99	1029+50 ℄				1	
SHEET TOTAL		2	1	2	2	

EROSION CONTROL				
CODE	LOCATION FROM	LOCATION TO	L-10 SOD S.Y.	14 PAVED GUTTER TYPE I MOD. L.F.
E-1	1022+00	1023+00	56	
E-2				10
E-3				30
TOTAL			56	40

I-4 UNDERDRAINS LIN. FT.					
CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4(a)
U-1	1020+00	1021+11	S	111	
U-2	A-94	1030+00	S	875	10
U-3	A-7 "K"	A-99	D	760	20
SHEET TOTAL				1746	30

RIDGE AVE
BITUMINOUS SURFACE
BRICK CEMENT BASE
STONE CURB

ESTIMATED QUANTITIES E-8 REMOVAL ITEMS					
CODE	LOCATION FROM	LOCATION TO	CURB	SIDE-WALK	RIGID PAV'T.
B-1	47+86.14	50+00.43		1730	
X-1	"	"	430		
K-1	"	"			430
SHEET TOTAL			430	1730	430

ESTIMATED QUANTITIES I-15 BARRIER RAIL			GUARD RAIL
CODE	LOCATION	L.F.	L.F.
R-18	℄	825	350

℄ REFERENCE MONUMENTS
1025+55.38

PROPOSED STRUCTURE
MAH.-18-1934
TYPE: CONTINUOUS STEEL BEAM, WITH REINFORCED CONCRETE DECK & SUBSTRUCTURE
SPAN = 78'-0" 81'-6" c/c BEARINGS
ROADWAY: 28' F/F CURB-5' SIDEWALK-BOTH SIDES
LOAD FREQUENCY - CF400 - ADEQUATE FOR AASHO ALTERNATE LOADING
SKEW = 15°-27'-25" R.F.
WEARING SURFACE 1" MONOLITHIC
APPROACH SLAB 25' LONG, AS-1-54
SUPERELEVATION - NONE
ALIGNMENT = TANGENT
TRAFFIC COUNT: 3900 ADT 1979

℄ CURVE DATA Nº 25

Δ = 53° 49' 25"	P = 6.68'
Dc = 5° 45'	K = 199.73'
Ls = 400'	x = 398.39'
Rc = 996.45'	y = 26.68'
Θs = 11° 30'	L.T. = 267.23'
Lc = 536.06'	S.T. = 133.85'
Ts = 708.91'	L.C. = 399.28'
Es = 128.51'	Δc = 30°49'25"

STA. 1029+50 (61.0' RT.℄)
I-8 Nº 2A-8 INLET
℄ 15" I-2 930.84

B.M.#47 TOP OF STEM ON HYDT. @ RIDGE & WERNER ELEV. 952.47

B.M.# 51 TOP OF STEM ON HYDT. S.E. COR. WOODLAND & WILLIAMS. ELEV. 962.54

B.M.# 52 N.E. BOLT ON HYDT. S.E. COR. WOODLAND & MARKET ST. ELEV. 942.32

B.M.#54 TOP OF STEM ON HYDT. @ N.W. COR. HUGHES & MARKET ST. ELEV. 966.86

BEGIN APPROACH SLAB 47+86.14

END APPROACH SLAB STA. 50+00.43

BRIDGE Nº. MAH-18-19.34

FOR RETAINING WALL DETAIL SEE SHEET

BEGIN APPROACH SLAB WOODLAND STA. 6+17.59

END APPROACH SLAB STA. 4+15.49

BRIDGE Nº. MAH-18-19.41

SEE SHEET 281-285 FOR WOODLAND AVE. DETAILS

SEE SHEET 55

SEE SHEET 59

SEE SHEET 60

FOR PROFILES OF PROPOSED I-2 NOT SHOWN THIS SHEET SEE SHEET Nº 83

T.S. 1021+55.38

S.C. 1025+55.38

BEGIN-T-FEL 1026+25.33

P.C.C. 1024+00 RAMP "M" 1+78.31

END TAPER 1026+25 RAMP "M" 1+00

BEGIN TAPER 1023+67.64 RAMP "M"

END TAPER 1027+17.64 RAMP "M"

EXP. STA. 1021+51.99
RIDGE STA. 48+91.43

EXP. STA. 1025+08.07
WOODLAND 4+58.34

℄ WILLIAMS 9+89.53
℄ WOODLAND 5+51.53

P.V.I. 1026+00
ELEV. 940.62

-2.72%
+3.26%

℄ 931.57
℄ 931.42
℄ 924.82
926.16

800' V.C.

INLET & STORM SEW. RAMP K ℄ 924.16

℄ 921.10 STA 1021+11 6" PLUG

550' 15" I-2 @ .0358

A-93
STA. 1021+00 (6.0' RT ℄)
I-8 Nº 1 M.H.
COVER ELEV. 924.44
℄ 12" I-2 917.20
℄ 15" I-2 916.95

A-94
STA. 1021+15 (1.25' RT. ℄)
I-8 Nº 2A-12 INLET
TOP OF CURB -925.31
WINDOW ELEV. 924.64
℄ 8" I-4 921.56
℄ 12" I-2 921.23

A-96
STA. 1021+90 (88.0' RT. ℄)
I-8 Nº 2-2A C.B.
WINDOW ELEV. 925.94
℄ 15" I-2 923.48

A-98
STA. 1023+00
I-8 Nº 2-2A C.B. (57.0' LT. ℄)
WINDOW EL. 926.17
℄ 12" I-2 924.00

A-95
STA. 1022+50 (61.0 LT.℄)
I-8 Nº 1 M.H.
COVER EL. 927.77
℄ 12" I-2 -921.85

A-97
STA. 1023+00 (42.0' RT ℄)
I-8 Nº 2A-8 INLET
TOP OF CURB - 931.90
WINDOW EL. - 931.23
℄ 12" I-2 -927.82

A-99
STA. 1029+50 (61'℄ RT.)
I-8 Nº 2A-8 INLET
TOP OF CURB - 934.92
WINDOW EL. 934.25
℄ 15" I-2 930.84
℄ 8" I-4 931.42

A-100
STA. 1030+60
I-8 Nº 1 M.H. 60' RT ℄
COVER ELEV. 928.00
℄ 12" I-2 924.00
℄ 15" I-2 922.50
℄ 24" I-2 915.60
℄ 48" I-2 913.66

130' 12" I-2 @ .0642

ESTIMATED QUANTITIES I-2 PIPES				
CODE	LOCATION FROM	LOCATION TO	CL."B" STORM SEWER UNDER PAV'T. & APPR. 15" L.F.	12" L.F.
P-91	1020+00	A-93	98	
P-92	A-93	A-7"K"	86	
P-93	A-93	A-5"L"	37	
P-94	A-93	A-94		12
P-95	A-95	A-5"L"		148
P-96	A-95	A-98		47
P-97	A-7"K"	A-96		41
P-98	A-7"K"	A-97		116
P-99	A-99	A-100		127
SHEET TOTAL			221	491

STA. 1020+00 TO 1030+00

FED. RD.	STATE	PROJECT	
2.	OHIO		

47
492

MAH-18-17.20

PROPOSED RELOCATED 48" ST. SEWER. FOR DETAILS SEE SHEET Nº 99 & 101

I-680-9(1) 222

S.R.18 STATIONING

S.R.7 STATIONING

END MAIN-LINE GRADING STA. 806+00

30'-0"

BRICK CEMENT WEARING SURFACE
STONE CURB
TYPICAL SECTION
EXIST. HAYES AVE.

68'-0"

5" REINF. CONC. OR BRICK CEMENT BASE
3" ASPHALT SURFACE
STONE CURB
TYPICAL SECTION
EXIST. MARKET ST.

℄ ERIE ST.
EXP. STA. 1036+51.33

END APPROACH SLAB STA. 50+84.01

BRIDGE Nº MAH-18-19.50

BEGIN SHEET - STA. 1030+00

1030+91.44

℄ MARKET ST.

SEE SHEET G-2 RAMP "N"

SEE SHEET G-1 RAMP "M"

℄ HAYES AVE. EXP STA. 1034+37.19

1034+91.44 (BACK)
806+88.34 (AHEAD)

EQUATION 1034+91.44 (BACK) = 806+88.34 (AHEAD)

804+79.03

PROVIDE 18" I-2 STUB FOR FUTURE SEWER

TEMPORARY CHANNEL

END WORK STA. 805+20

END SHEET - STA. 802+00

MARLIN ST.

FULTON STREET

END PROJECT

FEDERAL MARKER WILL BE FURNISHED AND ERECTED ON THE LEFT BY THE STATE OF OHIO BEFORE ACCEPTANCE OF THIS PROJECT.

FOR RETAINING WALL DETAIL SEE SHEET

BEGIN APPROACH SLAB STA. 48+55.15

℄ EXP STA. 1030+23.49
℄ MARKET ST. STA. 50+00

℄ WOODLAND

℄ EXP'Y

℄ MARKET ST.

RR. SPIKE 4T. ±

RR. SPIKE

270.65'

45.16'

60.45'

83°53'47"

C.S. 1030+91.44

S.T. 1034+91.44

S 18°18'29" E

78.21'

50.88'

38.38'

"X" CUT IN ST.

B.M.#61 TOP OF STEM ON HYDT. @ W. SIDE OF ERIE S. OF HENRY. ELEV. 961.37

B.M.#59 TOP OF STEM ON HYDT. @ N.W. COR. HAYES & HENRY ELEV. 969.19

℄ REFERENCE MONUMENTS
STA. 1030+91.44
STA. 1034+91.44

B.M.#69 TOP OF STEM ON HYDT. @ E. SIDE OF MARLIN & N. OF KYLE ELEV. 947.98

ESTIMATED QUANTITIES I-8 INLETS, MANHOLES & CATCH BASINS

CODE	LOCATION & STATION	I-8 Nº1 M.H.	I-8 2A-8 INLET	I-8 2-2A INLET	I-8 2A-6 INLET	I-8 Nº2 M.H.
A-100	1030+60 6' LT. ℄					1
A-101	1030+60 1.25' RT. ℄		1			
A-102	1033+50 6' LT. ℄	1				
A-103	1032+00 6' LT. ℄	1				
A-104	1033+50 54' RT. ℄			1		
A-105	1033+00 1.25' RT. ℄				1	
A-106	1034+91.44 54' LT. ℄			1		
A-107	1034+91.44 6' LT. ℄	1				
SHEET TOTAL		3	1	2	1	1

ESTIMATED QUANTITIES I-21 PORTLAND CEMENT CONCRETE MEDIAN (SQ. YDS.)

CODE	FROM	TO	QUANT.
N-16	1030+00	1034+91.44	322.5
SHEET TOTAL			322.5

ESTIMATED QUANTITIES I-12 CONCRETE CURB (L.F.)

CODE	FROM	TO	TYPE 6
G-21	1030+00	1034+91.44	966.2
G-22	HAYES	—	30
G-23	HAYES	—	30
G-21A	1030+00	1030+50	50
SHEET TOTAL			1076.2

ESTIMATED QUANTITIES I-2 PIPES

CODE	LOCATION FROM	LOCATION TO	CL. "B" STORM SEWER UNDER PAV'T. & APPROACHES 12"	18"	21"	27"
P-1	A-3 RAMP N	A-103	99			
P-2	A-104	A-102		57		
P-3	A-105	A-102	47			
P-4	A-106	A-107	56			
P-5	A-101	A-100	3			
P-6	A-107	A-102			3	137
P-7	A-102	A-103				146
P-8	A-103	A-100				136 *
SHEET TOTAL			205	60	137	146

ESTIMATED QUANTITIES I-15 GUARDRAIL & BARRIER RAIL

CODE	LOCA.	TYPE 2-B G.R. (L.F.)	TYPE 2B B.R. (L.F.)
R-19	℄	150	525
R-20	HAYES	62.5	
R-21	HAYES	62.5	
SH'T. TOTAL		275	525

EROSION CONTROL

CODE	I-14 PAVED GUTTER-TYPE I (MOD.) L.F.
E-1	20
E-2	20

ESTIMATED QUANTITIES E-8 REMOVAL ITEMS

CODE	LOCA.	SIDEWALK (S.F.)	CURB (L.F.)	PAVEMENT RIGID (S.Y.)
B-1	HAYES	2450		
X-1	HAYES		610	
K-1	HAYES			1050
B-2	MARKET	4330		
X-2	MARKET		382	
K-2	MARKET			1440
SH'T. TOTAL		6780	992	2490

* M-6.6 b or M-6.8 b

℄ CURVE DATA Nº 5

Δ = 53°49'25"
Dc = 5°45'
Ls = 400
Rc = 996.45'
Θs = 11°30'
Lc = 536.06'
Ts = 708.91'
Es = 128.51'

P = 6.68'
K = 199.73'
x = 398.39'
y = 26.68'
L.T. = 267.23'
S.T. = 133.85'
L.C. = 399.28'
Δc = 30°49'25"

A-106
STA. 1034+91.44 (54' LT.)
I-8 Nº 2-2A INLET
WINDOW EL. 924.15
℄ 12" I-2 921.58

A-105
STA. 1033+00
1.25' RT. ℄
I-8 Nº 2-A-6 INLET
TOP OF CURB 926.37
WINDOW EL. 925.70
℄ 12" I-2 922.29
℄ 8" I-2 922.62

A-104
STA. 1033+50 (54' RT.)
I-8 Nº 2-2A INLET
WINDOW EL. 924.74
℄ 15" I-2 922.28
℄ 18" I-2 922.03
℄ 8" I-4 923.03

A-101
STA. 1030+60 (1.25' RT. ℄)
I-8 Nº 2-A-8 INLET
TOP OF CURB 928.75
WINDOW EL. 928.08
℄ 12" I-2 924.67

A-103
STA. 1032+00 (6' LT. ℄)
I-8 Nº 1 M.H.
COVER EL. 926.08
℄ 24" I-2 917.27
℄ 12" I-2 918.27

A-100
STA. 1030+60 (6' LT. ℄)
I-8 Nº 2 M.H.
COVER EL. 928.00
℄ 12" I-2 924.00
℄ 24" I-2 915.66
℄ 48" I-2 913.66
℄ 8" I-4 924.33

A-102
STA. 1033+50 (6' LT. ℄)
I-8 Nº 1 M.H.
COVER EL. 925.99
℄ 18" I-2 919.51
℄ 21" I-2 919.26
℄ 24" I-2 919.01
℄ 12" I-2 920.0

A-107
STA. 1034+91.44 (6' LT. ℄)
I-8 Nº 1 M.H.
COVER EL. 927.88
℄ 12" I-2 921.80
℄ 18" I-2 921.40
℄ 21" I-2 921.15

FUTURE CONSTRUCTION

STA. 802+00 (1.25' RT. ℄)
I-8 Nº 2A-10 INLET
TOP OF CURB 942.42
WINDOW EL. 941.75
℄ 12" I-2 938.34

STA. 802+45 (℄)
I-8 Nº 1 M.H.
COVER EL. 942.11
℄ 12" I-2 934.22
℄ 18" I-2 933.99

STA. 802+00 (54' RT. ℄)
I-8 Nº 2-2A
GRATE EL. 937.40
℄ 18" I-2 934.69

STA. 805+53 ℄
I-8 Nº 2-10 MODIFIED
TOP OF CURB 931.88
WINDOW EL. 931.21
℄ 12" I-2 928.00

600' V.C.

PV.I. 1033+00
ELEV. 921.58

6'

6"

443-18" I-2 @ 2.842%

3.00%

-2.72%

℄ 925.45

℄ 924.86

℄ 923.98

℄ 926.15

℄ 924.33

℄ 6"-I-4 923.68

P-8: 140' 24" I-2 @ .0116
P-7: 150'-24" I-2 @ .0116
P-6: 141'-21" I-2 @ .0134

PROPOSED STRUCTURE MAH-18-19.50
TYPE: CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE DECK & SUBSTRUCTURE
SPANS: 77'-6", 56'-9" C/C BEARING ALONG ℄ ROADWAY: 68'-0", F/F 12' SIDEWALKS.
LOAD FREQ: 2000 C.F. (S7) ADEQUATE FOR AASHO ALTERNATE LOADING
WEARING SURFACE: 1" MONOLITHIC.
APPROACH SLAB: 25' LONG AS-1-54
ALIGNMENT: TANGENT
SUPERELEVATION: NONE
SKEW: 6° 06' 13" L.F.
TRAFFIC COUNT: 64,000 ADT 1979

A-8 RAMP "N"

P-1: 103'-12" I-2 @ .00165

P-2: 60'-18" I-2 @ .042

P-3: 51'-12" I-2 @ .0447

P-4: 60'-12" I-2 @ .003

7'-12" I-2

R5

I-4 UNDERDRAINS

CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" PIPE OUTLET M-6.4a	I-5 PIPE SP. 6"-90° BEND	I-5 PIPE SP. 6"-45° BEND
U-1	1030+00	1030+60	S	48	10		
U-2	1030+62	1033+00	S	226	10		
U-3	1033+00	1034+91	S	179	10		
U-4	1031+50	1033+50	S	238	10	1	1
U-5	A-104	1034+91.4	S	151	10	1	
U-6	A-3 "N"	1034+91.4	S	141	10		
SH'T. TOTAL					985'	60	2	1

SEWER PROFILE
HORIZ. 1" = 20'
VERT. 1" = 5'

STA. 1030+00 TO 802+00

FED. RD.	STATE	PROJECT	
2	OHIO		

48 / 492

MAH.-18-1720

PLAN & PROFILE — RAMP "A"

SILLIMAN ST.

℄ MARYLAND AVE.

℄ LAKEVIEW AVE.

℄ STEEL ST.

℄ OAKWOOD AVE.
SEE SHEET Nº 226 230

BRIDGE Nº
MAH.-18-1761

24'

TYPICAL SECTION
LAKEVIEW AVE.

2" BIT WEARING COURSE
8" MACADAM BASE
CONCRETE CURB

SEE INTERSECTION DETAIL SHEET Nº 64 FOR DETAIL ℄ QUANTITIES RAMP "A" ℄ OAKWOOD

SEE EXP. CROSS SECTIONS

SEE YE SHEET Nº 36

SEE RAMP-A CROSS SECTIONS

SEE EXP. CROSS SECTIONS

MAINLINE CURVE DATA
Δ: 23°41'40"
D: 4°00'00"
T: 104.74'
L: 208.22'
E: 5.36'
e: 4.0%
Tangent to Curve
Curve to Tangent
P.C. STA. 928+87.00
P.T. STA. 930+95.22
C.L. of Steel St. STA. 929+99.42

NOTE:
THE MEDIAN TRANSITIONS FROM 40' TO 16' IN CURVE. SEE DETAIL FOR OFFSETS. SEE DETAIL RAMPS 'A' & 'B' SHEET Nº 57

STA. 5+50 ℄ - DBL. "T"

STA. 6+14.76 6"I-4 PLUG

NOSE - 33.13 RT. OF STA. 928+87.00

NOSE STA. 929+38.87

STEEL ST. STA. 929+99.42

BACK OF WALK CURVE DATA
Δ: 14° 37' 52.5"
D: 2° 30' 0"
T: 25.80'
L: 51.37'
P.C.: 1+93.39
P.T.: 2+44.76
E: 0.65'
NOSE - 7.51 RT. STA. 1+96.10

FACE OF CURB
Δ: 14° 37' 52.5"
D: 2° 30' 0"
T: 26.16'
L: 51.93'
P.C.: 1+93.61 (20.5' LT.)
P.T.: 2+45.54
E: 0.66'

END CURB 3' RT. 1+96.10

END WALK STA. 1+19.19 6"I-4 PLUG

MATCH LINE Nº 1

CONSTRUCT 4' WALK

CONSTRUCT 5' WALK

BEGIN RAMP "A"
STA. 3+55.61
(18.5' LT.)
(OAKWOOD AVE.)

STA. 1+96.10 6"I-4 PLUG

CURVE DATA
Δ: 8°05'26.5"
D: 6°
R: 954.93'
T: 67.53'
L: 134.84'
E: 2.39

SPIRAL DATA
Ls = 200'
Φ = 5°
D1 = 1°
D2 = 6°
LT = 173.94'
ST = 126.31'
Δ1 = Δ2 = T

C.S. STA. 4+39.31

S.C. STA. 6+30.31

NOSE 14' LT. OF STA. 8+14.76

CURVE DATA
Δ: 4°58'27"
D: 1°
R: 5729.58'
T: 248.88'
Lc: 497.47'
E: 3.40'

Note:
FOR STEEL ST. IMPROVEMENT SEE SH. Nº 231 234

P.T. 11+27.73 = 44' RT. OF 932+00

END RAMP "A"
44' RT. OF STA. 932+00

NOSE - 17.5 LT. OF STA. 4+69.96

END TAPER 11.5' LT. OF STA. 5+69.96

END WORK
STA. 6+41.66
(11.5' LT.)

RAMP 'A' STA. 0+00
OAKWOOD STA. 3+75.21

BEGIN 350' TAPER 44' RT. OF STA. 935+87.00
END 350' TAPER 37' RT. OF STA. 939+37.00

ESTIMATED QUANTITIES I-12 CONCRETE CURB			
CODE	LOCATION FROM	LOCATION TO	SPECIAL L.F.
G-1	6+14.76	8+14.76	200

ESTIMATED QUANTITIES I-15 GUARD RAIL			
CODE	LOCATION FROM	LOCATION TO	TYPE B-2A L.F.
R-1	8+12.5 RT.	9+75 RT.	162.50
R-2	5+01.76 LT.	6+14.76 LT.	112.50
SHEET TOTAL			275

ESTIMATED QUANTITIES E-8 REMOVAL ITEMS					
CODE	LOCATION FROM	LOCATION TO	CURB L.F.	NON-RIGID PAV'T.	SIDE-WALK
B-1	M-L-1	OAKWOOD			750
X-1	M-L-1	OAKWOOD	168		
K-1	M-L-1	OAKWOOD		224	
B-2	3+55.61 OAKWOOD	6+41.66 OAKWOOD			1430
X-2	4+69.96	6+41.66	171.7		
SHEET TOTAL			339.7	224	2180

B.M.#119
TOP OF HYDRANT 7.8' S.E. COR. OAKWOOD & MARYLAND
ELEVATION - 968.48

B.M.#121
TOP OF HYDRANT 6.2' S.E. COR. OAKWOOD & LAKEVIEW
ELEVATION - 961.52

B.M.#122-A
S.E. COR. TOP STED. - SAMUEL'S SHEET METAL WORKS (HSE #220)
WEST SIDE STEEL ST.
ELEVATION - 931.66

SEE EXACT STA. @ BOTTOM OF SHEET

STATION	PROFILE GRADE	S.E. OUTSIDE EDGE
2+05.47	951.32	0.0 951.32
3+00	951.03	+.02 951.05
3+25	949.41	+.16 949.57
3+50	947.79	+.29 948.08
3+75	946.17	+.42 946.59
4+00	944.55	+.56 945.11
4+25	942.93	+.69 943.62
4+30.31	942.5	+.72 943.31
4+50	941.31	+.67 941.98
4+75	939.69	+.61 940.30
5+00	938.07	+.56 938.63
5+25	936.45	+.50 936.95
5+50	934.83	+.43 935.26
5+75	933.21	+.38 933.59
6+00	931.59	+.32 931.91
6+25	929.97	+.26 930.23
6+30.31	929.62	+.25 929.87

BEGIN RAMP ℄ OAKWOOD STA. 3+75.21
P.V.C. STA. 0+00 EL. 968.25
GRADE 968.5
PVI STA. 1+00 EL. 963.99
E 956.42 U-2
U-2
GRADE 965.0
F SEE 1.80 U-1
P.V.T. STA. 2+00 EL. 955.51
GRADE 961.5
HORIZONTAL P.C. POINT STA. 2+95.47 EL. 951.52
-6.48%
GRADE 955.5
U-2
U-1
E 932.63 U-2
E 932.07 U-1
CALCULATIONS BASED ON 200' V.C. ~ g = 6.48%, g1 = 5.47%

E 932.07 U-1
E 932.18 U-2
PVC 6+37 EL. 929.19
150' V.C.
PVI STA. 7+17 EL. 924.33
E 925.79 U-2
U-2
-5.26%
PVT STA. 7+87 EL. 921.88
NOSE STA. 8+15.73 EL. 920.58
GRADE 943.3
GRADE 938.5
U-1
E 932.18 U-2
E 925.79 U-2
GRADE 937.0
GRADE 935.0
PT. 11+27.73 EL. 911.40
E 905.40 U-1
GRADE 934.5
11+27.73

I-4 UNDERDRAINS LIN. FT.						I-5 PIPE SPEC. EACH	
CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 a	6"x6" 90° TEE	
U-1	1+96.10	11+27.73	D	932			
U-2	1+19.19	6+14.76	D	503	10	1	
SHEET TOTAL				1435	10	1	

EROSION CONTROL				
CODE	LOCATION FROM	LOCATION TO	L-10 SOD S.Y.	I-14 PAVED GUTTER L.F. TYPE 1
E-1	4+40	4+70	18	
E-2	4+70	4+88		27
SHEET TOTAL			18	27

LEGEND
- NEW PAVEMENT EDGE
- PROPOSED MAINLINE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAV'MT & CURB
- EXIST. SIDEWALK
- EDGE OF PAVED BERM
- PROPOSED CURB

SCALE: 1" = 50'

MAH.-18-1720

FED. RD.	STATE	PROJECT	
2	OHIO		

49
492

SEE RAMP "B" - WELLINGTON INTERSECTION DETAIL SHEET Nº 70 FOR CURB & SIDEWALK QUANTITIES AND CONSTRUCTION DETAILS

END RAMP "B"

RAMP ℄ ENDS AT STA. 15+98.54
℄ WELLINGTON - STA. 6+33.94

END CONSTRUCTION ℄ STA. 15+88.54

TYPE 2-A CURB

B.M.#125
NORTH SIDE WELLINGTON ~ TOP R.H. AT HOUSE 1 TOP ELEVATION 950.75

SPIRAL DATA
Ls: 150'
Θs: 7°30'
p: 1.64'
k: 74.96'
Xc: 149.74'
Yc: 6.54'
L.T.: 100.09'
S.T.: 50.08'
L.C.: 149.89'

ESTIMATED QUANTITIES E-8 REMOVAL ITEMS

CODE	LOCATION FROM	LOCATION TO	CURB L.F.	NON RIGID PAVT. S.Y.	SIDEWALK S.F.
B-1	M-L-2	WELLINGTON INCLUDING RETURNS			2085
X-1	M-L-2	WELLINGTON INCLUDING RETURNS	770		
K-1	M-L-2	WELLINGTON INCLUDING RETURNS		960	
SHEET TOTAL			770'	960	2085'

ESTIMATED QUANTITIES
I-12 CONCRETE CURB

CODE	LOCATION FROM	LOCATION TO	TYPE 6 L.F.
G-1	7+57.04	9+19.54	162.5
G-2	925+28.90	926+28.90 INCLUDING 4 MOSS	106
G-3	5+11	8+19	309
TOTAL THIS SHEET			577.5

CURB RETURN (WEST)
R: 30.17'
Δ: 90°11'32"
T: 30.15'
L: 47.28'

CURB RETURN (EAST)
R: 30.17'
Δ: 89°42'28"
T: 29.85'
L: 47.09'

TYPICAL SECTION
LAKEVIEW AVE.
2" BIT WEARING COURSE
8" MACADAM BASE
CONCRETE CURB

ESTIMATED QUANTITIES
I-15 GUARD RAIL

CODE	LOCATION FROM	LOCATION TO	TYPE 2-A L.F.
B-1	5+10 RT.	4+22.5 RT.	87.5

I-21 P.C.C. 4" MEDIAN PAVING

CODE	S.Y.
M-1	45

MAINLINE CURVE DATA
Δ: 43°47'40"
Dc: 5°30'
Ls: 100'
Ts: 621.04'
Es: 87.89'
Xc: 398.53'
Yc: 29.53'

SPIRAL DATA
Ls: 350'
Θs: 17°30'
p: 8.88'
k: 174.46'
Xc: 346.75'
Yc: 35.40'
L.T.: 234.48'
S.T.: 117.71'
L.C.: 348.55'

CURVE DATA
Δ: 58°27'20"
Dc: 10°
R: 572.96'
T: 321.18'
Lc: 584.56'
Ec: 86.83'

NOTE:
THE MEDIAN TRANSITIONS FROM 40' TO 16' IN CURVE Nº 1 ~ FOR OFFSETS, SEE DETAILS ~ RAMPS 'A' & 'B'
SEE SHEET Nº G3

B.M.#122-A ~ S.E. COR. TOP STEP ~ SAMUEL'S SHEET METAL WORKS (HSE. # 220, WEST SIDE STEES. ST.
ELEVATION ~ 951.66

~LEGEND~
- NEW PAVEMENT EDGE
- PROPOSED MAINLINE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAVMT & CURB
- EXIST. SIDEWALK
- EDGE OF PAVED BERM
- PROPOSED CURB

SCALE: 1" = 50'

I-5 STA. 918+03.16
STA. 914+83.57
915 ℄ YOUNGSTOWN - I EXP'WY
920
0+00
℄ MARYLAND AVENUE
S. 35° 00' 51" E
I-5 STA. 922+09.16
925
SEE EXP. CROSS SECTIONS
S. 76° 48' 31" E
℄ WELLINGTON AVENUE (ML-2)
℄ LAKEVIEW AVENUE
℄ STILLMAN STREET
℄ OAKWOOD AVENUE
℄ STEEL STREET
BRIDGE Nº 2 MAH.-18-1761
BEGIN RAMP "B" 44' LT. OF ℄ STA. 930+20.24
12' RAMP ℄
STA. 5+04 6"-I-4 PLUG
STA. 8+19 6"-I-4 PLUG
STA. 12+00 6"x6" TEE
STA. 12+00 6"-90° BEND
STA. 8+29.04 6"-60° BEND
STA. 15+56.71 6"-I-4 PLUG
STA. 15+56.29 6"-I-4 PLUG
STA. 15+84.77
SEE RAMP "B" CROSS SECTIONS
SEE NOTE BELOW
TYPE 6 CURB
NOSE STA. RAMP "B" 23' LT. OF STA. 8+19.54
NOSE STA. (MAINLINE) 47.75' LT. STA. 922+29.90
S.C. STA. 922+09.16
STA. 15+88.54
END CONSTRUCTION ℄ STA. 15+88.54

I-4 UNDERDRAINS LIN. FT. CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 a	I-5 PIPE SPEC. EACH 6" 60° BEND	6" 90° BEND	6"x6" TEE
U-1	15+56.71	11+25	D	430				1
U-2	15+56.29	12+00	D	374			1	
U-3	11+25	8+19.54	S	401	10	1		
U-4	8+16	5+09	D	297	10			
U-5	5+04	4+40.21	S	64				
SHEET TOTAL				1566	20	1	1	1

EROSION CONTROL CODE	LOCATION FROM	LOCATION TO	L-10 SOD S.Y.	I-14 PVD. GUTTER LIN. FT. TYPE-1
E-1	8+19.54	5+21		299
E-2	15+00	8+31	371.7	
E-3	15+00	9+38	312.2	
SHEET TOTAL			683.9	299

PROP. GRADE
EXISTING GROUND
955
950
945
940
935
930
925
920

STA. 15+88.54 EL. 955.73
+2.75 %
P.V.I. 15+25 EL. 951.98
P.V.T. STA. 15+75 EL. 953.36
E 947.04
E 946.68
P.V.C. STA. 14+75 EL. 949.61
U-2
U-1
100' V.C.
+4.75 %
E 931.76
E 930.54
E 930.15
200' V.C.
P.V.T. STA. 10+25 EL. 928.23
P.V.I. STA. 9+25 EL. 923.48
P.V.C. STA. 8+25 EL. 922.64
NOSE STA. 8+19.54 - EL. 922.81
BEGIN RAMP "B" 32' LT. OF ℄ STA. 934+60.45
GRAPHIC GRADE
+0.64 %
U-3
E 920.09
E 919.79
E 915.42
E 914.93
E 913.72
U-4
U-5
15+98.54 15 14 13 12 11 10 9 8+19.54 7 6 5 4+40.21

STATION	PROFILE GRADE	S.E.	OUTSIDE EDGE
9+50	925.25	+1.22	926.47
9+75	926.12	+1.22	927.34
10+00	927.10	+1.22	928.32
10+25	928.23	+1.22	929.45
10+50	929.42	+1.22	930.64
10+75	930.61	+1.22	931.83
11+00	931.79	+1.22	933.01
11+25	932.98	+1.22	934.20
11+50	934.17	+1.22	935.39
11+75	935.36	+1.22	936.58
12+00	936.54	+1.22	937.76
12+25	937.73	+1.22	938.95
12+50	938.92	+1.22	940.14
12+75	940.11	+1.22	941.33
13+00	941.29	+1.22	942.51
13+25	942.48	+1.22	943.70
13+50	943.67	+1.22	944.89
13+65.72	944.42	+1.22	945.64
13+75	944.86	+1.16	946.02
13+84.77	945.32	+1.11	946.43
14+00	946.04	+1.02	947.06
14+25	947.23	+.88	948.11
14+50	948.42	+.73	949.15
14+75	949.61	+.59	950.20
15+00	950.74	+.45	951.19
15+25	951.73	+.31	952.04
15+34.77	952.09	+.25	952.34

PLAN & PROFILE - RAMP "B"

FED.RD.	STATE	PROJECT	
2	OHIO		

50
492

MAH.-18-17.20

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS

CODE	LOCATION & STATION	YNG'T. TYPE-I INLET EACH	TYPE-I M.H. EACH	*2-2A C.B. EACH
A-1	5+84.81 14.0' RT. & SILLIMAN ST.	1		
A-2	5+87.21 20.0' LT. & SILLIMAN ST.	1		
A-3	6+25 9.0' RT. & SILLIMAN ST.		1	
A-4	7+44 57' LT. &			1
SHEET TOTAL		2	1	1

ESTIMATED QUANTITIES I-2 PIPES

CODE	LOCATION FROM	LOCATION TO	CL. 'B' STORM SEWER, UPA 12"	15"
P-1	5+51 SILLIMAN	A-3	32	
P-2	A-3	6+55 SILLIMAN		84
P-3	A-2	A-3	44	
P-4	A-1	A-3	41	
SHEET TOTAL			117	84

ESTIMATED QUANTITIES I-15 GUARD RAIL

CODE	LOCATION FROM	LOCATION TO	TYPE 2-A L.F.
R-1	4+53 LT.	8+28 LT.	315
R-2	4+28 RT.	11+03 RT.	675
SHEET TOTAL			1050


EROSION CONTROL

CODE	LOCATION FROM	LOCATION TO	SOD S.Y.
E-1	0+70	1+35	39
E-2	0+70	1+72	68
E-3	5+00	5+57.5	35
SHEET TOTAL			142

EROSION CONTROL

CODE	LOCATION	I-14 PAVED GUTTER TYPE I (MOD.) LIN. FT.
E-4	7+44 (57' LT.)	30

STORM SEWER PROFILE
STA. 5+91.04 TO STA. 6+98.22
SILLIMAN ST.



BEGIN WORK
SILLIMAN - 6+96.98
SILLIMAN - 5+91.01

SEWER EQUATION - 6+75.23 BACK = 6+61.56 AHEAD

SEE INTERSECTION DETAIL SHEET Nº 70 FOR REMOVAL AND CONSTRUCTION QUANTITIES

0+00 RAMP "C" 6+34.41 EXIST. SILLIMAN TYPE 2 CURB

SILLIMAN ST. CURVE DATA
Δ: 6°36'00.80"
T: 6°36'04.
T: 0+70.65
P.C.: 5+91.01
P.T.: 6+21.96

SILLIMAN
FOR PAVT. ELEV. FROM STA. 0+00 TO STA. 0+81.94 SEE INTERSECTION DETAILS SHEET Nº 70

EXPRESSWAY STA. 937+92.11
RAMP "C" STA. 2+98.99

EXPRESSWAY STA. 943+92.72
RAMP ENDS 14+43.71

℄ YOUNGSTOWN EXP'WY

P.C. 941+46.56

CURVE DATA
Δ: 19°05'51.15"
T: 1°40'01.15"
Δ: 0°20'00.00"
L.C.: 200'

0+90 RAMP 941+46.56 P.T.

SPIRAL DATA
Ls: 754.75'
Δ+Δ': 50°31'13"
Θs: 32°43'22"
S.T.: 164.15'
T.L.: 102.92'
Δc: 8°55'56"
Δs: 41°37'17"
p: 11.96'

SPIRAL DATA
Ls: 200'
Θs: 32°44'26"
L.T.: 135.69'
S.T.: 68.81'
L.C.: 197.17'
Δc: 19°05.58'
Δs: 57.17'
p: 98.92'
p: 99.40'

CURVE DATA
Δ: 204°02'55"
R: 175'
Lc: 622.23'
Dc: 32°44'26"
T: 821.58'

50°31'13"

FOR CHANNEL DETAILS SEE SHEET 107 108

FOR CULVERT DETAILS SEE SHEET 112 113

FOR CULVERT DETAILS SEE SHEET 107 108

B.M. #7
TOP P.H. - 1582
SECOND ST. ON
NORTH SIDE
EL. 936.04'

RAMP D3
RAMP C3
RAMP B

8+57.5 RAMP "C"
6" PLUG

E.-4 18' LT. ℄

FOR CONTINUATION OF RAMP "C" SEE SHEET 51

T.S. 13+95.11
T.S. 12+57.54

TRANSITIONAL CURVE DATA
Ls: 200'
Θs: 25°58'25"
p: 6.93'
k: 99.42'
x: 196.53'
y: 27.51
L.T.: 134.58'
S.T.: 67.80'
L.C.: 198.45'
Δ: 47°56'46"
T: 208.78'
Es: 30.15'
Rc: 259'

MAINLINE CURVE DATA
Δ: 54°44.10'
Dc: 5°30'
Rc: 1041.74'
Lc: 505.20'
Ls: 400'
T: 747.31'
Es: 139.49'
θs: 11°
L.T.: 267.18'
S.T.: 133.80'
L.C.: 3999.34'
x: 398.53'
y: 25.53'
p: 6.39'
k: 199.76'

BRIDGE Nº MAH.-18-1776

TS. 957+46.56

P.I. 0+70 TO 0+81.94 ON RAMP "C"

STA. 1+35

100' R.

P.C. 23' LT. OF 5+34.04

P.T. 18' LT. OF 6+38.29

P.C. 18' LT. OF 6+38.29

P.T. 18' LT. OF 6+56.24

P.C. 18' LT. OF 6+56.24

P.T. 18' LT. OF 6+82.76

P.C. 12' LT. OF 6+82.76

P.T. 12' LT. OF 6+98.22

5.0' WIDTH

E-2

E-1

E-3

A-1

A-2

A-3

A-4

U-1

U-2

U-3

U-4

R-1

R-2

P-1

P-2

P-3

P-4

-5.32%

-4.00%

-3.33% (LOCAL GRADE)

-3.33% (MAIN TANGENT)

FE. 905.46
4+25
6" PLUG

FE. 890.46
8+00
90° BEND

FE. 887.76
8+00 90° BEND

FE. 887.83
8+57.5
6" PLUG

FE. 887.76

FE. 874.46
21.0' LT. ℄

FE. 916.75

FE. 916.26
+57
6" PLUG

FE. 916.25
6"+6"+6" TEE

FE. 905.46
4+25
6" PLUG

92.10 6" PLUG
5+91.64
SILLIMAN

5+91.64

STA. 6+34.41 SILLIMAN =
STA. 10+00.00 RAMP "C"

0+81.94 P.T.

GRAPHIC GRADE

EXPRESSWAY STA. 937+92.11
RAMP "C" STA. 2+98.99

STA. 6+56
S-27-18" CULVERT
INV. ℄ 870.60

STA. 10+50
S-27 24" CULVERT
INV. ℄ - 866.05

PVC. STA. 12+25
EL. 869.69

NOTE: I-8 Nº 2-2A C.B. @ STA. 7+41 (63.0' LT. ℄) RAMP SHALL BE MODIFIED TO INCLUDE A 36" WINDOW OPENING TO THE NORTHEAST WITH A CONC. GUTTER AT EACH WINDOW.

A-1 (SILLIMAN ST.)
STA. 5+84.18 14' RT.
CITY OF YOUNGSTOWN #1 INLET
TOP EL. 925.33
WINDOW EL. 924.65
℄ 12" I-2 921.15

A-2 (SILLIMAN ST.)
CITY OF YOUNGSTOWN #1 INLET
TOP EL. 925.33
WINDOW EL. 924.58
℄ 12" I-2 921.08

NOTE: STA. 8+57.5 TO STA. 12+57.5 I-4 UNDERDRAIN SHALL BE PLACED 2.0' LT. OF LT. EDGE OF PROPOSED FUTURE PAVEMENT.

A-4
STA. 7+44 (57.0' LT. ℄)
I-8 Nº 2-2A C.B.
WINDOW ELEV. 875.30
℄ 15" I-2 872.80

PROPOSED STRUCTURE MAH-18-1776
TYPE - CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE DECK & SUBSTRUCTURE
SPAN: 60'-6" 74'-6" 75'-6" 47'-0" ℄ BRG'S.
ROADWAY: 28'-0" F/F PARAPETS
LOAD FREQUENCY = C.F.-2000 ADEQUATE FOR A.A. S.H.O. ALTERNATE LOADING
SKEW: 36°-56'-15" L.F.
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLAB: 25' LONG AS-1-54
SUPERELEVATION = NONE
ALIGNMENT = TANGENT
TRAFFIC COUNT = NOT AVAILABLE

I-4 UNDERDRAINS

CODE	LOCATION		DEEP OR SHALLOW	6" PIPE L.F.	8" OUTLET PIPE M-6.42	I-5 PIPE SPEC. EACH 6"-90° BEND	6"x6" TEE
U-1	4+25	8+00	S	388	10	1	
U-2	8+57.5	12+00	S	346			
U-3	8+00	8+57.5	D	72	10	1	
U-4	5+92 SILLIMAN	1+57 RAMP-C	D&S	195	10		1
SHEET TOTAL				1001	30	2	1

STATION	PROFILE GRADE	S.E. OUTSIDE EDGE
6+57.54	899.49	+.25 899.74
6+75	898.79	+.21 899.00
7+00	897.79	+.14 897.93
7+25	896.79	+.08 896.87
7+50	895.79	+.02 895.81
7+57.54	895.49	0.0 895.49
7+75	894.79	-.04 894.75
8+00	893.79	-.11 893.68
8+25	892.79	-.17 892.62
8+50	891.79	-.23 891.56
8+57.54	891.49	-.25 891.24
8+75	890.79	-.34 890.45
9+00	889.79	-.48 889.31
9+25	888.79	-.62 888.17
9+50	887.79	-.75 887.04
9+75	886.79	-.89 885.90
10+00	885.79	-1.02 884.77
10+25	884.79	-1.16 883.63
10+50	883.79	-1.29 882.50
10+57.54	883.49	-1.33 882.16
10+75	882.79	-1.24 881.55
11+00	881.79	-1.10 880.69
11+25	880.79	-.97 879.82
11+50	879.79	-.83 878.96
11+75	878.79	-.70 878.09
12+00	877.79	-.56 877.23
12+25	876.79	-.43 876.36

A-4
STA. 7+51 (63.0' LT. ℄)
I-8 Nº 2-2A C.B.
WINDOW ELEV. 875.30
℄ 15" I-2 866.25

℄ 866.25
S-27-18" CULVERT

PROFILE 2-2A @ STA. 7+41
SCALE: 1" = 20' HORIZ.
1" = 5' VERT.

~LEGEND~

- NEW PAVEMENT EDGE
- PROPOSED MAINLINE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAVMT & CURB
- EXIST. SIDEWALK
- EDGE OF PAVED BERM
- PROPOSED CURB

SCALE: 1" = 50'

PLAN & PROFILE ~ RAMP "C" (SHEET 1 OF 2)

FED.RD.	STATE	PROJECT	
2	OHIO		

51
492

MAH.-18-17.20

B.M.
TOP F.H. ~ S.W. COR., PRICE RD. & SALT SPRINGS RD. UNDER MAHONING BRIDGE.
EL. 850.56

B.M. #7
TOP F.H. ~ 1582 SECOND ST. ON NORTH SIDE.
EL. 930.04

CURVE I
CURVE II
CURVE III
℄ YOUNGSTOWN EXP'WY
℄ MAHONING AVE
℄ PIER LINE
12 RAMP "C"
EXPOSED PORTION OF PIER 12 RAMP "C" TO BE REMOVED
FOR BEGIN RAMP "C" SEE SHEET NO. □
T.S. 8+57.54
S.C. 9+29.40
C.S. 9+75.18
ST. 13+52.63
SPIRAL DATA
L_s = 254.25'
$\Delta_t + \Delta_c$ = 50°31'13"
Θ_s = 32°43'32"
L.T. = 164.15'
T.T. = 107.92'
Δ_t = 8°53'56"
Δ_c = 41°37'17"
p = 11.06'
STA. 945+00
106.0' RT. ℄ - BEGIN 42" S-27
3.0' OPEN CHANNEL FOR CONSTRUCTION DETAILS SEE SHEET NO. 114 115
SPIRAL DATA:
L_s = 200'
Θ_s = 32°44'26"
L.T. = 135.93'
S.T. = 68.81'
L.C. = 197.12'
= 193.58'
= 97.17'
= 55.92'
p = 9.40'
CURVE DATA
Δ = 204°02'55"
R = 175'
L_c = 623.73'
D_c = 32°44'26"
T = 821.58'
C.S. 11+52.63
STA. 6+56
5-27 18" CULVERT
FOR DETAILS SEE SHEET NO. 112 ℄ 113
S.C. 10+57.54 RAMP "C"
R = 870.18'
13+25 9° = 90° BEND
R = 870.12'
ST. 12+57.54
P-1
STA. 10+50.0
5-27 24" CULVERT
FOR DETAILS SEE SHEET NO. 114 115
CURVE Nº I TRANSITIONAL CURVE DATA
L_s = 200'
Θ_s = 2°58'23"
R_x = 6.93'
R_y = 199.42'
x_t = 196.53'
y_t = 27.54'
L.T. = 134.58'
S.T. = 67.80'
L.C. = 130.45'
Δ = 47°56'46"
T_s = 208.78'
E_s = 30.15'
D_c = 2.39°
CURVE Nº II MAINLINE CURVE DATA
Δ = 54°44'10"
D_c = 5°30'
R = 1041.74'
L_c = 595.20'
L_s = 400'
T_s = 742.31'
E_s = 138.45'
Θ_s = 11°
L.T. = 767.18'
S.T. = 393.80'
L.C. = 3999.54'
x_t = 398.53'
y_t = 25.53'
R_x = 6.39'
R_y = 199.76'
CURVE Nº III MAINLINE CURVE DATA
Δ = 60°43.03
D_c = 5°30'
R = 1041.74'
L_c = 709.85'
L_s = 400'
T_s = 813.68'
E_s = 172.95'
Θ_s = 11°
L.T. = 767.18'
S.T. = 393.80'
L.C. = 3999.54'
x_t = 398.53'
y_t = 25.53'
R_x = 6.39'
R_y = 199.76'
RAMP CURVE DATA
Δ = 24°45'30"
D_c = 12°
R = 477.46'
L_c = 206.32'
T = 104.82'
L_s = 200'
Θ_s = 12°
T_s = 317.83'
E_s = 50.58'
L.T. = 133.64'
S.T. = 66.95'
L.C. = 199.61'
x_t = 199.12'
y_t = 15.92'
R_x = 99.85'
R_y = 3.49'
Δ = 48°45'50"
CURB (SPECIAL TYPE) SEE DETAIL
STA. 955+50
S-27 24" CULVERT
FOR DETAILS SEE SHEET NO. 120
NOSE STA. 18+53.07 LT.
NOSE STA. 18+63.38 RT.
ST. 955+41.46
ST. 955+73.06
ST. 20+01.47
P.C. 20+63.26 44° RT.
P.C. 955+75
R = 866.77 6" TEE
R = 877.02 6" PLUG
R-1
U-1
U-2
U-3
G-1
C.S. 15+01.47
FOR CONSTRUCTION DETAILS NOSE RAMP "C" & MAINLINE SEE SHEET NO. 64
STA. 20+63.26 RAMP "C" QUANTITIES
STA. 955+75.00 MAINLINE QUANTITIES

ESTIMATED QUANTITIES I-15 GUARD RAIL			
CODE	LOCATION		TYPE 2-A
	FROM	TO	L.F.
E-1	18+00 RT.	20+63.26 RT.	262.5
SHEET TOTAL			262.5

I-12 CONCRETE CURB			
CODE	LOCATION		SPECIAL
	FROM	TO	L.F.
G-1	16+53.07 LT.	18+53.07 LT.	200

I-10 DUMPED ROCK CHANNEL PROTECTION		
CODE	STATION	C.Y.
P-1	13 + 10	71

~LEGEND~
- NEW PAVEMENT EDGE
- PROPOSED MAINLINE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAVMT & CURB
- EXIST. SIDEWALK
- EDGE OF PAVED BERM
- PROPOSED CURB
- FUTURE PAVING

SCALE: 1" = 50'

PROP. GRADE
EXIST. GROUND
-4.00%
+1.82%
P.V.C. STA. 12+25 EL. 876.79
P.V.I. STA. 14+25 EL. 868.79
400' V.C.
R = 874.46 21.0' LT. ℄
R = 870.18
R = 867.57
R = 875.37
R = 877.02
R = 866.77
NOSE STA. 18+53.07 EL. 876.59
P.C. RAMP "C" STA. 20+63.26 44° RT. 955+75
GRAPHIC GRADE

STATION	PROFILE GRADE	S.E.	OUTSIDE EDGE
12+25	876.79	-.43	876.36
12+50	875.84	-.29	875.55
12+57.54	875.57	-.25	875.32
12+75	874.97	-.19	874.78
13+00	874.20	-.10	874.10
13+25	873.52	-.01	873.51
13+26.33	873.49	0.0	873.49
13+50	872.93	+.09	873.02
13+75	872.43	+.18	872.61
13+95.11	872.10	+.25	872.35
14+00	872.02	+.28	872.30
14+25	871.70	+.41	872.11
14+50	871.48	+.55	872.03
14+75	871.34	+.68	872.02
15+00	871.30	+.82	872.12
15+25	871.34	+.95	872.29
15+50	871.48	+1.09	872.57
15+75	871.70	+1.12	872.82
15+95.11	871.89	+1.33	873.22
16+00	872.03	+1.33	873.36
16+25	872.43	+1.33	873.76
16+50	872.89	+1.33	874.22
16+53.07	872.94	+1.33	874.27
16+75	873.34	+1.29	874.63
17+00	873.80	+1.25	875.05
17+23.40	874.23	+1.21	875.44

I-4 UNDERDRAINS						I-5 PIPE SPEC. EA.	
CODE	LOCATION		DEEP OR SHALLOW	6" PIPE LIN.FT.	8" L.F. OUTLET PIPE M-6.4a	6"-90° BEND	6"x6" TEE
	FROM	TO					
U-1	12+00	15+00	S	300		2	
U-2	15+00	19+75	D	495	10		1
U-3	19+75	20+63	S	88			
SHEET TOTAL				883	10	2	1

PLAN & PROFILE ~ RAMP "C"

(SHEET 2 OF 2)

FED. RD.	STATE	PROJECT	
2	OH 10		

52
492

MAH.-18-17.20

ESTIMATED QUANTITIES I-15 GUARD RAIL			
CURB	LOCATION		
	FROM	TO	L.F.
R-1	0+75 RT.	10+00 RT.	925
R-2	8+25 LT.	10+00 LT.	175
SHEET TOTAL			1100

ESTIMATED QUANTITIES I-12 CONCRETE CURB			
CODE	LOCATION		TYPE 6
	FROM	TO	L.F.
G-1	4+35.03	5+35.03	100
G-2	954+96.97 INCLUDING NOSE	955+96.97	106
SHEET TOTAL			206

I-21 4" PCC MEDIAN PAVING	
CODE	S.Y.
M-1	22

LEGEND

- NEW PAVEMENT EDGE
- PROPOSED MAINLINE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAV'MT & CURB
- EXIST. SIDEWALK
- EDGE OF PAVED BERM
- PROPOSED CURB

NON-PARTICIPATING FUNDS

PARTICIPATING FUNDS

CURVE DATA
Δc = 14°25'12"
Dc = 7°
R = 818.51'
Lc = 206'
Tc = 103.55'
Δs = 24°55'12"
Ts = 256.09'

MAHONING RIVER

SPIRAL DATA
θs = 5°15'
Ls = 150'
LT = 100.04'
ST = 50.04'
LC = 149.94'
XLT = 149.87'
YLT = 4.58'
p = 1.14'
k = 74.98'

CURVE DATA
Δ = 18°54'
Dc = 7°
R = 818.51'
T = 136.24'
Lc = 270.00'

EDGE OF RIVER BED

TRAVERSE LINE

B.M.
TOP F.H. / S.W. COR. PRICE RD. & SALT SPRINGS RD. UNDER MAHONING BRIDGE
EL. 850.56

MAHONING AVE & PIER LINE

BEGIN WORK
0+00 AT 44' LT. OF STA. 960+50

BEGIN RAMP D
PVMT. WIDTH 0+50
FULL PAVEMENT 1+00

SALT SPRINGS ROAD

R/W LINE OF EXPY.

BRIDGE No
MAH.-18-1823

STA. 10+72.88
ST. 10+72.88

U-2 U-3 E-1 R-1 R-2 G-1 G-2 M-1 U-1

E-1 5'

BANK-RUN SLAG FOR CONST. DETAILS SEE CROSS SECTIONS

STA. 8+54
6"I-4 PLUG
STA. 8+50
6"-90° BEND

MATCH LINE SHEET RAMP D

STA. 5+35.03
6"I-4 PLUG

TYPE 6 CURB

12" BERM SEE CROSS SECTIONS

C.S. 2+70.00

C.S. 4+23.23 L.T.

T.S. 5+46.86

S.T. 4+20.00

S.C. 4+70.23

TYPICAL SECTION
SALT SPRINGS RD.
BITUMINOUS SURFACE
MACADAM BASE

℄ YOUNGSTOWN EXPWY

952 953 954 955 956 957 958 959 960 961 962 963

T.S. 954+73.06

S.T. 951+41.76

FOR NOSE DETAILS OF RAMP 'D' & MAINLINE SEE SHEET No 64

NOSE STA. 44' LT. OF STA. 955+96.97

24" S-27 CULVERT FOR DETAILS SEE SHEET No 120

S.C. 958+73.06

958+83.97

ESTIMATED QUANTITIES S-8 REMOVAL ITEMS			
CODE	LOCATION		NON RIGID
	FROM	TO	PAV'T. S.Y.

MAINLINE CURVE DATA
Δ = 60°43.03'
Dc = 5°30'
Ls = 400'
Ts = 813.68'
Es = 172.95'
Xc = 398.53'
Yc = 25.53'

863.62 864.43 865.31 866.20 867.08 867.97 868.86 869.74 870.62 871.51 872.39 873.28 874.02 874.84 875.47 875.98 876.40 876.71 876.92 877.02 877.12 877.17 877.22 877.27 877.32 877.37 877.35 877.45 877.55 877.66 877.77 877.90 878.03 878.15 878.26 878.40 878.61 878.92 879.22 879.57 879.87 880.14

-0.20%

-3.54%

U-1 U-2 U-3

E 871.71 U-2

E 865.51 U-3

E 865.31 U-3

E 857.87 U-2

E 857.62 U-3

E 857.00

PVT. STA. 8+00 EL. 873.28

PVI STA. 7+00 EL. 876.82

PVC. STA. 6+00 EL. 877.02

STA. 6+30 EL. 862.50

STA. 5+31 EL. 861.26

NOSE STA. 4+35.03 EL. 871.35

BEGIN RAMP 'D' EL. 880.14

E 874.14

200' V.C.

1.25%

0.56%

10%

BERM GRADE

GRAPHIC GRADE

HORIZONTAL ST. STA. 10+72.88 EL. 863.62

PROFILE GRADE MOVES ACROSS PAVEMENT

STA. 4+85
S-27 24" CULVERT
E 849.31

STATION	PROFILE GRADE	S.E. OUTSIDE EDGE
5+66.88	877.09	+.50 877.59
5+75	877.07	+.51 877.58
6+00	877.02	+.56 877.58
6+25	876.97	+.61 877.53
6+50	876.71	+.66 877.37
6+75	876.40	+.71 877.11
7+00	875.98	+.77 876.75
7+16.88	875.65	+.79 876.44
7+25	875.47	+.80 876.27
7+50	874.84	+.80 875.64
7+75	874.02	+.80 874.82
8+00	873.28	+.80 874.08
8+25	872.39	+.80 873.19
8+50	871.51	+.80 872.31
8+75	870.62	+.80 871.42
9+00	869.74	+.80 870.54
9+22.88	868.86	+.80 869.73
9+25	868.85	+.75 869.60
9+50	867.97	+.70 868.67
9+75	867.08	+.61 867.69
10+00	866.20	+.52 866.72
10+25	865.31	+.42 865.73
10+50	864.43	+.33 864.76
10+72.88	863.62	+.25 865.87

EROSION CONTROL			
CODE	LOCATION		L-10 SOD S.Y.
	FROM	TO	
E-1	8+00	10+72.88	151.7

I-4 UNDERDRAINS LIN. FT.						I-5 PIPE SPEC. EACH	
CODE	LOCATION		DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 &	6" 90° BEND	
	FROM	TO					
U-1	0+00	8+50	D	876	10	1	
U-2	5+35.03	10+72.88	D	538			
U-3	8+54	10+72.88	D	219			
SHEET TOTAL				1633	10	1	

PLAN & PROFILE — RAMP "D" (SHEET 1 OF 2)

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH.-18 - 17.20

53 / 432

MAHONING RIVER

FOR LOCATIONS & CONSTRUCTION DETAILS OF ITEMS MARKED B-5 UTILITY RELOC. B-6 UTILITY RELOC. B-7 UTILITY RELOC. B-10 UTILITY SEE SHEET Nº 85 & 86

D-9 THRU D-14 SEE SHEET Nº

ESTIMATED QUANTITIES I-15 GUARD RAIL			
CODE	LOCATION FROM	TO	L.F.
R-1	10+00 RT.	18+00 RT.	800
R-2	10+00 LT.	15+00 LT.	500
SHEET TOTAL			1300

FOR GEOMETRICS THIS AREA SEE INTERSECTION DETAIL SHEET Nº 237 238

SEE SHEET Nº 76 FOR DRAINAGE

EST. QUANT. I-8 INLETS, MANHOLES & CATCH BASINS			
CODE	LOCATION & STATION	#2-4 INLET EACH	
A-23	14+00 72' LT. ℄	1	

I-4 UNDERDRAINS LIN. FT.						I-5 PIPE SPEC. EACH	
CODE	LOCATION FROM	TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 a	6"x6" TEE	6" 90° BEND
U-1	10+72.88	15+00	D	444			1
U-2	10+72.88	16+00	D	525		1	
U-3	16+00	16+55.18	S	62	10		
SHEET TOTAL				1031	10	1	1

EST. QUANT. PIPE CULVERTS					
CODE	LOCATION FROM	TO	S-27 42" PIPE M-6.6(b) M-6.4(d) GAGE-12	S-27 42" PIPE M-6.4 (d) GAGE-8	E-2 EXCAV. FOR STRUCT. CU. YDS.
C-21	A-20	A-23		261	338
C-22	A-23	H-2	133		74
SHEET TOTAL			133	261	412

EROSION CONTROL			
CODE	LOCATION FROM	TO	L-10 SOD S.Y.
E-1	10+72.88	14+00	181.7
E-2	15+00	14+00	55.7
SHEET TOTAL			2374

P-C 4 ENDWALLS			
CODE	LOCATION		S-1 CONC. CL. "E" CU. YDS.
H-2	14+00	63' RT. ℄	0.76

TYPICAL SECTION
EXIST. SALT SPRINGS RD.
BITUMINOUS SURFACE
MACADAM BASE

NOTE:
FOR DETAILED INFORMATION @ RAMP "D" INTERSECTION SEE SHEET Nº 238

FOR CURB TYPES & QUANT. SEE INTERSECTION DETAILS SHEET Nº 238

ISLAND RADII ARE 2'

~LEGEND~

- NEW PAVEMENT EDGE
- PROPOSED MAINLINE WORK CONSIDERED WITH SALT SPRINGS RD. & BRIDGE ST. IMPROVEMENT (SEE DETAILS)
- EXIST. PAV'MT & R.R. TRACKS
- EDGE OF PAVED BERM
- PROPOSED CURB
- FUTURE PAVING

SPIRAL DATA
Θs = 5°15'
Ls = 150'
LT = 100.04'
ST = 50.04'
LC = 149.94'
x = 149.87'
y = 4.58'
p = 1.14'
k = 74.98'

CURVE DATA
Δc = 14°25'12"
Dc = 7°00'
Rc = 818.51'
Lc = 206'
Tc = 103.55'
Δs = 24°55'12"
Ts = 256.09'

SCALE : 1" = 50'

FOR THE REMAINDER OF RAMP "D" PLAN & PROFILE, MATCH TO SHEET 2 OF 2 (PLAN & PROFILE-RAMP "D")

MATCH LINE RAMP "D" SEE SHEET 1 OF 2

A-23
STA. 14+00 (72.0' LT. ℄)
I-8 Nº 2-4 C.B.
WINDOW ELEV. 843.50
℄ 42" I-2 837.35

STA. 14+00 (63.0' RT. ℄)
PC-4 ENDWALL
℄ OUTLET 42" I-2
833.75

42" S-27 PIPE
℄ 835.43

FOR PROFILES OF PROPOSED S-27 NOT SHOWN ON THIS SHEET SEE SHEET Nº 79

PLAN & PROFILE ~ RAMP "D" (SHEET 2 OF 2)

FED.RD.	STATE	PROJECT		54 / 492
2	OHIO			

MAH.-18-17.20

E-8 REMOVAL & DISPOSAL OF EXISTING

CODE	RIGID PAVT. SQ.YDS.	SIDEWALK SQ.FT.	HEADER CURB L.F.
R-1	467		
R-2		1,850	
R-3			190

I-15 STD. GUARD RAIL, STEEL BEAM (DEEP)

CODE	STATION FROM	STATION TO	LIN. FT.
G-1	8+36 ±	9+13 ±	137.50

I-12 CONCRETE CURB

CODE	STATION FROM	STATION TO	TYPE & L.F.	SPECIAL L.F.
C-1	2+45.54	3+45.54	106	
C-2	7+13.53	9+13.53		200

MAINLINE CURVE DATA

RT: Δ = 6°04'05"
D = 5°30'00"
R = 1041.74'
T = 55.23'
L = 110.32'
LC = 110.27'
E = 1.46'

PT: 6+79.99'
PC: 7+90.31'
X = 2998.58'
Y = 29.58'
LT: 110.32'
PT: 7+79.99'
PC: 7+90.31'
LC: 3000.34'

McKINLEY AVE. - TYPICAL SECTION

50'
1' 5' 6' 13' 13' 6' 5' 1'
6"
R/W R/W
ITEM I-13.5" SIDEWALK INCLUDING 5" CINDER BASE
ITEM I-12 COMBINED CURBS & GUTTER, TYPE 2.8
6" I-22 SUBBASE
9" T-71 REINFORCED PORT. CEMENT CONC. PAVE.

BRIDGE Nº

MAH-18-1815

BRIDGE Nº

MAH-18-1823

PARK ROAD DRIVE

FOR DETAILS SEE PLAN & PROFILE (PARK ROAD) SHEET Nº 244

B.M.#10

MAHONING AVE. @ OLD LADIES HOME. HYDRANT ON N. SIDE, TOP OF STEM
ELEV. 924.80

BEGIN WORK

27' RT. OF STA. 5+55.87

END WORK

28' RT. OF STA. 8+07.56

END WORK

ON A RADIAL LINE WITH STA. 1+25

END WORK

@ BRIDGE APPROACH SLAB RAMP STA. 9+64.60 (46.96' RT. OF 962+23.28)

FOR CONSTRUCTION DETAILS OF RAMP 'E' & MAHONING AVE. SEE SHEET Nº 71

FOR CONSTRUCTION DETAILS NOSE RAMP 'E' AND MAIN-LINE SEE SHEET Nº 65

DAVEMENT EDGE OF RAMP 'E' 0+20.17

BEGIN RAMP "C" TAPER 44' RT. OF 955+43.57

END RAMP "C" TAPER 44' RT. OF 962+25

NOSE ~30' RT. OF STA. 962+73.11

BEGIN RAMP "D" END RAMP "C"

NOSE ~27.50' RT. OF STA. 8+07.56 (℄ MAHONING)

ANGLE POINT 9+10.15

100' TRANSITION

3+45.54 6" I-4 PLUG

EXIST. 18" STORM

P.I. P.R. P.S.

STA. 1+85.71 6" I-4 PLUG

NOSE ~23.5' LT. OF STA. 2+45.54 (RAMP 'E')

STA. 7+00 6" 90° BEND

STA. 7+91.50 6" 60° BEND

STA. 8+08.50 6" 60° BEND

STA. 9+61 6" I-4 PLUG

T.S. STA. 4+33.77

S.C.S. STA. 6+33.77

S.T. STA. 8+33.77

NOSE ~ STA. 9+13.53

P.C. STA. 10+44.72 44' RT. STA. 963+00

PARK ROAD SEE SHEET Nº 244

℄ PRICE RD.

RAMP 'E'

SODDING

P.C. RAMP 'E' 0+00 27' RT. OF 5+55.87

P.T. RAMP 'E' 0+20.32

0+40.67 (Mc KINLEY) 1+42.07 (RAMP 'E')

RAMP CURVE DATA
Δ = 5°49'.19"
D = 100.00'
L = 20.32'

CURB RETURN DATA
Δ = 78°00'41"
T = 20.75'
L = 34.04'
PC = 1+08.33
PT = 0+58.07

CURB RETURN DATA
Δ = 101°58'.19"
D = 200.87
L = 344.90
T = 1+74.14
PC = 0+89.57
PT = 1+85.71

TRANSITIONAL CURVE DATA

L_s = 200'
D_c = 7°00'00"
θ_s = 7°00'00"
R_c = 818.51'
Δ = 14°00'00"
L.T. = 133.44'
S.T. = 66.76'
L.C. = 199.87'
T_s = 200.70'
E_s = 8.20'

26'±

BITUMINOUS SURFACE
BRICK
CONCRETE

EXISTING Mc KINLEY AVE.

7'-0" 40'-0" 7'-0"

BITUMINOUS SURFACE
BRICK
CONCRETE

EXISTING MAHONING AVE.

LEGEND

NEW PAVEMENT EDGE
PROPOSED MAINLINE
WORK DETAILED ELSEWHERE
CENTERLINE
EXIST. EDGE OF PAV'MT & CURB
EXIST. SIDEWALK
EDGE OF PAVED BERM
PROPOSED CURB

SCALE: 1" = 50'

PROFILE GRADE

BEGIN RAMP "E" STA. 0+00 27' RT. STA. 5+55.87 ON MAHONING AVENUE EL. 922.78

922.43 921.87 921.16 920.42 920.00 919.32 918.51 917.81 917.04 916.02 914.44 912.87 911.30 909.72 908.14 906.57 905.00 903.42 901.84 900.27 898.70 897.12 895.54 893.97 892.40 890.82 889.24 887.64 886.04 885.64 885.89 885.87 886.32 886.78 887.22 887.65 888.09 888.46 888.71 889.05

℄ 912.14

℄ 904.28

U-1 U-2 U-3

-6.30 %

150' V.C.

GRAPHIC GRADE

P.V.C. STA. 6+75 EL. 889.24

P.V.I. STA. 7+50 EL. 884.52

P.V.T. STA. 8+25 EL. 885.87

END RAMP "E" STA. 10+44.72 44' RT. STA. 963+00 EL. 889.52

+1.80%

℄ 882.32 ℄ 881.84 ℄ 880.65 ℄ 882.31 ℄ 885.38 INV. ℄ 880.59

STATION	PROFILE GRADE	S.E.	OUTSIDE EDGE
6+33.77	891.84	+.80	892.64
6+00	893.97	+.71	894.68
5+75	895.54	+.64	896.18
5+50	897.12	+.57	897.69
5+25	898.70	+.50	899.20
5+00	900.27	+.43	900.70
4+75	901.84	+.36	902.20
4+50	903.42	+.29	903.71
4+33.77	904.44	+.25	904.69
4+25	905.00	+.25	905.25
4+00	906.57	+.25	906.82
3+75	908.14	+.25	908.39
3+50	909.72	+.25	909.97
3+25	911.30	+.26	911.56
3+00	912.87	+.26	913.13

EST. QUANTITIES I-8 INLETS MANHOLES & CATCH-BASINS

CODE	LOCATION & STATION	YOUNGS. TYPE I INLET EACH	
A-1	1+01.50	℄ McKINLEY 13' LT. ℄	1
A-2	0+64.90	℄ McKINLEY 13' RT. ℄	1
A-3	0+80.97		1
SHEET TOTALS			3

I-4 UNDERDRAINS LIN. FT.

CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 &	I-5 PIPE SPEC. EACH 6" 60° BEND	6" 90° BEND	6"x6" TEE
U-1	3+45.54	7+00	D	354			1	
U-2	1+85.71	8+00	D	612	10	1		1
U-3	9+61	8+00	S	161	10	1		
SHEET TOTALS				1127	20	2	1	1

EROSION CONTROL

CODE	LOCATION FROM	LOCATION TO	L-10 SOD S.Y.
E-1	2+50	7+00	300
E-2	6+25	6+85	33
SHEET TOTALS			333

A-1
STA. 1+01.50 RAMP 'E'
YOUNGSTOWN TYPE I INLET
TOP OF CURB 920.92
WINDOW EL. 921.17
℄ 12" I-2 917.25

STA. 6+75 MAHONING
EXIST. M.H. 12.7' RT. ℄
COVER 920.53
EX. 18" INV. 913.73
℄ 12" I-2 914.23

24'~ 12" I-2 @ .0886

P-1

A-2
STA. 0+64.90 McKINLEY
YOUNGSTOWN TYPE I INLET
TOP OF CURB - 921.95
WINDOW ELEV. 921.00
℄ 12" I-2 918.28

STA. 6+75 MAHONING
EXIST. M.H. 12.7' RT. ℄
COVER 920.53
EX. 18" INV. 913.73
℄ 12" I-2 914.23

57'~ 12" I-2 @ .0705

P-2

ESTIMATED QUANTITIES I-2 PIPES

CODE	LOCATION FROM	LOCATION TO	CLASS "B" STORM SEWER LIN. FT. 12"	UNDER PAV'T & APPR.
P-1	A-1	6+75	31	
P-2	A-2	6+75	54	
P-3	A-3	7+08	67	
SHEET TOTALS			152	

A-3
STA. 0+80.97 McKINLEY
YOUNGSTOWN TYPE I
TOP OF CURB 921.74
WINDOW EL. 920.99
℄ 12" I-2 918.07

STA. 7+08 MAHONING
EXIST. M.H. 12' RT. ℄
COVER EL. 919.64
EX. 18" INV. 913.09
℄ 12" I-2 913.59

70'~ 12" I-2 @ .0711

P-3

EXIST. GROUND

0+00 1 2 3 4 5 6 7 8 9 10 10+44.72

PLAN & PROFILE ~ RAMP "E"

FED. RD.	STATE	PROJECT	
2	OHIO		

55
192

MAH.-18-17.20

℄ YOUNGSTOWN EXP'WY

BEGIN WORK
44' RT. OF STA. 975+54.99

BEGIN RAMP STA. 0+00
44' RT. STA. 975+54.99

℄ ROCKVIEW ST.

6" I-4 (SEE MAIN LINE)

STRUCTURE NO. MAH-18-18.55

STA. 5+26
6"x6" TEE

STA. 7+23
6" I-4 PLUG

STA. 7+27
6" I-4 PLUG

NOSE STA. 44' RT. OF MAINLINE
STA. 985+18.78
NOSE STA. 23' LT. OF RAMP
STA. 8+11.06

6" STANDARD TYPE 6 CURB

P.C. STA. 5+56.07
44' RT. STA. 981+11.06

CURVE DATA
Dc = 4°00'00"
R = 1432.40'
Δ = 10°14'10"
Lc = 255.90'
T = 128.29'

STA. 8+25
36" RT. ℄

STA. 8+25
6"x6" TEE

C.S. STA. 8+11.27

SPIRAL DATA
Ls = 200'
Δ1+Δ2 = 3°
T1 = 130.18'
Tt = 77.04'
θs = 2°

FOR DETAILS NOSE RAMP & MAINLINE SEE SHEET Nº 65

℄ ORANGE AVE.

℄ PROP. EDWARDS

℄ EXIST. EDWARDS

FOR CONSTRUCTION DETAILS RAMP "F" & HIGH ST. SEE SHEET Nº 71

S.C. STA. 10+11.27

CURVE DATA
Dc = 35°00'00"
R = 173.62'
Δ = 91°04'48"
Lc = 276.00'
T = 176.75'

℄ PLUM ST.

C.S. STA. 12+87.97

SPIRAL DATA
Ls = 200'
θs = 33°
L.T. = 135.73'
S.T. = 68.85'
L.C. = 197.01'

STA. 14+87.97
6" I-4 PLUG

℄ RAMP "F"

NOSE STA. 16+12.72
RAMP CLOSE STA. 16+17.72
BEGIN RELOC. HIGH ST. STA. 16+38.55

FOR INTERSECTION DETAILS SEE SHEET Nº 65

END RELOC. HIGH ST. STA. 17+38.55

END RAMP "F" ℄ AT STA. 17+34.85
(THIS STA. BASED ON INTERSECTION OF EXIST. EDWARDS & EXIST. HIGH.

END WORK
20' RT. OF ℄ RELOC. EDWARDS AT STA. 0+57.15

℄ RELOC. HIGH ST.
STA. 11+55.74

16' TYPE B-C CURB WITH PAVED MEDIAN

NOTE: THE ℄ OF EXIST. HIGH IS 0.07' NORTH OF ℄ PROP. HIGH ST.

℄ PROP. HIGH ST.

BEGIN PROP. & TAPER STA. 14+87.97

END PROP. & TAPER STA. 18+12.72

℄ PROP. HIGH ST.

STA. 11+55.74 (BASED ON ℄ RELOC. HIGH ST.)

ESTIMATED QUANTITIES I-15 GUARDRAIL (LIN. FT.)			
CODE	LOCATION		STEEL BEAM DEEP
	FROM	TO	
G-1	5+35	10+85	550'

ESTIMATED QUANTITIES I-12 CONCRETE CURB			
CODE	LOCATION		TYPE 6 LIN. FT.
	FROM	TO	
C-1	8+11.06	9+11.06	206'

I-21 4" PCC MEDIAN PAVING	
CODE	S.Y.
M-1	31'

~LEGEND~

- NEW PAVEMENT EDGE
- PROPOSED MAINLINE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAV'MT & CURB
- EXIST. SIDEWALK
- EDGE OF PAVED BERM
- PROPOSED CURB

SCALE : 1" = 50'

A-1
STA. 16+67.64 RAMP "F"
21' RT. ℄
YOUNGSTOWN TYPE II INLET
WINDOW EL. 925.35
℄ C.B. 920.35
℄ 12" I-2 922.04

STA. 12+60 HIGH ST.
MAN HOLE
COVER EL. 926.71
℄ EXIST 31"x39" BR. SEWER 917.48
℄ 12" I-2 919.06

925
920
915
55'-12" I-2
@ .0544
P-1

B.M. #18-A
P.K. SPIKE IN 34" MAPLE
105' N. OF INT. HIGH & EDWARDS
15' W. OF ℄ EDWARDS
ELEV. 932.55

B.M. #19-A
P.K. SPIKE IN W. SIDE 18" W. CHERRY
140' S. OF INT. HIGH & PLUM; LOCATION: 18' E. OF ℄ PLUM ST.
ELEV. 932.18

STATION	PROFILE GRADE	S.E. OUTSIDE EDGE
10+11.97	910.60	+1.50 912.10
10+75	911.30	912.80
10+50	912.64	914.14
10+75	913.98	915.48
11+00	915.32	916.82
11+25	916.66	918.16
11+50	918.00	919.50
11+75	919.34	920.84
12+00	920.63	922.13
12+25	921.82	923.32
12+50	922.91	924.41
12+75	923.90	925.40
12+87.97	924.69	926.19
13+00	924.80	+1.43 926.23
13+25	925.60	+1.21 926.81
13+50	926.29	+1.12 927.41
13+75	926.88	+.97 927.85
14+00	927.33	+.82 928.15
14+25	927.66	+.66 928.32
14+50	927.87	+.51 928.38
14+75	927.96	+.36 928.32
14+87.97	927.97	+.28 928.25

EST. QUANTITIES I-8 : NLETS MANHOLES & CATCH BASINS			
CODE	LOCATION & STATION	YOUNGS. TYPE II INLET EACH	
A-1	STA. 16+67.64 21' RT. ℄	1	
SHEET TOTALS			

EST. QUANTITIES I-2 PIPES					
CODE	LOCATION		CLASS "B" STORM SEWERS LIN. FT. UNDER PAVT. & APPR.		
	FROM	TO	12"		
P-1	A-1	HIGH ST. 12+60	52		
SHEET TOTALS			52		

I-4 UNDERDRAINS LIN. FT.							I-5 PIPE SPEC. EACH
CODE	LOCATION		DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 a	6"x6" TEE	
	FROM	TO					
U-1	5+56.07	6+25	D	96	10	1	
U-2	6+25	7+23	S	98			
U-3	7+27	14+87.97	S	782	10	1	
SHEET TOTALS				976	20	2	

EROSION CONTROL			
CODE	LOCATION		L-10 SOD S.Y.
	FROM	TO	
E-1	9+50	6+06	191.1
E-2	11+25	10+00	96.1
SHEET TOTAL			287.2

935
930
925
920
915
910
905
900

HORIZONTAL P.C. STA. 5+56.07 EL. 902.95

GRAPHIC GRADE

125' V.C.

PVC. 8+11.06 EL. 903.60

PVT. 9+36.06 EL. 906.55

-0.67%

+5.36%

PVI. 8+73.56 EL. 905.18

U-1

U-2

U-3

℄ 899.23

℄ 899.13

℄ 900.29

℄ 900.60

℄ 900.69

℄ 899.23

℄ 898.23

6" ℄ INV. 887.44

PVC. 11+75 EL. 910.34

PVI. 13+75 EL. 930.06

EL. 928.12

EL. 927.97

℄ 924.64

PROFILE GRADE MOVES TO OPPOSITE EDGE OF PAVEMENT STA. 14+87.97

GRAPHIC GRADE

400' V. C.

SEE SHEET Nº 64 FOR GRADES

END RAMP "F" ℄ STA. 17+34.85 ~ EL. 926.51

884.5 881.0 880.0 882.0 889.0 890.0 892.0 893.0 894.0 895.0 896.0 897.0 898.0 899.0 900.0 901.0 902.0 903.0 904.0 905.0 906.0 907.0 908.0 909.0 910.0 911.0 912.0 913.0 914.0 915.0 916.0 917.0 918.0 919.0 920.0 921.0 922.0 923.0 924.0 925.0 926.0 927.0 928.0 929.0 930.0 931.0 932.0 933.0 934.0 935.0 936.0 937.0 938.0 939.0 940.0 941.0 942.0 943.0 944.0 945.0

PLAN & PROFILE ~ RAMP "F"

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH.-18-17.20

56 492

FOR DETAILS OF INTERSECTION RAMP "G" & MARSHALL STREET SEE SHEET Nº. 71

BEGIN RAMP "D" 44' LT. STA. 960+80
END RAMP "G"

END WORK
44' LT. OF ℄
STA. 960+80

BRIDGE Nº
MAH.-18-18.31

℄ YOUNGSTOWN EXP'WY

℄ PRICE ROAD

DAM

MILL CREEK

C.S. 965+17.00

C.S. 967+13.33

BRIDGE Nº
MAH.-18-18.55

℄ GLENWOOD AVE.

℄ ORANGE AVE.

℄ EXIST. MARSHALL ST.
℄ PROP. MARSHALL ST.

CURVE DATA
Δ: 14° 08' 36"
Dc: 4°
Rc: 1432.39'
T: 177.69'
L: 353.58'

END WORK
FOR RAMP "G" CURB RETURN 18' RT. OF STA. 3+54.74

P.C. 3+22.72

NOSE STA. 4+12.46
R.T. OF 4+54.74

TYPE 2 INTEGRAL CURB & GUTTER (SEE MARSHALL ST.)

STA. 3+77
6" I-4 PLUG

STA. 3+73
6" I-4 PLUG

STA. 3+23.72
6"90° BEND

STA. 3+23.72
6"90° BEND

STA. 7+55
R.T. OF ℄ RELOC. MARSHALL

0+08.11
N RAMP "G"

6" I-4 45° BEND

BEGIN WORK
18' RT. OF ℄ RELOC. MARSHALL STA. 1+54.05

BEGIN RAMP "G" 18' RT. OF ℄ RELOC. MARSHALL STA. 1+27.13

STA. 7+55
R.T. OF 4+54.74

NOSE STA. 5+26.45
11° LT.

NOSE STA. 5+68.08

NOSE STA. 2+45.60

NOSE STA. 2+37.14

NOSE STA. 2+27.13
38' LT.

NOSE STA. 1+28.92
38' LT.

STA. 6+77.30

STA. 1+69.33

CURVE DATA
Δ: 14° 16' 30"
Dc: 9° 59'
Rc: 573.69'
T: 71.99'
L: 142.91'

FOR INTERSECTION DETAIL OF RAMP "G" & MAINLINE SEE SHEET Nº. 66

MAINLINE CURVE DATA
Δ: 60° 43' 03"
Dc: 5° 30'
Ls: 400'
Ts: 813.68'
Es: 172.95'
Xc: 398.53'
Yc: 75.52'

ESTIMATED QUANTITIES I-8 INLETS, MANHOLES & CATCH BASINS		
CODE	LOCATION & STATION	YOUNG. TYPE II INLET EACH
A-1	4+88.08 23' RT. ℄	1

ESTIMATED QUANTITIES I-12 CONCRETE CURB			
CODE	LOCATION		TYPE 6
	FROM	TO	LIN. FT.
C-1	2+37.36	3+37.36	206

B.M. #13
TOP OF STEM - FIRE HYDRANT
18.5' LT. OF ℄ RELOC. MARSHALL STA. 3+87.50

~LEGEND~
- NEW PAVEMENT EDGE
- PROPOSED MAINLINE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAV'MT & CURB
- EXIST. SIDEWALK
- EDGE OF PAVED BERM
- PROPOSED CURB

SCALE: 1" = 50'

ESTIMATED QUANTITIES I-2 PIPES			
CODE	LOCATION		CL. "B" STORM UNDER PAV'T APP. SEWER LIN. FT.
	FROM	TO	12"
P-1	D-1	4+24.3	22'

I-4 UNDERDRAINS LIN. FT.						I-5 PIPE SPEC. EACH	
CODE	LOCATION		DEEP OR SHALLOW	6" PIPE	8" OUT. PIPE M 6.4 a	6"-45° BEND	6"-90° BEND
	FROM	TO					
U-1	3+77	6+77.30	S	300			
U-2	3+73	3+23.72	S	67			1
U-3	3+23.72	7+55	S	340	10	1	1
SHEET TOTAL				707	10	1	2

EROSION CONTROL			
CODE	LOCATION		L-10
	FROM	TO	500 S.Y.
E-1	2+50	2+00	138.9

A-1
STA. 4+87.91
YOUNGSTOWN (230' RT. ℄ MARSHALL)
I-8 YOUNGSTOWN TYPE II INLET
TOP OF CURB 893.81
WINDOW ELEV. 893.06
℄ 12" I-2 889.75
℄ INLET 888.06

END RAMP "G" 44' LT. OF EXPRESSWAY STA. 965+50

℄ PROP. MARSHALL
℄ EXIST. MARSHALL

COVER ELEV. 894.91
℄ PROP 12" I-2 886.36
℄ EXIST. 12" I-2 886.11
℄ EXIST. 15" I-2 886.11

24' @ 12.5% = 3.0

P-1

SCALE: 1" = 20' HOR.
1" = 5' VERT.

STA. 6+77.30 EL. 891.89

NOSE STA. 5+68.08 EL. 892.60

NOSE STA. 2+45.60 EL. 892.96

NOSE STA. 2+37.14 EL. 892.99

PVT. STA. 1+00 EL. 894.81

PVT. STA. 2+50 EL. 892.24

PVT. STA. 3+25 EL. 893.55

℄ 891.16
℄ 891.62
℄ 891.27
℄ 891.21
℄ 892.08
℄ 892.44
℄ 891.36

U-1 U-2 U-3

0.99%
0.06%

150' V.C.

GRAPHIC GRADE

STA. BASED ON ℄ RELOC. MARSHALL

BEGIN RAMP "G" 0+08.11 18' RT. OF ℄ RELOC. MARSHALL STA. 1+27.13

℄ ROCKWELL ST.

891.91 892.21 892.49 892.77 893.05 893.33 893.57 893.82 894.07 894.31 894.56 894.81 894.95 894.98 894.90 894.73 894.45 893.55 893.08 892.62 892.17 891.31 890.26 889.82 889.48 887.59 886.07

(33.65' RT. 5+25) (34.58' RT. 5+50) (30.40' RT. 5+75) (25.50' RT. 6+00) (23.48' RT. 6+25) (24.12' RT. 6+50) (13.42' RT. 6+75) (10.38' RT. 7+00)

910 905 900 895 890 885 880 875

7 6 5 4 3 2 1 0+00

PLATE 1 — PLAN - PROFILE O. P. R. & R. E. STANDARD
261 FM-3 AGEPROOF FILM MADE AND PRINTED IN U. S. A.
EUGENE DIETZGEN CO., CHICAGO

PLAN & PROFILE — RAMP "G"

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH.-18-17.20

57 / 492

ESTIMATED QUANTITIES I-15 GUARDRAIL (L.F.)		
CODE	LOCATION	TYPE 2-A
R-1	WEST AVE.	50'

ESTIMATED QUANTITIES I-2 PIPES				
CODE	LOCATION FROM	TO	CLASS "B" STORM SEWER LIN. FT. UNDER. PAV'T. & APPR. 12"	
P-1	A-1	13+81	28	
P-2	A-2	31"x39" ELIP. SWR.	18	
SHEET TOTALS			46	

I-8 ADJ. MANHOLE TO GRADE
STA. 13+81 HIGH ST.
STA. 12+60 HIGH ST.
STA. 11+57 HIGH ST.
STA. 11+83.5 HIGH ST.

I-16 REMOVE INLETS
STA. 11+75 HIGH ST.
STA. 11+80 HIGH ST.

A-2
STA. 11+92.76 HIGH ST.
14' RT. ℄
YOUNGSTOWN TYPE II
WINDOW EL. 925.42
℄ C.B. 920.42
℄ 12" I-2 922.11

31"x39" SEWER
20"x12" I-2 @ 13.50
P-2
225
220
215

MAIN LINE REMOVAL QUANTITIES MATCH LINE 3

MAIN LINE REMOVAL QUANTITIES MATCH LINE 4

PROPOSED 30" & 36" WATER LINES FOR DETAILS SEE SHEET Nº 94

PROPOSED 16" C.I.P. WATER LINE FOR DETAILS SEE SHEET Nº 94 95

FOR EXISTING SECTION OF PLUM & EDWARDS STREETS SEE PLAN & PROFILE SHEET Nº 42

SEE INTERSECTION DETAIL SH'T. Nº 71 FOR PROP. CURB & SIDEWALK QUANTITIES, & "E-8" REMOVAL ITEMS.

ESTIMATED QUANTITIES E-8 REMOVAL ITEMS						
CODE	LOCATION FROM	TO	CURB (L.F.)	PAVED GUTTER (L.F.)	SIDE-WALK (S.F.)	RIGID PAV'T. (S.Y.)
B-1	M.L.3	HIGH			3000	
X-1	M.L.4	BARRICADE	400			
K-1	M.L.3	HIGH				600
S-1	M.L.3	HIGH		310		
B-2	M.L.4	BARRICADE			2000	
K-2	M.L.4	BARRICADE				400
SHEET TOTAL			400'	310'	5000	1000

FOR CONSTRUCTION DETAILS RAMP H, RAMP F & HIGH ST SEE SHEET Nº 71

TRANSITIONAL SPIRAL DATA
L': 130.00'
x: 129.95'
y: 15.89'

BEGIN RAMP "H" ℄ 0+00 SEE STA. 11+55.72 (BASED ON EX. HIGH & EDWARDS ℄'s) ON INT. OF EX. EDWARDS ST. & ℄ PROP. EDWARDS

EXTENSION OF RAMP "H" ℄ INTERSECTS AT STA. 13+16.46

NOSE STA. 6 LT. OF RELOC. HIGH 12+38.39

STA. 11+55.74 (BASED ON ℄ EX. EDWARDS) ON ℄ RELOC. HIGH ST. STA. 11+57.27

RELOC. HIGH ST.

PROP. EDWARDS

P-2

A-1

P-1

A-2

TYPE C CURB WITH 7" PAVED MEDIAN

TYPE C CURB

BEGIN PROP & TAPER STA. 14+62.15

END PROP & TAPER STA. 15+12.15

PROP 4' SIDEWALK

BEGIN TAPER OF PAVT. & SIDEWALK 10 LT. OF ℄

END SIDEWALK TAPER ONLY, TYPE 15+14.45

END PAVT. TAPER 11+97.09 14+20.0

NOSE-7 RT. 14+20.0 (RAMP)
NOSE-9 LT. 14+18.16 (HIGH)

TYPE 2 CURB & GUTTER

℄ WALLACE

END WORK STA. 14+50.16

SPECIAL NOTE:
THE ℄ OF EXIST. HIGH ST. IS 0.5' NORTH OF PROP. HIGH ST.

BEGIN WORK
29.15' SOUTH OF ℄ PROP. HIGH ST. ON A RADIAL LINE WITH PT. OF CURB RETURN

B.M. #18-A
P.K. SPIKE IN 34" MAPLE 10.8' S. OF INT. HIGH & EDWARDS 18' W. OF ℄ EDWARDS
ELEV. 926.95

STA. 3+00 6" 90° BEND

STA. 3+34.48 6"x4" PLUG

STA. 5+05 STA. 4+46.88

STA. 9+00 6" 90° BEND

STA. 9+00 6"x6" TEE

SPIRAL DATA
L': 60.00'
x: 59.98'
y: 2.00'

CURVE DATA
Δ: 74° 52' 50"
D: 40° 45'
R: 140.59'
T: 107.02'
L: 183.75'
P.C.: 11+28.86
P.T.: 13+12.61

CURVE DATA
Δ: 74° 52' 50"
D: 20° 00'
R: 286.70'
T: 214.72'
L: 374.72'
P.C.C.: 11+28.86
P.T.: 15+03.58

CURVE DATA
Δ: 74° 52' 50"
D: 20° 00'
R: 286.70'
T: 214.72'
L: 374.72'
P.C.C.: 11+28.86
P.T.: 15+03.58

EROSION CONTROL					
CODE	LOCATION FROM	TO	L.O. I-10 SOD S.Y.	L.O. I-10 DUMPROCK C.Y.	I-14 PAVED GUTTER TYPE I L.F.
E-1	8+50	13+70	188.8		
E-2	8+80	RT.		75	
E-3					44

I-4 UNDERDRAINS L.F.					I-5 PIPE SPEC. EACH	
CODE	LOCATION FROM	TO	DEEP OR SHALLOW	6" PIPE	6"-90° BEND	6"x6" TEE
U-1	3+34.48	5+00	S	166		
U-2	6+00	9+00	D	317	1	
U-3	5+00	10+00	D	498		1
U-4	10+00	18+30.27	S	831		
SHEET TOTAL				1812'	1	1

ESTIMATED QUANTITIES I-12 CONCRETE CURB LIN. FT.			
CODE	LOCATION FROM	TO	SPECIAL
G-1	14+23.12	16+23.12	200

EST. QUANTITES I-8 INLETS, MANHOLES AND CATCH-BASINS			
CODE	LOCATION & STATION	YOUNGS. TYPE II INLET EACH	
A-1	2+09 16' LT. ℄	1	
A-2	11+92.76 HIGH ST. 14' RT. ℄	1	
SHEET TOTALS		2	

HIGH ST. QUANTITIES

FOR CONSTRUCTION DETAILS NOSE RAMP "H" & MAINLINE SEE SHEET Nº 66

FOR PG. 81-4 UNDERDRAIN SEE INSERT

B.M. # 21
TOP OF STEM ON HYDRANT. N.W. COR. HIGH & SMITH
ELEV. 926.02

SCALE: 1" = 50'

PLAN

SURVEYED	
PLOTTED	
GRADES CHECKED	
R. R. ℄ NOTED	
STRUCTURE NOTATNS CHKD.	
NOTE BOOK	
NO.	

BY	DATE

PROFILE

HORIZONTAL T.S. & C.S. FOR RAMP "H" ℄

INCIDENT POINT OF ℄ EL. 926.60

GRAPHIC GRADE

P.V.C. STA. 12+76 EL. 935.15

P.V.T. STA. 5+12.75 EL. 921.75

300' V.C.

A-1
STA. 2+09 RAMP "H" 16' LT. ℄
YOUNGSTOWN TYPE II WINDOW EL. 927.85
℄ 12" I-2 924.54

STA. 13+81 HIGH ST. EXIST. M.H. COVER EL. 928.03
℄ 31"x39" SEWER 917.13
℄ 12" I-2 919.38

STA. 6+04
PROPOSED 30" C.I.P. WATER LINE
℄ 30" PIPE 809.80
1.0" CONC. ENCASEMENT

STA. 5+88
PROPOSED 36" R.C. WATER LINE
℄ 36" PIPE 809.75
1.0" CONC. ENCASEMENT

STA. 8+06
PROPOSED 16" C.I.P. WATER LINE
℄ 16" PIPE 802.39
1.0" CONC. ENCASEMENT

P.V.C. STA. 11+00 EL. 882.11

P.V.I. STA. 12+50 EL. 877.11

P.V.T. STA. 14+00 EL. 872.45

300' V.C.

NOSE STA. 6+23.12 EL. 873.17

NOSE STA. 16+23.12 EL. 863.47

STATION	PROFILE GRADE	S.E.	OUTSIDE EDGE
4+46.88	924.87	-.25	924.51
4+50	924.67	-.24	924.43
4+75	923.44	-.18	923.76
5+00	922.08	-.12	921.96
5+75	920.61	-.05	920.56
5+46.88	919.50	0.0	919.50
5+50	919.11	+.01	919.12
5+75	917.61	+.07	917.68
6+00	916.11	+.13	916.24
6+25	914.61	+.20	914.81
6+46.88	913.50	+.25	913.55
6+50	913.11	+.26	913.37
6+75	911.61	+.36	911.97
7+00	910.11	+.46	910.57
7+25	908.61	+.56	909.17
7+50	907.11	+.66	907.77
7+75	905.61	+.76	906.37
8+00	904.11	+.86	904.97
8+25	902.61	+.95	903.56
8+46.88	901.50	+1.04	902.34
8+50	901.11		902.15
8+75	899.61		900.65
9+00	898.11		899.15
9+25	896.61		897.65
9+50	895.11		896.15
9+75	893.61		894.65
10+00	892.11		893.15
10+25	890.61		891.65
10+50	889.11		890.15
10+75	887.61		888.65
11+00	886.11		887.15
11+25	884.64		885.68
11+50	883.23		884.27
11+75	881.88		882.92
12+00	880.58		881.63
12+25	879.36		880.40
12+50	878.19		879.23
12+75	877.08		878.17
13+00	876.03		877.07
13+25	875.04		876.08
13+50	874.11		875.15
13+75	873.24		874.28
14+00	872.43		873.47

FOR CONTINUATION OF SUPERELEVATION SEE PAV'T DETAILS SHEET Nº 60

PLATE 1 — PLAN - PROFILE O. P. R. & R. E. STANDARD
261 FM-3 AGEPROOF FILM MADE AND PRINTED IN U. S. A.
EUGENE DIETZGEN CO., CHICAGO

PLAN & PROFILE — RAMP "H"

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH.-18-17.20

58
452

FOR INTERSECTION DETAILS RAMP "J" & MARSHALL AVE. SEE SHEET Nº 72
FOR DETAILS OF INTERSECTION RAMP "J" & MAINLINE SEE SHEET Nº 67

END PROJECT @ PROP. MARSHALL ST.

℄ WEST AVE.

℄ PROP. MARSHALL ST.

STA. 13+50 18.0' RT. & 6"x6" TEE E. 850.76

STA. 13+93.92 6"I-4 PLUG

STA. 13+50 2.0' LT. & 6"x6" TEE E. 850.82

STA. 9+00 6"I-4 PLUG

PROPOSED MH. B-4 SEE SHEET Nº 57

PCC. 10+37.00

RAMP "J"

TYPE 2A CURB

TYPE G CURB

CURVE DATA
Δ: 26°08'27"
Dc: 4°00'
R: 1432.39'
T: 332.55'
L: 653.52'
E: 38.10'

STA. 16+85.52 6"I-4 PLUG

STA. 16+50.76 6"x6" TEE E. 851.87

STA. 14+93.92 6"I-4 PLUG

STA. 14+44.14 6"x6" TEE E. 852.84

STA. 16+85.52 6"I-4 PLUG

STA. 16+50.76 6"x6" TEE E. 851.87

STA. 14+93.92 6"I-4 PLUG

STA. 14+44.14 6"x6" TEE E. 852.84

℄ YOUNGSTOWN EXP'WY

995

990

1000

1005

℄ SMITH ST.

℄ WALTER STREET

NOSE STA. 8+00 44' LT. STA. 997+05.50

℄ WALKER STREET

STA. 2+50 2.5' LT. OF STA. 8+00

CURVE DATA
Δ: 10°32'12"
Dc: 1°40'
R: 3439.72'
T: 317.22'
L: 632.44'
E: 16.20'

PCC. 3+20.55 44' LT. OF STA. 10+04.00

STA. 16+85.52 6"I-4 PLUG

STA. 16+50.76 6"x6" TEE E. 851.87

STA. 14+93.92 6"I-4 PLUG

STA. 14+44.14 6"x6" TEE E. 852.84

STA. 16+85.52 6"I-4 PLUG

STA. 16+50.76 6"x6" TEE E. 851.87

STA. 14+93.92 6"I-4 PLUG

STA. 14+44.14 6"x6" TEE E. 852.84

P-1 P-2 P-3 P-4 P-5 P-6 P-7

X-1 K-1 G-3 G-2 U-4 A-5 U-5 R-1 G-4 E-5 E-6 U-1 M-1 G-5 G-6 E-1 E-2 U-2 A-2 U-3 A-3 A-4 E-3 G-1 B-1 A-6 A-7 E-4

I-15 GUARD RAIL TYPE 2-A				
CODE	FROM	TO	LOC.	L.F.
R-1	3+29.56	12+29.56	RT.	900
SHEET TOTAL				900

I-21 4" PCC MEDIAN PAVING	
CODE	S.Y.
M-1	27

I-12 CONCRETE CURB					
CODE	STATION FROM	STATION TO	LOC.	TYPE 2A L.F.	TYPE G L.F.
G-1	14+94	16+86	LT.	192	
G-2	21+44.14	22+00	RT. OF ℄ MARSHALL		
G-3	13+93.92	14+93.92	RT.		100
G-4	8+00	9+00	LT.		100
G-5	996+05.50	997+05.50	LT. & EXPWY		100
G-6	11+50	14+94	LT.	344	
SHEET TOTAL				536	300

BEGIN WORK
32' LT. OF STA. 1004+86.74

100' TAPER

BEGIN RAMP "J" 0.00 - 32' LT. OF STA. 1004+86.74

END WORK
16' RT. OF STA. 19+50.05 ON PROP. MARSHALL ST.

STA. 19+50.05 18.0' RT. EXIST. 6"x6" TEE E. 850.76

STA. 19+50.05 16.0' RT. EXIST. 6"x6" TEE E. 851.54

STA. 19+50.05 16.0' RT. EXIST. 6"x6" TEE E. 851.54

SC. 997+75.49

A-5
STA. 23+00 ℄ MARSHALL
INV. 15" COMB. SEWER 845.16
PAV'T. EL. 855.46

A-5
STA. 23+00 MARSHALL
12'2T. ℄
YOUNGSTOWN TYPE II INLET
WINDOW EL. 855.72
℄ C.B. 850.10
℄ 15" I-2 851.93
℄ 15" I-2 850.10
℄ B-I-4 850.68
55'-15" I-2
@ .0442
P-5
℄ RAMP "J"
P-6 12"-15" I-2 @ 60'-0"

A-3
STA. 13+50 RAMP "J"
37' LT. ℄
I-8 Nº 2A-8 INLET
WINDOW EL. 856.56
℄ 15" I-2 852.98

A-1
RAMP "J" STA. 9+55
61' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW 847.80
℄ 12" I-2 845.73
82'-12" I-2
@ .0518
P-7

B-4
℄ SMITH ST., 85' S. MARSHALL
I-8 Nº 1 M.H.
COVER EL. 849.80
℄ EXIST. 15" 841.23
℄ NEW 12" I-2 841.48

A-4
41.75' LT. ℄
STA. 14+50
I-8 Nº 2-2A C.B.
WINDOW EL. 860.17
℄ 12" I-2 857.67

A-3
3.7' LT. ℄
STA. 13+58
I-8 Nº 2A-16 INLET
TOP OF CURB 857.56
WINDOW EL. 856.89
℄ 12" I-2 853.73
℄ 15" I-2 853.48

A-2
STA. 12+50
41.75 LT. ℄
I-8 Nº 2-2A C.B.
WINDOW 859.95
℄ 12" I-2 857.01
100.0'-12" I-2 @ .0328
8.0' 8.0'
TOP CURB
INLET STA.
P-3 14+0
P-4 13+0

B.M. #15
TOP OF STEM ON HYDRANT @ W. SIDE OF MARSHALL @ SMITH
ELEV. 845.78

11"-12" I-2 @ .0600 P-2	
A-6	STA. 16+45 2' LT. RAMP "J" ℄ YOUNGSTOWN TYPE II INLET WINDOW EL. 867.22 ℄ C.B. 857.18 ℄ 12" I-2 858.87 ℄ 12" I-2 864.20 30° C.I.P.
A-7	STA. 16+56 4.5' LT. RAMP "J" I-8 Nº 2-2 A.C.B. WINDOW 867.03 ℄ 12" I-2 864.86
	8.0' CLR. 15" COMB. SEWER
	11"-12" I-2 @ .0738

ESTIMATED QUANTITIES I-2 PIPES				
CODE	LOCATION FROM	LOCATION TO	CLASS "B" STORM SWR UNDER PAV. & APPROACHES (L.F.) 12"	15"
P-1	A-6	15th SEWER & MARSHALL	30	
P-2	A-7	A-6	9	
P-3	A-4	A-3	97	
P-4	A-2	A-3	97	
P-5	A-3	A-5		52
P-6	A-5	15th SEWER & MARSHALL		12
P-7	A-1	B-4	79	
SHEET TOTALS			312	64

I-4 UNDERDRAINS LIN. FT.						I-5 PIPE SPEC. EACH	
CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4.2	6"x6" TEE	
U-1	9+00	12+75	S	375			
U-2	12+75	13+50	D	74			
U-3	16+85.52	13+50	D	335		1	
U-4	13+93.92	13+50	D	43			
U-5	13+50(J)	23+00(MARSHALL)	D	35	10	1	
SHEET TOTALS				862'	10'	2'	

EROSION CONTROL				
CODE	LOCATION FROM	LOCATION TO	L-10 SOD S.Y.	I-14 PAVED GUTTER L.F. TYPE 1
E-1	11+50	12+00	22.3	
E-2	12+00	12+40		40
E-3	14+60	15+25	28.9	
E-4	16+66	16+85.52		20
E-5	7+00	8+43		153
E-6	5+00	7+00	111.1	
SHEET TOTALS			162.3	213

STATION	PROFILE GRADE	S.E. OUTSIDE EDGE
8+00	870.78	870.40
8+25	871.43	871.05
8+50	872.09	871.71
8+75	872.62	872.24
9+00	872.93	872.55
9+25	873.01	872.63
9+50	872.83	872.45
9+75	872.34	871.96
10+00	871.80	871.42
10+25	870.93	870.55
10+37	870.65	870.27
10+37	870.53	+.38 870.71
10+50	869.51	869.89
10+75	868.79	868.67
11+00	867.07	867.45
11+25	865.85	866.23
11+50	864.63	865.01
11+75	863.41	863.79
12+00	862.19	862.57
12+25	860.97	861.35
12+50	859.75	860.13
12+75	858.53	858.91
13+00	857.53	857.91
13+25	856.96	857.34
13+50	856.82	857.20
13+75	857.12	857.50
14+00	857.86	858.24
14+25	859.03	859.41
14+50	860.41	860.79
14+75	861.79	862.17
14+93.92	862.84	863.22

E-8 REMOVAL ITEMS						
CODE	STATION FROM	STATION TO	LOC.	CURB	S.W.	RIGID PAVT.
B-1	19+50.05	22+00	MARSHALL ST. - RT.		1050 S.F.	
X-1	19+50.05	22+00	MARSHALL ST. - RT.	220 L.F.		
K-1	19+50.05	22+00	MARSHALL ST. - RT.			305 S.Y.
SHEET TOTAL				220 L.F.	1050 S.F.	305 S.Y.

EST. QUANTITIES I-8 INLETS MANHOLES & CATCH-BASINS						I-14 PAVED GUTTER TYPE-1 MOD. L.F.
CODE	LOCATION & STATION	YOUNGS TYPE II INLET EACH	2-2A C.B. EACH	2A-16 INLET EACH		
A-1	9+55 61' RT. ℄		1			20
A-2	12+50 4.75' LT. ℄		1			10
A-3	13+50 3.7' LT. ℄			1		
A-4	14+50 4.75' LT. ℄		1			10
A-5	MARSHALL 23+00 12' RT. ℄	1				
A-6	16+45 2' LT. ℄	1				
A-7	16+56 4.5' LT. ℄		1			20
SHEET TOTALS		2	4	1		60

GRAPHIC GRADE

END RAMP "J" STA. 16+85.52 E. 862.84

NOSE STA. 14+93.92 E. 862.84

P.V.I. STA. 14+25 EL. 859.03

P.V.I. STA. 13+50 EL. 854.87

P.V.C. STA. 12+75 EL. 858.53

PVT. STA. 10+50 EL. 869.51

P.V.I. STA. 9+50 EL. 874.71

PROFILE GRADE MOVES 870.93 ACROSS PAVMT.

NOSE STA. 8+00 EL. 870.78

P.V.C. STA. 8+50 EL. 872.09

STA. 3+20.55 P.C.C.

150' V.C.

200' V.C.

-4.85%

+2.07%

-4.80%

+2.24%

U-5 A-4 A-3 A-2 U-1 P-3 P-4 U-4 U-2

TOP CURB

℄ 852.53

℄ 852.86

℄ 850.76

A-4
STA. 14+50
I-8 Nº 2-2A C.B.
4.75' LT. ℄
WINDOW EL. 860.17
℄ 12" I-2 857.67

FOR LOCATIONS & ELEVATIONS OF A-4, A-3, & A-2 SEE DETAILS ON THIS SHEET

16+85.52 16 15 14 13 12 11 10 9 8 7 6 5 4 3+29.56

PLATE 1 — PLAN - PROFILE O. P. R. & R. E. STANDARD
201 FM-3 AGEPROOF FILM MADE AND PRINTED IN U. S. A.
EUGENE DIETZGEN CO., CHICAGO

PLAN & PROFILE - RAMP "J"

FED.RD.	STATE	PROJECT	
2	OHIO		

59 492

MAH.-18-17.20

EROSION CONTROL I-14				
CODE	LOCATION FROM	LOCATION TO	PAVED GUTTER TYPE L LIN. FT.	PAVED GUTTER TYPE L MOD. LIN. FT.
E-1	11+77.81	15+81	403	
E-2	16+00	13' RT.		10
E-3				10
SHEET TOTAL			403'	20'

I-18 SIDEWALK - S.F.			
CODE	LOCATION FROM	LOCATION TO	QUANTITY
H-1	RAMP "K"	HUGHES	1440
H-2	RAMP "K"	BRIDGE	2280
SHEET TOTAL			3720'

E-8 REMOVAL ITEMS				
CODE	LOCATION FROM	LOCATION TO	SIDEWALK	CURB
B-1	BRIDGE	HUGHES	3720 S.F.	
X-1	BRIDGE	HUGHES		345 L.F.

I-15 GUARD RAIL STL. BEAM (DEEP)				
CODE	FROM	TO	LOC.	L.F.
R-1	6+62.50	7+87.50	RT.	125
R-2	12+00	16+50	LT.	450
R-3	10+00	12+00	RT.	200
SHEET TOTAL				775'

PLAN

	BY	DATE
SURVEYED		
PLOTTED		
GRADES CHECKED		
B. M.'s NOTED		
RT. OF WAY CHECKED		
STRUCTURE NOTATIONS CHKD.		

NOTE BOOK

NO.

℄ YOUNGSTOWN EXP'WY

BRIDGE № MAH.-18-1934

BRIDGE № MAH.-18-1941

℄ RIDGE AVE.

℄ EXIST. WOODLAND & PROP. WOODLAND

MAINLINE CURVE DATA

PROPOSED RELOCATION 21" COMB. SEWER FOR DETAILS SEE SHEET № 99 & 100

PROPOSED RELOC. 6" WATER MAIN FOR DETAILS SEE SHEET № 99 & 100

PROPOSED RELOC. 48" COMBINATION SEWER. FOR DETAILS SEE SHEET № 101

BRIDGE № MAH.-18-1950

℄ MARKET ST.

STA. 1030+69.49 80+00 (MARKET ST.)

STA. 1029+00 (RAMP "M")

12' SIDEWALK BACK TO BRIDGE

℄ 946.79 STA. 16+42.65 6"~90° BEND

NOSE ELEV. 1.6' LT. OF RAMP "K" MARKET ST. STA. 44+85.39

EXIST. 48" BRICK

FOR INTERSECTION DETAILS SEE SHEET № 72

STA. 43+98.24 ℄ MARKET & HUGHES

TAC CURB RETURN ELEV. 1.5' RT. OF ℄ MARKET & HUGHES

EXISTING MANHOLE

90°03'35"

END WORK RAMP "K" STA. 19+23.48 (2.00' RT.) 70.01' LT.

SCALE: 1" = 50'

1018 1019 1020 1021 1022 1023 1024 1025 1026 1027 1028 1029

1030

P.C. STA. 4+46.81 44' RT. OF STA. 1018+25

44' RT. STA. 4+46.81 DECELERATION LANE INCLUDING 100' TAPER

CURVE DATA
$D_c = 3°00'00"$
$\Delta = 5°15'00"$
$R = 1909.86'$
$T = 87.56'$
$L = 175'$
$E = 2.01'$

BEGIN WORK
44' RT. OF STA. 1018+25

P.T. STA. 6+71.87

P.C. STA. 7+28.13

NOSE STA. 7+99.63 44' RT. STA. 102+12.13

102+51.99 48+91.91 (RIDGE)

5+21.53 97+69.53 (WILLIAMS)

END PROD & TAPER STA. 7+45

FOR CONSTRUCTION DETAILS & ELEVATIONS RAMP "K" & MAINLINE SEE SHEET № 68

1025+08.02 4+98.94 (PROP. WOODLAND)

1025+69.32 5+59.94 (EXIST. WOODLAND)

PROPOSED WATER LINE RELOC. 8"

FOR ADDITIONAL INFORMATION ON PROP. WOODLAND SEE SHEET № 303

SEE SHEET № FOR RETAINING WALL DETAILS.

P.T. STA. 14+03.81

P.C. STA. 16+42.65

P.T. STA. 17+38.17

CURVE DATA
$D_c = 3°00'00"$
$\Delta = 20°15'00"$
$R = 1909.86'$
$T = 341.06'$
$L = 675'$
$E = 30.21'$

FOR CONSTRUCTION DETAIL OF 2-2A C.B. @ STA. 16+0 SEE SHEET № 109

I-4 ℄ 955.79 16+64 6" PLUG

CURVE DATA
$D_c = 55°00'30"$
$T = 93.14'$
$L = 96.14'$

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH BASINS						
CODE	LOCATION & STATION	#2-2A C.B EACH	#2-2A G INLET EACH	YNGST. TYPE II INLET EACH	#1 M.H. EACH	#2-2A-8 INLET EACH
A-1	11+80 15.0' RT.	1				
A-2	15+04 43.25' RT		1			
A-3	17+45 3.0' RT.			1		
A-4	18+68 3.0' RT.			1		
A-5	16+00 13.0' RT.	1				
A-6	15+75 6.0' RT.				1	1
A-7	8+02 21.0' RT.					1

ESTIMATED QUANTITIES I-12 CONCRETE CURB. (LIN. FT.)				
CODE	LOCATION FROM	LOCATION TO	TYPE 6	TYPE 2-A
C-1	6+87.50	7+87.50	100	
C-2	102+78.13	1022+78.13	100	
C-3	10+25	15+99	584	
C-4	16+02	16+42.65	46	
C-5	16+42.65	HUGHS		280
C-6	16+42.65	MARKET		91
C-7	7+99.63	12+00	406	
SHEET TOTAL			1236'	371'

I-21 4" PCC MEDIAN PAVING	
CODE	S.Y.
M-1	18'

B.M.# 47
TOP OF STEM ON HYDRANT @ RT. OF ℄ WERNER ST. ELEV. = 952.47

B.M.# 52
N.E. BOLT ON WOODLAND ST. @ MARKET ST. ELEV. = 944.32

I-4 UNDERDRAINS LIN. FT.							
CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 &	I-5 PIPE SPEC. EACH 6"-90° BEND	
U-1	4+46.81	17+41	D & S	1204			
U-2	16+42.95	8+10	D	823	10		
U-3	A-3	18+64	D	113	10	1	
SHEET TOTAL				2230	20'	1'	

ESTIMATED QUANTITIES I-2 PIPES				
CODE	LOCATION FROM	LOCATION TO	CLASS "B" STORM SEWERS CIRC. REINF. CONC. PIPE LIN. FT. UNDER PAV'T. APP. 12"	DRTA
P-1	A-1	PROP. M.H. @ INTERSECTION EX. 48" SWR.	36	
P-2	A-3	47+81 MARKET EX. M.H. 34' LT. 19+23	52	
P-3	A-4	A-6	68	
P-4	A-2	A-6	69	
P-5	A-5	A-6	22	
P-6	A-6	48+14 MARKET	161	
SHEET TOTAL			408'	

FOR PROFILES OF PROPOSED I-2 NOT SHOWN THIS SHEET SEE SHEET №: 83

A-7
STA. 8+02 (21.0' LT. ℄)
I-8 № 2A-8
TOP OF CURB 927.91
WINDOW EL. 927.24
℄ 12" I-2 923.85
℄ 8" I-4 924.16

A-6
STA. 15+75 (60' RT. ℄)
I-8 № 1 M.H.
COVER ELEV. 950.00
℄ 12" I-2 944.10
℄ 8" I-4 944.43

A-5
STA. 16+0 (13.0' RT. ℄)
I-8 № 2-2A C.B.
WINDOW ELEV. 950.05
℄ 12" I-2 947.86

A-4
STA. 18+68 (13.0' RT. ℄)
YNGST. TYPE II INLET
TOP OF CURB 962.41
WINDOW ELEV. 961.66
℄ 12" I-2 958.35
℄ INLET 956.66

A-3
STA. 17+45
I-8 YNGST. TYPE II (3.0' RT. ℄)
TOP OF CURB 957.33
WINDOW ELEV. 956.58
℄ 12" I-2 953.27
℄ INLET 951.58

A-2
STA. 15+04 (4.25' RT. ℄)
I-8 № 2A-6 INLET
TOP OF CURB 948.54
WINDOW ELEV. 947.87
℄ 12" I-2 944.46

STA. 19+23.5
EXIST. M.H. (34.0 LT. ℄)
COVER ELEV. 964.98
℄ 12" I-2 955.00
℄ 48" (EXIST.) 950.86

STA. 47+81.5
EXIST. 48" DR. SW.
℄ 943.98
℄ 12" I-2 945.98

STA. 11+88
21" COMB. SEWER RELOC.
℄ 929.02
1.0' CONC. ENC.

STA. 11+94
RELOC. 8" W.M.
℄ 931.5
1.0' CONC. ENCASEMENT

STA. 1+46.81 ℄ 915.30

P.C. STA. 4+46.81 EL. 918.85

P.T. STA. 6+71.87 EL. 914.67

P.C. STA. 7+28.13 EL. 914.67

NOSE STA. 7+99.63 EL. 913.85

P.I. STA. 9+32.44 EL. 932.65

P.V.I. STA. 10+00 EL. 927.60

P.V.I. STA. 12+00 EL. 926.80

P.V.I. STA. 14+03.81 EL. 948.04

P.V.I. STA. 16+0 EL. 955.08

P.V.I. STA. 17+00 EL. 955.08

END RAMP STA. 19+23.48 EL. 954.47

℄ 911.97

℄ 926.58

℄ 946.72

℄ 955.79

+2.60%
+4.85%
+2.60%
+4.44%

200' V.C.

GRAPHIC GRADE

STATION	PROFILE S.E. OUTSIDE EDGE		OUTSIDE GRADE
9+49.63	933.60	-.80	932.80
10+00	935.04	-.80	934.24
10+25	935.69	-.80	934.89
10+50	936.34	-.80	935.54
10+75	936.99	-.80	936.19
11+00	937.64	-.80	936.84
11+25	938.29	-.80	937.49
11+50	938.94	-.80	938.14
11+75	939.59	-.80	938.79
12+00	940.24	-.80	939.44

CON'T.

STATION	PROFILE S.E. OUTSIDE EDGE		OUTSIDE GRADE
12+09.87	940.54	-.80	939.54
12+25	940.89	-.72	940.17
12+50	941.54	-.67	940.87
12+75	942.19	-.52	941.67
13+00	942.84	-.47	942.47
13+25	943.49	-.32	943.17
13+50	944.14	-.22	943.92
13+75	944.79	-.12	944.67
14+00	945.44	-.07	945.47
14+05.87	945.54	0.0	945.54
14+25	946.09	+.05	946.14
14+50	946.74	+.12	946.86
14+75	947.59	+.18	947.51
15+00	948.04	+.24	948.28
15+05.87	948.14	+.75	948.39

PROFILE

	BY	DATE
SURVEYED		
PLOTTED		
GRADES CHECKED		
B. M.'s NOTED		
STRUCTURE NOTATIONS CHKD.		

NOTE BOOK

NO.

PLATE 1 — PLAN - PROFILE O. P. R. & R. E. STANDARD
201 FM-3 AGEPROOF FILM MADE AND PRINTED IN U.S.A.
EUGENE DIETZGEN CO. CHICAGO

PLAN & PROFILE — RAMP "K"

FED. RD.	STATE	PROJECT	
2	OHIO	+	

MAH.-18-17.20

GO 492

PLAN | PROFILE

SURVEYED | PLOTTED | DESIGNED | CHECKED | QUANTITIES CHECKED | RT. OF WAY CHECKED | B. M.'s NOTED | STRUCTURE NOTATIONS CHK'D

NOTE BOOK | NO.

BY | DATE

END WORK 44' LT. OF STA. 1013+17.15

BEGIN WORK 15' RT. ON A RADIAL LINE WITH STA. 0+00 OT (REFER TO INTERSECTION DETAILS - RAMP "L" FOR PAV'MT LIMITS @ WOODLAND)

℄ YOUNGSTOWN EXPWY.

BEGIN ACCELERATION LANE TAPER 44' LT. OF STA. 1013+69.07
END TAPER 32' LT. OF STA. 1010+19.07

CURVE DATA
Δ: 11°-14'-32.69"
D: 14°-32'-49.5"
T: 154.00'
L: 307.07'

FOR CONSTRUCTION DETAILS RAMP "L" & MAINLINE SEE SHEET Nº [ ]

NOSE - 38' LT. OF 1001+50.01 — 74° 32' 35"

BRIDGE Nº MAH-18-1934

STA. 5+56 - ℄ PROP. RELOC. 6" W.M. FOR DETAILS SEE SHEET Nº 99 | 100

℄ RIDGE AVE.

1021+51.99 45+91.43 (RIDGE)

TS 1021+55.38

NOSE - 14' LT. OF STA. 1021+52.05

SEE SHEET Nº [ ] FOR RETAINING WALL DETAILS

BEGIN TYPE G CURB 10.0' RT. 1021+77.46

PCC STA. 5+99.47

CURVE DATA
Δ: 74°-40'-00"
D: 148.01°
R: 38.71'
T: 58.27'

SPIRAL DATA
Ls: 100.00'
θs: 5°-15'
Xs: 99.84'
Ys: 4.58'
Lc: 149.84'

STA. G+28.88 RAMP ℄ STA. 49+60.45 RIDGE ℄

NE 924.74 5+25 G-90° BEND

5.0'

SC 3+06.62

2 TYPE H CURBS

SEE INTERSECTION DETAIL SHEET Nº 72

NOSE - 24' LT. OF STA. 1021+48.00 (WOODLAND) 18° RT. 2+47.00 ℄ SIDE WALK @ STA. 1+29.48

PT 0+85.62

TS 1+56.62

PC STA. 0+00 0° 00' 00" OT

℄ SIDEWALK

℄ EXIST. WOODLAND

℄ PROP. WOODLAND

CURVE DATA
Δ: 74°-40'-00"
D: 148.01°
R: 38.71'
T: 58.27'
L: 125.45'

SEE WOODLAND AVE. RELOCATION FOR ADDITIONAL INFORMATION (SHEET Nº 302)

MAINLINE CURVE DATA
PDD: 5°-40'-25"
R: 1012.45'
D: 5°-40'-25"
T: 100.00'
E: 5°-40'-25"
L: 198.51'
℄

FED. RD.	STATE	PROJECT	
2	OHIO		

61
492

MAH.-18-17.20

PLAN | SURVEYED | PLOTTED | ALIGNMENT CHECKED | ST. OF WAY CHECKED | NOTE BOOK | NO. | BY | DATE

PROFILE | SURVEYED | PLOTTED | PROFILE CHECKED | B. M.'s NOTED | NOTE BOOK | NO. | STRUCTURE NO'S AT RIGHT ANGLES OR SKEW | BY | DATE

S.C. STA. 1025+55.38

BRIDGE Nº
MAH.-18-1050

BEGIN RAMP "M" 0+00
32' RT. OF ℄ STA. 1025+29.33

END TAPER 1+00
44' RT. OF 1026+25

P.C.C. STA. 1+78.31
44' RT. OF 1027+00

CURVE DATA
Δ: 14°
Dc: 5°30'
Ts: 201'
Lc: 400'

BEGIN APPROACH SLAB
℄ MARKET ST. STA. 48+05.19

FOR DETAILS
48" COMBINED SEWER
SEE SHEET Nº 101

FOR DETAILS OF
NOSE RAMP "M" &
MAINLINE SEE SHEET
Nº. G9

CONSTRUCT TYPE 6 CURB (LIMITS CORRESPOND WITH LENGTH OF RETAINING WALL)

FOR RETAINING WALL DETAILS SEE SHEET Nº

SPIRAL DATA
Ds: 3°30'
Ls: 200'
L.T.: 199.96'
S.T.: 100.00'

SPIRAL DATA
Ds: 2°58'52"
Ls: 150'
L.T.: 101.54'
S.T.: 51.22'

CURVE DATA
Δ: 108°31'12"
Dc: 9°58.11'
Rc: 570'
T: 720.44'
Lc: 784.10'

See Sheet Nº For Temporary Run Around

CURVE DATA
Δ: 67°01'16"
Dc: 57°17'45"
Rc: 100'
T: 69.53'
Lc: 117.03'

CURVE DATA
Δ: 68°00'43"
Dc: 190°05'55"
Rc: 30'
T: 22.33'
Lc: 35.75'

END RAMP "M" ℄ STA. 46+32.57

CONSTRUCT 12' SIDEWALK

END WORK
32' RT. OF STA. 46+07.00

STA. 46+07.00

B.M. #54
TOP OF STEM ON HYDRANT @ N.W. COR. HUGHES & MARKET ST. ELEV. 966.86

STA. 45+99.24

NOSE ~ 24' LT OF STA. 45+65.03 (RAMP) 45+88.51 (MARKET ST.)

TYPE 2A CURB

FOR CONSTRUCTION DETAILS RAMP "M" & MARKET STREET INTERSECTION SEE SHEET Nº 72

B.M. #59
TOP OF STEM ON HYDRANT @ N.W. COR. HAYES & HENRY
ELEV. 969.93

℄ HUGHES STREET

℄ MARKET STREET

℄ HAYES AVENUE

℄ HENRY STREET

BEGIN WORK
32' RT. OF STA. 1025+29.33

B-7
STA 48+49
℄ MARKET ST.
I-8 YNGST. Y-8 M.H.
COVER ELEV. 955.6
E 12" I-2 949.15
E 48" I-2 941.15

P-1 51'~12" I-2 @ .0308
P-2 36'~12" I-2 @ .0368

MAINLINE CURVE DATA
Δ: 55°49'.75"
Dc: 5°45'
Ts: 708.91'
Es: 128.51'
Ls: 400'
Rc: 996.45'
Θs: 11°30'
x: 398.39'
y: 26.68'
L.T.: 267.23'
S.T.: 133.85'
L.C.: 399.28'

I-15 STD. GUARD RAIL STEEL BEAM-DEEP			
CODE	STATION FROM	STATION TO	L.F.
G-1	4+00	6+00	300
G-2	7+00	9+00	200
			500'

I-21 4" PCC MEDIAN PAVING	
CODE	S.Y.
M-1	25'

ESTIMATED QUANTITIES I-8 INLETS, MANHOLES & CATCH BASINS			
CODE	LOCATION & STATION	I-8 Nº 2-2A C.B. EACH	YOUNGS. TYPE II INLET EACH
A-1	5+97 16.5' RT.	1	
A-2	MARKET 48+60 34' RT.		1
A-3	9+50 15' RT.	1	
A-4	9+50 33' LT.	1	
SHEET TOTAL		3'	1'

ESTIMATED QUANTITIES I-2 PIPES						
CODE	LOCATION FROM	LOCATION TO	CLASS "B" STORM SEWER UNDER PAV'T. & APPROACHES 12"	CLASS "B" STORM SEWER 15"	CLASS "B" STORM SEWER 12"	CLASS "B" STORM SEWER 15"
P-1	A-2	B-7	32			
P-2	A-1	A-2			47	
P-3	A-3	A-4		48		
P-4	A-4	A-104				137
SHEET TOTAL			32'	48'	47'	137'

I-12 CONCRETE CURB				
CODE	STATION FROM	STATION TO	TYPE 6 L.F.	TYPE 2-A L.F.
C-1	1+78.31	2+10	732	
C-2	15+16.16	16+33.57		118
C-3	15+16.16	15+60.5		55
C-4	5+42.01	6+42.01	206	
			938'	173'

I-13 5' SIDEWALK	
CODE	S.F.
S-1	180
S-2	822
	1002'

I-4 UNDERDRAINS					I-5 PIPE SPEC	
CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	8" PIPE OUTLET M-6.4 a	6" PIPE	6" CROSS	6" TEE
U-1	4+50	15+16	S		300		
U-1	"	"	D		766		
U-2	5+50	7+00	D		150	1	1
SHEET TOTAL					1216'	1	1'

EROSION CONTROL					
CODE	LOCATION FROM	LOCATION TO	L-10 SOD S.Y.	I-14 GUTTER TYPE 1 L.F.	I-14 GUTTER TYPE 1 MOD. L.F.
E-1	13+00	9+40	200		
E-2	5+87	9+40		353	
E-3					10
E-4					20
E-5					10
			200'	353'	40'

~LEGEND~
- NEW PAVEMENT EDGE
- PROPOSED MAINLINE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAV'MT & CURB
- EXIST. SIDEWALK
- EDGE OF PAVED BERM
- PROPOSED CURB

SCALE: 1"=50'

A-104
STA. 1033+00
I-8 Nº 2-2A C.B.
54.0 RT. ℄
WINDOW EL. 924.74
E 15" I-2 922.28
E 18" I-2 922.03

P-3 52'~15" I-2 @ .01
P-4 141'~15" I-2 @ .1184

HORZ. 1"=20'
VERT. 1"=5'

A-1
STA. 5+97 16.5' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL.=954.08
E 12" I-2 = 951.91

A-2
℄ MARKET ST. STA. 48+60
54' RT. ℄
YOUNGSTOWN TYPE II INLET
E 12" I-2 = 950.03
TOP OF CURB = 954.53
WINDOW EL.=953.78
BOTTOM EL.=948.78
E 12" I-2 = 850.47

A-3
STA. 9+50 15' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL.=941.94
E 15" I-2 = 939.50

A-4
STA. 9+50 33' LT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL.=944.59
E 15" I-2 = 938.58

HORIZONTAL CURVE STA. 1+78.31 TO STA. 2+10

BRIDGE INTERSECTION POINT ℄ MARKET ST.

NOSE STA. 5+42.01 EL. 932.14

P.V.C. STA. 5+50 EL. 933.05

GRADE BEGIN RAMP "M" 0+00 - 32' RT. 1025+29.33

150' V.C.

P.V.T. STA. 7+00 EL. 939.66

E 938.30

E 937.87

E 930.24

E 927.84

E 925.14

E 924.52

E 924.32

E 923.71

E 923.51

E 922.90

E 922.70

E 922.49

E 922.29

E 922.08

E 921.88

E 921.67

E 921.47

E 921.26

E 921.06

E 920.85

E 920.65

E 920.44

E 920.24

E 920.03

E 919.83

E 919.62

E 919.42

E 919.21

E 919.01

E 918.80

E 918.60

E 918.39

E 918.19

E 917.98

E 917.78

E 917.57

E 917.37

E 917.16

E 916.96

E 916.75

E 916.55

E 916.34

E 916.14

E 915.93

E 915.73

E 915.52

E 915.32

E 915.11

E 914.91

E 914.70

E 914.50

E 914.29

E 914.09

E 913.88

E 913.68

E 913.47

E 913.27

E 913.06

E 912.86

E 912.65

E 912.45

E 912.24

E 912.04

E 911.83

E 911.63

E 911.42

E 911.22

E 911.01

E 910.81

E 910.60

E 910.40

E 910.19

E 909.99

E 909.78

E 909.58

E 909.37

E 909.17

E 908.96

E 908.76

E 908.55

E 908.35

E 908.14

E 907.94

E 907.73

E 907.53

E 907.32

E 907.12

E 906.91

E 906.71

E 906.50

E 906.30

E 906.09

E 905.89

E 905.68

E 905.48

E 905.27

E 905.07

E 904.86

E 904.66

E 904.45

E 904.25

E 904.04

E 903.84

E 903.63

E 903.43

E 903.22

E 903.02

E 902.81

E 902.61

E 902.40

E 902.20

E 901.99

E 901.79

E 901.58

E 901.38

E 901.17

E 900.97

E 900.76

E 900.56

E 900.35

E 900.15

E 899.94

E 899.74

E 899.53

E 899.33

E 899.12

E 898.92

E 898.71

E 898.51

E 898.30

E 898.10

E 897.89

E 897.69

E 897.48

E 897.28

E 897.07

E 896.87

E 896.66

E 896.46

E 896.25

E 896.05

E 895.84

E 895.64

E 895.43

E 895.23

E 895.02

E 894.82

E 894.61

E 894.41

E 894.20

E 894.00

E 893.79

E 893.59

E 893.38

E 893.18

E 892.97

E 892.77

E 892.56

E 892.36

E 892.15

E 891.95

E 891.74

E 891.54

E 891.33

E 891.13

E 890.92

E 890.72

E 890.51

E 890.31

E 890.10

E 889.90

E 889.69

E 889.49

E 889.28

E 889.08

E 888.87

E 888.67

E 888.46

E 888.26

E 888.05

E 887.85

E 887.64

E 887.44

E 887.23

E 887.03

E 886.82

E 886.62

E 886.41

E 886.21

E 886.00

E 885.80

E 885.59

E 885.39

E 885.18

E 884.98

E 884.77

E 884.57

E 884.36

E 884.16

E 883.95

E 883.75

E 883.54

E 883.34

E 883.13

E 882.93

E 882.72

E 882.52

E 882.31

E 882.11

E 881.90

E 881.70

E 881.49

E 881.29

E 881.08

E 880.88

E 880.67

E 880.47

E 880.26

E 880.06

E 879.85

E 879.65

E 879.44

E 879.24

E 879.03

E 878.83

E 878.62

E 878.42

E 878.21

E 878.01

E 877.80

E 877.60

E 877.39

E 877.19

E 876.98

E 876.78

E 876.57

E 876.37

E 876.16

E 875.96

E 875.75

E 875.55

E 875.34

E 875.14

E 874.93

E 874.73

E 874.52

E 874.32

E 874.11

E 873.91

E 873.70

E 873.50

E 873.29

E 873.09

E 872.88

E 872.68

E 872.47

E 872.27

E 872.06

E 871.86

E 871.65

E 871.45

E 871.24

E 871.04

E 870.83

E 870.63

E 870.42

E 870.22

E 870.01

E 869.81

E 869.60

E 869.40

E 869.19

E 868.99

E 868.78

E 868.58

E 868.37

E 868.17

E 867.96

E 867.76

E 867.55

E 867.35

E 867.14

E 866.94

E 866.73

E 866.53

E 866.32

E 866.12

E 865.91

E 865.71

E 865.50

E 865.30

E 865.09

E 864.89

E 864.68

E 864.48

E 864.27

E 864.07

E 863.86

E 863.66

E 863.45

E 863.25

E 863.04

E 862.84

E 862.63

E 862.43

E 862.22

E 862.02

E 861.81

E 861.61

E 861.40

E 861.20

E 860.99

E 860.79

E 860.58

E 860.38

E 860.17

E 859.97

E 859.76

E 859.56

E 859.35

E 859.15

E 858.94

E 858.74

E 858.53

E 858.33

E 858.12

E 857.92

E 857.71

E 857.51

E 857.30

E 857.10

E 856.89

E 856.69

E 856.48

E 856.28

E 856.07

E 855.87

E 855.66

E 855.46

E 855.25

E 855.05

E 854.84

E 854.64

E 854.43

E 854.23

E 854.02

E 853.82

E 853.61

E 853.41

E 853.20

E 853.00

E 852.79

E 852.59

E 852.38

E 852.18

E 851.97

E 851.77

E 851.56

E 851.36

E 851.15

E 850.95

E 850.74

E 850.54

E 850.33

E 850.13

E 849.92

E 849.72

E 849.51

E 849.31

E 849.10

E 848.90

E 848.69

E 848.49

E 848.28

E 848.08

E 847.87

E 847.67

E 847.46

E 847.26

E 847.05

E 846.85

E 846.64

E 846.44

E 846.23

E 846.03

E 845.82

E 845.62

E 845.41

E 845.21

E 845.00

E 844.80

E 844.59

E 844.39

E 844.18

E 843.98

E 843.77

E 843.57

E 843.36

E 843.16

E 842.95

E 842.75

E 842.54

E 842.34

E 842.13

E 841.93

E 841.72

E 841.52

E 841.31

E 841.11

E 840.90

E 840.70

E 840.49

E 840.29

E 840.08

E 839.88

E 839.67

E 839.47

E 839.26

E 839.06

E 838.85

E 838.65

E 838.44

E 838.24

E 838.03

E 837.83

E 837.62

E 837.42

E 837.21

E 837.01

E 836.80

E 836.60

E 836.39

E 836.19

E 835.98

E 835.78

E 835.57

E 835.37

E 835.16

E 834.96

E 834.75

E 834.55

E 834.34

E 834.14

E 833.93

E 833.73

E 833.52

E 833.32

E 833.11

E 832.91

E 832.70

E 832.50

E 832.29

E 832.09

E 831.88

E 831.68

E 831.47

E 831.27

E 831.06

E 830.86

E 830.65

E 830.45

E 830.24

E 830.04

E 829.83

E 829.63

E 829.42

E 829.22

E 829.01

E 828.81

E 828.60

E 828.40

E 828.19

E 827.99

E 827.78

E 827.58

E 827.37

E 827.17

E 826.96

E 826.76

E 826.55

E 826.35

E 826.14

E 825.94

E 825.73

E 825.53

E 825.32

E 825.12

E 824.91

E 824.71

E 824.50

E 824.30

E 824.09

E 823.89

E 823.68

E 823.48

E 823.27

E 823.07

E 822.86

E 822.66

E 822.45

E 822.25

E 822.04

E 821.84

E 821.63

E 821.43

E 821.22

E 821.02

E 820.81

E 820.61

E 820.40

E 820.20

E 819.99

E 819.79

E 819.58

E 819.38

E 819.17

E 818.97

E 818.76

E 818.56

E 818.35

E 818.15

E 817.94

E 817.74

E 817.53

E 817.33

E 817.12

E 816.92

E 816.71

E 816.51

E 816.30

E 816.10

E 815.89

E 815.69

E 815.48

E 815.28

E 815.07

E 814.87

E 814.66

E 814.46

E 814.25

E 814.05

E 813.84

E 813.64

E 813.43

E 813.23

E 813.02

E 812.82

E 812.61

E 812.41

E 812.20

E 812.00

E 811.79

E 811.59

E 811.38

E 811.18

E 810.97

E 810.77

E 810.56

E 810.36

E 810.15

E 809.95

E 809.74

E 809.54

E 809.33

E 809.13

E 808.92

E 808.72

E 808.51

E 808.31

E 808.10

E 807.90

E 807.69

E 807.49

E 807.28

E 807.08

E 806.87

E 806.67

E 806.46

E 806.26

E 806.05

E 805.85

E 805.64

E 805.44

E 805.23

E 805.03

E 804.82

E 804.62

E 804.41

E 804.21

E 804.00

E 803.80

E 803.59

E 803.39

E 803.18

E 802.98

E 802.77

E 802.57

E 802.36

E 802.16

E 801.95

E 801.75

E 801.54

E 801.34

E 801.13

E 800.93

E 800.72

E 800.52

E 800.31

E 800.11

E 799.90

E 799.70

E 799.49

E 799.29

E 799.08

E 798.88

E 798.67

E 798.47

E 798.26

E 798.06

E 797.85

E 797.65

E 797.44

E 797.24

E 797.03

E 796.83

E 796.62

E 796.42

E 796.21

E 796.01

E 795.80

E 795.60

E 795.39

E 795.19

E 794.98

E 794.78

E 794.57

E 794.37

E 794.16

E 793.96

E 793.75

E 793.55

E 793.34

E 793.14

E 792.93

E 792.73

E 792.52

E 792.32

E 792.11

E 791.91

E 791.70

E 791.50

E 791.29

E 791.09

E 790.88

E 790.68

E 790.47

E 790.27

E 790.06

E 789.86

E 789.65

E 789.45

E 789.24

E 789.04

E 788.83

E 788.63

E 788.42

E 788.22

E 788.01

E 787.81

E 787.60

E 787.40

E 787.19

E 786.99

E 786.78

E 786.58

E 786.37

E 786.17

E 785.96

E 785.76

E 785.55

E 785.35

E 785.14

E 784.94

E 784.73

E 784.53

E 784.32

E 784.12

E 783.91

E 783.71

E 783.50

E 783.30

E 783.09

E 782.89

E 782.68

E 782.48

E 782.27

E 782.07

E 781.86

E 781.66

E 781.45

E 781.25

E 781.04

E 780.84

E 780.63

E 780.43

E 780.22

E 780.02

E 779.81

E 779.61

E 779.40

E 779.20

E 778.99

E 778.79

E 778.58

E 778.38

E 778.17

E 777.97

E 777.76

E 777.56

E 777.35

E 777.15

E 776.94

E 776.74

E 776.53

E 776.33

E 776.12

E 775.92

E 775.71

E 775.51

E 775.30

E 775.10

E 774.89

E 774.69

E 774.48

E 774.28

E 774.07

E 773.87

E 773.66

E 773.46

E 773.25

E 773.05

E 772.84

E 772.64

E 772.43

E 772.23

E 772.02

E 771.82

E 771.61

E 771.41

E 771.20

E 771.00

E 770.79

E 770.59

E 770.38

E 770.18

E 769.97

E 769.77

E 769.56

E 769.36

E 769.15

E 768.95

E 768.74

E 768.54

E 768.33

E 768.13

E 767.92

E 767.72

E 767.51

E 767.31

E 767.10

E 766.90

E 766.69

E 766.49

E 766.28

E 766.08

E 765.87

E 765.67

E 765.46

E 765.26

E 765.05

E 764.85

E 764.64

E 764.44

E 764.23

E 764.03

E 763.82

E 763.62

E 763.41

E 763.21

E 763.00

E 762.80

E 762.59

E 762.39

E 762.18

E 761.98

E 761.77

E 761.57

E 761.36

E 761.16

E 760.95

E 760.75

E 760.54

E 760.34

E 760.13

E 759.93

E 759.72

E 759.52

E 759.31

E 759.11

E 758.90

E 758.70

E 758.49

E 758.29

E 758.08

E 757.88

E 757.67

E 757.47

E 757.26

E 757.06

E 756.85

E 756.65

E 756.44

E 756.24

E 756.03

E 755.83

E 755.62

E 755.42

E 755.21

E 755.01

E 754.80

E 754.60

E 754.39

E 754.19

E 753.98

E 753.78

E 753.57

E 753.37

E 753.16

E 752.96

E 752.75

E 752.55

E 752.34

E 752.14

E 751.93

E 751.73

E 751.52

E 751.32

E 751.11

E 750.91

E 750.70

E 750.50

E 750.29

E 750.09

E 749.88

E 749.68

E 749.47

E 749.27

E 749.06

E 748.86

E 748.65

E 748.45

E 748.24

E 748.04

E 747.83

E 747.63

E 747.42

E 747.22

E 747.01

E 746.81

E 746.60

E 746.40

E 746.19

E 745.99

E 745.78

E 745.58

E 745.37

E 745.17

E 744.96

E 744.76

E 744.55

E 744.35

E 744.14

E 743.94

E 743.73

E 743.53

E 743.32

E 743.12

E 742.91

E 742.71

E 742.50

E 742.30

E 742.09

E 741.89

E 741.68

E 741.48

E 741.27

E 741.07

E 740.86

E 740.66

E 740.45

E 740.25

E 740.04

E 739.84

E 739.63

E 739.43

E 739.22

E 739.02

E 738.81

E 738.61

E 738.40

E 738.20

E 737.99

E 737.79

E 737.58

E 737.38

E 737.17

E 736.97

E 736.76

E 736.56

E 736.35

E 736.15

E 735.94

E 735.74

E 735.53

E 735.33

E 735.12

E 734.92

E 734.71

E 734.51

E 734.30

E 734.10

E 733.89

E 733.69

E 733.48

E 733.28

E 733.07

E 732.87

E 732.66

E 732.46

E 732.25

E 732.05

E 731.84

E 731.64

E 731.43

E 731.23

E 731.02

E 730.82

E 730.61

E 730.41

E 730.20

E 730.00

E 729.79

E 729.59

E 729.38

E 729.18

E 728.97

E 728.77

E 728.56

E 728.36

E 728.15

E 727.95

E 727.74

E 727.54

E 727.33

E 727.13

E 726.92

E 726.72

E 726.51

E 726.31

E 726.10

E 725.90

E 725.69

E 725.49

E 725.28

E 725.08

E 724.87

E 724.67

E 724.46

E 724.26

E 724.05

E 723.85

E 723.64

E 723.44

E 723.23

E 723.03

E 722.82

E 722.62

E 722.41

E 722.21

E 722.00

E 721.80

E 721.59

E 721.39

E 721.18

E 720.98

E 720.77

E 720.57

E 720.36

E 720.16

E 719.95

E 719.75

E 719.54

E 719.34

E 719.13

E 718.93

E 718.72

E 718.52

E 718.31

E 718.11

E 717.90

E 717.70

E 717.49

E 717.29

E 717.08

E 716.88

E 716.67

E 716.47

E 716.26

E 716.06

E 715.85

E 715.65

E 715.44

E 715.24

E 715.03

E 714.83

E 714.62

E 714.42

E 714.21

E 714.01

E 713.80

E 713.60

E 713.39

E 713.19

E 712.98

E 712.78

E 712.57

E 712.37

E 712.16

E 711.96

E 711.75

E 711.55

E 711.34

E 711.14

E 710.93

E 710.73

E 710.52

E 710.32

E 710.11

E 709.91

E 709.70

E 709.50

E 709.29

E 709.09

E 708.88

E 708.68

E 708.47

E 708.27

E 708.06

E 707.86

E 707.65

E 707.45

E 707.24

E 707.04

E 706.83

E 706.63

E 706.42

E 706.22

E 706.01

E 705.81

E 705.60

E 705.40

E 705.19

E 704.99

E 704.78

E 704.58

E 704.37

E 704.17

E 703.96

E 703.76

E 703.55

E 703.35

E 703.14

E 702.94

E 702.73

E 702.53

E 702.32

E 702.12

E 701.91

E 701.71

E 701.50

E 701.30

E 701.09

E 700.89

E 700.68

E 700.48

E 700.27

E 700.07

E 699.86

E 699.66

E 699.45

E 699.25

E 699.04

E 698.84

E 698.63

E 698.43

E 698.22

E 698.02

E 697.81

E 697.61

E 697.40

E 697.20

E 696.99

E 696.79

E 696.58

E 696.38

E 696.17

E 695.97

E 695.76

E 695.56

E 695.35

E 695.15

E 694.94

E 694.74

E 694.53

E 694.33

E 694.12

E 693.92

E 693.71

E 693.51

E 693.30

E 693.10

E 692.89

E 692.69

E 692.48

E 692.28

E 692.07

E 691.87

E 691.66

E 691.46

E 691.25

E 691.05

E 690.84

E 690.64

E 690.43

E 690.23

E 690.02

E 689.82

E 689.61

E 689.41

E 689.20

E 689.00

E 688.79

E 688.59

E 688.38

E 688.18

E 687.97

E 687.77

E 687.56

E 687.36

E 687.15

E 686.95

E 686.74

E 686.54

E 686.33

E 686.13

E 685.92

E 685.72

E 685.51

E 685.31

E 685.10

E 684.90

E 684.69

E 684.49

E 684.28

E 684.08

E 683.87

E 683.67

E 683.46

E 683.26

E 683.05

E 682.85

E 682.64

E 682.44

E 682.23

E 682.03

E 681.82

E 681.62

E 681.41

E 681.21

E 681.00

E 680.80

E 680.59

E 680.39

E 680.18

E 679.98

E 679.77

E 679.57

E 679.36

E 679.16

E 678.95

E 678.75

E 678.54

E 678.34

E 678.13

E 677.93

E 677.72

E 677.52

E 677.31

E 677.11

E 676.90

E 676.70

E 676.49

E 676.29

E 676.08

E 675.88

E 675.67

E 675.47

E 675.26

E 675.06

E 674.85

E 674.65

E 674.44

E 674.24

E 674.03

E 673.83

E 673.62

E 673.42

E 673.21

E 673.01

E 672.80

E 672.60

E 672.39

E 672.19

E 671.98

E 671.78

E 671.57

E 671.37

E 671.16

E 670.96

E 670.75

E 670.55

E 670.34

E 670.14

E 669.93

E 669.73

E 669.52

E 669.32

E 669.11

E 668.91

E 668.70

E 668.50

E 668.29

E 668.09

E 667.88

E 667.68

E 667.47

E 667.27

E 667.06

E 666.86

E 666.65

E 666.45

E 666.24

E 666.04

E 665.83

E 665.63

E 665.42

E 665.22

E 665.01

E 664.81

E 664.60

E 664.40

E 664.19

E 663.99

E 663.78

E 663.58

E 663.37

E 663.17

E 662.96

E 662.76

E 662.55

E 662.35

E 662.14

E 661.94

E 661.73

E 661.53

E 661.32

E 661.12

E 660.91

E 660.71

E 660.50

E 660.30

E 660.09

E 659.89

E 659.68

E 659.48

E 659.27

E 659.07

E 658.86

E 658.66

E 658.45

E 658.25

E 658.04

E 657.84

E 657.63

E 657.43

E 657.22

E 657.02

E 656.81

E 656.61

E 656.40

E 656.20

E 655.99

E 655.79

E 655.58

E 655.38

E 655.17

E 654.97

E 654.76

E 654.56

E 654.35

E 654.15

E 653.94

E 653.74

E 653.53

E 653.33

E 653.12

E 652.92

E 652.71

E 652.51

E 652.30

E 652.10

E 651.89

E 651.69

E 651.48

E 651.28

E 651.07

E 650.87

E 650.66

E 650.46

E 650.25

E 650.05

E 649.84

E 649.64

E 649.43

E 649.23

E 649.02

E 648.82

E 648.61

E 648.41

E 648.20

E 648.00

E 647.79

E 647.59

E 647.38

E 647.18

E 646.97

E 646.77

E 646.56

E 646.36

E 646.15

E 645.95

E 645.74

E 645.54

E 645.33

E 645.13

E 644.92

E 644.72

E 644.51

E 644.31

E 644.10

E 643.90

E 643.69

E 643.49

E 643.28

E 643.08

E 642.87

E 642.67

E 642.46

E 642.26

E 642.05

E 641.85

E 641.64

E 641.44

E 641.23

E 641.03

E 640.82

E 640.62

E 640.41

E 640.21

E 640.00

E 639.80

E 639.59

E 639.39

E 639.18

E 638.98

E 638.77

E 638.57

E 638.36

E 638.16

E 637.95

E 637.75

E 637.54

E 637.34

E 637.13

E 636.93

E 636.72

E 636.52

E 636.31

E 636.11

E 635.90

E 635.70

E 635.49

E 635.29

E 635.08

E 634.88

E 634.67

E 634.47

E 634.26

E 634.06

E 633.85

E 633.65

E 633.44

E 633.24

E 633.03

E 632.83

E 632.62

E 632.42

E 632.21

E 632.01

E 631.80

E 631.60

E 631.39

E 631.19

E 630.98

E 630.78

E 630.57

E 630.37

E 630.16

E 629.96

E 629.75

E 629.55

E 629.34

E 629.14

E 628.93

E 628.73

E 628.52

E 628.32

E 628.11

E 627.91

E 627.70

E 627.50

E 627.29

E 627.09

E 626.88

E 626.68

E 626.47

E 626.27

E 626.06

E 625.86

E 625.65

E 625.45

E 625.24

E 625.04

E 624.83

E 624.63

E 624.42

E 624.22

E 624.01

E 623.81

E 623.60

E 623.40

E 623.19

E 622.99

E 622.78

E 622.58

E 622.37

E 622.17

E 621.96

E 621.76

E 621.55

E 621.35

E 621.14

E 620.94

E 620.73

E 620.53

E 620.32

E 620.12

E 619.91

E 619.71

E 619.50

E 619.30

E 619.09

E 618.89

E 618.68

E 618.48

E 618.27

E 618.07

E 617.86

E 617.66

E 617.45

E 617.25

E 617.04

E 616.84

E 616.63

E 616.43

E 616.22

E 616.02

E 615.81

E 615.61

E 615.40

E 615.20

E 614.99

E 614.79

E 614.58

E 614.38

E 614.17

E 613.97

E 613.76

E 613.56

E 613.35

E 613.15

E 612.94

E 612.74

E 612.53

E 612.33

E 612.12

E 611.92

E 611.71

E 611.51

E 611.30

E 611.10

E 610.89

E 610.69

E 610.48

E 610.28

E 610.07

E 609.87

E 609.66

E 609.46

E 609.25

E 609.05

E 608.84

E 608.64

E 608.43

E 608.23

E 608.02

E 607.82

E 607.61

E 607.41

E 607.20

E 607.00

E 606.79

E 606.59

E 606.38

E 606.18

E 605.97

E 605.77

E 605.56

E 605.36

E 605.15

E 604.95

E 604.74

E 604.54

E 604.33

E 604.13

E 603.92

E 603.72

E 603.51

E 603.31

E 603.10

E 602.90

E 602.69

E 602.49

E 602.28

E 602.08

E 601.87

E 601.67

E 601.46

E 601.26

E 601.05

E 600.85

E 600.64

E 600.44

E 600.23

E 600.03

E 599.82

E 599.62

E 599.41

E 599.21

E 599.00

E 598.80

E 598.59

E 598.39

E 598.18

E 597.98

E 597.77

E 597.57

E 597.36

E 597.16

E 596.95

E 596.75

E 596.54

E 596.34

E 596.13

E 595.93

E 595.72

E 595.52

E 595.31

E 595.11

E 594.90

E 594.70

E 594.49

E 594.29

E 594.08

E 593.88

E 593.67

E 593.47

E 593.26

E 593.06

E 592.85

E 592.65

E 592.44

E 592.24

E 592.03

E 591.83

E 591.62

E 591.42

E 591.21

E 591.01

E 590.80

E 590.60

E 590.39

E 590.19

E 589.98

E 589.78

E 589.57

E 589.37

E 589.16

E 588.96

E 588.75

E 588.55

E 588.34

E 588.14

E 587.93

E 587.73

E 587.52

E 587.32

E 587.11

E 586.91

E 586.70

E 586.50

E 586.29

E 586.09

E 585.88

E 585.68

E 585.47

E 585.27

E 585.06

E 584.86

E 584.65

E 584.45

E 584.24

E 584.04

E 583.83

E 583.63

E 583.42

E 583.22

E 583.01

E 582.81

E 582.60

E 582.40

E 582.19

E 581.99

E 581.78

E 581.58

E 581.37

E 581.17

E 580.96

E 580.76

E 580.55

E 580.35

E 580.14

E 579.94

E 579.73

E 579.53

E 579.32

E 579.12

E 578.91

E 578.71

E 578.50

E 578.30

E 578.09

E 577.89

E 577.68

E 577.48

E 577.27

E 577.07

E 576.86

E 576.66

E 576.45

E 576.25

E 576.04

E 575.84

E 575.63

E 575.43

E 575.22

E 575.02

E 574.81

E 574.61

E 574.40

E 574.20

E 573.99

E 573.79

E 573.58

E 573.38

E 573.17

E 572.97

E 572.76

E 572.56

E 572.35

E 572.15

E 571.94

E 571.74

E 571.53

E 571.33

E 571.12

E 570.92

E 570.71

E 570.51

E 570.30

E 570.10

E 569.89

E 569.69

E 569.48

E 569.28

E 569.07

E 568.87

E 568.66

E 568.46

E 568.25

E 568.05

E 567.84

E 567.64

E 567.43

E 567.23

E 567.02

E 566.82

E 566.61

E 566.41

E 566.20

E 566.00

E 565.79

E 565.59

E 565.38

E 565.18

E 564.97

E 564.77

E 564.56

E 564.36

E 564.15

E 563.95

E 563.74

E 563.54

E 563.33

E 563.13

E 562.92

E 562.72

E 562.51

E 562.31

E 562.10

E 561.90

E 561.69

E 561.49

E 561.28

E 561.08

E 560.87

E 560.67

E 560.46

E 560.26

E 560.05

E 559.85

E 559.64

E 559.44

E 559.23

E 559.03

E 558.82

E 558.62

E 558.41

E 558.21

E 558.00

E 557.80

E 557.59

E 557.39

E 557.18

E 556.98

E 556.77

E 556.57

E 556.36

E 556.16

E 555.95

E 555.75

E 555.54

E 555.34

E 555.13

E 554.93

E 554.72

E 554.52

E 554.31

E 554.11

E 553.90

E 553.70

E 553.49

E 553.29

E 553.08

E 552.88

E 552.67

E 552.47

E 552.26

E 552.06

E 551.85

E 551.65

E 551.44

E 551.24

E 551.03

E 550.83

E 550.62

E 550.42

E 550.21

E 550.01

E 549.80

E 549.60

E 549.39

E 549.19

E 548.98

E 548.78

E 548.57

E 548.37

E 548.16

E 547.96

E 547.75

E 547.55

E 547.34

E 547.14

E 546.93

E 546.73

E 546.52

E 546.32

E 546.11

E 545.91

E 545.70

E 545.50

E 545.29

E 545.09

E 544.88

E 544.68

E 544.47

E 544.27

E 544.06

E 543.86

E 543.65

E 543.45

E 543.24

E 543.04

E 542.83

E 542.63

E 542.42

E 542.22

E 542.01

E 541.81

E 541.60

E 541.40

E 541.19

E 540.99

E 540.78

E 540.58

E 540.37

E 540.17

E 539.96

E 539.76

E 539.55

E 539.35

E 539.14

E 538.94

E 538.73

E 538.53

E 538.32

E 538.12

E 537.91

E 537.71

E 537.50

E 537.30

E 537.09

E 536.89

E 536.68

E 536.48

E 536.27

E 536.07

E 535.86

E 535.66

E 535.45

E 535.25

E 535.04

E 534.84

E 534.63

E 534.43

E 534.22

E 534.02

E 533.81

E 533.61

E 533.40

E 533.20

E 532.99

E 532.79

E 532.58

E 532.38

E 532.17

E 531.97

E 531.76

E 531.56

E 531.35

E 531.15

E 530.94

E 530.74

E 530.53

E 530.33

E 530.12

E 529.92

E 529.71

E 529.51

E 529.30

E 529.10

E 528.89

E 528.69

E 528.48

E 528.28

E 528.07

E 527.87

E 527.66

E 527.46

E 527.25

E 527.05

E 526.84

E 526.64

E 526.43

E 526.23

E 526.02

E 525.82

E 525.61

E 525.41

E 525.20

E 525.00

E 524.79

E 524.59

E 524.38

E 524.18

E 523.97

E 523.77

E 523.56

E 523.36

E 523.15

E 522.95

E 522.74

E 522.54

E 522.33

E 522.13

E 521.92

E 521.72

E 521.51

E 521.31

E 521.10

E 520.90

E 520.69

E 520.49

E 520.28

E 520.08

E 519.87

E 519.67

E 519.46

E 519.26

E 519.05

E 518.85

E 518.64

E 518.44

E 518.23

E 518.03

E 517.82

E 517.62

E 517.41

E 517.21

E 517.00

E 516.80

E 516.59

E 516.39

E 516.18

E 515.98

E 515.77

E 515.57

E 515.36

E 515.16

E 514.95

E 514.75

E 514.54

E 514.34

E 514.13

E 513.93

E 513.72

E 513.52

E 513.31

E 513.11

E 512.90

E 512.70

E 512.49

E 512.29

E 512.08

E 511.88

E 511.67

E 511.47

E 511.26

E 511.06

E 510.85

E 510.65

E 510.44

E 510.24

E 510.03

E 509.83

E 509.62

E 509.42

E 509.21

E 509.01

E 508.80

E 508.60

E 508.39

E 508.19

E 507.98

E 507.78

E 507.57

E 507.37

E 507.16

E 506.96

E 506.75

E 506.55

E 506.34

E 506.14

E 505.93

E 505.73

E 505.52

E 505.32

E 505.11

E 504.91

E 504.70

E 504.50

E 504.29

E 504.09

E 503.88

E 503

FED.RD.	STATE	PROJECT	
2	OHIO		

MAH.-18-17.20

62
492

FOR CONTINUATION OF RAMP 'N' SEE MAINLINE PLAN & PROFILE SHEET STA. 1020+00 TO 1050+00 SHEET Nº 40

TAPER BEGINS 44' LT. OF STA. 1027+17.64
END OF RAMP 'N' 52' LT. OF STA. 1023+67.64

BRIDGE Nº MAH-18-1050

END WORK 44' LT. OF 1050+50. P.C.C. 11+73.95

BEGIN RAMP 'N' ℄ 0+00
T+31.06 (WOODLAND)
0+07.50 (RAMP 'N')

℄ WOODLAND AVENUE

EXIST. ℄
PROP. ℄

S 88°57'35" E

P.C. 7+27.72

CURB RETURN DATA
Δ: 91°22'25"
D: 38°11'50"
R: 150'
T: 149.74'
L: 239.24'

P.T. 0+80.01
12 RT.

I.S. STA. 1+18.61

SPIRAL DATA
Ls: 150'
Θs: 28°38'52"
L.T.: 101.34'
S.T.: 51.22'

SPIRAL DATA
Ls: 200'
Θs: 38°11'50"
L.T.: 133.44'
S.T.: 66.76'

SPIRAL DATA
Ls: 150'
Θs: 28°38'52"
L.T.: 101.34'
S.T.: 51.22'

CURVE DATA
Δ: 24°30'
Dc: 7°
Rc: 818.51'
T: 177.72'
Lc: 350'

CURVE DATA
Δ: 36°11'18"
R: 150'
D: 38°11'50"
T: 49.01'
Lc: 94.74'

S.C. STA. 2+68.61

TYPE 2A CURB

TYPE C CURB

℄ MARKET STREET

℄ HAYES AVENUE

℄ ERIE STREET

℄ MARLIN STREET

EXIST 15" C.S. @ 0.46

℄ YOUNGSTOWN EXPWAY

PROPOSED RELOCATION 48" COMBINATION SEWER FOR DETAILS SEE SHEET Nº 101

STA. 1030+19.40
50+00 (MARKET ST.)

NOSE STA. 1032+82.24

NOSE STA. 38' LT. OF STA. 1032+82.24

C.S. STA. 1030+91.44

NOSE STA. 9+50.51

C.S. STA. 8+25.95

C.S. STA. 5+13.35

C.S. STA. 2+68.61

5' WIDTH

5' PAVED BERM

FOR CONSTRUCTION DETAILS - RAMP 'N' & MAIN LINE SEE SHEET NO. 69

MAINLINE CURVE DATA
Δ: 53°49'25"
D: 5°00'00"
Dc: 11°30'
T: 1035.91'
Es: 178.91'
Yx: 398.39'

Δ: 20°08'00"
D: 5°00'00"
Dc: 11°30'
T: 1035.91'
Es: 178.91'
Yx: 398.39'

1035

S 19°41'44" E

END WORK
ON A RADIAL LINE WITH STA. 7+75.45

NOSE STA. 7+34 LT. 15' RT. 7+75.45 (RAMP) (MARLIN)

I-12 CONCRETE CURB & COMBINATION CURB & GUTTER

CODE	LOCATION FROM	LOCATION TO	TYPE-6 L.F.	TYPE-2 L.F.	TYPE-2A L.F.	SPECIAL L.F.
C-1	8+58	11+73.95	276			
C-2	7+50.31	9+50.31				200
C-3	0+00	0+80		80		
C-4	0+80	3+63.35			283	
C-5	2+75.49	3+63.35	88			

EROSION CONTROL

CODE	LOCATION FROM	LOCATION TO	I-10 SOD S.Y.	I-14 PAVED GUTTER TYPE I LIN. FT.	I-14 GUTTER TYPE I MOD. L.F.
E-1	9+00	11+50		250	
E-2	5+00	A-4	217		
E-3					20
SHEET TOTAL			217	250	20

I-13 5' SIDEWALK

CODE	S.F.
S-1	45

I-4 UNDERDRAINS LIN. FT.

CODE	LOCATION FROM	LOCATION TO	DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 a	I-5 PIPE SPEC. EACH 6" 90° BEND	
U-1	11+74	A-3	D	240	18	1	
U-2	A-4	3+27	S	627		1	
U-3	A-6	3+21	S	311	10		
SHEET TOTAL				1178	28	2	

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH-BASINS

CODE	LOCATION & STATION	#2-2A C.B EACH	#6 C.B EACH	#1 M.H. EACH	YOUNGS TYPE2 INLET EACH	
A-2	9+47.5 -14.0 LT. ℄		1			
A-3	9+34.5 -17.0 LT. ℄			1		
A-4	9+00 -19.0 RT. ℄	1				
A-5	2+82.3 - 12.0' RT. ℄ MARLIN				1	
A-6	0+52 - 2.0' LT. ℄				1	
SHEET TOTAL		1	1	1	2	

ESTIMATED QUANTITIES I-2 PIPES

CODE	LOCATION FROM	LOCATION TO	CLASS "B" STORM SEWERS UNDER PAV & APP. 12"	
P-2	A-3	A-4	15	
P-3	A-2	A-3	50	
P-4	A-5		EX. 15" C.S. & MH.	
P-5	A-6		EX. M.H. & 44" MARLIN & WOODLAND	
SHEET TOTALS			119	

B.M.#54
TOP OF STEM ON HYDRANT 10' N.W. OF TOP OF HIGHES & MARKET ST. ELEV. 966.86

B.M.#69
TOP OF STEM ON HYDRANT ON E. SIDE OF MARLIN @ N. OF KYLE ST. ELEV. 947.98

SCALE: 1"=50'

A-4
STA. 9+0 (19.0' RT. ℄)
I-8 2-2A C.B.
WINDOW ELEV. 921.23
℄ 8" I-4 919.04
℄ 15" I-2 918.79

A-6
STA. 0+52 (2.0' LT. ℄)
YNG'ST TYPE II INLET
TOP OF CURB 931.10
WINDOW ELEV. 930.35
℄ 12" I-2 927.04
℄ INLET 925.35

A-5
STA. 2+82.3 MARLIN
I-8 YNG'ST. TYPE II
TOP OF CURB 933.08
WINDOW EL. 932.58
℄ 12" I-2 932.02
℄ INLET 930.33

EXIST. 15" C.S. ℄ 929.80

11.0' 12" I-2 @ 0.1850

A-3
STA. 9+34.5
I-8 Nº 1 M.H.
COVER ELEV. 924.36
℄ 8" I-4 918.77
℄ 12" I-2 918.44

A-2
STA. 9+47.5 (16.5' LT. ℄)
I-8 Nº 6 C.B.
GRATE EL. 924.23
℄ 12" I-2 - 920.98

15'-12" I-2 @ 0.1698

STA. 9+34.5
I-8 Nº 1 M.H.
℄ 12" - 918.44

P-2
STA. 9+0 (19.0' RT. ℄)
WINDOW EL. 921.23
℄ 8" I-4 919.04
℄ 12" I-2 918.79
BASE LINE RAMP 'N'

50'-12" I-2 @ 0.0070

P-5
STA. 0+80.01 ~ P.T. CURB RETURN
EL. 931.00

2.00'

45'-12" I-2 @ 0.0420

℄ RAMP 'L'

STA. 0+12
℄ MARLIN
EXIST. M.H.
℄ 12" I-2 923.35
℄ EXIST 15" 914.4

PROP. PAVT.

P-4
EXIST. 15" C.S. ℄ 929.80

P-3
15'-12" I-2 @ 0.1698

GRAPHIC GRADE

TAPER BEGINS 44' LT. OF STA. 1027+17.64
END RAMP 'N' 52' LT. OF STA. 1023+67.64

HORIZONTAL

P.C.C. 11+73.95

NOSE STA. 9+50.51
ELEV. 932.40

P.V.I. 9+34.00
ELEV. 919.11

P.V.C. STA. 6+34 - EL. 928.32

P.V.T. STA. 6+25 EL. 928.60

P.V.C. STA. 5+25
EL. 932.78

P.V.I. STA. 5+75
EL. 930.13

P.V.T. 4+50
EL. 930.76

-3.00%

+2.72%

6.00' V.C.

10.00' V.C.

15.00%

℄ 919.08

℄ 917.93

℄ 917.43
0+34.5

STA. 11+68
RELOC. 48" C.S.
℄ 48" 912.69
1.0 CONC. ENC.

FOR PROFILE GRADE & PAVT. DETAILS FOR 0+0 TO 0+80.01 SEE SHEET Nº 73

STATION	PROFILE GRADE	S.E.	OUTSIDE EDGE	STATION	PROFILE GRADE	S.E.	OUTSIDE EDGE
8+73.95	924.73	+.88	925.11	5+75	930.41	+.25	930.66
8+00	924.56	+.80	925.36	5+52.35	931.40	+.25	931.65
7+75	924.96	+.73	925.69	5+50	931.53	+.26	931.79
7+50	925.41	+.65	926.06	5+25	932.78	+.39	933.17
7+25	925.93	+.57	926.50	5+13.35	933.40	+.47	933.87
7+00	926.51	+.49	927.00	5+00	934.11	+.55	934.66
6+75	927.15	+.41	927.56	4+75	935.34	+.69	936.03
6+50	927.84	+.33	928.17	4+50	936.76	+.83	937.59
6+34	928.32	+.28	928.60	4+25	937.97	+.98	938.95
6+25	928.60	+.25	928.85	4+00	939.03	+1.12	940.15
6+23.95	928.63	+.25	928.88	3+75	939.87	+1.26	941.13
6+00	929.44	+.25	929.69	3+63.35	940.16	+1.33	941.49

PLATE I — PLAN - PROFILE O. P. R. & R. E. STANDARD
2GI FM-3 AGEPROOF FILM MADE AND PRINTED IN U. S. A.
EUGENE DIETZGEN CO., CHICAGO

PLAN & PROFILE - RAMP "N"


FED. RD.	STATE	PROJECT	
2	OHIO		

63
492

MAH-18-17.20

TABLE OF OFFSETS - CURVE Nº 1		
STATION	℄ TO FACE CURB	℄ TO O.E. RAMP "B"
926+28.90	6.73	70.73
926+50	6.51	67.61
926+75	6.25	63.41
927+00	6.00	59.72
927+25	5.75	56.65
927+50	5.50	53.72
927+75	5.25	51.49
928+00	5.00	49.62
928+25	4.75	47.94
928+50	4.50	46.70
928+75	4.25	45.75
929+00	4.00	45.05
929+25	3.75	44.50
929+50	3.50	44.20
929+75	3.25	43.97
929+99.42	3.00	44.00

TABLE OF OFFSETS - CURVE 1	
STATION	℄ TO FACE CURB
922 + 50	10.51
922 + 75	10.26
923 + 00	10.01
923 + 25	9.76
923 + 50	9.51
923 + 75	9.26
924 + 00	9.01
924 + 25	8.76
924 + 50	8.51
924 + 75	8.26
925 + 00	8.01
925 + 25	7.75
925 + 50	7.50
925 + 75	7.25
926 + 00	7.00



LEGEND FOR PAVING DETAILS

- Ⓐ STANDARD LONGITUDINAL JOINT
- Ⓒ EXPANSION JOINT WITHOUT DOWELS
- Ⓓ STANDARD EXPANSION JOINT
- Ⓔ STANDARD CONTRACTION JOINT-PLACED AT 60' INTERVALS OR LESS





TABLE OF OFFSETS - CURVE Nº 1		
STATION	℄ TO FACE CURB	℄ TO O.E. RAMP "A"
928+87.00	4.13	55.13
929+00	4.00	52.86
929+25	3.75	51.35
929+50	3.50	49.95
929+75	3.25	48.67
929+99.42	3.00	47.50
930+00	3.00	47.49
930+25	3.00	46.67
930+50	3.00	45.96
930+75	3.00	45.36
931+00	3.00	44.87
931+25	3.00	44.49
931+50	3.00	44.22
931+75	3.00	44.05
932+00	3.00	44.00

DETAILS - RAMPS "A" & "B"


FED. RD.	STATE	PROJECT	
2	OHIO		

G4
492

MAH - 18 - 17.20



RAMP "D"



RAMP "C"

DETAILS - RAMPS "C" & "D"

FED. RD.	STATE	PROJECT	
2	OHIO		

G5
492

MAH-18-17.20


RAMP 'E' SPIRAL DATA

Δ = 14°	P = 2.04'
R_c = 818.51'	K = 99.95'
L_s = 200'	Xc = 199.70'
D_c = 7°	Y_c = 8.14'
Θ_s = 7°	L.T. = 133.44'
T_s = 200.70'	S.T. = 66.76'
E_s = 8.20'	L.C. = 199.87'


THIS AREA TO BE PAVED WITH :
1¾" T-35 ASP. CONC. SURF. COURSE (70-85)
1½" B-35 ASP. CONC. LEVELING COURSE (70-85)
6¾" B-35 ASP. CONC. BASE COURSE (70-85)

MAINLINE CURVE DATA

Δ = 60° 43' 03"
D_c = 5° 30'
R_c = 1041.74'
L_s = 400'
T_s = 818.68'
E_s = 172.95'
L_c = 703.95'



RAMP 'E'



RAMP 'F'

DETAILS - RAMPS "E" & "F"


FED. RD.	STATE	PROJECT	
2	OHIO		

GG 402


MAH-18-17.20

DO NOT CONSTRUCT THIS CURB UNTIL THE MAHONING AVE. BRIDGE STRUCTURE Nº MAH-18-1815 IS COMPLETED & OPEN TO TRAFFIC. SEE MAINTENANCE OF TRAFFIC SHEET Nº 15

THIS AREA TO BE PAVED WITH :
1 1/4" T-35 ASPHALTIC CONC. SURFACE COURSE (70-85)
1 3/4" B-35 ASPHALTIC CONC. LEVELING COURSE (70-85)
4 1/2" B-35 ASPHALTIC CONC. BASE COURSE (70-85)



RAMP 'G'



RAMP "H"

DETAILS - RAMPS "G" & "H"


FED.RD.	STATE	PROJECT	
2	OHIO		

G7
492

MAH - 18 - 17.20

RAMP 'J' CURVE DATA

Δ = 10° 32' 12"
D_c = 1° 30'
R_c = 3819.72'
L_c = 702.44'
T_c = 352.22'
E_c = 16.20'



MAINLINE CURVE DATA

Δ = 32° 41' 03"
D_c = 2° 45'
R_c = 2083.48'
L_c = 1188.51'
T_c = 610.91'


RAMP 'J'

DETAIL - RAMP 'J'


FED. RD.	STATE	PROJECT	
2	OHIO		

68
492

MAH-18-17.20



RAMP "K"




RAMP "L"

DETAILS - RAMPS "K" & "L"


FED. RD.	STATE	PROJECT	
2	OHIO		

69
492

MAH-18-17.20



RAMP "M"



RAMP "N"

DETAILS - RAMPS "M" & "N"

FED. RD.	STATE	PROJECT	
2	OHIO		


MAH-18-17.20

70
492

CURVE DATA TO BACK OF WALK
Δ = 14° 37' 52"
R = 279.48'
T = 35.89'
L = 71.37'

NOTE: ELEVATIONS ARE ALONG GUTTER LINE.


CODE	I-15 SIDEWALK S.F.	
S-1	705	
S-2	895	
S-3	172	
S-4	172	
S-5	585	
S-6	240	
S-7	42	
	2781	✓



RAMP "A"

END RAMP "B" STA. 15+98.54
℄-WELLINGTON STA. 6+33.94

END WORK STA. 15+88.54



CURB RETURN DATA
Δ = 90° 17' 32"
R = 30.00'
T = 30.15'
Lc = 47.28

CURB RETURN DATA
Δ = 89° 42' 28"
R = 30.00'
T = 29.85'
Lc = 46.97'

RAMP "B"

CODE	I-12 HEADER CURB TYPE 2 - L.F.	I-12 CONC. CURB TYPE 2-A L.F.	I-12 COMB. CURB & GUTTER TYPE 2 - L.F.
C-1		141	
C-2	104		
C-3			172
C-4		47	
C-5		47	
C-6		103	
C-7		58	
C-8		63	
C-9		102	
C-10		138	
C-11		138	
Total	104 ✓	837 ✓	172 ✓

LEGEND FOR INTERSECTIONS

Ⓐ STANDARD LONGITUDINAL JOINT.
Ⓑ STANDARD KEY JOINT WITHOUT TIE BARS.
Ⓒ EXPANSION JOINT WITHOUT DOWELS - LOCATED ON RADIAL LINES.
Ⓓ STANDARD EXPANSION JOINT.
Ⓔ STANDARD CONTRACTION JOINT - PLACED AT 60' INTERVALS OR LESS.

000.00 DENOTES PAVEMENT ELEVATIONS.

CURVE	Δ	R	T	Lc	P.C.	P.T.
1	63°09'50"	64.00	39.34'	70.55'	5+91.01	6+61.56
2	63°09'50"	50.00	30.74'	55.12'	5+94.04	6+68.29
3	58°39'03"	100.00	56.164'	102.365	5+91.64	0+81.94
4	9°03'33"	100.00	7.91'	15.81'	17.25 LT. 0+46.44	10 LT. 0+62.19
5	112°17'24"	15.00			17.25 LT. 0+46.44	10 RT. 6+87.18
6	102°08'37"	15.00	18.54'	26.72'	17.31 RT. 6+71.47	15 LT. 6+82.71
7	18°46'33"	100.00	12.97'	25.79'	17.31 RT. 6+71.47	14 RT. 6+96.98

RAMP "C"

℄-BRIDGE ST.

CURVE DATA
℄-BRIDGE ST.
Δ = 128° 59' 50"
R = 57.00'
T = 119.49'
Lc = 128.33'

P.R.C. STA. 17+93.95

SALT SPRINGS RD.

NOTE:
FOR INTERSECTION DETAIL SEE SH. Nº 238

1'-0"
1" T-35 ASP. CONC. SURFACE COURSE TYPE "C"
2" T-35 ASP. CONC. SURFACE COURSE TYPE "A"
3"
T-71 PAV'T
EXIST. PAV'T.
I-22 SUBBASE

JOINT "F"

℄-CURVE DATA
Δ = 46° 36' 35"
Dc = 25°
R = 229.18'
T = 98.72'
Lc = 186.44

TYPE 2A CURB

P.C. STA. 16+55.28 BEGIN CURB

P.C. STA. 16+40.21 ℄-RAMP "D" BEGIN CURB

3' PAVED SHOULDER

RAMP "D"

E-8 REMOVAL & DISPOSAL OF EXISTING			
CODE	CURB & GUTTER	SIDEWALK	NON-RIGID PAVEMENT
R-1	225 L.F. ✓		
R-2		76 S.F. ✓	
R-3			356 S.Y. ✓

SCALE: 1" = 20'

INTERSECTION DETAILS

E-8 REMOVAL & DISPOSAL OF EXISTING				
CODE	RIGID PVT S.Y.	SIDEWALK S.F.	HEADER CURB L.F.	WEARING COURSE S.Y.
R-1	645			
R-2		1364		
R-3			418	
R-4		1156		
R-5			297	
R-6				404

I-12 CONCRETE CURB		
CODE	TYPE 2A L.F.	TYPE 6 L.F.
C-1	305	
C-2		257
C-3	100	
C-4		120
C-5		297
C-6		314
C-7		312
C-8		102

I-13 5" CONCRETE SIDEWALK	
CODE	SQ. FT.
S-1	864
S-2	136
S-3	1156

FED. RD.	STATE	PROJECT	
2	OHIO		

71
452

MAH-18-17.20

MAHONING AVE. STA. 6+92.92
McKINLEY AVE. STA. 0+00
MAHONING AVE. NOSE STA. 8+02.56
℄-MAHONING AVE.
83° 50' 00"
MEET EXIST. CURB
MEET EXIST. PAV'T.
McKINLEY AVE. 0+40.62
RAMP "E" 1+42.07
MEET EXIST. CURB
1.5' R.
4'
PAVED SHOULDERS
STA. 3+45.54 END CURB
MAHONING AVE. STA. 15+55.87
RAMP "E" STA. 0+00
P.T. STA. 0+20.32
S.W. CURB RETURN
Δ = 78°00'41"
R = 25'
T = 20.25'
Lc = 34.04
Δ = 5°49'19"
R = 200'
T = 10.17'
Lc = 20.32'
P.C. 1+08.33
P.T. 0+58.07
P.C. 0+74.14
P.T. 1+85.71
S.E. CURB RETURN
Δ = 101°59'19"
R = 25'
T = 30.87'
Lc = 44.50'
℄-McKINLEY AVE.
RAMP "E" NOSE STA. 2+45.54
TYPE 2A CURB & GUTTER
MEET EXIST. PAV'T. 1+25
MEET EXIST. CURB
S-1
C-1
C-3
C-8
C-7
C-6
C-4
RAMP "E"
NOTE:
DO NOT CONSTRUCT THIS CURB UNTIL THE MAHONING AVE. BRIDGE STRUCTURE № MAH-18-1815 IS COMPLETE & OPEN TO TRAFFIC. SEE MAINTENANCE OF TRAFFIC SHEET № 15
MARSHALL ST. STA. 4+94.74 22.5' RT.
MARSHALL ST. STA. 7+27.13
EXIST. ℄- MARSHALL
3+94.74
100' TAPER
10'
3+00
℄-RAMP "E"
TYPE 2A CURB
TYPE 6 CURB
PAVED SHOULDER
STA. 3+37.30 END CURB
RAMP "G" 2+57.36 ON ℄ MARSHALL ST.
PT 2+46.02
PC. 3+13.72 SWITCH P.G.
RAMP "G"
BEGIN RAMP "G" PC STA. 0+08.11
87.6.07

℄-EXIST EDWARDS
℄-PROP. EDWARDS
MEET EDWARDS ST. SEE SH. № (STREET IMPROVEMENT PROGRAM)
FACE OF CURB 20' RT. OF ℄ RELOC EDWARDS PT. STA. 0+57.15
Δ = 79°47'56"
R = 50'
T = 41.81'
Lc = 69.64'
6" T-22 SUBBASE
10" D-10 PCC BASE COURSE
1" T-35 ASPH. CONC. SURFACE COURSE TYPE "A"
1" T-35 ASPH. CONC. SURFACE COURSE TYPE "C"
T-30 TACK COAT
NOTE: ALL ELEVATIONS ARE ON GUTTER LINE.
NOSE STA. 4' LT. - RELOC. HIGH STA. 12+38.38
EXTENSION OF RAMP "H" INT. AT STA. 13+16.46
SEE SKETCH "A" FOR ENLARGED VIEW OF THIS AREA
MEET EXISTING PAVEMENT
℄-HIGH ST.
END T-71 SPR.U. PAVEMENT
℄-RAMPS "F" & "H"
TYPE 6 CURB
EXIST. HIGH
PROP 4' SIDEWALK
TYPE 6 CURB
REMOVE EXISTING SIDEWALK
REMOVE EXISTING CURB
REMOVE EXIST. PAVEMENT
R-1
R-2
R-3
R-4
R-5
S-2
S-3
C-2
C-5
C-6
C-7
C-4
MEET EXIST. EDWARDS -BEGIN WORK 29.15' SO. OF ℄-PROP. HIGH ST. ON A RADIAL LINE WITH P.T. OF CURB RETURN.
CURB RETURN DATA
Δ = 90°18'30"
R = 15'
T = 15.08'
Lc = 23.64'
P.C. 14+21 RT. OF STA. 11+85.93
REMOVE EXISTING WEARING SURFACE (R-6)
RESURFACE WITH
1" T-35 ASPH. CONC. SURFACE COURSE TYPE "A"
2" T-35 ASPH. CONC. SURFACE COURSE TYPE "A"
D-35 ASPH. CONC. LEVELING COURSE
BEGIN TAPER OF PAV'T. & SIDEWALK STA. 12+50 RT.
END ℄-SIDEWALK ONLY 17' RT. - STA. 13+14.53
END ℄-SIDEWALK TAPER 13+14.53
END PAV'T TAPER 11' RT. - STA. 14+50
NOSE - 7' RT. STA. 2+46.07 (RAMP "H") 14+18.16 (RELOC. HIGH)
END WORK STA. 14+51.16 MEET HIGH ST. (ST. IMPR. PROGRAM)
RAMPS "F" & "H"
SPIRAL DATA
Ls = 200'
Θs = 33°
L.T. = 135.73'
S.T. = 68.85'
Lc = 197.07'
S.T. STA. 11+82.37 (RAMP "F")
T.S. STA. 12+46.88 (RAMP "H")
C.S. STA. 12+87.97
TRANSITIONAL SPIRAL DATA
Θs = 13°28'23"
Ls = 200'
Dc = 13°28'23"
Rc = 425.26'
L.T. = 202.64'
T.S. = 133.72'
S.T. = 167.02'
Lc = 199.51'
D = 3.91'
X = 99.82'
Y = 15.59'
END CURB 3' RT. OF RAMP ℄ STA. 3+34.48
13.75' TAPER
END CURB 2' LT. OF RAMP "F" STA. 13+50
3' PAVED SHOULDER
SKETCH "A"
ENLARGED DETAILS OF INTERSECTION AT HIGH, EDWARDS & ℄ OF RAMPS "F" & "H" ~ NO SCALE
℄-IMPROVED HIGH ST.
℄-OLD HIGH ST.
BEGIN RAMP "H" 0+00 END RAMP "F" 17+32.82 (RAMP "F")
109°09'
STA. 11+57.86
℄-RAMPS "F" & "H"
8°56'56"
℄-EXIST. HIGH ST.
℄-PROP. HIGH ST.
0.07
88°41'30"
STA. 11+57.27
STA. 11+55.72
STA. 11+55.74
STA. 11+57.31
℄-EXIST. EDWARDS
℄-PROP. EDWARDS


NOTE: FOR LEGEND SEE SHEET 70
SCALE: 1" = 20'

INTERSECTION DETAILS


FED. RD.	STATE	PROJECT	
2	OHIO		

72
492

MAH - 18 - 17.20




RAMP "J"




RAMP "K"

℄ - CURVE DATA
Δ = 55° 04' 30"
R = 100'
T = 52.14'
L_c = 96.14'

CURB RETURN CURVE DATA
Δ = 94° 56' 25"
R = 30'
T = 32.70
L_c = 49.71



RAMP "L"




RAMP "M"

NOTE: FOR LEGEND SEE SHEET 70
SCALE: 1" = 20'


INTERSECTION DETAILS

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20



RAMP "N"



INTERSECTION ~ RELOC. PIKE & OAK HILL

NOTE: FOR LEGEND SEE SHEET 70
SCALE: 1" = 20'

INTERSECTION DETAILS

FED.RD	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

74
282

I-4 PIPE UNDERDRAINS LIN. FT.						
CODE	LOCATION		DEEP OR SHALLOW	6" PIPE	8" OUTLET PIPE M-6.4 a	I-5 PIPE SPEC. EACH 6"x90°
	FROM	TO				
U-1	6+00	9+70	D	392	10	1
SHEET TOTAL				392	10	1

BEGIN RAMP "A" 32' LT. OF STA. 7+01.71

FUTURE BRIDGE

NOSE - 14' LT. OF STA. 11+70.58 (RAMP D)

NOSE - 31' RT. OF STA. 4+46.87 (W. FEDERAL)

CURVE DATA
Δ: 75°22'06"
Δc: 31°22'06"
Dc: 12°
R: 760.44'
T: 73.13'
Lc: 142.58'
Ts: 305.60'
Ls: 200'

S.C. 3+00 - 47.68 LT. 4+01.95

NOSE - 23' LT. OF STA. 3+57.88

100 DAY'S TRANSITION

FIELD TIE WITH DT #2

NOSE - 42' LT. OF STA. 3+40.14

S.C. 9+86

Δ: 42°29'47"
Dc: 2°
R: 572.08'
T: 221.93'
L: 424.19'
Lc: 414.73'
Rc: 554.93'

STA. 14+00 (69' RT. ℄ RAMP "D")
P.C. 4 ENDWALL
℄ INV. 42'S-27-833.74

STA. 14+00 (72' LT. ℄)
I-8 NS. 2-4 (RAMP "D")
WINDOW EL. 843.50
℄ 42'S-27-837.31

SALT SPRINGS TRAVERSE LINE

SPIRAL DATA
Ls: 200'
θs: 2°
T: 100'
L: 200'
S.T.: 6.97'

SPIRAL DATA
Xs: 199.97'
Ys: 2.33'
K: 99.98'
P: 0.58'

TS. 7+86

ST. 10+72.88

RAMP "D"

CURVE DATA
Δ: 6°19'17"
Dc: 2°
R: 572.08'
T: 31.62'
L: 63.16'
Lc: 63.13'

CS. 9+72.88

NOTE:
FOR COMPLETE INFORMATION ON RAMP "D", SEE PLAN & PROFILE SHEET Nº 52 & 53

STA. 6+00
℄ 885.31
6"x90° BEND

BEGIN WEST FEDERAL EXPRESSWAY 0+00
END RAMP "A" STA. 14+43.71

℄ MAHONING-WEST FEDERAL EXPRESSWAY

STA. 945+73 (136' LT. ℄)
I-8 NS. 2-4 C.B.
WINDOW ELEV. 855.50
℄ 42'S-27-844.30

CS. 9+44.76

NOSE - 44' RT. OF STA. 7+76.93

CS. 9+41.76

STA. 945+25
I-8 NS. 2-10 INLET
WINDOW EL. 857.17
℄ 12' I-2 872.76

FUTURE STRUCTURE

CS. 7+01.76

SPIRAL DATA
θs: 9°
Ls: 300'
Lc: 100.24'
S.T.: 100.24'
Xs: 299.76'
Ys: 15.68'
K: 149.88'
P: 3.92'

FUTURE PAVED SHOULDER

RAMP "A"

BASE LINE ℄ P.G.

24' OFFSET BASELINE

RAMP "C"

RAMP "C" SPIRAL DATA
Ls: 754.75'
Δ1+Δ2: 50°31'13"
θs: 32°43'22"
T1: 104.15'
T2: 107.92'
Δ1: 8°53'56"
Δ2: 41°37'17"
P: 11.96'

ST. 4+16

NOSE - 23.06' LT. 4+08.93

11' SHOULDER

7' SHOULDER

15' SHOULDER

SC. 7+16.88

ST. 7+96.97

44' LT. 7+00

10' SURFACED SHOULDER

℄ YOUNGSTOWN EXP'WY

NOSE - 14' LT. STA. 9+45.00

ST. 10+72.88

100'

ST. 13+52.63

STA. 944+87 (114' RT. ℄)
PC-4 ENDWALL
℄ INV. 851.25

STA. 945+00
106' RT. ℄
PC-4 ENDWALL
℄ INV. 42'S-27 851.00

NOSE - 75' LT. OF STA. 4+00.43

SC. 5+25.40

ST. 9+51.41.76

NOSE - 44' LT. 9+50+86.26

RAMP "C" CURVE DATA
Δ: 70°4' 07'55"
R: 175'
Lc: 672.73'
Dc: 32°44' 26"
T: 821.58'

SC. 13+93.11

NOTE:
FOR COMPLETE INFORMATION ON RAMP "C", SEE PLAN & PROFILE SHEET Nº 50 & 51

NOTE:
PROPOSED I-2 PIPES S-27 CULVERTS AND I-8 C.B. SHOWN ON THIS SHEET ARE TO BE CONSTRUCTED UNDER THIS CONTRACT.

~LEGEND~

- NEW & FUTURE PAV'MT EDGE
- PROPOSED MAINLINE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAV'MT & CURB
- EXIST. SIDEWALK
- EDGE OF PAVED BERM
- PROPOSED CURB
- FUTURE PAVEMENT GRADING PERFORMED WITH THIS PROJECT SEE CROSS SECTIONS

SCALE: 1" = 50'

END RAMP "A" @ STA. 933+37.00 (EXP'WY)
2'-0" D.I. (RAMP "C")

BEGIN RAMP "A" 933+37.00 TAPER

933+32.11 (EXP'WY)
2'-0" D.I. (RAMP "C")

NOSE - 39' LT. OF STA. 9+40+75.66

FUTURE PAVED SHOULDER

T.S. 933+46.56

STA. 7+41 RAMP "C"
(65' LT. ℄)
I-8 NS. 2-2A C.B. MOD.
WINDOW EL. 875.30 (3 REQ)
℄ 15' I-2 872.86

STA. 5+57.50 RAMP "C"
(65' RT. ℄)
P.C. 4 MODIFIED ENDWALL
℄ INV. 18'S-27-875.50

STA. 10+50 RAMP "C"
(44' RT. ℄)
P.C. 4 ENDWALL
℄ INV. 24'S-27-867.70

STA. 10+50 RAMP "C"
108' LT. ℄
P.C. 4 HEADWALL
℄ 24" I-2 862.00

STA. 10+35 RAMP "C"
(76' RT. ℄)
P.C. 4 HEADWALL
℄ INV. 18" I-2 858.50

3' BOTTOM CHANNEL 2:1 SLOPES FOR LAYOUT SEE SHT. Nº FOR CROSS SEC. SEE SHT. Nº

NOTE:
THE PROFILE GRADE FOR RAMPS "C" & "D" IS CARRIED ALONG THE BASE LINE OF RAMP "C"

T.S. 8+57.54


S.C. 8+57.54

T.S. 12+57.94


GEOMETRIC PLAN OF FUTURE CONSTRUCTION

FED. RD.	STATE	PROJECT	
2	OHIO		


MAH-18-17.20



RAMP A_3



RAMP B_3




RAMP C_3 & RAMP D_3

PROFILES~RAMPS A_3, B_3, C_3 & D_3


FED. RD.	STATE	PROJECT	
2	OHIO		

76
452

MAH-18-17.20



PROPOSED MAHONING - WEST FEDERAL EXPRESSWAY
(PROFILE)
STA. 0+00 TO STA. 6+00



A-1
MAH. W. FED. STA. 4+50 145' LT.
I-8 Nº 2-2A C.B.
WINDOW EL. 850.87
Æ 12" I-2 848.70

A-2
RAMP "D" STA. 18+50 33' LT.
I-8 Nº 2-2A C.B.
WINDOW EL. 839.92
Æ 12" I-2 837.75

EROSION CONTROL		
CODE	I-14 PAVED GUTTER TYPE-I (L.F.)	I-14 PAVED GUTTER TYPE-I MOD. (L.F.)
E-1	350	
E-2	100	
E-3		10
E-5		10

I-2 12" STORM SEWER M-6.5(a) M-6.8(a)	LIN. FT.
P-1	18
P-2	45

I-8 Nº 2-2A CATCH BASINS - EACH	
A-1	1
A-2	1

DRAINAGE PLAN — RAMPS "A3", "B3", & "D"

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

77
492

STA. 345+78 (136' LT. ℄)
I-8 NB. 2-4 C.B.
WINDOW ELEV. 855.50
℄ 42° 5'-27' 844.30

STA. 345+25
I-8 NB. 2-ID INLET
WINDOW EL. 870.17
℄ 12° 42'-57' 866

STA. 344+76
106' RT ℄
PC-4 ENDWALL
℄ INV. 42° 5'-27' 851.00

END RAMP C_3 / D_3 EMBANKMENT
RAMP C_3 STA 13+41
SKEW ANGLE = 21° 33' 23"

3' BOTTOM CHANNEL FOR
LAYOUT DETAIL SEE SHT. 114
FOR CROSS-SECTIONS
SEE SHEET 115

GRADE TO DRAIN

EL. 890.00

890.00

STA. T+41 RAMP 'C'
(63' LT. ℄)
I-8 NB. 2-2A C.B.
WINDOW EL. 875.30
℄ 15° I-2 872.86

STA. 10+95 LOOP 'C'
(TC. ℄)
PC-4 HEADWALL
℄ INV. 18° I-2 866.80

STA. 10+50 RAMP 'C'
(108' LT. ℄)
PC-4 HEADWALL
℄ 24° I-2 862.00

STA. 5+57.50 RAMP 'C'
(63' RT. ℄)
P.C. 4 MODIFIED HEADWALL
℄ INV. 18° I-2 875.50

STA. 10+50 RAMP 'C'
(44' RT. ℄)
P.C. 4 HEADWALL
℄ INV. 24° I-2 867.70

RAMP 'C'

RAMP 'D3'


RAMP 'C3'

DRAINAGE PLAN · RAMPS "C" "C_3" & "D_3"

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH - 18 - 17.20

78
492



GRADING PLAN - RAMPS "H" & "F"

FED.RD.	STATE	PROJECT	
2	OHIO		

79
492

A-3
STA. 926+25
(54.75' RT. ℄)
I-8 Nº 2-2A C.B.
WINDOW EL. 927.57
FE 12" I-2 925.40
FE 8" I-4 925.73

A-2
STA. 926+50
I-8 Nº 1 M.H. (9.5' RT. ℄)
COVER 927.33
FE 12" I-2 916.45
FE 15" I-2 916.20
FE 27" I-2 915.20

A-4
STA. 926+00
51' LT. ℄
I-8 Nº 1 M.H.
COVER = 925.44
FE 12" I-2 917.32
FE 15" I-2 917.07
FE 12" I-2 920.88

℄ Y.E.

55' 12" I-2 @.1672 P-3

79' - 15" I-2 @.0112½ P-4

52'-12" I-2 @.01½ P-7

A-10
STA. 8+19.54 RAMP "B"
19' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 920.01
FE 12" I-2 917.84
FE 8" I-4 918.17

A-4
STA. 926+00
I-8 Nº 1 M.H.
51' LT. ℄
COVER 925.44
FE 12" I-2 920.88
FE 12" I-2 917.32
FE 15" I-2 917.07

101' 12" I-2 @.0490 P-5

A-6
STA. 925+00
67' LT. ℄
I-8 Nº 2 2A C.B.
WINDOW EL. 924.24
FE 12" I-2 922.07

A-9
STA. 929+50
49.2' LT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 917.26
FE 12" I-2 915.09
FE 8" I-4 915.42

A-7
STA. 929+65
I-8 Nº 1 M.H.
6' RT. ℄
COVER 918.22
FE 12" I-2 912.30
FE 12" I-2 914.46
FE 27" I-2 911.05

℄ Y.E.

58' 12" I-2 @.0481 P-9

A-7 MAH-18-17.20
STA. 929+65
6' RT. ℄
I-8 Nº 1 M.H.
COVER 918.22
FE 12" I-2 912.30
FE 12" I-2 914.46
FE 27" I-2 911.05

A-8
STA. 929+58
1.25' RT. ℄
I-8 Nº 2A-10 INLET
WINDOW EL. 917.46
FE 12" I-2 914.55

3' 12" I-2 @.0100 P-8

A-14
STA. 933+00
66' LT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 905.91
FE 12" I-2 903.74
FE 8" I-4 904.07

A-12
STA. 933+06
6' RT. ℄
I-8 Nº 1 M.H.
COVER 908.47
FE 12" I-2 904.69
FE 12" I-2 898.66
FE 33" I-2 896.91

A-13
STA. 933+00
66' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 905.91
FE 12" I-2 903.74
FE 8" I-4 904.07

℄ Y.E.

72' 12" I-2 @.0668 P-12

60' 12" I-2 @.0802 P-13

A-12
STA. 933+06
6' RT. ℄
I-8 Nº 1 M.H.
COVER 908.47
FE 12" I-2 904.69
FE 12" I-2 898.66
FE 33" I-2 896.91

8' 12" I-2 @.0100 P-14

A-15
STA. 933+00
1.25' RT. ℄
I-8 Nº 2A-6 INLET
WINDOW EL. 908.35
FE 12" I-2 904.77
FE 8" I-4 905.10

A-16
STA. 936+19 (℄)
I-8 Nº 2-8 MODIFIED INLET
WINDOW EL. (LT. ℄ P.T.) 899.23
FE 12" I-2 895.65

℄ RAMP "B"

5' 12" I-2 @ 0.5475 P-18

STA. 936+22
33" x 12" WYE
FE 33" I-5 890.63

A-18
STA. 937+20
57' LT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 894.54
FE 12" I-2 892.37

A-17
STA. 937+20
6' RT. ℄
I-8 Nº 1 M.H.
COVER 896.49
FE 12" I-2 890.34
FE 33" I-2 888.68

℄ Y.E.

63' 12" I-2 @.0322 P-16

A-21
STA. 945+67
136' LT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL. 851.45
FE 12" I-2 848.78

A-20
STA. 945+73
136' LT. ℄
I-8 Nº 1 M.H.
COVER 852.78
FE 42" I-2 844.41
FE 12" I-2 848.42

6' 12" I-2 @.0600 P-24

A-4 A-5
STA 926+26.90
44.73 LT. ℄
I-8 Nº 2A
TOP OF CURB - 925.24
WINDOW EL- 924.57
FE 12" = 921.16

28'-12" I-2 @.01 P-6

H-1
STA. 945+00
102' RT. ℄
P.C. 4 ENDWALL
FE INV. 42" S-27
851.00

℄ Y.E

H-2
STA. 14+00
63' RT. ℄ RAMP "D"
P.C. 4 ENDWALL
FE INV. 42" S-27 833.75

A-23
STA. 14+00
72' LT. ℄ RAMP "D"
I-8 Nº 2-4 C.B.
WINDOW EL. 843.50
FE 42" S-27 837.31

A-20
STA. 945+73
136' LT. ℄
I-8 Nº 2-4 C.B.
WINDOW ELEV. 855.60
FE 42" S-27 844.30

℄ RAMP "D" STA. 14+00

℄ ACCESS RD.

135' 42" S-27 M-G.G(b) OR M-G.4(d) GAGE-12 @.0264 C-22

261 42" S-27 M-G.4(d) GAGE 8 @.0264 C-21

252' 42" S-27 M-G.4(d) GAGE-10 OR M-G.6(d) @.0264 C-20


STORM SEWER PROFILES


FED. RD.	STATE	PROJECT	
2	OHIO		


80
492


MAH-18-17.20


A-41









































STORM SEWER PROFILES

FED. RD.	STATE	PROJECT	
2	OHIO		

81
492

MAH-18-17.20

A-52
STA. 985+60
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 902.52
℄ 12" I-2 896.60
℄ 12" I-2 898.76

A-53
STA. 985+60 ℄
I-8 № 2-8 MODIFIED INLET
WINDOW EL. 902.23
℄ 12" I-2 898.82

6' 12"I-2 @.0100 P-52

A-54
STA. 989+00
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 893.06
℄ 12" I-2 886.23
℄ 15" I-2 885.98

℄ Y.E.

60' 12"I-2 @.0500
P-54

A-55
STA. 989+00
54' RT. ℄
I-8 № 2-2A C.B.
WINDOW EL. 888.70
℄ 12" I-2 886.53

A-57
STA. 994+60
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 875.86
℄ 12" I-2 872.21
℄ 15" I-2 865.70
℄ 21" I-2 865.20
℄ 24" I-2 864.95

℄ Y.E.

61' 21"I-2 @.0200
P-58

A-58
STA. 994+50
54' RT. ℄
I-8 № 2-2A C.B.
WINDOW EL. 870.91
℄ 18" I-2 866.67
℄ 21" I-2 866.42

℄ RAMP "H"

47' 18"I-2 @.0200
P-59

A-59
RAMP "H" STA. 13+80
19' RT. ℄
I-8 № 2-2A C.B.
WINDOW EL. 870.32
℄ 18" I-2 867.61

A-57
STA. 944+60
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 875.86
℄ 12" I-2 872.21
℄ 15" I-2 865.70
℄ 21" I-2 865.20
℄ 24" I-2 864.95

℄ Y.E.

12' 12"I-2 @.0150 P-57

A-56
STA. 994+50
1.25' LT. ℄
I-8 № 2A-10 INLET
WINDOW EL. 875.20
℄ 12" I-2 972.39

A-60
STA. 997+00.41
46' LT. ℄
I-8 № 6 C.B.
GRATE EL. 870.42
℄ 12" I-2 867.67

A-61
STA. 997+10
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 868.16
℄ 12" I-2 863.07
℄ 12" I-2 866.83
℄ 24" I-2 859.95

A-62
STA. 996+86.03
38' RT. ℄
I-8 № 6 C.B.
GRATE EL. 866.38
℄ 12" I-2 863.58

℄ Y.E.

42' 12"I-2 @.0200 P-61

51' 12"I-2 @.0100 P-62

A-63
STA. 999+50
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 862.88
℄ 12" I-2 859.02
℄ 24" I-2 855.15

℄ Y.E.

5' 12"I-2 @.0150 P-65

A-64
STA. 999+50
1.25' LT. ℄
I-8 № 2A-10 INLET
WINDOW EL. 862.51
℄ 12" I-2 859.10

A-65
STA. 1000+41.48
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 862.45
℄ 12" I-2 854.78
℄ 12" I-2 858.60
℄ 27" I-2 853.53
℄ 8" I-4 858.62

℄ Y.E.

5' 12"I-2 @.0150 P-67

A-66
STA. 1000+41.48
1.25' LT. ℄
I-8 № 2A-6 INLET
WINDOW EL. 862.08
℄ 12" I-2 858.67

A-67
STA. 1001+50
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 863.06
℄ 12" I-2 857.14
℄ 12" I-2 859.21

℄ Y.E.

5' 12"I-2 @.0150 P-68

A-68
STA. 1001+50
1.25' LT. ℄
I-8 № 2A-6 INLET
WINDOW EL. 862.69
℄ 12" I-2 859.28

A-78
STA. 1007+10
1.25' LT. ℄
I-8 2A-8
TOP OF CURB 879.34
WINDOW EL. 878.67
℄ 12" I-2 874.26

2'-6" 6" 30° BEND 45' 12"I-2 @.01

CLASS "C" CONCRETE COLLAR TO BE INCLUDED WITH PRICE BID OF I-2 STORM SEWER

2'-6" MIN.

60' 12"I-2 M.G.4c P-83

A-73
STA. 1003+50
115.5' LT. ℄
I-8 № 2-2A C.B.
WINDOW EL. 840.17
℄ 12 I-2 838.00

A-72
STA. 1003+50
81.5' RT. ℄
I-8 № 2-2A C.B.
WINDOW EL. 848.20
℄ 18" I-2 845.49

℄ Y.E.

182' 18" I-2
M-6.6(d) @ 4.48%
P-77

16' 12"I-2 @.01 P-76

A-71
℄ RELOCATED PIKE

35' 12"I-2 @.01
I-5 PIPE SPEC. 30° BEND
℄ 845.00

A-65
STA. 1000+41.48
6' LT. ℄
I-8 № 1 M.H.
COVER EL. 862.45
℄ 12" I-2 854.78
℄ 12" I-2 858.60
℄ 27" I-2 853.53
℄ 8 I-4 858.62

140' 27"I-2 M-6.6c @.1133 P-69

A-69
STA. 1001+50
88' LT. ℄
I-8 № 1 M.H.
COVER EL. 849.00
℄ 27" I-2 837.67
℄ 33" I-2 837.17

209' 33" I-2 M-6.6b or M-6.8b @.00517 P-70

A-72
STA. 1003+50
100' LT. ℄
I-8 № 1 M.H.
COVER EL. 848.00
℄ 33" I-2 836.09
℄ 12" I-2 837.84
℄ 18" I-2 837.34
℄ 36" I-2 835.84

226' 36" I-2 M-6.6b or M-6.8b @.00514 P-71


A-70
STA. 0+05 PIKE ST. ℄
I-8 № 1 M.H.
COVER EL. 848.91
℄ 12" I-2 844.16
℄ 36" I-2 834.68

P-72

STORM SEWER PROFILES

FED. RD.	STATE	PROJECT		82 492
3	OHIO			

MAH-18-17.20




A-33
STA. 8+00 RAMP 'E'
19' RT. ℄
I-8 Nº 2-2A C.B.
WINDOW EL.- 882.93
℄ 12" I-2 -880.26

A-34
STA 8+00 RAMP 'E'
19' LT. ℄
I-8 Nº 6 C.B.
GRATE EL. 886.32
℄ 12" I-2 879.26


SCALE: HORZ. 1" = 20'
VERT. 1" = 5'

H-12 PC-4 ENDWALL
STA. 960+30 68' LT. ℄
F.L. 12" I-2 = 876.00




NOTE:
I-5 PIPE SPECIALS ℄ I-2 8" PIPE ARE TO BE PLACED AS REQUIRED TO DRAIN S-29 SCUPPERS.

SCUPPER DRAIN DETAIL
STA. 1015+88 TO STA. 1019+23 (LT. ℄)




A-53
STA. 985+60 ℄
I-8 Nº 2-8 MOD. INLET
WINDOW EL.- 902.23
℄ 12" I-2 -898.82
℄ 4" I-4 -899.49



H-G
PC-4 ENDWALL
STA. 945+25
(66' LT. OF ℄)
℄ 12" I-2 = 869.22

A-22
STA. 945+25 (1.5' RT ℄)
I-8 Nº 2A-10 INLET
WINDOW ELEV. = 876.17
℄ 12" I-2 = 872.76



A-20
STA. 941+25 ℄
6' RT ℄
I-8 Nº 1 MANHOLE
COVER ELEV. 885.00
℄ 33" I-2 = 878.42

H-7
STA. 944+87
114' RT. ℄
PC-4 ENDWALL
ELEV. 851.25


FED. RD.	STATE	PROJECT	
2	OHIO		

83
492

MAH-18-17.20

A-6-"K"

STA. 15+75 (6.0' RT. ℄ "K")
I-8 № 1 MANHOLE
COVER EL. 950.00
℄ 12" I-2 944.10



RAMP "K"
PROPOSED STORM SEWER

B-6


STA. 48+74 MARKET ST.
I-8 № 2 MANHOLE ℄
COVER EL. 954.40
℄ 48" PROP I-2 928.50
℄ 48" EXIST. BR. 939.94
℄ 12" I-2 942.46

A-93

STA. 102+00
I-8 № 1 MANHOLE
(6.0' RT. ℄)
COVER EL. 924.44
℄ 12" I-2 917.20
℄ 15" I-2 916.95

A-94

STA. 1021+15
I-8 № 2A-12 INLET
(1.25' RT. ℄)
WINDOW EL. 924.64
℄ 12" I-2 921.23



A-93

STA. 1021+00
I-8 № 1 MANHOLE
(6.0' RT. ℄)
COVER EL. 924.44
℄ 12" I-2 917.20
℄ 15" I-2 916.95


A-5-"L"

STA. 7+02.5 RAMP "L"
I-8 № 1 MANHOLE
(21.0' LT. ℄)
COVER EL. 924.17
℄ 12" I-2 918.25
℄ 15" I-2 918.00

A-1

STA. 11+80 RAMP "K"
(15.25' RT. ℄)
I-8 № 2-2A C.B.
WINDOW EL. 958.50
℄ 12" I-2 956.33

WILLIAMS ST.
STA. 9+02.5
PROP. MANHOLE (DROP)
COVER EL. 960.80
℄ 12" I-2 952.77
℄ 15" I-2 952.52
℄ 21" I-2 931.14




RAMP "K"
PROPOSED STORM SEWER

A-95

STA. 1022+50
I-8 № 1 MANHOLE
(21.0' LT. ℄)
COVER EL. 927.77
℄ 12" I-2 921.85

A-98

STA. 1023+00
I-8 № 2-2A C.B.
(57.0' LT. ℄)
WINDOW EL. 926.17
℄ 12" I-2 924.00




A-7

STA. 8+02 RAMP "K"
(21.0' LT. ℄)
I-8 № 2A-8 INLET
TOP OF CURB 927.91
WINDOW EL. 927.34
℄ 12" I-2 922.80
℄ 15" I-2 922.55

A-93

STA. 102+00
(6.0' RT. ℄)
COVER EL. 924.44
℄ 15" I-2 916.95
℄ 12" I-2 917.20




A-97

STA. 1023+00
I-8 № 2A-8 INLET
(42.0' RT. ℄)
TOP OF CURB 931.90
WINDOW EL. 931.23
℄ 12" I-2 927.82

A-7-"K"


STA. 8+02.5 RAMP "K"
(21.0' LT. ℄)
I-8 № 2A-8 INLET
WINDOW EL. 927.34
℄ 12" I-2 922.80
℄ 15" I-2 922.55



A-96

STA. 1021+90
I-8 № 2-2A C.B.
(88.0' RT. ℄)
WINDOW EL. 925.94
℄ 15" I-2 923.50

RAMP "K"
PROPOSED STORM SEWER



A-85

STA. 1010+50
I-8 № 1 MANHOLE
(6.0' RT. ℄)
COVER EL. 889.89
℄ 12" I-2 886.11
℄ 18" I-2 883.43


B-1

STA. 4+40 (7.0' LT. ℄)
RELOC. PIKE ST.
I-8 M.H. Y-B
COVER EL. 859.11
℄ 18" I-2 833.58
℄ 36" I-2 832.44
℄ 54" I-2 830.77
℄ 5'-8" BR. (EXIST.) 829.6

EXIST. 5'-8"
BRICK SEWER

SCALE : 1" = 20' HORIZ.
1" = 5' VERT.
(UNLESS NOTED OTHERWISE)

A-88



A-87

STA. 1015+50
I-8 № 2-2A C.B.
(63.0' RT. ℄)
GRATE EL. 902.45
℄ 12" I-2 900.28
℄ 18" I-2 899.78

A-86


STA. 1015+50
I-8 № 1 MANHOLE
(6.0' RT. ℄)
COVER EL. 906.29
℄ 18" I-2 898.78

A-88

STA. 1015+50
I-8 № 2-2A C.B.
(132.0' RT. ℄)
GRATE EL. 930.25
℄ 12" I-2 928.08

A-89

STA. 1015+88.5
I-8 № 2A-10 INLET
(1.25' LT. ℄)
WINDOW EL. 907.45
℄ 12" I-2 904.04



STA. 1015+85
I-5 PIPE SPEC.
12"x 15" WYE
℄ 901.83


SCALE : 1" = 5' HORIZ.
1" = 5' VERT.

A-91

STA. 1019+25 - ℄
I-8 № 2-8 INLET (MODIFIED)
WINDOW EL. 918.45
℄ 12" I-2 915.04


A-92

STA. 1019+90.5
I-8 № 2-2A C.B.
(21.0' LT. ℄)
GRATE EL. 919.31
℄ 12" I-2 917.14



A-90

STA. 1017+25
I-8 № 6 C.B.
(4.5' RT. ℄)
GRATE EL. 912.03
℄ 12" I-2 908.36



STA. 1017+25
I-5 PIPE SPEC.
12"x 15" TEE
℄ 905.00±

SCALE : 1" = 5' HORIZ.
1" = 5' VERT.

RAMP - STORM SEWER PROFILES

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS	I-16 MANHOLES ABANDONED EA.	I-16 CATCH BASINS ABANDONED EA.
EXISTING STRUCTURES "A"						
A-1	N.W. CURB ON SILLIMAN @ LAKEVIEW	CATCH BASIN		ABANDON		1
A-2	S.W. CURB ON SILLIMAN @ LAKEVIEW	CATCH BASIN		ABANDON		1
A-3	℄ SILLIMAN, 26'E. ℄ LAKEVIEW	MANHOLE	INV. 944.21	ABANDON -	1	
A-4	℄ SILLIMAN, 346'E. ℄ LAKEVIEW	MANHOLE	INV. 935.07	ABANDON -	1	
A-5	℄ LAKEVIEW, 40'S. ℄ SILLIMAN	MANHOLE	INV. 951.12	ABANDON -	1	
A-6	℄ OAKWOOD, 43'E. ℄ LAKEVIEW	MANHOLE	INV. 949.55	UNDISTURBED - ABANDON 12" LAKEVIEW INLET		
A-7	21'W. ℄ STEEL, 178'N. ℄ OAKWOOD	MANHOLE	INV. 936.55	ABANDON -	1	
A-8	20'E. ℄ STEEL, 215'N. ℄ OAKWOOD	MANHOLE	INV. 936.6	ABANDON -	1	
A-9	18'W. ℄ STEEL, 269'N. ℄ OAKWOOD	CATCH BASIN		ABANDON -		1
A-10	℄ SILLIMAN, 153'W. ℄ LAKEVIEW	MANHOLE	15" INV. 947.00	12" INV 947.25 NEW 15" OUTLET		
A-11	S.W. CURB ON SILLIMAN @ STEEL	CATCH BASIN		ABANDON -		1
PROPOSED STRUCTURES "B"					I-8 MANHOLES - YOUNGSTOWN TYPE Y-A EA.	
B-1	℄ OAKWOOD, 165'E. ℄ LAKEVIEW	MANHOLE Y-A	15" INV. 945.60	TOP EL. 952.3, ESTABLISH IN EXIST. 15" LINE	1	
B-2	11'N. ℄ OAKWOOD, 136'E. ℄ LAKEVIEW	MANHOLE Y-A	15" INV. 945.70	TOP EL. 953.3	1	
B-3	11'N. ℄ OAKWOOD, 41'E. ℄ LAKEVIEW	MANHOLE Y-A	15" INV. 945.90	TOP EL. 956.4	1	
B-4	3'W. ℄ LAKEVIEW, 775'S. ℄ SILLIMAN	MANHOLE Y-A	15" INV. 946.33	TOP EL. 954.7	1	
B-5	13'S. ℄ SILLIMAN, 92'W. ℄ LAKEVIEW	MANHOLE Y-A	15" INV. 946.55	TOP EL. 954.5	1	
B-6	7'N. ℄ SILLIMAN, 290'W. ℄ STEEL	MANHOLE Y-A	12" INV. 933.71	TOP EL. 942.2, ESTABLISH IN EXIST. 12" LINE	1	

DESCRIPTION OF WORK - COMBINED SEWERS.

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS "E"						
E-1	℄ SILLIMAN	A-10	A-3	12"	179'	SLOPE 1.69%, ABANDON
E-2	℄ SILLIMAN	A-3	A-4	12"	320'	SLOPE 2.81%, ABANDON
E-3	℄ SILLIMAN	A-4	B-6	12"	40'	SLOPE 3.39%, ABANDON
E-4	℄ LAKEVIEW	A-5	A-6	12"	286'	SLOPE 0.5%, ABANDON
E-6	℄ OAKWOOD	A-6	B-1	15"	122'	SLOPE 3.28%, HOUSE LINES FROM N. ABANDONED
E-7	21'W. ℄ STEEL	A-7	12+72	10"	12.5'	ABANDON
E-8	21'E. ℄ STEEL	A-8	B-7	10"	112.5'	ABANDON
PROPOSED SEWERS "F"						
F-1	OAKWOOD AVE.	B-1	B-2	15"	30'	SLOPE 0.2%, PLUG EXIST. HOUSE SEWERS FROM B-3 N. SIDE OAKWOOD TO E-6.
F-2	OAKWOOD AVE.	B-2	B-3	15"	95'	SLOPE 0.2%,
F-3	UNDER RAMP "A"	B-3	B-4	15"	215'	SLOPE 0.2%,
F-4	LAKEVIEW TO SILLIMAN	B-4	B-5	15"	110'	SLOPE 0.2%
F-5	SILLIMAN ST.	B-5	A-10	15"	62'	SLOPE 0.73%

I-2 COMBINATION SEWERS UNDER PAVT & APPROACHES 15" M-6.8 b L.F.

26
91
211
106
58

FED. RD.	STATE	PROJECT	
2	OHIO		

84 / 492

MAH-18-17.20


WATER REQUIREMENTS.


I-124 NEW WATER MAIN.

BID ITEM	DESCRIPTION	QUANT.
12" FITTINGS	90° BEND W/LUGS CL 250	2
	TEE CL 250	2
	SPECIAL BEND W/LUGS CL 250	4
	TOTAL	8
6" FITTINGS	90° BEND W/LUGS CL 250	2
6" VALVES & BOXES	CL 250	2
12" VALVES & BOXES	CL. 150	1
FIRE HYDRANTS		2
6" NEW WATER MAIN	CL. 22	20 L.F.
12" NEW WATER MAIN	CL. 23	104 L.F.
12" NEW WATER MAIN	CONC. ENCASED CL 23	240 L.F.
VALVE BOX	ADJUSTED TO GRADE	1


---6--- EXISTING GAS MAIN
——W—— EXISTING WATER MAIN
----HP---- HIGH PRESSURE GAS MAIN
⊖---S---⊖ EXISTING COMBINATION SEWERS
●—S—● PROPOSED SEWERS
——— EXISTING MAHONING VALLEY SANITARY DISTRICT WATER MAIN
——W—— PROPOSED WATER MAIN

NOTE: EXISTING OVERHEAD FACILITIES ARE NOT SHOWN WHERE THEY ARE TO BE REMOVED WITHIN THE RIGHT OF WAY LIMITS. TEMPORARY OVERHEAD FACILITIES TO BE MAINTAINED OVER THE CONSTRUCTION AREA AS INDICIATED. THESE TEMPORARY INSTALLATIONS ARE INDICATED THUSLY: ——o——o——. DETAILED UTILITY RELOCATION DRAWINGS ARE AVAILABLE AT THE UTILITY ENGINEERS OFFICE STATE HIGHWAY DEPT., DIVISION #4, RAVENNA, OHIO





RELOCATION 15" SILLIMAN ST. SEWER UNDER RAMP "A"



RELOCATION 12" C.I.P. WATER MAIN ON STEEL ST. UNDER EXPRESSWAY

W-1	H-1	V-1
E-12 12" PIPE REMOVED FOR STORAGE L.F.	E-12 FIRE HYDRANT REMOVED FOR STORAGE EA.	E-12 ℄ VALVE REMOVED FOR STORAGE EA.
267'	1	1

FOR DETAILS OF CONCRETE ENCASEMENT SEE SHEET 105

FOR DETAILS OF THRUST BLOCKS FOR 12" WATER MAIN SEE SHEET 85

RELOCATIONS OF SILLIMAN ST. SEWER & STEEL ST. WATER MAIN

FED. RD.	STATE	PROJECT	
2	OHIO		

85/492

MAH-18-17.20

NOTE: ALL EASEMENT AREA OF M.V.S.D. TO BE LEVELED AND SEEDED

SILLIMAN ST. 40'

RELOCATION M.V.S.D. 42" FEEDER MAIN - OAKWOOD AVE. SECTION

P.I. STA. 3+26 HOR. Δ 86°20' RT. 142' N ℄ STA. 930+60

AIR VALVE & ACC. M.H. STA. 3+54

CONCRETE THRUST BLOCK STA. 3+17 TO STA. 3+37 L=20' 140 TONS 70 S.F. BEARING

CONCRETE THRUST BLOCK STA. 11+05 TO STA. 11+09 L=4' 17 STONS 14 S.F. BEARING

ACCESS M.H. STA. 10+46

P.I. STA. 11+06 HOR. Δ 9°30' RT. 175' N ℄ STA. 938+46

END RELOCATION M.V.S.D. 42" FEEDER MAIN STA. 13+19 = EXISTING STA 79+43

CONCRETE THRUST BLOCK STA. 13+17 NEW PIPE TO STA. 79+48 OLD PIPE, L=7' 42.5 TONS 24.5 Q BRG SURF.

REMOVE 1220' 42" M.V.S.D. FEEDER MAIN (EXISTING)

EXIST. M.H. STA. 76+87

RAMP "C"

EXIST. MONUMENT M.V.S.D. P.I. STA. 68+93.08

EXIST. M.V.S.D. M.H. STA. 68+30

STA. 1+13 ACCESS M.H. & BLOW-OFF VALVE

8" DIA. DRAIN PIPE (300') C.I.P.

8" DRAIN OUTLET INTO SIDE DITCH 67' S. ℄ STA 933+69, INV. 904.7

CONCRETE THRUST BLOCK STA. 0+35 TO STA. 0+55 L=20' 137.5 TONS 70.0 BRG SURF.

P.I. STA. 0+44, HOR. Δ 84°30' LT. 147' S. ℄ STA. 930+60

EXIST. MONUMENT, M.V.S.D. P.I. STA. 67+43.44

24" GATE VALVE IN VAULT

BEGIN RELOCATION M.V.S.D. 42" FEEDER MAIN STA. 67+23.44 = STA. 0+00

EXPRESSWAY R/W LIMITS

SEE SHT. 18

PLAN

SCALE: 1" = 50'


NOTE: TIE JOINTS AT ALL BENDS

PROFILE


SCALE: H. 1" = 50' V. 1" = 10'

M.V.S.D. WATER REQUIREMENTS.		
I-124 NEW WATER MAIN		
4-2" DIA. PIPE	C 201 OR C 301	988 L.F.
4-2" DIA. PIPE ENCASED	C 201 OR C 301	338 L.F.
8" DIA.	CL. 23	300 L.F.
I-124 8" WATER MAIN FITTINGS		
8" DIA. 45° BEND	CL. 250 W/LUGS	1
I-8 MANHOLES - SPECIAL M.V.S.D.		
SPECIAL ACCESS MANHOLE		2
SPECIAL COMBINED ACC. & AIR VALVE M.H.		1
SPECIAL BLOW-OFF SETTING		1
I-16 MANHOLES ABANDONED		2
E-12 42" PIPE REMOVED		376 L.F.


NOTE: ON CONC. ENCASED PIPE WHICH REQUIRES THRUST BLOCKS, THRUST BLOCKS SHALL EXTEND BEYOND CONC. ENCASEMENT TO UNDISTURBED SOIL



PLAN VIEW




PLAN VIEW



GENERAL NOTE: CLASS "B" CONCRETE TO BE INCLUDED IN UNIT PRICE BID FOR ITEM I-124 "NEW WATER MAIN"

CONCRETE ANCHORAGE




CONCRETE THRUST BLOCK DETAILS

RELOCATION: M.V.S.D. 42" FEEDER MAIN - OAKWOOD AVE. SECTION

FED. RD.	STATE	PROJECT	
2	OHIO		

86
492



SEWER REQUIREMENTS

CODE	I-2 COMBINATION SEWER 27" M-6.6 c	I-2 COMBINATION SEWERS UNDER PVM'T. & APPROACHES 33" RADIUS PIPE M-6.6 b	15" M6.8(b)	27" M6.6(b)	27" M6.6(c)	27" M6.6(c)
F-1			185'			
F-2					308	*132
F-3	275			173'		
F-4				13'		
F-5		24				
TOTAL	275	24	185'	186'	308	*132


*Encased in Concrete

I-16 MANHOLES ABANDONED	
	6

S-24 STRUCTURE REMOVAL	
3'x17'x1' HEADWALL	1

I-8 MANHOLES		
SPECIAL YOUNGSTOWN MANHOLES	TYPE Y-A	2
SPECIAL SEWAGE REGULATOR CHAMBER		1

E-12 27" PIPE REMOVED
1013 LIN. FT.




PROFILE: SCALE: H. 1" = 50'
V. 1" = 10'
RELOCATION - 15" SEWER, LAIRD ST. TO EAST END OF 3RD. ST.
CODE F-1

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION		ELEV.	REMARKS
EXISTING STRUCTURES					
A-1	4' E. & LAIRD ST., 105' N. & 2ND. ST.	MANHOLE	I-8	15" INV. 884.74	TOP 894.1 CHANGE OUTLET
A-2	END 3RD. ST. M.H. 9+78.2 (S. SPR)	MANHOLE	I-8	15" INV. 876.5	18" INV. 876.24, 27" INV. 875.5 TOP 884.24 CHANGE OUTLET
A-3	SALT SPR. TO 3RD. ST. M.H. 9+09.3	MANHOLE	I-16	27" INV. 871.6	TOP 879.02 ABANDON
A-4	SALT SPR. TO 3RD. ST. M.H. 7+88.6	MANHOLE	I-16	27" INV. 865.7	TOP 873.10 ABANDON
A-5	SALT SPR. TO 3RD. ST. M.H. 6+80	MANHOLE	I-16	27" INV. 860.4	TOP 866.70 ABANDON
A-6	SALT SPR. TO 3RD. ST. M.H. 4+81	MANHOLE	I-16	27" INV. 851.41	TOP 857.24 ABANDON
A-7	SALT SPR. TO 3RD. ST. M.H. 2+51	MANHOLE	I-16	27" INV. 848.82	TOP 854.32 ABANDON
A-8	SALT SPR. TO 3RD. ST. M.H. 0+32.8	O.V. FLO. M.H.	I-16	27" INV. 844.55	TOP 856.16 ABANDON
A-9	SALT SPRINGS LINE M.H. 50+71.5	MANHOLE		27" INV. 845.24	TOP 856.7 SEE SHEET Nº 81
A-10	END OF E-9 OVERFLOW	END WALL	S-24	30" DIA.	3'x17'x1' ABANDON
PROPOSED STRUCTURES					
B-1	124' N. STA. 941 +60 EXP.-WAY	MANHOLE	Y-A	27" INV. 870.63	TOP 893.0
B-2	164' N. STA. 2+38 MAH.-W. FED.	MANHOLE	Y-A	27" INV. 867.16	TOP 874.0
B-3	STA. 0+27, 204' N STA 4+06 MAH. W. FED	REGULATOR CH.	29	27" INV. 847.89	SEE DETAIL SHEET Nº 89

DESCRIPTION OF WORK - COMBINED SEWERS

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	N. END LAIRD ST. TO 27" LINE	A-1	A-4	15"	142'	ABANDON
E-2	SALT SPR. RD. TO E. END 3RD. ST.	A-2	A-3	27"	69'	REMOVED E-12
E-3	SALT SPR. RD. TO E. END 3RD. ST.	A-3	A-4	27"	120.5	REMOVED E-12
E-4	SALT SPR. RD. TO E. END 3RD. ST.	A-4	A-5	27"	108.5	REMOVED E-12
E-5	SALT SPR. RD. TO E. END 3RD. ST.	A-5	A-6	27"	199'	REMOVED E-12
E-6	SALT SPR. RD. TO E. END 3RD. ST.	A-6	A-7	27"	230'	REMOVED E-12
E-7	SALT SPR. RD. TO E. END 3RD. ST.	A-7	A-8	27"	218.5	REMOVED E-12
E-8	SALT SPR. RD. TO E. END 3RD. ST.	A-8	A-10	27"	32.5	REMOVED E-12
E-9	OVERFLOW PIPE RUNS N. TO CREEK	A-8	N. TO CREEK	30"	35	REMOVED (C.I. PIPE OVERFLOW) E-12
PROPOSED SEWERS						
F-1	LAIRD ST. N. TO END 3RD. ST.	A-1	A-2	15"	185'	SLOPE 4.46 %
F-2	UNDER EXP.-WAY STA. 940+70	A-2	B-1	27"	440'	SLOPE 1.1%
F-3	W. TO E. N. EXP.-WAY	B-1	B-2	27"	275'	SLOPE 1.1%
F-4	N. OF RAMP A_3	B-2	B-3	27"	173'	SLOPE 11.43%
F-5	N. OF MAH. W. FED.	B-3	B-4	27"	13'	SLOPE 1.1 %



PROFILE: COMBINED SEWER SCALE: H. 1" = 50'
V. 1" = 10'
RELOCATION - 3RD. ST. TO SALT SPRINGS RD.

SEWER RELOCATIONS: LAIRD ST.; 3RD. ST. TO SALT SPRINGS RD.

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

87/492

ACCESS CORRIDOR FOR MAINTENANCE MVSD 42" FEEDER MAIN & 33" SAN. SEWER

MAHONING RIVER

C.M.P. 4' BOX SEWER EXTENSION SEE SHEET 116

BRIDGE STREET

EXISTING C.M.P. BOX SEWER

BANK SLAG FILL FOR BANK PROTECTION

TOP OF BANK

TOE OF BANK FILL

P.I. 2+17 Δ = 32°45' R.T. 62' WEST RAMP D

RAMP "D"

CORRIDOR

S.L.P. THRUST BLOCK

57.5 TONS 34.8 BRG SURF

ACC. M.H. 11+35

42" MVSD

AIR VALVE 8+00

SALT SPRING RD. 60'

P.I. STA. 0+03 Ha 25°40' Lt. 19' W. & STA. 1+24 MAH. W. FED.

BEGIN RELOCATION BLOW OFF MVSD 42" FEEDER MAIN STA. 0+01 STA. 8+41 = STA. 0+00

P.I. STA. 86+23 BLOW OFF MH & VALVE VAULT

ACCESS M.H.

BLOW OUT ACC. M.H. 88+35

EXISTING 42" MVSD FEEDER MAIN - REMOVE

EXISTING PIPE STA. 93+05 TO STA. 93+35 DO NOT REMOVE - FILL W/ SAND & LEAVE IN PLACE

P.I. STA. 7+02 Ha 17°45' Lt. 31' W. & STA. 11+11 RAMP "D"

THRUST BLOCK STA. 6+36 TO STA. 7+10 L = 14' 32.5 TONS 49 0 BRG. SURF.

ACC. MH. 7+20

1 FT. THICK CONCR. ENCASEMENT

P.I. STA. 11+90 Ha 9°Lt. 39' E. & STA. 6+26 RAMP "D"

ACC. MH. 12+10

ACC. MH. 99+71

ACCESS BENCH FOR MAINTENANCE SEWER & WATER LINES

FOR REMAINDER OF MVSD 42" FEEDER MAIN & 33" SEWER RELOCATION SEE SHEET Nº 90

FUTURE RAMP "B3"

FUTURE RAMP "B"

RAMP "C"

4" R.R. SPUR (TO BE REMOVED BY OTHERS)

EXISTING 33" SEWER

ABUTMENT

RESET ACCESS M.H. COVER STA. 88+61 42" MVSD. OAKWOOD SECTION NEW EL. 853.0 SEE DETAIL "A"

STA. 16+36 END RELOCATION 33" SEWER

SPECIAL FILL FOR 33" SEWER RELOCATION COVER

SAME AS B-3 SHEET #85

FEEDER MAIN

MVSD 42"W


FUTURE RAMP "A3"

MANHOLE "A3"


NOTES:
PROVIDE 3'@12" STUBS & PLUGS @ MANHOLES B-5 & B-6 FOR PROPOSED CATCH BASINS D-10, D-11, D-12, D-13 & D-14.

FOR DETAILS OF ITEMS D-10 D-11 D-12 D-13 D-14 SEE SHEET Nº 236

NOTE: FOR PROFILES OF SEWER & WATER LINE RELOCATIONS SEE SHEET Nº 88



DETAIL "A"



27" OVERFLOW TO RIVER FROM #29 REGULATOR CHAMBER

ITEM I-2 CLASS "B" STORM SEWERS UNDER PAVEMENT AND APPROACHES				
SIZE	FROM	TO	LENGTH	% GRADE
12"	B-5	D-10	3' STUB	7.21%
12"	B-5	D-11	3' STUB	4.40%
12"	B-5	D-12	3' STUB	7.12%
12"	B-6	D-13	3' STUB	4.04%
12"	B-6	D-14	3' STUB	10.38%

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS	
EXISTING STRUCTURES					
A-1	SALT SPRGS. LINE W. - R.R.	MANHOLE 40+68	33" INV. 843.40	TOP EL. 851.99	ABANDON I-16
A-2	" " SEWER E. - R.R.	MANHOLE	33" INV. 842.93	TOP EL. 853.41	ABANDON I-16
A-3	" " " W. - R.R.	MANHOLE 42+00	33" INV. 843.3	TOP EL. 853.93	ABANDON I-16
A-4	" " " W. - R.R.	MANHOLE 43+25	33" INV. 843.43	TOP EL. 854.90	ABANDON I-16
A-5	" " " W. - R.R.	MANHOLE 45+98	33" INV. 843.64	TOP EL. 854.50	ABANDON I-16
A-6	" " " W. - R.R.	MANHOLE 47+82	33" INV. 844.50	TOP EL. 856.10	ABANDON I-16
A-7	" " " W. - R.R.	MANHOLE 50+00	33" INV. 844.62	TOP EL. 856.44	ABANDON I-16
A-8	" " "	MANHOLE	SEE	SHEET Nº 84	
A-9	" " " W. - R.R.	MANHOLE 50+72	33" INV. 845.33	TOP EL. 856.73	ABANDON I-16
A-10	" " " N. - R.R.	MANHOLE 52+50	33" INV. 845.26	TOP EL. 858.81	ABANDON I-16
A-11	" " " S. ONETA	MANHOLE 55+01	33" INV. 846.04	TOP EL. 863.44	UNDISTURBED
PROPOSED STRUCTURES					
B-1	26' W. RAMP "D" & STA. 11+03.5	MANHOLE Y-A	33" INV. 843.90	TOP EL. 854.8	
B-2	48' W. RAMP "D" & STA. 15+18	MANHOLE Y-A	33" INV. 844.77	TOP EL. 851.2	
B-3	140' N. STA. 4+91 MAH. W. FED. EX.	MANHOLE Y-A	33" INV. 845.50	TOP EL. 852.25	
B-11		MANHOLE		SEE SHEET Nº 84	
B-5	18' W. STA. 18+48 RAMP "D" &	MANHOLE Y-A	33" INV. 845.69	TOP EL. 841.88 & 12" I-2 STUB = 836.74	
B-6	12' W. STA. 18+70 RAMP "D" &	MANHOLE Y-A	27" INV. 835.73	TOP EL. 841.56 & 12" I-2 STUB = 837.23	
B-10	18+40 RAMP "D"	6'X4' Box CULVT	—	FOR DETAIL & QUAN. SEE SHEET Nº 116	
B-7	103' N. STA. 5+95 MAH. W. FED. EX.	MANHOLE Y-A	27" INV. 836.39	TOP EL. 842.8 & 12" I-2 837.64	
B-8	135' N. STA. 4+83 MAH. W. FED. EX.	MANHOLE Y-A	27" INV. 842.00	TOP EL. 852.6 & 12" I-2 848.50	
B-9	SEE B-3 SHEET #80	#29 REG. CH.	27" INV. 849.52	SEE DETAIL SHEET Nº 83	
B-10	SEE DETAIL "A"				

I-8 MANHOLES		
SPECIAL YOUNGSTOWN MANHOLES	TYPE Y-A	G
	Y-A MOD	1

I-16 MANHOLES ABANDONED
9

SPECIAL, AS PER PLAN	
MH. EXTENSION	1

E-12 PIPE REMOVAL
SEWER OVER 15" DIA
1677 LIN. FT

DESCRIPTION OF WORK - COMBINED SEWERS

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS	ITEM
EXISTING SEWERS							
E-1	SALT SPRGS. SEG. BL. SEWER	A-8	A-1	33"	217'	REMOVED	E-12
E-2	" " " "	A-1	A-2	33"	117'	REMOVED	E-12
E-3	" " " "	A-2	A-3	33"	30'	REMOVED	E-12
E-4	" " " "	A-3	A-4	33"	125'	REMOVED	E-12
E-5	" " " "	A-4	A-5	33"	275'	REMOVED	E-12
E-6	" " " "	A-5	A-6	33"	184'	REMOVED	E-12
E-7	" " " "	A-6	A-7	33"	218'	REMOVED	E-12
E-8	" " " "	A-7	A-9	33"	72'	REMOVED	E-12
E-9	" " " "	A-9	A-10	33"	175'	REMOVED	E-12
E-10	" " " "	A-10	B-4	33"	149'	SLOPE 0.312%	E-12
E-11	" " " "	A-11	B-4	33"	101'	SLOPE 0.312% UNDISTURBED	E-12
E-12	CULVERT UNDER R.R.			4'x4'	70'	REMOVED	S-24
E-13	CULVERT UNDER S.SPR.RD.			48"	115'	REMOVED	E-12
PROPOSED SEWERS							
F-1	UNDER RAMP "D"	B-11	B-1	33"	475'	SLOPE 0.21%	
F-2	WEST OF RAMP "D"	B-1	B-2	33"	415'	SLOPE 0.21% 6"	
F-3	UNDER MAH. W. FED. EXP.	B-2	B-3	33"	350'	SLOPE 0.21% 62' CONCR. ENC. OVER 42" WATERLINE	
F-4	N. MAH. W. FED. EXP. RWY.	B-3	B-4	33"	110'	SLOPE 0.21%	
F-5	UNDER RAMP "D"	B-6	B-5	27"	32'	SLOPE 1.46%	
F-6	UNDER RELOCATED S. SPR. RD.	B-6	B-7	27"	52'	SLOPE 1.20% 6"	
F-7	OVER M.V.S.D. CROSS CONNECTION	B-7	B-8	27"	115	SLOPE 4.88% 30' CONCR. ENC. OVER 42" WATERLINE	
F-8	FROM REG. CH. #29	B-8	B-9	27"	100'	SLOPE 7.52%	

I-2 COMBINATION SEWERS UNDER PAVEMENT AND APPROACHES (LIN. FT.)


CODE	27" DIAM. M 6.6 (b)	27" DIAM. M 6.6(b) CONC. ENC.	27" DIAM.	33" DIAM. M 6.6(b)	33" DIAM. M 6.6(d)	33" DIAM. M 6.6(d) CONC. ENC.	
F-1					475'		
F-2				415			
F-3					288'	62'	
F-4				110'			
F-5	32						
F-6	52						
F-7	85'	30'					
F-8	100						
TOTAL	269'	30'		525'	763'	62'	

RELOCATIONS: SEWER & WATER LINES - SALT SPRINGS RD.


FED. RD.	STATE	PROJECT	
2	OHIO		

88
492

MAH-18-17.20



33" RCSP STA. 0+00 TO STA. 16+18
RADIUS PIPE CURVE STA. 16+18 TO STA. 16+36



RELOCATION 42" MVSD FEEDER MAIN
OAKWOOD AVE. SECTION
(SALT SPRINGS RD. AREA)


SCALE: HOR. 1" = 50'
VERT. 1" = 10'

RELOCATIONS OF SALT SPRINGS RD. AREA. SEWER & WATER MAINS


FED. RD.	STATE	PROJECT	
2	OHIO		

MAH - 18 - 17.20


89
492




LOCATION PLAN
SCALE: 1" = 50'



SECTIONAL PLAN
SCALE: 1/4" = 1'-0"




ROOF PLAN
SCALE: 1/4" = 1'-0"




HORIZONTAL SECTION VERTICAL SECTION


TYPICAL REINFORCING DETAILS
NO SCALE



SECTION D-D



SECTION B-B



SECTION C-C

REGULATOR EQUIPMENT SCHEDULE								
CHAMBER NO.	TYPE	FLOW M.G.D. ULTIMATE	MAXIMUM WATER ELEV. OUTFALL SEWER	FLOAT CHAMBER WATER SURFACE LOW	FLOAT CHAMBER WATER SURFACE HIGH	REGULATOR GATE SIZE	FLOAT SIZE	RATIO FLOAT TO GATE TRA
29	B	0.65		847.54	897.95	7 1/2" x 12 3/8"	24"	1 : 2

NOTES:

ALL REGULATORS ARE TO BE OF THE BROWN & BROWN TYPE OR APPROVED EQUAL. THE REGULATING EQUIPMENT IS TO BE DESIGNED FOR ULTIMATE FLOWS. THE CONTROLLING ELEVATION FOR EACH TYPE "B" REGULATOR IS THE INVERT ELEVATION OF THE EXISTING INTERCEPTING SEWER. IF THESE ELEVATIONS ARE DIFFERENT FROM ELEVATIONS SHOWN, ALL RELATING ELEVATIONS WILL BE CHANGED BY A CORRESPONDING AMOUNT. ALL REGULATOR GATES SHALL BE FULLY OPENED UNTIL THE LOW WATER ELEVATION OF FLOAT CHAMBER IS REACHED. WHEN HIGH WATER ELEVATION OF FLOAT CHAMBER IS REACHED, ALL TYPE "B" REGULATOR GATES SHALL BE COMPLETELY CLOSED.

REGULATOR CHAMBER NO. 29
SCALE: 1/4" = 1'-0"


26.4 CU. YD. CONCRETE
APPROX. 3316# REINFORCING STEEL
CLASS "C" CONCRETE

DETAIL - CAST IN PLACE CURVE & REGULATOR CHAMBER NO. 29


FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

90
492



1½" T-35 ASPHALTIC CONCRETE SURFACE COURSE - TYPE A



PAVEMENT REPLACEMENT.

WATER REQUIREMENTS

I-124 NEW WATER MAIN

16" DIA.	C.I. PIPE	CL. 25	174 L.F.
16" DIA.	C.I. PIPE	CL. 25, CONCRETE ENC.	296 L.F.
8" DIA.	C.I. PIPE	CL. 23	174 L.F.
8" DIA.	C.I. PIPE	CL. 23, CONCRETE ENC.	295 L.F.
VALVE	16" DIA.	CL. 150	2
VALVE	8" DIA.	CL. 150	1
BENDS	16" DIA.	45° W/LUGS CL 150	2
BENDS	16" DIA.	SPEC. W/LUGS CL 150	7
BENDS	8" DIA.	45° W/LUGS CL 250	2
BENDS	8" DIA.	SPEC. W/LUGS CL 250	7

E-12 PIPE REMOVED

16" C.I. PIPE REMOVED	427 L.F.

M.V.S.D. WATER REQUIREMENTS

I-124 NEW WATER MAIN

42" DIA. PIPE	C-201 OR C-301	340 L.F.
8" DIA.	CL 23	35 L.F.

I-8 MANHOLES SPECIAL M.V.S.D.

SPECIAL BLOW-OFF SETTING	1

E-12 PIPE REMOVED

42" DIA. STEEL PIPE REMOVED	214 L.F.

I-2 COMBINATION SEWERS UNDER PAV'T. & APPROACHES

CODE	12" DIA M6.8(b)	15" DIA M6.8(b)	24" DIA M6.6(a)	24" DIA M6.6(c)	30" DIA M6.6(c)	30" DIA M6.6(a)	30" DIA M6.6(b)	33" DIA M6.6(c)	33" DIA M6.6(a)	33" DIA M6.6(b)	33" DIA M6.6(c)
F-1	16'			30'							
F-2	4'				306'						
F-3					30'						
F-4							27'				
F-5							32'				
F-6								297'			
F-7				35'							
F-8											295'
TOTAL	20'			65'	336'		59'	297'			295'

I-8 MANHOLES

TYPE		EA.
YOUNGSTOWN	Y-A	9
	Y-D	2

I-16 MANHOLES ABANDONED

4

I-5 PIPE SPECIALS

CODE	TEE'S M6.6(b) 24"x24"x12"	TEE'S M6.6(b)	90° BEND M6.8(b) 12" DIA	90° BEND M6.8(b)
F-1	1		1	
F-2	1		1	
TOTAL	2		2	

E-12 PIPE REMOVED

15" TO 42"	152 L.F.

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
EXISTING STRUCTURES				
A-1	15' S. STA. 48+61.5 ℄ EX. PIERS	MANHOLE I-16	INV. 900.36	TOP 908.26 TOP BRIDGE - ABANDON
A-2	10' S. STA. 48+90 ℄ EX. PIERS	MANHOLE I-16	INV. 887.36	TOP 894.96 UNDER BRIDGE - ABANDON
A-3	12' S. STA. 52+56 ℄ EX. PIERS	MANHOLE	INV. 851.65	TOP 860.79 UNDER BRIDGE - UNDISTURBED
A-4	22' N. STA. 47+57.5 ℄ EX. PIERS	MANHOLE	INV. 903.21	TOP 911.56 - UNDISTURBED
A-5	1' N. STA. 48+64.5 ℄ EX. PIERS	MANHOLE I-16	INV. 895.08	TOP 908.08 TOP BRIDGE - ABANDON
A-6	6' S. STA. 53+17.5 ℄ EX. PIERS	MANHOLE	INV. 846.03	TOP 854.23 UNDER BRIDGE - UNDISTURBED
A-7	SALT SPRINGS 33" SEWER	M. H. 35+09	33" INV. 841.5	TOP 850.55 - UNDISTURBED
A-8	59' E. RAMP "D" B.L. STA. 3+63	M. H. 38+50 I-16	33" INV. 842.37	TOP 845.56 ABANDON
PROPOSED STRUCTURES				
B-1	13' S. STA. 48+31	MANHOLE Y-A	24" INV. 900.73	TOP 909.2, ESTABLISH IN EXIST. LINE
B-2	34' S. STA. 48+52.5	DROP M.H. Y-D	24" INV. 884.10	TOP 908.4, 24" INV. 900.37, 12" DIA. DROP PIPE
B-3	34' S. STA. 51+58	DROP M.H. Y-D	24" INV. 861.66	TOP 881.2, 24" INV. 865.89, 12" DIA. DROP PIPE
B-4	11.8' S. STA. 51+77	MANHOLE Y-A	30" INV. 859.39	TOP 867.4, 24" INV. 859.89 ESTAB. IN EXIST. LINE
B-5	11' N. STA. 48+13	MANHOLE Y-A	30" INV. 899.05	TOP 909.7, ESTABLISH IN EXIST. LINE (30")
B-6	7.5' S. STA. 48+32	MANHOLE Y-A	30" INV. 897.93	TOP 909.2, 18" INV. 898.93, ESTAB. IN EXIST. LINE (18")
B-7	30' S. STA. 48+54	MANHOLE Y-A	30" INV. 884.00	TOP 908.2, 30" INV. 896.04,
B-8	30' S. STA. 51+51	MANHOLE Y-A	24" INV. 865.36	TOP 880.4, 30" INV. 866.18
B-9	3.7' S. STA. 51+74	MANHOLE Y-A	24" INV. 861.57	TOP 868.0, ESTABLISH IN EXIST. 24" LINE
B-10	71' E. RAMP "D", ℄ STA. 3+29	MANHOLE Y-A	33" INV. 842.28	TOP 849.0, ESTABLISH IN EXIST. 33" LINE
B-11	46' E. RAMP "D", ℄ STA. 6+27	MANHOLE Y-A	33" INV. 842.90	TOP 862.6

DESCRIPTION OF WORK - COMBINED & STORM SEWERS

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	MAHONING AVE.	B-1	A-1	24"	31'	SLOPE 1.19% - REMOVE E-12
E-2	MAHONING AVE. THRU ABUTMENT	A-1	A-2	30"	29'	SLOPE 44.8% - ABANDON
E-3	MAHONING AVE. UNDER BRIDGE	A-2	B-4	30"	287'	SLOPE 9.75% - ABANDON
E-4	MAHONING AVE. UNDER BRIDGE	B-4	A-3	30"	79'	SLOPE 9.75% - UNDISTURBED
E-5	MAHONING AVE.	A-4	B-5	30"	56'	SLOPE 7.5% - UNDISTURBED
E-6	MAHONING AVE.	B-5	A-5	30"	53'	SLOPE 7.5% - REMOVE E-12
E-7	MAHONING AVE.	B-6	A-5	18"	34'	SLOPE 8.4% - REMOVE E-12
E-8	MAHONING AVE. UNDER BRIDGE	A-5	B-9	24"	309'	SLOPE 10.83% - ABANDON
E-9	MAHONING AVE. UNDER BRIDGE	B-9	A-6	24"	144'	SLOPE 10.83% - UNDISTURBED
E-10	SALT SPRINGS SEWER	A-7	B-10	33"	305'	SLOPE 0.253% - UNDISTURBED
E-11	SALT SPRINGS SEWER	A-8	B-10	33"	34'	SLOPE 0.253% - REMOVE E-12
PROPOSED SEWERS						
F-1	MAHONING AVE	B-1	B-2	24"	30'	SLOPE 1.2% -
F-2	S. MAHONING AVE. BRIDGE	B-2	B-3	24"	305.5'	SLOPE 6.0%
F-3	UNDER MAHONING AVE. BRIDGE	B-3	B-4	24"	29.5'	SLOPE 6.0%
F-4	MAHONING AVE. BRIDGE	B-5	B-6	30"	26.5'	SLOPE 4.23%
F-5	MAHONING AVE.	B-6	B-7	30"	31.5	SLOPE 6.0% -
F-6	S. MAHONING AVE. BRIDGE	B-7	B-8	30"	297'	SLOPE 6.0%
F-7	UNDER MAHONING AVE. BR	B-8	B-9	24"	35'	SLOPE 10.83%
F-8	EAST OF RAMP "D"	B-10	B-11	33"	295'	SLOPE 0.21% -
F-1	DROP M.H. B-2			12"	16'	1-24"x24"x12" TEE 1-12" 90° EL.
F-2	DROP M.H. B-3			12"	4'	1-24"x24"x12" TEE 1-12" 90° EL.


FOR PROFILES OF RELOCATIONS SEE SH. 91

RELOCATIONS OF MAHONING AVE. SEWER & WATER MAINS


FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20


91
492




RELOCATION - 30" STORM SEWER MAHONING AVE.



RELOCATION - 24" SANITARY SEWER MAHONING AVE.



RELOCATION - 16" WATER MAIN UNDER MAHONING AVE. BRIDGE



RELOCATION - 8" WATER MAIN UNDER MAHONING AVE. BRIDGE


SCALE: HOR. 1" = 50'
VERT. 1" = 10'

FOR PLAN VIEW OF RELOCATIONS SEE SH. 90

PROFILES - RELOCATIONS OF MAHONING AVE. SEWER & WATER MAINS


FED. RD.	STATE	PROJECT	
2	OHIO		

32
492




INSIDE DIAMETER OF HOSE COUPLING — $4\frac{1}{2}$"
NUMBER OF THREADS PER INCH — 6
BLANK END ON MALE PART — $\frac{1}{4}$"
OUTSIDE DIAMETER OF THREAD FINISHED — $5\frac{3}{8}$"
DIAMETER OF ROOT OF THREAD — 5.088
CLEARANCE BETWEEN MALE AND FEMALE THREADS — .062
TOTAL LENGTH OF THREADED MALE END — $1\frac{3}{8}$"
60° V THREAD PATTERN
FEMALE END TO BE CUT $\frac{1}{8}$" INCH SHORTER FOR ENDWISE CLEARANCE

INSIDE DIAMETER OF HOSE COUPLING — $2\frac{1}{2}$"
NUMBER OF THREADS PER INCH — $7\frac{1}{2}$
BLANK END ON MALE PART — $\frac{1}{4}$"
OUTSIDE DIAMETER OF THREAD FINISHED — $3\frac{1}{16}$"
DIAMETER OF ROOT OF THREAD — 2.8715
CLEARANCE BETWEEN MALE AND FEMALE THREADS — .03
TOTAL LENGTH OF THREADED MALE END — 1.00
60° V THREAD PATTERN $\frac{1}{100}$ INCH
CUT OFF TOP OF THREAD AND $\frac{1}{100}$ INCH
LEFT IN BOTTOM OF VALLEY FEMALE END TO BE CUT $\frac{1}{8}$" INCH SHORTER FOR ENDWISE CLEARANCE



YOUNGSTOWN STANDARD FIRE HYDRANT COUPLINGS FOR $2\frac{1}{2}$" & $4\frac{1}{2}$" HOSE



PROFILE: 6" WATER MAIN CONNECTION - MARSHALL ST. TO MAHONING AVE. VIA GLENWOOD AVE.
SCALE: H. 1" = 50'
V. 1" = 10'

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
EXISTING STRUCTURES				
A-1	6' N.-℄ ORANGE, 6' W.-℄ GLENW.	MANHOLE		SEE SHEET #7 (M.H.)
A-2	104' N.-℄ ORANGE, 10' W.-℄ GLENW.	MANHOLE	4' INV. 909.71	TOP EL. 920.31 - ABANDON I-16
A-3	70' N.-℄ MARSHALL, 10' W.-℄ GLENW.	MANHOLE	4' INV. 887.20	TOP EL. 897.20 - PLUG INLET
A-4	W. SIDE GLENWOOD@MARSHALL	CATCH BASIN		SEE SHEET # 240
A-5	E. SIDE GLENWOOD@MARSHALL	CATCH BASIN		SEE SHEET # 240

WATER REQUIREMENTS

I-124 NEW WATER MAIN

6" DIA. C.I. PIPE	CL. 22	362'
VALVE 6" DIA.	CL. 150	1
BENDS 6" DIA. SPECIAL W/LUGS	CL. 250	3

DESCRIPTION OF WORK - COMBINED SEWERS

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	GLENWOOD	A-1	A-2	48"	98'	DOUBLE RING BRICK - ABANDON
E-2	GLENWOOD	A-2	A-3	48"	300'	DOUBLE RING BRICK - ABANDON

SEWER REQUIREMENTS

I-16 STRUCTURES ABANDONED

MANHOLES ABANDONED
1


RELOCATION - 6" WATER MAIN - GLENWOOD AVE.

FED. RD.	STATE	PROJECT	
2	OHIO		

93
492

NOTE: PROPOSED REGULATOR CHAMBER 101 IS TO BE CONSTRUCTED BY OTHERS. THIS REGULATOR CHAMBER IS THE OUTLET OF THE PROPOSED COMBINATION SEWER SHOWN ON THESE PLANS. THE CONTRACTOR SHALL COORDINATE HIS CONSTRUCTION OPERATIONS WITH THE CONTRACTOR OF REGULATOR CHAMBER 101 FOR OUTLETTING THE COMBINATION SEWER

PROPOSED REGULATOR CHAMBER №101 SEE DETAIL DWG. #719-G-3 ON FILE YOUNGSTOWN SEWER DEPT. BEGIN RELOCATION S. WALL REGULATOR CHAMBER @ STA. 0+20



WATER REQUIREMENTS

I-124 NEW WATER MAIN	
CUT & PLUG 6" DIA. C.I.P.	2

SEWER REQUIREMENTS

I-2 COMBINATION SEWERS UNDER PVMT & APPROACHES						I-5 PIPE SPECIALS		
						TEE'S		90° BEND
CODE	18" DIA.	48" DIA.				48"X48"X18"		18" DIA.
	M 6.8(18)	M 6.6(48)	M 6.6(18)	M 6.6(12)	M 6.6(8)	M 6.8(48)	M 6.6(18)	M 6.8(18)
F-1		37'						
F-2		297'						
F-3			90'					
F-4	11				200'	1		1
F-5	8			57'			1	1
F-6	8		353'				1	1
F-7			296'					
F-8		25'						
F-9		20'						
TOTAL	27'	379'	739'	57'	200'	1	2	3


I-8 MANHOLES			I-16 STRUCTURES ABANDONED	
YOUNGSTOWN MANHOLES			MANHOLES	CATCH BASINS
Y-B	Y-D		ABANDONED	ABANDONED
5	3		1	2

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
EXISTING STRUCTURES				
A-1	G.N. & ORANGE, G.W. & GLENWOOD	MANHOLE	48"INV. 917.48	TOP EL. 927.28 - NEW OUTLET I-8
A-2	123'N. & ORANGE, & ROCKVIEW	MANHOLE	10"INV. 897.09	TOP EL. 907.59 - ABANDON I-16
A-3	& MARSHALL, & ROCKVIEW	MANHOLE	15"INV. 866.48	12"INV. 867.25, TOP EL. 876.65-UNDISTURBED
A-4	ROCKVIEW S. OF MARSHALL	CATCH BASIN		ABANDON - I-16
A-5	ROCKVIEW S. OF MARSHALL	CATCH BASIN		ABANDON - I-16
A-6	95.4' N. MARSHALL, & ROCKVIEW	MANHOLE	12"INV. 863.54	TOP EL. 872.66 - UNDISTURBED
A-7	& MAHONING, & ROCKVIEW	MANHOLE	20"INV. 856.14	TOP EL. 869.15 - UNDISTURBED
A-8	11.3' N. & MAHONING, 3' W. & ROCKVIEW	MANHOLE	48"INV. 858.91	TOP EL. 868.96 - UNDISTURBED
PROPOSED STRUCTURES				
B-2	29'S. & MAHONING, 8'W. & ROCKVIEW	MANHOLE Y-D	48"INV. 859.11	TOP EL. 869.5
B-3	33'N. & MARSHALL, 8'W. & ROCKVIEW	MANHOLE Y-D	48"INV. 861.75	TOP EL. 875.0
B-4	57'S. & MARSHALL, 8'W. & ROCKVIEW	DROP M.H. Y-D	48"INV. 864.63	INV. 875.75 (48"INLET) TOP EL. 883.7
B-5	10'N. & ORANGE, 8'W. & ROCKVIEW	DROP M.H. Y-D	48"INV. 891.00	INV. 899.0 (48"INLET) TOP EL. 916.0
B-6	30'N. & ORANGE, 48'W. & ROCKVIEW	DROP M.H. Y-D	48"INV. 903.00	INV. 911.23 (48"INLET) TOP EL. 925.5
B-7	30'N. & ORANGE, 401'W. & ROCKVIEW	MANHOLE Y-D	48"INV. 914.41	TOP EL. 929.4
B-8	30'N. & ORANGE, 35'E. & GLENWOOD	MANHOLE Y-D	48"INV. 917.08	TOP EL. 927.0
B-9	13'N. & ORANGE, 10'E. & GLENWOOD	MANHOLE Y-D	48"INV. 917.30	TOP EL. 927.1

DESCRIPTION OF WORK - COMBINED SEWERS

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	ROCKVIEW AVE.	A-2	A-3	10'	205'	ABANDON
E-2	ROCKVIEW AVE.	A-6	A-7	12"	260'	UNDISTURBED
E-3	MAHONING AVE.	A-8	B-1	48"	35'	SLOPE 0.89%, DOUBLE RING BRICK
PROPOSED SEWERS						
F-1	MAHONING AVE.	REG.CH.	B-2	48"	37'	SLOPE 0.3% REIN. CONC. PIPE
F-2	ROCKVIEW AVE.	B-2	B-3	48"	297'	SLOPE 0.9% REIN. CONC. PIPE
F-3	ROCKVIEW AVE.	B-3	B-4	48"	90'	SLOPE 3.2% REIN. CONC. PIPE
F-4	ROCKVIEW AVE.	B-4	B-5	48"	200'	SLOPE 7.63% REIN. CONC. PIPE
F-5	ROCKVIEW TO ORANGE	B-5	B-6	48"	57'	SLOPE 7.0% REIN. CONC. PIPE
F-6	ORANGE AVE.	B-6	B-7	48"	353'	SLOPE 0.9% REIN. CONC. PIPE
F-7	ORANGE AVE.	B-7	B-8	48"	296'	SLOPE 0.9% REIN. CONC. PIPE
F-8	ORANGE TO GLENWOOD	B-8	B-9	48"	25'	SLOPE 0.9% REIN. CONC. PIPE
F-9	GLENWOOD	B-9	A-1	48	20'	SLOPE 0.9% REIN. CONC. PIPE
	DROP MANHOLES B-4, B-5, B-6			18"	27'	3 TEES 48"x48"x18", 3-90° ELLS, 18" DIA.



GLENWOOD AVE. 48" SEWER RELOCATION
TO MAHONING AVE. VIA ORANGE & ROCKVIEW


SCALE: H: 1" = 50'
V: 1" = 10'

RELOCATION - GLENWOOD AVE. SEWER

MAH-18-17.20

FED. RD.	STATE	PROJECT	
2	OHIO		

94
492



WATER REQUIREMENTS

I-12 4 NEW WATER MAIN

36" DIA. PRESTRESSED REINF. CONC. PIPE C-301		11 L.F.
36" DIA. PRESTR'S'D REINF. CONC. PIPE C-301 CONC. ENCASED		249 L.F.
30" DIA. C.I. PIPE	CL 26	16 L.F.
30" DIA. C.I. PIPE	CL 26 CONC. ENCASED	62 L.F.
16" DIA. C.I. PIPE	CL. 25	19 L.F.
16" DIA. C.I. PIPE	CL. 25 CONC. ENCASED	373 L.F.
6" DIA. C.I. PIPE	CL. 22	26 L.F.
BENDS 90° W/LUGS, 6" DIA. C.I.P.	CL-250	2
BENDS 45° TIED, 36" DIA. PRESTR. REF. CONC. C-301		3
BENDS 45° 30" DIA. C.I.P. W/LUGS	CL 150	3
BENDS 45° 16" DIA. C.I.P. W/LUGS	CL 150	4
SPECIAL BENDS TIED, 36" DIA. PRESTR. REINF. CONC. C 301		3
SPECIAL BENDS 30" DIA. C.I.P. W/LUGS	CL 150	3
SPECIAL BENDS 16" DIA. C.I.P. W/LUGS	CL 150	5
REDUCER 8" DIA. TO 6" DIA. C.I.P.	CL 250	1
VALVES 30" DIA. C.I.P.	CL 200	1
VALVES 6" DIA. C.I.P.	CL 150	2
FIRE HYDRANTS		2
CUT & PLUG EXISTING WATER MAINS		2

E-12 PIPE REMOVED FOR STORAGE	
30" DIA. VALVE REMOVAL	1
6" DIA. VALVE REMOVAL	2
FIRE HYDRANT REMOVAL	2
36" PRESTR. REINF. CONC. PIPE	253 L.F.
C.I.P. REMOVAL	650 L.F.

I-8 M.H. ADJUSTED TO GRADE	
30" AIR VALVE M.H.	1

S.S. SPECIAL VALVE BOX	
SEE DETAIL SHEET 89	1

I-124 CONCRETE ENCASEMENT OF EXIST. WATER MAINS (6" MIN. THK.)	
36" DIA. PRESTR. REINF. CONC. PIPE	328 L.F.
30" DIA. C.I.P.	300 L.F.
16" DIA. C.I.P.	87 L.F.

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
EXISTING STRUCTURES				
A-1	℄ WEST AVE. - 26' N. ℄ MARSHALL	MANHOLE	856.08	TOP 866.51 UNDISTURBED
A-2	5' W. ℄ WEST AVE. 325' S. ℄ MARSHALL	MANHOLE I-16	910.51	TOP 919.0 ABANDONED
A-3	WEST AVE. 73' N. ℄ HIGH	MANHOLE I-16	923.34	TOP 930.99 ABANDONED
A-4	WEST AVE.	CATCH BASIN I-16	——	REMOVE
A-5	WEST AVE.	CATCH BASIN I-16	——	REMOVE
A-6	WEST AVE.	CATCH BASIN I-16	——	REMOVE
A-7	WEST AVE.	CATCH BASIN I-16	——	REMOVE
PROPOSED STRUCTURES				
B-1	℄ WEST AVE., 179' N. ℄ HIGH	MANHOLE Y-A	12" INV. 918.00	TOP 928.75
B-2	℄ HIGH ST., @ ℄ WEST AVE.	MANHOLE Y-A	INV. 912.49	12" INV. 917.46 TOP 932.4

SEWER REQUIREMENTS

I-12 COMBINED SEWER		
CODE	12" DIA.	
	M 6.8 (b)	
F-1	179'	

I-8 MANHOLES
YOUNGSTOWN M.H.
Y-A

I-16 STRUCTURES ABANDONED	
MANHOLES ABANDONED	CATCH BASINS ABANDONED
2	4

DESCRIPTION OF WORK - COMBINED SEWERS

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	WEST AVE.	A-2	A-1	15"	350'	ABANDON
E-2	WEST AVE.	B-1	A-2	15"	150'	ABANDON
E-3	WEST AVE.	A-3	B-1	15"	106'	SLOPE 3.85% ABANDON
PROPOSED SEWERS						
F-1	WEST AVE.	B-1	B-2	12"	179'	SLOPE 0.3% MAKE HOUSE CONNECTIONS


FOR PROFILES OF RELOCATIONS SEE SH. 95

RELOCATIONS: SEWER & WATER LINES - PLUM ST. & WEST AVE.


FED. RD.	STATE	PROJECT	
2	OHIO		

95
492


MAH-18-17.20



RELOCATION: 30" C.I.P. WATER MAIN - PLUM ST.



SEWER RELOCATION
WEST AVE.




30" TO 16" CROSSOVER
WEST AVE. & MARSHALL


ESTIMATED SP'L. VALVE BOX QUANTITIES

CLASS "C" CONCRETE	3.4 C.Y.
REINFORCING STEEL	184 LBS.


SCALE: HOR. 1" = 50'
VERT. 1" = 10'



VALVE BOX-SPECIAL DETAIL



RELOCATION : 36" REINF. CONC. WATER MAIN - PLUM ST.



RELOCATION : 16" C.I.P. WATER MAIN - WEST AVE.


FOR PLAN OF RELOCATIONS SEE SH. 88


PROFILES: SEWER & WATER LINES - PLUM ST. & WEST AVE.

FED. RD.	STATE	PROJECT	
2	OHIO		

96
492

MAH-18-17.20





ESTIMATED QUANTITIES — WATER

I - 124 NEW WATER MAIN


CODE	LOCATION FROM	LOCATION TO	C.I. PIPE LINEAL FT. 4" DIA. CL. 22	C.I. PIPE LINEAL FT. 6" DIA. CL. 22	C.I. FITTINGS CL. 250 EACH 6"X 4" CROSS TEE	6" TAP-IN TEE SLEEVE	4"X4"X2" REDUCING TEE	4" TEE	6" 90° BEND	6" 22 1/2° BEND	6" 11 1/4° BEND	VALVES CL. 150 EACH 2"	4"	6"	FIRE HYDRANT EACH	CUT & PLUG EXIST. LINE EACH	WROUGHT I. CONN. 2" TO 11/2" LINE EACH
W-1	HIGH ST. 11'E. & 10'N. M.H. A-2					1								1			
W-2	5' N. OF W-1	PHI HΔ13°									1						
W-3	W-1	W-4		110'						2							
W-4	5' N. STA. 2+51	ACCESS DR.			1												
W-5	115' N. STA. 2+52	ACCESS DR.											1				
W-6	BETWEEN W-4 & W-5													1			
W-7	4' N. STA. 2+57	ACCESS DR.	P.H.I.	HΔ 8°	(2 JOINT DEFLECTION)												
W-8	W-4	W-5		7'													
W-9	W-4	W-10	165'														
W-10	6.5' S. & 71' W	M.H. A-4					1 W/ PLUG										
W-11	N. OF W-10											1					
W-12	6.5' N. STA. 2+30.5	ACCESS DR.					1 W/plug										
W-13	E. OF W-12												1				
W-14	W-4	W-12	21'														
W-15	N. OF W-11																1
W-16	4' W. & 12' N.	M.H. A-5														1	
W-17	EDWARDS	110' S.℄ Y.E.		18					1					1	1		
W-18	HIGH 11' W. 17' N.	M.H. A-2														1	
TOTAL			186	135	1	1	1	1	1	2	1	1	1	3	2	2	1

E-12 PIPE REMOVED FOR STORAGE & REUSE


CODE	LOCATION	4" VALVE REMOVED
W-18	HIGH 11' W. & 17' N. M.H. A-2	1
TOTAL		1

I-8 INLETS & CATCH BASINS

CODE	LOCATION & STATION	WINDOW ELEV.	OUTLET SIZE	OUTLET INV. ELEV.	YNGSTN. INLETS TYPE I	YNGSTN. INLETS TYPE II
C-1	RELOC. EDWARDS 20'RT. STA. 0+57	921.63	12"	918.32	1	
C-2	ACCESS RD. 10' RT. STA. 0+54.7	918.56	12"	915.25	1	
C-3	ACCESS RD. 10' LT. STA. 0+41	918.19	12"	914.88		1
C-4	HALL CT. 8' RT. STA. 0+28.6	932.50	12"	929.19	1	
C-5	HALL CT. 8' LT. STA. 0+25	932.34	12"	929.00		1
C-6	ACCESS RD. 10' LT. STA. 2+57.7	932.32	12"	929.00		1
TOTAL					3	3



BURNS CT. - HALL CT. 12" SEWER RELOCATION



6" C.I.P. STA. 0+00 TO STA. 1+10
4" C.I.P. STA. 1+10 TO STA. 2+75

BURNS CT. - HALL CT. WATER MAIN RELOCATION

ESTIMATED QUANTITIES - SEWER

DESCRIPTION OF WORK

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
EXISTING STRUCTURE				
A-1	N. END HALL CT.	MANHOLE	12" IE. 919.68	TOP 934.0 UNDISTURBED
A-2	3' S. & HIGH, 358.6' W. ℄ PLUM	MANHOLE	31.39" IE. 917.13	TOP 928.03 NEW 12" INLET INV. 918.5
A-3	BURNS CT., 107' W. M.H. A-4	MANHOLE	10" IE. 922.54	TOP 933.5 UNDISTURBED
A-4	BURNS CT., 178' N. M.H. A-5	MANHOLE	10" IE. 920.83	TOP 933.5 ABANDON
A-5	1.5' S. & HIGH, 142' W. ℄ PLUM	MANHOLE	31.39" IE. 915.56	TOP 930.6 UNDISTURBED
PROPOSED STRUCTURE				
B-1	℄ ACCESS DR. STA. 2+34.5	MANHOLE Y-A	12" IE. 919.52	TOP 932.15 ESTABLISHED IN EXIST. 12" LINE
B-2	45' W. M.H. A-4	MANHOLE Y-A	12" IE. 921.55	TOP 933.50 ESTABLISHED IN EXIST. 10" LINE

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWER						
E-1	HALL COURT	A-1	B-1	12"	123' APPROX.	SLOPE 0.13% UNDISTURBED
E-2	HALL COURT	B-1	A-2	12"	111'	SLOPE 0.13% ABANDON (TAKEN BY EXCAV. F-1)
E-3	BURNS COURT	A-3	B-2	10"	62'	SLOPE 1.6% UNDISTURBED
E-4	BURNS COURT	B-2	A-4	10"	45'	SLOPE 1.6% ABANDON
E-5	BURNS COURT	A-4	A-5	10"	178'	SLOPE 1.6% ABANDON (TAKEN BY EXCAV. RAMPS)
PROPOSED SEWER						
F-1	HALL CT. TO HIGH ST.	B-1	A-2	12"	111'	SLOPE 0.92%
F-2	IN NEW ACCESS DR.	B-2	B-1	12"	209'	SLOPE 0.97%
F-3	EDWARDS ST. & RAMP "F"	C-1	C-2	12"	30'	SLOPE 11.70%
F-4	ACCESS RD.	C-2	C-3	12"	25'	SLOPE 3.24%
F-5	EDWARDS ST. & ACCESS RD.	C-3	L-5	12"	42'	SLOPE 10.43%
F-6	HALL CT.	C-4	C-5	12"	16'	SLOPE 4.00%
F-7	ACCESS RD. & HALL CT.	C-5	B-1	12"	26'	SLOPE 36.46%
F-8	ACCESS RD.	C-6	F-2	12"	11'	SLOPE 77.00%
TOTAL						

PAY ITEM

I-16 STRUCTURES ABANDONED

MANHOLES ABONDONED EA.
1
TOTAL 1

I-8 MANHOLES


YNGSTN. MANHOLES Y-A EACH
1
1
TOTAL 2

I-2 COMBINED SEWERS PER LIN. FT. M.G.S (b) 12" DIA.	I-5 FITTINGS EACH M.G.S (b) 60° WYE 12" x 12"
111'	
209'	1
30'	
25'	
42'	
16'	
26'	
11'	
TOTAL 470'	TOTAL 1

FED. RD.	STATE	PROJECT	
2	OHIO		

97
492

MAH - 18-17.20



WATER REQUIREMENTS

I-124 NEW WATER MAIN

6" DIA. C.I. PIPE	CL. 22	23'	L.F.
VALVES 6" DIA.	CL. 150	2	EA.
BENDS 6" DIA. 90° W/LUGS	CL. 250	2	EA.
FIRE HYDRANTS		2	EA.
CUT & PLUG 6" DIA. C.I.P.		1	EA.

E-12 PIPE REMOVED FOR STORAGE

6" VALVE REMOVAL	2
FIRE HYDRANT REMOVAL	2

DESCRIPTION OF WORK — STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS	
EXISTING STRUCTURES					
A-1	℄-SMITH, 116' N. ℄-HIGH ST.	MANHOLE	15" INV. 897.43	TOP 905.03 - UNDISTURBED	
A-2	℄-SMITH, 225' S. ℄-MARSHALL ST.	MANHOLE	15" INV. 849.75	TOP 858.95 - ABANDON	I-16
A-3	℄-MARSHALL, Y. SEW. REC. 12+00	MANHOLE	15" INV. 835.61	TOP 845.61 - UNDISTURBED	
A-4	12.5' LT. ℄ SMITH, 267' N. ℄ HIGH ST.	CATCH BASIN		REMOVE & SALVAGE	I-16
A-5	13.5' RT. ℄ SMITH, 270' N. ℄ HIGH ST.	CATCH BASIN		REMOVE & SALVAGE	I-16
A-6	℄-WALTER ST, 246' E. ℄ SMITH ST.	MANHOLE	12" INV. 842.43	TOP 853.23 - ABANDON	I-16
A-7	11' R. ℄ WALTER ST, 227' E. ℄ SMITH ST.	CATCH BASIN		REMOVE & SALVAGE	I-16
A-8	8' L. ℄ WALTER ST, 237' E. ℄ SMITH ST.	STORM INLET		REMOVE & SALVAGE	I-16
PROPOSED STRUCTURES					
B-1	℄-SMITH ST, 247' N. ℄ HIGH ST.	MANHOLE Y-A	15" INV. 877.46	TOP 884.4 ESTABLISH IN EXISTING LINE	
B-2	5' W. ℄ SMITH ST, 252' N. ℄ HIGH ST.	DROP M. Y-D	15" INV. 867.70	15" INV. 877.11, TOP 884.4, 8" DROP PIPE	
B-3	5' W. ℄ SMITH ST, 90' S. ℄ MARSHALL	MANHOLE Y-A	15" INV. 841.81	TOP 849.8	
B-4	℄-SMITH ST., 85' S. ℄ MARSHALL	MANHOLE Y-A	15" INV. 841.23	TOP 849.8 ESTABLISH IN EXISTING LINE	
			12" INV. 841.48	(STORM DRAIN INLET)	

DESCRIPTION OF WORK — COMBINED SEWERS.

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	℄-SMITH ST.	A-1	B-1	15"	132'	SLOPE 15.13% - UNDISTURBED
E-2	℄-SMITH ST.	B-1	A-2	15"	183'	SLOPE 15.13% - ABANDON
E-3	℄-SMITH ST.	A-2	B-4	15"	139'	SLOPE 5.10% - ABANDON
E-4	℄-SMITH ST.	B-4	A-3	15"	90'	SLOPE 5.72% - UNDISTURBED
E-5	C.B. DRAIN	A-4	SEWER	10"	13'	ABANDON
E-6	C.B. DRAIN - SMITH ST.	A-5	SEWER	10"	14'	ABANDON
E-7	℄-WALTER ST. SEWER	A-6	SH. 10	12"	438'	SLOPE 1.64% - ABANDON
E-8	WALTER ST.	A-7	A-6			C.B. DRAIN - ABANDON
E-9	WALTER ST.	A-8	A-6			INLET DRAIN - ABANDON
PROPOSED SEWERS						
F-1	℄-SMITH ST.	B-1	B-2	15"	7'	SLOPE 5.0%, DROP PIPE, 15"x8"T, 8"-90°EL
F-2	5' W. ℄-SMITH ST.	B-2	B-3	15"	313'	SLOPE 8.27%,
F-3	℄-SMITH ST.	B-3	B-4	15"	7'	SLOPE 8.27%

SEWER REQUIREMENTS

I-2 COMBINATION SEWERS UNDER PVMT. ℄ APPROACHES

I-5 PIPE SPECIALS

CODE	8" DIA. M 6.8 (b)	15" DIA. M 6.8 (b)	TEE M 6.8 (d) 15"x15"x8"	90° BEND M 6.8 (f) 8" DIA
F-1	10'	7'	1	1
F-2		313'		
F-3		7'		
TOTAL	10'	14'	313'	1	1

I-8 MANHOLES

YOUNGSTOWN MANHOLES	
Y-A	Y-D
3	1

I-16 STRUCTURES ABANDONED

MANHOLES ABANDONED	CATCH BASINS ABANDONED
2	4

PROFILE: SCALE: H = 1" = 50' V = 1" = 10'

15" - STA. 0+90 TO 4+17


SEWER RELOCATION AT SMITH ST.

RELOCATIONS OF SMITH ST. SEWER & WATER MAIN


FED. RD.	STATE	PROJECT	
2	OHIO		

98
492


MAH-18-17.20



PLAN : PIKE ST. - RELOCATION OF COMBINED SEWER & 8" WATER LINE
SCALE: 1"=50'



PROFILE: COMBINED SEWER, SCALE: H. 1"=50' V. 1"=10'



PROFILE: RELOCATED PIKE ST. 8" WATER LINE, SCALE: H. 1"=50' V. 1"=10'

DESCRIPTION OF WORK - COMBINED SEWERS

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	℄ WALTER ST.	A-2	R/W LINE	12"	255'	SLOPE 0.55% - ABANDON
E-2	℄ WALTER ST.	75'W. A-1	A-1	12"	75'	UNDISTURBED
E-3	WALTER ST.	A-3	E-2	10"		CATCH BASIN DRAIN - ABANDON
E-4	WALTER ST.	A-4	E-2	10"		CATCH BASIN DRAIN - ABANDON
E-5	℄ PIKE ST.	A-5	A-6	54"	357'	SLOPE 3.0 % - ABANDON E-12
E-6	OUTFALL	A-6	B-1	68"	115'	SLOPE 1.78 % - ABANDON E-12
E-7	℄ WALTER ST.	SH'T 90	A-1	12"		SEE SHEET #90
PROPOSED SEWERS						
F-1	OAK HILL AVE. TO RELOC. PIKE	A-5	B-1	54"	377'	SLOPE 3.02% - EX. STR REIN. CONC. PIPE (6 IN. CONCR. ENCASED)

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
EXISTING STRUCTURES				
A-1	℄ - OAK HILL AVE. ℄ - WALTER ST.	MANHOLE	12" INV. 832.4	TOP 846.30 - UNDISTURBED
A-2	℄ - WALTER ST. 330' W. ℄ - OAK HILL	MANHOLE I-16	12 INV. 835.92	TOP 843.10 - ABANDON
A-3		CATCH B. I-16		
A-4		CATCH B. I-16		
A-5	℄ - PIKE ST. 40.5' E. ℄ - OAK HILL	MANHOLE I-8	54" INV. 842.17	TOP 858.17 30" INV. 36" x 46" INV.
A-6	℄ - PIKE ST. 396' E. ℄ - OAK HILL	MANHOLE I-16	68" INV. 831.65	TOP 843.65 54" INV. 832.82 ABANDON
PROPOSED STRUCTURES				
B-1	7' N. ℄ - RELOCATED PIKE ST. STA. 4+40, 158' N. Y.E. ℄ STA. 1009+70	MANHOLE Y-B	68" INV. 829.6	TOP 859.11 54" INV. 830.77 ESTAB. IN EXIST. LINE

SEWER REQUIREMENTS

I-8 MANHOLES	
YOUNGSTOWN MH	
Y-B	
1	

I-16 STRUCTURES ABANDONED.	
MANHOLES ABANDONED	CATCH BASINS ABANDONED.
2	2

E-12 PIPE REMOVAL
15" TO 42"
472 LIN. FT.

I-2 COMBINED SEWERS		
CODE	54" DIA.	54" DIA. CONC. ENCASED
	M.G.G (d)	M.G.G (d)
F-1	6 LIN. FT.	371 LIN. FT.

WATER REQUIREMENT

I-124 NEW WATER MAIN		
8" DIA. C.I. PIPE	CL. 22	390' L.F.
6" DIA. C.I. PIPE	CL. 22	35' L.F.
VALVES 8" DIA.	150#	1
VALVES 6" DIA.	150#	3
BENDS 8" DIA. 90°	W/LUGS 250#	1
BENDS 8" DIA SPECIAL	W/LUGS 250#	10
BENDS 6" DIA 90°	W/LUGS 250#	2
REDUCER 8" TO 6"	250#	1
TEE 8"x8"x8"	250#	1
TEE 8"x8"x6"	250#	1
TEE 6"x6"x6"	250#	1
FIRE HYDRANTS		1
CUT & PLUG 6" DIA. C.I.P.		1


E-12 PIPE REMOVED FOR STORAGE	
VALVE REMOVAL	3
FIRE HYDRANT REMOVAL	3

PIKE ST. - RELOCATION OF COMBINED SEWER & 8" WATER LINE

FED. RD.	STATE	PROJECT	
2	OHIO		

99
492

MAH-18-17.20



WATER REQUIREMENTS

I-12 4 NEW WATER MAINS		
8" DIA. C.I. PIPE	CL. 23	234 L.F.
8" DIA. C.I. PIPE, CONC. ENCASED	CL. 23	166 L.F.
6" DIA. C.I. PIPE	CL. 22	112 L.F.
6" DIA. C.I. PIPE, CONC. ENCASED	CL. 22	297 L.F.
VALVES 8" DIA.	150#	1
VALVES 6" DIA.	150#	5
TEE'S 8"X8"X6"	250#	2
TEE'S 6"X6"X6"	250#	2
BENDS 8" DIA. 90° W/LUGS	250#	1
BENDS 8" DIA. 45° W/LUGS	250#	2
BENDS 8" DIA. 22½°	250#	1
BENDS 8" DIA. SPECIAL	250#	5
BENDS 6" DIA. 90° W/LUGS	250#	2
BENDS 6" DIA. 45° W/LUGS	250#	3
BENDS 6" DIA. SPECIAL	250#	6
FIRE HYDRANTS		5

E-12 PIPE REMOVED FOR STORAGE	
VALVE REMOVAL	3
FIRE HYDRANT REMOVAL	2

SEWER REQUIREMENTS

I-2 COMBINED SEWERS UNDER PAVEMENT & APPROACHES						I-5 PIPE SPECIALS	
CODE	8" DIA. M 6.8(b)	15" DIA. M 6.8(b)	18" DIA. M 6.6(c)	18" DIA. M 6.6(d)	21" DIA. M 6.6(d)	24" DIA. M 6.6(d)	TEE'S M 6.8(b) 15"X15"X8"	90° BEND 8" DIA M 6.8(b)
F-1						346'		
F-2						101'		
F-3					186'			
F-4				79'				
F-5			44'					
F-6			359'					
F-7	20'	14'					1	1
F-8	19'						1	1
TOTAL	39'	14'	403'	79'	186'	447'	2	2

I-8 MANHOLES	
YOUNGSTOWN MANHOLES	
Y-A	Y-C
6	2

I-16 STRUCTURES ABANDONED	
MANHOLES ABANDONED	CATCH BASINS ABANDONED
3	6

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
EXISTING STRUCTURES				
A-1	℄ WOODLAND, 356' W. ℄ MARKET ST.	MANHOLE	20" INV. 940.76	18" INV. 940.93 TOP 950.46 UNDISTURBED
A-2	℄ WOODLAND - ℄ WILLIAMS	MANHOLE I-16	18" INV. 949.69	15" INV. 950.19 TOP 959.14 ABANDON
A-3	8' S. ℄ WOODLAND, 40' W. ℄ WILLIAMS	MANHOLE I-16	INV. 955.21	TOP EL. 960.76 ABANDON
A-4	WOODLAND	CATCH BAS. I-16		REMOVE & SALVAGE GRATE & FRAME
A-5	WOODLAND	CATCH BAS. I-16		" " " " " "
A-6	WILLIAMS	CATCH BAS. I-16		" " " " " "
A-7	WILLIAMS	CATCH BAS. I-16		" " " " " "
A-8	4' N. RIDGE ST. & STA. 48+91	MANHOLE I-16	15" INV. 935.53	TOP EL. 946.48 ABANDON
A-9	RIDGE	CATCH BAS. I-16		REMOVE & SALVAGE GRATE & FRAME
A-10	RIDGE	CATCH BAS. I-16		" " " " " "
PROPOSED STRUCTURES				
B-1	30' E. ℄ MARKET, 6' N. ℄ WOODLAND	MANHOLE	24" INV. 912.26	SEE SHEET # 94 M.H. B-3
B-2	6' N. ℄ WOODLAND, 316' W. ℄ MARKET	MANHOLE Y-A	24" INV. 919.18	TOP EL. 948.1
B-3	STA. 4+47	MANHOLE Y-A	24" INV. 921.20	21" INV. 921.45 TOP EL. 953.3
B-4	10' E. WILLIAMS ST. STA. 9+02.5	DROP M.H. Y-C	21" INV. 931.14	18" INV. 931.39, 15" INV. 952.52, TOP EL. 960.8
B-5	18' S. ℄ WOODLAND, 70' W. ℄ WILLIAMS	MANHOLE Y-A	18" INV. 934.15	TOP EL. 961.50
B-6	℄ WOODLAND, 109' W. ℄ WILLIAMS	DROP M.H. Y-C	18" INV. 935.69	15" INV. 954.75, TOP EL. 963.20 ESTAB. IN EXIST. SEWER
B-7	4' N. RIDGE ST., ℄ STA. 47+25	MANHOLE Y-A	18" INV. 937.31	15" INV. 937.56, TOP EL. 947.9 ESTAB. IN EXIST. SEWER
B-8	℄ WILLIAMS ST., ℄ STA. 8+92	MANHOLE Y-A	15" INV. 952.94	TOP EL. 961.3 ESTAB. IN EXIST. SEWER
B-9	4' N. RIDGE ST., ℄ STA. 50+05	MANHOLE Y-A	15" INV. 931.00	TOP EL. 943.0 ESTAB. IN EXIST. SEWER

DESCRIPTION OF WORK - COMBINED SEWERS


CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	WOODLAND AVE.	A-2	A-1	18"	200'	SLOPE 4.47% ABANDON
E-2	WOODLAND AVE.	B-6	A-2	15"	109'	SLOPE 4.18% ABANDON
E-3	WILLIAMS ST.	B-4	A-2	15"	108'	SLOPE 2.78% ABANDON
E-4	RIDGE AVE.	A-8	B-9	15"	114'	SLOPE 3.97% ABANDON
E-5	RIDGE AVE.	B-7	A-8	15"	166	SLOPE 1.12% ABANDON
PROPOSED SEWERS						
F-1	WOODLAND AVE.	B-1	B-2	24"	346'	SLOPE 2.0%
F-2	S. OF WOODLAND	B-2	B-3	24"	101'	SLOPE 2.0%
F-3	UNDER EXPRESSWAY	B-3	B-4	21"	186'	SLOPE 5.2%
F-4	WILLIAMS TO WOODLAND	B-4	B-5	18"	79'	SLOPE 3.5%
F-5	WOODLAND	B-5	B-6	18"	44'	SLOPE 3.5%
F-6	S. OF EXPRESSWAY	B-6	B-7	18"	359	SLOPE 0.45%
F-7	WILLIAMS	B-8	B-4	15"	14'	SLOPE 2.78%
F-7	DROP M.H. B-4			8"	20'	DROP PIPE 1-15"x15"x8" TEE, 1-8" 90° EL.
F-8	DROP M.H. B-6			8"	19'	DROP PIPE 1-15"x15"x8" TEE, 1-8" 90° EL.

FOR PROFILES OF RELOCATIONS SEE SH. 100

RELOCATIONS: SEWER & WATER LINES - RIDGE & WOODLAND


FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20




RELOCATION: 6" C.I.P. WATER MAIN - RIDGE ST.


NOTE:
FOR DETAIL OF ENCASEMENT
SEE SHEET Nº 102



RELOCATION: 8" C.I.P. WATER MAIN - WOODLAND AVE.



RELOCATION: 15" SEWER WILLIAMS ST.



RELOCATION: 21" SEWER RIDGE TO WOODLAND & WILLIAMS TO MARKET ST.

SCALE: HOR. 1" = 50'
VERT. 1" = 10'

FOR PLAN OF RELOCATIONS SEE SH. 99

FED. RD.	STATE	PROJECT	
2	OHIO		

101
492

SEWER REQUIREMENTS

I-2 COMBINATION SEWERS UNDER PVM'T. & APPROACHES — I-5 PIPE SPECIALS

CODE	18" DIA. M 6.8(b)	48" DIA. M 6.6(b)	48" DIA. M 6.6(c)	48" DIA. M 6.6(d)	TEES M 6.6(d) 48"x48"x18"	90° BENDS M 6.8(b) 18" DIA.
F-1			38'			
F-2				295'		
F-3				180'		
F-4				218		
F-5	12'			10'	1	1
F-6	12'	32'			1	1
TOTAL	24'	32'	38'	703'	2	2

I-8 MANHOLES


SPECIAL	TYPE	
YOUNGST.	Y-B	5
MANHOLE	Y-D	2

I-16 STRUCTURES ABANDONED

MANHOLES ABANDONED	CATCH BASINS ABANDONED
1	2

S-S

JUNCTION CHAMBER	1.



WATER REQUIREMENTS.

I-124 NEW WATER MAIN.

6" DIA C.I. PIPE	CL. 22	66'
VALVES 6" DIA.	150#	2
BENDS		
BENDS 8" DIA 90°	250#	2
REDUCERS 8" TO 6"	250#	2
FIRE HYDRANTS		2

E-12 PIPE REMOVAL FOR STORAGE AND REUSE

FIRE HYDRANTS REMOVED	1
VALVES REMOVED	1

NOTE: EXISTING SEWER TO BE MAINTAINED NORTH OF NORTH CONSTRUCTION LIMIT, STA. 0+00 TO STA. 5+40. ALL HOUSE CONNECTIONS BOTH SIDES OF STREET TO EXIST. 48" SEWER TO BE MAINTAINED.

48" DIA. REINF. CONC. PIPE STA. 0+25 TO STA. 7+98

PROFILE SCALE: HOR. 1"=50' VERT. 1"=10'

DESCRIPTION OF WORK - STRUCTURES.

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
EXISTING STRUCTURES				
A-1	1'E. ℄-MARKET UNDER BRIDGE, 7.8' N. ABUT.	MANHOLE	48" INV. 900.14	TOP EL. 911.8 UNDISTURBED
A-2	℄-MARKET, 11' S. ℄-RIDGE	MANHOLE (C.B. DRAIN)	48" INV. 912.01	TOP EL. 926.61 UNDISTURBED
A-3	℄-MARKET, 37' S. ℄-RIDGE	MANHOLE (C.B. DRAIN)	—	TOP EL. 927.42 UNDISTURBED
A-4	℄-MARKET, ℄-W. WOODLAND	MANHOLE	48" INV. 925.18	TOP EL. 939.41 UNDISTURBED
A-5	℄-MARKET ST. STA. 49+01	MANHOLE	48" INV. 939.39	TOP EL. 953.69 TO BE ABANDONED I-16
A-6	55' N ℄-WOODLAND, 45' E. ℄-MARKET	MANHOLE	18" INV. 928.44	TOP EL. 936.46 UNDISTURBED
A-7	MARKET ST.	CATCH BASIN		ABANDON I-16
A-8	MARKET ST.	CATCH BASIN		ABANDON I-16
PROPOSED STRUCTURES				
B-1	0.42' E. ℄-MARKET ST. STA. 56+06.5	JUNCTION CHAMBER	48" OUTL. INV. 903.52	48" INLET INV. 903.72, SEE DETAIL SHEET Nº 12-13
B-2	30' E. ℄-MARKET ST. STA. 55+72	MANHOLE Y-D	48" INV. 904.30	TOP EL. 927.0
B-3	30' E. ℄-MKT. ST. STA. 52+77	MANHOLE Y-D	48" INV. 908.78	24" INV. 912.26 TOP EL. 938.5, M.H. B-1 SHEET Nº 12
B-4	30' E. ℄-MKT. ST. STA. 50+97	MANHOLE Y-D	48" INV. 911.52	TOP EL. 945.6
B-5	30' E. ℄-MKT. ST. STA. 48+79	DROP M.H. Y-D	48" INV. 916.15	48" INV. 928.12, TOP EL. 954.0
B-6	23' E. ℄-MKT. ST. STA. 48+72	DROP M.H. Y-D	48" INV. 928.5	48" INV. 939.94, TOP EL. 954.4
B-7	℄-MARKET ST. STA. 48+49	MANHOLE Y-D	48" INV. 941.15	TOP EL. 955.6 ESTABLISH IN EXIST. LINE
B-8	℄-MARKET ST. STA. 50+94	MANHOLE Y-D	48" INV. 932.3	TOP EL. 946.36 ESTABLISH IN EXIST. LINE

DESCRIPTION OF WORK - COMBINED SEWERS

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	℄-MARKET ST.	B-1	A-1	48"	15'	SLOPE 22.6% UNDISTURBED
E-2	℄-MARKET ST.	WITHIN	B-1	48"	10.5'	SEE DETAIL SHEET Nº
E-3	℄-MARKET ST.	A-4	B-1	48"	328'	SLOPE 6.17% UNDISTURBED
E-4	℄-MARKET ST.	B-8	A-4	48"	177'	SLOPE 3.78% UNDISTURBED
E-5	℄-MARKET ST.	A-5	B-8	48"	193'	SLOPE 3.78% ABANDON
E-6	℄-MARKET ST.	B-7	A-5	48"	52'	SLOPE 3.78% ABANDON
E-7	E. WOODLAND TO MARKET	A-6	48" SEWER	18"	50'	UNDISTURBED
PROPOSED SEWERS						
F-1	MARKET ST.	B-1	B-2	48"	38'	SLOPE 1.52%
F-2	30' E. ℄-MARKET ST.	B-2	B-3	48"	295'	SLOPE 1.52%
F-3	30' E. ℄-MARKET ST.	B-3	B-4	48"	180'	SLOPE 1.52%
F-4	MARKET ST. UNDER EXP-WAY	B-4	B-5	48"	218'	SLOPE 2.12%
F-5	MARKET ST.	B-5	B-6	48"	10'	SLOPE 3.78%
F-6	MARKET ST.	B-6	B-7	48"	32'	SLOPE 3.78%
F-5	DROP MANHOLE B-5	DROP PIPE		18"	12'	1-48"x48"x18" TEE, 1-18" 90° EL.
F-6	DROP MANHOLE B-6	DROP PIPE		18"	12'	1-48"x48"x18" TEE, 1-18" 90° EL.

GENERAL NOTE:
IT IS INTENDED THAT EXISTING 48" SEWER, STA. 50+94 TO STA. 56+00 REMAIN IN SERVICE AFTER RELOCATION IS ACCOMPLISHED. 48" RELOCATION TO BE CONSTRUCTED WITHOUT DISTURBING HOUSE CONNECTIONS AND LATERAL CONNECTIONS TO EXISTING 48" SEWER.

RELOCATI 12" MARKE WE


FED. RD.	STATE	PROJECT	
2	OHIO		

101A
492

MAH. 18-17.20

THE EXISTING M.H. (B-7) STA. 48+49 ℄ MARKET ST. SHALL BE TOTALLY REMOVED AND THE PROPOSED JUNCATION CHAMBER DETAIL ON SHEET Nº 101B IS TO BE CONSTRUCTED "AS PER PLAN". THE MAN-HOLE FRAME & COVER FOR B-7 IS TO BE SALVAGED & RESET AS SHOWN ON THE PROPOSED JUNCATION CHAMBER.

THE VOID BETWEEN THE PROPOSED 48" PRESSURE PIPE & THE C.M.P. IS TO PRESSURE FILL WITH M-2.1 SAND.



THE M.H. A-2 SHOWN ABOVE AT STA. 51+22.37 ℄ MARKET ST. WILL REPLACE THE PROPOSED MANHOLE B-8 SHOWN ON SHEET 101 OF THE CONTRACT PLANS. FRAME & COVER OF M.H. A-2 SHALL BE WATER TIGHT - LOCKING TYPE NEENAH R-1919" OR EQUAL.

FOR CONSTRUCTION DETAILS & QUANTITIES SHOWN THUS:


A-1030-802 M.L.	SEE SHEET Nºs 46 & 47
A-G RAMP "K"	SEE SHEET Nºs 59 & 83
A-2 RAMP "M"	SEE SHEET Nºs 61 &

SEQUENCE OF CONSTRUCTION

THE PROPOSED 48" INVERT SIPHON SHALL BE CONSTRUCTED AFTER ALL THE PILING FOR THE MARKET ST. STRUCTURE HAS BEEN DRIVEN

THE REVISIONS TO THE EXISTING JUNCTION CHAMBER B-1 SHOWN IN DETAIL ON SHEET Nºs 101 C & D

THE QUANTITY OF PIPE DESIGNATED AS P-1 ℄ ALL I-5 PIPE SPECIALS INCORPORATED IN THE RUN OF PIPE SHALL BE REINFORCED CONCRETE PRESSURE PIPE CONFORMING WITH AMERICAN WATER WORKS ASSOCIATION A.W.W.A. C 302-57. THE PIPE SHALL ALSO MEET THE STRENGTH REQUIREMENTS FOR THE OHIO DEPARTMENT OF HIGHWAYS CONSTRUCTION & MATERIAL SPECIFICATIONS FOR M-6.6(d) PIPE.
*OR 48" REINFORCED CONCRETE PIPE, STEEL CYLINDER TYPE, PRESTRESSED A.W.W.A. SPEC. C-301



FOR CONSTRUCTION DETAILS OF PROPOSED INVERTED SIPHON SEE SHEET Nº 101 B.


I-8 MANHOLES — S-24

CODE	LOCATION	JUNCATION CHAMBER AS PER PLAN	Nº 2 MAN-HOLE EACH	REVISE EXISTING JUNCTION CHAMBER	REMOVE EXIST. MANHOLE
B-7	48+49 ℄ MARKET ST.	1			1
A-2	51+22.37 ℄ MARKET ST.		1		
B-1	56+06.5 042E ℄ MARKET			1	
	SHEET TOTALS	1	1	1	1

ESTIMATED QUANTITIES - INVERTED SIPHON (LUMP)

CODE	LOCATION	I-2 CLASS "A" SEWERS L.F. 48" PIPE RADIUS	48" PIPE STRGHT	12" C.I. PIPE CLASS 24 LIN. FT.	66" OR OVER M-64(6) ✱	I-5 PIPE SPEC. EACH FLAP VALVES 12"	24"	48" R.H. TANG BLOW OFF WITH 125# 12" FLANGE	45° Bend 12" C.I.P. Class 24
P-1 ‡	B-7 TO A-2	112	160		36			1	
P-2	50+60.64 - B-4 UTLY			48					1
P-99	12" I-2 FROM A-99 @ A-100					1			
P- 8	24" I-2 FROM A-103 @ A-100						1		
P- 5	12" I-2 FROM A-101 @ A-100					1			
	SHEET TOTALS	112	160	48	36	2	1	1	1

THE ABOVE ESTIMATED QUANTITIES FOR THE PROPOSED SIPHON ARE FOR GENERAL INFORMATION ONLY.
✱ GAGE OF MATERIAL AS REQUIRED BY THE ENGINEER
‡ 48" STRAIGHT PIPE AND 48"-30° BENDS MAY BE USED AS AN ALTERNATE TO RADIUS PIPE. SEE PROFILE BELOW.




— NOTES —

For details of Manhole A-2, and its connection with this siphon and the existing sewer, see Std. Drawing I-8 Nº 2 or Std. Drw'g. I-8 Nº 1-A, both dated 1-26-59.

The location and direction of "Relief Pipe" P-2 will be as directed by the Engineer to best connect the low point of this siphon with existing manhole B-4.

The flow in the existing, and in the already relocated, 48" combination sewers shall be maintained at all times in a manner which will protect the new work herein proposed and satisfactory to the Engineer.




PROPOSED 48" SIPHON MARKET ST.

Rev. 4-4-62
REV. 6-5-62

FED. RD.	STATE	PROJECT	
2	OHIO		


101B 492

MAH - 18 - 17.20




PLAN VIEW


DETAIL KEY JOINT




DETAIL MARKET ST. SIPHON SCALE 1" = 20' HORIZ. & VERTICAL




ROOF PLAN



DETAIL R.H. TANGENT BLOW-OFF




SECTION "A"-"A"




SECTION "X-X"

SECTION "A"-"A"



SECTION "B"-"B"



SECTION "C"-"C"


SCALE : 1" = 2'

DETAILS REVISED
JUNCTION CHAMBER B-7
MARKET ST. UTILITIES

REV 6-9-62


FED. RD.	STATE	PROJECT	
2	OH10		

101C
492




SECTIONAL PLAN


NOTE:
ALL CONCRETE TO BE CLASS "C"




COLLAR AT OUTLET
SCALE 1"=1'-0"




SECTION E-E




COLLAR AT OUTLET
WITH RAISED SHOULDERS
SCALE 1"=1'-0"




SECTION A-A



SECTION B-B



SECTION C-C



SECTION D-D
SCALE 1"=1'-0"

DESIGN CHANGE TO IMPROVE OUTLET FLOW IN JUNCTION CHAMBER MARKET ST. SEWER RELOCATION STRUCTURE B-1 SHEET Nº 101 ℄


107 MAH.-18-17.20

SCALE: ¼"=1'-0"


4/10

FED. RD.	STATE	PROJECT	
2	OHIO		

101D
492



JUNCTION CHAMBER
AS DESIGNED



DESIGN CHANGE TO IMPROVE
OUTLET FLOW IN
JUNCTION CHAMBER

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER & HOCH, Consulting Engineers
AKRON, OHIO


JUNCTION CHAMBER
MARKET STREET SEWER RELOCATION
STRUCTURE B-1 SHEET Nº 101 & 102
MAH-18-17.20

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED

FED. RD.	STATE	PROJECT	
2	OHIO		


102
4-92

MAH-18-17.20




SECTIONAL PLAN

NOTE:
ALL CONCRETE TO BE CLASS 'C'




24" TYPE "A" C.I. MANHOLE FRAME & COVER


ROOF PLAN




TOP OF COVER



UNDERSIDE OF COVER



SECTION Y-Y



PLAN OF FRAME

SECTION Z-Z

NOTE: CASTING SHALL BE OF CAST IRON IN ACCORDANCE W/ STATE SPECIFICATION U-7.8

YOUNGSTOWN STANDARD MANHOLE FRAME & COVER

NOTES

BEARING AREAS OF FRAME AND COVER SHALL BE SO FITTED AND FINISHED AS TO PROVIDE A FIRM AND EVEN SEAT FOR ALL PORTIONS OF THE COVER IN THE FRAME. NO PROJECTIONS SHALL EXIST ON BEARING AREAS OF EITHER CASTING AND EACH COVER SHALL SEAT IN ITS FRAME WITHOUT ROCKING. FRAMES AND COVERS SHALL BE FITTED, MATCHED AND MARKED BEFORE DELIVERY TO THE PROJECT

SETTING OF CASTING:~ THE BASE OF THE FRAME SHALL BE SET IN A FULL BED OF PORTLAND CEMENT MORTAR AND SO ADJUSTED TO CONFORM TO THE FINISHED PAVEMENT GRADE.

CASTING:~ CASTING SHALL BE OF CAST IRON IN ACCORDANCE WITH STATE SPECIFICATIONS. THE DESIGN SHALL BE ESSENTIALLY THE SAME AND EQUALLY AS STRONG AS THOSE SHOWN HEREON. WEIGHT MINIMUM, FRAME 220 POUNDS, COVER 140 POUNDS


STEPS SHALL BE OF GOOD QUALITY WROUGHT IRON IN ACCORDANCE WITH MATERIAL DETAILS.

CONSTRUCTION:~ MANHOLES SHALL BE BUILT OF BRICK, PRECAST SOLID CONCRETE BLOCKS, PRECAST CONCRETE RINGS, OR CAST IN PLACE CONCRETE. WHEN MANHOLES ARE CONSTRUCTED OF BRICK, EVERY SIXTH COURSE SHALL BE A STRETCHER COURSE.


BOTTOM OF MANHOLE SHALL BE OF CLASS C CONCRETE.

CHANNEL SECTIONS IN THE MANHOLE SHALL BE CONSTRUCTED OF SPLIT PIPE OR BRICK EXCEPT CURVED SECTIONS WHICH MAY BE BUILT BY FORMING A CHANNEL IN THE CONCRETE.


NOTE:
ON CONC ENCASED PIPE WHICH REQ THRUST BLOCKS, THRUST BLOCKS SHALL EXTEND BEYOND CONC. ENCASEMENT TO UNDISTURBED SOIL




TYPICAL SECTION OF S-1 CLASS 'E' CONC. ENCASEMENT OF YOUNGSTOWN WATER MAINS AND COMBINATION SEWERS



SECTION A-A



SECTION B-B



SECTION C-C

NOTE: CONCRETE ENCASEMENT TO BE INCLUDED IN THE CONTRACT PRICE BID PER LINIAL FOOT UNDER THE APPROPRIATE ITEM OF THE FOLLOWING:
ITEM I-124 'NEW WATER MAIN (CONC. ENCASED)"
ITEM I-2 "COMBINED SEWER"
ITEM I-124 "ENCASEMENT OF EXISTING WATER MAIN"

JUNCTION CHAMBER
MARKET ST. SEWER RELOCATION
STRUCTURE B-1 SHEET Nº 101
SCALE ¼" = 1'-0"

DETAIL OF JUNCTION CHAMBER RELOCATION: 48" MARKET ST. SEWER

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

103
492

WOODLAND AVE.

50'

HAYES AVE.

60'

ERIE ST.

30'

MARLIN ST.

40'

KYLE ST.

40'

RAMP "N"

RAMP "M"

RAMP Bx

FUTURE

MARKET ST.

94'

FULTON ST.

40'

S.C. 2+68.61

C.S. 3+69.35

S.T. 5+13.35

T.S. 5+33.35

P.C. 1+73.95

C.S. 1+23.95

C.S. 5+28.31

S.C.S. 7+28.31

DEAD END 6" C.I.P. WATER
200' S. ℄-WOODLAND.
INSTALL 90° EL., VALVE
& FIRE HYDRANT (12-6" C.I.P.)

DEAD END 6" C.I.P. WATER
230' S. ℄-WOODLAND
INSTALL 90° EL. VALVE
& FIRE HYDRANT (17-6" C.I.P.)

REMOVE VALVE & FIRE HYDRANT

ABANDON 6" C.I.P. (400')
BETWEEN DEAD ENDS

REMOVE VALVE &
FIRE HYDRANT

ABANDON 6" C.I.P.
430'
BETWEEN DEAD ENDS.

DEAD END 6" C.I.P. WATER
630' S. ℄-WOODLAND.
INSTALL 90° EL. VALVE
& FIRE HYDRANT (10-6" C.I.P.)

DEAD END 6" C.I.P. WATER
630' S. ℄-WOODLAND.
INSTALL 90° EL. VALVE
& FIRE HYDRANT (6'-6" C.I.P.)

LIMIT FUTURE CONSTRUCTION

OHIO EDISON CO. PERMANENT OVERHEAD
INSTALLATION TO SPAN CONSTRUCTION AREA

B-1 B-2 E-2 E-4 A-4 A-3 A-2 A-1 E-3 E-1

1031 1032 1033 1034 806 805 804 803

DESCRIPTION OF WORK - STRUCTURES

CODE	LOCATION	DESCRIPTION	ELEV.	REMARKS
EXISTING STRUCTURES				
A-1	℄-HAYES, 424' S. ℄-WOODLAND	MANHOLE	18" INV. 949.02	TOP 958.82 - ABANDON I-16
A-2	8' W. ℄-ERIE, 294' N. ℄-FULTON	MANHOLE	15" INV. 946.35	TOP 958.0 - ABANDON I-16
A-3	HAYES	CATCH BASIN		ABANDON I-16
A-4	HAYES	CATCH BASIN		ABANDON I-16
PROPOSED STRUCTURES				
B-1	℄-HAYES, 206' S. ℄-WOODLAND	MANHOLE Y-A	18" INV. 941.34	TOP 950.40 - ESTABLISH IN EXIST. 18" LINE
B-2	8' W. ℄-ERIE, 236' S. ℄-WOODLAND	MANHOLE Y-A	15" INV. 940.78	TOP 952.39 - ESTABLISH IN EXIST. 15" LINE

DESCRIPTION OF WORK - COMBINED SEWERS

CODE	LOCATION	FROM	TO	SIZE	LENGTH	REMARKS
EXISTING SEWERS						
E-1	HAYES AVE. (SHEET 3-X)	B-4	A-1	18"	181'	ABANDON
E-2	HAYES AVE.	A-1	B-1	18"	218'	ABANDON
E-3	ERIE ST. (SHEET 3-X)	B-3	A-2	15"	112'	ABANDON
E-4	ERIE ST.	A-2	B-2	15"	189'	ABANDON

SEWER REQUIREMENTS

I-8 MANHOLES
YOUNGSTOWN MANHOLES
Y-A
2

I-16 STRUCTURES ABANDONED	
MANHOLES ABANDONED	CATCH BASINS ABANDONED
2	2

WATER REQUIREMENTS

I-124 NEW WATER MAIN			
C.I. PIPE	6" DIA.	CL. 22	45'
VALVES	6" DIA.	150	4
BENDS	6" DIA. 90° 250	W/LUGS	4
FIRE HYDRANTS			4

E-12 PIPE REMOVAL FOR STORAGE & REUSE	
VALVE REMOVAL	2
FIRE HYDRANT REMOVAL	2

NOTE: THE CONTRACTOR SHALL COORINATE HIS OPERATIONS WITH THE CONTRACTOR OF PROJECT MAH-7-14.80. OUTLETS FOR THE COMBINATION SEWERS IN HAYES AVE. AND ERIE ST. ARE TO BE PROVIDED IN PROJECT MAH-7-14.80 AS INDICATED ON THIS PLAN. EXISTING COMBINATION SEWERS IN HAYES AVE. AND ERIE ST. MAY NOT BE REMOVED WITHIN CONSTRUCTION LIMITS UNTIL OUTLETS ARE PROVIDED

DISPOSITION OF UTILITIES: HAYES AVE. & ERIE ST.

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

104
492

WOODLAND AVE. 50'

HAYES AVE. 60'

ERIE ST. 30'

M.H. B-1
SEE SHEET 96

M.H. B-2
SEE SHEET 96

RAMP "N"

RAMP "M"

MARKET ST. 94'

1031

1032

1033

1034

M.H. A-1
SEE SHEET 96

M.H. A-2
SEE SHEET 96

806 ± 88 LF 34" RCP CONTRACT

806

805

804

803

802

801

800

TOP OF BACK SLOPE

FUTURE RAMP BX

MARLIN ST. 40'

A-3
0+00

FULTON ST. 40'

SEWER RELOCATION
PROPOSED FOR PROJECT.
MAH. 7-14.80

HENRY ST. 50'


NOTE: THE CONTRACTOR SHALL COORINATE HIS OPERATIONS WITH THE CONTRACTOR OF PROJECT MAH-7-14.80. OUTLETS FOR THE COMBINATION SEWERS IN HAYES AVE. AND ERIE ST. ARE TO BE PROVIDED IN PROJECT MAH-7-14.80 AS INDICATED ON THIS PLAN. EXISTING COMBINATION SEWERS IN HAYES AVE. AND ERIE ST. MAY NOT BE REMOVED WITHIN CONSTRUCTION LIMITS UNTIL OUTLETS ARE PROVIDED.

TEMPORARY SEWER MAINS - HAYES, HENRY, ERIE, FULTON & MARLIN

FED. RD.	STATE	PROJECT	
2	OHIO		

105
492

MAH-18-17.20



BLOW-OFF MANHOLE


SCALE : 3/8" = 1'-0"

BLOW-OFF SETTING


SCALE : 3/8" = 1'-0"

NOTE "A"

SPACE BETWEEN COVERS ON ALL AIR VALVE MANHOLES SHALL BE PACKED WITH FIBERGLASS INSULATION INSTALLED IN LAYERS OF 3" THICK BATT BLANKETS. CUT TO FIT PROPERLY. MATERIAL TO BE SIMILAR TO FLINTKOTE INSULATING WOOL OR EQUAL.




SECTION C-C




PLAN

GENERAL NOTE: MANHOLES, ALL CONCRETE TO BE CLASS "C"




PLAN

NOTE:
ON CONC. ENCASED PIPE WHICH REQ. THRUST BLOCKS, THRUST BLOCKS SHALL EXTEND BEYOND CONC. ENCASEMENT TO UNDISTURBED SOIL




TYPICAL SECTION OF S-I CLASS "E" CONCRETE ENCASEMENT OF 42" MAHONING VALLEY SANITARY DISTRICT FEEDER MAIN

NOTE:
ENCASEMENT TO BE INCLUDED IN THE CONTRACT PRICE BID PER LIN. FT. FOR ITEM I-124 "NEW WATER MAIN" (CONCRETE ENCASED)




PLAN




PLAN

ACCESS MANHOLE

SCALE: 1/2" = 1'-0"




SECTION A-A



SECTION B-B

COMBINATION AIR VALVE AND ACCESS MANHOLE



SECTION D-D

AIR VALVE MANHOLE


NOTE:
EQUIPMENT SHOWN IS FOR USE WITH STEEL PIPE. IF CONCRETE PIPE IS USED, EQUIPMENT SHALL BE AS FOLLOWS:
2" SADDLE
2" GATE VALVE
2" AIR RELEASE VALVE.

FED. RD.	STATE	PROJECT	
2	OHIO		


106
492


MAH-18-17.20

6" - 30° SHORT RADIUS CURVE




TYPICAL STACK DETAIL
FOR SANITARY SEWER LINES







STD. CONSTRUCTION JT.
~NO SCALE~





VIT. PIPE CONNECTION
~NO SCALE~






PLAN OF TYPE-I STORM INLET AT "A-A"






NOTE:
MANHOLE CASTING FOR TYPE-I INLET IS IDENTICAL TO CASTING FOR TYPE II INLET. FOR DETAILS SEE SHEET Nº ☐


SECTIONAL ELEVATION TYPE-I STORM INLET
SCALE: 1"=1'-0"




SEWERS UP TO 42" (TYPE Y-A)




SEWERS 48" TO 72" (TYPE Y-B)



LATERAL DROP CONNECTION (TYPE Y-C)



LINE-DROP MANHOLE (TYPE Y-D)



NOTE: PULLING IRON TO BE PLACED IN MANHOLE WALLS OPPOSITE ALL SEWERS OF 18"DIA. & SMALLER & LOCATED 6" ABOVE SEWER CROWN

PULLING IRON
SCALE: 3"=1'-0"

STANDARD MANHOLE DETAILS
SCALE: 1/2"=1'-0"


NOTE:
ALL MANHOLES - CLASS "C" CONCRETE

YOUNGSTOWN MANHOLES & INLET


FED. RD.	STATE	PROJECT	
2	OHIO		

107/492

MAH-18-17.20




SECTION B-B




INLET APPROACH & CURB TRANSITION

SCALE: 1 1/2" = 1 FT.




SECTION A-A



PLAN


CHART "A"	
EXIST. DRIVE TYPE	REPLACEMENT MATERIAL
ASPHALT	3" T-35 ASPHALTIC CONC. SURFACE COURSE - TYPE-A *
CONCRETE	5" T-71 P.C.C. PAVEMENT
SLAG	3" B-19 AGG. BASE COURSE
CINDERS	3" B-19 AGG. BASE COURSE
BRICK	5" T-70

* PLACE IN TWO LAYERS



TYPICAL PLAN OF DRIVEWAY APPROACH

DRIVEWAY APPROACHES INCLUDING REINFORCEMENT MESH AND CINDER BASE SHALL BE INCLUDED UNDER THE CONTRACT UNIT PRICE BID PER SQ.YD. FOR "5" T-71 P.C.C. DRIVEWAY APPROACH"



SECTIONAL ELEVATION
TYPE II - COMBINATION INLET

SCALE: 1" = 1 FT.

NOTES

FRAME & COVER SHALL BE OF CAST IRON IN ACCORDANCE WITH MATERIAL DETAILS FOR STANDARD TYPE I & II 320# INLET CASTING & 50# COVER.

BRICK SHALL BE EIGHT INCHES IN SIZE LAID IN MORTAR AND INTERIOR SURFACE SHALL BE PLASTERED WITH A SMOOTH COATING OF PORTLAND CEMENT MORTAR AT LEAST ONE HALF INCH THICK TO THE HEIGHT SHOWN. THE BRICK SHALL BE LAID IN A FULL BED OF MORTAR WITH NO JOINTS APPEARING ON EITHER SURFACE OF MORE THAN THREE EIGHTHS INCHES IN THICKNESS. JOINTS SHALL BE NEATLY POINTED AND STRUCK ON THE INSIDE OF THE INLET. THE MORTAR SHALL BE COMPOSED OF ONE PART OF PORTLAND CEMENT TO TWO PARTS OF SAND BY VOLUME.


THE TOP OF THE WALLS OF THE STANDARD INLETS SHALL BE PROPERLY LEVELED OFF SO AS TO FORM A FLAT SURFACE UPON WHICH THE INLET CASTING IS TO REST.

THE TOP OF THE CASTING SHALL BE FILLED WITH CLASS "B" CONCRETE AND TROWELLED TO A SMOOTH EVEN FINISH.


WHENEVER THE STREET GRADE IS FOUR PER-CENT OR GREATER THE STORM INLET SHALL BE SET AT SUCH AN ANGLE ALONG THE CURB SO AS TO COLLECT MAXIMUM GUTTER FLOW AS MAY BE SPECIFIED ON THE CONTRACT DRAWINGS.

THE BOTTOM OF THE STORM INLET SHALL BE CONSTRUCTED OF TWO COURSES OF BRICK LAID IN MORTAR. A CONCRETE BOTTOM MAY BE USED IN THE PLACE OF BRICK. THE PAD SHALL BE 9 INCHES IN THICKNESS, CLASS "C" CONCRETE AND LEVELED OFF TO A FLAT SURFACE.

INTEGRAL CURB AND GUTTER SHOWN WILL BE CONSTRUCTED AND PAID FOR AS ITEM I-8, "CATCH BASIN". REINFORCE SLAB WITH #4 BARS @ 4" CENTER TO CENTER, 8 FT. LONG CENTERED ON OPENING.



50# INLET COVER



DETAILS OF INLET FRAME & COVER

SCALE: 1" = 1 FT.

CITY OF YOUNGSTOWN

DRIVEWAY APPROACH & COMBINATION INLET DETAILS


ARTERIAL HIGHWAY SYSTEM

SCALE AS SHOWN | MARCH, 1959

FED. R.D.	STATE	PROJECT	
2	OHIO		


108
492

MAH-18-17.20




PLAN


I-2 CLASS B STORM SEWER
UNDER PAV'T OR APPROACH



KEY JOINT
SCALE: ½" = 1"



SECTION B-B




ELEVATION

QUANTITIES OF CURB WITHIN THE LIMITS OF THE INLET SHALL BE DEDUCTED FROM THE PROJECT QUANTITIES

NOTE:
THE TABLE OF QUANTITIES BELOW IS INCLUDED WITH THIS DRAWING FOR ESTIMATING PURPOSES ONLY. THE COST OF FURNISHING AND PLACING ALL CONCRETE, REINFORCING STEEL, CASTING, ETC. SHALL BE INCLUDED IN ITEM I-8 FOR PAYMENT.

CONCRETE & REINFORCING STEEL QUANTITIES

TYPE INLET	CONCRETE C.Y.	S-5a NO.	S-5a L.F.	S-5b NO.	S-5b L.F.	S-5c NO.	S-5c L.F.	S-6a NO.	S-6a L.F.	S-7a NO.	S-7a L.F.	S-8a NO.	S-8a L.F.	TYPE	H-5a NO.	H-5a L.F.	H-5b NO.	H-5b L.F.	V-5a NO.	V-5a L.F.
2-6		1	4'-0"	7	5'-10"	1	3'-2"	8	7'-0"					#2-6	7	3'-8		5'-8	5	1'-0"
2-8		1	6'-0"	9	5'-10"	1	3'-2"			8	7'-0"			#2-8	7	5'-8"		5'-8"	7	1'-0"
2-10		1	8'-0"	11	5'-10"	1	3'-2"					8	7'-0"	#2-10	7	7'-8"	9	5'-8"	9	1'-0"



SECTION A-A


STANDARD Nº 2-6, 2-8 & 2-10 INLETS - MODIFIED

FED. RD.	STATE	PROJECT	
2	OHIO	:	


109
492

MAH-18-17.20


CONSTRUCTION DETAILS
STA. 966+64.5 TO 968+85.0
67.0' RT. ℄



ELEVATION




PLAN




DETAIL "A-A"


STA. 968+68.85
I-8 Nº 2A-6 INLET (54.0' LT.)
TOP OF CURB 890.36
WINDOW ELEV. 889.67
℄ 18" I-2 884.62




I-10 DUMPED ROCK
BACK SLOPE PROTECTION
SCALE: 1/8" = 1'-0"




CONSTRUCTION DETAILS
STA. 967+78 TO 968+69
56.0' LT. ℄




TOP OF SLOPE CURB
STA. 1012+30 TO STA. 1013+95 (RT.)




PLAN
CONSTRUCTION DETAIL
I-8 2-2A C.B. @ STA. 16+00
RAMP "K"




PLAN



I-14 TYPE 2 MODIFIED
CONCRETE GUTTER FOR
2-2A CATCH BASIN
SCALE: 1/2" = 1'-0"



TOP OF SLOPE DITCH
STA. 1013+95 TO STA.




SECTION A-A

MODIFIED Nº 4 CATCH BASIN


FED. RD.	STATE	PROJECT	
2	OHIO		

110
492


MAH-18-17.20




SECTION - "A" - "A"
SCALE: 1"=1'-0"



SECTION - "B" - "B"
SCALE: 1"=1'-0"



SECTION THRU GRATE
SCALE: 1½"=1'-0"



PLAN OF MEDIAN GRADING AT CATCH BASIN
SCALE: NONE

NOTES:

BRICK OR CONCRETE BLOCK MAY BE USED IN WALL CONSTRUCTION BETWEEN THE CONCRETE BASE AND THE PERMISSIBLE CONSTRUCTION JOINT.

THE WALL THICKNESS SHALL BE 8" WHERE BRICK OR CONCRETE BLOCK IS USED.

CONCRETE TO BE CLASS "C"

GRATING AND FRAME SHALL BE OF STRUCTURAL STEEL IN ACCORDANCE WITH CONSTRUCTION AND MATERIALS SPECIFICATION SEC. M-7.4(a). WELDING SHALL BE CLASS "A". THE DESIGN SHALL BE ESSENTIALLY THE SAME AND EQUALLY AS STRONG AS THE ONE SHOWN HEREON AND SHALL BE GIVEN ONE COAT OF ASPHALTUM PAINT AS PER SPECIFICATIONS.

MINIMUM WEIGHT OF GRATES - 361 POUNDS.


MINIMUM WEIGHT OF FRAME - 69 POUNDS.

GRATE SHALL BE DEPRESSED 3" BELOW FLOW LINE OF DITCH AT THE UPSTREAM EDGE.


PAVED GUTTER: - THE COST OF PAVED GUTTER AND DOWNSTREAM DIKE TO BE INCLUDED IN THE UNIT PRICE BID FOR CATCH BASIN.

SEEDING AND SOD: - IN ADDITION TO THE SEEDING INDICATED IN THE PLANS, THE AREA 8' EACH WAY FROM THE DITCH CENTERLINE AND 200' UPSTREAM FROM THE CATCH BASIN, SHALL BE OVERSEEDED IN ACCORDANCE WITH THE FOLLOWING. - FROM JANUARY 1 TO JULY 1, FIVE POUNDS OF OATS (AVENA SATIUA) PER THOUSAND SQUARE FEET, - FROM JULY 1 TO JANUARY 1, TWO POUNDS OF NORTHERN RYE (LOLIUM MULTIFLORUM) PER ONE THOUSAND SQUARE FEET. A ROTARY TYPE OF MIXER SHALL NOT BE USED AND NO MULCHING WILL BE PERMITTED IN THIS AREA.


THE COST OF OVERSEEDING AS DESCRIBED ABOVE SHALL BE INCLUDED IN THE PRICE BID PER SQUARE YARD OF SEEDING. THE SOD AS INDICATED ON THIS DETAIL SHALL BE INCLUDED IN THE ROADWAY QUANTITIES AND SHALL NOT BE INCLUDED IN THE COST OF THIS CATCH BASIN.




PLAN OF CATCH BASIN
SCALE: 1"=1'-0"



UPSTREAM END VIEW OF CONC. GUTTER
SCALE: NONE





CONSTRUCTION DETAILS
INLET STA. 924+90


DRAINAGE DETAILS

OK
WKD


FED. RD.	STATE	PROJECT	
2	OHIO		

111
492

MAH-18-17.20



ONE LANE EXIT DETAIL - USE WHERE ONE LANE EXIT RAMP LEAVES AN EXPRESSWAY FROM A DECELERATION LANE, EXPRESSWAY IS NOT REDUCED IN NUMBER OF LANES.



ONE LANE ENTRANCE RAMP


ONE LANE ENTRANCE DETAIL - USE WHERE
1. ONE LANE ENTERING JOINS AN EXPRESSWAY ON AN ACCELERATION LANE.
2. ONE LANE ENTERING JOINS AN EXPRESSWAY ON AN ADDITIONAL LANE.

DETAILS OF ENTRANCE & EXIT TERMINALS

NOTES:


TRANSITION PAVED BEERM FROM 10' TO 8' IN LENGTH FOR PAVEMENT TRANSITION.

0.0312 FT./FT. MAXIMUM CHANGE IN RATE OF PAVEMENT CROSS SLOPE.



½" PREMOULDED JOINT MATERIAL WHERE CURB IS ADJACENT TO CONCRETE PAVEMENT.

SPECIAL PORTLAND CEMENT CONCRETE CURB DETAILS




TYPICAL ACCELERATION & DECELERATION LANES

RAMP "C" STA. 6+56


FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

112
492



PC-4 MODIFIED ENDWALL
SCALE 1"=3'-0"



NOTES:
FOR KEY PLAN AND CHANNEL RELOCATION SEE SHEET Nº 114
FOR CROSS SECTIONS SEE SHEET Nº 113

PLAN
SCALE: 1"=20'-0"

CULVERT DATA (d)

TYPE: STANDARD PIPE CULVERT M.G.(c)
SIZE: 18" x 410'-0"
SKEW: 57°00' LT. FWD.
WORK REQ'D.: BUILD NEW 18" x 410' STD. PIPE


M.G.(c) (d) HW_{50} = 3.75 V_h = 13.8
AREA = 5.2 ACRES
Q_{50} = 17.0 C.F.S.

ESTIMATED QUANTITIES

E-2	EXCAVATION FOR STRUCTURES	123.82 CU. YDS.
E-3	CHANNEL EXCAVATION	10.20 CU. YDS.
I-10	DUMPED ROCK CHANNEL PROTECTION	12.00 CU. YDS.
S-1	CONCRETE FOR STRUCTURES CLASS "E"	1.02 CU. YDS.
S-27	18" PIPE FOR ROADWAY STRUCTURES	408 L.F.

PLAN
SURVEYED
PLOTTED
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
C.S. & ALIGNMENT CHECKED
STRUCTURE NOTATIONS CHKD.




Rev 11-23-60

CULVERT DETAIL RAMP "C" STA. 6+56


PLATE 1 — PLAN-PROFILE O. P. R. & R. S. STANDARD
251 FAR-3 ACEPROOF FILM MADE AND PRINTED IN U.S.A.
GREENE BLUEPRINT CO., CHICAGO

FED. RD.	STATE	PROJECT		113 / 432
2	OHIO			


MAH-18-17.20




2+00
864.79




1+50
862.71




1+00
860.64




0+50
858.56



0+48.50
858.50




0+03.30
855.93




0+01.50
855.83


866
864
864
862
862
860
860
858
860
858
858
856
856




4+58.50
875.50
ZERO SECTION FRONT OF HEADWALL.




4+50
875.16




4+00
873.09



3+50
871.01



3+00
868.94



2+50
866.86

876
874
876
874
874
872
872
870
870
868
868
866

STA.	END AREA		CU. YDS.	
	E-2	E-3	E-2	E-3
0+01.50	0	0	0	0
0+03.30	0	3.46	0	0.12
0+48.50	6.36	8.60	0	10.08
0+50	6.40	0	0.35	0
1+00	10.66	0	15.80	0
1+50	4.53	0	14.05	0
2+00	8.91	0	12.45	0
2+50	12.78	0	20.10	0
3+00	11.68	0	22.70	0
3+50	5.84	0	16.20	0
4+00	5.26	0	10.30	0
4+50	8.61	0	12.85	0
4+58.50	9.34	0	2.82	0
HW.EXC.			2.20	
TOTAL			120.82	10.20

CHANNEL
CROSS SECTIONS
RAMP "C" STA. 6+56
SCALE: 1" = 2'-0"


12 8 4 0 4 8 12 12 8 4 0 4 8 12

RAMP C STA. 10+50


FED. RD.	STATE	PROJECT	
2	OHIO		

114
492

MAH-18-17.20



KEY PLAN
SCALE- 1"=100'



PLAN
SCALE 1"=10'

SEE SHEET Nº 68 FOR PLAN OF CHANNEL RELOCATION

CULVERT DATA


TYPE : STANDARD PIPE CULVERT MG.4(d), MG.G(C)
SIZE : 24"x152'-0"
SKEW : NONE
WORK REQ'D. : BUILD NEW 24"x 152' STANDARD PIPE CULVERT AS SHOWN.
MG.4(d) HW_{50} = 3.5 V_h = 10.3
MG.G(C) HW_{50} = 3.0 V_h = 14.3
AREA = 7.7 ACRES
Q50 = 23.0 C.F.S.

ESTIMATED QUANTITIES

E-2 EXCAVATION FOR STRUCTURES	51.47 CU.YDS.
E-3 CHANNEL EXCAVATION	52.16 CU.YDS.
I-10 DUMPED ROCK CHANNEL PROTECTION	40 CU.YDS.
S-1 CONCRETE FOR STRUCTURES CLASS "E"	0.82 CU. YDS.
S-27 24" DIPE FOR ROADWAY CULVERTS	152 L.F.

PLAN | SURVEYED | BY | DATE
PLOTTED
ALIGNMENT CHECKED
ALL OF WAY CHECKED
NOTE BOOK
NO.

PROFILE | SURVEYED | BY | DATE
PLOTTED
CROSS SECTIONS CHECKED
R. & L. NOTED
STRUCTURE NOTATIONS CHKD
NOTE BOOK
NO.





PROFILE OF CHANNEL RELOCATION


SCALE 1"= 10'-0"


PLATE 1—PLAN-PROFILE O. P. R. & R. E. STANDARD
261 FM-3 ACEPROOF FILM MADE AND PRINTED IN U. S. A.
EUGENE DIETZGEN CO., CHICAGO


CULVERT DETAIL RAMP "C" STA. 10+50
















858
856
856
854
854
852
854
852
852
850
852
850


STA.	END AREA		CU. YDS.	
	E-2	E-3	E-2	E-3
0+02	0	0	0	0
0+03	0	2.24	0	0.04
0+50	0	7.20	0	8.23
1+00	0	3.80	0	10.20
1+50	0	3.29	0	6.55
2+00	0	3.83	0	6.55
2+50	0	7.82	0	10.80
2+86	5.98	3.97	0	5.17
3+00	8.21	0	6.57	0
3+50	9.06	0	12.00	0
4+00	6.67	0	23.80	0
4+38	7.52	8.83	7.10	4.40
4+39.34	0	0	0	0.22
HW.EXC.			2.00	
TOTAL			51.47	52.16


CHANNEL
CROSS SECTIONS
RAMP "C" STA. 10+50
SCALE 1" = 2'-0"





MAH-18-17.20














870
868
868
866
866
864
864
862
864
862
862
860


12 8 4 ℄ 4 8 12 12 8 4 ℄ 4 8 12

FED.RD.	STATE	PROJECT	
2	OHIO		

116
492

MAH-18-17.20

STA. 18+40 RAMP "D"



SYMBOLS

- (B-5) TYPE Y-A MANHOLE MODIFIED SEE SHEET Nº &
- (B-6) TYPE Y-A MANHOLE SEE SHEET Nº
- (B-7) TYPE Y-A MANHOLE SEE SHEET Nº
- (D-10) (D-11) (D-12) (D-13) (D-14) TYPE 2 INLETS SEE SHEET Nº

SCALE: 1"=10'

CULVERT DATA

TYPE: REINFORCED CONCRETE BOX CULVERT
SIZE: 6'x4' x 77'
WORK REQUIRED: BUILD NEW 6'x4'x77' REINFORCED CONCRETE BOX CULVERT WITH WINGWALLS AND Y-A MODIFIED YOUNGSTOWN MANHOLE AS SHOWN.

ESTIMATED QUANTITIES

E-3	CHANNEL EXCAVATION	400 CU.YDS.
S-1	CONCRETE FOR STRUCTURES CLASS "C"	60.70 CU.YDS.
S-4	REINFORCING STEEL	7,420 LBS.
E-2	EXCAVATION FOR STRUCTURES	40 CU.YDS.

SEE SHEET Nº 118 FOR CHANNEL CROSS SECTIONS.
SEE SHEET Nº 117 FOR CONSTRUCTION DETAILS OF BOX CULVERT AND MODIFIED MANHOLE.

PLAN — SURVEYED, PLOTTED, NOTE BOOK, NO., BY, DATE, A.I. CHECKED, RT. OF WAY CHECKED

PROFILE — SURVEYED, PLOTTED, NOTE BOOK, NO., BY, DATE, GRADES CHECKED, S.I. & S. LISTED, STRUCTURE NOTATIONS CHKD.




PLATE 1 — PLAN-PROFILE O. P. R. & R. E. STANDARD
2GI FM-3 AGEPROOF FILM MADE AND PRINTED IN U. S. A.
EUGENE DIETZGEN CO., CHICAGO

BOX CULVERT STA. 18+40 RAMP "D"

FED. RD.	STATE	PROJECT	
2	OHIO		

117
492

MAH-18-17.20

REINFORCING BAR SCHEDULE

MARK	NO. REQD.	LENGTH	WEIGHT	SHP. OR RAD.	MARK	NO. REQD.	LENGTH	WEIGHT	SHP. OR RAD.
401	91	11'-7"	704	BT.	509	5	23'-1"	120	75°-0"
402	172	7'-6"	862	ST.	510	5	22'-6"	117	73°-6"
403	92	2'-5"	149	BT.	511	12	22'-1"	276	71°-9"
404	168	5'-11"	664	BT.	512	242	7'-6"	1893	ST.
405	86	4'-0"	230	ST.	513	1	5'-1"	5	76°-6"
406	6	5'-6"	22	ST.	514	1	14'-10"	15	76°-6"
407	6	4'-4"	17	ST.	515	1	3'-9"	4	75°-0"
408	2	3'-2"	4	ST.	516	1	14'-5"	15	75°-0"
409	15	1'-8"	14	BT.	517	1	4'-4"	5	73°-6"
410	2	16'-3"	22	BT.	518	1	14'-7"	15	73°-6"
411	8	1'-10"	10	ST.	519	1	4'-1"	4	75°-9"
412	7	3'-6"	16	BT.	520	1	14'-8"	15	75°-9"
413	10	6'-6"	43	ST.	521	1	3'-9"	4	74°-3"
414	3	12'-6"	25	ST.	522	1	14'-5"	15	74°-3"
415	4	3'-11"	10	BT.	523	8	4'-10"	40	BT.
416	4	3'-5"	9	BT.	524	16	3'-10"	64	BT.
417	8	2'-8"	14	BT.	525	8	4'-0"	33	BT.
418	4	5'-3"	14	ST.	526	16	3'-0"	50	BT.
419	2	4'-1"	5	ST.	527	19	8'-4"	165	ST.
420	2	2'-11"	4	ST.					
					701	3	9'-2"	56	BT
					702	3	12'-6"	77	ST
501	12	24'-2"	302	78°-9"	703	4	7'-8"	63	ST,
502	6	23'-9"	149	77°-3"					
503	5	23'-4"	122	75°-9"	TOTAL WEIGHT = 7420 LBS.				
504	5	22'-11"	120	74°-3"	REPLACEMENT BARS				
505	6	22'-5"	140	72°-9"					
506	12	21'-11"	274	71°-3"	RE 401	1	5'-3"		ST.
507	12	24'-1"	301	78°-3"	RE 501	1	5'-6"		ST.
508	5	23'-7"	123	76°-6"	RE701	1	6'-3"		ST.

IF THE BARS ARE FABRICATED FROM STOCK THAT HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SEC. S-402 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.

ESTIMATED QUANTITIES

ITEM	UNIT	DESCRIPTION	QUAN.
E-2	CU. YDS.	UNCLASSIFIED EXCAVATION	40
S-1	CU. YDS.	CLASS "C" CONCRETE	60.7
S-14	LBS.	REINFORCING STEEL	7420

NOTES

SEE SHEET FOR LOCATION AND QUANTITIES.

SEE SHEET 99 FOR DETAILS OF YOUNGSTOWN MANHOLE TYPE "A" MOD.

DESIGN SPECIFICATIONS THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF "DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES" OF THE STATE OF OHIO, DEPARTMENT OF HIGHWAYS, DATED 9-1-57 TOGETHER WITH CURRENT REVISIONS THEREOF.

CONTRACTION JOINTS SHALL EXTEND ENTIRELY AROUND CULVERT BARREL AND SHALL BE PROVIDED WITH KEYS AS SHOWN.

FOUNDATION MATERIAL OF APPROXIMATELY UNIFORM BEARING CAPACITY IS CONTEMPLATED. SPOTS OF SOFT EARTH SHALL BE REMOVED AND BE REPLACED WITH THOROUGHLY COMPACTED GRANULAR FILL.

EMBANKMENT SHALL BE PLACED SYMMETRICALLY ON BOTH SIDES OF THE CULVERT AFTER THE TOP SLAB IS IN PLACE. EMBANKMENT OVER THE BARREL SHALL BE PLACED IN HORIZONTAL LAYERS SIMULTANEOUSLY WITH THAT ON EACH SIDE OF CULVERT.


CONCRETE SHALL BE CLASS "C"


STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES


BEISWENGER & HOCH, Consulting Engineers
AKRON, OHIO

6'X4' BOX CULVERT
UNDER RAMP "D"
STA. 18+40
YOUNGSTOWN MAHONING COUNTY


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	R.D.H.		DHC	DHC		









FOR DETAILS NOT SHOWN IN SECTIONS B-B, C-C, D-D SEE BELOW









FED. RD.	STATE	PROJECT	
2	OHIO		

118
492


MAH-18-17.20







STA.	END AREA			CU.YDS.	
	E-2	E-3 (2:1)	E-3 (1:1)	E-2	E-3
0+00	11	0	93		
				20	196
0+50	11	0	120		
				20	111
0+77	11	161	102		
				0	92
1+00	0	55	0		
				0	1
1+50	0	3	0		

BOX CULVERT STA.18+40 RAMP "D"







BOX CULVERT STA. 18+40 RAMP "D"


STRUCTURE Nº MAH-18-1810

STA. 955 + 50

FED. RD.	STATE	PROJECT	
2	OHIO		

120
492

MAH - 18 - 17.20



FOR CROSS SECTIONS
SEE SHEET Nº 121


PLAN
SCALE : 1" = 10'

CULVERT DATA

TYPE : STANDARD PIPE CULVERT MG.6(d) MG.4(d) GAGE 14.
SIZE : 24" x 247'-0"
SKEW : NONE
WORK REQ'D : BUILD NEW 24" x 247' STANDARD PIPE CULVERT AS SHOWN.
MG.4(d) HW50
MG.6(d) HW50
AREA = 8.8 SQ
Q_{50} = 29 C.F.S.

ESTIMATED QUANTITIES

E-2	EXCAVATION FOR STRUCTURES	67.37 CU.YDS.
S-1	CONCRETE FOR STRUCTURES CLASS "E"	0.82 CU.YDS.
S-27	24" PIPE FOR ROADWAY CULVERTS	247 L.F.
I-10	DUMPED ROCK CHANNEL PROTECTION	35 C.Y.



CULVERT DETAIL STA. 955 + 50


PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
ALL QUANTITIES CHECKED
NOTE BOOK
NO.
BY
DATE


PROFILE
SURVEYED
PLOTTED
ALIGNMENT CHECKED
G. L. A. NOTED
NOTE BOOK
NO.
STRUCTURE NOTATIONS CHKD


PLATE 1 — PLAN-PROFILE U. P. R. A. & B. E. STANDARD
RECORD ACETATE FILM BASE AND PRINTED IN U. S. A.
EUGENE DIETZGEN CO., CHICAGO


FED. RD.	STATE	PROJECT		12.1 / 492
2	OHIO			


MAH -18-17.20















STA.	END AREA	CU. YDS.
	E-2	E-2
0+19	2.52	0
0+27	12.61	2.24
0+50	8.30	8.90
1+00	9.08	16.05
1+50	7.00	15.75
2+00	5.60	11.65
2+43	8.05	10.88
HW. EXC.		1.0
TOTAL		67.37

CULVERT
CROSS SECTIONS
STA. 955+50
SCALE 1"=2'-0"




12 8 4 ℄ 4 8 12 8 4 ℄ 4 8


	STATE	PROJECT	
	OHIO		

122
492

MAH-18-17.20







140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

921+00 TO 922+00

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
2	OHIO		

123
492

MAH.-18-17.20

END AREA	CUBIC YARDS

104

SEE RAMP "B" X-SECTIONS

℄ SILLIMAN ST.

933.84 | 934.26 | 934.26 | 934.68 | 934.68

2:1 | 8:1 | 8:1 | 4:1 | 2:1

929.09 | 933.13 | 934.87

924+00
952.00

C-3053
F-0

940

C-5620
F-0

℄ SILLIMAN ST.

℄ LAKEVIEW AVE

120

SEE RAMP "B" X-SECTIONS

933.22 | 935.64 | 935.64 | 936.06 | 936.06

2:1 | 8:1 | 8:1 | 4:1 | 2:1

930.47 | 934.45 | 936.25

923+50
952.06

C-3017
F-0

940

C-5520
F-0

℄ LAKEVIEW AVE

℄ SILLIMAN ST.

124

SEE RAMP "B" X-SECTIONS

934.51 | 934.93 | 934.93 | 937.35 | 939.35

2:1 | 8:1 | 8:1 | 4:1 | 2:1

931.76 | 935.68 | 937.54

923+00
953.25

C-2945
F-0

940

C-5322
F-0

℄ LAKEVIEW AVE.

℄ SILLIMAN ST

139

SEE RAMP "B" X-SECTIONS

935.69 | 938.11 | 938.11 | 938.53 | 940.53

2:1 | 8:1 | 8:1 | 4:1 | 2:1

932.94 | 936.80 | 938.72

922+50
953.45

C-2803
F-0

940

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

922+50 TO 924+00

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
2	OHIO		

124 / 492

MAH.-18-17.20

END AREA	CUBIC YARDS

112

217

128

2:1

920.61

923.02 | 924.58 | 925.30 | 926.18 | 927.13 | 928.12 | 928.54 | 928.54 | 928.96 | 929.95 | 930.95

RAMP "B"
8+46

926+00
947.3

4:1

928.1

2:1

937.28 | 936.77

RAMP "A"
5+22

934.77

2:1

C-5208
F-0

930

350

D

2:1

D

C-10305
F-0

245

145

2:1

921.31

923.73 | 925.22

RAMP "B"
8+92

925+50
950.0

926.72 | 927.55 | 928.55 | 929.55 | 929.97 | 930.39 | 932.39

4:1

930.58

Varies

940.44 | 939.82

RAMP "A"
4+73

937.82

2:1

D

C-5521
F-0

930

+278
+171

104

2:1

922.44

924.85 | 926.07

RAMP "B"
9+37

C.B.
INLET 924.24

924.3

Varies

4:1

925+00
950.04

928.98 | 931.40 | 931.40 | 931.82 | 932.82

4:1

932.01

2:1

Y.E. 925+00
CUT-5259

RAMP "A" 4+20
CUT-745

2:1

943.91 | 943.25

RAMP "A"
4+20

941.25

C-11402
F-0

C

940

C

2:1

940

C-745
C-5259
F-0

+202
+95

RAMP "B" 9+78
CUT-2210

Y.E. 924+50
CUT 2937

2:1

923.82

926.23 | 927.45

RAMP "B"
9+78

926.12

2:1

2:1

927.66

924+50
950.35

930.41 | 932.83 | 932.83 | 933.25 | 935.25

8:1

8:1

931.77

933.44

2:1

C-5635
F-0

C-2210
C-2937
F-0

930

C-5990
F-0

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

924+50 TO 926+00

SEEDING	
END WIDTH	SQ YDS
86	


FED. RD.	STATE	PROJECT	
2	OHIO		

125
492

MAH.-18-17.20

END AREA	CUBIC YARDS

NOTE:
STA. 928+00
END 12" I-22



SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
2	OHIO		

126
492

MAH.-18-17.20

END AREA	CUBIC YARDS

82

141

924.50

2:1

914.59

44.00'

916.72 916.91 917.10 917.10 917.10 917.13 917.50 917.49 917.25

47.49

917.25

Varies

928.25

C-3872
F-0

915.25

81

910.50

912.50

930+00
937.0

910.25

910

C-5848
F-0

NOTE:
S.T. STA. 929+99.42
END MEDIAN TRANSITION

152

44.20'

2:1

917.88 918.07 918.24 918.45 918.53 918.61 918.47 918.61 918.62 918.63

49.95'

2:1

C-3444
F-0

917.83

916.91

86

929+50
938.0

910

C-653
F-0

157

45.05'

2:1

918.91 919.12 919.55 919.86 919.96 919.96 920.17 920.51 920.86 920.96

52.86'

2:1

C-3610
F-0

920

87

918.83

929+00
939.7

918.56

C-6931
F-0

156

46.70'

2:1

919.82 920.32 920.76 921.21 921.36 921.60 922.54 922.42 922.10

2:1

C-3876
F-0

C-7272
F-0

920

919.82

928+50
941.5

RAMP "A"
7+78

920.19

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

928+5 TO 930+00

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT		127 492
2	OHIO			

MAH.-18-17.20

END AREA	CUBIC YARDS

88

158

89

NORMAL

44.00'

911.40 | 911.59 | 911.78 | 911.59 | 911.38 | 911.38 | 911.59 | 911.78 | 911.59 | 911.40

909.27

932+00
929.4

909.27

2:1

NOTE: STA. 932+00 BEGIN 12" I-22

C-4319 ↓
C-4269 ↓
F-0

910

C-8095
F-0

161

88

44.22'

912.81 | 913.00 | 913.19 | 913.00 | 912.81 | 912.81 | 913.02 | 913.21 | 913.02 | 912.83

910.68

931+50
934.5

910.77

2:1

C-4474
F-0

910

C-8065
F-0

157

87

44.87'

NORMAL

914.11 | 914.30 | 914.49 | 914.31 | 914.24 | 914.24 | 914.45 | 914.64 | 914.45 | 914.24

911.98

931+00
935.0

912.24

2:1

NOTE:
STA. 931+00 TO 932+00 (RT.)
TRANSITION TOTAL WIDTH
OF SHOULDER FROM 12' TO 15'

C-4236
F-0

C-7644
F-0

910

155

45.96'

915.42 | 915.61 | 915.80 | 915.71 | 915.67 | 915.67 | 915.88 | 916.07 | 915.94 | 915.72

913.29

930+50
936.5

913.72

2:1

C-4020
F-0

C-7307
F-0

910

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

930+50 TO 932+00


SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
2	OHIO	-	

128/492

MAH.-18-17.20

END AREA	CUBIC YARDS




SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT		129 492
2	OHIO			

MAH.-18-17.20

END AREA	CUBIC YARDS



SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
2	OHIO		

130
492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — NOTE BOOK — PAGE NO. — DATE CHECKED

ORIGINAL SURVEY — NOTE BOOK — PAGE NO. — DATE CHECKED

89
161
89

2:1

894.92 | 894.80 | 894.66 | 894.45 | 894.22 | 894.22 | 893.74 | 893.54

4.70

892.91

892.00

891.41

2:1

938+00
926.00

C-5898
F-0

890

C-10781
F-0

148
81

NOTE:
STA. 937+46.56
BEGIN FUTURE RAMP A3

2:1

896.07 | 896.07 | 896.05 | 895.86 | 895.65 | 895.65 | 895.65 | 895.63 | 895.44 | 895.25

6.41

894.05

892.90

893.12

2:1

937+50
927.25

C-5745
F-0

900

C-10453
F-0

145

2:1

C-5544
F-0

NOTE:
STA. 936+72.31
BEGIN SUPERELEVATION (LT.)

80

897.24 | 897.36 | 897.48 | 897.29 | 897.08 | 897.08 | 897.12 | 897.20 | 897.01 | 896.82

8.13

895.11

894.69

2:1

900

937+00
927.85

C-9893
F-0

142

2:1

898.53 | 898.72 | 898.91 | 898.72 | 898.51 | 898.51 | 898.58 | 898.76 | 898.57 | 898.38

2.64

896.40

896.25

2:1

C-5140
F-0

900

936+50
925.65

C-9041
F-0

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 2 CROSS SECTIONS OF P.R.R.R. STANDARD
KEUFFEL & ESSER CO., NEW YORK

936+50 TO 938+00

SEEDING	
END WIDTH	SQ YDS
64	

131
492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOK / SHEET / NO. / L.A.S. INITIALS

ORIGINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOK / SHEET / NO. / L.A.S. INITIALS

159

940+00
913.4

2:1

890.40 890.18 889.48 888.79 888.50 888.21 886.90 886.24

888.41

883.91

2:1

C-5279
F-0

890

87

NOTE:
S.T. STA. 10+07.16 RAMP A₂
TO STA. 9+07.16 TRANSITION
SHOULDER 15' TO 11'

C-10009
F-0

155

939+50
918.6

2:1

891.49 891.36 890.77 890.18 889.93 889.23 889.71 888.61 888.06

889.49

885.75

2:1

C-5531
F-0

890

87

C-10879
F-0

157

939+00
926.0

2:1

892.63 892.54 892.05 891.57 891.36 891.18 890.32 889.88

890.63

887.76

4:1

C-6218
F-0

900

88

C-11407
F-0

159

938+50
928.0

2:1

892.77 893.71 893.35 893.00 892.79 892.79 892.66 892.05 891.72

891.76

889.59

4:1

C-6102
F-0

C-11102
F-0

890

140 120 100 80 60 40 20 ℄ 20 40 80 100 120 140

PLATE 3 - CROSS SECTIONS OF P.R.I.E.P.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

938+50 TO 940+00

SEEDING	
END WIDTH	SQ YDS
37	

FED. RD	STATE	PROJECT	
2	OHIO		

132
492

MAH.-18-17.20

END AREA	CUBIC YARDS

75

886.10

RAMP "A3"
7+21

890.17 890.86 VARIES 4:1 882.20 884.01 883.01 882.01 881.59 881.17 879.17 878.18 2:1 875.71

942+50
884.8

C-1537
F-1392

880

44

C-4428
F-1207

83

885.14 889.73 VARIES 4:1 885.28 884.28 883.28 882.86 882.84 882.44 880.44 879.46 2:1

886.49

RAMP "A3"
7+67

883.47

942+00
897.2

876.04

C-3075
F-0

880

C-6584
F-0

45

80

886.64 888.90 884.43 885.63 884.43 884.21 884.21 882.79 882.79 881.85 880.85 2:1

886.64

RAMP "A3"
8+18

886.3

941+50
904.3

878.11

C-3967
F-0

NOTE: STA. 941+46.56 TO 942+46.56
TRANSITION TOTAL WIDTH
OF SHOULDER 15' TO 11'

C-7972
F-0

880

43

C-4643
F-0

76

888.68 888.74 887.83 886.93 886.02 885.64 885.64 885.27 883.48 882.59 2:1

886.72

RAMP "A3"
8+69

941+00
908.0

879.98

890

41

C-8320
F-0

70

2:1 889.37 889.29 889.00 888.20 887.40 887.07 887.07 886.75 885.19 884.41 2:1

887.59

RAMP "A3"
9+20

940+50
908.0

881.93

C-4343
F-0

890

C-8309
F-0

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

940+50 TO 942+50

PLATE B CROSS SECTION A.R.E.A. & A.A.S.H.T.O. STANDARDS
REVISED 1938 PUBLIC SQ., NEW YORK.

F.A.I. COUNTY ROUTE SECTION

ORIGINAL SURVEY NOTE DATUM

SEEDING	
END WIDTH	SQ YDS
99	
57	
106	
60	
109	
47	
61	
33	
59	

		PROJECT	
2	GRID		

133
492

MAH.-18-17.20

END AREA	CUBIC YARDS

MAHONING-W. FEDERAL STA. 1900

2:1 BRIDGE SLOPES

877.31

879.12 876.70 874.28 872.23

NOTE: STA. 945+00 TO 945+50 TAPER SUBBASE

2:1

945+00
850.0

851.00

C-15
F-3392

C-27
F-7153

850

MAHONING-W. FEDERAL STA. 1700

2:1 BRIDGE SLOPES

4:1

878.10

879.91 877.49 875.07 873.34

2:1

C-14
F-3733

944+50
856.0

C-13
F-6715

850

MAHONING-W. FEDERAL STA. 1400

2:1 BRIDGE SLOPES

4:1

878.98

880.79 878.37 875.95 874.43

2:1 BRIDGE SLOPES

872.01

C-0
C-12
F-3519
F-3100

F-3394
C-12

4:1

885.60

C-26
F-9905

944+00
858.2

870

850

"A"

893.06 893.78

RAMP "A3"
STA. 6+40

"A"

VARIES

4:1

879.96

881.77 879.35 876.93 875.60

2:1 Bridge Slopes

873.18

C-16
F-4290

870

943+50
860.0

C-429
F-5744

891.66 897.38

RAMP "A3"
STA. 6+76

4:1

885.90

VARIES

4:1

881.04

882.85 881.85 880.85 880.48 880.43 878.01 876.84

2:1

874.42

NOTE:
STA. 943+00
END 12"I-22

C-347
F-2275
C-352
F-2232

870

943+00
873.5

C-1843
F-3135

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

943+00 TO 945+00

SEEDING	
END WIDTH	SQ YDS

	END AREA	CUBIC YARDS
MAH-18-17.20		

134
492

41

73

876.92

874.50

872.08

869.58

867.92

4:1

4:1

4:1

10:1

2:1

8G2.29

℄ RAMP B3 DITCH

947+00
901.3

865.58

RAMP "C3"
5+10

864.0

C-4132

C-4517
F-186

880

41

76

877.83

874.91

872.49

870.23

868.07

4:1

4:1

2:1

10:1

8G2.22

℄ RAMP B3 DITCH

946+50
878.0

RAMP "C3"
4+70

862.0

C-1178
F-201

C-1467
F-1847

870

44

83

877.85

875.41

872.99

871.45

869.79

3:1

3:1

2:1

858.99

℄ RAMP B3 DITCH

946+00
862.0

RAMP "C3"
4+27

860.0

C-406
F-1794

C-390
F-4792

860

49

95

878.43

876.01

873.59

870.95

2:1

2:1

VARIES
BRIDGE SLOPE

858.43

945+50
853.3

855.29

C-15
F-3381

C-28
F-6827

860

54

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 5 CROSS SECTIONS C.P.R.R.R.E. STANDARD
ATLANTIC & GREAT WEST, NEW YORK.

945+50 TO 947+00

SEEDING	
END WIDTH	SQ YDS

MAH.-18-17.20	END AREA	CUBIC YARDS

135
492

4G

846.3

8:1

"C" 850

SEE RAMP "D" X SECTIONS

200 180 160

8G

879.13 879.38

RAMP "B3" 6+48

867.60

2:1

875.72 874.94 874.17 873.85 872.04

4:1

868.52

2:1

12:1

SEE RAMP "C3" LOOP X-SECTIONS

C-3532
F-2697

870

948+50
884.1

C-6315
F-5596

"C"

"B" 860

4G

845.76

2:1 10:1 2:1

SEE RAMP "D" X-SECTIONS

261.77 240 220 200 180

SEE RAMP "C" LOOP X-SECTIONS

C-3288
F-3347

8G

RAMP "B3" 7+00

2:1 2:1 2:1

8640

876.09 875.22 874.34 873.97 871.88

2:1

868.77

C-5988
F-6627

870

948+00
888.1

"B"

"A"

C-3179 ↓↑
C-2595↓
F-166 ↓↑
F-3644 ↑

4G

SEE RAMP "D" X-SECTIONS

846.74

2:1 16:1

884.54 270 864.73 260 240 220 160

SEE RAMP "C3" LOOP X-SECTION

RAMP "C3" STA. 5+50

7G

RAMP "B3" 7+53

2:1

F-3644 ↔ C-3179 F-166

876.54 874.19 871.89

2:1

868.62

870

C-3172
F-154

"A"

863.80

947+50
894.8

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

947+50 TO 948+50

SEEDING	
END WIDTH	SQ YDS

136
492

MAH.-18-17.20	END AREA	CUBIC YARDS

37

66

40

77

44

81

A

See Ramp "C" X-Sections

C-4622
F-1504

880

C-8929
F-3128

12:1

2:1

869.37

874.80 875.10 874.95 875.24 875.14 874.71 874.26 874.05 873.07

Ramp B3
4+96

874.00

4:1

950+00
896.7

8.95

See Ramp "D" X-Sections

875.56 875.45 874.68 874.12 873.88 872.63

Ramp "B3"
5+45

873.2

869.22

C-5021
F-1920

880

949+50
895.9

C-9683
F-3559

8.75

See Ramp "D" X-Sections

877.06 877.31 876.44 874.77 874.10 873.82 872.25

Ramp "B3"
5+96

871.40

869.07

C-5437
F-1970

880

949+00
898.0

C-8305
F-4300

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

949+00 TO 950+00

ORIGINAL SURVEY
FINAL SURVEY
NOTE BOOK
NO.
PLOTTED
CHECKED
AREAS
TOTALS CHECKED

FED. RD.	STATE	PROJECT		137 / 492
2	OHIO			

SEEDING.	
END WIDTH	SQ YDS
36	
71	
46	
95	
45	
68	

END AREA	CUBIC YARDS

MAH-18-17.20

SEE RAMP "C" X-SECTIONS

C-2441
F-914

880

875.05 875.48 875.40 875.31 875.10 875.11 875.12 874.93

863.6

2:1

RAMP "B3"

871.54

C-4984
F-1791

SEE RAMP "D" X-SECTIONS

951+50
890.8

SEE RAMP "C" X-SECTIONS

C-2942
F-1020

880

874.74 875.26 875.06 874.86 874.65 874.58 874.42 874.23

C-6363
F-2029

RAMP "B3"

869.91

855.5

SEE RAMP "D" X-SECTIONS

951+00
887.4

NOTE:
STA. 950+00 TO 951+00
TAPER SUBBASE

SEE RAMP "C" X-SECTIONS

C-3930
F-1194

880

874.53 874.85 874.98 875.17 875.16 874.83 874.51 874.30 875.00

RAMP "B3"
4+45.5

2:1

4:1

869.52

C-7919
F-2456

854.5

SEE RAMP "D" X-SECTIONS

950+50
893.0

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

950+50 TO 951+50

FINAL SURVEY FILED NOTE BOOK PAGE NO.

ORIGINAL SURVEY FILED NOTE BOOK PAGE NO. TEXAS CITIES

SEEDING	
END WIDTH	SQ YDS

		PROJECT	138 492

MAH-18-17.20

END AREA	CUBIC YARDS

141

106± EDGE WATER
EL 829.4 ±

C

170 160

875.49 876.29 876.48 876.72 876.91 876.72 876.51 876.72 876.91 876.72 876.34 875.42

4251
4103

49' ± TOP BANK
EL. 850±

RAMP "D"
7+26

875.24

RAMP "B3"

953+00
880.0

RAMP "C"
17+89

86B31

SEE RAMP "C" X-SECTIONS

C-3042 ↑
C-3139 ↑
F-2047 ↑

RAMP 'C' 17+89
C-3042

880

C-6792
F-3638

62

BANK SLAG FILL VARIES

2:1

4:1

38" SEWER

42" M.W.S.D. WATER

C

850

B

106' EDGE WATER
EL. 829.4±

170 160

874.18 874.98 875.96 876.25 876.44 876.25 876.04 876.13 876.32 876.13 875.93 874.40

122

RAMP "D"
7+73

873.49

RAMP "B3"

874.8

952+50
895.3

RAMP "C"
17+44 ±

86B45

C-4202
F-1882

SEE RAMP "C" X-SECTIONS

880

C-8525
F-3781

56' ± TOP BANK
FROM ℄ RAMP "D"
EL. 848.2 ±

2:1

BANK SLAG FILL VARIES

8

75

TOP BANK 59± FROM ℄ RAMP "D"
EL 848.0

VARIES

A

850

105' ± EDGE WATER FROM ℄
EL 829.4±

BANK SLAG FILL

C-2075 ↑
C-2930 ↑
F-1769 ↑
F-432 ↑↑

Y.E. 952+00
C-2930
F-432

RAMP 'C' 16+98
C-2075

SEE RAMP "C" X-SECTIONS

880

170 160

RAMP "D"
F-1769

872.50 873.30 875.47 875.82 875.97 876.78 875.57 875.41 875.72 875.53 875.61 873.74

873.17

+148
+60

RAMP "B3"

871.15

952+00
894.5

RAMP "C"
16+98 ±

86B59

C-4973
F-1246

2:1

A

35" SEWER

42" WATER MAIN

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 5 - CROSS SECTION O.D.S.R.R.F. STANDARD
KENTILE & LOS ANGELES NEW YORK

952+00 TO 953+00

ORIGINAL SURVEY
NOTE BOOK
NO.
DATE
PAGE
FINAL SURVEY
NOTE BOOK
NO.
DATE
PAGE

SEEDING	
END WIDTH	SQ YDS.

FED.	STATE	PROJECT	
	CONT.		

139
492

MAH.-18-17.20

END AREA	CUBIC YARDS

112

190

197

204

128

257

960.30

962.50

962.40

12:1

2:1

11/2:1

BANK

SLAG

FILL

38" SEWER

42" WATER MVSD

GRANULATED MATERIAL

955+00
853.5

954+50
854.6

954+00
855.2

953+50
859.2

RAMP "D"
5+31 ±

RAMP "D"
5+80 ±

RAMP "D"
6+30 ±

RAMP "D"
6+80 ±

RAMP "B"

RAMP "C"
18+39

877.16 877.74 877.89 878.05 878.24 878.35 878.39 878.40 878.19 878.32 878.05

877.06 877.58 877.42 877.19 877.98 877.94 877.92 878.13 878.32 878.24 878.15

877.17

876.88 877.50 877.24 877.45 877.64 877.57 877.46 877.44 877.85 877.64 877.23

876.79

876.32 877.18 874.85 877.10 877.29 877.10 874.98 877.19 877.38 877.19 874.95 874.32

876.34

857.0

859.8

868.0

868.16

4:1

3:1

2:1

VARIES

7'-12" I-2
M-6.4(4)

C-39
F-4522

C-34
F-8987

C-73
F-4784

C-52
F-8311

C-98
F-4192

C-2652
F-6666

C-2833
F-3007

C-8346
F-4680

850

860

870

920

900

160 170

102 ± EDGE WATER FROM ℄
EL 829.4

57' TOP BANK
EL 852 ±

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 1 CROSS SECTION

953+50 TO 955+00

SEEDING	
END WIDTH	SQ YDS

140
492

MAH-18-17.20

END AREA	CUBIC YARDS

113

878.81 880.27 880.54 881.18 881.91

S.S.H. 4.84

RAMP "D"
3+36±

877.80
872.8

A A

C-0
F-5190

860

226

957+00
853.8

GRANULATED MATERIAL

33" SEWER

42" WATER

123

878.62 879.80 880.02 880.55 881.09

S.S.H. 4.38

RAMP "D"
3+85±

2:1

A
870
A
110

C-2
F-8408

C-25
F-4533

952.40

216

BANK RUN SLAG

1½:1

GRANULATED MATERIAL

33" SEWER

42" MYSD WATER

956+50
853.6

859.6

850

125

878.43 879.33 879.54 879.95 880.32

S.S.H. 3.93

RAMP "D"
4+32

S.S.H. 9.00

2:1

C-0
F-8423

955.80

234

12:1

BANK RUN SLAG

FILL

1½:1

FILL

GRANULATED MATERIAL

33" SEWER

42" MYSD WATER

956+00
853.7

858.6

C-60
F-4564

850

124

877.26 877.87 878.03 878.24 878.86 879.07 879.35 879.64 879.93

S.S.H. 3.4

RAMP "D"
4+81±

S.S.H. 7.70

2:1

C-10
F-8420

955.20

214

12:1

BANK RUN SLAG

1½:1

FILL

INV. 849.13

24" S27

4.13 % FLOW

955+50
853.6

RC-4 END WALL

856.5

INLET INV. 856.42

C-74
F-4530

850

FILL

GRANULATED MATERIAL

33" SEWER

42" MYSD WATER

C-21
F-8752

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 2 CROSS SECTION O.F.P.R.R. STANDARD
RUFFELL & LERNER - NEW YORK

955+50 TO 957+00

ORIGINAL SURVEY FROM FIELD NOTE BOOK TEXAS & PACIFIC NO. 1 MILES

SEEDING	
END WIDTH	SQ YDS
60	
115	
73	
141	
83	
157	
94	
182	

FED. RD.	STATE	PROJECT	
2	OHIO		

141
492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY
NOTE BOOK
NO.

ORIGINAL SURVEY
NOTE BOOK
NO.

SEE RAMP "E" X-SECTIONS STA. 6+26

SEE RAMP "E" X-SECTIONS STA 5+73

959+00
880.0

C-1219
F-979

890

C-1374
F-2654

873.73 882.15 884.67 884.09 2:1 2:1 5.5H 6.61

854.00

959+00
880.0

873.39 881.68 882.08 883.08 883.98 883.36 2:1 2:1 5.5H 6.19

C-265
F-1887

880

958+50
865.2

873.20 881.21 881.56 882.41 883.24 882.51 2:1 2:1 5.5H 5.74

849.00

C-639
F-4351

C-400
F-2812

880

EXISTING 33" SEWER.

EXISTING 12" M.V.S.D. WATER

958+00
857.0

C-394
F-7100

873.01 880.74 880.74 881.105 881.80 882.54 883.43 880.00 A-31 5.5H 5.29

848.00

C-6
F-4546

870

EXISTING 33" SEWER

EXISTING 12" M.V.S.D. WATER

957+50
854.2

C-0
F-8707

847.50

12" WATER M.V.S.D.

GRANULATED MATERIAL

140 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 CROSS SECTIONS A.P.P.A.R.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK

957+50 TO 959+00

SEEDING.	
END WIDTH	SQ. YDS

FED. RD.	STATE	PROJECT	
2	OHIO		

142
492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY
SHEETS PLOTTED
NOTE BOOK
NO.

ORIGINAL SURVEY
SHEETS PLOTTED
NOTE BOOK
NO.

48

90

51

93

60

+123
+102

890

890

890

890

960+50
891.2

960+00
893.2

959+50
892.0

876.0

875.0

859.0

S.S.H. 8.00

S.S.H. 7.55

S.S.H. 7.15

4:1

3:1

2:1

891.14

888.66

885.98

885.47

885.47

883.47

RAMP "E"
7+88.5

820.47

883.09

885.51

884.91

886.46

884.46

RAMP "E"
7+34±

890.20

882.62

886.04

885.24

888.64

886.64

RAMP "E" & PARK RD.
G+85±

SEE RAMP "E" & PARK RD. X-SECTIONS STA. 5+88 P.R.

C-5072
F-0

SEE RAMP "E" & PARK RD. X-SECTIONS STA. 6+38 P.R.

C-5335

C-9636
F-0

C-9835
F-381

SEE X-SECTIONS STA. 6+85

YE 959+50
C-1908
F-412

RAMP "E" 6+85
C-1548

C-3378 +
C-1908 ++
F-412 ++

C-2895
F-1288

120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 3 - CROSS SECTION O. P. R. R. & P. E. STANDARD
NEWFELD & KISSER CO., NEW YORK

959+50 TO 960+50

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	143 / 492
2	OHIO		

MAH-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — NOTE BOOK — NO. — DATE — BY — ORIGINAL SURVEY — SURVEYED — OFFICE — TEMP. FILL — AREAS — AREAS CHECKED




PLATE 3. CROSS SECTION O.P.R.& R.I. STANDARD
KEUFFEL & ESSER CO., NEW YORK

961+00 TO 962+00

SEEDING	
END WIDTH	SQ YDS

STATE	PROJECT	
OHIO		144 492

MAH.-18-17.20

END AREA	CUBIC YARDS

964+00
845.8

884.48 884.8 885.

850

963+50
847.8

883.49 885.21 886.33

850

C-3138
F-0

870

963+00
856.2

883.02 885.44 887.84

SEE PARK ROAD
X-SECTIONS
STA 4+09

C-3389
F-0

870

962+50
876.5

C-5189
F-479

120 100 80 60 40 20 ℄ 20 40 60 80 100 120

PLATE 3 CROSS SECTION O. P. R. & R. E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

962+50 TO 964+00


SEEDING	
END WIDTH	SQ YDS

FED. RD	STATE	PROJECT		145 492
2	OHIO			

MAH.-18-17.20

END AREA	CUBIC YARDS


880



840

965+50
847.2


880



840

965+00
846.9

880



840

964+50
846.0

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 7. CROSS SECTION C. P. R. & R. E. STANDARD
HEINTZE & LESEMAN CO., NEW YORK.

964+50 TO 965+50

FINAL SURVEY
SURVEYED
PLOTTED
CHECKED
NOTE FROM
DATE

ORIGINAL SURVEY
SURVEYED
PLOTTED
CHECKED
NOTE FROM
DATE

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
	OHIO		

146
492

MAH.-18-17.20

END AREA	CUBIC YARDS

870

967+00
832.0

DAM

SPILLWAY

WATER

WATER

840

887.19 883.20 891.25

890

966+50
834.0

DAM

SPILLWAY

WATER

WATER

840

886.44 888.73 883.13 890.08 897.03

890

HIGH WATER

WATER

840

966+00
835.0

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3 - CROSS SECTION C. P. R. & R. E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

966+00 TO 967+00

ORIGINAL SURVEY
SURVEYED
PLOTTED
NOTE BOOK
TEMPLATE
PIC
CARDS - PUNCHED

SEEDING	
END WIDTH	SQ YDS

STATE OHIO	PROJECT		147 492

MAH.-18-17.20

END AREA	CUBIC YARDS

72

888.35

889.31

C=1580
F=0

880

968+50
898.0

C=1416
F=0

888.82

890

850

968+00
856.0

860.81

863.16

890

DAM

SPILLWAY

WATER 7

840

WATER 7

967+50
831.0

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE'S CROSS SECTION C.E.P.S. A.G.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK

967+50 TO 968+50

ORIGINAL SURVEY
SCALE 1000
SCALE 1000
NO. ____ DATE JULY 1937

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
2	OHIO		

148
492

MAH-18-17.20

END AREA	CUBIC YARDS

ORIGINAL SURVEY
FINAL SURVEY
NOTE INCOR. TEMPLATE
NO. SHEETS CHANGED

91

139.42

908.55

145

MARSHAL ST.
0+35.42

891.49 891.68 891.87 891.98 892.02 892.02 892.23 892.42 892.55 892.68

887.56

886.53

890.68

2:1

C-5930

969+50
924.0

890

72

C-3175
F-0

115

890.48 890.93 891.13 891.41 891.55 891.55 891.74 892.05 892.24 892.43

886.06

890.42

2:1

C-3979

969+00
913.2

890

52

C-5101
F-0

STA. 968+69
I-8 M.H. #3-A
57.5 LT. ℄
TOP OF CURB
GRATE ELEV.
#1 " I-2
80# " I-2

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 3 CROSS SECTIONS OF PROPOSED PAVEMENT
ROUTES 8 CASEY TO NEW YORK

969+00 to 969+50

SEEDING	
END WIDTH	SQ YDS

		PROJECT	149 492

MAH-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY: SURVEYED, PLOTTED, TEMPLATED, AREAS, NOTE BOOK, NO. — AREAS REVISED

ORIGINAL SURVEY: SURVEYED, PLOTTED, TEMPLATED, AREAS, NOTE BOOK, NO. — AREAS REVISED

95

172

98

139.08

902.70

½"/ft

12.58'

MARSHAL ST.
1+85.42

2:1

893.28 893.37 893.56 893.75 893.56 893.43 893.43 893.64 893.83 893.64 893.45

891.26

891.32

2:1

C-8375

971+00
231.0

890

181

139.19

903.09

½"/ft

13.56'

MARSHAL ST.
1+35.42

2:1

892.73 892.95 893.14 893.01 892.96 892.96 893.17 893.36 893.17 892.98

890.67

890.85

2:1

C-8437

NORMAL (RT)

970+50
334.0

890

C-15733
F-0

182

139.31

903.30

½"/ft

14.55'

MARSHAL ST.
0+85.42

2:1

892.17 892.36 892.55 892.51 892.45 892.49 892.70 892.83 892.83 892.77

890.06

890.78

2:1

C-8555

C-13412
F-0

970+00
334.3

890

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE D CROSS SECTION O.P.W.&.I.C. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

970+00 TO 971+00

SEEDING	
END WIDTH	SQ. YDS

OHIO	156 492

MAH-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY PLOTTED / CHKD / NOTE BOOK / PAGE NO

ORIGINAL SURVEY PLOTTED / CHKD / NOTE BOOK / PAGE NO




PLATE 3 - CROSS SECTION © U.P.A.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

971+50 TO 972+50

SEEDING	
END WIDTH	SQ YDS

STATE		
OHIO		

151
492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — SURVEYED — PLOTTED — NOTE BOOK — PAGE — NO. — SHEETS CHECKED

ORIGINAL SURVEY — SURVEYED — PLOTTED — NOTE BOOK — PAGE — NO. — SHEETS CHECKED

94

167

894.26 894.03 893.84 893.78 892.86 894.25 896.25

MARSHAL ST 4+74

RAMP "G" 2+58

889.00

974+00
918.2

894.14

2:1

C-5053
F-0

890

94

C-9825
F-0

170

896.57 894.38 894.26 894.22 895.78 895.78 895.99 896.18 895.99 895.80

MARSHAL ST 4+23.5

893.21

RAMP "G" 3+03

893.09

973+50
922.0

2:1

C-5558
F-0

890

C-10783
F-0

91

158

NOTE:
STA 3+94.91 BEGIN TAKING QUANTITIES TO ℄ MARSHALL ST

NOTE:
RAMP "G" STA 6+23.03 TO 7+23.03
PAVT TRANSITIONS TO 3½% /' IN OPPOSITE DIRECTION
STA 6+73.03 PAVT LEVEL SWITCH PG

℄ MARSHALL ST.

898.29 894.30 895.31 895.31 895.52 895.71 895.52 895.33

3%

SPECIAL DITCH - SEE DETAIL

3+79±

892.90

RAMP "G" 3+58

894.60

973+00
924.0

893.20

2:1

C-6088
F-0

C-11852
F-0

890

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 - CROSS-SECTION PAPER AS STANDARDIZED
KEUFFEL & ESSER CO., NEW YORK

973+00 TO 974+00

SEEDING	
END WIDTH	SQ YDS

OH-10	152 492

MAH.-18-17.20

END AREA	CUBIC YARDS

107

192

106

137.93

879.49

879.42

4:1

3:1

MARSHAL ST. G+85.42

RAMP "G" 0+38

877.6

898.38

898.73

NOTE: STA 976+00 END 12" I-22

976+00

201.3

896.03

2:1

C-1637 ↑
C-1685 ↓
F-0

890

C-3984
F-0

189

138.94

883.71

883.46

883.38

4:1

3:1

MARSHAL ST. G+35.42

RAMP "G" 0+98

881.0

897.68

897.44

975+50

200.0

895.55

2:1

C-2618
F-0

890

C-6012
F-0

102

NOTE:
STA. 0+00 TO 1+00 RAMP "G" TRANSITION 3' PAVED SHOULDER TO MEET 2' CONC. GUTTER ON MARSHALL ST.

180

138.16

883.72

883.57

883.33

4:1

3:1

MARSHAL ST. 5+85.42

RAMP "G" 1+49

880.33

897.19

897.15

975+00

209.8

895.08

2:1

C-3875
F-0

890

C-7822
F-0

97

NOTE: STA. 974+50 BEGIN 12" I-22

171

138.27

890.37

890.72

890.89

4:1

3:1

MARSHAL ST. 5+35.42

RAMP "G" 2+00

888.1

896.72

896.72

974+50

213.0

894.61

2:1

C-4573 ↑
C-4525 ↓
F-0

890

C-8869
F-0

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 6 - CROSS SECTION O. P. R. & R. E. STANDARD
REUFFEL & ESSER CO., NEW YORK.

974+50 TO 976+00

FINAL SURVEY
CHECKED
PLOTTED
NOTE BOOK
NO.
TEMPLATE
AREAS CHECKED

ORIGINAL SURVEY
CHECKED
PLOTTED
NOTE BOOK
NO.
TEMPLATE
AREAS CHECKED

SEEDING	
END WIDTH	SQ YDS

STATE OHIO — 153 432

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — SURVEYED / PLOTTED / COMPUTED / NOTE BOOK / NO. / AREAS / AREAS CHECKED / DATE

ORIGINAL SURVEY — SURVEYED / PLOTTED / TEMPLATE / NOTE BOOK / NO. / AREAS / AREAS CHECKED / DATE

105

137.47

872.38

873.06

4:1

871.39

2:1

900.01

900.01

3:1

835.0

C-251
F-1771

890

978+00
888.5

2+85.42

105

137.68

873.80

873.39

4:1

872.05

2:1

899.54

899.54

3:1

837.43

C-453
F-1019

890

977+50
892.2

1.89

8+35.42

106

137.70

875.40

875.48

4:1

873.48

2:1

899.07

899.07

3:1

896.99

C-621
F-463

890

977+00
896.5

7+85.42

107

137.21

877.15

877.25

4:1

874.06

2:1

898.60

898.60

3:1

896.49

C-836
F-306

890

976+50
898.1

7+35.42

192

MARSHALL ST.

BAMP "G"
0+00.00

C-2250
F-283

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 3-CROSS SECTION O.P.S.&R.E. STANDARD

KENFEEL & ESSER CO. NEW YORK

SEEDING	
END WIDTH	SQ YDS

			154
	OHIO		492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — SURVEYED, PLOTTED, TYPED, CHK'K, NOTE BOOK, AREAS, AREAS CHECKED, NO.

ORIGINAL SURVEY — SURVEYED, PLOTTED, TYPED, CHK'K, NOTE BOOK, AREAS, NO.

℄ MARSHALL ST.

137.89 — 872.96 — 11+35.42

137.01 — 872.43 — 10+85.42

137.12 — 872.53 — 10+35.42

137.24 — 872.72 — 872.50 — 9+85.42 — 870.88

137.35 — 872.58 — 872.64 — 9+35.42 — 870.85

I-8 No 2-2-A
STA 978+75
WINDOW ELEV. 870.33

902.36 902.36 — 888.90 — C-11 F-319 — 880

980+50 — 881.5 — 901.89 901.89 — C-10 F-295

C-0 F-0 — 880

980+00 — 880.1 — 901.42 901.42 — C-13 F-621

3:1 4:1 — 887.70 — C-14 F-671 — 880

979+50 — 881.0 — 900.65 900.65 — C- F-2094

3:1 3:1 — 890.14 — C-189 F-2563 — 880

979+00 — 881.0 — 900.48 900.48 — C- F-4369

4:1 2:1 — 892.57 — C-172 F-2156 — 880

978+50 — 883.0 — C- F-3636

2:1 2:1

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

FLATE 3 - CROSS SECTION O.P.R.A.&.E. STANDARD
KRUTTER & LOGAN CO., NEW PHILA.

978+50 TO 980+50

SEEDING	
END WIDTH	SQ YDS

FED. PROJ.	STATE	PROJECT		155 492
	OHIO			

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — SURVEYED — PLOTTED — NOTE BOOK — AREAS — NO.

ORIGINAL SURVEY — SURVEYED — PLOTTED — NOTE BOOK — AREAS — NO.

DATE — BY

80

144

136.43

870.75

2:1

870.18

MARSHALL ST.
13+35.42

904.19

904.19

RAMP "F"
6+96±

2:1

3:1

890.40

C-11
F-4090

880

982+50
875.8

79

136.65

871.05

2:1

870.47

MARSHALL ST.
12+85.42

903.77

903.77

12'

RAMP "F"
6+46±

2:1

890.00

C-7
F-3930

880

982+00
876.0

140

77

136.66

871.35

2:1

870.77

MARSHALL ST.
12+35.42

SPECIAL CONC. DITCH SEE DETAIL SHEET N°

903.30

903.30

13.50'

RAMP "F"
5+96±

2:1

889.80

4:1

C-48
F-3637

880

981+50
877.0

136

76

136.78

871.67

2:1

871.09

MARSHALL ST.
11+85.42

902.83

902.83

16'

2:1

C-5
F-3197

880

981+00
880.7

138

C-51
F-7006

C-49
F-6328

C-17
F-7426

C-15
F-3256

NOTE:
STA. 981+00 TO 982+00
TRANSITION TOTAL WIDTH
OF SHOULDER 15' TO 12'

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120

PLATE 3 · CROSS SECTION · O. P. R. & H. C. STANDARD
KRUPPER & KESTER CO., NEW YORK

981+00 TO 982+50

SEEDING	
END WIDTH	SQ YDS
90	
150	
82	
146	
80	
141	
78	
143	

CO. RTE.	STATE	PROJECT		156 492
	OHIO			

MAH. 18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — NOTE BOOK — SHEET NO.

ORIGINAL SURVEY — SURVEYED — PLOTTED — NOTE BOOK — SHEET NO. — AREAS — QUANTITIES — SHEET NO.

903.92 — 902.1 — 905.18 — 904.22 — 8+88 — 895.10

135.97 — 2:1 — 865.88 — MARSHAL ST. 15+35.42 — 869.46

C-14 F-4555

884+50 875.5

C-35 F-8537

904.29 — 904.58 — 905.86 — 8+40 — 892.80

C-24 F-4665

156.09 — 2:1 — 870.10 — MARSHAL ST. 14+85.42 — 869.68

884+00 874.0

C-39 F-8513

904.46 — 2:1 — 891.30

C-18 F-4529

136.20 — 2:1 — 870.31 — MARSHAL ST 14+35.42 — 869.89

883+50 874.0

C-25 F-8206

904.43 — 904.43 — 2:1 — 801.00

C-9 F-4333

136.32 — 2:1 — 870.52 — MARSHAL ST. 13+85.42 — 870.10

883+00 875.0

C-19 F-7799

900 890 900 870 900 870

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 7. CROSS SECTION [illegible] STANDARD
KRUPPER & TOSTER ETC., NEW YORK

883+00 TO 884+50

SEEDING	
END WIDTH	SQ YDS

NED. RD.	STA.	PROJECT	
	CHSC.		

157
492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — UNPLOTTED / PLOTTED — NOTE BOOK — PAGE — NO. — AS ONGOING

ORIGINAL SURVEY — UNPLOTTED / PLOTTED — NOTE BOOK — PAGE — NO.

61
114
73
148
67
100
203
105
174

135.51
868.08
868.61
MARSHALL ST.
17+35.42

135.63
868.25
868.85
MARSHALL ST.
16+85.42

135.74
869.46
869.04
MARSHALL ST.
16+35.42

135.36
869.67
869.25
MARSHALL ST.
15+85.42

2:1

900.43 900.43

894.0

C-11
F-3000

986+50
878.0

901.61 901.61

4:1 VARIES

895.0

C-12
F-5893

870

C-2
F-3364

986+00
877.5

902.58 902.58 903.24 903.24

Y.E. 985+50
C-2
F-3330

RAMP "F" 9+76
C-14
F-13931

3:1

896.2

9+76
RAMP "F"

900.05 898.67

C-4
F-6198

900 899.10

150 160 170 180

880

985+50
877.0

903.35 903.35

907.66 906.48

4:1

900.94

9+34
RAMP "F"

C-2 ↑↑
C-14 ↓
F-33301↑
F-13931↓

C-21
F-8906

896.75

C-7
F-4896

880

C-19
F-8751

985+00
874.0

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 CROSSSECTIONS

985+00 TO 986+50

SEEDING	
END WIDTH	SQ YDS
71	
129	
66	
110	
59	
104	
58	
105	

FED. RD.	STATE	PROJECT	
2	OHIO		

158
492

MAH-18-17.20'

END AREA	CUBIC YARDS

FINAL SURVEY — SURVEY C. PLOTTED — TEMPLATE — NOTE BOOK — PAGE — NO. — CHECKED

ORIGINAL SURVEY — SURVEY C. PLOTTED — TEMPLATE — NOTE BOOK — PAGE — NO. — CHECKED



PLATE 3 CROSS SECTIONS OF P.A.P.E. STANDARD
KEUFFEL & ESSER CO. NEW YORK.

987+00 TO 988+50

SEEDING	
END WIDTH	SQ YDS

	STATE	PROJECT		155	
				492	

END AREA	CUBIC YARDS

MAH-18-17.20

SURVEYED / PLOTTED / TEMPLATE / NOTE BOOK / CHECKED — FINAL SURVEY

SURVEYED / PLOTTED / TEMPLATE / NOTE BOOK / CHECKED — ORIGINAL SURVEY

TG

128

75

141

82

155

80

134

72

125

SEE RAMP "H" STA. 10+70

C-2108 ↑
F-44 ↑
C-2146 ↓
F-40 ↓

890

888.44 886.75 886.75 884.86

NOTE:
STA 991+00
END 12" I-22
881.91

991+00
892.0

2:1

859.78 859.42

RAMP "J"
14+32

C-4156
F-92

SEE RAMP "H"
STA. 10+25

890.18 886.29 886.29 886.40

C-2343
F-59

890

990+50
892.5

883.41

C-4155
F-94

862.62 862.66 862.34 VARIES

MARSHALL ST.
21+53.5

RAMP "J"
14+85

861.20

SEE RAMP "H"
STA. 9+80

891.72 889.83 889.83 881.94

C-2144
F-43

990+00
894.0

884.91

890

C-3019
F-208

865.96 865.48 VARIES

MARSHALL ST.
20+91.5

864.69

891.37 891.37 889.63

C-1117 ↑
F-182 ↑
C-1085 ↓
F-192 ↓

890

989+50
892.8

2:1 4:1 2:1

887.23

NOTE
STA. 989+50
BEGIN 12" I-22

C-1644
F-456

867.51 867.18

MARSHALL ST.
20+40

865.89

NOTE:
BEGIN DITCH @ STA. 16+05 RAMP J"

892.91 892.91 891.45

C-691
F-301

NOTE:
END I-14 PAVED GUTTER
@ STA. 16+55 RAMP "J"

889.20

MARSHALL ST.
19+88.5

989+00
893.5

867.95 867.70

880

C-990
F-814

100 80 60 40 20 ℄ 20 40 60 80 100 120

PLATE 3 CROSS SECTION C. P. A. & R. R. STANDARD
REUFFEL & ESSER CO. NEW YORK

989+00 TO 991+00

SEEDING	
END WIDTH	SQ YDS

FED.	STATE	PROJECT	
	OHIO		

160
492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY QUANTITIES NOV 2 1956 DATE

ORIGINAL SURVEY QUANTITIES NOV 2 1956 DATE

NO. — DATE — REVISIONS — BY — CHECKED

146

250

154

NOTE:
BEGIN I-14 PAVED GUTTER @STA. 12+00, FLARE TO MEET DITCH.

882.48 880.59 880.59 878.70

861.53 861.21

4:1 2:1

RAMP "J"
12+20

860.83

993+00
878.5

A

2:1

160

160

878.91 877.87

875.91 4:1 875.59

2:1

A

880

C-3696
F-615

12+57
RAMP "H"

C-6767
F-1030

1300
+133

NOTE:
END I-14 PAVED GUTTER @ 12+40
FLARE CURB TO MEET MODIFIED
2-2A INLET

884.02 882.13 882.13 880.24

858.95 858.63

2:1

RAMP "J"
12+73

992+50
882.0

877.41

SEE RAMP "H"
12+10

C-3848 *
C-764 X *
F-493 X *
AHEAD *
BACK X

880

C-1685
F-910

74

885.56 883.67 883.67 881.78

C-1056
F-490

890

992+00
883.7

878.91

C-2047
F-960

133

857.32 856.94

887.10 885.21 885.21 883.32

2:1

C-1137 †
F-547 †
C-1148 †

890

77

RAMP "J"
13+26

880.41

991+50
886.0

2:1

NOTE:
2A-8 INLET @ 13+50

144

857.61 857.23

C-3015
F-547

860

RAMP "J"
13+80

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 CROSS SECTION U. P. P. & R. E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

991+50 TO 993+00

SEEDING	
END WIDTH	SQ YDS.

FED. RD.	STATE	PROJECT	
	OHIO		

161
492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY
ORIGINAL SURVEY
NOTE BOOK
PAGES

102 192 112 211 124 236 142 277

RAMP "J" 10+08
850.0
867.55 867.25 4:1 VARIES 869.44
876.82 874.43 874.43 872.54 872.28 871.08 2:1
871.56
995+00
865.7
14+43 RAMP "H"
868.78
C-752 F-1961
C-1868 F-3233
870

RAMP "J" 10+61
850.3
869.29 868.97 4:1 VARIES 867.18
877.76 875.97 875.97 874.08 873.63 872.59 2:1
871.41
994+50
868.0
13+35 RAMP "H"
870.31
C-1265 F-1531
C-2055 F-2652
870

RAMP "J" 11+14
851.5
866.71 866.39 4:1 VARIES 864.60
879.40 875.62 875.51 875.32 874.22 875.22 2:1
872.91
994+00
870.5
13+47 RAMP "H"
871.94
C-1954 F-1333
870

RAMP "J" 11+67
852.0
864.12 863.80 4:1 VARIES 862.75
880.94 878.05 878.05 877.16 875.91 875.29 2:1
874.41
993+50
872.4
13+03 RAMP "H"
873.63
C-2396 F-1237
C-5641 F-1719
870

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 CROSS SECTION O. F. P. & B. E. STANDARD
REUPPEL & ESSER CO. NEW YORK.

993+50 TO 995+00

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	162 / 452
	OHIO		

END AREA	CUBIC YARDS

MAH-18-17.20

YOUNGSTOWN FURNACE

℄ HILKER

59 104 52 84 64 148 83 152 91 176

866.55 868.62 866.73 866.73 864.84 863.69 861.33

997+50
856.0

C-132
F-1623

860

870.86 870.44 870.16 868.27 868.27 866.38 865.11 862.81

RAMP "J"
8+03

997+00
860.8

C-202
F-2850

C-86
F-1498

860

872.19 871.79 871.70 869.81 869.81 867.92 866.60 864.32

RAMP "J"
8+54

RAMP "H"
15+87

996+50
858.0

C-283
F-3481

C-220
F-2262

860

849.0

872.96 872.58 873.24 871.85 871.85 869.96 868.12 865.85

RAMP "J"
9+05

871.8

RAMP "H"
15+38

996+00
860.0

C-439
F-4224

C-254
F-2300

860

848.7

872.77 872.45 874.78 872.89 872.89 871.00 870.72 867.62 867.34

RAMP "J"
9+55

871.1

RAMP "H"
14+20.2

995+50
862.5

C-501
F-4055

C-294
F-2079

870

848.4

C-369
F-3741

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 3 CROSS SECTION C.P.V. & R.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

995+50 TO 997+50

ORIGINAL SURVEY
FINAL SURVEY
NOTE BOOK
NO.
DATE
BY
REVISED

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH.-18-17.20

163
492

END AREA	CUBIC YARDS

69

121

865.19 864.22 862.33 862.33 860.44

2:1 4:1 4:1

841.55 854.8

1000+00
847.6

C-22
F-1803

850

67

119

865.67 864.57 862.68 862.68 860.79

2:1 4:1 4:1

841.70 856.6

999+50
848.5

C-38
F-3388

C-19
F-1856

850

66

118

866.45 865.19 863.30 863.30 861.41

2:1 4:1 4:1

843.60 857.13

999+00
850.1

C-17
F-1707

C-33
F-3299

850

64

113

867.27 864.07 864.18 864.18 862.29 861.39

2:1 4:1 4:1

844.40 859.02

998+50
851.5

C-13
F-1730

C-28
F-3182

850

62

110

868.31 867.21 865.32 865.32 863.43 862.41

2:1 4:1 4:1

846.20 860.01

998+00
853.3

C-11
F-1702

C-22
F-3178

C-132
F-3079

850

120 100 80 60 40 20 ℄ 20 40 60 80 100 120

PLATE 3-CROSS SECTION O.P.R.&R.E STANDARD
REHFELD-ESSER CO., N.Y.C.

998+00 TO 1000+00


ORIGINAL SURVEY PLOTTED
SURVEY PLOTTED AT
NOTE BOOK REFERENCE
AREA & CUBIC
NO.

STATE	PROJECT	
OHIO		

164
492

MAH.-18-17.20

SEEDING		END AREA	CUBIC YARDS
END WIDTH	SQ YDS		
79		C-23 F-2918	840
141		C-55 F-5228	
79		C-36 F-2728	
143		C-91 F-4779	840
80		C-62 F-2433	
145		C-79 F-4244	840
76		C-23 F-2150	
130		C-53 F-3898	840
72		C-35 F-2060	
129		C-53 F-3577	840



NOTE:
STA. 1000+73.79
BEGIN PAVT. & SHOULDER TRANSITION

PLATE 3 CROSS SECTION C. P. R. & P. C. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

1000+50 TO 1002+50

FINAL SURVEY
ORIGINAL SURVEY

SEEDING	
END WIDTH	SQ YDS

FED RD	STATE	PROJECT	
Z	OHIO		

165
492

MAH.-18-17.20

	END AREA	CUBIC YARDS

FINAL SURVEY
ORIGINAL SURVEY PLOTTED
NOTE BOOK
NO.
TYPE OF SURVEY
AREAS CHECKED
DATE
BY
CHECKED

134
874.08
872.19
2:1
857.10
1005+00
849.7
C-9
F-2450
860
850

78
872.42
870.53
868.64
2:1
2:1
844.0
1004+50
848.6
851.00
C-20
F-5166
C-13
F-3129
C-78
F-5682
870
860
850

NOTE:
STA. 1004+51.34 ℄
END PAVT. & SHOULDER TRANSITION

81
870.79
868.90
867.01
2:1
843.0
1004+00
847.0
850.85
C-71
F-3008
C-118
F-5687
870
860
850

80
869.16
867.27
865.38
2:1
2:1
840.5
1003+50
845.6
848.70
C-56
F-3134
C-97
F-5593
860
850
840

79
867.66
865.77
863.88
2:1
2:1
840.65
1003+00
844.7
850.15
C-49
F-2906
C-67
F-5393
860
850
840

143
143
145

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 - CROSS SECTION U.S.P.R. & R.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK

1003+00 TO 1005+00

SEEDING	
END WIDTH	SQ YDS
85	
153	
86	
157	
52	
130	

FED. RD	STATE	PROJECT		166 492
2	OHIO			

MAH-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY PLOTTED CHECKED NOTE BOOK PAGE NO. AREAS

ORIGINAL SURVEY PLOTTED CHECKED NOTE BOOK PAGE NO. AREAS

882.20 880.31 880.31 878.42

2:1 2:1

SEE 2+05 PIKE ST.

852.0

855.3

℄ PIKE ST.

C-6 F-3834

1007+50 853.0

878.68 878.68

C-17 F-6436

850

2:1

SEE 1+50 PIKE ST.

851.0

C-12 F-3117

1007+00 853.7

878.94 877.05 875.16

C-11 F-3886

850

VARIES

SEE 1+00 PIKE ST.

C-0 F-1080

1006+50 853.0

877.31 875.42 875.42 873.53

C-0 F-1000

850

C-0 F-0

1006+00 852.3

875.68 873.79 873.79 871.90

C-0 F-0

850

1005+50 851.6

C-8 F-2269

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3 - CROSS SECTIONS OF E. P. A. R. 2 STANDARD

REVISED & ISSUED AT NEW YORK

1005+50 TO 1007+50

STATE	PROJECT		167
OHIO			492

SEEDING	
END WIDTH	SQ YDS

END AREA	CUBIC YARDS

MAH-18-17.20

89

159

888.72 886.83 886.83 884.94

2:1 2:1

856.1

SEE PIKE ST X-SECTIONS STA. 4+18

℄ PIKE ST.

SPECIAL COMPACTION

BENCHES

BOTTOM OF FILL

865.6

1009+50

845.8

C-122
F-5971

850

C-140
F-10724

87

887.09 885.20 885.20 883.31

2:1 2:1 3:1

855.9

SEE PIKE ST X-SECTIONS STA. 3+64

℄ PIKE ST.

SPECIAL COMPACTION

863.0

153

1009+00

846.6

C-29
F-5611

850

C-90
F-9241

86

885.46 883.57 883.57 881.68

2:1 2:1 4:1

855.2

SEE PIKE ST X-SECTIONS STA. 3+11

℄ PIKE ST.

SPECIAL COMPACTION

858.8

156

1008+50

849.0

C-68
F-5125

850

C-84
F-8808

86

883.83 881.94 881.94 880.05

2:1 2:1 4:1

854.0

SEE PIKE ST X-SECTIONS STA. 2+58

℄ PIKE ST.

SPECIAL COMPACTION

857.1

153

1008+00

850.8

C-23
F-4388

850

C-27
F-2613

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE + CROSS SECTION OF R.R. & I.R.T. TRACKAGE
REVISED & REDRAWN FROM WORK

1008+00 TO 1009+50

SEEDING	
END WIDTH	SQ YDS

FED. NO.	STATE	PROJECT	
2	OHIO		

168
492

MAH-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — PLOTTED — TEMPLATE — CHECKED — AREAS CHECKED — NO. —

ORIGINAL SURVEY — PLOTTED — NOTE BOOK — TEMPLATE — CHECKED — NO. — AREAS CHECKED —

168'
HOSPITAL

RW

C-174
F-6037

92

166

893.61
891.72
891.72
889.83

2:1

SPECIAL COMPACTION

870.0

855.1

SEE 5+80
PIKE ST.

℄ PIKE ST.

BENCHES

BOTTOM OF FILL

1011+00
855.6

891.98
890.69
890.09
888.20

C-251
F-11448

850

92

RW

2:1

SPECIAL COMPACTION

℄ PIKE ST.

871.0

BOTTOM OF FILL

C-97
F-6327

166

855.6

BENCHES

1010+50
854.0

888.46
888.46
886.57

890.35

850

RW

C-166
F-11650

91

STA 1010+19.07
PAVT BEGINS WIDENING (LT)

2:1

C-82
F-6255

℄ PIKE ST

SPECIAL COMPACTION

870.7

BOTTOM OF RANDOM FILL

160

855.8

SEE 4+71
PIKE ST.

BENCHES

C-189
F-11320

1010+00
849.2

840

100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 CROSS SECTION O.D.T. & R.E. STANDARD
REUFFEL & ESSER CO., NEW YORK.

1010+00 TO 1011+00

SEEDING	
END WIDTH	SQ YDS

FED. NO.	STATE	PROJECT	
7	OHIO		

169
492

END AREA	CUBIC YARDS

PARKING LOT

MAH.-18-17.20

RW

2:1

137'
HOSPITAL

C-1726
F-4055

C-2271
F-8083

C-727
F-4675

C-673
F-9300

C-0
F-5369

C-161
F-10561

119

208

112

107

100

164

870

850

1012+50
879.0

851.8

SEE 7+43
PIKE ST.

898.50

896.61

894.72

890.224

1' UNDERCUT

BOTTOM OF FILL

896.87

894.98

893.09

890.61

SPECIAL COMPACTION

151'
HOSPITAL

BENCHES

1012+00
870.0

853.2

SEE 6+89
PIKE ST.

℄ PIKE ST.

895.24

893.35

891.46

3:1

885.2

SPECIAL COMPACTION

BOTTOM OF FILL

BENCHES

1011+50
861.2

854.2

SEE 6+35
PIKE ST.

120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 - CROSS SECTION O. P. R. & R. E. STANDARD
REUFFEL & ESSER CO., NEW YORK

1011+50 TO 1012+50

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
2	OHIO		

170
492

END AREA	CUBIC YARDS

931.50

MAH.-18-17.20

FINAL SURVEY PLOTTED / TRACED / TEMPLAT / CHECKED / NOTE BOOK / PAGE / NO. / ASSISTANT

ORIGINAL SURVEY PLOTTED / TRACED / TEMPLAT / CHECKED / NOTE BOOK / PAGE / NO. / ASSISTANT

115

226

121

SEE 9+08 PIKE ST.

PARKING LOT

RW

C-2657
F-1593

900

C-4276
F-4354

1014+00
904.8

1' UNDERCUT

897.01

903.38
901.50
901.06
899.68

2:1

C-1961
F-3109

890

208

SEE 8+53 PIKE ST

119

1013+50
890.0

900.13
898.24
898.24
896.35

1' UNDERCUT

893.87

BOTTOM OF FILL

C-3478
F-6154

C-1795
F-3537

880

219

170 160 150

SEE 7+98 PIKE ST.

1013+00
883.3

903.77
897.87
897.68

1' UNDERCUT

895.50

C-3260
F-7030

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 1 CROSS SECTION C.P.R. STYLE STANDARD
NEWTEFFE & RIDER CO. NEW YORK.

1013+00 TO 1014+00

SEEDING	
END WIDTH	SQ YDS
111	
182	
86	
129	
80	
160	
97	
188	

FED RD.	STATE	PROJECT	
2	OHIO		

171
492

	END AREA	CUBIC YARDS
MAH-18-17.20		

1036.00

C-3569
F-0

C-5791
F-24

910

908.90
908.02
907.28
904.97
2:1
12:1
2:1
1016+00
923.3

R.W.

930.75

C-2685
F-26

910

907.49
906.39
905.31
902.95
2:1
6"
0"
2:1
1015+50
920.3

R.W.

C-4845
F-111

931.00

C-2548
F-94
C-2503
F-103

910

909.13
904.76
903.45
900.87
2:1
2:1
1015+00
917.0

NOTE:
STA 1015+00
BEGIN 12"II-22

R.W.

C-5025
F-640

931.25

C-2924
F-588

910

904.76
903.13
901.54
898.84
2:1
2:1
1014+50
913.0

C-5168

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 3-CROSS SECTION U. S. B. & R. E. STANDARD
KEUFFEL & ESSER CO. NEW YORK

1014+50 TO 1016+00

FINAL SURVEY
NOTE BOOK
PAGE
CHKD
INCL

ORIGINAL SURVEY
NOTES
NOTE BOOK
PAGE
INCL

SEEDING	
END WIDTH	SQ YDS

FED. NO.	STATE	PROJECT		172 492
	OHIO			

END AREA	CUBIC YARDS

MAH.-18-17.20

134

244

132

232

131

239

110

158

EXISTING BOTTLE STORAGE BLDG

"M" CELLAR EXISTING BLDG

"M" CELLAR EXISTING BLDG

EXISTING BLDG

1470

1042.00

C-1025
F-360

914.75 914.94 914.75 914.54 914.61 914.79 914.53

2:1

912.1

C-2300
F-475

910

1018+00
904.0

1041.00

C-1459
F-153

913.18 913.31 913.12 912.91 912.95 913.04 912.85

2:1

910.66

C-2957
F-162

910

1017+50
906.4

1042.0

C-1735
F 22

911.67 911.68 911.49 911.28 911.49 911.68 911.67

2:1

909.66

C-3669
F-20

910

1017+00
908.0

1037.00

C-2227 ↑
F 01
C-2253 ↓
F- 04

910.29 910.07 908.86 909.65 908.19

2:1

12:1

8:1

907.00

910

1016+50
912.0

NOTE:
STA 1016+50
END 12" I-22

C-5391
F-0

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 3. CROSS SECTION O.P.R.R.R.E. STANDARD
KENNELL & FERGER CO., NEW YORK.

1016+50 TO 1018+00

FINAL SURVEY
NOTE BOOK
PAGE

ORIGINAL SURVEY
NOTE BOOK
PAGE

SEEDING	
END WIDTH	SQ. YDS.
133	
72	
125	
65	
110	
83	
189	
119	
240	

FED. RD.	STATE	PROJECT	
	OHIO		

173
492

MAR-18-17.20

END AREA	CUBIC YARDS

C-2962
F- 0

C-2840
F-264

C-165
C-286
F-285

C-294
F-264.4

C- 31
F-257.1

C-71
F-443.9

C- 46
F-222.3

C-539
F-252.3

C-536
F-502

C-1445
F-798

930
920
900
900
900

1020+50
941.7

1020+00
918.0

1019+50
899.3

1019+00
899.0

1018+50
904.2

922.07 922.76 922.95 922.77 922.69 922.90 923.09 922.90 922.51 920.51

922.50 922.50 920.68 921.26 921.45 921.26 921.06 921.27 921.46 921.27 920.96 914.21

921.54

919.29 919.64 919.83 919.64 919.43 919.64 919.83 919.64 919.36 913.1

917.82 918.01 918.20 918.01 917.80 918.01 918.20 918.01 917.62 912.9

916.20 916.38 916.57 916.38 916.17 916.38 916.57 916.38 916.19 912.5

931.17 932.17

2:1 4:1

VARIES

← BEGIN RET. WALL
STA. 1020+02.62
STA. 7+98 RAMP "L"

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3-CROSS SECTIONS (C.P.S.R.R.E. STANDARD)
KEUFFEL & ESSER CO., NEW YORK.

1018+50 TO 1020+50

SEEDING	
END WIDTH	SQ YDS

FED. NO.	STATE	PROJECT	
	OHIO		

174
432

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOKS / AREAS / TOTAL SHEETS / NO.

ORIGINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOKS / AREAS / TOTAL SHEETS / NO.

104

4183
+101

57

106
20

190

17

12

26

44

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

950

940

940

940

C-6468
F-0

C-10883
F-0

C-5286
F-0

C-8030
F-0

C-3386
F-0

C-6306
F-0

C-3424
F-0

C-5857
F-0

2:1

924.86

926.87 927.89 928.41 929.12 929.33 929.66 929.99 930.27 930.38 930.88

RAMP "L"
5+54

927.0

1022+50
954.5

RAMP "K"
8+73.8

929.15

BRIDGE ABUTMENT

6.8.14

925.45 926.37 927.14 927.33 927.51 927.58 927.58 927.79 927.99 928.20 928.38 928.47 928.67

RAMP "L"
6+03

1022+00
951.8

RAMP "K"
8+22.95

926.78

END RET. WALL
STA. 6+46.22

9+4.13

924.38 925.12 925.77 925.96 925.95 925.95 926.16 926.35 926.33 926.31 926.28

21.31

ABUT.

RAMP "L"
6+52

1021+50
946.3

RAMP "K"
7+72.70

NOTE:
STA. 7+98 TO 6+79 TOP WALL GR + 18.07%
STA. 6+79 TO 6+56.27 " " - 0.75%
STA. 6+56.27 TO 6+46.27 " " - 16.50%

940.85

938.85

923.28 923.97 924.27 924.46 924.36 924.32 924.53 924.72 924.58 924.44 924.24

17.27

RAMP "L"
7+02

1021+00
946.3

PLATE 3 CROSS SECTION © K. & E. 8 X 8 E. TANSPARENT
KEUFFEL & ESSER CO., NEW YORK.

1021+00 TO 1022+50

SEEDING	
END WIDTH	SQ. YDS.

2	OHIO		
MAH-18-17.20		END AREA	CUBIC YARDS

175
492

26

SEE RAMP "L" X-SECTIONS

2:1

931.39 931.56 933.39 935.27 936.32 937.12

RAMP "K" 10+80

928.93

1024+50
959.0

950

C-4491
F-0

71

58

C-9365
F-0

SEE RAMP "L" X-SECTIONS

2:1

931.07 932.91 934.24 934.99 935.79 2:1

RAMP "K" 10+28.72

934.16

928.73

1024+00
959.0

950

C-5623↑
C-5581↓
F-0

NOTE:
STA. 1024+00
BEGIN 12" I-22

C-9893
F-0

139

72

76
42
34

SEE RAMP "L" X-SECTIONS

930.36 931.63 933.01 932.82 933.50 934.30

RAMP "K" 9+74

932.67

928.28

1023+50
958.0

950

C-5103↑
C-5092↓
F-0

120

C-9222
F-0

64

RAMP "L" 5+07
C-1710

YE 1023+00
C-4868

928.86 929.74 929.48 930.47 930.47 930.68 931.90 931.38 932.08 932.76

RAMP "L" 5+07

926.92

926.67

RAMP "K" 9+24.67

931.15

1023+00
956.2

950

C-4868↑
C-1710↓
F-0 ++

C-12080
F-0

111
191

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 - CROSS SECTION O. P. R. & P. E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

1023+00 TO 1024+50

FINAL SURVEY
NOTE BOOK
NO.
SURVEYED BY
PLAT BY
AREAS
CHECKED BY

ORIGINAL SURVEY
NOTE BOOK
NO.
SURVEYED BY
PLAT BY
AREAS
CHECKED BY

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
2	OHIO		

176
492

END AREA	CUBIC YARDS

MAH-18-17.20

FINAL SURVEY — SURVEYED BY ... DRAWN BY ... TRACED BY ... CHECKED BY ... NOTE BOOK ... PAGE ... SCALE ... DATE ...

ORIGINAL SURVEY — SURVEYED BY ... DRAWN BY ... TRACED BY ... CHECKED BY ... NOTE BOOK ... PAGE ... SCALE ... DATE ...

962.32
FL I-14 960.00
955.61
928.63
931.17
932.12
934.54
936.96
937.96
943.27
943.98
RAMP "K"
13+44
1027+00
951.5

C-3493
F - 0

940

C-6517
F-0

943.27
FL I-14
962.27
955.89
931.45
932.26
934.68
937.10
938.10
941.81
942.61
RAMP "K"
12+91
1026+50
957.7

C-3545
F - 0

940

C-6480
F-0

963.36
962.12
956.17
931.56
932.22
934.64
937.06
937.73
940.40
941.20
RAMP "K"
12+37
1026+00
958.4

NOTE
11+77.85 TO 12+40.4 TOP WALL GR + 12.91%
12+40.4 TO 13+00.4 " " - 0.0%
13+00.4 TO 15+81 " " - 3.21%

C-3453
F - 0

950

C-6309
F-0

NOTE:
BEGIN RET WALL
STA 1025+21.81
959.64
FL I-14
958.64
ABUT.
931.52
932.03
934.41
934.41
936.80
936.96
939.05
939.85
RAMP "K"
11+85
1025+50
958.3

C-3361
F - 0

950

NOTE:
STA. 11+77.85
BEGIN RET. WALL

C-6002
F-0

SEE RAMP "L"
X-SECTIONS
78.92
ABUT.
ABUT.
931.56
931.89
934.00
934.00
936.18
937.67
938.47
RAMP "K"
11+33.57
1025+00
956.5

C-3121
F - 0

950

C-7048
F-0

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3. CROSS SECTION C.P.R.R.E. STANDARD
KRUPPEL & KESSER CO., NEW YORK.

1025+00 TO 1027+00

FED. RD.	STATE	PROJECT	
2	OHIO		

177
492

SEEDING	
END WIDTH	SQ YDS
49	
174 / 98	
49	
80	
40	
64	
34	
57	
29	
160 140 120 100 80 60 40 20	

END AREA	CUBIC YARDS

MAH-18-17.20
C-2680 ← → C-100

947.64 — 927.59 — 928.59 — 932.07 — 933.43 — 934.54 — 934.44 — 951.81

2:1 — 1/2:1

RAMP "K" 16+13

C-2880 ↓
C-100 ↓
F-0 ↓↑

940

NOTE: STA. 15+81
END RET. WALL

1029+50
948.5

949.56 — 928.67 — 929.67 — 932.09 — 934.51 — 935.56 — 935.46 — 949.98 — 949.70 — 955.32

2:1 — 12:1

RAMP "K" 15+58

C-5537
F-0

940

C-3000
F-0

1029+00
950.0

951.45 — 929.56 — 930.56 — 932.98 — 935.40 — 936.39 — 936.21 — 948.16 — 948.14 — 957.21

VARIES

RAMP "K" 15+04

C-5373
F-0

Fr. 954.0

C-2803
F-0

940

C-5546
F-0

1028+50
951.7

953.41 — 930.27 — 931.27 — 933.69 — 936.11 — 937.07 — 936.91 — 946.58 — 946.79 — 958.96

VARIES

RAMP "K" 14+54

Fr. I-14
958.0

C-3187
F-0

940

C-6093
F-0

1028+00
954.0

955.33 — 930.78 — 931.78 — 934.20 — 936.62 — 937.57 — 937.41 — 944.98 — 945.41 — 960.74

VARIES

RAMP "K" 13+99

Fr. I-14
958.5

C-3393
F-0

940

C-6376
F-0

1027+50
955.8

℄

PLATE 5 CROSS SECTIONS O.P. S. & R. E. STANDARD
REMPEL & REMPEL CO., NEW YORK

1027+50 TO 1029+50

FINAL SURVEY NOTE: TEMPORARY AREA SHOWN
NO. ADD'L SURVEYS
ORIGINAL SURVEY NOTE: TEMPORARY AREA SHOWN
NO. ADD'L SURVEYS

SEEDING	
END WIDTH	SQ YDS

FED. ID	STATE	PROJ.	
	CNTY.		

178
492

MAH-18-17.20	END AREA	CUBIC YARDS

FINAL
SURVEY
PLOTTED
NOTE BOOK
NO.
DATE
CHECKED
TRACED
QUANTITIES

ORIGINAL
SURVEY
PLOTTED
NOTE BOOK
NO.
DATE
CHECKED
TRACED
QUANTITIES

1A

N 6

940

940

940

940

C-4867
F-0

C-8537
F-0

C-4353
F-0

C-6835
F-0

C-3029
F-0

C-5281
F-0

C-2675
F-0

C-5144
F-0

957.05

955.58

957.05

955.58

954.68

954.68

ABUT.

ABUT

ABUT

RAMP "M"
6+50

RAMP "M"
5+97

RAMP "M"
5+45

1031+50
954.0

1031+00
952.5

1030+50
949.5

1030+00

10+78
10+78

11+27
11+27

923.56
923.78
924.64
926.73
929.1
931.66
931.98

923.88
925.13
927.50
927.50
928.87
930.03
931.40

926.08
928.50
930.92
931.35
931.85

927.32
929.74
932.16
933.37

NOTE:
STA 5+82.78 RAMP "M"
BEGIN RET. WALL
TOP WALL EL 950.59

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 CROSS SECTION © P.R.S.P.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK

1030+00 TO 1031+50

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT		179 492
2	OHIO			

MAH-18-17.20

	END AREA	CUBIC YARDS

FINAL SURVEY GROUND CHECKED NOTE BOOK CHECKED NO. CORRECTED

ORIGINAL SURVEY FIELD NOTE BOOK NO.




PLATE 7 CROSS SECTION O.D.O.T. E.E. STANDARD
REVISED 1-1-55 8-1-57 8-1-61

1032+00 TO 1033+50

SEEDING	
END WIDTH	SQ YDS

FED. RD.	STATE	PROJECT	
	CHIO		

180
492

MAH-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — SURVEYED / PLOTTED / PLOTTED / NOTE BOOK / CROSS SECTIONS / AREAS / CHECKED / DATE

ORIGINAL SURVEY — SURVEYED / PLOTTED / PLOTTED / NOTE BOOK / CROSS SECTIONS / AREAS / CHECKED / DATE




PLATE 3 CROSS-SECTION O.P.R.R.R.E. STANDARD
REMPEL & ESSLER CO., NEW YORK.

1034+00 TO 1034+91.44 END

FED. RD.	STATE	PROJECT	
2	OHIO		

181
492

FINAL SURVEY PLOTTED NOTE BOOK AREA AREAS CHECKED NO.

ORIGINAL SURVEY PLOTTED NOTE BOOK AREA AREAS CHECKED NO.

C = 0
F - 0

C - 6400

805+20
END WORK

960

C - 4320
F - 0

SEE RAMP N
X-SECTIONS

930.00
930.19
930.03
929.99
930.11

2:1

C = 19974
F - 0

928.88

927.99

806+00
END GRADING


PLATE 3 CROSS SECTION O.P.R.&R.E. STANDARD
KEUFFEL & ESSER CO. NEW YORK

SEEDING	
END WIDTH	S.Q YDS

182
492

MAH-18-17.20

END AREA	CUBIC YARDS



C-324
F - 0
960

C-214
F - 0
960

C - 83
F - 0
960

C - 39
F - 0
970

C - 17
F - 5
970

ORIGINAL SURVEY
SURVEYED
PLOTTED
CHECKED
NOTE BOOK
TRACED
CHECKED

FINAL SURVEY
INSPECTED
CUTTED
CHECKED
NOTE BOOK
TRACED
CHECKED

PLATE 3-CROSS SECTION U. S. C. & G. S. STANDARD
KEUFFEL & ESSER CO., NEW YORK.


RAMP "A" 0+00 TO 2+00

SEEDING	
END WIDTH	SQ YDS

STATE	STATE PROJECT	183 492
	OHIO	


MAH-18-17.20

END AREA	CUBIC YARDS




C- 795
F- 0

950




C- 702
F- 0

950



C- 485
F- 0

950



C- 272
F- 21

950

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3-CROSS SECTION O.P.R.R.R.L. STANDARD
KEUFFEL & ESSER CO., NEW YORK

RAMP "A" 2+50 TO 4+00


SEEDING

END WIDTH	SQ YDS


	184
	492

MAH-18-17.20


END AREA	CUBIC YARDS




C-1473 940



C-2073 940



C-2270 940



C-2402 940

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3-CROSS SECTIONS O.P.R.&R.E. STANDARD
KEUFFEL & ESSER CO. NEW YORK.

RAMP "B" 10+00 TO 11+50

FINAL SURVEY — CONTROL — STATION — NOTE BOOK — PAGE — AREAS CHECKED — NO.

ORIGINAL SURVEY — SURVEYED — STATION — NOTE BOOK — PAGE — AREAS — CHECKED — NO.

SEEDING
END WIDTH SQ. YDS.

185
492

MAH-18-17.20 END AREA CU. YDS

947.19 946.04 2:1 945.86 943.68

14+00
252.5

C-513

940

944.89 943.67 943.56 941.26

13+50
252.0

C-641

940

942.51 941.29 941.18 939.88

13+00
251.5

C-765

940

940.14 938.92 938.81 936.51

12+50
251.0

C-1015

940

937.76 936.54 936.43 934.13

12+00
251.0

C-1233
C-1222

940

100 80 60 40 20 CB 20 40 60 80 100

PLATE 3-CROSS SECTION O.P.R.R. & P.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

RAMP "B" - 12+00 TO 14+00

FINAL SURVEY
NOTE BOOK
NO.
BY
PLOTTED
CHECKED
MPLAT
AREAS CHECKED

ORIGINAL SURVEY
NOTE BOOK
NO.
SURVEYED
PLOTTED
TEMPLATE
AREAS CHECKED

SEEDING
END WIDTH SQ. YDS.

OHIO

186
492

MAH-18-17.20 END AREA CU. YDS.

15+88.54

C-150
F- 0

960

15+50

4:1 4:1

C-134
F- 0

960

950.72

15+00

2:1

C-229
F- 0

960

948.42

948.80 947.32

14+50

2:1

C-420
F- 0

100 80 60 40 20 0 20 40 60 80 100

PLATE 3 - CROSS SECTION O. F. P. & R. E. STANDARD
PEURFEL & ESSER CO., NEW YORK

RAMP "B" 14+50 TO 15+88.54 END

FINAL SURVEY PLOTTED
NOTE BOOK TRAVERSE
NO. PAR. SHEET

ORIGINAL SURVEY PLOTTED
NOTE BOOK TRAVERSE
NO. PAR. SHEET


SEEDING	
END WIDTH	SQ YDS

187
492


MAH-18-17.20	END AREA	CUBIC YARDS

FINAL SURVEY — DATE — BY
SURVEYED
PLOTTED
TRAVERSE
REPASTE
AREAS CHECKED
NOTE BOOK
NO


ORIGINAL SURVEY — DATE — BY
SURVEYED
PLOTTED
TRAVERSE
REPASTE
AREAS CHECKED
NOTE BOOK
NO



C-96



C-112





C-35

PLATE 1 CROSS SECTION U.S.P.R. & R.R.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK

RAMP "C" 0+00 TO 0+23.42

SEEDING	
END WIDTH	SQ YDS

MAH.-18-17,20	END AREA	CUBIC YARDS
		188 492

9.13.79

3+00

C - 0
F - 0

920

9.15.79

2+50

C - 0
F - 0

920

9.22.79

2+00

C - 0
F - 0

920

920.04 919.79

3:1 2:1

918.47

1+50

C-1073
F - 0

920

906.34

921.87 921.62

3:1 3:1

920.30 919.62

1+00

C-302
F - 0

920

922.31

3:1

920.9 920.7

0+50

C-216
F - 0

920

100 80 60 40 20 0 20 40 60 80 100

PLATE 3 CROSS SECTIONS C.P.R.R.R. LETCHWORTH
KEUFFEL & ESSER CO., NEW YORK

RAMP "C" 0+50 TO 3+00

ORIGINAL SURVEY
SURVEYED
PLOTTED
NOTE BOOK
NO.
TRACED
CHECKED
FINAL
DRAWING NO.
DATE
BY

SEEDING	
END WIDTH	SQ YDS


	189
	492

MAH-18-17.20

END AREA	CUBIC YARDS


FINAL SURVEY — SURVEYED / PLOTTED / SCALE / NOTE BOOK / PAGE / NO. / DATE / DRAFTSMAN / LAYOUT CHECKED

ORIGINAL SURVEY — SURVEYED / PLOTTED / SCALE / NOTE BOOK / PAGE / NO. / DATE / DRAFTSMAN / LAYOUT CHECKED




C - 66
F - 54.2

890




C - 232
F - 28

900




C - 422
F - 0

910



C - 0
F - 0

910



C - 0
F - 0

920

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3 CROSS SECTION O.F.P.R.&R.I. STANDARD
REUFFEL & ESSER CO., NEW YORK.

RAMP "C" 3+50 TO 5+50

SEEDING	
END WIDTH	SQ YDS

MAH.-18-17.20	END AREA	CUBIC YARDS
	190	492





PLATE 3-CROSS SECTION OF TYPICAL SEMI-CUT

RAMP "C" 6+00 TO 7+50 ; RAMP "C3" MAH.W.F 11+43.5

SEEDING	
END WIDTH	SQ YDS.

MAH-18-17.20	END AREA	CUBIC YARDS
C - 567		
F - 1018		

191
492



C - 842
F - 572

C - 1129
F - 989

C - 422
F - 3998

PLATE 1 CROSS SECTION SHEET 2 OF 2 SHEETS STANDARD
KEUFFEL & ESSER CO. NEW YORK

RAMP "C" 8+00 TO 9+50 ; RAMP "C3" MAH. W.F. 10+01.84 TO 11+00

SEEDING	
END WIDTH	SQ YDS

NO.	DATE	BY	
2	6-60		192
			432

MAH.-18-17.20

END AREA	CUBIC YARDS

C-3174
F- 0

C-2333
F- 0

F-65.1
C-101

C- 8
F-1705

C- 11
F-1828

880

880

880

880

FINAL SURVEY	SURVEYED	DATE
	PLOTTED	
	COMPUTED	
NOTE BOOK	TEMPLATE	
	AREAS	
NO.	AREAS CHECKED	

ORIGINAL SURVEY	SURVEYED	DATE
	PLOTTED	
NOTE BOOK	TEMPLATE	
	AREAS	
NO.	AREAS CHECKED	




PLATE 9 CROSS SECTION C.P.R.R.M.E. STANDARD
KENNEDY & DOUGLASS NEW YORK

RAMP "C" 10+00 TO 12+00; RAMP "C3" MAH.W.F 8+12 TO 9+64.46

SEEDING	
END WIDTH	SQ YDS

	193 492
MAH-18-17.20	END AREA / CUBIC YARDS

SEE RAMP C_3 X-SECTIONS

12:1

2:1

872.40 872.30 872.02

870.84

RAMP "C" 14+00

870.02

2:1

C-6328
F - 0

880

SEE RAMP C_3 X-SECTIONS

A927

12:1

2:1

873.06 873.02 872.93

871.45

RAMP "C" 13+50

870.93

C-4927
F - 0

880

2:1

A

A

2:1

866.87 871.53 874.05 874.10 874.20

867.37

RAMP "C_3" MAH. W.F. 7+38

870.23

872.26

RAMP "D_3" MAH.W.F

RAMP "C" 13+00

872.40

2:1

C-4570
F - 0

880

871.08 872.74 875.40 875.55 875.84

869.58

RAMP "C_3" MAH.W.F 7+72

871.44

873.61

RAMP "D_3" MAH.W.F

RAMP "C" 12+50

874.08

2:1

C-3247
F - 0

880

160 140 120 100 80 60 40 20 0 20 40 60 80 100 120 140 160

PLATE 3 - CROSS SECTION - U.S.P.R.R.A. STANDARD
KEUFFEL & ESSER CO., NEW YORK

RAMP "C" 12+50 TO 14+00 ; RAMP "C_3" MAH.W.F. 7+38 & 7+72

FINAL SURVEY — SURVEYED / PLOTTED / TEMPLATE / AREAS / AREAS CHECKED / NOTE BOOK / NO. / BY / DATE

ORIGINAL SURVEY — SURVEYED / PLOTTED / TEMPLATE / AREAS / AREAS CHECKED / NOTE BOOK / NO. / BY / DATE

SEEDING	
END WIDTH	SQ. YDS.

194
492

MAH-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOK / AREAS / AREAS CHECKED — DATE / BY

ORIGINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOK / AREAS / AREAS CHECKED — DATE / BY

SEE MAIN LINE X-SECTIONS

C-6849

12:1 12:1 2:1 2:1

872.82 872.67 871.48

870.42 869.03

RAMP "C"
15+50

880

SEE MAIN LINE X-SECTIONS

C-7467

12:1 12:1 2:1 2:1

872.35 872.12 871.30

870.57 869.18

RAMP "C"
15+00

880

SEE MAIN LINE X-SECTIONS

C-7762

12:1 12:1 2:1 2:1

872.21 872.03 871.48

870.72 869.57

RAMP "C"
14+50

880

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3-CROSS SECTION U.S.P.S. S.B.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK

RAMP "C" 14+50 TO 15+50

SEEDING	
END WIDTH	SQ YDS

	STATE	PROJECT	
	OHIO		

195
492

MAH.-18-17.20

END AREA	CUBIC YARDS

FINAL SURVEY
SURVEYED BY
PLOTTED
FIELD BOOK
NOTE BOOK
AREAS
ATLAS CHECKED
NO.
DATE

ORIGINAL SURVEY
SURVEYED BY
PLOTTED
FIELD BOOK
NOTE BOOK
AREAS
ATLAS CHECKED
NO.
DATE

C-5497

See Main Line X-Sections Sta. 951+50

874.41
874.22
872.89
871.54
871.5
2.23
868.73
16+50

2:1

870

See Main Line X-Sections

C-6244

873.61
873.36
872.03
869.91
869.9
2.27
868.88
16+00

870

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 3 - CROSS SECTION [illegible]
REVISED [illegible]

RAMP "C" 16+00 & 16+50

SEEDING	
END WIDTH	SQ YDS

148

STATE	PROJECT	196 492

MAN-18-17.20

END AREA	CUBIC YARDS
C-3042	910
	870
C-2953	920
	880
C-2798	920
	870

SEE MAINLINE X-SECTIONS STA. 953+00

868.31

RAMP "C" 17+89

SEE MAINLINE X-SECTIONS STA. 952+50

868.45

RAMP "C" 17+44

SEE MAINLINE X-SECTIONS STA. 952+00

868.59 RAMP "C" 16+98

℄ DITCH

20 40 60 80 100 120

RAMP "C" 16+98 TO 17+89

PLATE 3 CROSS SECTIONS FOR R & R C STANDARD
BEMENT & CLEARY CO., NEW YORK

FINAL SURVEY — SURVEYED, PLOTTED, TYMAGE, NOTE BOOK, MAPS, NO., AREAS CHECKED, BY, DATE

ORIGINAL SURVEY — SURVEYED, PLOTTED, TYMAGE, NOTE BOOK, MAPS, NO., AREAS CHECKED, BY, DATE

SEEDING

END WIDTH	50 YDS

197
492

MAH-18-17.20

	END AREA	CUBIC YARDS
10+50	848.1	
		860
		C - 28 F-1637 BK.S.F-137
		840
		C-56 F-3155
10+00	853.0	
		860
		C - 33 F-1770 BK.S.F-152
		840
		C-77 F-3217
9+50	857.8	
		860
		C-50 F-1704 BK.S.F-163
		840
		C-60 F-3125
9+00	862.5	
		860
		C-15 F-1671 BKSF-100
		840
		C-14 F-3024
8+50	866.80	
		860
		C-0 F-1595 BK.S.F-90
		C-0 F-1716 840

864.76 | 864.43 | 866.72 | 866.20 | 868.67 | 867.97 | 870.54 | 869.74 | 872.31 | 871.51

2:1 | 1½:1

SEE RAMP "B3" X-SECTIONS

BANK SLAG FILL

42" MUSD WATER | 33" SEWER

TOP BANK 60'

TOP BANK 58'±

96'± EDGE WATER EL. 829.5±

100'± EDGE WATER EL. 829.4

VARIES

100 80 60 40 20 0 20 40 60 80 100

PLATE 3 - CROSS SECTIONS - O.P.R.R.R.E. STANDARD
SCHEFFEL & ESSER CO., NEW YORK.

RAMP "D" 8+50 TO 10+50

ORIGINAL SURVEY
NOTE BOOK
NO.

FINAL SURVEY
NOTE BOOK
PAGES
NO.


SEEDING
END WIDTH SQ. YDS.

PROJ. 198
492

MAH.-18-17.20 END AREA CU. YDS.

FINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOK / TRACED / CHECKED / NO. / DATE

ORIGINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOK / TRACED / CHECKED / NO. / DATE



C - 10
F - 1633
BK S.F. - 42.

C - 28
F - 2927

C - 20
F - 1528
BK S.F. - 108

C - 38
F - 2774

C - 21
F - 1468
BK S.F. - 63

C - 18
F - 2851

C - 0
F - 1611

C - 0
F - 3092

C - 0
F - 1728

C - 26
F - 3116

840


PLATE 3 - CROSS SECTION N.Y.P.A. & M.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

RAMP "D" 11+00 TO 13+00

SEEDING
END WIDTH SQ. YDS.

PROJECT 199 492

MAH.-18-17.20 END AREA CU.YDS.



C - 0
F - 6.77
BK.S.F - 81

C - 0
F - 1047

C - 0
F - 454

C - 0
F - 849

C - 0
F - 463

C - 0
F - 1040

C - 0
F - 660

C - 11
F - 1502

C - 12
F - 962
BK.S.F - 64

C - 28
F - 2305

C - 18
F - 1527
BK.S.F - 105

C - 26
F - 2926

PLATE 3 CROSS SECTION O.T.P.S.R.R. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

RAMP "D" 13+50 TO 16+00

SEEDING
END WIDTH SQ. YDS.

MAH-18-17.20

END AREA CU. YDS.

			C-0 F-0
			C-122 F-93
			C-132 F-100
			C-202 F-344
			C-86 F-272 BK.S.F-72
			C-205 F-497
			C-135 F-265 BK.S.F-95
			C-245 F-512
			C-130 F-288
			C-157 F-578
			C-40 F-336
			C-37 F-938

840

840

840

840

19+09.78

12:1

841.53

12:1

839.92

18+50

12:1

842.00

841.52

841.13

12:1

840.11

BANK SLAG FILL

18+00
842.3

12:1

842.62

842.16

841.80

8:1

840.31

BANK SLAG FILL

2:1

17+50
843.0

841.30

842.94

842.61

12:1

841.84

17+00
843.8

847.00

844.01

12:1

842.91

16+50
844.3

120 100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3-CROSS SECTION O.P.R. & N.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

RAMP "D" 16+50 TO 19+09.78


FINAL SURVEY
SURVEYED
PLOTTED
NOTE BOOK
NO.
TRACED
CHECKED
CROSS SECTIONS


ORIGINAL SURVEY
SURVEYED
PLOTTED
NOTE BOOK
NO.
TRACED
CHECKED
CROSS SECTIONS


		PROJECT	200 492

MAH.-18-17.20

McKINLEY AVE.







ORIGINAL SURVEY
DRAWN
CHECKED
TRACED
NOTE BOOK
AREAS
NO.
FINAL SURVEY
DRAWN
CHECKED
TRACED
NOTE BOOK
AREAS
NO.

PROJECT 202 492
MAR-18-1720

FINAL SURVEY
ORIGINAL SURVEY SURVEYED PLOTTED FINAL AS NOTE BOOK

RAMP "E"

PARK R.D.

111.4' TO ℄ Y.E.
SEE Y.E. X-SECTIONS STA. 958+50
C - 2955
2:1
896.30
895.67
894.79
5+73
RAMP "E"
893.67
2:1
1"/1'
920.49
2:1
918.30
7+96
C - 740
920

C - 2401
2:1
897.69
897.12
896.16
5+50
RAMP "E"
895.12
2:1
921.76
1"/1'
919.69
8+17
C - 495
930
900

C - 2124
2:1
900.70
900.27
899.19
5+00
RAMP "E"
898.27
2:1
923.36
1"/FOOT
8+66
921.30
C - 280
930
900

C - 1050
2:1
903.71
903.42
902.16
4+50
RAMP "E"
901.42
2:1
924.42
1" PER FOOT
END PARK RD.
9+34.87
C - 135
930
900

100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160 180

PLATE 3 - CROSS SECTION O. P. R. & R. STANDARD
KRUTTER & EGERS CO., N.Y. YORK.

RAMP "E" 4+50 TO 5+73 ; PARK RD. 7+96 TO 9+34.87

203
492

MAH.-18-17.20

SEE Y.E.
X-SECTIONS
STA. 960+50

901.66

2:1

1:1

890.58

PARK ROAD
5+88

C=1082

900

SEE Y.E.
X-SECTIONS
STA. 960+00

906.28

2:1

1½:1

1½:1

904.29

PARK ROAD
6+38
℄

C=1091

910

SEE Y.E.
X-SECTIONS
STA. 950+50

912.016

1:1

1½:1

908.63

PARK ROAD
6+86

C=1096

910

889.24

888.64

2:1

886.64

RAMP "E"
6+85

NOTE:
END RETAINING WALL
@ STA. 7+25 PARK RD.

92.1' ℄ Y.E.

SEE Y.E.
X-SECTIONS
STA. 950+00

915.88

1½:1

1½:1

PARK ROAD
7+42
℄

913.80

C=1070

910

893.11

892.33

2:1

801.59

RAMP "E"
6+26

800.25

80 60 40 20 ℄ 20 40

PLATE 5 CROSS SECTION U.S.P.R.A.&E. STANDARD
STOTZEL & ESSER CO., NEW YORK.

RAMP "E" 6+26 TO 6+85 PARK RD 5+88 TO 7+42

FED. RD.	STATE	PROJECT	
2	OHIO		

204
492


MAH-18-17.20

RAMP "F" 10+00 TO 13+00; RAMP "H" 4+45 TO 5+50

PLATE 3 CROSS SECTION © P. R. & R. C. STANDARD
KEUFFEL & ESSER CO., NEW YORK

ORIGINAL SURVEY — NOTE BOOK

FINAL SURVEY — NOTE BOOK



RAMP "F" 13+50 TO ; RAMP "H" TO 3+85

MAH-18-17.20

2	FED. RD.	STATE
OHIO		
	PROJECT	

205
432

FED. RD.	STATE	PROJECT	
2	OHIO		

206
492

M.A.H.-18-17.20

FINAL SURVEY

ORIGINAL SURVEY

9+50

C-3196

4:1 892.83 895.11 890.15 4:1 892.54 1:1 2:1

9+00

C-2635
C-2646

4:1 895.83 898.11 893.15 4:1 897.79 1:1 2:1

8+50

C-2197

4:1 898.83 901.11 896.15 4:1 900.79 1:2 2:1

8+00

C-2966

4:1 901.97 904.11 899.15 4:1 903.56 1:2 2:1

7+50

C-2511

4:1 905.11 907.11 902.15 4:1 906.31 1:2 2:1

7+00

C-2127

4:1 908.11 910.11 905.15 4:1 909.07 1:2 2:1

6+50

C-1473

4:1 911.11 913.11 908.15 4:1 911.81 1:2 2:1

6+00

C-1341
C-1351

4:1 914.11 916.11 911.15 4:1 914.45 1:2 2:1

920 910 900 890

80 60 40 20 0 20 40 60 80

PLATE 5 - CROSS SECTION O. P. R. & R. E. STANDARD
REINTEL & KESSLER CO., NEW YORK.

RAMP "H" 6+00 TO 9+50

STATE	PROJECT
OHIO	

MAH.-18-17.20

207
492

FINAL SURVEY	BY	DATE
NOTE BOOK	PLOTTED	
NO.	TEMPLATE	
	AREAS	
	CHECKED	

ORIGINAL SURVEY	SURVEYED	BY	DATE
	PLOTTED		
NOTE BOOK	TEMPLATE		
NO.	AREAS		
	CHECKED		

B

B

1:2

4:1

877.79

880.07

881.11

817.41

12+10

C=3865

890

A

A

1:2

4:1

880.12

882.40

883.44

876.91

11+65

C=3822

890

1:2

882.95

884.93

885.97

882.41

11+20

C=3972

890

1:2

886.63

888.91

888.95

881.91

10+70

C=3700

900

1:2

888.23

890.61

891.65

883.41

10+25

C=3600

900

1:2

891.29

893.57

894.61

884.91

9+80

C=3274

900

80

60

40

20

℄

PLATE 1: CROSS SECTION O. P. R. & R. E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

RAMP "H" 9+80 TO 12+10

ORIGINAL SURVEY	SURVEYED	BY	DATE
	PLOTTED		
NOTE BOOK	TEMPLATE		
NO	AREAS CHECKED		

FINAL SURVEY	SURVEYED	BY	DATE
	PLOTTED		
NOTE BOOK	TEMPLATE		
NO	AREAS		
	ATLAS CHECKED		

RAMP "K" 16+50 TO 19+23.48

964.43

19+23.48
964.47

960

963.47

19+00
963.88

C- 28

960

961.24

NOTE: END 12" I-22
STA 18+50

C- 38 ↑
C- 43 ↑

18+50
962.01

960

C- 55

18+00
960.24

957.15

C- 80

17+50
958.00

950

955.38

955.04

C- 54

17+00
956.30

950

953.27

952.95

C- 88

16+50
954.50

950

60 40 20 0 20 40 60

MAH:18-17.20

OHIO

206
492

FED. RD.	STATE	PROJECT	
2	OHIO		

203
432

MAH.-18-17.20

FINAL SURVEY DATA

ORIGINAL SURVEY DATA




PLATE 3 - CROSS SECTION © P.R.A.P.E. STANDARDS
KEUFFEL & ESSER CO., NEW YORK

RAMP "L" 3+00 TO 4+50

ORIGINAL SURVEY	SURVEYED	BY	DATE
	PLOTTED		
NOTE BOOK	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

FINAL SURVEY	SURVEYED	BY	DATE
	PLOTTED		
NOTE BOOK	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

940.71

C = 0
F = 10

940

0+00
940.2

942.36

C = 2
F = 9

940

0+50

944.02

C = 18
F = 0

940

1+00

945.60

C = 47
F = 0

940

1+50

947.13

C = 87
F = 0

950

2+00

946.84

C = 167
F = 0

950

2+50

60 40 20 ℄ 20 40 60

RAMP 'L' 0+00 TO 2+50

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-[illegible]-17.20

210
452

	PROJECT	

211
492

MAH-18:17.20

951.02
949.35
2:1
4:1
949.85
10+50
946.85
4:1
2:1
962.9
C-3077
960

948.77
947.10
2:1
4:1
947.48
10+00
944.60
2:1
962.7
963.2
C-2835
960

SEE STA. 1034+50
Y.E. X-SECTIONS
20'
946.40
944.86
2:1
4:1
945.09
9+50
942.44
2:1
962.3
962.8
C-2579
960

SEE STA. 1034+00
Y.E. X-SECTIONS
19.62'
943.78
942.61
2:1
4:1
942.40
9+00
948.70
947.20
V
961.5
962.0
C-1914
950

960.74
959.24
960.0
18.96'
941.18
940.37
SEE STA. 1033+50
Y.E. X-SECTIONS
8+50
C-1727
950

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3 CROSS SECTION OF N.Y.S.B.P.C. STANDARD
KEARFOTT & FERGUSON, NEW YORK

RAMP "M" 8+50 TO 10+50

FINAL SURVEY
SURVEYED
PLOTTED
TRACED
NOTE BOOK
NO.
DATE
CHECKED

ORIGINAL SURVEY
SURVEYED
PLOTTED
TRACED
NOTE BOOK
NO.
DATE
CHECKED

FED. HWY.	STATE	PROJECT	
2	OHIO		

212
432

MAH.-18-17.20




PLATE 3 - CROSS SECTION O.D.P.R.R.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK

RAMP "M" 11+00 TO 13+50

FINAL SURVEY
SURVEYED
PLOTTED
NOTE BOOK
NO.
CHKD.
CHECKED

ORIGINAL SURVEY
SURVEYED
PLOTTED
NOTE BOOK
NO.
CHKD.
CHECKED

FED. RD.	STATE	PROJECT	
2	OHIO		

213
492

MAH-18-17.20

FINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOK / NO. — DATE / BY / SHEETS / AREAS CHECKED

ORIGINAL SURVEY — SURVEYED / PLOTTED / NOTE BOOK / NO. — DATE / BY / SHEETS / AREAS CHECKED

961.57

16+33.57
END

962.77

16+00

964.95

364.55

2:1

15+50

966.01

965.61

3:1

3:1

965.04

15+00

963.83

966.37

965.68

3:1

4:1

3:1

964.89

14+50

963.68

965.72

964.74

3:1

4:1

2:1

964.30

14+00

962.65

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3 - CROSS SECTION O.P.P.&R.E. STANDARD

C- 4 960

C- 21 960

C-215 970

C-502 970

C-590 970

C-635 970

FED. RD	STATE	PROJECT		214 492
7	OHIO			

MAH-18-17.20

0+00 — ℄ MARLIN AVE.

C - 0
F - 0

0+50

C - 20
F - 0

930

1+00

C - 2
F - 0

930

1+50 — ℄ MARLIN AVE.

937.15

C - 2
F - 0

930

2+00

939.40 940.18

C - 12
F - 0

940

2+50

940.90 942.02

C - 108
F - 0

940

3+00 — ℄ MARLIN AVE. STA. 3+15

C - 385

940

3+50

940.40 941.28

C - 503

940

120 100 80 60 40 20 ℄ 20 40 60 80 100 120

PLATE 3 - CROSS SECTION O.P.W.A.I. STANDARD

FED. RD.	STATE	PROJECT	
	OHIO		

215
492

MAH-18-17.20

FINAL SURVEY PLOTTED FROM FIELD NOTE BOOK NO. DATED

ORIGINAL DRAWING SURVEY PLOTTED FROM FIELD NOTE BOOK NO. DATED




PLATE 3 CROSS SECTION O.P.R.&R.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

RAMP "N" 4+00 TO 5+50

FED.	STATE	PROJECT	
	OHIO		

216
492

MAH.-18-17.20




PLATE 5 - CROSS SECTION O. P. R. & R. E. STANDARD

FINAL SURVEY
SURVEYED BY
DRAWN BY
TRACED BY
CHECKED BY
DATE
NO. OF SHEETS

ORIGINAL SURVEY
SURVEYED BY
DRAWN BY
TRACED BY
CHECKED BY
DATE
NO. OF SHEETS

FED. RD.	STATE	PROJECT	
2	OHIO		

217
492

MAH-18-17.20

68.79'

72'

895.05

RAMP A_3

A

883.8

2:1

901.36

F = 3394

F = 4216

C = 12
F = 7610

860

2:1

A

880

879.5

170

1+00
853.0

C = 0
F = 0

860

0+50
856.5

C = 0
F = 0

860

0+00 AH.
14+43.71 BK.
858.0

140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140

PLATE 3. CROSS SECTION O. P. R. & R. E. STANDARD
FENCELL & ESSER CO., NEW YORK

FINAL SURVEY
NOTE BOOK
PAGE
NO.

ORIGINAL SURVEY
NOTE BOOK
PAGE
NO.
DATE
COMPUTED
PLOTTED
CHECKED

FED. RD.	STATE	PROJECT	
2	OHIO		

218
497

MAH-18-17.20

ORIGINAL SURVEY	SURVEYED BY
	PLOTTED
NOTE BOOK	PROFILE
NO.	AREAS
	AREAS CHECKED
	DATE

FINAL SURVEY	SURVEYED BY
	PLOTTED
NOTE BOOK	PROFILE
NO.	AREAS
	AREAS CHECKED
	DATE

RAMP A_3

900.35 901.08 902.71 903.04 903.04

2:1

866.7

875.60

C: 15
F: 10163

860

2+50
850.5

45.65 54.0

898.77 899.49 902.15 902.48 902.48 902.15

RAMP A_3

2:1

890.50

870.3

C: 18
F: 10634

856.00

860

2+00
851.0

56.01

896.94 897.66 901.59 901.92 901.92 901.59

RAMP A_3

2:1

889.0

A

C: 33
F: 9931

853.09

860

1+50
852.5

874.60 160

A

160 140 120 100 80 60 40 20 0 20 40 60 80 100 120 140 160

PLATE 3 CROSS SECTION O.D.P.W. & R.R. STANDARD
KOVILL & FISHER CO., YOUNGSTOWN

MAHONING W FEDERAL EXPRESSWAY 1+50 TO 2+50

FED. RD.	STATE	PROJECT	
2	OHIO		

213
492

MAH-18-17.20

FINAL SURVEY — DATE — BY
STAKED
PLOTTED
NOTE BOOK
NO.
AREAS CHECKED

ORIGINAL SURVEY — DATE — BY
SURVEYED
PLOTTED
TRACED
NOTE BOOK
NO.
AREAS CHECKED

RAMP A_3

903.82 904.53 904.72 904.80 904.72 904.72 904.80 904.69

2:1

857.5

4+00
841.0

902.74 903.79 903.98 904.16 904.16 904.16 904.16 903.92

RAMP A_3

2:1

859.0

3+50
853.0

901.65 902.42 903.33 903.52 903.60 903.60 903.27

RAMP "A"3

2:1

861.3

3+00
854.0

RAMP B_3

903.96 902.99

2:1

'B'

12:1

845.12

2:1

160

'B' 850

C = 20
F = 14985

900.0

902.59 901.32

RAMP 'B'3

2:1

C = 17
F = 14793

'A'

2:1

12:1

844.87

160

"A" 850

887.6

C = 15
F = 8916

850

160 140 120 100 80 60 40 20 ℄ 20 40 60 80 100 120 140 160

PLATE 5 CROSS SECTION C.P.F. & S. C. STANDARD
RENTSCH & ESSER CO., NEW YORK

MAHONING W. FEDERAL EXPRESSWAY 3+00 TO 4+00

FED. RD.	STATE	PROJECT	
2	OHIO		

220
492

MAH.-18-17.20

FINAL SURVEY
SURVEYED
PLOTTED
NOTE BOOK
AREAS
AREAS CHECKED
NO.

ORIGINAL SURVEY
SURVEYED
PLOTTED
NOTE BOOK
AREAS
AREAS CHECKED
NO.

5+50
842.0

850

1.65%

905.18 905.37 905.36 5+00 841.0 905.28 905.28 905.36 905.37 904.38

904.95

950

C=0
F=5960

℄ 33" SEWER

A

2:1

16:1

A

C=0
F=11742

A

24" 846.72

160

A

851.37

950

A

4+50
841.0

℄

160 140 120 100 80 60 40 20 20 40 60 80 100 120 140 160

PLATE 1 CROSS SECTIONS

MAHONING W. FEDERAL EXPRESSWAY 4+50 TO 5+50

FED. RD.	STATE	PROJECT	
2	OHIO		

221
492

MAH-18-17.20

FINAL SURVEY — SURVEYED / PLOTTED / TRACED / AREAS / LAYOUT CHECKED — NOTE BOOK — PAGE — NO.

ORIGINAL SURVEY — SURVEYED / PLOTTED / TRACED / AREAS / LAYOUT CHECKED — NOTE BOOK — PAGE — NO.

880
850
840

862.0 — 2:1 — 893.07 — 892.21 — 2:1 — 12:1 — 844.10 — 2%

9+00
855.3

C - 0
F - 5286

SEE RAMP "D" X-SECTIONS

LOW POINT
RAMP "D" STA. 14+00
EL. 844.0

862.5 — 2:1 — 890.20 — 889.60 — 2:1 — 12:1 — 844.31 — 2%

8+50
855.2

SEE MAIN LINE X-SECTIONS

C - 0
F - 4818

863.0 — 2:1 — 887.32 — 884.99 — 2:1 — 12:1 — 844.75 — 2%

8+00
855.0

8" 12" W.V.SD. WATER EXISTING TO BE REMOVED.

C - 0
F - 4246

SEE RAMP "D" X-SECTIONS

140 120 100 80 60 40 20 0 20 40 60 80 100 120 140 160

PLATE 3 - CROSS SECTION C.P.R.R.R.E. STANDARD.
KELLER & GOLDEN CO., NEW YORK.

RAMP "B3" 8+00 TO 9+00

FED. RD.	STATE	PROJECT	
2	OHIO		

222
492

MAH.-18-17.20

FINAL SURVEY — SURVEYED, PLOTTED, TEMPLATE, NOTE BOOK, PAGES, NO., AREAS CHECKED, BY, DATE

ORIGINAL SURVEY — SURVEYED, PLOTTED, TEMPLATE, NOTE BOOK, PAGES, NO., AREAS CHECKED, BY, DATE




PLATE 3 CROSS SECTION O.F.R.&B.P. STANDARD
REUTTEL & ESCHLEMAN NEW YORK

RAMP "B" 9+50 TO 10+50

FED. RD.	STATE	PROJECT
7	OHIO	

223
492

MAH-18-17.20

FINAL SURVEY
ORIGINAL SURVEY
NOTE BOOK
NO.
PLOTTED
CHECKED
TRAVERSE
DATE
SCALE SHOWN

SEE RAMP "C" X-SECTIONS

12:1

2:1

869.52

867.86

868.22

RAMP C_3 MAH.W.F.
6+50

865.44

2:1

C=6162
F=0

870

SEE MAIN LINE X-SECTIONS

12:1

2:1

869.08

867.42

867.78

RAMP "C_3" MAH.W.F.
6+00

865.00

2:1

C=5507
F=0

870

SEE MAIN LINE X-SECTIONS

2:1

869.15

867.49

866.60

RAMP "C_3" MAH.W.F.
5+50

864.50

2:1

C=2595
F=0

870

120 100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 7 CROSS SECTIONS C & E & E STANDARD
ROBERT B. ROGGE CO., NEW YORK

RAMP "C" MAHWF 5+50 TO 6+50


FED. RD	STATE	PROJECT	
2	OHIO		

224
492

MAH.-18-17.20

FINAL SURVEY | COMPUTED / PLOTTED / CHECKED / AREAS | BY / DATE

ORIGINAL SURVEY | SURVEYED / PLOTTED / CHECKED / AREAS | BY / DATE



C-3792
F-10

870

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3 CROSS SECTION A.R.B.A. & B.E. STANDARD
KEUFFEL & ESSER CO. [illegible]


RAMP "C3" MAH. W.F. 7+00

SEEDING	
END WIDTH	SQ YDS

	225
	492

MAH-18-17.20

END AREA	CUBIC YARDS





RAMP "C3" MAH.W.F. 12+00 & 13+00

FED. RD.	STATE	PROJECT	
2	OHIO		

22G
492


MAH-18-17.20






ESTIMATED QUANTITIES PER LIN. FT.					
①	CU. YDS. FOOTER	CONC. WALL	REINF. STL. LBS.	EXCA. CU. YDS	C.Y. POROUS BACKFILL
1'-0"	.0702	.083	6.841	.656	–
1'-6"	.0702	.095	7.181	.687	–
2'-0"	.0702	.107	7.515	.734	.098
2'-6"	.0702	.120	7.849	.786	.136
3'-0"	.0702	.132	8.350	.833	.173
3'-6"	.0702	.145	8.684	.885	.210
4'-0"	.0702	.159	9.018	.932	.247

① HEIGHT OF WALL ABOVE GROUND.



TYPICAL RETAINING WALL



① 1" T-35 ASPHALTIC CONCRETE SURFACE COURSE - TYPE 'C' (70-85)

② 2" B-35 ASPHALTIC CONCRETE LEVELING COURSE (70-85)

④ T-30 BITUMINOUS TACK COAT 0.10 GAL. PER SQ. YD.

⑤ 9" B-70 PORTLAND CEMENT CONCRETE BASE COURSE

⑥ 6" I-22 SUBBASE

⑦ I-12 COMBINED CURB & GUTTER - TYPE 2

⑧ L-9 SEEDING & PROTECTING


⑨ 5" I-13 CONCRETE SIDEWALK - - INCLUDING 5" CINDER SUBBASE

TYPICAL SECTION - OAKWOOD AVE.

FED. RD.	STATE	PROJECT	
&	OHIO		

MAH-18-17.20

227
492



ITEM E-8 EXIST. CURB REMOVAL (LIN. FT.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
A-1	0+12	4+60.66	13.5'L.	485
A-2	0+12	3+06	13.5'R.	363
A-3	3+28	5+94.66	13.5'R.	299

ITEM I-12 CONC. CURB REPLACE (LIN. FT.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
G-1	0+12	3+53.61	20.5'L.	355.87
G-2	0+12	3+06	13.5'R.	349.35
G-3	3+28	5+94.66	13.5'R.	292.11

ITEM I-8 M.H. ADJUSTED TO GRADE (EA.)

CODE	STA.	LOCA.	TOP ELEV.	REMARKS
E-1	0+38	ON ℄	972.17	
E-2	3+58	ON ℄	970.20	

ITEM E-8 EXIST. SIDEWALK REMVL. (S.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
B-1	0+12	3+06	24'R.	1470
B-2	0+12	3+53.61	24'L.	1705
B-3	3+28	5+95.66	24'R.	1335

ITEM I-13 CONCRETE STEPS

CODE	WIDTH	Nº OF RISERS	RISER	TREAD	L.F.
S-1	4'-0"	2	8"	12"	2.5
S-2	3'-0"	2	6½"	12"	2.5
S-3	4'-0"	1	8"	12"	1.25

ITEM I-13 CONC. SIDEWALK REPLACE. (S.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
H-1	0+16	3+01	24'R.	1425
H-2	0+22	3+53.61	27'L.	1355
H-3	3+33	5+95.66	24'R.	1260

ITEM I-18 INLETS YNGSTN. TYPE II (EA.)

CODE	STATION	LOCA.	WIND. FT.	C.B. INV.	
D-1	0+12	45.45ℓ	984.01	980.01	
D-2	2+73.94	13.5'R	974.50	969.50	
D-3	0+45.06	PORTL.	972.48	967.48	
D-4	0+45.60	PORTL.	971.07	966.07	
D-5	3+46.78	20.5'L.	970.21	965.21	
D-6	5+87.83	13.5'R	958.59	953.59	

ITEM I-2 COMB. SEWER (UNDER PAV'T. & APPROACHES) SEC. M-6.8(6)

CODE	FROM	TO	LOCA.	SIZE.	LIN. FT.
C-1	D-1	M.H. 0+00	RT.	12"	20
C-2	D-2	2+84	RT.	12"	18
C-3	D-3	℄ PORT.	RT.	12"	16
C-4	D-4	SEWER	RT.	12"	16
C-5	D-5	E-2	LT.	12"	25
C-6	D-6	5+02	RT.	12"	14

ITEM E-8 REMOV. & DISP. OF EXIST. WEARING COURSE

CODE	FROM STA.	TO STA.	SQ. YDS.	REMARKS
K-1	0+10	1+00	281	
K-3	2+50	3+58.61	311	

ITEM E-8 FULL DEPTH REMOV. & DISP. OF EXIST. PAV'T.

CODE	FROM STA.	TO STA.	SQ. YDS.	REMARKS
K-2	3+53.61	6+41.66	864	


ITEM I-124 WATER VALVE BOXES ADJ. TO GR. (EA.)

CODE	STA.	LOCA.	TOP ELEV.	REMARKS
M-1	3+33	5'L OF ℄	971.43	MAIN LINE

DRIVEWAYS

TYPE	CODE	STATION	LOCA.	TYPE	LIMIT OF WORK REQ'D.	S.T-10 S.Y.	S.T-35 Y.	T-1 PCC DRIVEWAY APPROACH S.Y.
SINGLE	J-1	1+09	LT.	BR. RIBBON	45' FROM ℄	20		7
SINGLE	J-2	1+50	LT.	ASPHALT	35' FROM ℄		.75	7
SINGLE	J-3	1+97	LT.	CONC.	35' FROM ℄	9		7
SINGLE	J-4	2+48	LT.	ASPHALT	35' FROM ℄		.75	7
SINGLE	J-5	2+90	LT.	ASPHALT	35' FROM ℄		.75	7
SINGLE	J-6	3+40	LT.	ASPHALT	NONE REQ'D.			7
SINGLE	J-7	4+60	RT.	CONC.	35' FROM ℄	12		7

FB. 25, PG. 45-55
FB. 8, PG. 4-6



OAKWOOD AVE. IMPROVEMENT

SCALES: HOR. 1" = 50'
VER. 1" = 5'

PLATE 4—CROSS SECTION OF PAVEMENT
REMINGTON RAND CO., NEW YORK


FED. RD	STATE	PROJECT	
2	OHIO		

228/492

MAH - 18 - 17.20

N.E. CURB RETURN CURVE DATA

Δ = 89° 29' 21"
R = 25.00'
T = 24.78'
L_c = 39.04'
P.C. = 50+45.28
P.T. = 0+36.78




S.E. CURB RETURN CURVE DATA


Δ = 90° 30' 39"
R = 25.00'
T = 25.22'
L_c = 39.49'
P.C. = 49+61.38
P.T. = 0+37.22

INTERSECTION - OAKWOOD & MARYLAND

NOTE: CURB RET. ELEVA'S. SHOWN ARE TOP OF CURB GRADES



INTERSECTION - OAKWOOD & RAMP 'A'




S.W. CURB RETURN CURVE DATA

Δ = 89° 22' 30"
R = 25.00'
T = 24.73'
L_c = 38.99'
P.C. = 2+80.77
P.T. = 0+38.23

S.E. CURB RETURN CURVE DATA

Δ = 90° 37' 30"
R = 25.00'
T = 25.27'
L_c = 39.56'
P.C. = 0+38.77
P.T. = 3+55.77

INTERSECTION - OAKWOOD & PORTLAND



INTERSECTION - OAKWOOD & LAKEVIEW

PAVEMENT DETAILS - OAKWOOD AVE.

ORIGINAL SURVEY	SURVEYED	BY	DATE
	PLOTTED		
NOTE BOOK	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

FINAL SURVEY	SURVEYED	BY	DATE
	PLOTTED		
NOTE BOOK	TEMPLATE		
NO.	AREAS		
	AREAS CHECKED		

SEEDING	
END WIDTH	SQ. YDS.
7	78
7	35
7	50
11	50
7	22
7	

END AREA		CU. YDS.	
CUT	FILL	CUT	FILL
		14.1	0.2
15.0	0.3		
		57.6	1.3
16.2	0.4		
		29.7	0.8
15.8	0.4		
		32.1	0.4
18.8	0.0		
		32.4	
16.2			
		15.6	
21.0			
		8.4	
0.0			

W.A. REQ'D

DRIVEWAY @ 2+30

973.36

974

972

3+00

(973.24)

W.A. REQ'D

DRIVEWAY @ 1+97

1:1

980.47

982

980

2+00

(980.22)

W.A. REQ'D

DRIVEWAY @ 1+50

984.08

984

982

1+50

(983.87)

W.A. REQ'D

DRIVEWAY @ 1+05

987.69

990

988

986

1+00

(987.50)

991.30

992

990

0+50

(991.25)

993.36

994

992

0+21.5

(993.29)

℄ 5' N. SWK. ON MARYLAND

994.31

994

992

0+00


℄ OAKWOOD & MARYLAND

50 40 30 20 10 ℄ 10 20 30 40

X - SECTIONS OAKWOOD AVE. STA. 0+00 - STA. 3+00

2	FED. RD.
OHIO	STATE
	PROJECT
	MAH-18-17.20


229
492



ORIGINAL SURVEY
NOTE BOOK
NO.
SURVEYED
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED
FINAL SURVEY
NOTE BOOK
NO.
SURVEYED
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED
50 40 30 20 10 0 10 20 30 40 50
7+00
955.11
956
954
958
956
956.68
6+50
(956.68)
MEET EXIST. PAV'T.
960
958
0.0
958.70
6+00
(958.62)
963
961
1.1
1.2
960.72
5+50
(960.02)
965
963
6.4
5.7
962.82
5+00
(963.27)
V.A. REQ'D
FOR DRIVEWAY
AT STA. 4+60±
967
965
9.1
4.1
0.0
965.37
4+50
(965.58)
971
969
9.4
0.4
6.0
0.4
967.00
4+00
(967.04)
971
969
7.0
0.3
9.1
0.3
969.30
3+75
969.09
972
970
11.1
0.8
14.8
1.6
970.62
3+50
970.37
973
971
14.0
0.7
15.5
971.23
3+25
971.73
X-SECTIONS
OAKWOOD AVE
STA. 3+25 - STA. 6+50
MAH-18-1720
STATE
PROJECT
230
492

FED. RD.	STATE	PROJECT	
2	OHIO		

231
492

MAH-18-17.20





TYPICAL SECTION
STA. 0+0 TO STA. 5+91.01
SILLIMAN STREET

(1) 1" T-35 ASPHALTIC CONCRETE SURFACE COURSE TYPE "C" (70-85)
(2) 2" B-35 ASPHALTIC CONCRETE LEVELING COURSE (70-85)
(3) B-35 ASPHALTIC CONCRETE PRELEVELING COURSE VARIABLE THICKNESS (70-85)
(4) T-30 BITUMINOUS TACK COAT 0.10 GAL. PER SQ. YD.
(5) 9" B-70 PORTLAND CEMENT CONCRETE BASE COURSE
(6) 6" I-22 SUBBASE
(7) I-12 COMBINED CURB & GUTTER TYPE 2
(8) L-9 SEEDING & PROTECTING
(9) 5" I-13 CONCRETE SIDEWALK- INCLUDING 5" CINDER SUBBASE

SILLIMAN STREET

B.M. #122 ELEV. 938.21
TOP BOLT FIRE HYDRANT
S.E. CORNER STEEL ST.
& SILLIMAN ST.

NOTE: FIRE HYDT. ON S.E. COR. SILLIMAN & STEEL TO BE MOVED & RESET ON THE N.E. COR. (LOCA. TO BE DETERMINED IN THE FIELD BY THE ENGR.)

B.M. #3 ELEV. 926.79
TOP BOLT-FIRE HYDRANT
14.0' LT. - STA. 6+03.5

STEEL ST. 60'

FOR INTERSECTION DETAIL SEE SHEET No 231

12'C.I.P. CONC. RETAINING WALL

LIMIT OF SURFACING

STA. 0+00.00
SEE SH No 234

ONE STY. BRICK BLDG.

TWO ST'Y. FR. HO.

TWO ST'Y. BRICK HO.

TWO ST'Y. FR. APART

6784 6788 15349 15350 15351 15352 15353 15354 6789 6790 6791 11781

NOTE: INLETS & LEADS & SEWER TO BE INCLUDED IN RAMP "C" QUANTITIES SHEET No

6" WATER LINE
2" GAS
EXIST. NORTH R/W

1+0 EXISTING ℄ 2+0 3+0 PROPOSED ℄ 4+0 5+0

STA. 6+34.41 SILLIMAN ST. = STA. 0+00.00 RAMP "C"

END WORK
STA. 5+91.01

O.L. 595

SILLIMAN ST. 40'

HEDGE ROW

I.P. 64.75

℄ SILLIMAN 81.0'

EXIST. ℄
NEW ℄

R=55.79

TACKED HUB ALONG FENCE

TACKED HUB @ W. END OF WALL

STA. 6+34.41

6787 6786 6785 6782 6781 6780 6779 6778 6777 11782 42446 42447 42448 42449

STA. 929+98.87 ℄ EXPRESSWAY & STEEL ST.

931 932 933 934 935 936 937 EXPRESSWAY ℄

MAINLINE STA. 937+92.11
RAMP "C" STA. 2+98.99

RAMP "C"

REMOVAL OF EXISTING CURB (L.F.)					
CODE	ITEM	FROM STA	TO STA.	LOC.	QUAN.
A-1	E-8	53+61.38	5+91.01	NORTH	503.60
A-2	E-8	APPROACH SLAB	5+91.01	SOUTH	611.89
A-3	E-8	APPROACH SLAB	0+49.29W	SOUTH	35.00

REMOVAL OF EXISTING SIDEWALK					
CODE	ITEM	FROM STA	TO STA	LOC	QUAN
B-1	E-8	0+23	5+91.01	NORTH	2272 S.F.
B-2	E-8	53+39	53+61.38	EAST	905 S.F.
B-3	E-8	0+23	5+91.01	SOUTH	2272 S.F.
B-4	E-8	APP. SLAB	53+00	EAST	1605 S.F.

INLETS ABANDONED				
CODE	ITEM	STA.	LOC.	REMARKS
I.F-1	I-16	0+27	SOUTH	PLUG LEAD

ADJUSTED GRADE - EXISTING M.H.'s			
CODE	ITEM	STA	ADJ. EL.
E-1	I-8	0+72	934.71
E-2	I-8	4+41	931.75

PROPOSED INLETS & M.H.'s						
CODE	ITEM	TYPE	STA	LOC.	WINDOW	INV.
D-1	I-8	YOUNG-2	0+53.12W	SOUTH	935.20	930.20
D-2	I-8	YOUNG-2	1/2 PT	WEST	934.70	929.70
D-3	I-8	YOUNG-2	0+55.87E	SOUTH	934.02	929.02
D-4	I-8	YOUNG-2	0+49.72E	NORTH	933.79	928.79
D-5	I-8	YOUNG-1	4+10.00E	SOUTH	932.06	928.75
D-6	I-8	YOUNG-1	4+10.00E	NORTH	931.99	928.68
D-7	I-8	No 1 M.H.	4+15	9' RT.		
D-8	I-8	No 1 M.H.	0+20	15' LT.		

REMOVAL AND DISPOSAL OF EXISTING WEARING COURSE-STEEL ST.					
CODE	ITEM	STA	TO STA	LOC.	QUANT.
K-1	E-8	52+80	53+10	15' L & R	100 SY

DRIVEWAYS				APPROACHES		
CODE	ITEM	MAT	QUANT.	ITEM	MAT	QUANT.
J-1	T-70	5" PCC	111 SY	T-71	5" PCC	76 SY
J-2	T-70	5" PCC	111 SY	T-71	5" PCC	76 SY
J-3	T-70	5" PCC	111 SY	T-71	5" PCC	76 SY
J-4	T-70	5" PCC	111 SY	T-71	5" PCC	76 SY
J-5	T-70	5" PCC	111 SY	T-71	5" PCC	76 SY
J-6	T-70	5" PCC	111 SY	T-71	5" PCC	76 SY
J-7	T-70	5" PCC	111 SY	T-71	5" PCC	76 SY
J-8	B-18		1.00 EA	T-71	5" PCC	76 SY

CONCRETE CURB & GUTTER (L.F.)							
CODE	ITEM	FROM STA	TO STA	LOC	QUAN.	TYPE	REMARKS
G-1	I-12	53+61.38	5+91.01	NORTH	520	2	
G-2	I-12	APP SLAB	5+91.01	SOUTH	520	2	
G-4	I-12	APP SLAB	0+46.29W	WEST	10	2	

I-124 FIRE HYDRANTS REMOVE & RESET		
CODE	STA.	QUANTITY
H-1	0+20	1

(SF) CONCRETE SIDEWALK				
CODE	ITEM	FROM	TO	SF
H-1	I-13	53+61.38	5+91.01	1762

I-2 STORM SEWER-UNDER PAV'T AND APPROACHES (MG.8(b))			
CODE	ITEM	TYPE	QUANT.
C-1	I-2	12"	174 LF
C-2	I-2	12"	38 LF
C-3	I-2	12"	32 LF
C-4	I-2	10"	35 LF
C-5	I-2	10"	25 LF
C-6	I-2	12"	28 LF
C-7	I-2	12"	5 LF

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

232
492

F.B. 22 PGS. 5-15
F.B. 14 PGS. 130-134
F.B. 4 PGS. 39

27'
EXISTING BRICK CURB & GUTTER
SECTION CONCRETE

C2 INV @ MH = 929.20
C3 INV @ MH = 928.70
EX. M.H. — STA. 0+00 ℄ STEEL ST. — BEGIN PROJECT
-0.72%
PVI STA 0+25.00
ELEV. 934.08
934.24 934.23 934.48
50' V.C.
℄ 928.64
M.H. STA. 0+12
INV. 925.12
TOP 934.00
NOTE: CONSTRUCT THIS M.H. TO MEET EXISTING SEWER
934.23 935.09 935.68 935.65 935.32 934.39 933.43 932.46 931.48 930.05 927.21 923.96 921.99
EXIST. 12" COMBINATION SEWER @ 1.15%
INV @ MH = 928.00
INV @ MH = 927.66
EXIST. 15" COMBINATION SEWER @ 4.56%
12" I.P. @ 3.50% FOR 210.6'
PROPOSED GRADE RAMP "C"
935.28 933.72 932.82 931.34 930.42 929.18 924.82
EVC STA 1+40
ELEV. 935.52
PVI STA 1+90.00
ELEV. 936.72
PVT STA 2+40
ELEV. 935.80
934.24 936.06 936.27 936.25 936.26 936.04 935.62
50' V.C.
EVC STA 4+15
ELEV. 932.26
MH STA 4+15
INV. 932.26
TOPEL. 932.26
EVC STA 4+50
ELEV. 931.82
100' V.C.
PVI STA 5+00.00
ELEV. 931.55
PVT STA 5+50
ELEV. 929.18
STA. 5+91.01 END SILLIMAN ST. BEGIN RAMP "C"
TOP ELEV. 923.62
MH STA. 6+12.62
INV. 918.78 S.E.
INV. 918.78 N.E.
STA. 6+34.41 SILLIMAN ST. = STA. 0+00.00 RAMP "C"
+34.41
940 935 930 925 920 915
0+0 +20 1+0 2+0 3+0 4+0 5+0 6+0

PLATE 1—CROSS SECTION O.P.R.&R.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK

SILLIMAN ST. - STEEL ST. TO ANGLE PT.

FINAL SURVEY — SURVEYED, REVISED, TEMPLATE, AREAS, AREAS CHECKED, NOTE BOOK, NO., BY, DATE

ORIGINAL SURVEY — SURVEYED, REVISED, NOTE BOOK, NO., BY, DATE

FED. RD.	STATE	PROJECT	
7	OHIO		

23
492

MAH-18-17.20

FINAL SURVEY
NOTE INDIC.

ORIGINAL SURVEY
NOTE INDIC.

PLATE 3 CROSS SECTION OF R.R. & E. ST. LINE
KEUFFEL & ESSER CO., NEW YORK

X-SECTIONS SILLIMAN ST. 0+0 to 5+90.41

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

234
432

MILL CREEK

NOTE: FOR MARSHALL-GLENWOOD INTERSECTION DETAIL SEE SH. No 252

NOTE: FOR ORANGE-GLENWOOD INTERSECTION DETAIL & ITEMS OF WORK TO BE PERFORMED IN THIS AREA SEE SHT. No 235

℄ MAH-18-17.20 STA. 969+31.38
℄ GLENWOOD STA 50+00

MEET EXIST. PAVE. & SIDEWALKS

50+82.74

℄-GLENWOOD AVE.

DAM

45 45 51 35 18' 19'

See Structure Sht. No. 382 for additional Data

℄-ORANGE AVE. STA. 48+14.44

℄-EXPRESSWAY STA. 50+00

EXIST. ℄ MARSHALL ST. STA. 51+40.13

24' - ORANGE ST.
40' - GLENWOOD AVE

BITUMINOUS WEARING SURFACE
BRICK
CONCRETE

EXISTING TYPICAL SECTION
ORANGE ST. & GLENWOOD AVE.

T. HUB BESIDE P. POLE N. OF SINCLAIR STA.

T. HUB S.E. COR. PORCH DAIRY STORE

23.2' ℄ OAKWOOD 45.85'

℄ STEEL ST.

8.45'

IRON PIN N.W. CORNER CHURCH

℄ OAKWOOD

REMOVE EXISTING WEARING COURSE & RESURFACE WITH 2" I.T.-35 ASPH. CONC. SURF. COURSE TYPE A I.T.-35

BEGIN WORK STA. 49+58.53

A-1 B-1 H-1 K-1 G-1 B-3 A-3 K-2 K-3 B-2 A-2 H-2 G-2

END WORK STA. 0+89

STA. 50+00 STEEL ST. ℄ = STA. 0+00 OAKWOOD ℄

65' 15' 25' 50'

9" B-70
2" B-35
1-35

APPROACH SLAB ℄ STEEL ST.

SEE STRUCTURE SHT. No 332 FOR ADDITIONAL DATA

END APPROACH SLAB STA. 50+35.11

STA. 50+58.53 END WORK

℄-OAKWOOD AVE. STA. 50+00

84° 27' 46"

℄-SILLIMAN ST. STA. 52+99.49

SILLIMAN (W.)

T. HUB N. EDGE WALK N. OF GUY ANCHOR

52.06'

7.30'

IRON PIN AT E. END CURB FOR PARKING LOT

STEEL

24.88

PUNCH MARK ON R.R. SPIKE

SILLIMAN (E.)

6.15'

T. HUB S.W. COR. O-H GRILL

FOR INTERSECTION DETAILS SEE SHEET No 231

48+00 50+00 51+00 52+00 53+00

48' FF 8'

℄-STEEL ST.

MICROFILMED SEP 19 1985

FOR UTILITY RELOCATION SEE SHEET No 84

FOR SILLIMAN ST. DETAILS SEE SHEET No 232

EXPRESSWAY STA. 52+08.87 "
STEEL STREET STA. 51+44.37

℄-EXPRESSWAY STA. 51+44.37

B.M. # 12.2 TOP BOLT HYDT. S.E. CORNER STEEL ST. AND SILLIMAN ST. ELEV. 936.21

PROPOSED ℄ 14' 20'

℄-SILLIMAN ST. STA. 53+24.46

36'
BIT. WEARING COURSE
BRICK
CONCRETE
STONE CURB

EXIST. STEEL ST.

ITEM E-8 REMOVAL & STORAGE OF EXIST. CURB (L.F.)

CODE	FROM	TO	QUAN.	REMARKS
A-1	0+37	0+89	52	ON OAKWOOD
A-2	49+58.53	52+70	311	STEEL ST.
A-3	0+37 OAKW.	52+72	267	STEEL ST.

ITEM E-8 REMOVAL OF EXIST. SIDEWALK (S.FT.)

CODE	FROM	TO	QUAN.	REMARKS
B-1	0+30	0+89	354	ON OAKWOOD
B-2	49+58.53	52+70	1500	STEEL ST.
B-3	50+15	52+73	1290	STEEL ST.

ITEM I-12 TYPE 6 CONC. CURB REPLACEMENT (L.F.)

CODE	FROM	TO	QUAN.	REMARKS
G-1	0+37	0+89	53	OAKWOOD
G-2	49+58.53	50+08.53	50	STEEL ST.

ITEM I-13 CONC. SIDEWALK REPLACEMENT (S.F.)

CODE	FROM	TO	QUAN.	REMARKS
H-1	0+37	0+89	312	OAKWOOD
H-2	49+58.53	50+18.53	300	STEEL ST.

ITEM E-8 REMOVAL & DISP. OF EXIST. PAVEMENT (S.Y.)

CODE	FROM	TO	QUAN.	REMARKS
K-1	0+18	0+89	68	5" WEARING COURSE
K-2	49+58.53	50+10.11	69	5" WEARING COURSE
K-3	50+10.11	52+71.68	349	FULL DEPTH

GLENWOOD AVE. CROSSING

928.22 927.21 925.53 924.74 923.08 922.50 922.32

P.C. STA. 47+61.07 EL. 930.77

BEGIN WORK ℄ ORANGE AVE. STA. 48+14.44 EL. 927.27

P.V.C. STA. 48+50 EL. 924.94

100' V.C.

P.V.I. STA. 49+00 EL. 921.42

P.V.T. STA. 49+50 EL. 917.87

℄-EXPRESSWAY - STA. 50+00

7.16%

P.V.C. STA. 51+00

43' 6" V.C.

P.V.I. STA. 51+21.33 EL. 904.85

P.V.T. STA. 51+43.66

2.00%

END CONSTRUCTION STA. 51+96.36 EL. 898.32

930 925 920 915 910 905 900 895 890 885

48+00 49+00 50+00 51+00 52+00

STEEL ST. CROSSING

END WORK ℄ STA. 50+10.11

MEET EXIST. STEEL ST. STA. 49+70.81 EL. 940.75

℄ OAKWOOD AVE. STA. 50+00

℄ EXPRESSWAY STA. 51+44.37 EL. 937.16

℄-SILLIMAN ST.-WEST EL. 934.56

7.14%

℄-PROP. SILLIMAN ST. STA. 53+16.49 EL. 934.29

EXIST. ℄ SILLIMAN ST. EAST EL. 934.12

930.90 938.03 936.29 935.42 934.55

950 945 940 935 930 925 920 915 910 905

49+00 50+00 51+00 52+00 53+00

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
NOTE BOOK
NO.
BY
DATE
STRUCTURE NO. & PATHS CHKD

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
NOTE BOOK
NO.
BY
DATE
R.P. OR MAT CHECKED

Printed in U.S.A. On DIETZGEN DRAFTEX MOISTURE PROOF Cloth

PLAN-PROFILE GLENWOOD AVE.

PLATE 1. PLAN-PROFILE B.P.R. STANDARD
EUGENE DIETZGEN CO. CHICAGO - N.Y. YORK


PLAN-PROFILE STEEL ST.

Printed in U.S.A. On DIETZGEN DRAFTEX MOISTURE PROOF Cloth

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

235
492



5:24 REMOVAL OF EXISTING STRUCTURES	
CODE	DESCRIPTION
R-1	STONE WALL

ITEM E-8 REM'V. & STORE EXIST. CURB (L.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUANT.
A-1	0+50.21 (ORG.)	TO 48+47.05 GLEN. (℄ op ℄)	GT	
A-2	48+57	50+87.76	LT.	226
A-3	48+47.05	50+87.76	RT.	236

ITEM E-8 REM'V. EXIST. SIDEWALK (S.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
B-1	48+25	48+45	RT. of ℄	170
B-2	0+19	0+60	ORANGE	234
B-3	48+45	50+87.76	RT.	1428
B-4	48+60	50+87.76	LT.	1338

ITEM I-8 MANHOLES ADJ. TO GRADE (EA.)

CODE	STA.	LOCA.	TOP ELEV.	REMARKS
E-1	48+21	11.2' LT.	926.75	
E-2	0+20 ORG.	ON ℄	928.45	

ITEM I-2 STORM SEWERS UND. PAV'T. OR APPR. VIT. PIPE SEC. M-6.8(b)

CODE	FROM STA.	TO STA.	LOCA.	L.F.	REMARKS
C-1	D-1	E-2	ORANGE	26	12" PIPE

ITEM I-8 INLETS YOUNGSTOWN TYPE II (EA.)

CODE	STA.	LOCA.	TOP ELEV.	C.B. BOTT.	REMARKS
D-1	0+52.37	ORANGE	928.70	922.95	

ITEM I-16 INLETS ABANDONED (EA.)

CODE	STA.	LOCA.	REMARKS
F-1	0+24	ORANGE	

ITEM I-12 COMBINED CURB & GUTTER (L.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.	TYPE
G-1	1+86 PK. DR.	48+48.67	GLENW'D. (LT.)	55	2
G-2	0+50.21 ORG.	48+47.05	GLENW'D. (RT.)	51	2

ITEM I-13 CONC. SIDEW'K. REPLACE. (S.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
H-1	48+31.50	48+48.67	LT	60
H-2	0+60	48+47.05	GLEN. (N.E. RT)	300

ITEM E-8 REM'V. & DISP. OF FULL DEPTH PAV'T.


CODE	FROM	TO	LOCA.	QUAN.
K-1	48+14.44	50+87.76	GLENW'D.	397
K-2	1+86 (ORG.)	48+48 (GLEN)	24'-55' LT ℄	21
K-3	0+20	0+60.25	ORANGE	20

INTERSECTION DETAIL
GLENWOOD AVE.
AT ORANGE ST.
SCALE: 1"=10'

FED. RD	STATE	PROJECT	
2	OHIO		

MAH - 18 - 17.20


236
492


MAHONING RIVER
Bridge St.
SEE RAMP "D" & DETAIL ON SHEET Nº 238
SEE DETAIL EXTENDED 6'x4' BOX ON SHEET Nº 116
RAMP "D"
NOTE: FOR INTERSECTION DETAIL SEE SH. Nº 238
SEE RAMP "D" ON SHEET Nº 52
0+00 REL. SALT SPRINGS RD. 19+09.78 (4.5' RT) & RAMP "D"
CURVE DATA & REL. SALT SPRINGS RD.
Δ = 18°04'21"
D = 12°30'
R = 458.37'
T = 72.90'
L = 144.58'
STA. 7+05.81 (REL. SALT SPRINGS RD.)
STA. 0+00 (RICHLAND)
END WORK STA. 7+44.52
BEGIN WORK STA. 0+00 SALT SPRINGS RD.
STA. 5+20.16
TRAVERSE LINE
WARP GUTTER TO PROP. INLET
RELOCATED SALT SPRINGS RD.
2-PROP. 4' SIDEWALK
EXIST. 6'x4' CONC. STORM SEWER
STA. 3+60.11 (REL. SALT SPRINGS) STA. 0+00 (ONETA ST.)
SIGN
NOTE: SEE SHEET Nº 238 FOR HORIZONTAL & VERTICAL CONTROL ON SALT SPRINGS RD.
NOTE: SEE SHEET Nº 6 FOR TYPICAL SECTION OF PROPOSED PAVEMENT
NOTE: FOR ITEMS B-5, B-6 & B-7 UTLY SEE SHEET Nº 87 & —
B.M. ON CORNER OF BRIDGE ST. & SALT SPRINGS RD. SQUARE CUT IN N.W. CORN. OF FIRST STEP AT GORGIE MFG. CO. ELEV. 844.58
END WORK STA. 0+75 RICHLAND
END WORK STA. 1+25 ONETA
TRAVERSE LINE
ROAD
5 SPRINGS
RICHLAND
ONETA
NEW MANHOLE
TOP-855.88 INV.-847.08
TOP-855.69 INV.-847.19
TOP-855.50 INV.-847.30
TOP-855.41 INV.-847.41
TOP-855.22 INV.-847.52
TOP-855.03 INV.-847.63
TOP-854.84 INV.-847.74
TOP-854.65 INV.-847.85
TOP-854.46 INV.-847.96
TOP-854.27 INV.-848.07
TOP-854.08 INV.-848.18
TOP-853.89 INV.-848.29
TOP-853.70 INV.-848.40
TOP-853.51 INV.-848.51
TOP-853.32 INV.-848.62
TOP-853.13 INV.-848.73
TOP-852.94 INV.-848.84
TOP-852.75 INV.-848.95
TOP-852.56 INV.-849.06
TOP-852.37 INV.-849.17
TOP-852.18 INV.-849.28
TOP-851.99 INV.-849.39
TOP-851.80 INV.-849.50
TOP-851.61 INV.-849.61
TOP-851.42 INV.-849.72
TOP-851.23 INV.-849.83
TOP-851.04 INV.-849.94
TOP-850.85 INV.-850.05
TOP-850.66 INV.-850.16
TOP-850.47 INV.-850.27
TOP-850.28 INV.-850.38
TOP-850.09 INV.-850.49
TOP-849.90 INV.-850.60
TOP-849.71 INV.-850.71
TOP-849.52 INV.-850.82
TOP-849.33 INV.-850.93
TOP-849.14 INV.-851.04
TOP-848.95 INV.-851.15
TOP-848.76 INV.-851.26
TOP-848.57 INV.-851.37
TOP-848.38 INV.-851.48
TOP-848.19 INV.-851.59
TOP-848.00 INV.-851.70
TOP-847.81 INV.-851.81
TOP-847.62 INV.-851.92
TOP-847.43 INV.-852.03
TOP-847.24 INV.-852.14
TOP-847.05 INV.-852.25
TOP-846.86 INV.-852.36
TOP-846.67 INV.-852.47
TOP-846.48 INV.-852.58
TOP-846.29 INV.-852.69
TOP-846.10 INV.-852.80
TOP-845.91 INV.-852.91
TOP-845.72 INV.-853.02
TOP-845.53 INV.-853.13
TOP-845.34 INV.-853.24
TOP-845.15 INV.-853.35
TOP-844.96 INV.-853.46
TOP-844.77 INV.-853.57
TOP-844.58 INV.-853.68
TOP-844.39 INV.-853.79
TOP-844.20 INV.-853.90
TOP-844.01 INV.-854.01
TOP-843.82 INV.-854.12
TOP-843.63 INV.-854.23
TOP-843.44 INV.-854.34
TOP-843.25 INV.-854.45
TOP-843.06 INV.-854.56
TOP-842.87 INV.-854.67
TOP-842.68 INV.-854.78
TOP-842.49 INV.-854.89
TOP-842.30 INV.-855.00
TOP-842.11 INV.-855.11
TOP-841.92 INV.-855.22
TOP-841.73 INV.-855.33
TOP-841.54 INV.-855.44
TOP-841.35 INV.-855.55
TOP-841.16 INV.-855.66
TOP-840.97 INV.-855.77
TOP-840.78 INV.-855.88
TOP-840.59 INV.-855.99
TOP-840.40 INV.-856.10
TOP-840.21 INV.-856.21
TOP-840.02 INV.-856.32
TOP-839.83 INV.-856.43
TOP-839.64 INV.-856.54
TOP-839.45 INV.-856.65
TOP-839.26 INV.-856.76
TOP-839.07 INV.-856.87
TOP-838.88 INV.-856.98
TOP-838.69 INV.-857.09
TOP-838.50 INV.-857.20
TOP-838.31 INV.-857.31
TOP-838.12 INV.-857.42
TOP-837.93 INV.-857.53
TOP-837.74 INV.-857.64
TOP-837.55 INV.-857.75
TOP-837.36 INV.-857.86
TOP-837.17 INV.-857.97
TOP-836.98 INV.-858.08
TOP-836.79 INV.-858.19
TOP-836.60 INV.-858.30
TOP-836.41 INV.-858.41
TOP-836.22 INV.-858.52
TOP-836.03 INV.-858.63
TOP-835.84 INV.-858.74
TOP-835.65 INV.-858.85
TOP-835.46 INV.-858.96
TOP-835.27 INV.-859.07
TOP-835.08 INV.-859.18
TOP-834.89 INV.-859.29
TOP-834.70 INV.-859.40
TOP-834.51 INV.-859.51
TOP-834.32 INV.-859.62
TOP-834.13 INV.-859.73
TOP-833.94 INV.-859.84
TOP-833.75 INV.-859.95
TOP-833.56 INV.-860.06
TOP-833.37 INV.-860.17
TOP-833.18 INV.-860.28
TOP-832.99 INV.-860.39
TOP-832.80 INV.-860.50
TOP-832.61 INV.-860.61
TOP-832.42 INV.-860.72
TOP-832.23 INV.-860.83
TOP-832.04 INV.-860.94
TOP-831.85 INV.-861.05
TOP-831.66 INV.-861.16
TOP-831.47 INV.-861.27
TOP-831.28 INV.-861.38
TOP-831.09 INV.-861.49
TOP-830.90 INV.-861.60
TOP-830.71 INV.-861.71
TOP-830.52 INV.-861.82
TOP-830.33 INV.-861.93
TOP-830.14 INV.-862.04
TOP-829.95 INV.-862.15
TOP-829.76 INV.-862.26
TOP-829.57 INV.-862.37
TOP-829.38 INV.-862.48
TOP-829.19 INV.-862.59
TOP-829.00 INV.-862.70
TOP-828.81 INV.-862.81
TOP-828.62 INV.-862.92
TOP-828.43 INV.-863.03
TOP-828.24 INV.-863.14
TOP-828.05 INV.-863.25
TOP-827.86 INV.-863.36
TOP-827.67 INV.-863.47
TOP-827.48 INV.-863.58
TOP-827.29 INV.-863.69
TOP-827.10 INV.-863.80
TOP-826.91 INV.-863.91
TOP-826.72 INV.-864.02
TOP-826.53 INV.-864.13
TOP-826.34 INV.-864.24
TOP-826.15 INV.-864.35
TOP-825.96 INV.-864.46
TOP-825.77 INV.-864.57
TOP-825.58 INV.-864.68
TOP-825.39 INV.-864.79
TOP-825.20 INV.-864.90
TOP-825.01 INV.-865.01
TOP-824.82 INV.-865.12
TOP-824.63 INV.-865.23
TOP-824.44 INV.-865.34
TOP-824.25 INV.-865.45
TOP-824.06 INV.-865.56
TOP-823.87 INV.-865.67
TOP-823.68 INV.-865.78
TOP-823.49 INV.-865.89
TOP-823.30 INV.-866.00
TOP-823.11 INV.-866.11
TOP-822.92 INV.-866.22
TOP-822.73 INV.-866.33
TOP-822.54 INV.-866.44
TOP-822.35 INV.-866.55
TOP-822.16 INV.-866.66
TOP-821.97 INV.-866.77
TOP-821.78 INV.-866.88
TOP-821.59 INV.-866.99
TOP-821.40 INV.-867.10
TOP-821.21 INV.-867.21
TOP-821.02 INV.-867.32
TOP-820.83 INV.-867.43
TOP-820.64 INV.-867.54
TOP-820.45 INV.-867.65
TOP-820.26 INV.-867.76
TOP-820.07 INV.-867.87
TOP-819.88 INV.-867.98
TOP-819.69 INV.-868.09
TOP-819.50 INV.-868.20
TOP-819.31 INV.-868.31
TOP-819.12 INV.-868.42
TOP-818.93 INV.-868.53
TOP-818.74 INV.-868.64
TOP-818.55 INV.-868.75
TOP-818.36 INV.-868.86
TOP-818.17 INV.-868.97
TOP-817.98 INV.-869.08
TOP-817.79 INV.-869.19
TOP-817.60 INV.-869.30
TOP-817.41 INV.-869.41
TOP-817.22 INV.-869.52
TOP-817.03 INV.-869.63
TOP-816.84 INV.-869.74
TOP-816.65 INV.-869.85
TOP-816.46 INV.-869.96
TOP-816.27 INV.-870.07
TOP-816.08 INV.-870.18
TOP-815.89 INV.-870.29
TOP-815.70 INV.-870.40
TOP-815.51 INV.-870.51
TOP-815.32 INV.-870.62
TOP-815.13 INV.-870.73
TOP-814.94 INV.-870.84
TOP-814.75 INV.-870.95
TOP-814.56 INV.-871.06
TOP-814.37 INV.-871.17
TOP-814.18 INV.-871.28
TOP-813.99 INV.-871.39
TOP-813.80 INV.-871.50
TOP-813.61 INV.-871.61
TOP-813.42 INV.-871.72
TOP-813.23 INV.-871.83
TOP-813.04 INV.-871.94
TOP-812.85 INV.-872.05
TOP-812.66 INV.-872.16
TOP-812.47 INV.-872.27
TOP-812.28 INV.-872.38
TOP-812.09 INV.-872.49
TOP-811.90 INV.-872.60
TOP-811.71 INV.-872.71
TOP-811.52 INV.-872.82
TOP-811.33 INV.-872.93
TOP-811.14 INV.-873.04
TOP-810.95 INV.-873.15
TOP-810.76 INV.-873.26
TOP-810.57 INV.-873.37
TOP-810.38 INV.-873.48
TOP-810.19 INV.-873.59
TOP-810.00 INV.-873.70
TOP-809.81 INV.-873.81
TOP-809.62 INV.-873.92
TOP-809.43 INV.-874.03
TOP-809.24 INV.-874.14
TOP-809.05 INV.-874.25
TOP-808.86 INV.-874.36
TOP-808.67 INV.-874.47
TOP-808.48 INV.-874.58
TOP-808.29 INV.-874.69
TOP-808.10 INV.-874.80
TOP-807.91 INV.-874.91
TOP-807.72 INV.-875.02
TOP-807.53 INV.-875.13
TOP-807.34 INV.-875.24
TOP-807.15 INV.-875.35
TOP-806.96 INV.-875.46
TOP-806.77 INV.-875.57
TOP-806.58 INV.-875.68
TOP-806.39 INV.-875.79
TOP-806.20 INV.-875.90
TOP-806.01 INV.-876.01
TOP-805.82 INV.-876.12
TOP-805.63 INV.-876.23
TOP-805.44 INV.-876.34
TOP-805.25 INV.-876.45
TOP-805.06 INV.-876.56
TOP-804.87 INV.-876.67
TOP-804.68 INV.-876.78
TOP-804.49 INV.-876.89
TOP-804.30 INV.-877.00
TOP-804.11 INV.-877.11
TOP-803.92 INV.-877.22
TOP-803.73 INV.-877.33
TOP-803.54 INV.-877.44
TOP-803.35 INV.-877.55
TOP-803.16 INV.-877.66
TOP-802.97 INV.-877.77
TOP-802.78 INV.-877.88
TOP-802.59 INV.-877.99
TOP-802.40 INV.-878.10
TOP-802.21 INV.-878.21
TOP-802.02 INV.-878.32
TOP-801.83 INV.-878.43
TOP-801.64 INV.-878.54
TOP-801.45 INV.-878.65
TOP-801.26 INV.-878.76
TOP-801.07 INV.-878.87
TOP-800.88 INV.-878.98
TOP-800.69 INV.-879.09
TOP-800.50 INV.-879.20
TOP-800.31 INV.-879.31
TOP-800.12 INV.-879.42
TOP-799.93 INV.-879.53
TOP-799.74 INV.-879.64
TOP-799.55 INV.-879.75
TOP-799.36 INV.-879.86
TOP-799.17 INV.-879.97
TOP-798.98 INV.-880.08
TOP-798.79 INV.-880.19
TOP-798.60 INV.-880.30
TOP-798.41 INV.-880.41
TOP-798.22 INV.-880.52
TOP-798.03 INV.-880.63
TOP-797.84 INV.-880.74
TOP-797.65 INV.-880.85
TOP-797.46 INV.-880.96
TOP-797.27 INV.-881.07
TOP-797.08 INV.-881.18
TOP-796.89 INV.-881.29
TOP-796.70 INV.-881.40
TOP-796.51 INV.-881.51
TOP-796.32 INV.-881.62
TOP-796.13 INV.-881.73
TOP-795.94 INV.-881.84
TOP-795.75 INV.-881.95
TOP-795.56 INV.-882.06
TOP-795.37 INV.-882.17
TOP-795.18 INV.-882.28
TOP-794.99 INV.-882.39
TOP-794.80 INV.-882.50
TOP-794.61 INV.-882.61
TOP-794.42 INV.-882.72
TOP-794.23 INV.-882.83
TOP-794.04 INV.-882.94
TOP-793.85 INV.-883.05
TOP-793.66 INV.-883.16
TOP-793.47 INV.-883.27
TOP-793.28 INV.-883.38
TOP-793.09 INV.-883.49
TOP-792.90 INV.-883.60
TOP-792.71 INV.-883.71
TOP-792.52 INV.-883.82
TOP-792.33 INV.-883.93
TOP-792.14 INV.-884.04
TOP-791.95 INV.-884.15
TOP-791.76 INV.-884.26
TOP-791.57 INV.-884.37
TOP-791.38 INV.-884.48
TOP-791.19 INV.-884.59
TOP-791.00 INV.-884.70
TOP-790.81 INV.-884.81
TOP-790.62 INV.-884.92
TOP-790.43 INV.-885.03
TOP-790.24 INV.-885.14
TOP-790.05 INV.-885.25
TOP-789.86 INV.-885.36
TOP-789.67 INV.-885.47
TOP-789.48 INV.-885.58
TOP-789.29 INV.-885.69
TOP-789.10 INV.-885.80
TOP-788.91 INV.-885.91
TOP-788.72 INV.-886.02
TOP-788.53 INV.-886.13
TOP-788.34 INV.-886.24
TOP-788.15 INV.-886.35
TOP-787.96 INV.-886.46
TOP-787.77 INV.-886.57
TOP-787.58 INV.-886.68
TOP-787.39 INV.-886.79
TOP-787.20 INV.-886.90
TOP-787.01 INV.-887.01
TOP-786.82 INV.-887.12
TOP-786.63 INV.-887.23
TOP-786.44 INV.-887.34
TOP-786.25 INV.-887.45
TOP-786.06 INV.-887.56
TOP-785.87 INV.-887.67
TOP-785.68 INV.-887.78
TOP-785.49 INV.-887.89
TOP-785.30 INV.-888.00
TOP-785.11 INV.-888.11
TOP-784.92 INV.-888.22
TOP-784.73 INV.-888.33
TOP-784.54 INV.-888.44
TOP-784.35 INV.-888.55
TOP-784.16 INV.-888.66
TOP-783.97 INV.-888.77
TOP-783.78 INV.-888.88
TOP-783.59 INV.-888.99
TOP-783.40 INV.-889.10
TOP-783.21 INV.-889.21
TOP-783.02 INV.-889.32
TOP-782.83 INV.-889.43
TOP-782.64 INV.-889.54
TOP-782.45 INV.-889.65
TOP-782.26 INV.-889.76
TOP-782.07 INV.-889.87
TOP-781.88 INV.-889.98
TOP-781.69 INV.-890.09
TOP-781.50 INV.-890.20
TOP-781.31 INV.-890.31
TOP-781.12 INV.-890.42
TOP-780.93 INV.-890.53
TOP-780.74 INV.-890.64
TOP-780.55 INV.-890.75
TOP-780.36 INV.-890.86
TOP-780.17 INV.-890.97
TOP-779.98 INV.-891.08
TOP-779.79 INV.-891.19
TOP-779.60 INV.-891.30
TOP-779.41 INV.-891.41
TOP-779.22 INV.-891.52
TOP-779.03 INV.-891.63
TOP-778.84 INV.-891.74
TOP-778.65 INV.-891.85
TOP-778.46 INV.-891.96
TOP-778.27 INV.-892.07
TOP-778.08 INV.-892.18
TOP-777.89 INV.-892.29
TOP-777.70 INV.-892.40
TOP-777.51 INV.-892.51
TOP-777.32 INV.-892.62
TOP-777.13 INV.-892.73
TOP-776.94 INV.-892.84
TOP-776.75 INV.-892.95
TOP-776.56 INV.-893.06
TOP-776.37 INV.-893.17
TOP-776.18 INV.-893.28
TOP-775.99 INV.-893.39
TOP-775.80 INV.-893.50
TOP-775.61 INV.-893.61
TOP-775.42 INV.-893.72
TOP-775.23 INV.-893.83
TOP-775.04 INV.-893.94
TOP-774.85 INV.-894.05
TOP-774.66 INV.-894.16
TOP-774.47 INV.-894.27
TOP-774.28 INV.-894.38
TOP-774.09 INV.-894.49
TOP-773.90 INV.-894.60
TOP-773.71 INV.-894.71
TOP-773.52 INV.-894.82
TOP-773.33 INV.-894.93
TOP-773.14 INV.-895.04
TOP-772.95 INV.-895.15
TOP-772.76 INV.-895.26
TOP-772.57 INV.-895.37
TOP-772.38 INV.-895.48
TOP-772.19 INV.-895.59
TOP-772.00 INV.-895.70
TOP-771.81 INV.-895.81
TOP-771.62 INV.-895.92
TOP-771.43 INV.-896.03
TOP-771.24 INV.-896.14
TOP-771.05 INV.-896.25
TOP-770.86 INV.-896.36
TOP-770.67 INV.-896.47
TOP-770.48 INV.-896.58
TOP-770.29 INV.-896.69
TOP-770.10 INV.-896.80
TOP-769.91 INV.-896.91
TOP-769.72 INV.-897.02
TOP-769.53 INV.-897.13
TOP-769.34 INV.-897.24
TOP-769.15 INV.-897.35
TOP-768.96 INV.-897.46
TOP-768.77 INV.-897.57
TOP-768.58 INV.-897.68
TOP-768.39 INV.-897.79
TOP-768.20 INV.-897.90
TOP-768.01 INV.-898.01
TOP-767.82 INV.-898.12
TOP-767.63 INV.-898.23
TOP-767.44 INV.-898.34
TOP-767.25 INV.-898.45
TOP-767.06 INV.-898.56
TOP-766.87 INV.-898.67
TOP-766.68 INV.-898.78
TOP-766.49 INV.-898.89
TOP-766.30 INV.-899.00
TOP-766.11 INV.-899.11
TOP-765.92 INV.-899.22
TOP-765.73 INV.-899.33
TOP-765.54 INV.-899.44
TOP-765.35 INV.-899.55
TOP-765.16 INV.-899.66
TOP-764.97 INV.-899.77
TOP-764.78 INV.-899.88
TOP-764.59 INV.-899.99
TOP-764.40 INV.-900.10
TOP-764.21 INV.-900.21
TOP-764.02 INV.-900.32
TOP-763.83 INV.-900.43
TOP-763.64 INV.-900.54
TOP-763.45 INV.-900.65
TOP-763.26 INV.-900.76
TOP-763.07 INV.-900.87
TOP-762.88 INV.-900.98
TOP-762.69 INV.-901.09
TOP-762.50 INV.-901.20
TOP-762.31 INV.-901.31
TOP-762.12 INV.-901.42
TOP-761.93 INV.-901.53
TOP-761.74 INV.-901.64
TOP-761.55 INV.-901.75
TOP-761.36 INV.-901.86
TOP-761.17 INV.-901.97
TOP-760.98 INV.-902.08
TOP-760.79 INV.-902.19
TOP-760.60 INV.-902.30
TOP-760.41 INV.-902.41
TOP-760.22 INV.-902.52
TOP-760.03 INV.-902.63
TOP-759.84 INV.-902.74
TOP-759.65 INV.-902.85
TOP-759.46 INV.-902.96
TOP-759.27 INV.-903.07
TOP-759.08 INV.-903.18
TOP-758.89 INV.-903.29
TOP-758.70 INV.-903.40
TOP-758.51 INV.-903.51
TOP-758.32 INV.-903.62
TOP-758.13 INV.-903.73
TOP-757.94 INV.-903.84
TOP-757.75 INV.-903.95
TOP-757.56 INV.-904.06
TOP-757.37 INV.-904.17
TOP-757.18 INV.-904.28
TOP-756.99 INV.-904.39
TOP-756.80 INV.-904.50
TOP-756.61 INV.-904.61
TOP-756.42 INV.-904.72
TOP-756.23 INV.-904.83
TOP-756.04 INV.-904.94
TOP-755.85 INV.-905.05
TOP-755.66 INV.-905.16
TOP-755.47 INV.-905.27
TOP-755.28 INV.-905.38
TOP-755.09 INV.-905.49
TOP-754.90 INV.-905.60
TOP-754.71 INV.-905.71
TOP-754.52 INV.-905.82
TOP-754.33 INV.-905.93
TOP-754.14 INV.-906.04
TOP-753.95 INV.-906.15
TOP-753.76 INV.-906.26
TOP-753.57 INV.-906.37
TOP-753.38 INV.-906.48
TOP-753.19 INV.-906.59
TOP-753.00 INV.-906.70
TOP-752.81 INV.-906.81
TOP-752.62 INV.-906.92
TOP-752.43 INV.-907.03
TOP-752.24 INV.-907.14
TOP-752.05 INV.-907.25
TOP-751.86 INV.-907.36
TOP-751.67 INV.-907.47
TOP-751.48 INV.-907.58
TOP-751.29 INV.-907.69
TOP-751.10 INV.-907.80
TOP-750.91 INV.-907.91
TOP-750.72 INV.-908.02
TOP-750.53 INV.-908.13
TOP-750.34 INV.-908.24
TOP-750.15 INV.-908.35
TOP-749.96 INV.-908.46
TOP-749.77 INV.-908.57
TOP-749.58 INV.-908.68
TOP-749.39 INV.-908.79
TOP-749.20 INV.-908.90
TOP-749.01 INV.-909.01
TOP-748.82 INV.-909.12
TOP-748.63 INV.-909.23
TOP-748.44 INV.-909.34
TOP-748.25 INV.-909.45
TOP-748.06 INV.-909.56
TOP-747.87 INV.-909.67
TOP-747.68 INV.-909.78
TOP-747.49 INV.-909.89
TOP-747.30 INV.-910.00
TOP-747.11 INV.-910.11
TOP-746.92 INV.-910.22
TOP-746.73 INV.-910.33
TOP-746.54 INV.-910.44
TOP-746.35 INV.-910.55
TOP-746.16 INV.-910.66
TOP-745.97 INV.-910.77
TOP-745.78 INV.-910.88
TOP-745.59 INV.-910.99
TOP-745.40 INV.-911.10
TOP-745.21 INV.-911.21
TOP-745.02 INV.-911.32
TOP-744.83 INV.-911.43
TOP-744.64 INV.-911.54
TOP-744.45 INV.-911.65
TOP-744.26 INV.-911.76
TOP-744.07 INV.-911.87
TOP-743.88 INV.-911.98
TOP-743.69 INV.-912.09
TOP-743.50 INV.-912.20
TOP-743.31 INV.-912.31
TOP-743.12 INV.-912.42
TOP-742.93 INV.-912.53
TOP-742.74 INV.-912.64
TOP-742.55 INV.-912.75
TOP-742.36 INV.-912.86
TOP-742.17 INV.-912.97
TOP-741.98 INV.-913.08
TOP-741.79 INV.-913.19
TOP-741.60 INV.-913.30
TOP-741.41 INV.-913.41
TOP-741.22 INV.-913.52
TOP-741.03 INV.-913.63
TOP-740.84 INV.-913.74
TOP-740.65 INV.-913.85
TOP-740.46 INV.-913.96
TOP-740.27 INV.-914.07
TOP-740.08 INV.-914.18
TOP-739.89 INV.-914.29
TOP-739.70 INV.-914.40
TOP-739.51 INV.-914.51
TOP-739.32 INV.-914.62
TOP-739.13 INV.-914.73
TOP-738.94 INV.-914.84
TOP-738.75 INV.-914.95
TOP-738.56 INV.-915.06
TOP-738.37 INV.-915.17
TOP-738.18 INV.-915.28
TOP-737.99 INV.-915.39
TOP-737.80 INV.-915.50
TOP-737.61 INV.-915.61
TOP-737.42 INV.-915.72
TOP-737.23 INV.-915.83
TOP-737.04 INV.-915.94
TOP-736.85 INV.-916.05
TOP-736.66 INV.-916.16
TOP-736.47 INV.-916.27
TOP-736.28 INV.-916.38
TOP-736.09 INV.-916.49
TOP-735.90 INV.-916.60
TOP-735.71 INV.-916.71
TOP-735.52 INV.-916.82
TOP-735.33 INV.-916.93
TOP-735.14 INV.-917.04
TOP-734.95 INV.-917.15
TOP-734.76 INV.-917.26
TOP-734.57 INV.-917.37
TOP-734.38 INV.-917.48
TOP-734.19 INV.-917.59
TOP-734.00 INV.-917.70
TOP-733.81 INV.-917.81
TOP-733.62 INV.-917.92
TOP-733.43 INV.-918.03
TOP-733.24 INV.-918.14
TOP-733.05 INV.-918.25
TOP-732.86 INV.-918.36
TOP-732.67 INV.-918.47
TOP-732.48 INV.-918.58
TOP-732.29 INV.-918.69
TOP-732.10 INV.-918.80
TOP-731.91 INV.-918.91
TOP-731.72 INV.-919.02
TOP-731.53 INV.-919.13
TOP-731.34 INV.-919.24
TOP-731.15 INV.-919.35
TOP-730.96 INV.-919.46
TOP-730.77 INV.-919.57
TOP-730.58 INV.-919.68
TOP-730.39 INV.-919.79
TOP-730.20 INV.-919.90
TOP-730.01 INV.-920.01
TOP-729.82 INV.-920.12
TOP-729.63 INV.-920.23
TOP-729.44 INV.-920.34
TOP-729.25 INV.-920.45
TOP-729.06 INV.-920.56
TOP-728.87 INV.-920.67
TOP-728.68 INV.-920.78
TOP-728.49 INV.-920.89
TOP-728.30 INV.-921.00
TOP-728.11 INV.-921.11
TOP-727.92 INV.-921.22
TOP-727.73 INV.-921.33
TOP-727.54 INV.-921.44
TOP-727.35 INV.-921.55
TOP-727.16 INV.-921.66
TOP-726.97 INV.-921.77
TOP-726.78 INV.-921.88
TOP-726.59 INV.-921.99
TOP-726.40 INV.-922.10
TOP-726.21 INV.-922.21
TOP-726.02 INV.-922.32
TOP-725.83 INV.-922.43
TOP-725.64 INV.-922.54
TOP-725.45 INV.-922.65
TOP-725.26 INV.-922.76
TOP-725.07 INV.-922.87
TOP-724.88 INV.-922.98
TOP-724.69 INV.-923.09
TOP-724.50 INV.-923.20
TOP-724.31 INV.-923.31
TOP-724.12 INV.-923.42
TOP-723.93 INV.-923.53
TOP-723.74 INV.-923.64
TOP-723.55 INV.-923.75
TOP-723.36 INV.-923.86
TOP-723.17 INV.-923.97
TOP-722.98 INV.-924.08
TOP-722.79 INV.-924.19
TOP-722.60 INV.-924.30
TOP-722.41 INV.-924.41
TOP-722.22 INV.-924.52
TOP-722.03 INV.-924.63
TOP-721.84 INV.-924.74
TOP-721.65 INV.-924.85
TOP-721.46 INV.-924.96
TOP-721.27 INV.-925.07
TOP-721.08 INV.-925.18
TOP-720.89 INV.-925.29
TOP-720.70 INV.-925.40
TOP-720.51 INV.-925.51
TOP-720.32 INV.-925.62
TOP-720.13 INV.-925.73
TOP-719.94 INV.-925.84
TOP-719.75 INV.-925.95
TOP-719.56 INV.-926.06
TOP-719.37 INV.-926.17
TOP-719.18 INV.-926.28
TOP-718.99 INV.-926.39
TOP-718.80 INV.-926.50
TOP-718.61 INV.-926.61
TOP-718.42 INV.-926.72
TOP-718.23 INV.-926.83
TOP-718.04 INV.-926.94
TOP-717.85 INV.-927.05
TOP-717.66 INV.-927.16
TOP-717.47 INV.-927.27
TOP-717.28 INV.-927.38
TOP-717.09 INV.-927.49
TOP-716.90 INV.-927.60
TOP-716.71 INV.-927.71
TOP-716.52 INV.-927.82
TOP-716.33 INV.-927.93
TOP-716.14 INV.-928.04
TOP-715.95 INV.-928.15
TOP-715.76 INV.-928.26
TOP-715.57 INV.-928.37
TOP-715.38 INV.-928.48
TOP-715.19 INV.-928.59
TOP-715.00 INV.-928.70
TOP-714.81 INV.-928.81
TOP-714.62 INV.-928.92
TOP-714.43 INV.-929.03
TOP-714.24 INV.-929.14
TOP-714.05 INV.-929.25
TOP-713.86 INV.-929.36
TOP-713.67 INV.-929.47
TOP-713.48 INV.-929.58
TOP-713.29 INV.-929.69
TOP-713.10 INV.-929.80
TOP-712.91 INV.-929.91
TOP-712.72 INV.-930.02
TOP-712.53 INV.-930.13
TOP-712.34 INV.-930.24
TOP-712.15 INV.-930.35
TOP-711.96 INV.-930.46
TOP-711.77 INV.-930.57
TOP-711.58 INV.-930.68
TOP-711.39 INV.-930.79
TOP-711.20 INV.-930.90
TOP-711.01 INV.-931.01
TOP-710.82 INV.-931.12
TOP-710.63 INV.-931.23
TOP-710.44 INV.-931.34
TOP-710.25 INV.-931.45
TOP-710.06 INV.-931.56
TOP-709.87 INV.-931.67
TOP-709.68 INV.-931.78
TOP-709.49 INV.-931.89
TOP-709.30 INV.-932.00
TOP-709.11 INV.-932.11
TOP-708.92 INV.-932.22
TOP-708.73 INV.-932.33
TOP-708.54 INV.-932.44
TOP-708.35 INV.-932.55
TOP-708.16 INV.-932.66
TOP-707.97 INV.-932.77
TOP-707.78 INV.-932.88
TOP-707.59 INV.-932.99
TOP-707.40 INV.-933.10
TOP-707.21 INV.-933.21
TOP-707.02 INV.-933.32
TOP-706.83 INV.-933.43
TOP-706.64 INV.-933.54
TOP-706.45 INV.-933.65
TOP-706.26 INV.-933.76
TOP-706.07 INV.-933.87
TOP-705.88 INV.-933.98
TOP-705.69 INV.-934.09
TOP-705.50 INV.-934.20
TOP-705.31 INV.-934.31
TOP-705.12 INV.-934.42
TOP-704.93 INV.-934.53
TOP-704.74 INV.-934.64
TOP-704.55 INV.-934.75
TOP-704.36 INV.-934.86
TOP-704.17 INV.-934.97
TOP-703.98 INV.-935.08
TOP-703.79 INV.-935.19
TOP-703.60 INV.-935.30
TOP-703.41 INV.-935.41
TOP-703.22 INV.-935.52
TOP-703.03 INV.-935.63
TOP-702.84 INV.-935.74
TOP-702.65 INV.-935.85
TOP-702.46 INV.-935.96
TOP-702.27 INV.-936.07
TOP-702.08 INV.-936.18
TOP-701.89 INV.-936.29
TOP-701.70 INV.-936.40
TOP-701.51 INV.-936.51
TOP-701.32 INV.-936.62
TOP-701.13 INV.-936.73
TOP-700.94 INV.-936.84
TOP-700.75 INV.-936.95
TOP-700.56 INV.-937.06
TOP-700.37 INV.-937.17
TOP-700.18 INV.-937.28
TOP-699.99 INV.-937.39
TOP-699.80 INV.-937.50
TOP-699.61 INV.-937.61
TOP-699.42 INV.-937.72
TOP-699.23 INV.-937.83
TOP-699.04 INV.-937.94
TOP-698.85 INV.-938.05
TOP-698.66 INV.-938.16
TOP-698.47 INV.-938.27
TOP-698.28 INV.-938.38
TOP-698.09 INV.-938.49
TOP-697.90 INV.-938.60
TOP-697.71 INV.-938.71
TOP-697.52 INV.-938.82
TOP-697.33 INV.-938.93
TOP-697.14 INV.-939.04
TOP-696.95 INV.-939.15
TOP-696.76 INV.-939.26
TOP-696.57 INV.-939.37
TOP-696.38 INV.-939.48
TOP-696.19 INV.-939.59
TOP-696.00 INV.-939.70
TOP-695.81 INV.-939.81
TOP-695.62 INV.-939.92
TOP-695.43 INV.-940.03
TOP-695.24 INV.-940.14
TOP-695.05 INV.-940.25
TOP-694.86 INV.-940.36
TOP-694.67 INV.-940.47
TOP-694.48 INV.-940.58
TOP-694.29 INV.-940.69
TOP-694.10 INV.-940.80
TOP-693.91 INV.-940.91
TOP-693.72 INV.-941.02
TOP-693.53 INV.-941.13
TOP-693.34 INV.-941.24
TOP-693.15 INV.-941.35
TOP-692.96 INV.-941.46
TOP-692.77 INV.-941.57
TOP-692.58 INV.-941.68
TOP-692.39 INV.-941.79
TOP-692.20 INV.-941.90
TOP-692.01 INV.-942.01
TOP-691.82 INV.-942.12
TOP-691.63 INV.-942.23
TOP-691.44 INV.-942.34
TOP-691.25 INV.-942.45
TOP-691.06 INV.-942.56
TOP-690.87 INV.-942.67
TOP-690.68 INV.-942.78
TOP-690.49 INV.-942.89
TOP-690.30 INV.-943.00
TOP-690.11 INV.-943.11
TOP-689.92 INV.-943.22
TOP-689.73 INV.-943.33
TOP-689.54 INV.-943.44
TOP-689.35 INV.-943.55
TOP-689.16 INV.-943.66
TOP-688.97 INV.-943.77
TOP-688.78 INV.-943.88
TOP-688.59 INV.-943.99
TOP-688.40 INV.-944.10
TOP-688.21 INV.-944.21
TOP-688.02 INV.-944.32
TOP-687.83 INV.-944.43
TOP-687.64 INV.-944.54
TOP-687.45 INV.-944.65
TOP-687.26 INV.-944.76
TOP-687.07 INV.-944.87
TOP-686.88 INV.-944.98
TOP-686.69 INV.-945.09
TOP-686.50 INV.-945.20
TOP-686.31 INV.-945.31
TOP-686.12 INV.-945.42
TOP-685.93 INV.-945.53
TOP-685.74 INV.-945.64
TOP-685.55 INV.-945.75
TOP-685.36 INV.-945.86
TOP-685.17 INV.-945.97
TOP-684.98 INV.-946.08
TOP-684.79 INV.-946.19
TOP-684.60 INV.-946.30
TOP-684.41 INV.-946.41
TOP-684.22 INV.-946.52
TOP-684.03 INV.-946.63
TOP-683.84 INV.-946.74
TOP-683.65 INV.-946.85
TOP-683.46 INV.-946.96
TOP-683.27 INV.-947.07
TOP-683.08 INV.-947.18
TOP-682.89 INV.-947.29
TOP-682.70 INV.-947.40
TOP-682.51 INV.-947.51
TOP-682.32 INV.-947.62
TOP-682.13 INV.-947.73
TOP-681.94 INV.-947.84
TOP-681.75 INV.-947.95
TOP-681.56 INV.-948.06
TOP-681.37 INV.-948.17
TOP-681.18 INV.-948.28
TOP-680.99 INV.-948.39
TOP-680.80 INV.-948.50
TOP-680.61 INV.-948.61
TOP-680.42 INV.-948.72
TOP-680.23 INV.-948.83
TOP-680.04 INV.-948.94
TOP-679.85 INV.-949.05
TOP-679.66 INV.-949.16
TOP-679.47 INV.-949.27
TOP-679.28 INV.-949.38
TOP-679.09 INV.-949.49
TOP-678.90 INV.-949.60
TOP-678.71 INV.-949.71
TOP-678.52 INV.-949.82
TOP-678.33 INV.-949.93
TOP-678.14 INV.-950.04
TOP-677.95 INV.-950.15
TOP-677.76 INV.-950.26
TOP-677.57 INV.-950.37
TOP-677.38 INV.-950.48
TOP-677.19 INV.-950.59
TOP

FED. RD.	STATE	PROJECT	
2	OHIO		

237
492

MAH - 18 - 17.20



LEGEND FOR INTERSECTIONS

- (A) STANDARD LONGITUDINAL JOINT.
- (B) STANDARD KEY JOINT WITHOUT TIE BARS.
- (C) EXPANSION JOINT WITHOUT DOWELS - LOCATED ON RADIAL LINES.
- (D) STANDARD EXPANSION JOINT.
- (E) STANDARD CONTRACTION JOINT - PLACED AT 60' INTERVALS OR LESS.


NOTE: ALL ELEVATIONS SHOWN ARE FINISH SURFACE PAV'T. GRADES.

SCALE: 1" = 20'-0"

INTERSECTION DETAILS ~ SALT SPRINGS

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20



JOINT LEGEND

- (A) STANDARD LONGITUDINAL JOINT
- (B) STANDARD KEY JOINT WITHOUT TIE BARS
- (C) EXPANSION JOINT WITHOUT DOWELS - LOCATED ON RADIAL LINES
- (D) STANDARD EXPANSION JOINT
- (E) STANDARD CONTRACTION JOINT - PLACED AT 60' INTERVALS OR LESS
- (F) SPECIAL JOINT

I-12 CONCRETE CURB

CODE	STATION FROM	STATION TO	TYPE G	TYPE 2-A
C-1	1+28.33	1+39.50	11 ⌐	
C-2	1+28.33	1+39.50	11 ⌐	
C-3	17+93.35 "D"	1+28.33 BRIDGE		148 ⌐
C-4	–	–		102 ⌐
C-5	–	–		166 ⌐
C-6	–	–		100 ⌐
C-7	17+93.35	19+09.78		135
TOTALS			22	651

INTERSECTION DETAIL - RAMP "D", BRIDGE ST. & SALT SPRINGS

FED. RD	STATE	PROJECT
?	OHIO	

239
492

MAH-18-17.20

END AREA

FINAL SURVEY — SURVEYED — COMPUTED — TEMPLATE — NOTE BOOK — PARTY — NO. — DATE — BY — CHECKED

ORIGINAL SURVEY — SURVEYED — COMPUTED — TEMPLATE — NOTE BOOK — PARTY — NO. — DATE — BY — CHECKED




PLATE 3. CROSS SECTIONS ON 4 X 4 CROSS SECTION STANDARD
KEUFFEL & ESSER CO., NEW YORK.

SALT SPRING RD. STA 0+00 to 1+00

FED. RD.	STATE	PROJECT	
2	OHIO		

240
492

MAH-18-17.20
END AREAS #

FINAL SURVEY
ORIGINAL SURVEY

NOTE BOOK
PLOTTED
CHECKED
AREAS CHECKED
NO.
BY
DATE

2:1
2:1
2:1

E-8

3+00
847.45
P.G. 847.49

C=198
F=5

C=163
F=0

C=285
F=0

C=145
F=0

C=387
F=0

2+50
846.53
P.G. 846.57

C=273
F=0

2+00
845.84
P.G. 845.86

C=308
F=3

C=60
F=3

1+50
845.07
P.G. 845.19

862
850
848
846
844

70 60 50 40 30 20 10 0 10 20 30 40 50 60 70

RELOC. SALT SPRING
PLATE 3 - CROSS SECTION C.P.R.R.R.E. STANDARD
PERRY L.A. ESSER OF NEW YORK

SALT SPRING RD STA 1+50 to 3+00

FED. RD.	STATE	PROJECT	
2	OHIO		

24.1
492

MAH - 18 - 17.20

END AREA

FINAL SURVEY — SURVEYED / PLOTTED / TRACED / NOTE BOOK / NO. / AREAS CHECKED / DATE / BY

ORIGINAL SURVEY — SURVEYED / PLOTTED / TRACED / NOTE BOOK / NO. / AREAS CHECKED / DATE / BY




PLATE 3 CROSS SECTION O. P. R. & R. E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

SALT SPRING RD. 3+50 TO 5+00

FED. RD.	STATE	PROJECT	
	OHIO		

242
492

MAH - 18 - 17.20

FINAL SURVEY
NOTE BOOK
NO
SURVEYED
PLOTTED
TEMPLATE
AREAS CHECKED
DATE

ORIGINAL SURVEY
NOTE BOOK
NO
SURVEYED
PLOTTED
TEMPLATE
AREAS CHECKED
DATE




PLATE 3 - CROSS SECTION O. P. R. & R. E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

SALT SPRING RD. 5+50 TO 7+44.52

FED. RD.	STATE	PROJECT	
2	OHIO		

243
492

MAH-18-17.20

FINAL SURVEY
ORIGINAL SURVEY
DESIGNED
DRAWN
TRACED
CHECKED
QUANTITIES
NOTE BOOK
SHEETS
DATE
NO.

END AREA
STA. 1+50 { F=0

F=5

C=18
F=12

860
858

859.22
E-8
END CONSTRUCTION
1+25
859.22

C=15
F=17

856.09
E-8
C=14
F=24
856
854

1+00
856.07

C=37
F=24

852
850

850.50±
E-8
(SEE SALT SPRINGS RD. X-SEC.)
0+50
850.55

C=26
F=2

C=14
F=11

852
850

840.20
½' PER FT.
E-8
(SEE SALT SPRINGS RD. X-SEC.)
BEGIN CONSTRUCTION
0+25.2
840.36

C=5
F=21

80 70 60 50 40 30 20 10 ℄ 10 20 30 40 50 60

PLATE 3 CROSS SECTION O.P.R.&R.E. STANDARD
KEUFFEL & ESSER CO., NEW YORK

ONETA ST. 0+25.2 TO 1+25

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

244
492

ESTIMATED QUANTITIES I-8 INLETS, MANHOLES & CATCH BASINS		
CODE	LOCATION & STATION	# 2-2A EACH
A-1	0+50 45' RT. ℄	1
A-2	0+50 20' RT. ℄	1
A-3	0+50 20' LT. ℄	1
SHEET TOTAL		3 ✓

ESTIMATED QUANTITIES I-2 PIPES				
CODE	LOCATION		CLASS "A" STORM SEWER M-6.4 c	CL. "B" STORM SEWER UNDER PAVEMENT & APPROACHES
	FROM	TO	12"	18"
P-1	A-1	A-2	26	
P-2	A-2	A-3		36
P-3	A-3	A-4		60
SHEET TOTAL			26 ✓	96 ✓

ESTIMATED QUANTITIES ITEM L-7 HAND LAID STONE RIP-RAP				
CODE	FROM	TO	AVERAGE THKNS.	SQ. YDS.
W-1	0+75	7+25	2'-6"	614

EROSION CONTROL				
CODE	LOCATION FROM	LOCATION TO	1:1-4 PAVED GUTTER TYPE-1 L.F.	1:1-4 PAVED GUTTER TYPE-1-MOD
E-1	0+50	0+34.87	874	
E-2	0+60	4+00	340	
E-3				10
E-4				10
E-5				10
SHEET TOTAL			1214 ✓	30 ✓

PC-4 ENDWALLS	
CODE	S-1 CLASS "E" CONCRETE C.Y.
A-4	0.30 ✓

SEE SHEET RAMP-B

T.S. 4+33.77
116.05'
END WORK STA. 5+34.87

BRIDGE No. MAH-18-18.28

C.S. STA. 3+65.77

P.T. 6+11.22

RIP-RAP RETAINING WALL FROM STA. 0+75 TO STA. 7+25 (SEE DETAIL THIS SHEET)

℄ CURVE DATA
Δ = 44°00'00"
D_a = 14°00'00"
R = 409.26'
T = 165.58'
L_c = 314.28'

W-1

P.C. 2+96.64

PT STA. 1+54.70

P.C. STA. 0+46.35 AHEAD = STA. 0+44.75 BACK

EXISTING 42" PRICE ROAD

SURVEY LINE

OVERFLOW CHAMBER #19

E-3 E-1 E-2 E-4 E-5 A-1 A-2 A-3 A-4

P-1 P-2

FEATHERED AREA

BEST EXISTING PAVEMENT

T. HUB NEXT TO LIGHT POLE

PUNCH I.P BASE, 14" ELM

T. HUB NEXT TO PRICE RD.

PUNCH I.P NEXT 10" CRAB APPLE TREE

PUNCH I.P AT BASE OF SPILLWAY WALL

MILL CREEK

STA. 0+00 PARK RD.

STA. 0+00 PARK RD. @ INTERSECTION WITH SURVEY LINE

EXISTING 60'

℄ CURVE DATA
Δ = 42°30'00"
R = 200.00'
T = 77.78'
L_c = 148.35'

2'-3" 1:1 6'-0" 2'-6" 2'-3" 1 1 5 3

HAND LAID STONE RIP-RAP RETAINING WALL 0+75 TO 7+25 LAID UP DRY

LEGEND
- NEW PAVEMENT EDGE
- WORK DETAILED ELSEWHERE
- CENTERLINE
- EXIST. EDGE OF PAV'M'T.

A-3 & PRICE ROAD P-3 62.18°I-2 @ .02% PC4 END WALL EXISTING 42" SEWER A-4

PVI STA. 8+15 EL. 922.61

PVT STA. 8+65 EL. 922.36

PVC STA. 7+65 EL. 917.99

+1.51%

-3.23%

100' V.C.

A-3
STA. 0+50 20' LT ℄
I-8 Nº 2-2A
WINDOW EL = 850.10
℄ 18" I-2 = 847.12

A-2
STA. 0+50 20' RT ℄
I-8 Nº 2-2A
WINDOW EL = 850.10
℄ 12" I-2 = 848.02
℄ 18" I-2 = 847.52

A-1
STA. 0+50 45' RT ℄
I-8 Nº 2-2A
WINDOW EL = 847.37
℄ 12" I-2 = 845.20

EQUATION: 0+46.35 AHEAD = 0+44.75 BACK

100' V.C.

PVT STA. 1+01.60 EL. 856.77

PVI STA. 0+51.60 EL. 852.15

PVC STA. 0+00 EL. 850.00

-4.30%

30'-18°I-2 P-1

P-2 40'-18°I-2@.01

PLAN & PROFILE — PARK ROAD

FED. RD.	STATE	PROJECT	245 492
2	OHIO		

MAH-18-17.20

FINAL SURVEY
ORIGINAL SURVEYED
FIELD BOOK
NOTE BOOK
DATE
INITIALS
NO.
CHECKED
DATE
INITIALS

ORIGINAL SURVEY
SURVEYED
DATE
FIELD BOOK
NOTE BOOK
INITIALS
NO.
CHECKED
DATE
INITIALS

PRICE RD.

850.00 ℄

0+00

852.77

1:1

857.00

850.60

0+51.60

BEGIN RET. WALL
STA. 0+75

882.50

C-731

856.77

2:1

1:1

852.60

854.60

1+01.60

860

890.00

C-730

861.23

2:1

1:1

859.15

859.15

1+50

℄

870

100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3-CROSS SECTION O.P.P. & R.R. STANDARD
REMPEL & TESSER CO., NEW YORK

C-198

850

860

PARK RD. 0+00 TO 1+50


FED. RD.	STATE	PROJECT	
2	OHIO		

246
492

MAH-18-17.20

FINAL SURVEY PLOTTED
NOTE BOOK
NO.
SURVEYED
CHKD. BY
AREAS CHECKED

ORIGINAL SURVEY PLOTTED
NOTE BOOK
NO.
SURVEYED
CHKD. BY
AREAS CHECKED



100 80 60 40 20 ℄ 20 40 60 80 100

PLATE 3 CROSS SECTIONS OF PARK RD. STANDARD
ALFRED E. BEACH, NEW YORK

PARK RD. 2+00 TO 3+50

FED. RD.	STATE	PROJECT		247 492
2	OHIO			

930

MAH-18-17.20

C=1090

930

C=2362

930

C=1657

930

C=1209

RAMP "E" EX.

SEE Y.E. X-SECTIONS STA. 962+50

12'

885.14

1:1

882.39

4+09

883.06

231.00

RAMP "E" EX.

SEE Y.E. X-SECTIONS STA. 962+00

17'

889.20

4:1

3:1

1:1

885.96

886.03

4+53

887.96

RAMP "E" EX.

BEGIN DITCH PARK RD.

SEE Y.E. X-SECTIONS STA. 961+50

22'

893.36

1'½'

3:1

1:1

885.06

4+98

891.28

RAMP "E" EX.

SEE Y.E. X-SECTIONS STA. 961+00

1'½'

897.42

2:1

1:1

895.54

5+42

80 60 40 20 ℄ 20 40 60 80

PLATE 1 OF 155 SHEETS DESIGN & DRAWING STANDARD KEUFFEL & ESSER CO., NEW YORK.

PARK RD. 4+09 TO 5+42


FINAL SURVEY — NOTE BOOK — NO. — DATE — SURVEYED — PLOTTED — CHECKED — AREAS — CHECKED

ORIGINAL SURVEY — SURVEYED — PLOTTED — CHECKED — NOTE BOOK — AREAS — CHECKED — NO. — DATE

FED. RD.	STATE	PROJECT	
2	OHIO		


248
492

MAH-18-17.20



LIMITING		STATIONS
0+00	TO	3+94.74
7+27.13	TO	19+50.05

(1)	ITEM T-71	9"	REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
(2)	ITEM I-22	6"	SUBBASE
(3)	ITEM I-12		STANDARD TYPE 2A CONCRETE CURB
(4)			STANDARD LONGITUDINAL JOINT
(5)	ITEM I-13	5"	CONCRETE SIDEWALK INCLUDING 5" CINDER SUBBASE
(6)	ITEM L-9		SEEDING AND PROTECTING
(7)	ITEM I-14		STANDARD TYPE 1 PAVED GUTTER



LIMITING		STATIONS
11+24	TO	19+50.05

TYPICAL SECTION - MARSHALL STREET

FED. RD.	STATE	PROJECT	
2	OHIO		

249
492

MAH-18-17.20

NOTE: THESE QUANTITIES INCLUDE THE INTERSECTIONS OF MARSHALL WITH GLENWOOD, ROCKVIEW, AND EDWARDS.

B.M. #13 ELEV. 902.69
TOP OF STEM - FIRE HYDRANT
15.5' LT. STA. 3+87.50

B.M. #12 ELEV. 903.57
TOP OF STEM - FIRE HYDRANT
N.E. CORNER MARSHALL ST. & GLENWOOD AVE.

STA. 969+15.83 ℄-EXPRESSWAY 1 ℄ APPROACH 2+38.5
R.R. SPK. SET
FB 17 P 9
STA. 979+99.50 R.R. SPK. SET
STA. 976+68.30 X-ON STONE
STA. 9+69+15.83 ℄-EXPRESSWAY & ℄ GLENWOOD AVE.
STA. 0+04.00 MARSHALL 51+40.13 GLENWOOD 50+82.74
STA. 0+04.00 PROP. ℄ GLENWOOD
STA. 7+27.13
7+53.43 MARSHALL 0+00 ROCKVIEW
STA. 10+84.17 MARSHALL 6+65.85 EDWARDS
STA. 7+04.13

THREE STORY BRICK BLD'G.
FOR DETAILS OF ISALY PROPERTY SEE SHEET Nº 253
FOR INTERSECTION DETAILS SEE SHEET NO.
TWO STORY BRICK APARTMENT
ONE STORY CONC. BLK. BLD'G.
NOTE: SEE CROSS SECTIONS FOR S.W. ELEV'S
MATCH LINE FOR ESTIMATED QUANTITIES STA 12+00
WATER VALVES
EXISTING MARSHALL ST.
STONE CURB
BLACKTOP 2½"
BRICK 3¾"
SAND 2"
CONCRETE 4½"

RAMP "G" QUANTITIES

E-8 REMOVAL AND DISPOSAL OF EXIST. PAVEMENT (SY)

CODE	FROM STA	TO STA	LOC	QUANT.
K-1	0+00	12+00	LT&RT	3814

I-13 CONCRETE SIDEWALK

CODE	FROM STA	TO STA	LOC	S.F.
H-1	0+25	7+40	LT.	2230
H-2	7+68	10+60	LT.	1180
H-3	11+04	12+00	LT.	1110
H-4	APP. SLAB	51+94.39	GLEN LT	751

I-14 TYPE I PAVED GUTTER

CODE	FROM STA	TO STA	LOC	LIN FT.
P-1	11+24	12+00	RT	76

I-12 CONCRETE CURB-TYPE 2A

CODE	FROM STA	TO STA	LOC	LIN. F.
G-1	0+23	7+43	LT	741
G-2	7+65	10+64	LT	321
G-3	11+04	12+00	LT	108
G-4	APP SLAB	3+94.74	RT	377
G-5	7+27.13	10+64	RT	341
G-6	11+04	12+00	RT	113
G-7	APP SLAB	51+94.39	GLEN LT	110

E-8 REMOVAL & STORAGE OF EXISTING CURB (L.F.)

CODE	FROM STA	TO STA	LOC.	L.F.
A-1	0+15	7+43	LT.	770
A-2	7+65	10+71	LT.	352
A-3	10+98	12+00	LT.	124
A-4	0+20	3+94.74	RT.	403
A-5	7+66	10+71	RT.	323
A-6	10+98	12+00	RT.	123
A-7	APP SLAB	51+94.39	GLEN LT	110

F.B. 21 PGS. 2-41
F.B. 2 PGS. 5,9&11
F.B. 17 PGS. 9&10

5" PCC DRIVEWAY APPROACH

CODE	ITEM	WIDTH	TYPE	QUANTITY
J-1	T-71	16 FT.	DOUB. PRI.	16 SY
J-2	T-71	16 FT.	DOUB. PRI.	16 SY
J-3	T-71	16 FT.	DOUB. PRI.	16 SY
J-4	T-71	16 FT.	DOUB. PRI.	16 SY
J-5	T-71	60 FT.	DOUB. BUS.	60 SY
J-6	T-71	30 FT.	SIN. BUS.	30 SY
J-7	T-71	60 FT.	DOUB. BUS.	60 SY
J-8	T-71	16 FT.	DOUB. PRI.	16 SY
J-9	T-71	10 FT.	SIN. PRI.	10 SY
J-10	T-71	16 FT.	DOUB. PRI.	16 SY
J-11	T-71	10 FT.	SIN. PRI.	10 SY
J-12	T-71	10 FT.	SIN. PRI.	10 SY
J-13	T-71	16 FT.	DOUB. PRI.	16 SY
J-27	T-71	10 FT.	SIN. PRI.	10 SY

E-8 REMOVAL OF EXISTING & DISPOSAL SIDEWALK (S.F.)

CODE	FROM STA.	TO STA.	LOC.	QUANT.
B-1	0+25	7+40	LT.	4518
B-2	7+68	10+71	LT.	1974
B-3	10+98	12+00	LT.	1498
B-4	0+25	3+94.74	RT.	2418
B-5	7+68	10+71	RT.	1986
B-6	10+98	12+00	RT.	780
B-7	APP. SLAB	51+94.39	GLEN. LT.	710

NOTE: SEE MARSHALL ST. UNDERGROUND SHEET Nº [ ] FOR WATER MAIN QUANTITIES

APPROX. PROFILE OF EXIST. WATER MAIN.
PROP. 12" C.I.P.
EXIST. 12" C.I.P.
5' CONSTANT DEPTH
GRAPHIC GRADE
-1.75%

STA. 2+93.4
EXIST. MANHOLE ℄
COVER ELEV 904.4
℄ 12" PIPE 894.84

STA. 4+94.3
EXIST. MANHOLE - ℄
COVER ELEV. 894.31
℄ 12" PIPE 886.11
℄ 15" PIPE 886.11

STA. 7+53.43
EXIST. MANHOLE - ℄
COVER ELEV. 876.67
℄ MANHOLE 866.47

END LOWERING WATER MAIN @ STA. 7+00
℄ ROCKVIEW 7+53.43 875.18

STA 10+84.17
EXIST. MANHOLE ℄
COVER ELEV 862.75
℄ 15" PIPE WEST 862.90
℄ 15" PIPE NORTH 862.35

STA 11+05.70
EXIST. MANHOLE ℄
COVER ELEV 871.47
℄ 12" PIPE EAST 861.11

PLATE 1 - CROSS SECTION OF N.Y. STANDARD
KEMPPEL & ESSER CO., NEW YORK

MARSHALL ST. - STA. 0+00 TO STA. 12+00

FED. RD.	STATE	PROJECT	
2	OHIO		

250
492

MAH-18-17.20

E-8 REMOVAL OF EXISTING SIDEWALK

CODE	FROM STA	TO STA	LOC	S.F.
B-8	12+00	20+00	LT	4878
B-9	20+33	22+00	LT	907
B-10	12+00	19+50.05	RT	4320

E-8 REMOVAL AND DISPOSAL OF EXISTING RIGID PAVEMENT

CODE	FROM STA	TO STA	LOC	SY
K-2	12+00	22+00	LT. & RT.	2836

E-8 REMOVAL & STORAGE OF EXISTING CURB (L.F)

CODE	FROM STA	TO STA	LOC	LIN. FT.
A-8	12+00	20+02	LT.	822
A-9	20+32	22+00	LT.	188
A-10	12+00	19+50.05	RT.	715
A-11	22+00	22+50	LT	50
A-12	22+00	22+50	RT	50

I-13 CONCRETE SIDEWALK

CODE	FROM STA	TO STA	LOC	S.F.
H-5	12+00	20+00	LT.	2424
H-6	20+33	22+00	LT.	716

I-12 CONCRETE CURB (L.F)

TYPE	CODE	FROM STA	TO STA	LOC	LIN. FT.
2-A	G-8	12+00	20+02	LT	773
2-A	G-9	20+32	22+00	LT	179
2-A	G-10	12+00	19+50.05	RT	723
C	G-11	22+00	22+50	LT & RT	100

I-14 PAVED GUTTER TYPE I MOD

CODE	L.F.
P-5	10
P-6	10

DRIVEWAY APPROACHES (SY)

CODE	ITEM	WIDTH @ CURB	WIDTH @ S.W.	QUANT.
J-14	T-71	16 FT	DBL. PRI.	16
J-15	T-71	30	SIN. BUS.	30
J-16	T-71	10	SIN. BUS.	10
J-17	T-71	16	DBL. PRI.	16
J-18	T-71	16	DBL. PRI.	16
J-19	T-71	10	SIN. PRI.	10
J-20	T-71	16	DBL. PRI.	16
J-21	T-71	16	DBL. PRI.	16
J-22	T-71	10	SIN. PRI.	10
J-23	T-71	16	DBL. PRI.	16
J-24	T-71	30	SIN. BUS.	30
J-25	T-71	10	SIN. PRI.	10
J-26	T-71	10	SIN. PRI.	10
J-27	T-71	30	SIN. BUS.	30
J-28	T-71	30	SIN. BUS.	30

I-14 TYPE 1 PAVED GUTTER

CODE	FROM STA	TO STA	LOC.	LIN. FT.
P-2	12+00	13+78	RT.	168
P-3	14+03	16+78	RT.	265
P-4	17+03	19+50.05	RT.	247

MATCH LINE FOR ESTIMATED QUANTITIES STA 12+00

EDWARDS ST

MARSHALL ST

WEST AVE NORTH

EXPRESSWAY

STA. 989+27.04 "X" CUT IN BR. PAV'T.

ONE STORY CONC. BLOCK BL'D'G.

TWO STY. FR. HO.

TWO STORY BRICK BL'D'G. WAREHOUSE

ONE STORY BRICK BL'D'G. WAREHOUSE

ONE STORY VIT. BLOCK BL'D'G.

ONE STORY CONC. BLOCK BL'D'G. WAREHOUSE

ONE STORY BLOCK.

TWO STORY BRICK BL'D'G.

20+17.38 MARSHALL 0.00 WEST

130 EXIST. ℄

PROP. ℄

RAMP "J" QUANTITIES

10+50.05 14+85.52 RAMP "J"

FEATHER AREA

END NORMAL STA. 22+50

END T-71 PAV'T STA. 22+00

BM. #14 ELEV. 872.07
TOP OF STEM FIRE HYDRANT
S.E. CORNER MARSHALL AVE. & WEST ST.

STA. 10+84.17
EXIST. MANHOLE - ℄
COVER ELEV. - 872.75
℄ 15" PIPE WEST - 862.90
℄ 15" PIPE NORTH - 862.35

STA. 11+95.70 - ℄
EXIST. MANHOLE
COVER 871.47
℄ 12" EAST 862.50

STA. 14+93.40
0.40' LT. ℄
EXIST. MANHOLE
COVER ELEV.
℄ 12" PIPE E & W. 860.40

STA. 17+87.30 ℄
EXIST. MANHOLE
COVER ELEV 868.77
℄ 12" PIPE 858.37
℄ 15" PIPE 858.12

STA. 19+74 - ℄
EXIST. MANHOLE
COVER ELEV. 868.96
℄ 15" PIPE E & W. 857.16

STA. 20+17.8 25.8' LT.
EXIST. MANHOLE ℄ WEST AVE. (NORTH)
COVER ELEV. 866.51
℄ 15" PIPE NORTH 856.08

STA. 10+84.17

100' V.C.

P.I. STA. 13+50
EL. 870.67

GRADE

-0.4250%

STA. 17+77.96 ℄ PLUM ST.
ELEV. 869.09

STA. 20+17.38 ℄ WEST AVE.

P.I. STA. 20+60
EL. 867.65

-5.372%

EXIST. 15" COMB. SEWER

MEET EXIST. PAV'T. STA. 22+00

MARSHALL ST. - STA. 12+00 TO STA. 22+00

PLATE 17 SECTION OF PIPE & STAFF
REGFFEL & ESSER CO. NEW YORK


FED. RD.	STATE	PROJECT	
2	OHIO		

251
492

MAH-18-17.20

I-124 LOWER WATER LINE (6" C.I.P.)

CODE	FROM	TO	LOCA.	LIN. FT.
W-1	0+04	7+00	10' LT. ℄	696



I-8 CITY OF YOUNGSTOWN CATCH BASINS

CODE	TYPE	STA	LOC	WINDOW	INVT
D-1	2	4+00	NORTH	876.00	871.00
D-2	2	7+15.43	NORTH	876.16	871.16
D-3	2	10+37.07	NORTH	872.05	867.05
D-4	2	10+32.64	SOUTH	872.06	867.06
D-5	2	14+00	NORTH	869.03	864.03
D-6	2	14+00	SOUTH	869.03	864.03
D-7	2	17+00	NORTH	868.65	863.65
D-8	2	17+00	SOUTH	868.65	863.65
D-9	2	19+75.52	NORTH	867.48	862.48
D-10	1	3/4 PT	SOUTH	871.55	868.24
D-11	1	1/4 PT	SOUTH	871.51	868.20

I-2 COMBINATION SEWERS UNDER PAVEMENT & APPROACHES - M-6.8(b)


CODE	FROM ST	TO STA.	LOC.	SIZE	L.F.
C-1	4+00	4+15.5	NORTH	12"	22
C-2	7+15.69	7+31.19	NORTH	12"	22
C-3	10+43.45	10+58.95	NORTH	12"	22
C-4	10+32.45	10+52.95	SOUTH	12"	20
C-5	14+00	14+15.50	NORTH	12"	22
C-6	14+00	14+20.50	SOUTH	12"	20
C-7	17+00	17+15.50	NORTH	12"	22
C-8	17+00	17+20.50	SOUTH	12"	22
C-9	19+75.52	19+74	NORTH	12"	16
C-10	13+89	14+00	SOUTH	12"	8
C-11	16+89	17+00	SOUTH	12"	8
C-12	10+74	—	N & S	21"	84
C-13	3/4 PT	10+74	SOUTH	12"	15
C-14	1/4 PT	10+74	SOUTH	12"	40

I-16 INLETS ABANDONED

CODE	STA	LOC	REMARKS
F-1	0+18	29' RT	PLUG LEAD
F-2	0+27	23' RT	PLUG LEAD
F-3	4+57	16' LT	PLUG LEAD
F-4	7+18	16' LT	PLUG LEAD
F-5	10+48	16' LT	PLUG LEAD
F-6	10+43	10.5' RT.	PLUG LEAD
F-7	10+65	30' RT.	PLUG LEAD
F-8	10+92	28' RT.	PLUG LEAD
F-9	14+58	16' LT.	PLUG LEAD
F-10	14+73	10.5' RT.	PLUG LEAD
F-11	17+45	16' LT.	PLUG LEAD
F-12	17+53	10.5' RT.	PLUG LEAD
F-13	18+48	10.5' RT.	PLUG LEAD
F-14	19+08	10.5' RT.	PLUG LEAD
F-15	19+83	16' LT.	PLUG LEAD

I-8 2-2A CATCH BASINS

CODE	STA.	LOC.	WINDOW	INV
N-1	13+89	20.5' RT.	869.71	867.54
N-2	16+89	20.5' RT.	868.39	866.22



I-8 M.H.'s ADJ TO GRADE

CODE	STA.	LOC.
E-1	0+60	2.5' LT
E-2	2+93.4	2.5' LT
E-3	4+54.3	2.5' LT
E-4	10+84.17	2.5' LT
E-5	10+74.17	2.7' LT
E-6	11+35.7	2.5' LT
E-7	14+93.4	2.5' LT
E-8	17+87.3	2.5' LT
E-9	19+74	2.5' LT

I-124 FIRE HYDRANTS REMOVED & RESET

CODE	QUANTITY
H-1	1
H-2	1
H-3	1
H-4	1
H-5	1

I-124 VALVE BOX ADJ. TO GRADE

CODE	STA	LOC
M-1	0+24	28.5' LT.
M-2	3+82.4	17.3' LT.
M-3	7+56	11.5' RT.
M-4	7+66	8.5' LT.
M-5	11+01.4	8.5' LT.
M-6	10+90	13.3' RT.
M-7	20+17.8	7.7' LT.

UNDERGROUND MARSHALL STREET


FED. RD.	STATE	PROJECT	
2	OHIO		

252
492


MAH-18-17.20

MEET EXISTING SIDEWALK & END T-71 PAV'T. @ STA. 22+00. CONSTRUCT TYPE 2 COMBINED CURB & GUTTER FROM STA. 22+00 TO STA. 22+50 (MEET EXISTING CURBS); FEATHER TO MEET EXISTING PAVEMENT AT STA. 22+50

NOSE ~ GRT 21+44.14



INTERSECTION ~ MARSHALL & EDWARDS



INTERSECTION ~ MARSHALL & WEST

GENERAL NOTES


ALL ELEVATIONS SHOWN AT CURB LINE ARE TOP OF CURB

ALL ELEVATIONS SHOWN AT CURB RETURNS ARE AT QUARTER POINTS


SCALE: 1" = 20'

JOINT LEGEND

- (A) STANDARD LONGITUDINAL JOINT
- (B) STANDARD KEY JOINT WITHOUT TIE BARS
- (C) EXPANSION JOINT WITHOUT DOWELS (LOCATED ON RADIAL LINES)
- (D) STANDARD EXPANSION JOINTS
- (E) STANDARD CONTRACTION JOINTS (TO BE PLACED AT 60' INTERVALS OR LESS IN ALL T-71 PAVEMENT



INTERSECTION ~ MARSHALL & GLENWOOD




INTERSECTION ~ MARSHALL & ROCKVIEW

PAVEMENT DETAILS ~ MARSHALL ST.

FED. RD.	STATE	PROJECT	
2	OHIO		

253
492

MAH-18-17.20



TYPICAL SECTION @ "A-A"

TYPICAL SECTION @ "B-B"

TYPICAL SECTION @ "C-C"

NOTE: EXCAVATION QUANTITIES FOR PARKING & LOADING AREAS ARE INCLUDED IN ROADWAY EXCAVATION QUANTITIES ON "X-SECTION SHEETS OF MARSHALL ST.

ITEM E-8 REMOVAL & DISPOSAL OF EXIST. S. WALK (S.FT.)

CODE	FROM	TO	LOCA.	QUAN.	REMARKS
B-1A	2+48	——	28'-53' LT.	260 ✓	

ITEM I-13 CONCRETE SIDEWALK (S.FT.)

CODE	FROM	TO	LOCA.	QUAN.	REMARKS
H-1A	2+48	——	28'-53' LT.	260 ✓	SET TO LINE & GRADE

SS-18

ITEM SS-18 REMOVAL & REPLACEMENT OF EXISTING CHAIN LINK FENCE & GATES (LIN. FT.)

CODE	FROM	TO	LOCA.	QUAN.	REMARKS
V-1	2+46	-	LT.	65 ✓	
V-2	2+80	-	LT.	65 ✓	
V-3	3+00	-	LT.	45 ✓	
V-4	3+00	4+60	LT.	160 ✓	

ITEM SS-18 FENCE - TYPE "A"

CODE	FROM	TO	LOCA.	QUAN.	REMARKS
N-1	0+34	2+45		235 ✓	

ITEM T-10 TRAFFIC COMPACTED SURFACE COURSE (CU. YDS)

CODE	FROM	TO	LOCA.	DEPTH	QUANT.	REMARKS
W-1	0+34	2+46	LT.	6"	212 ✓	PARKING AREA
W-2	2+50	3+00	27'-53' LT.	6"	60 ✓	" "

ITEM B-10 AGGREGATE BASE COURSE (CU. YDS.)

CODE	FROM	TO	LOCA.	DEPTH	QUAN.	REMARKS
X-1	3+00	4+00	27'-74' LT.	6"	63 ✓	LOADING AREA

ITEM T-35 ASPHALTIC CONC. SURFACE COURSE (DRIVES)

CODE	FROM	TO	LOCA.	DEPTH	QUANTITY C.Y.	REMARKS
Y-1	3+00	4+00	27'-74' LT.	3"	37 ✓	TYPE "C"

DAIRY PROPERTY ON MARSHALL ST.

FED. RD.	STATE	PROJECT		254 / 452
2	OHIO			

MAH -18-17.20

ORIGINAL SURVEY — CERTIFIED CORRECTED — FINAL SURVEY — NOTE BOOK — DATE — BY — NO.

70 60 50 40 30 20 10 ℄ 10 20 30 40 50 60

"B" "B" ¼"/1' T-10 EXIST FENCE "B" "B" 905 903 902.96 80 70

EXISTING FENCE 901 "A" 899 "A" 897

903.54 903.21 902.93

STA. 970+64.58 EXPRESSWAY

1+50 (902.24)

1/4"/1' T-10 "A" "A" EXIST. FENCE 1/4"/1' 902.37

903.76 903.36 903.14

STA. 970+14.58 EXPRESSWAY

1+0 (905.82)

904 902 900 110 100 90 80 70 FENCE 1/4"/1' 903.04 EXISTING NORTH R/W LINE

903.78 903.38 EXISTING ℄ 903.55 903.16

STA. 969+64.58 EXPRESSWAY

0+50 (903.01)

903.17

0+33 (903.63)

STA. BEGIN WORK AND CONTRACT

2.5'

905 C.Y. 75

903 C = 382.0

C.Y. 674

906

C = 346.0

904

902

906 C.Y. 550

904

902

906 C = 248.0

904

C.Y. 78

904

902 C = 0.0

70 60 50 40 30 20 10 ℄ 10 20 30 40 50 60 70

PLATE 3 CROSS SECTIONS OF PROPOSED IMPROVEMENT AS SHOWN ON PLANS

X- SECTIONS MARSHALL ST. STA. 0+00 TO STA. 1+50

FED. RD.	STATE	PROJECT	
2	OHIO		

255/492

MAH-18-17.20

70 60 50 40 30 20 10 ℄ 10 20 30 40 50 60

EXISTING ℄

MEET EXIST. GROUND @BLDG. ELEV. 902.40

3 STORY BUILDING

MEET EXIST'G GROUND 93.0' LT. ℄ EL. 902.30

"C" 904 902 "C"

90 80 70

900.61 900.72 P.G. 900.24

3+0 (903.98)

STA. 972+14.58 EXPRESSWAY

EXISTING NORTH

2.5'

'C' 'C'

DRIVEWAY

901.20 901.31 P.G.

"B" 903 901 "B"

1/4"/1'

90 80 70

R/W LINE

2+75 (904.75)

STA. 971+80.58 EXPRESSWAY

'B' 'B'

1/4"/1'

902.04 901.82 P.G. 902.04

EXISTING FENCE

'A' 904 902 'A'

1/4"/1'

901.60

90 80 70

2+50 (905.22)

STA. 971+64.58 EXPRESSWAY

'A' 'A'

DRIVEWAY

1/4"/1'

902.46 902.57 P.G. 902.76

2+0 (906.27) ℄

STA. 971+14.58 EXPRESSWAY

70 60 50 40 30 20 10 ℄ 10 20 30 40 50 60 70

END AREA C.Y.

906

904

902 C=275.0

904 613

902

905

C=387.0

903

901 762

C=436.0

906

904 758

902


PLATE 7 CROSS SECTION C. P. R. R. E. STANDARD KEUFFEL & ESSER CO. NEW YORK.

X-SECTIONS MARSHALL ST. STA. 2+00 - STA. 3+00

FED. RD.	STATE	PROJECT	
2	OHIO		

256
492

MAH-18-17.20



FINAL SURVEY — SURVEYED — COMPUTED — PLANIMETER — NOTE BOOK — AREAS — AREAS CHECKED — BY — DATE — NO.

ORIGINAL SURVEY — SURVEYED — COMPUTED — PLANIMETER — NOTE BOOK — AREAS — AREAS CHECKED — BY — DATE — NO.

PLATE 1 CROSS SECTION SHEET FOR FEDERAL AID PROJECT NO. AS YSHOWN ON PLAN

X- SECTIONS - MARSHALL ST. STA. 3+06 - STA. 4+0

| | | |

ORIGINAL SURVEY

FINAL SURVEY

SEEDING END WIDTH	SEEDING SQ. YDS


END AREA CUT	END AREA FILL	CU. YDS. CUT	CU. YDS. FILL



12+50
(871.10)

872
STA. 981+64.58 EXPRESSWAY
870


23.2 | 47



12+00
(871.80)

872
STA. 981+14.58 EXPRESSWAY
870


17.2 | 38



11+50
(871.88)


872
STA. 980+64.58 EXPRESSWAY
870

28.3 | 42



11+00
(872.52)

874
STA. 980+14.58 EXPRESSWAY
872




10+84.17
(872.79)

℄ EDWARDS ST.

874
872

6+20


4.6 | 1.0



10+50
(872.40)

874
872
STA. 979+64.58 EXPRESSWAY


21.9 | 1.1



10+00
(872.60)

874
872
STA. 979+14.58 EXPRESSWAY


21.9 | 1.0 | 4.0 | 2.0



9+50
(872.82)

874
872
STA. 978+64.58 EXPRESSWAY

28.5 | 0.8 | 4.7 | 1.6 | 6.0 | 1.7



9+00
(873.10)

874
872
STA. 978+14.58 EXPRESSWAY

35.7 | 1.0

X-SECTIONS MARSHALL ST. STA. 9+00 - STA. 12+50

FED. RD.	STATE	PROJECT
2	OHIO	MAH-18-17.20

255 252

END AREA CUT	END AREA FILL	CU. YDS. CUT	CU. YDS. FILL
24.3		44	0.3
22.9		43	
24.7		44	
25.6		47	
25.2		51	
26.3		52	
24.8		47	
26.5		50	
25.5		50	
21.8		50	

FED. RD.	STATE	PROJECT	
2	OHIO		

259
492

MAH-18-17.20

STA. 986+64.58 EXPRESSWAY 868
STA. 986+14.58 EXPRESSWAY 868
STA. 985+64.58 EXPRESSWAY 868
STA. 985+14.58 EXPRESSWAY 868
STA. 984+64.58 EXPRESSWAY 868
STA. 984+14.58 EXPRESSWAY 870
STA. 983+64.58 EXPRESSWAY 870
STA. 983+14.58 EXPRESSWAY 870
STA. 982+64.58 EXPRESSWAY 870
STA. 982+14.58 EXPRESSWAY 870

868.97 P.G. 869.19 869.19
868.18 P.G. 869.40 869.40
869.39 P.G. 869.61 869.61
869.61 P.G. 869.83 869.83
869.82 P.G. 870.04 870.04
870.03 P.G. 869.92 870.25
870.25 P.G. 870.14 870.47
870.46 P.G. 870.68 870.68
870.69 P.G. 870.91 870.91
870.96 P.G. 870.85 871.18

17+50 (868.71)
17+00 (869.11)
16+50 (869.45) EXISTING
16+00 (869.45)
15+50 (869.79)
15+00 (869.99)
14+50 (870.15)
14+00 (870.50)
13+50 (870.70)
13+00 (870.89)

EXIST. ℄

EXIST. & PROP. NORTH R/W LINE

DRIVEWAY APPROACH

DRIVEWAY APPROACH

ONE STORY BLOCK BLDG

1/4":1'

SEEDING END SQ WIDTH YDS

X-SECTIONS MARSHALL ST. STA. 13+0 - STA. 17+50

ORIGINAL SURVEY
FINAL SURVEY

SEEDING	
END WIDTH	SQ. YDS

END AREA		CU. YDS.	
CUT	FILL	CUT	FILL

22+50
END CONTRACT

MEET EXIST. S.W.

860.12 P.G.

22+00
(860.12)

863.06 P.G.

21+50
(862.80)

865.48 P.G.

21+00
(865.62)

867.29 P.G.

1/4"/1'

20+50
(868.22)

867.83 P.G.

20+17.38
(869.14)
℄ WEST AVE.

867.90 P.G.

BLDG.

19+92.38
(868.92)

26'-6"

868.34

868.12 P.G.

868.34

1/4"/1'

19+50
(868.92)

NOTE:
STA. 19+50.05
END TYPE I GUTTER.
RAMP "J" QUANTITIES
TAKEN TO ℄ MARSHALL ST.

TWO STORY BRICK BLDG.

DRIVEWAY APPROACH 1/4"/1'

868.22

868.33 P.G.

868.55

19+00
(868.63)

DRIVEWAY APPROACH 1/4"/1'

868.43

868.54 P.G.

868.76

18+50
(868.51)

EXIST. CONC. DRIVEWAY APPROACH 1/4"/1'

868.98

868.76 P.G.

868.98

18+00
(868.68)

	END AREA CUT	END AREA FILL	CU. YDS. CUT	CU. YDS. FILL
860			6	0.0
858	6.8			
864			8	4.0
862	2.0	4.3		
866			6	6.4
864	4.2	2.6		
868			18	4.0
870	14.6	1.7		
868				
868			147	5.2
866				
870				
868	65.0	1.0		
870			94	1.0
868	36.5	0.0		
870			62	0.3
868	31.7	0.3		
872			51	0.6
870				
870	23.4	0.3		

FED. RD.	
STATE	OHIO
PROJECT	

MAH-18-17.20

2.66
432


40 30 20 10 ℄ 10 20 30 40

X-SECTIONS MARSHALL ST. STA. 18+0 - STA. 22+0


FED. RD.	STATE	PROJECT	
2.	OHIO		

MAH-18-17.20

261
492



LIMITING STATIONS
STA. 3+65.38 – STA. 6+20.00
STA. 7+04.13 – STA. 9+90.32



LIMITING STATIONS
STA. 0+98.66 – STA. 3+00.40

(1) ITEM T-71 9" REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
(2) ITEM I-22 6" SUBBASE
(3) ITEM I-12 STANDARD TYPE 2A CONCRETE CURB
(4) ITEM I-13 5" CONCRETE SIDEWALK (CLASS "C") INCLUDING 5" CINDER SUBBASE
(5) ITEM L-9 SEEDING AND PROTECTING
(6) ST'D LONGITUDINAL JOINT

TYPICAL SECTIONS – EDWARDS ST.

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

262
492

MICROFILMED
SEP 19 1985

T- HUB BY PORCH STEPS HOUSE 903

IRON PIN BY STONE RET. WALL, 12' SW. OF 15" MAPLE

T. HUB, EAST SIDE OF 8" MAPLE, SOUTH OF HOUSE 128

T. HUB BY N.E. COR. HOUSE 901

IRON PIN AT SW. COR. HOUSE 30

PK. NEAREST S. RIM OF MH.

R.R. SPIKE IN WALK AT N.W. COR. WAREHOUSE

IRON PIN BY FRONT PORCH HOUSE 309

R.R. SPIKE

T- HUB W. SIDE OF CHURCH

T-HUB SW. COR. PORCH HOUSE 133

PT. ON MH. COVER

PT. ON MH. COVER

CURVE DATA

Δ = 18°-37'-00"
R = 200.00'
T = 32.78'
L_c = 64.98'

NOTE: TAPER CURB TO 2.0' FROM ℄ IN 10'

BM # 17 A.
"D" CUT IN NW. COR. OF BOTTOM STEP HSE. 1003 HIGH ST. EL. 933.22

BM #18
EDWARDS AND HIGH ST.
F.H. SW. COR. TOP OF STEM
EL. 929.64

BM #25
SW. COR. HO. 903 ON ORANGE
"D" CUT ON CONC. STEP
EL. 901.95

STA. 0+63.31
BEGIN WORK

FOR DETAILS ON RELOCA BURNS ST. SEE SH'T. Nº 268

NOTE: SEE EDWARDS STREET CROSS SECTIONS FOR CROSS SLOPE BETWEEN 0+63.31 ℄ 0+98.66

STA. 6+20
END WORK

STA. 9+99.32
END WORK

STA. 7+04.13
BEGIN WORK

STA. 979+99.50
℄ Y. EXP.

STA. 5+28.84

FOR DETAILS OF PROPOSED & EXIST. R/W LINES SEE TYPICAL SECTIONS SHEET NO. 261

FOR DETAILS OF INTERSECTIONS SEE SHEET Nº 263

FOR LOCATION OF PROPOSED TYPE II. INLETS OR THOSE TO BE ABANDONED OR REMOVED SEE SHEET NO. 263

SEE SH'T. Nº 263 FOR M.H'S. TO BE ADJUSTED TO GRADE.

ITEM E-8 EXIST. SIDEWALK REMOVAL (S.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
B-1	0+63.31	3+32	LT.	1520
B-2	3+54	6+20	LT.	1505
B-3	0+63.31	6+20	RT.	2785
B-4	7+04.13	9+99.32	LT.	1600
B-5	7+04.13	9+99.32	RT.	1600

ITEM I-13 CONC. SIDEWALK REPL. (S.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
H-1	0+63.31	3+30	LT.	1238
H-2	3+58	6+20	LT.	1158
H-3	0+63.31	6+20	RT.	2228
H-4	7+04.13	9+90	LT.	1279
H-5	7+04.13	9+90	RT.	1440

ITEM E-8 REMOVAL & DISPOSAL OF EXISTING RIGID PAVEMENT (SQ. YD.)


CODE	FROM	TO	S.Y.
P-1	0+57.18	6+20	1689
P-2	7+04.13	9+99.32	885
TOTAL			2574

ITEM I-12 CONC. CURB REPLACE. (L.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
G-1	0+63.31	3+37	LT.	292
G-2	3+54	6+20	LT.	260
G-3	0+63.31	6+20	RT.	530
G-4	7+04.13	9+97	LT.	292
G-5	7+04.13	9+97	RT.	291

ITEM E-8 EXIST. CURB REMOVE & STORE (L.F.)

CODE	FROM	TO	LOCA.	QUAN.
A-1	0+63.31	3+37	LT.	307
A-2	3+54	6+20	LT.	300
A-3	0+63.31	6+20	RT.	557
A-4	7+04.13	9+97	LT.	307
A-5	7+04.13	9+97	RT.	306



TYPICAL SECTION
EXISTING EDWARDS ST.

ITEM SS DRIVEWAYS

CODE	STA.	W.A. REQ.	TYPE	QUANT.
J-1	1+05 L			
J-2	1+17 R			
J-3	8+05 L			
J-4	2+12 R			
J-5	3+00 R			
J-6	3+52 R			
J-7	0+78 R			
J-8	7+26 R			
J-9	7+46 R			
J-10	8+10 R			
J-11	8+95 R			
J-12	9+36 R			
J-13	8+20 L			

DRIVE T-18 RCC APPROACHES (SY)

ITEM	QUANT
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3
T-71	5.3

SINGLE PRIVATE

10' ROUNDING

PROFILE GRADES

EXIST. ELEV.

PROF. HIGH ST. WEST
EL. 926.51

P.V.I. STA. 0+25
EL. 926.10

-1.64%

STA. 0+63.31 BEGIN WORK
EL. 922.05

-10.54%

50' V.C.

P.V.I. 1+00
EL. 918.18

-9.09%

12" COMB. SEWER

INV. 909.72 - 12"

P.V.I. STA. 3+00
EL. 900.00

-7.40%

INV. 889.71 - 12"
INV. 885.64 - 15"

P.V.I. STA. 4+00
EL. 892.60

-12.51%

100' V.C.

P.V.I. STA. 4+40
EL. 887.99

-6.99%

15" COMB. SEWER @ 9.00% FOR 150'

STA. 4+74.01 MIN. CLEAR
EL. 883.34

P.V.I. STA. 5+00
EL. 880.09

℄ EXPRESSWAY 979+99.5
5+28.84

P.V.I. STA. 6+00
EL. 871.30

P.V.I. STA. 7+50
EL. 871.15

PROP. ℄ MARSHALL
STA. 6+65.85
EL. 874.43

+1.56%

-1.47%

-1.32%

-4.68%

50' V.C.

100' V.C.

21" @ 1.00% FOR 375'

21" @ 2.00% FOR 45'

P.V.I. STA. 9+50
EL. 868.55

18" COMB. SEWER

INV. 864.32 - 15"
INV. 864.32 - 18"

0+00 1+00 2+00 3+00 4+00 5+00 6+00 7+00 8+00 9+00 10+00

EDWARDS ST. PLAN - PROFILE

PLAN
SURVEYED BY
PLOTTED DATE
ALIGNMENT CHECKED
RT. OF WAY CHECKED
NOTE BOOK
NO.

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
R/W NOTES
NO.
STRUCTURE NOTATIS CHKD

Printed in U.S.A.
On DIETZGEN GRAFTEX MOISTURE PROOF Cloth

PLATE 1 PLAN - PROFILE & TYPICAL SECTIONS

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

263
492

ITEM I-8 MANHOLES-ADJ. TO GRADE (EA)				
CODE	STATION	LOCA.	TOP EL.	REMARKS
E-1	1+75.96	℄	920.72	—
E-2	3+30.66	℄	897.07	


ITEM I-6 INLETS-ABAND (EACH)		
CODE	STATION	LOCA.
F-1	3+05	LT.
F-2	3+14	LT.
F-3	3+23	LT.

ITEM I-2 STORM SEWERS UNDER PAVEMENT & APPROACHES SEC. M6.8(b)					
CODE	FROM STA.	TO STA.	LOCA.	SIZE	L.F.
C-1	3+50	4+50	LT	12"	96
C-2	4+50	6+00	LT	15"	146
C-3	6+00	6+20	LT	21"	18
C-4	7+04.13	9+75	LT	21"	270
C-5	9+75	EX. M.H.	LT.	21"	38
C-6	D-1	D-2	L&R	12"	50
C-7	D-2	L-1	LT	12"	30
C-8	D-3	L-1	LT	12"	38
C-9	D-6	L-4	L&R	12"	30
C-10	D-7	L-4	LT	12"	37
C-11	D-8	L-4	LT	12"	11.5
C-12	D-4	L-2	LT	12"	12
C-13	D-5	L-2	L&R	15"	25
C-14	L-5	E-1	℄	12"	98

372.5 = 12"
326 = 21"
175 = 15"

I-8 INLETS YOUNGSTOWN (No 1)				
CODE	STA.	LOC.	WINDOW	INVT.
D-1	2+03.57	RT	900.21	896.90
D-2	1/4 PT	LT	898.26	894.95
D-3	0+53.81	ORANGE	899.95	896.64
D-4	4+44.84	LT	886.43	883.12
D-5	4+44.84	RT	886.43	881.25
D-6	9+70.19	RT	867.14	863.83
D-7	10+53.51	MAHON	866.88	863.57
D-8	9+70.78	LT	867.08	863.77

ITEM I-8 MANHOLE-ST'D No 1 (EACH)						
CODE	STATION	LOCA.	12" INVERT	15" INVERT	21" INVERT	TOP
L-1	3+50	10' LT.	890.40			896.14
L-2	4+50	10' LT.	880.50	880.25		886.18
L-3	6+00	10' LT.		866.75	866.25	872.52
L-4	9+75	10' LT			862.50	867.37
L-5	1+07	℄	810.50			



ORIGINAL SURVEY — NOTE BOOK — NO. — DATE — SURVEYED — PLOTTED — COMPILED — AREAS

FINAL SURVEY — NOTE BOOK — NO. — DATE — CORRECTED — PLOTTED — COMPILED — AREAS — AREAS CHECKED

50 40 30 20 10 ℄ 10 20 30 40

SEEDING	
END WIDTH	SQ. YDS
—	

END AREA		CU. YDS.	
CUT	FILL	CUT	FILL
		68.7	0.1
38.1	0.0		
		67.4	
34.7			
		33.4	
37.4			
		31.1	
29.7			
		26.5	
27.6			
		6.9	
6.4			

FACE OF BLDG.

909.21
2'
℄ EXIST.
℄ PROP.
1/2":1
1/2":1
912
910
908

1+98.66
(909.24)

FACE OF BLDG.

913.76
2'
1/2":1
1/2":1
916
914
912

BRICK RETAINING WALL

1+48.66
(913.91)

916.03
2'
1/2":1
1/2":1
918
916
914

1+23.66
(916.16)

918.40
2'
1/2":1
.0156 1/1
.0156 1/1
1/2":1
920
918
916

0+98.66
(918.38)

920.06
2'
1/2":1
.0156 1/1
.0410 1/1
1/2":1
922
920

0+73.66
(920.58)

922.05
.0227 1/1
.0415 1/1
924
922
920

0+63.31

X - SECTIONS - EDWARDS ST. STA. 0+63.31 - STA. 1+98.66

FED. RD.	STATE	PROJECT
	OHIO	


MAH-18-17.20

264
462

ORIGINAL SURVEY — FINAL SURVEY

SEEDING	
END WIDTH	SQ. YDS

END AREA		CU. YDS.	
CUT	FILL	CUT	FILL



FEATURE CROSS SECTION ©/T. R. & E. CORP'N
KOPPEL & GOSS CO., NEW YORK

X-SECTIONS : EDWARDS ST. STA: 2+48.66 – STA. 3+99.09

FED. RD.	STATE	PROJECT
2	OHIO	MAH-18-17.20

2651
492

ORIGINAL SURVEY — NOTE BOOK — NO.

FINAL SURVEY — NOTE BOOK — NO.

50 40 30 20 10 ℄ 10 20 30 40

SEEDING END WIDTH	SEEDING SQ. YDS

END AREA CU. YDS. CUT	END AREA CU. YDS. FILL	CUT	FILL

SEE PROF GRADES ON MARSHALL ST.

872.43 872.54 872.47 872.72 872.73

874 872

6+65.85
(872.75)
℄ MARSHALL AVE.

872.17 1/2 "/1 1/2 "/1

874 872 61.7

6+20
(END EDWARDS ST. QUANTITIES
BEGIN MARSHALL ST. QUANTITIES)

107.8

872.73 1/2 "/1

876 874 182.6

5+98.66
(875.39)

463.5

875.86 PIER 1/2 "/1 PIER

880 878 876 312.0

5+48.66
(878.87)

524.1

880.71

884 882 254.1

4+98.66
(883.10)

319.5

886.51 2:1 1/2 "/1 1/2 "/1 2:1

890 888 886 90.9

4+48.66
(887.43)

PLATE 3. CROSS SECTION OF R.R.& STRAND
FURNISH 2 COPIES TO ARCH.

X-SECTIONS EDWARDS ST. STA. 4+48.66-6+20

2	FED. RD.
OHIO	STATE
	PROJECT

MAH-18-17.20


492 266

ORIGINAL SURVEY — NOTE BOOK — NO. — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED

FINAL SURVEY — NOTE BOOK — NO. — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED

X-SECTIONS EDWARDS ST. 7+04.13 TO 9+99.32

	END AREA		CU. YDS.	
	CUT	FILL	CUT	FILL
9+99.32 END CONT. (866.80)	0.0			
			30.3	
9+48.66 (868.21)	33.1			
			60.5	
8+98.16 (869.13) (℄ DRIVEWAY L & R)	32.2			
			65.7	
8+48.66 (869.83)	38.7			
			73.6	
7+98.66 (870.63)	40.8			
			79.4	
7+49.16 (871.28) (℄ DRIVEWAY R.)	44.9			
			68.4	
7+04.13 (END MARSHALL ST. QUANTITIES) (BEGIN EDWARDS ST. QUANTITIES)	37.2			



FED. RD.	STATE	PROJECT
2	OHIO	


MAH-18-17.20


367
392

FED RD.	STATE	PROJECT	
2	OHIO		

268
492

MAH-18-17.20





TYPICAL SECTION A-A
SCALE: 3/8"=1'-0"

1. 1" T-35 ASPH. CONC. SURFACE COURSE – TYPE "C"
2. 2" B-35 ASPH. CONC. LEVELING COURSE
3. 8" B-19 AGGREGATE BASE COURSE
4. I-12 CONC. CURB – TYPE 6
5. 5' I-13 CONC. SIDEWALK, CLASS "C" INCL. 5" CINDER BASE
6. L-9 SEEDING & PROTECTING

ITEM: E-8 REMOV. & DISP. OF EXIST. CURB				
CODE	FROM	TO	LOCA.	QUAN.
A-1	0+60.68	1+17.18	RT.	56.50'

ITEM: E-8 REMOV. & DISP. OF EXIST. S.WALK				
CODE	FROM	TO	LOCA.	QUAN.
B-1	0+60.68	1+17.18	RT.	226 S.F.

ITEM: I-12 TYPE 6 CONCRETE CURB				
CODE	FROM	TO	LOCATION	QUAN.
G-1	0+23.25	2+24.00	LT. of ℄	221.28'
G-2	2+39.00	3+04.80	LT. of ℄	128.07'
G-3	0+23.25	3+04.80	RT. of ℄	410.73'

760-06

ITEM: I-13 5' CONC. SIDEWALK CLASS "C"				
CODE	FROM	TO	LOCA.	QUAN.
H-1	0+25	2+15	LT. of ℄	816 S.F.
H-2	2+40	3+04.80	LT. of ℄	444 S.F.

1760

NOTE: FOR DETAILS AND QUANTITIES ON UNDERGROUND UTILITIES SEE UTILITY RE-LOCATION SHEET Nº 96

FOR RAMP "F" DETAILS SEE SHEET Nº 55

FOR RAMP "H" DETAILS SEE SHEET Nº 57


FOR HIGH ST. & EDWARDS ST. INTERSECTION DETAILS SEE SHEET Nº 71

FOR DETAILS ON EDWARDS ST. SEE SHEET Nº 262

SEE X-SEC. SH'T. Nº 271 FOR LIMITS OF WORK ON HALL CT.

FOR R/W DETAILS ON RELOCA. BURNS ST. SEE SHT. Nº 472

FOR INTERSECTION DETAILS SEE SHEET Nº 269



PROFILE OF BURNS ST. (RELOCA.)

PROFILE OF HALL CT.

PLATE 4—CROSS SECTION O. P. B. & R. E. STANDARD
EUGENE DIETZGEN CO. CHGO.—N. Y.

(RELOCA.) BURNS ST. & HALL CT.

Printed in U.S.A.
On DIETZGEN DRAFTEX MOISTURE PROOF Cloth

Printed in U.S.A.
DIETZGEN DRAFTEX MOISTURE PROOF Cloth


FINAL SURVEY — NOTE BOOK — NO. — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED — BY — DATE

ORIGINAL SURVEY — NOTE BOOK — NO. — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED — BY — DATE


FED RD	STATE	PROJECT	
2	OHIO		

269
492

MAH-18-17.20




INTERSECTION EDWARDS ℄ RELOCA. BURNS ST.



INTERSECTION RELOCA. BURNS ST. & EXIST. HALL CT.

NOTE: ALL CURB ELEV. SHOWN ARE TOP OF CURB GRADES



INTERSECTION EXIST. & RELOCATED BURNS ST.

FED. RD.	STATE	PROJECT	
2	OHIO		

270
492

4- MAH-18-17.20

TOTAL CUT = 792 C.Y.
TOTAL FILL = 53 C.Y.

END AREA	CU. YDS.
CUT	FILL

105 1 | 103 6 | 20 6 | 57 6 | 41 0 | 93 0 | 60 0 | 36 1 | 38 2 | 50 1 | 52 0 | 106 1 | 63 1 | 162 7 | 112 6 | 144 2 | 43 17 | 41 10 | 45 4

BLDG. TO BE REMOVED

BLDG. TO BE TAKEN BY "RAMP"

BLDG. TO BE TAKEN BY "RAMP"

BLDG. TO BE TAKEN BY "RAMP"

BLDG. TO BE TAKEN BY "RAMP"

BLDG. TO BE TAKEN BY "RAMP"

BLDG. TO BE REMOVED

BLDG. TO BE REMOVED

BLDG. OK

BLDG. TO BE REMOVED

BLDG. TO BE REMOVED

SEE HALL CE X-SECTIONS

BLDG. TO BE REMOVED

BLDG. TO BE REMOVED

933.70	933.48	933.23	932.71	932.00	930.33	926.10	919.65	918.81	918.27
3+94.80	3+50	3+00	2+50	2+30	2+00	1+50	1+00	0+50	0+25
934.0	933.0	934.0	934.0	932.2	931.0	926.6	922.2	918.0	918.6

RELOCA. BURNS ST. X-SEC.

PLATE 3 - CROSS SECTION C. P. R. & B. E. STANDARD
KEUFFEL & ESSER CO., NEW YORK.

FINAL SURVEY: SURVEYED, PLOTTED, TEMPLET, AREAS, CHECKED — BY, DATE, NOTE BOOK, NO.

ORIGINAL SURVEY: SURVEYED, PLOTTED, TEMPLET, AREAS, CHECKED — BY, DATE, NOTE BOOK, NO.

FED. RD.	STATE	PROJECT	
2	OHIO		

271/492

MAH-18-17.20

END AREA	CU. YDS.
CUT / FILL	CUT / FILL

TOTAL CUT = 151 C.Y.
TOTAL FILL = 0

0+20.09 BEGIN WORK
232.18
233.0

BLDG TO BE REMOVED

BLDG. OK

0+50
232.85
234.0

1+00
233.83
234.4

BLDG OK

1+35 END WORK
234.00
234.0

1+50
233.3

BLDG.

BLDG.

234
232

REGRADED HALL CT.

PLATE 3 CROSS SECTION O.D.O.T. S.H.E. STANDARD


FINAL SURVEY
NOTE BOOK
NO


ORIGINAL SURVEY
NOTE BOOK
NO

FED. RD.	STATE	PROJECT	
	OHIO		

272
492

MAH - 18 - 17.20





(1) 1"-T-35 ASPHALTIC CONCRETE SURFACE COURSE - TYPE "C" (70-85)

(2) 2"-B-35 ASPHALTIC CONC. LEVELING COURSE (70-85)

(3) B-35 ASPHALTIC CONC. PRE-LEVELING COURSE- VARIABLE THICKNESS (70-85)

(4) T-30 BITUMINOUS TACK COAT-0.10 GAL. PER SQ. YD.

(5) 9" B-70 PORTLAND CEMENT CONCRETE BASE COURSE

(6) 6" I-22 SUBBASE

(7) I-12 COMBINED CURB & GUTTER-TYPE 2

(8) L-9 SEEDING & PROTECTING

(9) 5" I-13 CONCRETE SIDEWALK-INCLUDING 5" CINDER SUBBASE

HIGH ST.

CODE	ITEM	REMARKS
R-1	S-24	REMOVAL AND DISPOSAL OF EXIST. CONC. BLOCK RET. WALL

NOTES :

ALL NEW LEADS SHALL BE 12" M-G.8 (b)

FOR DETAILS OF PROPOSED & EXIST. R/W LINES SEE TYPICAL SECTIONS SHEET NO. 272

FOR DETAILS OF INTERSECTIONS SEE SHEET Nº 275 AND Nº 276

FOR LOCATION OF PROPOSED TYPE II. INLETS OR THOSE TO BE ABANDONED OR REMOVED SEE SHEET NO. 275

SEE SHT. Nº 275 FOR M.H's. TO BE ADJUSTED TO GRADE.

ITEM I-13 CONCRETE STEPS					
CODE	WIDTH	Nº OF RISERS	RISER	TREAD	LF
S-1	3	3	8"	12"	3.6
S-2	4.5	3	8"	12"	3.6

NOTE: EXISTING PAVEMENT, CURBS AND SIDEWALK TO BE REMOVED AND ENTIRE AREA GRADED AND SEEDED

BEGIN NEW SIDEWALK AT STA. 17+59 LT.

NOTE: SEE UTILITY RELOCATION SHEET Nº2 FOR THIS NEW RUN OF SEWER

ITEM I-12 CONC. CURB REPLACE. (LIN. FT.)					
CODE	FROM STA.	TO STA.	LOCA.	STR. QUAN.	CRV. QUAN.
G-1	14+50.16	14+60.09	RT.	—	15.64
G-2	14+85.37	17+34.52	RT.	224.50	30.32
G-3	17+56.52	21+23.01	RT.	336.01	47.21
G-4	21+42.21	26+50	RT.	492.85	23.50
G-5	25+89.90	26+50	LT.	45.30	23.36
G-6	23+54.12	25+73.90	LT.	180.41	47.49
G-7	19+97.15	23+38.12	LT.	311.17	46.82
G-8	14+59.16	19+73.15	LT.	460.40	57.55

ITEM E-8 EXIST. CURB REMOVAL & STORAGE (L.F.)				
CODE	FROM STA.	TO STA.	LOCA.	QUAN.
A-1	14+50.16	14+60	RT	17.4
A-2	14+86	17+34	RT	248.5
A-3	17+55	21+23	RT	304
A-4	21+42	26+50	RT	521
A-5	25+00	26+50	LT.	70
A-6	23+54	25+74	LT.	258
A-7	19+97	23+38	LT.	370
A-8	17+55	19+73	LT.	256
A-9	17+55(14'L)	17+55(80'L)	LT.	66
A-10	17+27(14'L)	17+27(65'L)	LT.	51
A-11	16+09	17+24	LT.	121
A-12	14+50	15+91	LT.	135

ITEM I-13 CONC. SIDEWALK REPL. (S.F.)				
CODE	FROM STA.	TO STA.	LOCA.	QUAN.
H-1	14+50.16	14+68.56	R.T.	38
H-2	14+86.04	17+31.54	R.T.	908
H-3	17+58.04	21+20.55	R.T.	1228
H-4	21+44.15	26+50	R.T.	1823
H-5	25+01.70	26+50	LT.	233
H-6	23+56.25	25+71.70	LT.	742
H-7	19+09.11	23+36.28	LT.	1229
H-8	17+59	19+71.11	LT.	778

FED. RD.	STATE	PROJECT	
2	OHIO		

273
492

MAH - 18 - 17.20

W-1	CONC. RESIDENTIAL RET. WALL —— H=2'
S-1	CLASS "C" CONC. FOR RET. WALL —— 5 C.Y.
S-4	REINF. STEEL FOR RET. WALL — 210 LBS.
E-2	EXCAVATION FOR STRUCTURE —— 20 C.Y.
S-29	POROUS BACKFILL —— 27 C.Y.

ITEM-E-8 REMOV. & DISP. OF EXIST. WEARING COURSE				
CODE	FROM STA.	TO STA.	SQ.YDS.	REMARKS
K-1	14+50.16	15+25	161	VAR. DEPTH
K-2	16+25	18+50	550	" "
K-3	19+50	26+50	1711	" "

FEDERAL AID FUNDS — CITY OF YOUNGSTOWN FUNDS

P.C. STA. 14+59.16

FOR PAV'T CONST. DETAILS FROM STA. 14+59.16 TO STA. 15+12.22, SEE SHEET Nº 276

B.M. # 18-A. R.R. SPIKE IN 34" MAPLE, 105' S. OF HIGH & EDWARDS INT. & 18' W. OF ℄ EDWARDS ST. ELEV. 929.548

B.M. # 19-A. R.R. SPIKE, IN W. SIDE 18" WILD CHERRY 140' S. OF HIGH & PLUM INT. AND 18' E. OF ℄ PLUM ST. ELEV. 932.175

B.M. # 20-A. R.R. SPIKE IN E. SIDE 18" MAPLE, 42' E. OF HIGH & WEST INT. AND 21' S. OF ℄ HIGH ST. ELEV. 933.704


B.M. # 21-A. R.R. SPIKE IN E. SIDE 24" MAPLE, 48' W. OF ℄ INT. HIGH & SMITH AND 21' S OF ℄ HIGH ST. ELEV. 925.832

DRIVEWAYS (SINGLE PRIVATE)					
CODE	STATION	LOC.	5"T-T-I PCC DRIVEWAY APPROACH S.Y.	DRIVEWAYS 5" T-TO S.Y.	DRIVEWAYS 3"B-I9 C.Y.
J-1	16+05	RT	8.7		-
J-2	18+59	RT	8.7		-
J-3	19+27	RT	8.7		-
J-4	19+42	RT	8.7		
J-5	19+88	RT	8.7	8	
J-6	20+66	RT	8.7		
J-7	22+06	RT	8.7		
J-8	24+00	RT	8.7		
J-9	24+70	RT	8.7		
J-10	25+45	RT	8.7		
J-11	25+48	LT	7.5		
J-12	24+65	LT	7.5		
J-13	22+51	LT	7.5		-
J-14	21+46	LT	7.5		
J-15	18+69	LT	7.5		-
J-16	15+65	RT	8.7		-
J-17	18+21	RT	8.7		
J-18	20+57	LT	7.5		
J-19	22+44	RT	8.7		
J-20	24+07	LT	7.5		
J-23	18+80	LT	7.5		

ITEM E-8 EXISTING SIDEWALK REMOVAL (S.F.)									
CODE	FROM STA.	TO STA.	LOCA.	QUAN.	CODE	FROM STA.	TO STA.	LOCA.	QUAN.
B-1	14+59.16	14+68.56	R.T.	47	B-11	16+09	17+27.20	LT.	501
B-2	14+86.04	17+34.40	R.T.	1242	B-12	14+59.16	15+91	LT.	650
B-3	17+57.40	21+22.57	R.T.	1826					
B-4	21+42.77	26+50	R.T.	2536					
B-5	25+00.50	26+50	LT.	207					
B-6	23+54.47	25+73.50	LT.	1096					
B-7	19+07.68	23+37.47	LT.	1600					
B-8	17+55.20	19+72.68	LT.	1087					
B-9	17+61(14'L)	17+61(85'L)	LT.	346					
B-10	17+18(14'L)	17+18(65'L)	LT.	246					

EXIST. RET. WALL FROM 25+52 TO 27+50 NOT TO BE DISTURBED SEE CROSS SEC'S.

REPLACE RETAINING WALL SEE SHEET Nº


PROFILE GRADE ELEVS.
935
930
925
920
915
910
905
900
150' V.C.
GRAPHIC GRADE
100' V.C.
+1.32 %
0.24%
+0.72 %
- 0.02 %
-2.02%
-2.19 %
-2.56 %
-7.10 %
P.V.I. STA. 12+00 EL. 929.90
P.V.I. STA. 17+50 EL. 931.08
P.V.I. STA. 19+50 EL. 932.52
P.V.I. STA. 21+25 EL. 932.48
P.V.I. STA. 23+00 EL. 928.95
P.V.I. STA. 24+50 EL. 925.66
P.V.I. STA. 25+50 EL. 923.10
12" V.P.
STA. 11+40.50 BEGIN WORK MEET EXIST. PAV'T
STA. 11+55.74 (FORWARD) ℄ EDWARDS ST.
℄ WALLACE ST. RT. STA. 14+77.54
℄ PLUM ST. LT. STA. 17+39.70
℄ PLUM ST. RT. STA. 17+47.68
℄ SOUTHWEST AVE. LT. STA. 19+84.88
℄ SCHOOL ST. RT. STA. 21+32.48
℄ CITYVIEW CT. LT. STA. 23+45.97
℄ SMITH ST. LT. STA. 25+86.09
31" x 39" BRICK OVAL EXISTING COMBINATION SEWER @ 0.5%
40" x 51" BRICK OVAL COMB. SEWER @ 0.8 %
INV. 916.34
INV. 914.48
INV. 911.31
INV. 909.19
INV. 907.17
PROFILE GRADE ELEVS.
926.11 926.81 926.66 926.56 926.41 926.37 926.44 926.61 926.85 927.22 927.55 927.88 928.20 928.33 928.48 928.85 929.27 929.69 930.05 930.36 930.56 930.70 930.80 930.84 930.90 930.96 931.04 931.14 931.28 931.44 931.80 932.16 932.32 932.43 932.45 932.51 932.50 932.49 932.42 932.23 931.92 931.48 930.57 929.45 928.53 928.35 927.85 926.76 926.19 925.61 925.01 924.38 923.60 923.53 923.18 922.55 921.69 920.63
11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26
926.17 927.05 926.09 926.46 927.00 927.76 928.37 928.93 929.31 929.61 931.40 931.40 931.42 931.46 931.70 931.89 932.30 932.40 932.40 932.45 932.52 932.28 932.48 931.69 931.00 930.66 929.57 928.56 927.87 927.51 926.42 925.27 924.08 921.99
85 42 61 15.38 46.38 15.38 32.48 46.38 15.38 46.38 15.38 46.38 15.38

FED. RD.	STATE	PROJECT	
	OHIO		

274
492

MAH-18-17.20

FOR DETAILS OF ALL INTERSECTIONS, SEE SHEET No. 276

FOR RELOCATION OF EXISTING UTILITIES, SEE SHEET NO. 275

FOR DETAILS OF PAV'T. TRANSITION STA. 27+45.01 - STA. 28+43.81 SEE SHEET NO. 276

FOR LOCATION OF EXIST. & PROPOSED MANHOLES & INLETS TO BE CONSTRUCTED OR ADJUSTED TO GRADE, SEE SHEET No. 275

FOR TYPICAL PAV'T. SECTION SEE SH'T. No. 272

I-13 CONCRETE STEPS					
CODE	WIDTH	# OF RISES	RISER	TREAD	L.F.
S-1	6'-0"	5	8"	12"	6.5

ITEM E-8 EXIST. SIDEW'K. REM'V. (S.F.)				
CODE	FROM STA.	TO STA.	LOCA.	QUAN.
B-13	26+50	34+00	LT.	3181
B-14	26+50	34+00	RT.	3711

ITEM E-8 EXIST CURB REM'V. & STORE.				
CODE	FROM STA.	TO STA.	LOCA.	QUAN. L.F.
A-13	26+50	34+00	LT.	755.3
A-14	26+50	34+00	RT.	744.7

ITEM I-13 CONC. SIDEW'K REPL. (S.F.)				
CODE	FROM STA.	TO STA.	LOCA.	QUAN.
H-9	26+50	34+00	LT.	3033
H-10	26+50	27+92.07	RT.	520

ITEM I-12 CONC. CURB REPL. (L.F.)				
CODE	FROM STA.	TO STA.	LOCA	QUAN.
G-9	26+50	34+00	LT.	755.3
G-10	26+50	34+00	RT.	744.7

S-1 REPLACE EXISTING STEPS

MATCH LINE FOR QUANT. ESTIMATE STA. 26+50

NOTE: FROM STA. 25+52 TO 27+50 SOUTH SIDE NEW WALK TO FOLLOW OLD ALIGNMENT SO AS NOT TO DISTURB AN EXISTING RETAINING WALL IN THIS AREA. (SEE CROSS SECTION SH'T. No. 283)

PROPOSED NORTH R/W

EXISTING & PROPOSED SOUTH R/W LINE

P.C. 27+45.01

P.T. 28+43.81

HIGH ST. 36'

EXIST. ℄ PROPOSED

LIMIT OF R/W

OAKHILL CEMETERY O.L. 138

FOR DETAILS OF NEW RETAINING WALL SEE SH'T. No.

STA. 34+00.00 END WORK

MAINLINE STA. 1006+00.21
OAKHILL STA. 50+00.00

STA. 34+63.91 HIGH ST. (PROP.)
STA. 49+32.18 OAK HILL AVE.

OAK HILL AVE.

PIKE ST. 30'

ST. BRIDGE

ITEM E-8 REMOV. & DISP. OF EXIST. WEARING COURSE				
CODE	FROM STA.	TO STA.	SQ. YDS.	REMARKS
K-1	27+40	34+00	1613	VAR. DEPTH

ITEM	EXIST. DRIVEWAYS & APPROACHES			
CODE	STA.	LOCA	5" T-1 BIT. BASE APPROACH (S.Y.)	3" BIT. DRIVEWAYS (S.Y.)
J-21	27+17	RT.	9	
J-22	27+53	LT	9	1

T. IN HUB
56.00' STREET
℄ HIGH
60.00'
58.75
IRON PIN
T. IN HUB

SMITH ST.
R 47.55'
T. IN HUB
STREET
IRON PIN
35.68
℄ HIGH
S 1.82' E

B.M. R.R. SPIKE 24" MAPLE

B.M.# 32 - TOP STEM OF FIRE HYDT. S. SIDE HIGH ST. @ ∠ PT. ELEV. 888.96

F.D.K. REFERENCES	
F.D.# 18	PG.# 82
" # 5	" # 41-43, 85
" # 18	" # 75-81
" # 21	" # 136-149, 76-95
" # 22	" # 43-88

B.M.# 30-A. R.R. SPIKE IN N. SIDE 28" MAPLE, 24' S. OF PIKE & OAKHILL INT. AND 30' W. OF ℄ OAKHILL AVE. ELEV. 861.811

R.R. SPIKE
OAKHILL AVE.
℄ HIGH ST.
60.00'
T. IN HUB
IRON PIN
R.R. SPIKE
PIKE ST.
B.M. R.R. SPIKE IN 30" MAPLE
T. IN HUB

TOP OF PROFILE
NO. CURVE GRADE

925 920 915 910 905 900 895 885 880 875 870 865 860 855 850 845 840

-2.5% -1.10% -9.80% -11.10% -9.76% -9.28% -4.32% -2.42%

EXIST. ℄ PROFILE

GRAPHIC GRADE

SEE X-SECT. FOR TOP OF N & S CURB ELEVATIONS

P.V.I. STA. 25+50 EL. 923.10
P.V.I. STA. 27+50 EL. 906.20 (886.12)
P.V.I. STA. 30+00 (880.18) EL. 880.44
P.V.I. STA. 31+75 (863.98) EL. 863.52
P.V.I. STA. 33+00 EL. 858.12
P.V.I. STA. 14+50 EL. 916.00
P.V.I. STA. 28+50 EL. 895.10
℄ SMITH ST. STA. 25+82.09 EL. 919.55
℄ OAK HILL AVE. STA. 34+63.91 ELEV. 854.95

100' V.C.

36"x40" BRICK OVAL EXIST. COMB. SEWER

INV. 885.28

SEWER @ 9.16%

12" V.P.

INV. 856.86

36"x52" BRICK OVAL

36"x46" BRICK OVAL EXIST. COMB. SEWER @ 2.53%

INV. 848.87

| | | | | |

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


275
492

N.W. CURB RETURN CURVE DATA

Δ = 89° 22' 15"
R = 15'
T = 14.84'
L_c = 23.40'
P.C. = 2.5+23.28
P.T. = 0+28.75

N.E. CURB RETURN CURVE DATA

Δ = 90° 37' 45"
R = 15'
T = 15.17'
L_c = 23.73'
P.C. = 0+20.26
P.T. = 23+60.25




N.W. CURB RETURN CURVE DATA

Δ = 90° - 45' - 45"
R = 15.00
T = 15.20
L_c = 23.76
P.C. = 25+58.70
P.T. = 0+20.31

N.E. CURB RETURN CURVE DATA

Δ = 89° - 14' - 15"
R = 15.00
T = 14.80
L_c = 23.36
P.C. = 0+28.69
P.T. = 26+04.70



NOTE: ELEVATIONS SHOWN ON CURB RETURNS ARE TOP OF CURB ELEV.

ITEM I-8 M.H. ADJ. TO GRADE (EA.)

EXIST. TOP	CODE	STA.	LOCA.	TOP EL.	REMARKS
929.54	E-1	14+88	1.6'R	929.47	INV. 916.34
	E-2	15+97.5	1.5'R	930.67	
	E-3	17+20	0.5'L	930.90	
931.48	E-4	17+50.6	1.5'R	931.12	INV. 914.48
	E-5	17+52.5	20.5'R	931.10	
919.67	E-6	25+26.5	℄	919.78	INV. 907.17
867.46	E-7	31+33	0.5'L	867.60	INV. 856.86
931.11	E-8	21+35	1.5'R	932.09	INV. 911.31

ITEM I-8 INLETS - YOUNGSTOWN - TYPE II (EACH)

CODE	STATION	LOCA.	WINDOW ℄	C.B. INV.
D-1	15+02.27	14'R	929.12	924.12
D-2	15+03.38	14'L	929.13	924.13
D-3	17+78.77	14'L	930.72	925.72
D-4	17+78.77	14'R	930.72	925.72
D-5	21+01.12	14'R	931.82	926.82
D-6	23+16.45	14'L	927.98	922.98
D-7	23+16.45	14'R	927.98	922.98
D-8	25+35	14'L	922.57	917.57
D-9	25+61	14'R	921.34	916.34
D-10	28+11	14'L	898.84	893.84
D-11	28+11	14'R	898.78	893.78
D-12	31+25	14'L	867.19	862.19
D-13	31+25	14'R	867.72	862.72

ITEM I-8 MANHOLES (EA.)

CODE	STATION	LOCA.	INV.-SIZE	ST'D NO.	TOP ELEV.
L-1	23+25	1.5'R	900.79 (40"x51")	2	928.37
L-2	28+25	℄	885.28 (34"x40")	1	897.90

ITEM I-16 INLETS ABAND. (EA.)

CODE	STA.	LOCA.	REMARKS
F-1	14+96	10.3'R	PLUG LEAD
F-2	15+90	25.5'L	PLUG LEAD
F-3	16+05.5	25.5'L	PLUG LEAD
F-4	17+10.5	11.'R	PLUG LEAD
F-5	17+67.0	11'R	PLUG LEAD
F-6	17+70.5	10.5'L	PLUG LEAD
F-7	25+61.0	10.6'R	USE EXIST. LEAD
F-8	25+61.5	10.5'L	USE EXIST. LEAD
F-9	28+11.5	10.5'L	USE EXIST. LEAD
F-10	28+84.5	10.5'R	PLUG LEAD
F-11	21+18	11'R	PLUG LEAD

ITEM I-124 WATER VALVE BOXES ADJ. TO GR. (EA.)


CODE	STA.	LOCA.	REMARKS
M-1	14+85	10.7' R.	MAIN LINE
M-2	17+47	25.5'R	MAIN LINE
M-3	17+52	11'L	MAIN LINE
M-4	17+72.5	10'L	HYDT. VAL.
M-5	18+85	6.7'L	MAIN LINE
M-6	19+90	10.7'L	MAIN LINE
M-7	25+41	10'L	HYDT. VAL.
M-8	28+30	1.5'L	MAIN LINE
M-9	28+32	0.1'R	MAIN LINE
M-10	29+42	10'R	HYDT. VAL.
M-11	14+79	10'L	HYDT. VAL.
M-12	21+44	9'L	HYDT. VAL.


ITEM I-2 STORM SEWERS UNDER PAV'T. & APPROACH SEC. M-6.8(6)

CODE	FROM	TO	LOCA.	SIZE	LIN. FT.
C-1	D-1	E-1	RT	12"	20
C-2	D-2	E-1	LT	"	24
C-3	D-3	E-4	LT	"	34
C-4	D-4	E-4	RT	"	32
C-5	D-5	E-8	RT	"	36
C-6	D-6	L-1	LT	"	20
C-7	D-7	L-1	RT	"	18
C-8	D-8	F-8	LT	"	26
C-9	D-9	F-7	RT	"	4
C-10	D-10	F-9	LT	"	6
C-11	D-11	L-2	RT	"	22
C-12	D-12	E-7	LT	"	18
C-13	D-13	E-7	RT	"	18

INTERSECTION - HIGH ℄ CITYVIEW

INTERSECTION - HIGH ℄ SMITH






UTILITY RELOCATION

PAVEMENT DETAILS - HIGH ST.

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

276
492



S.W. CURB RETURN CURVE DATA

Δ = 89° 36'-30"
R = 10'.00
T = 9.93
L_c = 15.64

S.E. CURB RETURN CURVE DATA

Δ = 90°-23'-30"
R = 10.00
T = 10.07
L_c = 15.78


CURVE 2.

Δ = 44°56'-40"
R = 10.88
T = 4.50
L_c = 8.53
P.I. 14+68.05
P.C. 14+63.00
4.71' LT.
P.R.C. 14+75.53

CURVE 3.

Δ = 42°-50'-45"
R = 34.00
T = 13.34
L_c = 25.42
P.T. 14+96.55
P.I. 14+84.06

INTERSECTION - HIGH ST. AND WALLACE ST.



CURVE DATA

PROP. ℄

Δ = 21°-40'-12"
R = 261.24
T = 50.00
L_c = 98.80

SO. CURB (14' RT.)

Δ = 21°-40'-12"
R = 247.24
T = 47.32
L_c = 93.51

NO. CURB (14' LT.)

Δ = 21°-40'-12"
R = 275.24
T = 52.68
L_c = 104.10

NO. SIDEWALK (FRONT EDGE)


P.C. 17' LT. @ STA. 27+45.01
P.T. 16' LT @ STA. 28+38.59
Δ = 21°-40'-12"
R = 264.09
T = 50.55
L_c = 99.88

PROP. NO. ℄

P.C. 22' LT. @ STA. 27+45.01
P.T. 21' LT. @ STA. 28+38.59
Δ = 21°-40'-12"
R = 269.09
T = 51.50
L_c = 101.77

CENTERLINE TRANSITION
STA. 27+45.01 - STA. 28+43.81

NOTE: ELEVATIONS SHOWN ON CURBS & CURB RETURNS ARE TOP OF CURB ELEVATIONS.




S.W. CURB RETURN CURVE DATA

Δ = 89° 56'
R = 15'
T = 14.98'
L_c = 23.54'
P.C. 17+19.94
P.T. 0+28.97

S.E. CURB RETURN CURVE DATA

Δ = 90° 04'
R = 15'
T = 15.02'
L_c = 23.58'
P.C. 0+29.04
P.T. 17+71.94

INTERSECTION - PLUM & HIGH ST.




N.W. CURB RETURN CURVE DATA

Δ = 90°08'30"
R = 15'
T = 15.04'
L_c = 23.60'
P.C. 19+58.11
P.T. 0+29.07

N.E. CURB RETURN CURVE DATA

Δ = 89° 51'30"
R = 15'
T = 14.96'
L_c = 23.52'
P.C. 0+28.93
P.T. 20+12.11

INTERSECTION - HIGH & WEST ST.



S.W. CURB RETURN CURVE DATA

Δ = 90° 14' 30"
R = 15'
T = 15.06'
L_c = 23.63'
P.C. 21+07.95
P.T. 0+29.10

S.E. CURB RETURN CURVE DATA

Δ = 89° 45' 30"
R = 15'
T = 14.94
L_c = 23.50
P.C. 0+28.90
P.T. 21+57.15

INTERSECTION - HIGH & SCHOOL ST.

PAVEMENT DETAILS - HIGH ST.

| | | |

END AREA		CU. YDS.	
CUT	FILL	CUT	FILL
2.1	4.0	13.7	3.7
11.1	0.0	12.2	3.7
10.2		20.4	
4.0		6.1	
0		1.4	

FED. RD.	STATE	PROJECT	
2	OHIO		

278
492

MAH-18-17.20

EXISTING SOUTH R/W LINE

DRIVEWAY @ 16+05

16+05 W.A. REQ.

DRIVEWAY 15+65

15+65 W.A. REQ'D.

16+00 (930.78) ℄ BURNS ST. LT. (ABANDON)

℄ EXIST. HIGH ST.

3'

15+50 (929.63)

15+00 (929.53)

14+78 929.29 ℄ WALLACE ST.

14+59.16 (928.93)

STA. 14+59.16 BEGIN WORK ℄ CONTRACT

14+00 (928.57)

13+50 927.76

930.70 930.85 930.83 930.51 929.84 929.48 929.31 929.23 928.92 928.53 928.33 928.07 927.88

REMOVE EXIST. ASPHALT

EXISTING NORTH R/W LINE

PROP NORTH R/W LINE

930.30

1½

13+43 RAMP "H"

13+93 RAMP "F"

15+40 RAMP "I"

14+87.91 RAMP "I"

15+38.53 RAMP "I"

SEEDING	
END STA.	
WORK TO.	

X- SECTIONS HIGH ST. STA. 13+50 - STA. 16+00

FED. RD.	STATE	PROJECT	
2	OHIO		

279
452

MAH -18-17.20

END AREA	CUT	12.1
	FILL	0.0
CU. YDS.	CUT	21.8
	FILL	0.4

22.2 | 19.7 | 17.7 | 32.8 | 25

11.8 | 15.4 | 30.0 | 14.3 | 12.7

932 930 931 934 932 930 934 932 930 934 932 930 934 932 930

40 30 20 10 0

DRIVEWAY 18+21 (No WA. REQ'D.)

EXISTING SOUTH R/W LINE

STA. 0+25.00 MEET EXIST. PAVT. ELEV. 931.15

ONE STORY BR. BLDG.

931.74

931.80 — 18+50 (931.10)

931.44 — 18+00 (931.44)

℄ EXISTING HIGH ST.

5'

931.20 — 17+61 (931.42) ℄ N-S. SIDEWALK

931.10 — 17+39.70 (931.40) ℄ PLUM ST. LT.

17+42.60 (931.40) ℄ PLUM ST. RT.

930.34 — 17+00 (931.09)

930.84 — 16+50 (930.86)

℄ EXIST.

EXISTING NORTH R/W LINE

PROPOSED NORTH R/W LINE

15'

932.60

HOUSE

BEGIN SIDEWALK THIS SIDE AT STA. 17+55

REMOVE EXIST. PAV'T. AND BASE

SEEDING	
END SEC.	
WIDTH	

X-SECTIONS HIGH ST. STA. 16+50 - STA. 18+50

| | | |

FED. RD.	STATE	PROJECT
	OHIO	

281
492

MAH -18 -17.20

END AREA	CU. YDS.
CUT	FILL
CUT	FILL

8.7 | 31.0 | 44.0 | 39.9 | 16.0 | 8.5 | 0.0

12.4 | 21.1 | 26.4 | 16.7 | 14.2 | 11.3

930 | 928 | 932 | 930 | 928 | 930 | 932 | 930 | 932 | 930 | 934 | 932 | 930 | 934 | 932

MEET EXIST. PAVT @ STA. 0+23 (S.) ELEV. 932.30

EXISTING SOUTH R/W LINE

23 + 15.26 (928.54)

22 + 65.26 (929.57)

EXIST. RETAINING WALL FROM STA. 21+86 TO 22+17 TO BE REMOVED (31 Lin.)

22 + 15.26 (930.66)

℄ EXIST. HIGH ST.

21 + 65.26 (931.66)

21 + 32.57 ℄ SCHOOL ST.

21 + 15.26 (932.28)

928.60 | 929.65 | 930.66 | 931.66 | 932.15 | 932.32

3' | 5'

EXISTING NORTH R/W LINE

PROPOSED NORTH R/W LINE

2:1

W.A. REQD.

DRIVEWAY @ 22+51

HOUSE

Note: STA. 22+77 TO STA. 22+05 STORE BLDG. @ 25' Lt. of EXIST ℄

DRIVEWAY @ 21+46 (NO W.A. REQD.)

931 | 929 | 932

SEEDING END REQ. WORTHYS.

X-SECTIONS HIGH ST. STA. 21+15.26 - STA. 23+15.26

END AREA	CU.YDS.
CUT	CUT
	FILL
FILL	FILL

| | | |

| | | |

END AREA	CU. YDS.
CUT	FILL
FILL	CUT
CUT	FILL

30.2 | 25.6 | 32.6 | 48.4 | 4.0

11.6 | 16.0 | 19.2 | 0.0 | 29.2 | 4.0

FED. RD.	STATE	PROJECT
	OHIO	

284
492

MAH-18-17.20

RET. WALL

EXISTING SOUTH R/W LINE

1:2

EXIST. HIGH ST.

29+64.06
(893.93)
883.97

29+14.06
(888.78)
888.85

28+64.06
(893.84)
893.82

28+10
(892.55)
892.55

3'

883.43

888.44

893.48

892.11

EXISTING NORTH R/W LINE

RET. WALL

SEEDING AND MULCHING

X-SECTIONS HIGH ST. STA. 28+10 - STA. 29+64.06

END AREA CU. YDS.	
CUT	FILL
95.4	
13.5	
	12.5
13.4	
	38.9
14.6	
	5.4
14.3	
	3.9
6.5	

FED. RD.	STATE	PROJECT	
2	OHIO		

285
482

MAH-18-17.20

FACE OF 8" WALL

EXISTING SOUTH R/W LINE

EXISTING NORTH R/W LINE

859.69 — 32+64.06 (859.84) — 859.52

EXIST. HIGH ST.

860.75 — 32+39.06 (860.03) — 860.58

864.98 — 31+64.06 (864.13) — 864.72

3'

874.26 — 30+64.06 (874.02) — 873.80

EXIST. HIGH ST.

875.23 — 30+54.06 (875.02) — 874.72

12" STONE RET. WALL BETWEEN HOUSES

SEEDING
END I SQ
WIDTH YD.

X- SECTIONS HIGH ST. STA. 30+54.06 - STA. 32+64.06

FED. RD.	STATE	PROJECT	
2	OHIO		

286
492

MAH-18-17.20

END AREA	CU. YDS.
CUT	FILL
FILL	CUT
CUT	FILL

45.3

30.0 30.0

856 854 852 858 856 854 858 856

49+25 OAKHILL AVE.
ELEV. 856.05

854.99

34+64.06 HIGH ST.
49+42.18 OAKHILL AVE.
(855.16) ℄ OAKHILL AVE.

34+15.70
(855.85)

STA. 34+00.00
END WORK

34+00.00
(856.17)

33+64.06
(854.92)

856.33

856.00

3'

855.83

856.41

EXISTING SOUTH R/W LINE

FACE OF WALL

EXISTING NORTH R/W LINE

49+75 OAKHILL
ELEV. 853.13

NOTE: FOR DETAILS OF NEW RETAINING WALL SEE SHT. No.


SEEDING	
END	SQ.
WIDTH	YD.

X - SECTION HIGH ST. STA. 33+65.38 - STA. 34+65.38

FED. RD.	STATE	PROJECT	
2	OHIO		

287
492

MAH-18-17.20



OAKHILL AVE.
LIMITING STATIONS
STA. 48+45 TO STA. 51+65.14

(1) 1" T-35 ASPHALTIC CONCRETE SURFACE COURSE - TYPE 'C' (70-85)

(2) 2" B-35 ASPHALTIC CONCRETE LEVELING COURSE - (70-85)

(3) B-35 ASPHALTIC CONCRETE LEVELING COURSE - VARIABLE THICKNESS (70-85)

(4) T-30 BITUMINOUS TACK COAT 0.1 GAL. PER SQ. YD.

(5) 9" B-70 PORTLAND CEMENT CONCRETE BASE COURSE

(6) 6" I-22 SUBBASE

(7) I-12 COMBINED CURB & GUTTER - TYPE 2

(8) L-9 SEEDING & PROTECTING

(9) 5" I-13 CONCRETE SIDEWALK - INCLUDING 5" CINDER SUBBASE


(10) I-12 TYPE G HEADER CURB

TYPICAL SECTIONS

FED.RD.	STATE	PROJECT	
2	OHIO		

288
492

MAH-18-17.20



I-2 STORM SEWER UNDER PAVEMENT & APPROACHES M-6.6

CODE	FROM	TO	TYPE & SIZE	LENGTH BID	LENGTH ℄ To ℄	% GRADE
C-1	D-3	EXIST. M.H.	12"	19'	21'	1%
C-2	D-4	EXIST. M.H.	12"	22'	24'	1%
C-3	D-5	LEAD® F-1	12"	10'	10'	SAME AS LEAD
C-4	D-6	E-2	12"	28'	30'	6%

E-8 REMOVAL & DISPOSAL OF EXISTING CURB (L.F.)

CODE	FROM	TO	QUANTITY
A-1	S. SIDE WALTER ST.		22
A-2	49+64	51+28	165
A-3	N. SIDE HIGH ST.		55
A-4	S. SIDE HIGH ST.		33
A-5	48+45	48+90	45
A-6	51+32	51+65	33

E-8 REMOVAL & DISPOSAL OF EXISTING SIDEWALK (S.F.)

CODE	FROM	TO	QUANTITY
B-1	48+25	49+07	492
B-2	S. SIDE HIGH ST.		56
B-3	N. SIDE HIGH ST.		184
B-4	49+53	51+36	1058
B-5	48+25	48+68	258
B-6	48+87	50+45	948
B-7	51+12	51+65	318

I-16 INLETS ABANDON (EACH)

CODE	STATION	LOCATION	REMARKS
F-1	51+30	19' LT.	
F-2	34+12	10' LT. HIGH ℄	
F-3	48+48	18' LT.	
F-4	48+48	18' RT.	
F-5	34+28	14' RT. HIGH ST. ℄	

E-8 REMOVAL & DISPOSAL OF EXIST. PAVEMENT (SQ.YDS.)

CODE	FROM	TO	QUANTITY
K-1	SEE SHADED AREA		194
K-2	AT EXISTING PIKE ST.		27
K-3	AT EXISTING WALTER ST.		37

I-8 MANHOLES ADJUSTED TO GRADE

CODE	STATION	LOCATION	TOP ELEV.	REMARKS
E-1	48+51	ON ℄	861.66	
E-2	49+38	38' LT.	855.48	
E-3	49+83	ON ℄	853.09	
E-4	51+50	ON ℄	846.59	

I-8 YOUNGSTOWN TYPE II INLETS


CODE	STATION	LOCATION	TOP ELEV.	FLOW LINE
D-1	48+48	18' LT.	861.55	USE EXISTING
D-2	48+48	18' RT.	862.09	USE EXISTING
D-3	34+06.66	14' RT. HIGH ℄	856.38	852.88
D-4	P.C. 34+15.60	14' LT. HIGH ℄	855.58	852.08
D-5	51+25	30' LT.	847.28	EXTEND FROM F-1
D-6	49+07.70	30' LT.	857.10	853.60

I-13 CONCRETE SIDEWALK REPLACEMENT (S.F.)

CODE	FROM	TO	LOCATION	QUANTITY
H-1	48+25	49+07	LEFT	492
H-3	N. SIDE HIGH ST.		—	104
H-4	49+64	51+65	LEFT	1224
H-5	48+25	50+45	RIGHT	1380
H-6	51+12	51+65	RIGHT	318

I-12 CONCRETE CURB (L.F.)

CODE	FROM	TO	LOCATION	TYPE 2 COMB. CURB	TYPE 6 HEADER CURB
G-1	48+45	CEMETERY	OAKHILL	82	
G-2	34+00	CEMETERY	HIGH ST.	22.81	
G-3	34+00	34+15.60	HIGH ST.	15.60	
G-4	N.W. RET. HIGH & OAK HILL		—	30.39	
G-5	48+70.64	51+33	OAKHILL (LT.)	162.36	
G-6	51+33	51+65.14	OAKHILL (LT.)	34.90	
G-7	48+45	50+47.71	OAKHILL (RT.)	—	202.71
G-8	51+32	51+65.14	OAKHILL (RT.)		33.14




OAKHILL AVE. IMPROVEMENT

SCALES: HOR. 1" = 50'
VER. 1" = 5'

FED. R.D.	STATE	PROJECT	
2	OHIO		

289/492

MAH - 18 - 17.20



PAVEMENT DETAILS OAKHILL AVE.

END AREAS #

END AREAS #
FOR B-35

CU. YDS. OF B-35




C = 15
F = 3

C = 18.7
F 4.1

50+09.71
851.44
PG. 851.72

3.8

C = 14
F = 3



C = 18.2
F 3.8

C = 18
F = 7

49+89.71
852.48
PG. 852.76

2.9



C = 18.6
F 10.4

C = 5
F = 10

49+64.71
853.83
PG. 854.12

2.4




C = 0
F = 10.4

C = 0
F = 10

49+39.71
855.28
PG. 855.53

1.7




C = 0
F = 11.9

C = 0
F = 19

49+14.71
856.81
PG. 857.12

2.9




C = 0
F = 28.1

48+89.17
858.62
PG. 858.83

6.9

C = 0
F = 43



C = 0
F = 25.0

48+45

BEGIN CONSTRUCTION OF CURB & PAVT.

861.85

PG. 862.10

℄
OAK HILL

40 30 20 10 0 10 20 30 40

OAK HILL AVE STA. 48+45 to 50+97.1

MAH-18-17.20

	2	NO.	SHEET
	OHIO	STATE	
		PROJECT	
			290 492

END AREAS #

END AREA #
FOR B-35




51+65.14
END CONSTRUCTION
AND WORK
846.05
PG. 846.11



51+33
846.87
PG 847.18

2.7


C=10
F=0



51+19.71
847.31
PG 847.58

3.5

C=16
F=0



50+89.71
848.28
PG. 848.55

3.1'


C=18
F=0



50+69.71
849.01
PG 849.25

2.7


C=18
F=4



50+49.71
849.71
PG 849.96

2.9

C=18
F=5



50+29.71
850.48
PG 850.78

℄
OAKHILL

40 30 20 10 0 10 20 30 40

OAKHILL AVE STA 50+29.71 to 51+65.14

MAH-18-17.20

2	SHEET NO.	STATE
	OHIO	PROJECT

291
492

FED. RD.	STATE	PROJECT	
2	OHIO		

292
492

MAH-18-17.20

CURVE DATA
R = 200'
T = 49.81'
L = 97.74'
Δ = 28°00'00"
D = 28°38'52"

CURVE DATA
Δ = 8°02'44"
D = 4°
T = 100.73'
R = 1432.39'
L = 201.14'

CURVE DATA
Δ = 11°20'50"
D = 5°25'16"
T = 105'
R = 1056.89'
L = 209.31'

℄ OAK HILL

FOR INTERSECTION DETAILS SEE SHEET Nº 13

EXISTING 66" COMBINATION SEWER SEE SHEET N8

FOR REMOVAL OF EXISTING CONCRETE BINS SEE SHEET Nº 293

BEGIN WORK STA. 0+18

P.T. STA. 0+48

P.C. STA. 1+84.87

P.C. STA. 4+46.27

P.T. STA. 5+41.41

P.C. STA. 7+55.87

P.T. STA. 9+51.01

END WORK STA 9+50

54" COMBINATION SEWER SEE SHEET N8

℄ RELOCATED PIKE STA 0+00
℄ OAKHILL STA. 501+89.71

MEET EXISTING CURB & PAVEMENT GRADE

℄ EXISTING PIKE ST.

℄ MAH-18-17.20 STA. 1006+00.21
℄ OAKHILL STA. 50+00

NOTE:
FOR QUANTITIES AND CONSTRUCTION DETAILS OF ITEMS MARKED (A-70 M.L.) (A-78 M.L.) (A-76 M.L.) SEE SHEET Nº 44

5'-0" 18'-0" 5'-0"
BITUMINOUS WEARING SURFACE
BRICK
CONCRETE
EXISTING PIKE STREET

ESTIMATED QUANTITIES I-8 INLETS MANHOLES & CATCH-BASINS						
	CODE	LOCATION & STATION	#1 M.H. EACH	#2 YOUNGS C.B. EACH	#2-2A C.B. EACH	#2 M.H. EACH
	A-71	1+50 10.0' LT.				1
‡	A-75	9+70 ℄	1			
	A-79	0+54.83 12.0' LT.		1		
	A-80	0+54.83 12.0' RT.		1		
	A-81	9+25 10.0' RT.		1		
‡	A-82	9+25 10.0' LT.		1		
	A-83	9+08 34.0' RT.			1	
	SHEET TOTAL		1	4	1	1

EROSION CONTROL	
CODE	3½ PAVED GUTTER TYPE I (MOD.) L.F.
E-1	10

ESTIMATED QUANTITIES I-2 PIPES						
CODE	LOCATION		CLASS "B" STORM SEWERS UNDER PAV'T. OR APPR. L.F.			
	FROM	TO	36"	18"	12"	15"
P-72	A-70	A-71	141#			
P-73	A-71	B-1	286*			
P-82	A-75	B-1		526*		
P-78	A-80	A-70			47	
P-79	A-79	A-70			47	
P-80	A-82	A-75				42
P-81	A-81	A-75			42	
P-84	A-83	A-82				23
SHEET TOTAL						

I-12 TYPE 2A CON. CURB
1978 L.F.

†NOTE:-
The City of Youngstown proposes to construct a sewer system to replace these items - See Sheet 8, General Note.

M-6.6 b or M-6.8 b
* M-6.6 d

A-79
STA 0+54.83 (12.0' LT ℄)
I-8 TYPE II YNG ST. INLET
TOP OF CURB - 848.73
WINDOW EL - 847.98
℄ INLET - 842.98
℄ 12" I-2 - 844.67

A-71
℄ STA 1+50 10' LT.
I-8 Nº2 M.H.
COVER EL. 850.95
FL 36" I-2 833.93
℄ 12" I-2 845.00

A-80
I-8 YNG ST. TYPE II INLET
℄ STA 0+54.83 12' RT
TOP OF CURB - 848.73
WINDOW EL - 847.98
℄ INLET - 842.98
℄ 12" I-2 - 844.23
℄ 12" I-2 OUTLET 844.67


A-82
STA. 9+25 (10.0' RT ℄)
I-8 YNG ST. TYPE II INLET
TOP OF CURB - 847.36
WINDOW EL - 846.61
℄ INLET - 841.61
℄ 12" I-2 - 842.86
℄ 15" I-2 - 843.30

A-83
℄ STA 9+08 34' RT
I-8 Nº2-2A C.B.
WINDOW EL. 845.20
℄ 12" I-2 - 843.03


STA 9+25 (10.0' LT ℄)
I-8 YNG ST. TYPE II INLET
TOP OF CURB - 847.36
WINDOW EL - 846.61
℄ INLET 841.61
℄ 12" I-2 843.30

A-81
500' V.C.
P.V.C. STA. 2+00
EL. 853.41
P.V.T. STA. 7+00
EL. 854.66
P.V.C. 0+50
EL. 848.31
P.V.T. 1+50
EL. 851.16
P.V.C. 8+50
EL. 848.66
P.V.T. 9+50
EL. 847.14
P.V.I. STA. 4+50
EL. 864.60
P.V.I. STA. 9+00
EL. 846.66
STA. 9+64.63
EL. 844.28
+4.50%
-4.00%
0.00%
+0.92%
100' V.C.
100' V.C.
SEE SHEET NO. FOR INTERSECTION ELEVATIONS
STA. 0+00
EL. 848.31
P.V.I. STA. 1+00
EL. 848.31
P-72
145' 36"I-2 @ 0.517%
P-73
290' 36" I-2 @ 0.514%
P-82
530' 18"I-2 @ 1.00%
A-70
A-71
A-75
B-1
STA. 4+40 (7.0' LT. ℄)
I-8 YNG ST. TYPE Y-B M.H.
COVER ELEV. 859.11
℄ 12" I-2 833.58
℄ 36" I-2 832.44
℄ 54" I-2 830.77
℄ 68" I-2 (BIST) 829.60
0+00 1+00 2+00 3+00 4+00 5+00 6+00 7+00 8+00 9+00 10+00
865 860 855 850 845 840

A-75
℄ STA 9+70
I-8 Nº1 M.H.
COVER EL. 847.33
℄ 12" I-2 841.41
℄ 15" I-2 841.16
℄ 18" I-2 838.92



STA 0+05 ℄
I-8 Nº1 M.H.
COVER ELEV. 848.27
℄ 12" I-2 844.16
℄ 36" I-2 834.68



SEWER PROFILES
HORZ. 1"=20'
VERT. 1"=5'

PLAN - PROFILE RELOC. PIKE ST.

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

293
492

TOP OF RAIL

4'-2½"

2'-6"

TO BE REMOVED

2'-6"

3/4" RODS - 6" C.C.

PROP. PROFILE GRADE OF RELOC. PIKE ST.

GROUND LINE

EXISTING DRIVEWAY -1.00%

3/4" RODS 12" C.C.

3/4" RODS 6" C.C.

3/4" RODS 4" C.C.

3/4" RODS BENT

3/4" RODS BENT

THIS AREA TO BE REMOVED

-4.00%

EL. 848.00

30'-0"

30'-0"

30'-0"

30'-0"

BIN No 7

BIN No 6

BIN No 5

PROP. CURB

3'-0"

11'-0"

2'-6"

2" ANCHOR BOLTS 2'-9" LONG

3/4" RODS 10'-0" LONG PROJECT 3' FROM MASONRY.

7+30

7+40

PROP. PIKE STREET

7+50

7+60

7+63

7+70

7+80

7+80

7+92

P.C. 7+55.87

26.5'

CROSS-HATCHED WALL TO BE REMOVED

℄ OF GIRDERS

℄ OF TRACK & PIERS

℄ OF GIRDERS

3/4" RODS 13'-0" LONG PROJECT 5'-3" FROM PIERS ALL LONGITUDINAL RODS LAPPED 2'-0"

3/4" RODS 30'-0" LONG

1½" RODS 2'-0" C.C.

FOOT OF SLAG FILL

1¼" RODS

2" ANCHOR BOLTS 2'-0" LONG (SAME FOR ALL PIERS)

3/4" RODS

5'-6"

5'-0"

5'-6"

5'-0"

5'-0"

5'-0"

30°

3'-6"

3'-6"

MAHONING RIVER

L.E.&E.R.R.

B.&O.R.R.

WALL

COAL BINS

3'-6"


3'-6"

PIKE ST.

WALL


LOCATION PLAN
SCALE: 1" = 100'

REMOVAL OF EXISTING COAL BINS




C-162
F-82

850




C-94
F-194

850




C-0
F-721

850




C-0
F-652

850




C-43
F-204

850




C-91
F-0

850




C-3
F-174

850




C-4
F-46

850




C-23
F-10

850



C-26
F-4

850



850

80 60 40 20 ℄ 20 40 60 80

PIKE ST. 0+00 TO 5+25

MAH-18-17.20


FED. RD.	STATE
2	OHIO
PROJECT	

294
492




9+64.63
847.5

850
C- 0
F- 0



9+50
846.8

850
C- 22
F- 4




9+08
845.0

SEE 1014+00
Y.E. X-SECTIONS

C-153
F-168

850




8+53
844.0

SEE 1013+50
Y.E. X-SECTIONS

C- 0
F- 271

850




7+98
843.5

SEE 1013+00
Y.E. X-SECTIONS

C- 23
F- 240

850




7+43
846.0

SEE 1012+50
Y.E. X-SECTIONS

C- 13
F- 240

860




6+89
848.0

SEE 1012+00
Y.E. X-SECTIONS

C- 0
F-335

850




6+35
853.0

SEE 1011+50
Y.E. X-SECTIONS

C- 59
F- 274

850



5+80
861.5

SEE 1011+00
Y.E. X-SECTIONS.

C-136
F-136

860

80 60 40 20 0 20 40 60 80

PIKE ST. 5+80 TO 9+64.63

MAH-18-11.20


2	FED. RD.	
OHIO	STATE	
	PROJECT	

235
432


FED RD	STATE	PROJECT	
2	OHIO		

MAH -18-17.20

296
492




LIMITING STATIONS
STA. 2+30 TO STA. 4+29.90



LIMITING STATIONS
STA. 4+29.90 TO STA. 7+91.06

1. 1 T-35 ASPHALTIC CONCRETE SURFACE COURSE - TYPE "C" (70-85)
2. 2" B-35 ASPHALTIC CONCRETE LEVELING COURSE - (70-85)
3. B-35 ASPHALTIC CONCRETE PRELEVELING COURSE - VARIABLE THICKNESS (70-85)
4. T-30 BITUMINOUS TACK COAT 0.10 GAL. PER SQ. YD.
5. 9" B-70 PORTLAND CEMENT CONCRETE BASE COURSE
6. 6" I-22 SUBBASE
7. I-12 COMBINED CURB & GUTTER -TYPE 2
8. L-9 SEEDING & PROTECTING
9. 5" I-13 CONCRETE SIDEWALK - INCLUDING 5" CINDER SUBBASE

TYPICAL SECTIONS - WOODLAND AVE. EAST



CODE	ITEM	REMARKS
R-1	S-24	REMOVAL OF EXISTING RETAINING WALL
R-2	S-24	REMOVAL OF EXISTING RETAINING WALL
R-3	S-22	REMOVAL OF PORTION EXISTING HOUSE

FED RD.	STATE	PROJECT	
2	OHIO		

297
492

MAH-18-17.20

ITEM E-8 EXIST. CURB REMOV. & DISPOSAL (L.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
A-1	2+45	4+23	RT.	247
A-2	4+39	7+79	RT.	379
A-3	8+02	8+66.06	RT.	57
A-4	1+20.96	8+66.06	LT.	746

ITEM I-12 CONC. CURB REPLACE. (LIN. FT.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
G-1	2+45.00	4+18.95	RT.	226.07
G-2	4+39.95	7+27.22	RT.	305.36
G-3	8+02.74	8+66.06	RT.	91.16
G-4	1+20.96	8+66.06	LT.	746

ITEM I-8 M.H. ADJUSTED TO GRADE (EA.)

CODE	STA.	LOCA.	TOP ELEV.	REMARKS
E-1	2+30	28' RT.	UNDISTURBED	
E-2	2+68	℄	943.25	
E-3	4+40.6	℄	940.59	
E-4	8+03.4	℄	927.60	

ITEM I-2 COMBINATION SEWER UNDER PAV'T & APPR. M-6.8(b)

CODE	FROM	TO	LOCA.	SIZE	LIN. FT.
C-1	D-1	E-1	HAYES	12"	22
C-2	D-2	F-2	RT. OF ℄	12"	12
C-3	D-4	MAIN	ERIE	12"	20
C-4	D-5	F-5	LT. OF ℄	12"	8
C-5	D-6	MAIN	MARLIN	12"	14

ITEM EXIST. DRIVEWAYS & APPROACHES (SQ. YDS.)

CODE	STA.	LOCA.	5"-7" P.C.C. DRIVEWAY APPROACH	DRIVEWAYS (SINGLE PRIVATE) 5" T.T.C.
J-1	5+10	RT.	7	
J-2	5+78	RT.	7	
J-3	6+44	RT.	7	19
J-4	8+62	RT.	9	
J-5	2+70	LT.	8	
J-6	3+20	LT.	8	
J-7	4+01	LT.	8	
J-8	4+84	LT.	8	
J-9	8+23	LT.	8	
J-10	6+08	RT.	7	

ITEM E-8 REMOV. & DISP. OF EXIST. WEARING COURSE

CODE	FROM STA.	TO STA.	SQ. YDS.	REMARKS
K-1	7+01	8+66	253	INCL. PART OF MARLIN
K-2	3+00	7+30	860	

ITEM E-8 EXIST. SIDEWALK REMVL. (S.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
B-1	2+45	4+23	RT.	1215
B-2	4+39	7+79	RT.	1865
B-3	8+02	8+66	RT.	470
B-4	1+84	8+66	LT.	3410

ITEM I-13 CONC. SIDEWALK REPLACE. (S.F.)

CODE	FROM STA.	TO STA.	LOCA.	QUAN.
H-1	2+46	4+19	RT.	1288
H-2	4+41	7+27	RT.	1826
H-3	8+07	8+66	RT.	504
H-4	1+84	8+66	LT.	4052

ITEM I-16 INLETS ABAND. (EA.)

CODE	STATION	LOCA.	REMARKS
F-1	2+45	28' RT. OF ℄	PLUG LEAD
F-2	4+11	12.5' RT.	USE EX. L.D.
F-3	4+40	28' RT.	PLUG LEAD
F-4	7+67	12.5' RT.	PLUG LEAD
F-5	7+66	12.5' LT.	USE EX. L.D.
F-6	8+04	28' RT.	PLUG LEAD

ITEM I-8 INLETS YNGSTN TYPE II (EA.)


CODE	STATION	LOCA.	WIND PE.	C.B. INV.
D-1	0+44.08	HAYES	943.70	938.70
D-2	3+98.52	20' R.	940.60	935.60
D-3	0+41.58	ERIE	941.20	936.20
D-4	0+48.12	ERIE	941.34	936.34
D-5	7+66	20' L.	928.86	923.86
D-6	0+44.25	MARLIN	928.22	923.22

I-13 CONCRETE STEPS

CODE	WIDTH	Nº OF RISERS	RISER	TREAD	L.F
S-1	4'-0"	5	8"	12"	6'
S-2	4'-6"	6	8"	12"	7.2'
S-3	4'-0"	4	8"	12"	5'
S-4	5'-0"	8	8"	12"	9.7'
S-5	4'-0"	4	8"	12"	5'
S-6	4'-0"	4	8"	12"	5'

CONCRETE RETAINING WALL - SEE SHEET Nº

CODE	S-1 CLASS "C" CONCRETE C.Y.	S-4 REINFORCING STEEL lbs.	S-2 EXCAVATION FOR STRUCTURE C.Y.	S-29 PORUS BACKFILL C.Y.	HEIGHT	LENGTH
W-1	12.5	503	51	12	3.5	58'
W-2	5.0	208	21	4	3.	25'



WOODLAND AVE. EAST


MARKET ST. TO EAST OF MARLIN ST.

SCALES: H-1" = 50'
V-1" = 5'


FED. RD.	STATE	PROJECT	
2	OHIO		

298
492

MAH -18-17.20




INTERSECTION - WOODLAND ℄ MARLIN



INTERSECTION - WOODLAND ℄ ERIE

NOTE: CURB ELEVATIONS AS SHOWN ARE TOP OF CURB GRADES.



INTERSECTION - WOODLAND ℄ HAYES


PAVEMENT DETAILS - WOODLAND AVE. EAS

END AREA	CU. YDS.
CUT	FILL
CUT	FILL

| | | |

SEEDING	
END WIDTH	SQ. YDS.

END AREA CU.YDS.			
CUT	FILL	CUT	FILL




3.6

6.3


5.8

4.6




7.4

6.2




9.3

19.9



44.5

64.1



39.9

50 40 30 20 10 ℄ 10 20 30 40

X-SECTIONS WOODLAND AVE. STA. 7+30 – STA. 8+30

FED. RD.	STATE	PROJECT
2	OHIO	

MAY 18-17-20


300

4492

FED. RD	STATE	PROJECT	
2	OHIO		

301
492


MAH -18-17.20



WOODLAND AVE. (WEST)
LIMITING STATIONS
STA. 6+18.46 - STA. 7+50

(1) ITEM T-71 9" REINFORCED PORTLAND CEMENT CONC. PAV'T.
(2) ITEM I-22 6" SUBBASE
(3) ITEM I-12 STANDARD TYPE 2A CONCRETE CURB

(4) ITEM I-13 5" CONC. SIDEWALK INCLUDING 5" CINDER SUBBASE
(5) ITEM L-9 SEEDING & PROTECTING



WOODLAND AVE. (WEST)
LIMITING STATIONS
STA. 0+64 To STA. 4+11.38

(1) 1" T-35 ASPHALTIC CONCRETE SURFACE COURSE - TYPE "C" (70-85)
(2) 2" B-35 ASPHALTIC CONCRETE LEVELING COURSE - (70-85)
(3) B-35 ASPHALTIC CONCRETE PRELEVELING COURSE - VARIABLE THICKNESS (70-85)
(4) T-30 BITUMINOUS TACK COAT 0.1 GAL. PER SQ. YD.
(5) 9" B-70 PORTLAND CEMENT CONCRETE BASE COURSE

(6) 6" I-22 SUBBASE
(7) I-12 COMBINED CURB & GUTTER - TYPE 2
(8) L-9 SEEDING & PROTECTING
(9) 5" I-13 CONCRETE SIDEWALK - INCLUDING 5" CINDER SUBBASE

TYPICAL SECTIONS WOODLAND AVE. (WEST)

FED. RD	STATE	PROJECT
2	OHIO	

302
492

MAH-18-17.20

ITEM S-5 DRIVEWAYS & APPROACHES

CODE	STA.	LOCA.	8'-11' SGL. APPROACH (SY.)	5'-7' SINGLE PRIVATE DRIVES (SY.)
J-1	1+40	LT.	40 (DOUB. BUS)	
J-2	2+56	LT.	7	33
J-3	3+05	LT.	7	33

ITEM E-8 REMOV. & DISP. OF EXIST. S. WALK (S.F.)


CODE	FROM	TO	LOCA.	QUAN.
B-1	MARKET ST.	7+50	N	4308
B-2	MARKET ST.	WILLIAMS	S	3030
B-3	WILLIAMS	7+50	S	1032
B-4	W. SIDE WMS.	8+88	W	498
B-5	E. SIDE WMS.	8+88	E.	642

ITEM E-8 REMOV. & DISP. OF EXIST. PAV'T. (S. YDS.)

CODE	FROM	TO		QUAN.
K-1	4+15.45	7+50		1115
K-2	0+32	0+47		50
K-3	ON WILLIAMS ST.			288.

ITEM E-8 REMOV. & DISP. OF EXIST. CURB (L.F.)

CODE	FROM	TO	LOCA.	QUAN.
A-1	0+32	7+50	N.	718
A-2	0+32	5+37	S.	505
A-3	6+77	7+50	S.	73
A-4	WILLIAMS ST.		W.	123
A-5	WILLIAMS ST.		E.	143



ITEM I-8 YOUNGSTOWN TYPE II INLETS (EA.)

CODE	STA.	LOCA.	TOP	FLOW LINE
D-1	PT. 52+07.66	34' LT. MARKET ℄	941.50	938.00
D-2	P.C. 0+63.99	24' LT. WOODL'D ℄	939.74	936.24
D-3	P.C. 0+64.01	24' RT. WOODL'D ℄	939.74	936.24
D-4	3+25	24' RT. WOODL'D ℄	949.49	946.50
D-5	3+25	24' LT. WOODL'D ℄	949.49	946.50
D-6	8+87	16' RT. WILLIAMS	962.02	958.52
D-7	1/8 PT OF S.W.	RET. @ WILLIAMS	961.50	958.00
D-8	6+50	21.2' LT. WOODL'D ℄	963.44	959.94
D-9	6+50	19' RT. WOODL'D ℄	963.47	959.97

ITEM I-16 INLETS ABANDONED (EA.)

CODE	STATION	LOCA.	REMARKS
F-1	0+38	19' LT. ℄	PLUG LEAD
F-2	0+57	4' LT. ℄	PLUG LEAD
F-3	0+60	24' RT. ℄	PLUG LEAD
F-4	3+66	30' RT. ℄	PLUG LEAD
F-5	3+50	ON ℄	PLUG LEAD

ITEM I-8 MANHOLES ADJUSTED TO GRADE

CODE	STATION	LOCATION	TOP ELEV.	REMARKS
E-1	0+50	5' RT. OF ℄	935.63	
E-2	3+54	18' RT. OF ℄	950.25	

ITEM I-2 M-686 COMB. SWR. UNDER PAV'T. & APPROACHES

CODE	FROM	TO	TYPE & SIZE	LENGTH BID	LENGTH GRADE	% GRADE
C-1	D-1	EXIST. M.H.	12"	62	65	3.40%
C-2	D-2	EXIST. M.H.	12"	34	36	1.0%
C-3	D-3	EXIST. M.H.	12"	19	21	1.71%
C-4	D-4	PROP. M.H.	12"	14	16	2.54%
C-5	D-5	PROP. M.H.	12"	38	41	1.0%
C-6	D-6	PROP. M.H.	12"	6	8	10.50%
C-7	D-7	PROP. M.H.	12"	30	32	1.0%
C-8	D-8	PROP. M.H.	12"	12	14	2.25%
C-9	D-9	PROP. M.H.	12"	33	35	1.0%

ITEM I-4 UNDERDRAIN (SHALLOW) L.F.

CODE	FROM	TO	6" PIPE	8" OUTLET PIPE M-6.4(4)
U-1	0+64.01	0+90.90	16	10

ITEM I-13 CONC. SIDEWALK REPLACE. (S.F.)


CODE	FROM	TO	LOCA.	QUAN.
H-1	N.W. CORNER ℄ MARKET ST.			150
H-2	S.W. CORNER ℄ MARKET ST.			258
H-3	0+64	4+24	S	1800
H-4	3+18	4+29	N	786
H-5	8+88	9+20	WILLIAMS	182
H-6	8+88	AND S.W. RETURN		366
H-7	6+21	7+50	N	762
H-8	6+08	7+50	S	858

ITEM I-12. CONCRETE CURB (L.F.)

CODE	FROM	TO	LOCA.	TYPE 2 CONC. CURB & GUTTER	TYPE 2A CURB
G-1	N.W. RETURN ℄ MARKET			33.45	
G-2	0+64.01	0+90.07	N.	26.06	
G-3	3+17.48	4+25.05	N.	93.90	
G-4	S.W. RETURN ℄ MARKET			40.30	
G-5	0+63.99	4+06.05	S.	314.72	
G-6	6+26.30	7+50	N.		110.03
G-7	8+50.00	9+04.20	WBS		40.53
G-8	8+50.00	8+13.34	WBS		63.34
G-9	S.W. RETURN ℄ WILLIAMS				12.3
G-10	6+21.24	6+90.31	S		64.66
G-11	6+28.31	7+50	S		40.93

GUTTER LINE ELEVATIONS

N.W. CURB RETURN @ WOODLAND AVE. & MARKET ST.				
P.C. STA. 0+64.01 ON WOODLAND AVE.	1/4	1/2	3/4	P.T. STA. 53+15.66 ON MARKET ST.
939.74	939.24	938.62	938.00	937.48
S.W. CURB RETURN @ WOODLAND AVE. & MARKET ST.				
P.C. STA. 0+63.99 ON WOODLAND AVE.	1/4	1/2	3/4	P.T. STA. 52+07.66 ON MARKET ST.
939.74	939.83	940.21	940.65	941.09



PROFILE - REL. WOODLAND AVE.

PLAN-PROFILE RELOCATED WOODLAND AVE. (WEST)

END AREAS ℄

C=104
F=0

END AREA ℄ FOR B-35

CU. YD. OF B-35

15.2

C=67.5
F=0

PROP ℄

EXIST ℄

8.2

948

C=103
F=0

SEE RAMP L X-SECTIONS

B-35

946

(946.41)

2+50

PG. 946.87

944

C=43.8
F=0

13.9

12.3

946

SEE RAMP L X-SECTIONS

C=77
F=0

B-35

944

(944.59)

2+00

PG. 945.09

21.5

C=38.7
F=0

18.9

944

SEE RAMP L X-SECTION

C = 85
F = 8

B-35

942

(942.77)

1+50

PG. 943.81

C=52.8
F=8.3

16.2

944

6.4

942

C = 129
F = 12

B-35

(941.03)

940

1+00

PG. 941.53

C= 77.3
F= 4.3

5.8

942

940

C=157
F=4

E-8

(939.51)

0+47

938

PG. 939.05

C=102.7
F=0

940

E-8

(939.04)

938

BEGIN CONSTRUCTION

PG. 939.24

0+32

940

50

40

PROP ℄

EXIST ℄

940

0+00

(939.36)

938

(INTERSECTION WOODLAND & MARKET)

936

40 30 20 10 0 10 20 30 40

CROSS - SECTIONS - WOODLAND AVE. (WEST)

MAH-18-17.20

FED. RD.	STATE
2	OHIO
	PROJECT

304
492

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH -18-17.20

303-492

BEGIN APPROACH SLAB STA. 5+93.46

TAPER SIDEWALK FROM 5' @ STA. 6+08.25 TO 6' @ STA. 7+00

PROP. SIDEWALK

℄ ABUTMENT Nº II STA. 5+91.01

℄ PIER Nº II STA. 5+50.60

STA. 5+46.18 (PROP WOODLAND STA.) = STA. 10+00 (WILLIAMS ST.)

50'

15'

12.5'

℄ PIER Nº II

ELEVATION LINE

STA. 5+51.53 WOODLD. = STA. 9+89.53 WILLIAMS

℄ EXIST. WOODLAND AVE.

PROP. WOODLAND AVE.

5+00

6+00

7+00

7+50

103.76'

103.33'

23.43'

2°58'26"

85°18'24"

62°15'41"

62°43'35"

60°42'46"

END WORK P.T. STA. 7+50.00

PROP. 6' SIDEWALK

P.C. STA. 6+93.31

EXPANSION JOINT STA. 6+40.43

END APPROACH SLAB STA. 6+18.46

P.T. STA. 6+21.24

FACE OF CURB DATA
Δ = 7°40'
T = 25.00'
R = 373.11'
L = 49.93'

CURB RETURN DATA
Δ = 113°02'45"
R = 25'
T = 37.80'
L = 49.33'

½ POINT

P.C. STA. 9+13.34

P.T. STA. 9+42.67

P.C. STA. 5+18.72

CURB RETURN DATA.
Δ = 59°17'15"
R = 50'
T = 28.45'
L = 51.74'

EXIST. SIDEWALK

PROP. SIDEWALK

WILLIAMS ST.

MATCH LINE STA. 8+88.97

BEGIN APPROACH SLAB STA. 9+13.21

EXISTING PAVEMENT

ST'D. EXPAN. JOINT

9" T-71

9" T-70

6" I-22

SECTION A-A.

BEGIN WORK STA. 8+50

℄ G.E. DRIVE STA. 8+62

℄ ABUTMENT Nº II FACE OF BACK WALL

℄ ABUTMENT Nº II STA. 9+43.10

END APPROACH SLAB STA. 9+40.21

LEGEND

- (A) STANDARD LONGITUDINAL JOINT
- (B) STANDARD KEY JOINT WITHOUT TIE BARS
- (C) EXPANSION JOINT WITHOUT DOWELS (LOCATED ON RAD. LINES)
- (D) STANDARD EXPANSION JOINTS
- (E) STANDARD CONTRACTION JOINTS (TO BE PLACED AT 60' INTERVALS OR LESS IN ALL T-71 PAVEMENT)
- ℄ BEAM LINES = ———— ———— ————

NOTE: ALL ELEVATIONS ARE ON THE FINISHED SURFACE.

INTERSECTION DETAIL & JOINT PLAN

WEST WOODLAND AVE. & WILLIAMS ST.


SCALE- 1" = 10'

END AREAS ∅

BRIDGE

END AREA ∅
for B-35


CU. YD of B-35



4+40.49

END APPROACH SLAB


RG. 953.97



BEGIN APPROACH SLAB


4+15.49 952.66

RG. 952.89




4+00

RG 952.24



3+50

RG. 950.43



3+00


RG. 948.65

CROSS - SECTIONS - WOODLAND AVE. (WEST)

MAR-18-17.20


2	FED. RD	
OHIO	STATE	
	PROJECT	

305
492




970
C = 0
F = 0
968

8+00




968
C = 7.8
F = 0
966

7+50
END WORK
& MEET EXIST
CURB, PAVT., & WALK




966
C = 14.6
F = 1.0
964

7+00



964
C = 31.0
F = 0.9
962

6+50



962

960

6+00
ON BRIDGE SLAB
LOOKING WEST

CROSS - SECTIONS - WOODLAND AVE. (WEST)

FED. NO.	STATE	PROJECT
2	OHIO	
3		

MAH-18-17.20

306
492

FED. RD.	STATE	PROJECT	
2	OHIO		

307
492

MAH-18-17.20

GENERAL NOTES - LIGHTING

INSPECTION AND TESTING

COSTS OF ALL OF THE FOLLOWING INSPECTIONS AND TESTS SHALL BE INCLUDED IN THE UNIT PRICES BID FOR VARIOUS ITEMS ON THIS PROJECT.

THE INSTALLATION OF ALL STREET LIGHTING EQUIPMENT WILL BE INSPECTED BY A REPRESENTATIVE OF THE OHIO EDISON COMPANY WHILE BEING INSTALLED. THE COST OF SUCH INSPECTION SHALL BE BORNE BY THE CONTRACTOR.

UPON COMPLETION OF THE LIGHTING SYSTEM, THE FOLLOWING TESTS WILL BE CONDUCTED BY THE OHIO EDISON COMPANY, SUCH TESTS TO BE PAID FOR BY THE CONTRACTOR.

POTENTIAL TESTS:

THE POTENTIAL OF THE SYSTEM SHALL BE CONSIDERED SATISFACTORY WHEN THE TEST VOLTAGE OF TWICE THE OPERATING VOLTAGE PLUS 1,000 VOLTS IS HELD FOR ONE MINUTE.

BURNING TEST:

THE COMPLETED LIGHTING SYSTEM SHALL BE OPERATED FROM SUNSET TO SUNRISE EACH NIGHT FOR A PERIOD OF ONE WEEK PRIOR TO ACCEPTANCE. DURING THIS TRIAL OPERATION, THE CONTRACTOR SHALL CORRECT ANY DEFECT WHICH MAY DEVELOP, AT NO EXTRA COST TO THE STATE.

LIGHTING STANDARD FOUNDATIONS AND CONDUIT WIRE AND CABLE:

THE LAMP STANDARD FOUNDATIONS SHALL BE CLASS "C" CONCRETE WITH FOUR(4) 1"x3'-4" STEEL ANCHOR RODS, CADMIUM COATED OR GALVANIZED, 6" ON THREADED ENDS, EXTENDED 2 5/8" ABOVE THE TOP OF THE FOUNDATION. THE LIGHTING CABLES SHALL ENTER THE LIGHTING STANDARD BASE THRU A 2" GALVANIZED CONDUIT, FROM THE 24" SQUARE CONC. PULL BOX MOUNTED ADJACENT TO IT, AS INDICATED ON THE PLANS. THE STANDARDS ON BRIDGES ARE TO BE MOUNTED ON THE CONC. PARAPET WALL, WITH A GALVANIZED CAST IRON BOX ADJACENT TO IT, TO FACILITATE THE WIRING.

THE N°6 AWG CABLE, AS INDICATED ON THE PLANS, SHALL BE 5,000 VOLTS, STRANDED COPPER, SERIES CABLE WITH 10/64" RUBBER INSULATION, NON-SHIELDED, WITH 4/64" NEOPRENE JACKET, SUPER CORONAL-GEOPRENE OR EQUAL.

THE N°2 AWG CABLE, AS INDICATED ON THE PLANS, SHALL BE SEVEN STRANDED TINNED COPPER CABLE WITH 2/64" FLAMENOL INSULATION OR EQUAL.

THE N°8 AWG CABLE USED TO CONNECT BETWEEN THE SECONDARY OF THE 175 W. SERIES TRANSFORMERS AND THE LUMINAIRE SHALL BE 1,000 VOLTS T STRAND, COPPER WIRE WITH 5/64" VERSATOL GEOPRENE INSULATION OR EQUAL. DUPLEX CABLE MAY BE USED IN PLACE OF 2 SINGLE WIRES, AT THE OPTION OF THE CONTRACTOR.

STANDARDS:

THE STANDARDS SHALL BE OF SUCH DESIGN AS TO MAKE A COMPLETE WIRING RACEWAY AFTER THE STANDARDS HAVE BEEN ASSEMBLED AND ERECTED. THE BRACKET SHALL NOT BE LESS THAN 2" INSIDE DIAMETER. THE STANDARD SHALL BE EQUIPPED WITH A "J" HOOK PLACED INSIDE AND ABOVE THE BRACKET MOUNTING HEIGHT, TO ATTACH A CABLE GRIP IN SUCH A MANNER TO PREVENT THE CABLE FROM HANGING IN THE POLE AND BRACKET BUSHING AT THE POINT OF BRACKET ATTACHMENT TO THE POLE. THE LIGHT STANDARD SHALL BE SUPPLIED WITH A GROUNDING LUG INSIDE THE BASE, AND A 4"x6½" HAND HOLE.

LUMINAIRE:

THE LUMINAIRES SHALL BE AS FOLLOWS:

(A) EXPRESSWAY- G.E. FORM M-400 #C-704G022 OR WESTINGHOUSE OV-25 STYLES OV-25E II 20S AND AV-25E III 20S., *or approved equal.* THEY SHALL BE DESIGNED FOR 2" SLIPFITTER, ASA-IES TYPE II OR III DISTRIBUTION (AS INDICATED ON THE PLANS) AND A 21,500 LUMEN HI-LS 400 WATT. MERCURY LAMP (CLEAR).

(S) UNDERSTRUCTURE UNITS- G.E. FORM 101S (IF ADAPTED FOR 175 W. MERCURY LAMP), *or approved equal* OR WESTINGHOUSE AK-10, OR L.M. CO. CAT. #LM2541, THEY SHALL BE DESIGNED FOR 1¼" SIDE MOUNTING SLIPFITTER, ASA-IES TYPE V DISTRIBUTION, AND A 7,000 LUMEN H22KD 175 WATT MERCURY LAMP (CLEAR).

SERIES MERCURY TRANSFORMERS:

A SERIES MERCURY TRANSFORMER SHALL BE PROVIDED FOR EACH LUMINAIRE TO BE MOUNTED IN THE LUMINAIRE OF ALL ROADWAY AND RAMP STANDARDS, AND IN THE 24"x10"x10" CAST BOX OF THE UNDERSTRUCTURE UNITS. ALL SERIES TRANSFORMERS SHALL BE FOR SERIES CIRCUITS RATED AT 20 AMPERES, AND OF THE WATTS REQUIRED FOR THE LUMINAIRE WITH WHICH IT IS USED.

DIRECT BURIAL CABLE INSTALLATION:

THE N°6 5,000 VOLT LIGHTING CABLES, AND N°2 GROUND WIRE (ALSO USED TO COMPLETE THE SERIES LOOP), SHALL BE CONTINUOUS FROM BASE TO BASE OF STANDARDS, AND EXCEPT FOR THAT PART IN GALVANIZED STEEL CONDUIT ON BRIDGES AND IN CONCRETE ENCASED CEMENT-ASBESTOS CONDUIT WHERE CROSSING UNDER PAVED RAMPS AND SHOULDERS, SHALL BE DIRECT BURIAL, LAID NOT LESS THAN 18" BELOW GRADE. CONDUIT SHALL COMPLY WITH SPECIFICATION N°M-206.14 AND SHALL BE GRADED TO PREVENT WATER POCKETS.

EXCAVATION:

THE CONTRACTOR SHALL DO ALL EXCAVATION OF EVERY DESCRIPTION TO THE DIMENSIONS AND LEVELS SHOWN ON THE PLANS, OR AS DIRECTED BY THE ENGINEER. EXCAVATION MAY BE ACCOMPLISHED WITH MECHANICAL TRENCHING EQUIPMENT. WALLS OF TRENCHES SHALL BE ESSENTIALLY VERTICAL, AND BOTTOMS SHALL BE SMOOTH AND FREE FROM AGGREGATE LARGER THAN ¼". PROVIDE SHORING WHEN REQUIRED.

WHEN ROCK IS ENCOUNTERED IN EXCAVATION FOR CABLE TRENCHES, THE ROCK SHALL BE REMOVED TO A DEPTH OF AT LEAST THREE INCHS(3") BELOW THE REQUIRED DEPTH OF EXCAVATION, AND A BED OF SAND OR EARTH CONTAINING NO MINERAL AGGREGATE PARTICLES THAT WOULD BE RETAINED ON A ¼" SIEVE, SHALL BE PLACED IN THE BOTTOM OF THE TRENCH AND COMPACTED AS SPECIFIED FOR SLOPES.

CABLE INSTALLATION:

CABLES SHALL BE UNREELED IN PLACE ALONGSIDE, OR IN CABLE TRENCH, AND SHALL BE CAREFULLY PLACED ALONG THE BOTTOM OF THE TRENCH. UNDER NO CIRCUMSTANCES SHALL THE CABLE BE UNREELED AND PULLED INTO THE TRENCH FROM ONE END.

NO SPLICES IN CABLES WILL BE PERMITTED IN TRENCHES BETWEEN STANDARDS OR PULL BOXES. 24" SQUARE CONCRETE PULL BOXES ARE TO BE PROVIDED AT EACH LIGHTING STANDARD, AND AT ENDS OF EACH RUN OF CEMENT-ASBESTOS CONDUIT, WHERE LIGHTING CIRCUITS CROSS UNDER PAVEMENTS. IN MOST CASES CROSSING UNDER PAVEMENT WILL BE AT A STANDARD, THEREBY UTILIZING THE PULL BOX AT THE STANDARD. PULL BOXES SHALL BE LOCATED OUTSIDE THE PAVED SHOULDER IN ALL CASES, AND CABLES SHALL BE ROUTED THROUGH THEM. AT THE PULL BOXES ADJACENT TO THE STANDARDS, SUFFICIENT CABLE SHALL BE LEFT, SO THAT IT MAY BE PULLED THROUGH THE 2" CONDUIT, AND UP THE STANDARD TO A CONNECTION MADE AT THE SERIES TRANSFORMER IN THE LUMINAIRE.

BACKFILLING:

BACKFILL FOR CABLE TRENCHES SHALL BE PLACED IN LAYERS. THE FIRST LAYER SHALL BE EITHER EARTH OR SAND, 3" THICK LOOSE MEASUREMENT, AND SHALL CONTAIN NO MINERAL AGGREGATE PARTICLES THAT WOULD BE RETAINED IN A 1/4" SIEVE. THE SECOND LAYER SHALL BE 4" THICK, AND SHALL CONTAIN NO PARTICALS THAT WOULD BE RETAINED IN A 1" SIEVE. THE THIRD LAYER AND SUBSEQUENT LAYERS SHALL CONTAIN NO AGGREGATE LARGER THAN 3". THE COMPACTION OF THE DIFFERENT LAYERS AND FINISH GRADING AROUND BACKFILL WORK SHALL BE IN ACCORDANCE WITH THAT OF THE ADJACENT AREAS, RAMPS, AND GRADES; ALL TO BE ACCOMPLISHED IN A MANNER SATISFACTORY TO THE ENGINEER.

CABLE TERMINATION AND SPLICING:

THE CABLE TERMINATION AND SPLICES SHALL BE MADE IN ACCORDANCE WITH THE LATEST CABLE MANUFACTURER'S RECOMMENDATIONS AND UNDER THE SUPERVISION OR DIRECTION OF THE OHIO EDISON COMPANY'S INSPECTOR.

GROUNDING:

A "GROUND ROD OR RODS SHALL BE DRIVEN UNDER THE BASE OF EACH LIGHT STANDARD, WITH A TINNED FLEXIBLE #6 BARE COPPER WIRE TAIL OF SUFFICIENT LENGTH TO REACH THE GROUNDING LUG ON THE STANDARD. STANDARD AND GROUND ROD MUST NOT MEASURE MORE THAN 15 OHMS. RESISTENCE.

THE #2 CABLE SHALL BE GROUNDED TO THE LIGHTING STANDARD GROUND LUG AT EACH STANDARD, AT THE MIDPOINT AND AT EACH END OF THE CIRCUIT, THE #2 GROUND CONDUCTER SHALL BE CONNECTED TO THE OHIO EDISON COMPANY NEUTRAL GROUND GRID. LOCATION OF THESE GROUND POINTS AND METHOD OF INSTALLATION SHALL BE OBTAINED FROM THE OHIO EDISON COMPANY.

IF ADDITIONAL GROUND RODS ARE REQUIRED TO OBTAIN 15 OHMS. RESISTENCE, THEY MAY BE DRIVEN 5'-0" OR MORE FROM THE BASE OF THE STANDARD AND TAILS FROM THE ADDITIONAL GROUND RODS SHALL BE EXTENDED FROM THESE RODS THROUGH A CABLE ENTRANCE CONDUIT TO THE GROUNDING LUG IN THE STANDARD, ALL GROUNDING RODS AND TAILS SHALL NOT BE EXPOSED ABOVE THE GRADE LINE. THE BRIDGE LIGHT STANDARDS SHALL BE GROUNDED AS INDICATED ON THE PLANS.

ELECTRICAL SYSTEM PRINTS:

THE CONTRACTOR SHALL FURNISH TO THE OHIO EDISON COMPANY AT LEAST THREE (3) PRINTS OF THE ELECTRICAL SYSTEM SHOWING THE EXACT LOCATION OF CABLE, CONNECTIONS AND OTHER PERTINENT INFORMATION.

PAINTING:

LIGHT STANDARDS SHALL BE GIVEN TWO FIELD COATS OF ALUMINUM PAINT CONFORMING TO SEC. M-912. THE FIRST COAT SHALL BE SUITABLY TINTED.

CONSTANT CURRENT SERVICES:

THE 20-AMPERE CONSTANT CURRENT STATIONS WILL BE PROVIDED BY THE OHIO EDISON COMPANY. THE CONTRACTOR SHALL EXTEND CIRCUIT LEADS UP SERVICE POLES IN 3" GALVANIZED RIGID CONDUITS AND TERMINATE WITH SUFFICIENT LEADS EXTENDING FROM SUITABLE ENTRANCE FITTINGS OR TERMINATORS FOR CONNECTIONS BY OHIO EDISON COMPANY. EXTEND RIGID CONDUIT TO 2'-0" BELOW GROUND AND HORIZONTALLY CONVERT TO CONCRETE ENCASED CEMENT-ASBESTOS CONDUIT. CONCRETE ENCASE THE TURN-UP AT POLE TO A MINIMUM OF 8" ABOVE THE GRADE.


LIGHTING DESIGN:


THE LIGHTING DESIGN IS BASED ON 0.6 TO 0.8 FOOTCANDLE AVERAGE MAINTAINED VALUE ON THE EXPRESSWAY, LANES AND RAMPS.

FED. RD.	STATE	PROJECT	
2	OHIO		

308
492

MAH-18-17.20





LIGHTING CIRCUIT Nº 1

TOTAL-34 400W. MERCURY LAMPS + 2 FUTURE

LIGHTING CIRCUIT Nº 2

TOTAL-33 400W. MERCURY LAMPS + 2 FUTURE

ALL LAMPS 400 W. MERCURY EXCEPT WHERE INDICATED. SYSTEM 20 A. SERIES

LEGEND


- ROADWAY LIGHT STANDARD SEE DWG. Nº 295 FOR DETAIL.
- #6-5000V. TYPE R.R. COPPER WIRE, DIRECT BURIAL OR CEMENT-ASBESTOS CONDUIT (2" OR 3") SLASH MARKS INDICATE NUMBER OF WIRES INCLUDING GROUND; NUMERAL INDICATES SIZE OF CONDUIT. GALV. STEEL CONDUIT SHALL BE USED IN BRIDGES.
- III-15-1 DESIGNATION OF LIGHT STANDARDS. III INDICATES I.E.S. TYPE III DISTRIBUTION THE NUMBER 15 INDICATES THE BRACKET ARM LENGTH, THE NUMERAL 1 INDICATES THE SERIES CIRCUIT NUMBER.
- STA. STATIONING - STATIONING SHOWN FOR LIGHT STANDARDS IS APPROXIMATE AND IN THE EVENT OF INTERFERENCE WITH OTHER PARTS OF THE WORK, LIGHT STANDARDS SHALL BE RELOCATED AS DIRECTED BY ENGINEER. SPACING OF LIGHTS DESIGNED FOR .6 TO .8 MAINTAINED FC.
- GROUND TO O.E. CO. NEUTRAL GRID.
- CONSTANT CURRENT TRANSFORMER 30KW-20AMP ON WOOD POLE BY O.E. CO.
- 175 W. MERCURY UNDER STRUCTURE LIGHT. FOR LOCATION SEE BRIDGE DWG'S _____ FOR DETAIL SEE DWG. 309


ROADWAY LIGHTING

FED. RD.	STATE	PROJECT	
2	OHIO		

303
492

MAH-18-17.20






SERIES CIRCUIT TO TERMINATE AT 30 K.W. 20 A. C.C. TRANSFORMER ON POLE AT WEST SIDE OF WEST WOODLAND AVE. (POLE & TRSF. BY O.E. Co.)


LIGHTING CIRCUIT Nº 4

TOTAL 28 - 400 W. MERCURY LAMPS + 2 - 175 W. MERCURY LAMPS




LIGHTING CIRCUIT Nº 3

TOTAL 30 - 400W. MERCURY LAMPS



DETAIL - MTG. OF TRSF. BOX & GROUNDING




TYPICAL DETAIL
LUMINAIRE MTG UNDER STRUCTURE
SCALE 3/8"=1'-0"


LIGHTING QUANTITIES

ITEM	DESCRIPTION	UNIT	QUANTITIES
S-25	STANDARD 27'-0" POLE WITH 15' BRACKET	EACH	57
	STANDARD 27'-0" POLE WITH 10' BRACKET	EACH	55
	TWIN STANDARD 27-0" POLE WITH 1-15' BRACKET & 1-10' BRACKET.	EACH	3
	BRIDGE STANDARD 27'-0" POLE WITH 10' BRACKET	EACH	7
	POLE FOUNDATION - CONCRETE	EACH	115
	CONCRETE ENCASED 3" TRANSITE CONDUIT	LIN.FT.	900
	CONCRETE ENCASED 2" TRANSITE CONDUIT	LIN.FT.	1400
	LUMINAIRE - 21,500 LUMEN TYPE III	EACH	74
	LUMINAIRE - 21,500 LUMEN TYPE II	EACH	51
	#6-5000 VOLT LIGHTING SINGLE COND. CABLE	LIN.FT.	56,750
	#2-600 VOLT GRD. GRID SINGLE COND. CABLE	LIN.FT	35,500
	#8-1000 VOLT SEC. SINGLE COND. CABLE.	LIN.FT	250
	5/8" x 8'-0" GROUND RODS	EACH	115
	24" SQUARE CONCRETE PULL BOX	EACH	150
	LUMINAIRE - 7000 LUMEN TYPE V	EACH	2


ROADWAY LIGHTING




BRIDGE LIGHTING UNIT
SCALE 3/8" = 1'-0"




COND. SECTION UNDER PAVEMENT




PLAN - BASE AND CONDUIT TREATMENT AT BRIDGES
SCALE 3/8" = 1'-0"



ELEVATION - BASE AND CONDUIT TREATMENT AT BRIDGES
SCALE 3/8" = 1'-0"




PLAN




ELEVATION

DETAIL - BRIDGE LIGHTING UNIT
SCALE ½" = 1'-0"



TYPICAL - CABLE TRENCH




PLAN VIEW

CABLE AND PULL BOX LOCATION

FED. RD.	STATE	PROJECT	
2	OHIO		


310
192

MAH-18 17.20



J-HOOK DETAIL

UNION METAL DESIGN #440-A
STEEL STANDARD
H-270-D2 - 10' ARM
H-270-F2 - 15' ARM



TYPICAL ROADWAY LIGHTING UNIT
SCALE ½" = 1'-0"


SECTION "A"-"A"
SCALE ½" = 1'-0"

PROVIDE ½" WASH FROM POLE BASE TO EDGE OF CHAMFER.

THIS IS A COMPOSITE ELEVATION VIEW, AND INDICATES THE TYPICAL NORMAL POSITION OF THE 24" SQUARE CONC. PULL BOX BEHIND STANDARD, AS WELL AS AN ALTERNATE POSITION OF PULL BOX USED WHERE CABLES ARE TO BE INSTALLED UNDER ROADWAY (RAMPS) DIRECTLY IN CONDUIT FROM A LAMP STANDARD. ONLY ONE PULL BOX IS REQUIRED AT EACH STANDARD LOCATION. STANDARD FOUNDATION SHALL BE FORMED 2'-6" SQUARE FOR AT LEAST THE TOP ONE FOOT, OR A MINIMUM OF SIX INCHES BELOW FINISHED GROUND LINE. THE LOWER PORTION OF THE FOUNDATION MAY BE CAST WITHOUT FORMS IN A 2'-6" DIAMETER ROUND, OR A 2'-6" SQUARE HOLE.


REQUIRED

5 UNITS ON BRIDGE MAH-18-1823
1 UNIT ON BRIDGE MAH-18-1855
1 UNIT ON BRIDGE MAH-18-1923



ELECTRICAL CONDUIT-EXPANSION FITTING IN BRIDGE CONC. SLAB

ONE AT EACH EXPANSION JOINT OF BRIDGE SLAB.



PLAN

SECTION "B-B"

24" SQUARE CONC. PULL BOX
SCALE 1" = 1'-0"


PULL BOX MAY BE PRECAST OR CAST IN PLACE.

* 27" MINIMUM DEPTH - DEPTH OF BOX SHALL BE INCREASED WHERE CONDUIT PASSES UNDER PAVEMENT, TO MAKE ITS BOTTOM NO LESS THAN UNDERSIDE OF CONC. ENCASEMENT.


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


311
492




PLAN OF WALL




ELEVATION



DETAIL OF RUSTICATION GROOVES



SECTION A-A



LOCATION PLAN

ESTIMATED QUANTITIES

ITEM №	UNIT	DESCRIPTION	TOTAL
E-2	CU.YDS.	UNCLASSIFIED EXCAVATION	27
S-1	CU.YDS.	CLASS "E" CONCRETE - FOOTINGS	13.8
S-1	CU.YDS.	CLASS "E" " - ABOVE FOOTER	6.3
S-4	LBS.	REINFORCING STEEL	834
S-29	CU.YDS.	POUROUS BACKFILL	2.0

REINFORCING STEEL SCHEDULE

MARK	№ REQ'D	LENGTH	WEIGHT	SHAPE
501	22	4'-9"	109	BT.
502	21	3'-7"	78	BT.
503	6	VARIES FROM 2'-7" TO 4'-6" INCR. 4⅜"	22	ST.
504	2	13'-3"	28	ST.
505	11	26'-8"	306	ST.
506	5	VARIES FROM 2'-3" TO 4'-5" INCR. 6¼"	17	ST.
507	2	10'-0"	21	ST.
601	11	VARIES FROM 2'-10" TO 4'-9" INCR. 2¼"	63	ST.
602	10	VARIES FROM 2'-5" TO 4'-7" INCR. 2⅛"	53	ST.
603	21	4'-4"	137	BT
TOTAL			834	

— REPLACEMENT STEEL —

RE501	1	5'-6"		ST.
RE601	1	6'-0"		ST.

GENERAL NOTES.

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS, DATED 9-1-57 TOGETHER WITH CURRENT REVISIONS THEREOF.

EXCAVATION QUANTITY: INCLUDES THE REMOVAL OF MATERIAL FROM TOP OF THE EXISTING GRADE TO THE BOTTOM OF THE FOOTING.

THE KEY UNDER THE FOOTER SHALL BE PLACED ON UNDISTURBED EARTH.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


RETAINING WALL
ALONG HIGH STREET
PLAN & ELEVATION
YOUNGSTOWN, MAHONING COUNTY
STA. 996+79.36 To STA. 997+75.18

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.H.	D.S.					


FED. RD.	STATE	PROJECT	
	OHIO		

312
492

MAH-18-17.20



— ELEVATION —



DETAIL OF RUSTICATION GROOVES

GENERAL NOTE:

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO, DEPARTMENT OF HIGHWAYS, DATED 9-1-57, TOGETHER WITH CURRENT REVISIONS THEREOF

EXCAVATION QUANTITY: INCLUDES THE REMOVAL OF MATERIAL BETWEEN THE SURFACE OF THE EXISTING GROUND LINE AND THE BOTTOM OF THE FOOTINGS.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL ALONG RAMP 'L'

YOUNGSTOWN, MAHONING COUNTY

STA. 6+28.88 To STA. 7+08.00

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	L.N.P.		D.S.	D.H.C.		

REINFORCING STEEL LIST

CURVE IV - RAMP "L"	
Dc	4° 00' 00"
Δ.	11° 21' 36"
R.	1432.39'
T.	142.47'
E.	7.07'
L.	248.00'
PCC.	STA. 5+99.47
PT.	STA. 8+83.47

IDENT.	Nº REQ'D	LENGTH	WEIGHT	SHP.
501	10	27'-6"	287	ST.
502	21	5'-1"	111	BT.
503	21	3'-7"	78	BT.
504	48	29'-8"	1486	ST.
505	35	32'-4"	1180	ST.
506	8	4'-8"	15	BT.
507	11	32'-0"	73	ST.
508	15	5'-4"	37	BT.
509	7	4'-10"	35	BT.
SER. OF 510	1 SET OF 11 BARS	VARIES 3'-10"to 8'-7" @ 5 3/8" INC.	71	ST
511	2	16'-0"	33	ST.
512	2	4'-9"	10	ST.
SER. OF 513	1 SET OF 10 BARS	VARIES 8'-6" to 13'-5" @ 6 1/2" INC.	114	ST.
514	2	23'-0"	48	ST.
515	2	12'-0"	25	ST.
SER. OF 516	1 SET OF 10 BARS	VARIES 13'-0" to 18'-0" @ 6 3/8" INC.	162	ST.
517	2	20'-0"	42	ST.
518	41	10'-0"	428	ST.
SER. OF 519	1 SET OF 10 BARS	VARIES 17'-6" to 22'-6" @ 6 3/8" INC.	209	ST.
520	2	18'-0"	39	ST.
521	2	6'-6"	14	ST.
SER. OF 522	1 SET OF 3 BARS	VARIES 21'-6" to 26'-6" @ 6" INC.	69	ST.
523	8	22'-6"	188	ST.
601	23	7'-8"	265	BT.
602	36	11'-10"	640	BT.
SER. OF 603	1 SET OF 21 BARS	VARIES 6'-10" to 11'-7" @ 2 5/8" INC.	291	BT.
SER. OF 604	1 SET OF 26 BARS	VARIES 5'-6" to 11'-0" @ 2 5/8" INC.	322	ST.
SER. OF 605	1 SET OF 26 BARS	VARIES 6'-1" to 11'-6" @ 2 5/8" INC.	343	ST.
SER. OF 606	1 SET OF 26 BARS	VARIES 11'-7" to 17'-1" @ 2 5/8" INC.	560	ST.
SER. OF 607	1 SET OF 9 BARS	VARIES 15'-7" to 16'-10" @ 2 5/8" INC.	218	ST.
608	19	16'-10"	480	ST.
701	23	8'-10"	415	BT.
702	38	14'-2"	1101	BT.
703	48	9'-10"	965	BT.
704	87	15'-4"	2726	BT
705	20	6'-9"	276	BT
706	51	8'-5"	860	BT
707	52	11'-3"	1196	ST
801	25	9'-11"	662	BT.
1001	26	12'-10"	1435	BT
1002	52	7'-10"	1752	BT
1003	54	11'-10"	2749	BT
TOTAL WEIGHT			22,010 #	

IDENT	Nº REQ'D	REPLACEMENT BARS LENGTH	SHP.
501	1	5'-6"	ST.
601	1	6'-0"	ST.
701	1	6'-3"	ST.
801	1	6'-6"	ST.
1001	1	7'-2"	ST.

NOTE: BAR SIZE IS INDICATED IN THE BAR IDENT. THE FIRST DIGIT WHERE THREE DIGITS ARE USED, AND THE FIRST TWO DIGITS WHERE FOUR ARE USED INDICATE THE BAR SIZE NUMBER. FOR EXAMPLE 701 IS A Nº 7 BAR AND 1014 IS A Nº 10 SIZE BAR.

FED. RD.	STATE	PROJECT	
	OHIO		

313/492


MAH.-18-17.20

WATERPROOFING TYPE "B" INCLUDED IN BRIDGE QUANTITIES

PREFORMED EXPANSION JOINT STRIP

FACE OF ABUTMENT

℄ ABUT Nº 2 BRG'S 64°08'34"



LOCATION & PILE PLAN

℄ RIDGE AVE.


SER: 603, 705, 706, 801, 1001, 1002, 1003

5'-11 to 10'-8"	SER. 603
5'-10"	705
7'-4"	706
9'-0"	801
11'-7"	1001
6'-8"	1002
10'-8"	1003


502	4'-6"	7"
503	3'-0"	7"
601	7'-0"	8"
701	8'-0"	10"
703	9'-0"	10"

2'-0"	6"	2'-0" 506
2'-1"	11"	2'-1" 508
2'-0"	8"	2'-0" 509


8"	10'-6"	8" 602
10"	12'-6"	10" 702
10"	13'-8"	10" 704




SECTION - A-A




SECTION - B-B




SECTION - C-C



SECTION D-D



SECTION - E-E



TYPICAL CONTRACTION JOINT

EXPANSION JOINT DETAILS

ESTIMATED PILE LENGTH = 20'

FOR SHEET PILING ANCHORAGE DETAIL SEE SHEET No. 316

~ ESTIMATED QUANTITES ~

ITEM	UNIT	DESCRIPTION	TOTAL
E-2	CU.YD.	UNCLASSIFIED EXCAVATION	475
E-7	SQ.FT.	STL. SHEET PILING, LEFT IN PLACE 32 lb/ft²	753
E-2	LUMP	COFFERDAMS, CRIBS & SHEETING	LUMP
S-1	CU.YD.	CLASS "E" CONCRETE FOOTINGS	198
S-1	CU.YD.	CLASS "E" CONCRETE WALL	179

ITEM	UNIT	DESCRIPTION	TOTAL
S-3	LIN.FT.	WATERPROOFING 12" PREMOLDED SEALING STRIP	65
S-4	LBS.	REINFORCING STEEL	22,010
S-9	SQ.FT.	1" PREFORMED EXPANSION JOINT FILLER	84
S-16	LUMP	FIRST TEST PILE	LUMP
S-18	LIN.FT.	12" CAST-IN-PLACE REINFORCED CONCRETE PILE	1100
S-29	CU.YD.	POROUS BACKFILL	153

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

DEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL ALONG RAMP "L"

YOUNGSTOWN, MAHONING COUNTY


STA. 6+28.88 To STA. 7+98.00

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.S.H.	L.A.P.		D.S.	D.H.C		


FED. RD.	STATE	PROJECT	
	OHIO		

MA H -18-17.20


314
492




ELEVATION



TYPICAL CONTRACTION JOINT



EXPANSION JOINT DETAIL



DETAIL OF RUSTICATION GROOVE

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


RETAINING WALL
ALONG HILKER ST.
PLAN & ELEVATION
YOUNGSTOWN, MAHONING COUNTY
STA. 996+79.36 To STA. 997+75.18


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.S.	LNP		D.S.			

FED. RD.	STATE	PROJECT	
	OHIO		

315/492

MA H - 18 - 17.20






— REINFORCING STEEL SCHEDULE —


MARK	NO REQD.	LENGTH	WEIGHT	SHAPE
501	8	19'-8"	164	ST.
502	30	5'-7"	112	BT.
503	33	5'-1"	175	BT.
504	1	18'-2"	19	BT
505	8	19'-10"	166	BT.
506	9	20'-4"	191	BT.
507	1	22'-0"	23	BT.
508	1	22'-8"	24	BT.
509	16	26'-2"	470	ST.
510	3	29'-6"	92	BT.
511	5	32'-5"	169	BT.
512	1	24'-0"	25	BT.
513	6	21'-6"	135	BT.
514	5	19'-10"	103	BT.
515	1	17'-8"	18	BT.
516	2	4'-3"	9	ST.
SERIES OF 517	1 SET OF 8 BARS	VARIES 6'-6 TO 11'-6 @ 8 3/4" INC.	75	ST.
518	4	10'-0"	42	ST.
SERIES OF 519	1 SET OF 7 BARS	VARIES 11'-8 TO 15'-4 @ 4 INC.	92	ST.
520	30	14'-2"	443	ST.
521	12	29'-0"	363	ST.
522	6	12'-10"	80	ST.
523	6	11'-6"	72	ST.
524	1	17'-11"	19	BT.
525	1	19'-6"	21	BT.
526	1	13'-9"	14	BT.
527	1	15'-6"	16	BT.
528	4	10'-10"	45	ST.
SERIES OF 529	1 SET OF 4 BARS	VARIES 5'-8 TO 6'-1 @ 1 3/8" INC.	33	ST.
530	2	11'-0"	23	ST.
531	1	18'-2"	19	BT.
532	1	17'-8"	18	BT.
533	2	21'-0"	44	ST.
534	2	13'-0"	27	ST.
535	10	14'-5"	150	ST.
536	8	32'-10"	274	ST.
537	7	22'-4"	163	ST.
538	30	10'-0"	313	ST.
601	88	6'-11"	915	BT.
SERIES OF 602	1 SET OF 15 BARS	VARIES 4'-8 TO 9'-6 2 1/8" INC.	160	ST.
SERIES OF 603	1 SET OF 7 BARS	VARIES 9'-9 TO 11'-9 @ 4" INC.	113	ST.
604	40	12'-4"	741	ST.
605	6	10'-10"	98	ST.
606	6	9'-6"	86	ST.
607	8	8'-10"	106	ST.
SERIES OF 608	1 SET OF 7 BARS	VARIES 5'-9 TO 6'-5 @ 7/8" INC.	63	ST.
701	82	6'-11"	1160	BT.
702	59	4'-7"	552	BT.
703	116	7'-4"	1738	BT.
		TOTAL	9,973	

— REPLACEMENT STL. —


RE 501	1	5'-6"		ST.
RE 601	1	6'-0"		ST.
RE 701	1	6'-3"		ST.




SECTION A-A




SECTION B-B




SECTION C-C



SECTION D-D




SECTION E-E




QUANTITIES TABLE

ITEM	UNIT	DESCRIPTION	TOTAL
E-2	CU. YDS	UNCLASSIFIED EXCAVATION	190
S-1	CU. YDS	CLASS "E" CONCRETE FOOTINGS	95
S-1	CU. YDS	CLASS "E" CONCRETE WALLS	117
S-3	LIN. FT	WATERPROOFING 12" × 1/2" PREMOLDED SEALING STRIPS	53
S-4	LBS	REINFORCING STEEL	9973
S-9	SQ FT	1" PREFORMED EXPANSION JOINT FILLER	29
S-29	CU. YDS	POROUS BACKFILL	69



LOCATION PLAN



GENERAL NOTES

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS, DATED 9-1-57 TOGETHER WITH CURRENT REVISIONS THEREOF.

EXCAVATION QUANTITY: INCLUDES THE REMOVAL OF MATERIAL BETWEEN THE EXISTING GROUND LINE AND THE BOTTOM OF THE FOOTING.

POROUS BACKFILL: 2 FT. THICK, FULL LENGTH OF RETAINING WALL SHALL EXTEND UP TO THE UNDERSIDE OF THE IMPERVIOUS MATERIAL.

THE KEY: UNDER THE FOOTER SHALL BE PLACED ON UNDISTURBED EARTH.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL
ALONG HILKER ST.
WALL SECTIONS
YOUNGSTOWN, MAHONING COUNTY
STA. 996+79.36 To STA. 997+75.18

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.S.	J.F.					

FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18-17.20

316
492


NOTES

DESIGN SPECIFICATIONS: THE WALL CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATION FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO, DEPARTMENT OF HIGHWAYS, DATED 9-1-57. TOGETHER WITH CURRENT REVISIONS THEREOF


LOCATION AND GEOMETRIC PLAN IS ON SHEET NO.




PARTIAL PLAN




SECTION "A-A"




PARTIAL ELEVATION




TYPICAL EXPANSION JOINT DETAILS





DETAIL OF SHEET PILING



TYPICAL CONTRACTION JOINT DETAILS

SCHEDULE OF QUANTITIES

ITEM NO.	UNIT	DESCRIPTION	QUANTITY
E-2	CU.YDS.	UNCLASSIFIED EXCAVATION	4,450
E-2	SQ.FT.	STL. SHEET PILING - LEFT-IN-PLACE 32 LBS PER SQ.FT. INCLUDES ANCHORS	3,186
E-2	LUMP	COFFERDAMS, CRIBS, & SHEETING	LUMP
S-1	CU.YDS.	CLASS 'E' CONCRETE - FOOTERS	748
S-1	CU.YDS.	CLASS 'E' CONCRETE - WALLS	804
S-3	LIN.FT.	WATERPROOFING 12" x ½" PREMOLDED SEALING STRIP	335
S-4	LBS	REINFORCING STEEL	135,171
S-9	SQ.FT.	1" PREFORMED EXPANSION JOINT FILLER	317
S-16	LUMP	FIRST TEST PILE	LUMP
S-18	LIN.FT.	12" CAST-IN-PLACE REINFORCED CONC. PILES	7050
S-29	CU.YDS.	POROUS BACKFILL	598

ESTIMATED PILE LENGTH 25'-0"

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL ALONG RAMP "N"

PLAN AND ELEVATION


YOUNGSTOWN MAHONING COUNTY
STA. 1025+66.53 TO STA. 1029+72.77

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.S.	D.S		DHC.			


FED. RD.	STATE	PROJECT	
	OHIO		

MAH.-18-17.20

317
492



PARTIAL PLAN



PARTIAL ELEVATION

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL ALONG RAMP "N" PLAN AND ELEVATION

YOUNGSTOWN MAHONING COUNTY
STA. 1025+66.53 TO STA. 1029+72.77

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DS	DS		DHC.			

FED. RD.	STATE	PROJECT	
	OHIO		

318
492

MAH.-18-17.20

DESIGN SECTION "BB"

DESIGN SECTION "CC"

6 SPACES @ 9'-6" = 57'-0"

59 SPACES @ 1'-0" = 59'-0"

60-701

5 SPACES @ 9'-0" = 45'-0"

53 SPACES @ 1'-0" = 53'-0"

54-702

MATCH LINE SHEET NO. 317

701 @ 1'-0"

702 @ 8"

DETAIL-A

FACE OF WALL

2-805

7-805 PER PILE SPACE

88-805 TOTAL BARS THIS SECTION

8-703

2-805

8-703 PER PILE SPACE

76-703 TOTAL THIS SECTION

4-703

12 SPACES @ 4'-9" = 57'-0"

33 PILES THIS SECTION

8 SPACES @ 5'-9" = 46'-0"

24 PILES THIS SECTION

STA 1029+72.77 END OF WALL

118'-11⅝" DEVELOPED LENGTH MEASURED ALONG FACE OF WALL

PARTIAL PLAN

CONTRACTION JOINT 30'-0" | CONTRACTION JOINT 30'-0" | EXPANSION JOINT 30'-0" | CONTRACTION JOINT 23'-11⅝" | EXPANSION JOINT

4" 22 SP. @ 1'-4" = 29'-4" SERIES 520 NS

¾" 23 SP. @ 1'-3" = 28'-9" SERIES 521 & 804 FS 11½"

& 1103 FS

11½" 23 SP. @ 1'-3" = 28'-9" 24-1104 FS ¾"

4" 22 SP. @ 1'-4" = 29'-4" SERIES 522 NS 4"

¾" 23 SP. @ 1'-3" = 28'-9" SERIES 523 & 804 FS 11½"

& 1103 FS

11½" 23 SP. @ 1'-3" = 28'-9" 24-1104 FS ¾"

4" 22 SP. @ 1'-4" = 29'-4" SERIES 524 NS 4"

22 SP @ 1'-4" = 29'-4" SERIES 602 & 1002 FS

1'-0" 21 SP. @ 1'-4" = 28'-0" 22-1003 FS 1'-0"

7¾" 6SP @ 1'-4" 8'-0" 3¾" 1'-0½" 10 SP. @ 1'-4" 13'-4" 7¾"

SERIES 526 NS SERIES 527 NS

6SP @ 1'-4" = 8'-0" 10 SP @ 1'-4" = 13'-4"

SERIES 528 FS SERIES 529 FS

17 SP @ 1'-4" = 22'-6" 18-1002 FS

1'-3¾" 16 SP @ 1'-4" 21'-4" 17-1003 FS 1'-3¾"

15'-0"

EL. 951.54 2-505 EL. 950.28 2-505 EL. 949.02 EL. 947.76 EL. 947.38 2-533 2-532 EL. 944.96 TOP OF CURTAIN WALL AT MARKET ST. ABUT.

SERIES 521 SERIES 523 SERIES 602 SERIES 528 SERIES 529

804 804

1104 1103 1104 1002 1002 1003 1003

24'-1¾" 11 SP. @ 2'-0" = 22'-0" 12-505 NS & FS

2'-0" 7 SPA. @ 4'-0" = 28'-0" RUSTICATION GROOVES

10⅞" 22'-0" 2'-0"

7 SPA. @ 4'-0" = 28'-0" RUSTICATION GROOVES

2'-0" 23'-0¾" 11 SP @ 2'-0" = 22'-0" 12-505 NS & FS

21'-7⅝" 21'-9⅛" 21'-4⅝"

7 SPA. @ 4'-0" = 28'-0" RUSTICATION GROOVES

5 SPA @ 4'-0" = 20'-0" RUSTICATION GROOVES

3'-11⅝" 9 SP @ 2'-0" = 18'-0" 10-525 NS & FS 18'-11½" 3'-2"

6-530 TOP 9-505 BOTTOM 12-510 6-530 TOP 9-530 BOTTOM 12-510 8-505 BOTTOM 5-530 TOP 11-510 5-531 TOP 8-531 BOTTOM

EL. 924.08

B B "C" "C"

TYPE B WATER-PROOFING-INCL. WITH BRIDGE QUANT. EL. 919.00 FOOTER FOR MARKET ST. ABUT. CURTAIN WALL OF ABUT. EL. 944.96 FACE OF ABUT.

EL. 922.83.

1" THICKNESS OF PREFORMED EXPANSION JOINT FILLER ½"

PARTIAL ELEVATION

DETAIL - "A"

7'-7" 13'-7" 11'-7" 13'-8" 6'-6" 12'-8" 12

1003 1002 1004 1003 1002 1001

¾" 1'-2"

10"	12'-6"	10" 703
11"	14'-2"	11" 805
1'-5"	15'-6"	1'-5" 1001

9'-10"		10" 701
8'-11"		10" 702
10'-8"		11" 803

SERIES 523 SERIES 522

505

804

1103

1104

24" LAP 6'-8" 24" LAP

7'-10" 1'-0" 5'-10"

701

530 510

10'-9" 8'-10" 5'-0" 3'-1" 3'-4"

7-805 PER 4'-9" PILE SPACE

12" CAST-IN-PLACE PILING DRIVEN TO 40T BEARING

7'-2" 4'-6" 1'-6" 14'-8"

11 SPACES @ 2'-0" = 22'-0"

SHEET PILING BETHLEHEM DP-1 OR EQUAL

1'-0" 2'-0" 1'-6" 1'-6"

SECTION "BB"

2'-0" OF IMPERVIOUS MAT'L OVER POROUS BACKFILL - TYPICAL

1'-0" MIN.

SERIES 602 SERIES 524

POROUS BACKFILL TYP. ¾"

TYP 12"

505

2'-0" LAP

1002

4"ϕ WEEP HOLES @ 10'-0"℄ SLOPE 3" FROM BACK TO FRONT.

11'-0" 5'-0" 2'-11" 5'-0"

1003

5'-1"

7'-0" 6"

2'-0"

11" 3" 3'-2"

702

530 505 510

8-703 PER 5'-9" PILE SPACE

12" CAST-IN-PLACE PILING DRIVEN TO 40T BEARING

1'-6" 6'-0" 4'-0" 1'-6"

13'-0"

SHEET PILING BETHLEHEM DP-1 OR EQUAL

SECTION "CC"

~ REINFORCING SCHEDULE ~

MARK	NO. REQ'D	LENGTH	WEIGHT	SHAPE
SERIES 501	1-SET OF 12	FROM 22'-0" TO 24'-0" INCR. OF 4⅜"	300	ST
SERIES 502	1-SET OF 11	FROM 25'-8" TO 26'-0" INCR. OF ⅜"	296	ST
SERIES 503	1-SET OF 12	FROM 3'-9" TO 7'-9" INCR. OF 4⅜"	72	ST
SERIES 504	1-SET OF 11	FROM 7'-5" TO 7'-9" INCR. OF ⅜"	87	ST
505	337	29'-8"	10,429	ST
506	2	27'-0"	56	ST
507	2	20'-0"	42	ST
508	2	14'-8"	30	ST
509	92	25'-1"	2407	ST
510	167	10'-0"	1742	ST
SERIES 511	1-SET OF 23	FROM 25'-1" TO 25'-8" INCR. OF ⅜"	609	ST
SERIES 512	1-SET OF 23	FROM 6'-6" TO 7'-2" INCR. OF ⅜"	164	ST
513	92	6'-7"	632	ST
SERIES 514	1-SET OF 23	FROM 24'-10" TO 26'-1" INCR. OF ⅝"	611	ST
SERIES 515	1-SET OF 23	FROM 6'-10" TO 8'-1" INCR. OF ⅝"	179	ST
SERIES 516	1-SET OF 23	FROM 23'-6" TO 24'-10" INCR. OF ¾"	580	ST
SERIES 517	1-SET OF 23	FROM 5'-6" TO 6'-10" INCR. OF ¾"	148	ST
SERIES 518	1-SET OF 23	FROM 2'-2" TO 23'-6" INCR. OF ¾"	546	ST
SERIES 519	1-SET OF 23	FROM 4'-2" TO 5'-6" INCR. OF ¾"	116	ST
SERIES 520	1-SET OF 23	FROM 22'-6" TO 23'-10" INCR. OF ⅜"	556	ST
SERIES 521	1-SET OF 24	FROM 10'-7" TO 11'-10" INCR. OF ⅝"	281	ST
SERIES 522	1-SET OF 23	FROM 21'-3" TO 22'-7" INCR. OF ¾"	526	ST
SERIES 523	1-SET OF 24	FROM 9'-4" TO 10'-7" INCR. OF ⅝"	250	ST
SERIES 524	1-SET OF 23	FROM 21'-6" TO 22'-10" INCR. OF ¾"	532	ST
525	20	23'-8"	495	ST
SERIES 526	1-SET OF 7	FROM 21'-1" TO 21'-6" INCR. OF ¾"	155	ST
SERIES 527	1-SET OF 11	FROM 16'-8" TO 21'-1" INCR. OF 2⅞"	228	ST
SERIES 528	1-SET OF 7	FROM 12'-7" TO 13'-0" INCR. OF ⅝"	94	ST
SERIES 529	1-SET OF 11	FROM 10'-2" TO 12'-7" INCR. OF 2⅞"	131	ST
530	156	32'-0"	5207	ST
531	13	26'-0"	353	ST
532	2	19'-0"	40	ST
533	2	9'-0"	19	ST
601	270	7'-0"	2840	ST
602	1-SET OF 23	FROM 13'-0" TO 14'-3" INCR. OF ⅝"	471	ST
701	60	10'-8"	1308	BT
702	54	9'-9"	1076	BT
703	76	14'-2"	2201	BT
801	270	8'-6"	6128	ST
802	270	13'-8"	9853	ST
803	294	11'-7"	9093	BT
804	48	6'-8"	801	ST
805	88	16'-0"	3760	BT
1001	360	18'-4"	28,400	BT
1002	41	14'-7"	2573	BT
1003	39	8'-7"	1441	BT
1101	270	13'-8	19605	BT
1102	270	7'-6"	10,759	BT
1103	48	14'-8"	3740	BT
1104	48	12'-7"	3209	BT
TOTAL REINFORCING STEEL			135171	

REPLACEMENT BARS

MARK	NO. REQ'D	LENGTH	SHAPE
RE501	2	5'-6"	ST
RE601	1	6'-0"	ST
RE701	1	6'-3"	ST
RE801	2	6'-6"	ST
RE1001	2	7'-2	ST
RE1101	2	7'-6"	ST

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL ALONG RAMP "N"

PLAN AND ELEVATION


YOUNGSTOWN MAHONING COUNTY
STA. 1025+66.53 TO STA. 1029+72.77

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.S.	D.S.		DHC.			

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

319
492



MAIN LINE CURVE DATA
Δ = 53° 49' 25"
R_c = 996.45'
L_c = 536.06'
D_c = 5° 45' 00"
L_s = 400'
T_s = 708.91
E_s = 128.31

CURVE DATA - RAMP "K"
Δ = 20°-15'-30"
R = 1,909.86
L = 675.00
T = 341.06
E = 30.21
D = 3°-00'-00"

ESTIMATED QUANTITIES

ITEM Nº	TOTAL	UNIT	DESCRIPTION
E-2	3990	C.Y.	UNCLASSIFIED EXCAVATION
S-1	496	"	CLASS "E" CONCRETE - FOOTINGS
S-1	528	"	" "E" " - ABOVE FOOTER
E-2	LUMP	LUMP	COFFERDAMS, CRIBS, & SHEETING
S-3	322	LIN.FT.	WATERPROOFING 12" ½" PREMOLDED SEALING STRIP
S-4	67267	LBS.	REINFORCING STEEL
S-9	176	SQ.FT.	1" PREFORMED EXP. JT. FILLER
S-16	LUMP	SUM	FIRST TEST PILE
S-18	2175	LIN.FT.	12" CAST-IN-PLACE REINFORCED CONCRETE PILE
S-18	411	LIN.FT.	CORRUGATED SHEET PILING
E-2	3240	SQ.FT.	STL. SHEET PILING, LEFT IN PLACE 32#/FT²

GENERAL NOTES:

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO, DEPARTMENT OF HIGHWAYS, DATED SEPTEMBER 1, 1957 TOGETHER WITH CURRENT REVISIONS THEREOF.

EXCAVATION QUANTITY: INCLUDES THE REMOVAL OF MATERIAL BETWEEN THE SURFACE OF THE EXISTING GROUND LINE AND THE BOTTOM OF THE FOOTINGS.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL
ALONG RAMP "K"
LOCATION PLAN
YOUNGSTOWN, MAHONING COUNTY
STA. 11+77.82 To STA. 15+81.00

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.S.A. R.H.	E.S.S.					

MAH-18-17.20

FED. RD.	STATE	PROJECT	
	OHIO		

320
492

BEGIN RETAINING WALL STA. 11+77.82

21" V.S.P. SEWER PIPE

8" WATER MAIN WITH 6" CONC. WALL

FRONT FACE OF WALL

227'-5⅜"- DIMENSION GIVEN AT FRONT FACE OF WALL

℄ PROFILE GRADE LINE OF RAMP "K"

END SECTION "C" & P.T. STA. 14+03.87

1" EXPANSION JT. SEE DETAIL THIS SHEET

9 SP. @ 5'-9" = 51'-9" FOR FRONT & MIDDLE ROW OF PILES

17 SP. @ 5'-9" = 97'-9" FRONT & MIDDLE ROW OF PILES

FOR CONTINUATION (STRAIGHT PORTION) OF WALL, SEE SH. #321

CONTRACTION JT.

SHEET PILING - BETHLEHEM SECTION DP-1 OR EQUAL. SEE DETAIL SH. 321

62'-6½"- SECTION "A"

60'-0"- SECTION "B"

104'-10⅞"- SECTION "C"

SPACING OF PILES AT REAR ROW

RUSTICATION GROOVE SPACING

BACK FACE OF WALL AT TOP OF FOOTER

LOCATION AND PILING PLAN OF RETAINING WALL

62'-6½"- SECTION A

22'-6½"	20'-0"	20'-0"
		22 SPACES @ APPROX. 10'-0" ℄ = 220'-0"
17 SP. @ 15" = 21'-3"	15 SP. @ 15" = 18'-9"	15 SP. @ 15" = 18'-9"
18-601 N.S.	16-602 N.S.	16-603 N.S.
16 SP. @ 16" = 21'-4"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"
17-504 F.S.	15-506 F.S.	15-509 F.S.
17 SP. @ 15" = 21'-3"	15 SP. @ 15" = 18'-9"	15 SP. @ 15" = 18'-9"
18-1101 N.S.	16-1101 N.S.	16-1101 N.S.
17 SP. @ 15" = 21'-3"	15 SP. @ 15" = 18'-9"	15 SP. @ 15" = 18'-9"
18-1102 N.S.	16-1102 N.S.	16-1102 N.S.

60'-0"- SECTION B

20'-0"	20'-0"	20'-0"	20'-0"
4" ₵ WEEPHOLES (JOINTS TO BE LEFT CLEAR)			
14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"
15-604 N.S.	15-604 N.S.	15-604 N.S.	15-605 N.S.
14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"
15-505 F.S.	15-505 F.S.	15-505 F.S.	15-510 F.S.
14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"
15-1001 N.S.	15-1001 N.S.	15-1001 N.S.	15-1001 N.S.
14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"
15-1002 N.S.	15-1002 N.S.	15-1002 N.S.	15-1002 N.S.

104'-10⅞"- SECTION C

20'-0"	20'-0"	24'-10⅞"	20'-0"	20'-0"
14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	18 SP. @ 16" = 24'-0"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"
15-606 N.S.	15-606 N.S.	19-607 N.S.	15-608 N.S.	15-609 N.S.
14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	18 SP. @ 16" = 24'-0"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"
15-511 F.S.	15-511 F.S.	19-512 F.S.	15-513 F.S.	15-514 F.S.
14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	17 SP. @ 16" = 22'-8"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"
15-1001 N.S.	15-1001 N.S.	18-1001 N.S.	15-1001 N.S.	15-1001 N.S.
14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"	18 SP. @ 16" = 24'-0"	14 SP. @ 16" = 18'-8"	14 SP. @ 16" = 18'-8"
15-1002 N.S.	15-1002 N.S.	19-1002 N.S.	15-1002 N.S.	15-1002 N.S.

EL. 961.62 — EL. 962.37 — EL. 965.12 — EL. 963.12 — EL. 962.51 — EL. 961.91 — EL. 961.16 — EL. 960.55 — EL. 959.94

TOP OF CURTAIN WALL EL. 959.03±

WOODLAND AVE. ABUT #2 - FOR PLAN, ELEVATION & DETAILS, SEE SH. #4 & 4

INV: EL. = 930.40

INV. ELEV. = 931.21

62'-6½" DEVELOPED LENGTH — EL. 935.92 — PILE CUT-OFF EL. 936.92

60'-0" DEVELOPED LENGTH — 227'-5⅜"- DEVELOPED LENGTH AT FACE OF WALL — EL. 937.42 — PILE CUT-OFF EL. 938.42

104'-10⅞"- DEVELOPED LENGTH — EL. 938.83 — PILE CUT-OFF EL. 939.83

FOR CONTINUATION = OF WALL, SEE SH. #321

REAR ELEVATION

SECTION C | SECTION D

4-532 TO LAP WITH 531

5-528 TOP

7-532 TO LAP WITH 531

EXPOSED FACE OR FRONT

12"x½" PREMOLDED SEALING STRIP IN 13"x¾" RECESS

1½"x5½" KEY-CENTERED IN WALL FULL HEIGHT

6" MIN.

DETAIL OF CONTRACTION JOINT

4-527 TOP LAP WITH 526

5-528 TOP

7-527 BOTTOM LAP WITH 526

5-530 TO LAP WITH 529 & 531

7-528 TOP

9-530 TO LAP WITH 529 & 531

EXPOSED FACE OR FRONT

1" THICKNESS OF PREFORMED EXPANSION JOINT FILLER

12"x½" PREMOLDED SEALING STRIP IN 13"x¾" RECESS. (TYP.)

WOODLAND AVE. ABUT. NO. 2

RETAINING WALL

6"x½" PREMOLDED SEALING STRIP IN 6"x¾" RECESS

EXPANSION JOINT DETAILS

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL ALONG RAMP "K" PLAN & ELEVATION

YOUNGSTOWN, MAHONING COUNTY
STA. 11+77.82 To STA. 15+81.00

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.S. & R.H.	E.S.S.					

FED. RD.	STATE	PROJECT	
	OHIO		

321
492

MAH-18-17.20

BEGIN SECTION "D" &
P.T. STA. 14+03.87

FRONT FACE OF WALL

177'-1⅞"

PROFILE GRADE LINE OF RAMP "K"

14+00

3'-3"

5 SP. @ 7'-6" = 37'-6"
FOR FRONT & MIDDLE ROW OF PILES

4'-9"

9 SP. @ 7'-0" = 63'-0"
FRONT ROW PILES

15+00

1'-6"

END RETAINING WALL
STA. 15+81

1" EXPANSION JT.

1" EXPANSION JT.

1" EXPANSION JT.

CONTRACTION JT.

CONTRACTION JT.

CONTRACTION JT.

CONTRACTION JT.

CONTRACTION JT.

FOR CONTINUATION (RADIAL PORTION) OF WALL, SEE SH.#320

ANCHORS - SEE DETAIL THIS SHEET

SHEET PILING - BETHLEHEM SECTION DP-1 OR EQUAL SEE DETAIL THIS SHEET

BACK FACE OF WALL AT TOP OF FOOTER

4 SP. @ 10'-0" = 40'-0"

5 SP. @ 12'-0" = 60'-0"

3'-0" SPACING OF PILES AT REAR ROW

5 SPA @ 4'-0" 20'-0" 20

3½" SPACING FOR RUSTICATION GROOVES

44'-0" - SECTION "D"

66'-0" - SECTION "E"

67'-1⅞" - SECTION "F"

LOCATION AND PILING PLAN OF RETAINING WALL

4" × 3" × 3'-2" ANCHOR

2'-8" o.c.

BACK FACE OF FOOTER

VOID

BETHLEHEM SECTION DP-1 OR EQUAL

DETAIL OF SHEET PILING

(SEE DETAIL SHEET 316)

44'-0" - SECTION D | 66'-0" - SECTION E | 67'-1⅞" - SECTION F

17 SPACES @ APPROX. 10'-0"% = 170'-0" - 4"ϕ WEEPHOLES (JOINTS TO BE LEFT CLEAR)

17-610 N.S. 16 SP. @ 16" = 21'-4"	17-611 N.S. 16 SP. @ 16" = 21'-4"	17-612 N.S. 16 SP. @ 16" = 21'-4"
17-515 F.S. 16 SP. @ 16" = 21'-4"	17-516 F.S. 16 SP. @ 16" = 21'-4"	17-518 F.S. 32 SP. @ 8" = 21'-4"
17-802 N.S.	17-802 N.S.	17-701 & 16-613 N.S.

17-614 N.S. 16 SP. @ 16" = 21'-4"	17-615 N.S. 16 SP. @ 16" = 21'-4"	17-616 N.S. 16 SP. @ 16" = 21'-4"
17-519 F.S. 32 SP. @ 8" = 21'-4"	17-520 F.S. 32 SP. @ 8" = 21'-4"	9-521 F.S. 32 SP. @ 8" = 21'-4"
17-701 & 16-613 N.S.	17-701 & 16-613 N.S.	17-702 & 16-617 N.S.

17-618 N.S. 8 SP. @ 32" = 21'-4"	18-619 N.S. 17 SP. @ 16" = 22'-8"	
9-522 F.S. 32 SP. @ 8" = 21'-4"	18-702 & 17-617 N.S. 8 SP. @ 32" = 21'-4"	9-523 F.S. 34 SP. @ 8" = 22'-8"
17-702 & 16-617 N.S.	17-702 & 16-617 N.S.	

EL. 959.94 | EL. 959.28 | EL. 958.61 | EL. 957.95 | EL. 957.28 | EL. 956.61 | EL. 955.95 | EL. 955.28 | EL. 954.58

FOR CONTINUATION OF WALL, SEE SH.#320

SERIES 610 N.S. | SERIES 611 N.S. | SERIES 612 N.S. | SERIES 614 N.S. | SERIES 615 N.S. | SERIES 616 N.S. | SERIES 618 N.S. | SERIES 619 N.S.

802 N.S. | 16-901 @ 16" N.S. | 701 & 613 | 702 & 617 N.S.

50 SP @ 16" = 66'-8" 51-525

44'-0" | 66'-0" | 67'-1⅞"

177'-1⅝"

EL. 941.54 | EL. 943.00 | EL. 944.94 | EL. 943.69 BOTTOM OF KEY

PILE CUT-OFF EL. 942.54 | PILE CUT-OFF EL. 944.00

REAR ELEVATION

3-530 TO LAP WITH 533

4-528

5-530 TO LAP WITH 533

3-535 TO LAP WITH 534

4-528

4-535 TO LAP WITH 534

DETAIL OF RUSTICATION GROOVE

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


RETAINING WALL
ALONG RAMP "K"
PLAN & ELEVATION
YOUNGSTOWN, MAHONING COUNTY
STA. 11+77.82 To STA. 15+81.00

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.H.	E.S.S.					


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


322
492




SECTION A-A




SECTION B-B




SECTION C-C



SECTION D-D



SECTION E-E



SECTION F-F

NOTE: ALL REINFORCING STEEL TO HAVE 2" MIN. COVER IN WALL & 3" MIN. COVER IN FOOTING UNLESS NOTED OTHERWISE.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL

ALONG RAMP K

WALL SECTIONS

YOUNGSTOWN, MAHONING COUNTY


STA. 11+77.82 To STA. 15-81.00

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.S. & R.H.	E.S.S.		ϕ.K.L.			


FED. RD.	STATE	PROJECT	
	OHIO		

MAH - 18 - 17.20


323
492



SECTION H-H



SECTION J-J




REINFORCING STEEL SCHEDULE


MARK	NO. OF BARS REQ'D	LENGTH	WEIGHT	SHAPE
501	2	22'-4"	48	ST.
502	212	19'-8"	4348	ST.
503	20	22'-2"	462	ST.
SERIES 504	1 SET OF 17 BARS	FROM 19'-1" TO 22'-2" INCR. OF 13/16"	370	ST
505	45	22'-4"	1048	ST
SERIES 506	1 SET OF 15 BARS	FROM 22'-2" TO 22'-11" INCR. OF 5/16"	353	ST
507	22	24'-6"	562	ST
508	2	15'-0"	81	ST
SERIES 509	1 SET OF 15 BARS	FROM 22'-11" TO 23'-8" INCR OF 5/16"	364	ST
SERIES 510	1 SET OF 15 BARS	FROM 20'-11" TO 20'-4" INCR OF 1/2"	323	ST
SERIES 511	1 SET OF 15 BARS	FROM 20'-4" TO 19'-9" INCR OF 1/2"	313	ST
SERIES 512	1 SET OF 19 BARS	FROM 19'-9" TO 19'-0" INCR OF 1/2"	383	ST
SERIES 513	1 SET OF 15 BARS	FROM 18'-11" TO 18'-4" INCR OF 1/2"	292	ST
SERIES 514	1 SET OF 15 BARS	FROM 18'-4" TO 17'-9" INCR OF 1/2"	282	ST.
SERIES 515	1 SET OF 17 BARS	FROM 15'-2" TO 14'-6" INCR OF 1/2"	263	ST
SERIES 516	1 SET OF 17 BARS	FROM 14'-6" TO 13'-10" INCR OF 1/2"	252	ST
517	98	21'-8"	2215	ST
SERIES 518	1 SET OF 17 BARS	FROM 12'-9" TO 12'-1" INCR OF 1/2"	220	ST
SERIES 519	1 SET OF 17 BARS	FROM 12'-1" TO 11'-5" INCR OF 1/2"	208	ST.
SERIES 520	1 SET OF 17 BARS	FROM 11'-5" TO 10'-9" INCR. OF 1/2"	196	ST.
SERIES 521	1 SET OF 9 BARS	FROM 9'-0" TO 8'-4" INCR OF 1"	81	ST
SERIES 522	1 SET OF 9 BARS	FROM 8'-4" TO 7'-8" INCR OF 1"	75	ST


MARK	NO. OF BARS REQ'D	LENGTH	WEIGHT	SHAPE
SERIES 523	1 SET OF 9 BARS	FROM 7'-8" TO 7'-0" INCR. OF 1"	69	ST.
524	8	22'-9"	190	ST.
526	51	3'-7"	191	BT.
526	28	32'-4"	944	ST.
527	11	6'-5"	76	BT.
528	158	10'-0"	1648	ST.
529	28	31'-0"	905	ST.
530	22	6'-4"	145	BT.
531	42	36'-0"	1577	ST.
532	11	8'-1"	93	BT.
533	22	22'-8"	520	ST.
534	20	33'-8"	702	ST.
535	7	5'-7"	41	BT.
536	14	34'-2"	499	ST.
537	52	5'-1"	276	BT.
SERIES 601	1 SET OF 18 BARS	FROM 6'-5" TO 9'-0" INCR. OF 19/16	208	ST
SERIES 602	1 SET OF 16 BARS	FROM 9'-0" TO 9'-9" INCR OF 5/16"	225	ST.
SERIES 603	1 SET OF 16 BARS	FROM 9'-9" TO 10'-6" INCR OF 5/16"	248	ST.
604	45	13'-7"	918	ST.
SERIES 605	1 SET OF 15 BARS	FROM 12'-2" TO 11'-7" INCR OF 1/2"	268	ST.
SERIES 606	1 SET OF 15 BARS	FROM 11'-7" TO 11'-0" INCR OF 1/2"	254	ST
SERIES 607	1 SET OF 19 BARS	FROM 11'-0" TO 10'-3" INCR OF 1/2"	303	ST.
SERIES 608	1 SET OF 15 BARS	FROM 10'-3" TO 9'-8" INCR OF 1/2"	224	ST.
SERIES 609	1 SET OF 15 BARS	FROM 9'-7" TO 9'-0" INCR. OF 1/2"	210	ST.


MARK	NO. OF BARS REQ'D	LENGTH	WEIGHT	SHAPE
SERIES 610	1 SET OF 17 BARS	FROM 9'-6" TO 8'-10" INCR OF 1/2"	234	ST
SERIES 611	1 SET OF 17 BARS	FROM 8'-10" TO 8'-2" INCR OF 1/2"	217	ST
SERIES 612	1 SET OF 17 BARS	FROM 11'-0" TO 10'-4" INCR OF 1/2"	272	ST.
613	48	7'-3"	523	BT
SERIES 614	1 SET OF 17 BARS	FROM 10'-4" TO 9'-8" INCR OF 1/2"	255	ST
SERIES 615	1 SET OF 17 BARS	FROM 9'-8" TO 9'-1" INCR OF 1/2"	238	ST
SERIES 616	1 SET OF 17 BARS	FROM 7'-3" TO 6'-7" INCR OF 1/2"	177	ST
617	49	7'-0"	515	BT
SERIES 618	1 SET OF 17 BARS	FROM 6'-7" TO 5'-11" INCR OF 1/2"	160	ST
SERIES 619	1 SET OF 18 BARS	FROM 5'-11" TO 5'-3" INCR OF 1/2"	151	ST.
620	33	7'-8"	380	BT
621	52	11'-8"	911	BT.
622	50	6'-5"	482	BT.
701	51	7'-3"	756	BT.
702	52	7'-0"	744	BT.
703	68	10'-10"	1395	BT.
704	124	9'-0"	2281	BT.
705	226	14'-2"	6645	BT.
706	47	9'-10"	944	BT.
801	50	6'-9"	901	ST.
802	34	11'-6"	1044	BT.


MARK	NO. OF BARS REQ'D	LENGTH	WEIGHT	SHAPE
803	94	16'-4"	4098	BT.
901	32	8'-6"	925	BT.
1001	123	10'-6"	5557	BT.
1002	124	14'-9"	7870	BT.
1101	50	11'-10"	3143	BT
1102	50	14'-7"	3873	BT.
			68,009	














STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL
ALONG RAMP "K"
REINFORCING SCHEDULE
YOUNGSTOWN, MAHONING COUNTY
STA. 11+77.82 To STA. 15+81.00

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.R.L. R.M.J.	E.S.S.					

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

324
4.92

MATCH LINE II-II, SHEET #325

30'-0"

32 SPA. @ 11" = 29'-4" 33-805 TOP

90'-2¼"

97 SPA. @ 11" = 88'-11" 98-805 TOP

5¾" 2⅛" 7½" 7⅝"

511 BOTT — SHEET PILING — 511 TOP — 511 TOP — 511 BOTT — 511 TOP — 524 BOTT — 524 TOP

ROW #3 — 5'-3" — 3'-9" — ROW #2 — ROW #1

2-1001 — 2-1001 — 2-1001 — 2-1001

4-1001 PER PILE SPACE - (TYP)

2½" 2½" 2½"

40-1001 BOTT

4-1001 PER PILE SPACE - (TYP)

120-1001 BOTT

FACE OF WALL

2-1001

PARTIAL FOOTER PLAN

CONTRACTION JOINT 30'-0" — EXPANSION JOINT 30'-0" — CONTRACTION JOINT 30'-0" — CONTRACTION JOINT 20'-0" — 10'-2¼"

1'-6" 1'-6" 6" 2" 2'-6" 2½"

9 SPA. @ 3'-0" = 27'-0" SER. 523 NS. — 9 SPA. @ 3'-0" = 27'-0" SER. 526 NS. — 9 SPA. @ 3'-0" = 27'-0" 10-528 NS. — 6 SPA. @ 3'-0" = 18'-0" 7-528 NS.

22 SPA. @ 16" = 29'-4" 23-522 FS. — 22 SPA. @ 16" = 29'-4" 23-525 FS. — 22 SPA. @ 16" = 29'-4" 23-527 FS. — 14 SPA. @ 16" = 18'-8" 15-527 FS

3 SPA @ 3'-0" = 6'-0" SER 530 NS. — 6 SPA @ 16" = 8'-0" SER. 529 FS.

1'-8¼" 1'-10½" K

EL. 957.00 — H — EL. 956.50 — J — EL. 956.00 — EL. 956.00 — EL. 956.00

534 NS & FS — 533 NS & FS — 532 NS & FS

EL. 950.62 EL. OF CURTAIN WALL ON MARKET ST ABUT.

29 SPA @ 12" = 29'-0" FS 30-604 — 29 SPA @ 12" = 29'-0" FS 30-604 — 29 SPA @ 12" = 29'-0" FS 30-604 — 29 SPA @ 12" = 29'-0" FS 30-604

7 SPA @ 4'-0" = 28'-0" RUSTICATION GROOVES — 7 SPA @ 4'-0" = 28'-0" RUSTICATION GROOVES — 7 SPA @ 4'-0" = 28'-0" RUSTICATION GROOVES — 7 SPA @ 4'-0" = 28'-0" RUSTICATION GROOVES

58 SPA @ 6" = 29'-0" FS 30-806 @ 12" ALT/W 29-807 @ 12" — 58 SPA @ 6" = 29'-0" FS 30-806 @ 12" ALT/W 29-807 @ 12" — 58 SPA @ 6" = 29'-0" FS 30-806 @ 12" ALT/W 29-807 @ 12" — 59 SPA @ 6" = 29'-6" FS 30-806 @ 12" ALT/W 30-807 @ 12"

504 NS & FS — 504 NS & FS — 531 NS & FS

TYPICAL SPACING FOR ALL 30'-0" SECTIONS

5'-0" 10'-0" 10'-0" 5'-0"

4" ϕ WEEP HOLES

24'-5⅜" 23'-11⅜" 26'-1⅜" 25'-7⅜" 20'-2¾" 8¼" 2'-2¾" 4⅛"

EL. 928.90 — 3'-8" — 9-539 — 10-535 — 9-535 — 10-535 — 9-535 — 10-535 — 3'-8" — EL. 926.73

MATCH LINE II-II SHEET #325

H — H — J — J — 1'-8¼" — 4'-8¼" — K

9 SPA @ 3'-0" = 27'-0" ROW #1 & 2 - 20 PILES

4 SPA @ 6'-0" = 24'-0" ROW #3, 5 PILES

29 SPA @ 3'-0" = 87'-0" ROW #1 & 2 60 PILES

14 SPA @ 6'-0" = 84'-0" ROW #3 15 PILES

120'-2¼" DEVELOPED LENGTH. MEASURED ALONG FACE OF WALL

- PARTIAL ELEVATION -

ESTIMATED PILE LENGTH = 25'-0"

— QUANTITIES TABLE —

ITEM NO	UNIT	DESCRIPTION	QUANTITY	ITEM NO	UNIT	DESCRIPTION	QUANTITY
E-2	CU. YDS.	UNCLASSIFIED EXCAVATION	3,296	S-9	SQ. FT.	1" PREFORMED EXPANSION JOINT FILLER	209
E-2	SQ. FT.	STL. SHEET PILING, LEFT-IN-PLACE 32# PER SQ. FT. INCLUDING ANCHORS.	2733				
E-2	LUMP	COFFERDAMS, CRIBS & SHEETING	LUMP	S-16	LUMP	FIRST TEST PILE	LUMP
S-1	CU. YDS.	CLASS "E" CONCRETE, FOOTERS	641				
S-1	CU. YDS.	CLASS "E" CONCRETE, WALLS	603	S-18	LIN. FT.	12" CAST-IN-PLACE REINFORCED CONCRETE PILE	5525
S-3	LIN. FT.	WATERPROOFING PREMOLDED SEALING STRIP 12" x ½"	249				
S-4	LBS.	REINFORCING STEEL	99,271	S-29	CU. YDS.	POROUS BACKFILL	610

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RETAINING WALL ALONG RAMP "M"

PLAN & ELEVATION

YOUNGSTOWN, MAHONING COUNTY

STA. 5+83.03 To STA. 9+07.87

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH F D.S.	LNP		D.S.			

FED RD.	STATE	PROJECT	
	OHIO		

MAH - 18 - 17.20

325
492

MATCH LINE II-II SHEET #326

30'-0" | 29 SPA @ 1'-0" = 29'-0" | 30-701 TOP

60'-0" | 59 SPA @ 1'-0" = 59'-0" | 60-701 TOP

30'-0" | 32 SPA @ 11" = 29'-4" | 33-805 TOP

MATCH LINE II-II SHEET #324

SHEET PILING

511 BOTT

511 TOP

511 TOP

511 BOTT

511 BOTT

511 TOP

511 TOP

511 BOTT

ROW #3

ROW #2

ROW #1

7'-2"

4'-6"

1'-6"

FACE OF WALL

2-803

2-803

2-803

2-1001

2-1001

FRONT FACE OF WALL

7-803 PER PILE SPACE. (TYPICAL)

44-803 BOTT.

7-803 PER PILE SPACE - (TYP)

88-803 BOTT.

4-1001 PER PILE SPACE. (TYP)

40-1001 BOTT.

PARTIAL FOOTER PLAN

℄ CONTRACTION JT. 30'-0" | 9 SPA @ 3'-0" = 27'-0" SER-515 NS | 23 SPA @ 15" = 28'-9" 24-514 FS

℄ CONTRACTION JT. 30'-0" | 9 SPA @ 3'-0" = 27'-0" SER-517 NS | 23 SPA @ 15" = 28'-9" 24-516 FS

℄ EXPANSION JT. 30'-0" | 9 SPA @ 3'-0" = 27'-0" SER-519 NS | 23 SPA @ 15" = 28'-9" 24-518 FS

℄ CONTRACTION JT. 30'-0" | 9 SPA @ 3'-0" = 27'-0" SER-521 NS | 22 SPA @ 16" = 29'-4" 520 FS

℄ CONTR. JOINT

EL. 959.00

EL. 958.50

EL. 958.00

EL. 957.50

EL. 957.00

D

E

F

G

504 NS & FS

504 NS & FS

504 NS & FS

504 NS & FS

22-1 3/16"

21-7 3/16"

24-2 3/16"

23-8 3/16"

23-2 3/16"

24-5 3/16"

24-11 3/16"

7½"

23 SPA @ 15" = 28'-9" 24-804 FS

7 SPA @ 4'-0" = 28'-0" RUSTICATION GROOVES

2'-0"

46 SPA @ 7½" = 28'-9" FS
24-1101 @ 15" ALT/W 23-1102 @ 15"

29 SPA @ 12" = 29'-0" FS.
30'-604

58 SPA @ 6" = 29'-0" FS.
30-806 @ 12" ALT/W. 29-807 @ 12"

58 SPA @ 6" = 29'-0" FS
30-1103 @ 12" ALT/W 29-1104 @ 12"

EL. 933.50

EL. 931.02

EL. 928.90

10-537

6-535

10-535

6-535

10-538

6-535

9-535

10-535

3'-4"

3'-8"

6 SPA @ 4'-9" = 28'-6" ROW #1 & #2, 14 PILES
3 SPA @ 9'-6" = 28'-6" ROW #3, 4 PILES

12 SPA @ 4'-9" = 57'-0" ROW #1 & #2 26 PILES
6 SPA @ 9'-6" = 57'-0 ROW #3, 7 PILES

9 SPA @ 3'-0" = 27'-0" ROW #1 & #2 20 PILES
4 SPA @ 6'-0" = 24'-0" ROW #3, 5 PILES

120'-0" DEVELOPED LENGTH, MEASURED ALONG FACE OF WALL

MATCH LINE II-II SHEET #326

MATCH LINE II-II SHEET #324

PARTIAL ELEVATION

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

SWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


RETAINING WALL
ALONG RAMP "M"
PLAN & ELEVATION
YOUNGSTOWN, MAHONING COUNTY
STA. 5+83.03 To STA. 9+07.87

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH & DS	JNP		DS.			


FED. RD.	STATE	PROJECT	
	OHIO		

326
492


MAH-18-17.20



PARTIAL FOOTER PLAN




TYPICAL CONTRACTION JOINT



TYPICAL EXPANSION JOINT

PARTIAL ELEVATION

DETAIL OF SHEET PILING



LOCATION PLAN

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


RETAINING WALL
ALONG RAMP "M"
PLAN & ELEVATION
YOUNGSTOWN, MAHONING COUNTY
STA. 5 + 83.03 To STA. 9 + 07.87

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH & D.S.	JNP		D.S.			


FED. RD.	STATE	PROJECT	
	OHIO		

327
492


MAH -18-17.20



SECTION A-A




SECTION B-B




SECTION C-C & D-D

FOR BAR NOS., DIMENSIONS & NOTES NOT SHOWN, SEE SECTION B-B




SECTION E-E & F-F

FOR BAR Nos., DIMENSIONS & NOTES NOT SHOWN, SEE SECTION C-C




SECTION G-G & H-H



SECTION J-J

FOR BAR Nos., DIMENSIONS & NOTES NOT SHOWN, SEE SECTION, G-G & H-H





SECTION K-K


FOR BAR Nos., DIMENSIONS, & NOTES NOT SHOWN, SEE SECTION, G-G & H-H


REINFORCING STEEL LIST


MARK	No REQD.	LENGTH	WT.	SHAPE
501	12	22'-11"	287	ST.
SER OF 502	1 SET OF 9 BARS	VARIES 2'-6 TO 8'-2 @ 8 INC.	50	ST
SER OF 503	2 SETS OF 5 + 10 BARS	VARIES 2'-6 TO 18'-6 @ 4'-0 INC	110	ST.
504	246	29'-8"	7613	ST
SER OF 505	1 SET OF 16 BARS	VARIES 8'-6 TO 9'-5 @ ¾ INC	150	ST
SER OF 506	1 SET OF 7 BARS	VARIES 5'-6 TO 9'-0 @ 6⅝ INC.	57	ST
SER OF 507	1 SET OF 16 BARS	VARIES 20'-8 TO 21'-6 @ ¾ INC.	352	ST
SER OF 508	1 SET OF 7 BARS	VARIES 17'-7 TO 21'-1 @ 7 INC.	141	ST
509	2	28'-9"	60	ST.
510	2	24'-6"	51	ST
511	112	30'-10"	3601	ST
SER OF 512	1 SET OF 24 BARS	VARIES 9'-8 TO 11'-0 @ 1⅛ INC.	259	ST
SER OF 513	1 SET OF 10 BARS	VARIES 21'-11" TO 22'-5 @ ⅝ INC	231	ST.
514	24	9'-8"	242	ST
SER OF 515	1 SET OF 10 BARS	VARIES 21'-5 TO 21'-11 @ ⅝ INC.	226	ST
516	24	11'-9"	294	ST.
SER OF 517	1 SET OF 10 BARS	VARIES 23'-5 TO 24'-0 @ ¾ INC.	247	ST.
518	24	11'-3"	282	ST
SER OF 519	1 SET OF 10 BARS	VARIES 22'-11 TO 23'-5 @ ⅝ INC.	242	ST
520	23	6'-9"	162	ST
SER OF 521	1 SET OF 10 BARS	VARIES 24'-2 TO 24'-8 @ ⅝ INC.	255	ST
522	23	6'-3"	150	ST.
SER OF 523	1 SET OF 10 BARS	VARIES 23'-8 TO 24'-2 @ ⅝ INC.	249	ST.
524	16	31'-3"	522	ST
525	23	7'-9"	186	ST.
SER OF 526	1 SET OF 10 BARS	VARIES 25'-4 TO 25'-10 @ ⅝ INC.	267	ST
527	38	7'-3"	287	ST
528	17	25'-4"	449	ST
SER OF 529	1 SET OF 7 BARS	VARIES 2'-9 TO 7'-0 @ 8½ INC.	35	ST
SER OF 530	1 SET OF 3 BARS	VARIES 20'-6 TO 23'-7 @ 18½ INC	69	ST
531	20	29'-10"	622	ST
532	2	27'-6"	57	ST
533	2	23'-6"	49	ST
534	2	19'-9"	41	ST
535	123	10'-0"	1283	ST
536	6	11'-9"	74	BT
537	20	12'-1"	252	BT
538	10	11'-11"	124	BT.
539	9	12'-1"	113	BT.
SER OF 540	1 SET OF 5 BARS	VARIES 7'-5 TO 10'-3 @ 8½ INC.	46	BT.
SER OF 541	1 SET OF 8 BARS	VARIES 3'-10 TO 15'-10 @ 1'-8⅜ INC.	82	ST.
542	2	5'-0"	14	ST.
543	3	16'-6"	52	ST.
544	2	20'-0"	42	ST.
601	20	11'-8"	351	BT
602	12	7'-8"	138	BT.
SER OF 603	1 SET OF 4 BARS	VARIES 10'-11 TO 13'-1 @ 8½ INC.	72	BT
604	150	7'-0"	1577	ST
605	29	9'-4"	406	BT.
606	6	5'-10"	53	BT.
SER OF 607	1 SET OF 9 BARS	VARIES 8'-0 TO 11'-8 @ 5⅛ INC.	133	BT.
701	120	12'-4"	3024	BT.
702	23	6'-9"	317	ST.
703	46	14'-6"	1363	BT.
801	9	11'-4"	272	BT.
802	OPEN			
803	176	16'-4"	7674	BT.
804	96	6'-3"	1602	ST
805	164	12'-7"	5509	BT.
806	150	8'-6"	3404	ST.
807	146	13'-8"	5329	ST.
901	8	8'-4"	227	BT.
1001	200	18'-4"	15,775	BT.
1002	23	13'-8"	1353	BT.
1003	22	8'-6"	805	BT.
1101	96	14'-5"	7355	BT
1102	92	12'-6"	6110	BT
1103	150	13'-6"	10759	BT.
1104	146	7'-4"	5686	BT.
TOTAL WEIGHT			99,271	











REPLACEMENT STEEL

MARK	No REQD.	LENGTH	WEIGHT	SHAPE
RE-501	2	5'-6"		ST.
RE-601	1	6'-0"		ST
RE-701	1	6'-3"		ST
RE-801	2	6'-6"		ST.
RE-901	1	6'-10"		ST
RE-1001	1	7'-2"		ST
RE-1101	2	7'-6"		ST.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


RETAINING WALL
ALONG RAMP 'M'
WALL SECTIONS & REINFORCING SCHEDULE
YOUNGSTOWN, MAHONING COUNTY
STA. 5+83.03 To STA. 9+07.87

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH & DS	JNF		DS.			


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


328
49




EDWARDS STREET




MILL CREEK POND




EAST APPROACH - WOODLAND AVE.




MAHONING AVE.




RENNER BREWERY BY-PASS




OAK HILL AVE.




RIDGE AVE.



SILLIMAN ST. - (RAMP "C")



GLENWOOD AVE.



MARKET STREET

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

APPROACH SLAB DETAILS YOUNGSTOWN, MAHONING COUNTY


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED

APPROACH SLAB DETAILS

FED. RD.	STATE	PROJECT	
	OHIO		

54
492


MAH-18-17.20




TYPICAL SIDEWALK SECTION AT ABUTMENTS


STEEL STREET APPROACH SLABS

N







SECTION A-A



SECTION B-B



SECTION C-C



AS-803

270 SQ. YDS. GLASS "C" CONCRETE

98-1"ϕ x 1'-6" DOWELS = 392#

REINFORCING STEEL SCHEDULE

MARK	NO. REQD.	LENGTH	WEIGHT	SHP
AS-501	59	25'-0"	1534	ST
SERIES OF AS-502	1 SET OF 6 BARS	VARY FROM 25'-4" TO 28'-10" IN INC. OF 7"	169	ST
SERIES OF AS-503	1 SET OF 3 BARS	VARY FROM 25'-6" TO 26'-3" IN INC. OF 3"	81	ST
AS-801	10	6'-0"	160	ST
AS-802	3	4'-6"	36	ST
AS-803	198	25'-9"	13,693	ST
		TOTAL =	15,673#	

NOTE.
BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT INDICATES THE BAR SIZE NUMBER. FOR EXAMPLE AS-801 IS A NO.8 SIZE BAR.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


STEEL STREET APPROACH SLABS YOUNGSTOWN, MAHONING COUNTY

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JLH					

FED. RD.	STATE	PROJECT	
	OHIO		


330
492

MAH-18-17.20




PLAN


PLAN OF APPROACH SLAB FOR WEST ABUTMENT OF MILL CREEK POND STRUCTURE, SOUTH HALF ONLY IS SHOWN



SECTION A-A



SECTION B-B



SECTION C-C


REINFORCING BAR SCHEDULE

MARK NO.	NO. REQD	LENGTH	WEIGHT	SHAPE
AS 501	21	24'-0"	526	ST.
AS 502	21	VARIES 15'-5" TO 16'-1" INC. OF 1"	334	ST.
AS 801	27	25'-9"	1856	BT.
AS 802	23	26'-1"	1602	BT.
AS 803	22	26'-4"	1547	BT.
AS 804	1	23'-0"	61	ST
AS 805	1	12'-6"	33	ST.
AS 806	1	5'-0"	14	ST.
AS 807	4	26'-9"	286	BT.

TOTAL WEIGHT 6259

109 SQ YDS CLASS "C" CONCRETE
39-1"ϕ x 1'-6" DOWELS = 156 #

NOTE:
BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT INDICATES THE BAR SIZE NUMBER. FOR EXAMPLE, AS 801 IS A NO. 8 SIZE BAR.



STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


MILL-CREEK POND APPROACH SLAB
YOUNGSTOWN,
MAHONING COUNTY

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED


FED. RD.	STATE	PROJECT	
	OHIO		

MAH - 18 - 17.20


331
492




NORTH APPROACH SLAB
WESTBOUND LANES




SECTION A-A




SECTION B-B



SECTION C-C




SECTION D-D



SECTION E-E

REINFORCING STEEL SCHEDULE				
MARK	NO. REQD.	LENGTH	WEIGHT	SHP
SERIES OF AS-501	1 SET OF 5 BARS	VARY FROM 19'-11" TO 7'-0" IN INC. 3-2¾	70	ST
SERIES OF AS-502	1 SET OF 5 BARS	VARY FROM 24'-6 TO 23'-11" IN INC. OF 1¾	126	ST
AS-503	6	23'-8"	149	ST
SERIES OF AS-504	1 SET OF 6 BARS	VARY FROM 20'-3 TO 3'-2" IN INC. OF 3'-5	73	ST
AS-505	1	25'-10"	27	ST
AS-506	1	23'-6"	24	ST
AS-507	1	5'-7	6	BT
SERIES OF AS-801	2 SETS OF 6 BARS	VARY FROM 26'-10 TO 24'-2" IN INC. OF 1¾	425	BT
SERIES OF AS-802	1 SET OF 6 BARS	VARY FROM 26'-4 TO 25'-8" IN INC. OF 1¾	417	BT
AS-803	4	15'-9"	168	ST
AS-804	40	25'-9"	2750	BT

TOTAL REINFORCING STEEL = 4,230#
TOTAL CLASS "C" CONCRETE = 80 SQ.YDS.
TOTAL 1¼ x 1'-6" DOWELS = 104#



AS-507

NOTE:
BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT INDICATES THE BAR SIZE NUMBER. FOR EXAMPLE AS-803 IS A NUMBER 8 SIZE BAR.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


OAK-HILL AVENUE APPROACH SLABS YOUNGSTOWN, MAHONING COUNTY

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DC	JLH					


FED. RD.	STATE	PROJECT	
	OHIO		

331-A
492


MAH-18-17.20




PLAN OF APPROACH SLAB AT ABUTMENT # 2




SECTION A-A



SECTION-B





SECTION-C




SECTION-D

MARK	RAD.	L.
AS-505	24'-9"	11'-0"
AS-506	26'-3"	11'-8"
AS-507	27'-9"	12'-4"
AS-508	24'-9"	11'-10"
AS-509	26'-3"	12'-7"
AS-510	27'-9"	13'-6"







263 SQ. YDS. CLASS "C" CONCRETE
104 - 1 1/4" x 1'-6" DOWELS = 417 #

REINFORCING STEEL SCHEDULE

MARK	NO.	LENGTH	WEIGHT	SHAPE
AS-501	35	36'-0"	1314	ST.
SERIES OF AS-502	1-SET OF 6	VARY FROM 4'-6" TO 6'-4 3/4" INCR. 4 3/4"	34	ST.
SERIES OF AS-503	1-SET OF 10	VARY FROM 17'-7" TO 20'-5 3/8" INCR. 1'-2 3/8"	148	ST.
AS-504	1	18'-9"	20	ST.
AS-505	1	11'-0"	11	BT.
AS-506	1	11'-8"	12	BT.
AS-507	1	12'-4"	13	BT.
AS-508	1	11'-10"	12	BT.
AS-509	1	12'-7"	13	BT.
AS-510	1	13'-6"	14	BT.
AS-511	2	27'-6"	57	ST.
SERIES OF AS-512	1-SET OF 6	VARY FROM 20'-6" TO 21'-9" INCR. 3"	132	ST.
SERIES OF AS-513	1-SET OF 12	VARY FROM 22'-6" TO 30'-9" INCR. 9"	334	ST.
AS-801	52	20'-1"	2788	BT.
SERIES OF AS-802	1-SET OF 23	VARY FROM 22'-10" TO 23'-0 3/4" INCR. 1/8"	1410	BT.
SERIES OF AS-803	1-SET OF 3	VARY FROM 20'-0" TO 23'-0" INCR. 1'-0"	168	BT.
SERIES OF AS-804	1-SET OF 25	VARY FROM 5'-1" TO 20'-1" INCR. 7 1/2"	840	BT.
AS-805	1	26'-9"	71	BT.
AS-806	8	8'-0"	171	ST.
SERIES OF AS-807	1-SET OF 22	VARY FROM 22'-10" TO 23'-0 3/8" INCR. 1/8"	1348	BT.
SERIES OF AS-808	1-SET OF 3	VARY FROM 21'-8" TO 23'-0" INCR. 11"	177	BT.
AS-809	86	23'-1"	5300	BT.
SERIES OF AS-810	1-SET OF 17	VARY FROM 7'-0" TO 23'-0" INCR 1'-0"	601	BT.
AS-811	1	27'-6"	73	BT.
TOTAL: 15,061 LBS				

NOTE BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT INDICATES THE BAR SIZE. FOR EXAMPLE AS-801 IS A NO 8 SIZE BAR.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

WOODLAND AVENUE APPROACH SLAB YOUNGSTOWN, MAHONING COUNTY

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					

FED. RD.	STATE	PROJECT	
2	OHIO		

332
492

MAH-18-1761

RAMP 'A' CURVE DATA


Δ_c = 6°21'00"
D_c = 1°00'00"
L_c = 635.00'
R_c = 5729.58'
T = 317.88

℄ CURVE DATA


Δ = 43°47'40"
$L_{\frac{1}{2}c}$ = 5°30'00"
L_{s_1} = 400.00'
R_c = 1041.74'
θ_s = 11°00'00"
x = 398.53'
y = 25.53'
L_s = 267.18'
S.T. = 133.80'
L.C. = 399.34'
T_2 = 621.04'
Δ_c = 21°47'40"

RAMP 'B' CURVE DATA

Δ_c = 53°21'20"
D_c = 10°00'00"
L_c = 350.00'
R_c = 572.96'
θ_s = 17°30'00"
x = 346.75'
y = 85.40'
L_s = 234.48'
S.T. = 187.71'
L.C. = 338.55'
T_2 = 635.27'




TYPICAL SECTION
STEEL STREET



PROPOSED STRUCTURE

TYPE: CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE DECK AND SUBSTRUCTURE
SPAN: 40'-60'-64'-43' ℄ BRGS.
ROADWAY: 48'-0" F/F CURBS 5'-0" SIDEWALK ON BOTH SIDES
LOAD FREQUENCY: CF 2000 - ADEQUATE FOR A.A.S.H.O. ALTERNATE LOADING
SIDEWALK: 2-5'-0" WIDTHS
SKEW: 5°32'14" L.F.
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLAB: AS-1-54; 25' LONG
SUPERELEVATION: NONE
ALIGNMENT: TANGENT
TRAFFIC COUNT: 15,800 ADT 1977




FOUNDATION SOUNDING

FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF SOIL-SAMPLING SOUNDINGS MADE AT THE SITE. THIS SOUNDING INFORMATION MAY BE INSPECTED AT THE OFFICE OF THE DISTRICT ENGINEER, COLUMBUS OR THE DIVISION OFFICE, BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THEREOF.

SLOPE PROTECTION

1:10 CRUSHED AGGREGATE SLOPE PROTECTION




STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES
BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SITE PLAN.
BRIDGE Nº MAH.-18-1761
UNDER STEEL ST.
YOUNGSTOWN MAHONING COUNTY
STA. 929+98.87


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.A.K	R.E.		D.G.S.	D.G.S.	-	

FED. RD.	STATE	PROJECT	
	OHIO		

333
492



PLAN



ELEVATION

GENERAL NOTES

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS. DATED 9-1-57, TOGETHER WITH CURRENT REVISIONS THEREOF.

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE DECK SLAB, THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS BETWEEN TRANSVERSE CONSTRUCTION JOINTS WHICH ARE NORMAL TO THE CENTERLINE OF BRIDGE AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

ALL PILES TO BE 12" Φ CAST-IN-PLACE CONCRETE, DRIVEN TO A MINIMUM BEARING CAPACITY OF 40 TONS.

SLOPE PROTECTION:- CRUSHED AGGREGATE, ITEM I-10; EXTENDING FROM FACE OF ABUTMENT TO TOE OF SLOPE, SHALL BE PROVIDED AT EACH ABUTMENT FOR FULL WIDTH OF BRIDGE PLUS THREE FEET ON EACH SIDE OF BRIDGE & PARALLEL WITH ℄ OF SUPERSTRUCTURE.

POROUS BACKFILL 2 FT. THICK FULL LENGTH OF ABUTMENT, SHALL EXTEND UP TO THE UNDERSIDE OF APPROACH SLAB, OR TO THE FINISHED GROUND SURFACE.

REFERENCE SHALL BE MADE TO THE FOLLOWING STANDARD DRAWINGS

RB-1-55 DATED 2-2-59
AR-1-57 DATED 2-2-59
CSB-2-56 SHEETS 2 & 3 DATED 2-2-59
SUPPLEMENTAL SPECIFICATION 5101 DATED 12-2-59

EXCAVATION AND BACKFILL: EXCAVATION QUANTITY INCLUDES THE REMOVAL OF FILL MATERIAL BETWEEN THE SURFACE OF PROPOSED EMBANKMENT AND THE BOTTOM OF FOOTINGS.

PAINTING: AFTER ERECTION & AFTER THE SHOP COAT HAS BEEN CLEANED AND WHERE NECESSARY, REPAINTED IN ACCORDANCE WITH SEC. 804, AN ADDITIONAL COAT OF THE SAME PAINT AS USED IN THE SHOP SHALL BE APPLIED OVER OUTSIDE FACE OF OUTSIDE STEEL BEAMS & ALL SIDES OF BOTTOM FLANGES.

MACHINE FINISH: The concrete bridge deck shall be finished as specified in the Proposal Note, "Machine Finishing of Bridge Deck Slabs."

ELECTRICAL GROUNDS: A SOLID Nº 0 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON EACH SIDE OF THE STRUCTURE AT PIER Nº 2. THE LOWER ENDS OF WIRES SHALL TERMINATE IN A 25 FT. LENGTH COILED UNDER THE FOOTING AND SEPARATED FROM THE CONCRETE BY TWO LAYERS OF TAR PAPER, AND THE UPPER ENDS SHALL EXTEND SUFFICIENTLY ABOVE THE TOP OF THE CONCRETE TO PROVIDE FOR A SUITABLE SPLICE AND EXTENSION FOR CONNECTION TO THE SUPERSTRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE A Nº 6 GAGE BARE STRANDED TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE AND TO THE SOLID COPPER WIRE IN THE PIER SHAFT. THERE SHALL BE A TINNED Nº 6 GAGE COPPER WIRE BRAZED TO THE *ANCHOR BOLTS* OF THE LIGHT STANDARD AND THE OTHER END BRAZED OR BOLTED TO THE OUTSIDE BEAM FLANGE. PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM BID FOR ITEM-525 "ELECTRICAL LIGHTING SYSTEM."

ITEM S-25: ELECTRICAL LIGHTING SYSTEM INCLUDES 8-1½"Φ×4'-1" ANCHOR BOLTS.

ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER.	ABUT.	PIERS	GEN.
E-2	LUMP	SUM	COFFERDAMS, CRIBS, AND SHEETING				LUMP
E-2	760	CU.YDS.	UNCLASSIFIED EXCAVATION		298	462	
S-1	434	CU.YDS.	CLASS "C" CONCRETE SUPERSTRUCTURE	434			
S-1	105	CU.YDS.	CLASS "B" CONC. ABUTMENTS ABOVE FOOTING		105		
S-1	126	CU.YDS.	CLASS "C" CONC. PIERS ABOVE FOOTINGS			126	
S-1	210	CU.YDS.	CLASS "E" CONC. PIER & ABUT. FOOTINGS		95	115	
S-29	16	EA	SCUPPERS	16			
S-4	146,957	LBS.	REINFORCING STEEL	100,914	9949	36,094	
S-25	LUMP	SUM	ELECTRICAL LIGHTING SYSTEM				
S-7	338,500	LBS.	STRUCTURAL STEEL	338,500			
S-8	338,500	LBS.	FIELD PAINTING OF STRUC. STEEL, AS PER PLAN	338,500			
S-14	472	LIN.FT.	RAILING (ALUM. RAIL & SUPPORTS, CONC. PARAPETS, & REIN. STL.), *Type "C"*	418	54		
S-16	LUMP	SUM	FIRST TEST PILE				LUMP
S-18	600	LIN.FT.	12" Φ CAST-IN-PLACE REIN. CONC. PILES		600		
S-29	40	CU.YDS.	POROUS BACKFILL		40		
I-10	592	SQ. YDS.	CRUSHED AGGREGATE SLOPE PROTECTION				592

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


GENERAL PLAN & ELEVATION

BRIDGE NO. MAH-18-1761
UNDER STEEL ST.
YOUNGSTOWN MAHONING COUNTY
STA. 929+98.87


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.A.K.	R.J.		D.H.C.	D.H.C.		1-22-60

FED. RD.	STATE	PROJECT	
	OHIO		


334
492





"E" PLAN - ABUTMENT #1




PLAN - ABUTMENT #2







ELEVATION of EAST WINGWALL ABUT #1



ELEVATION of EAST WINGWALL ABUT #2

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT PLAN & DETAILS

BRIDGE NO MAH-18-1761
UNDER STEEL ST.
YOUNGSTOWN MAHONING COUNTY
STA. 929+98.87

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	J.R.J.		DHC	DJC		

FED. RD.	STATE	PROJECT	
	OHIO		

335
492

EAST

℄ ABUTMENT

K AT HEEL OF L

L AT HEEL OF ANGLE

AT HEEL OF L M

WEST

EL. 941.54

EL. 940.60

EL. 937.43

DIMENSIONS ARE AT RIGHT ANGLE TO ℄ OF BRIDGE.

A532

A540

A512

A510

49-AG01 @1'-0"

4-AG02 @1'-0"

6-A537 @1'-0" F.S.

A533 @1'-0" N.S.

4-A534

5-A534 UNDER EACH BEARING ℄

4 ϕ WEEP HOLES

59-A535 @1'-0" N.S. 54-A535 @1'-0" F.S.

A538 OR A539

4-A550 (TYPICAL)

CURVED WINGWALL FOR ABUTMENT #1 ONLY

1'-0" 2'-0" 7'-0" 7'-0" 7'-0" 7'-0" 7'-0" 7'-0" 7'-0" 7'-0" 2'-0" 1'-0"

62'-0" (62'-3½" ALONG SKEW ANGLE)

DIMENSIONS ARE AT RIGHT ANGLE TO ℄ OF BRIDGE.

ELEVATION - ABUTMENT #1
REFLECTED ELEVATION OF ABUTMENT #2 (EXCEPT AS NOTED)

A-G02

SECTION "H-H"

A532

4-A533

AG01

A534

6-A-537

A535 @1'-0"

4-A550

A538

A539

3'-3"

3'-0"

SECTION "G-G"

18-A504

17-A504

2-A517

2-A521

84°

R=8'-0"

T=9'-6"

3-A502

℄ ABUTMENT

W.P.

A532

14-A504 @1'-0"

14-A504 @1'-0"

8-A502

SECTION "A-A"

A-505

A527

2-A521

11-A504 @1'-0" NS & FS AT 15° 4¾" AT O.S. FACE OF WALL

6'-11"

AT INSIDE FACE OF WALL

T-A512 & 7A-504

6-A512

3-A504

3-A512

3-A504 @1'-0"

A540

3-A512

A542 @1'-0"

49-AG01

A537

A533

4-AG02

W.P. STA. 50+35.11

℄ ABUTMENT

= ℄ STEEL STREET

4-AG02

A542 @1'-0"

A514

3-A512 & 3-A504

3-A512

A506

3-A504

3-A512

A540

8-A504 NS & FS

6-A512 & 6A-504

3-A512

SECTION "B-B"

8'-0" RAD.

15°

20°

4'-0⅜"

3'-1⅜"

10-A510

A530

A510

A524

A539

A512

A538

A525

4-A541

5-A510

5'-5⅞"

A542

A533

A537

A535

W.P. STA. 50+35.11

℄ ABUTMENT

= ℄ STEEL STREET

4-A550

5-A510

A542

A512

A-513

A-511

A515

A509

9-A510

4-A541

SECTION "C-C"

4-R504

-A502

A504

4-A505

2-A506

2-A514

A512

A538

A507

A508

A539

4-A509

4-A515

A511

A513

A510

3'-6"

SECTION "E-E"

2-R506

2-R507

A502

A504

A517

2-A527

A521

A522

A528

A523

A529

A512

4-A524 @1'-0"

4-A530 @1'-0

A525

A511

A510

SECTION F-F

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


ABUTMENT DETAILS

BRIDGE NO MAH 18 17.01
UNDER STEEL ST
YOUNGSTOWN MAHONING COUNTY
STA. 929+98.87


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	R.J.		DHC	DHC		

FED. RD.	STATE	PROJECT	
	OHIO		


336
492



SECTION J-J




SECTION K-K




SECTION "M-M"

NOTE:
1-11 I.D. × ½" THK. × 3'-0" Lg. SOCKET EAST SIDE OF STRUCTURE, 1-9" I.D. × ½" THK. × 3'-0" Lg. SOCKET WEST SIDE OF STRUCTURE. ITEM S-25.




PLAN



SECTION 1-1

DETAIL OF LIGHT STANDARD SUPPORT
2 REQUIRED



ANCHOR BOLT DETAIL
(8 REQD)

ELEVATIONS													
	A	B	C	D	E	F	G	H	J	K	L	M	P
ABUTMENT #1	934.43	934.52	934.62	934.72	934.82	934.70	934.53	934.45	934.33	938.72	939.06	938.64	937.39
ABUTMENT #2	930.81	930.92	931.02	931.12	931.22	931.10	930.97	930.85	930.73	935.08	935.41	935.00	933.75

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE NO MAH-18-1761
UNDER STEEL ST.
YOUNGSTOWN MAHONING COUNTY
STA. 929+98.87

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.A.K.	R.J.		D.H.C.	D.H.C.		


FED. RD.	STATE	PROJECT	
	OHIO		

337
492


RECEIVED
SEP 3 1965

CARE SHALL BE TAKEN IN PLACING REINFORCING STEEL SO AS TO AVOID INTERFERENCE WITH ANCHOR BOLTS.

MAXIMUM SOIL LOADING UNDER PIER FOOTINGS = 2.50 TONS PER SQ. FOOT




PLAN



ELEVATION

SECTION A-A



SEC. B-B SEC. C-C

PIER ELEVATION TABLE

	A	B	C	D	E	F	G	H	J
PIER #1	933.29	933.39	933.49	933.59	933.69	933.57	933.45	933.32	933.20
PIER #2	932.18	932.28	932.37	932.47	932.57	932.45	932.33	932.21	932.09
PIER #3	931.13	931.22	931.32	931.42	931.52	931.40	931.28	931.16	931.04

"K" BASE ELEVATIONS

LOC.	ELEV.
PIER #1	910.50
PIER #2	905.50
PIER #3	910.50

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS


BRIDGE NO. MAH-18-1761
UNDER STEEL ST
YOUNGSTOWN MAHONING COUNTY
STA. 929+98.87

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.A.K.	E.S.S.		D.H.C.	B.J.C.		


FED. RD.	STATE	PROJECT		338 / 492
	OHIO			

THESE DIMENSIONS ARE NOMINAL. THE QUANTITY OF DECK CONCRETE TO BE PAID FOR SHALL BE BASED ON THESE DIMENSIONS EVEN THOUGH DEVIATION FROM THEM MAY BE NECESSARY BECAUSE THE TOP FLANGE OF THE BEAM MAY NOT HAVE THE EXACT CAMBER OR CONFIGURATION TO PLACE IT PARALLEL TO THE FINISHED GRADE.

NOTE: SEE RAILING DETAILS FOR REINFORCING BAR SPACING IN PARAPET




TRANSVERSE SECTION





SECTION "A-A"

FOR SECTION THROUGH ROADWAY END DAM SEE STD. DWG. CSB-2-56 SHT. #2




SECTION "C-C"






SECTION "B-B"


BEAM SPLICE DETAILS
G INDICATES GRINDING



SECTION "D-D"




PARTIAL SLAB REINFORCING PLAN



BAR STAGGERING DETAIL OVER PIERS

BEAM SPLICE WELDING PROCEDURE

1. - RAISE BEAM ENDS AT PIER #3 - 2½"
2. - BUTT WELD BEAM FLANGES & WEB AT PIER #2 USING THE FOLLOWING SEQUENCE: MAKE TWO PASSES ON EACH FLANGE, THEN TWO ON WEB; REPEAT, USING ONE PASS AT EACH LOCATION, UNTIL WELD IS COMPLETED.
3. - WELD TOP & BOTTOM MOMENT PLATES AT PIER #2
4. - LOWER ENDS OF BEAMS INTO PLACE AT PIER #3
5. - RAISE BEAM ENDS AT ABUTMENTS ⅜"
6. - MAKE SPLICES AT FIRST AND THIRD PIERS IN SAME MANNER AS AT PIER #2.
7. - LOWER BEAM ENDS INTO PLACE AT ABUTMENTS



FRAMING PLAN

DEFLECTION & CAMBER				
LOCATION	OUTSIDE BEAMS		INSIDE BEAMS	
	END SPANS	MIDDLE SPANS	END SPANS	MIDDLE SPANS
DEFLECTION DUE TO WEIGHT OF STEEL	0.03	0.08	0.02	0.06
DEFLECTION DUE TO REMAINING DEAD LOAD	0.15	0.60	0.08	0.39
CONVEXITY REQUIRED FOR VERTICAL CURVE	0.00	0.00	0.00	0.00
SUM OF DEFLECTION & CONVEXITY	0.18	0.68	0.10	0.45
REQUIRED CAMBER	0	0	0	0

NOTES:
1. SLAB THICKNESS SHOWN INCLUDES 1" MONOLITHIC WEARING SURFACE.
2. WELDING OF STRUCTURAL STEEL SHALL BE CLASS 'A' EXCEPT AS OTHERWISE SHOWN. ANY WELDS SHOWN AS FIELD WELDS MAY, AT THE OPTION OF THE CONTRACTOR, BE MADE IN THE SHOP.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


FRAMING PLAN

BRIDGE NO MAH-18-1761
UNDER STEEL ST
YOUNGSTOWN MAHONING COUNTY
STA. 929+98.87

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.A.K.	R.J.		D.M.C.	D.M.C.		

FED. RD.	STATE	PROJECT	
	OHIO		

339
492



REINFORCING STEEL SCHEDULE

MARK	NO	L'TH	WEIGHT	SHIP
ABUTMENTS				
A-501	8	14'-2	118	ST
A-502	33	5'-4"	184	BT
A-503				
A-504	123	3'-6	449	BT
A-505	4	15'-4"	64	ST
A-506	2	17'-4"	36	ST
A-507	1	10'-6	11	ST
A-508	1	8'-9	9	ST
A-509	12	9'-6	115	BT
A-510	57	5'-0	297	BT
A-511	1	10'-4	11	ST
A-512	73	6'-0"	457	ST
A-513	1	7'-0	7	ST
A-514	2	14'-6	30	ST
A-515	12	6'-0	75	ST
A-516	4	16'-6	70	ST
A-517	2	16'-7	35	BT
A-518				BT
A-519				BT
A-520				BT
A-521	4	17-9	74	BT
A-522	1	8'-6	9	BT
A-523	1	6'-9	7	BT
A-524	4	6'-3	26	BT
A-525	1	7'-10	8	BT
A-526	4	14'-0"	58	ST
A-527	2	19'-0	40	BT
A-528	1	12'-3	13	BT
A-529	1	10'-11	11	BT
A-530	4	9'-8	40	BT
A-531	1	11'-2	12	BT
A-532	4	26'-8	111	ST
A-533	32	31'-0"	1035	ST
A-534	86	5'-9	516	BT
A-535	226	6'-4	1454	BT
A-536	1	7'-6	8	ST
A-537	24	29'-9	745	ST
A-538	4	31'-7	132	ST
A-539	4	30'-7	128	ST
A-540	16	3'-6"	58	ST
A-541	16	4'-10	81	BT
A-542	32	4'-0"	134	ST
A-543	2	10'-3"	22	ST
A-544	2	6'-0	13	ST

MARK	NO	L'TH	WEIGHT	SHIP
A-545	2	10'-2"	21	ST
A-546	2	8'-10"	10	ST
A-547	2	7'-2"	15	ST
A-548	2	5'-10"	12	ST
A-549	1	5'-6"	6	ST
A-550	92	7'-6"	563	BT
A-551	6	7'-7"	47	BT
A-601	98	15'-5"	2245	BT
A-602	16	13'-3"	318	BT
TOTAL ABUT'S			9,949 #	
PIERS				
P-501	198	7'-8"	1583	BT
P-601	12	29'-7"	533	ST
P-602	108	9'-6"	1541	BT
P-701	144	11'-4"	3336	BT
P-801	12	12'-3	394	ST
P-802	6	13'-10"	223	ST
P-803	42	10'-4"	1160	BT
P-901	48	19.5	3169	ST
P-902	48	23'-3"	3795	ST
P-903	48	17.3	2815	ST
P-904	144	6'-7"	3223	BT
P-905	12	9'-6	388	BT
P-1101	24	14-0	1785	ST
P-1102	18	10-0	956	ST
P-1103	15	20 3	1614	ST
P-1104	18	24'-5"	2335	BT
P-1105	9	35'-1"	1678	BT
P-1106	9	39'-0	1865	ST
TOTAL PIERS INCLUDING SPIRALS			36,094#	

SUPERSTRUCTURE				
S-501	312	8-0	2604	BT
S-502	84	3'-0	3154	ST
S-503	328	5'-4"	1824	BT
S-504	312	2'-4	760	BT
S-601	624	26-6	24,837	ST
S-602	522	36-3	28,422	ST
S-603	126	2'-0	4921	ST
S-604	312	10-0	4686	ST
S-605	4	10'-3"	62	BT
S-606	28	7'-4	308	ST
S-701	624	23-0	29,336	ST
TOTAL SUPERST. 100914 #				

RAILING #				
R-502	16	12'-0"		ST
R-503	96	15'-0		ST
R-504	4	15'-2"		ST
R-505	8	14'-0"		ST
R-506	2	17'-4		BT
R-507	2	16'-7"		BT
R-508	8	8'-8		BT
R-509	12	10'-4"		BT

REPLACEMENT BARS				
RE-401	1	5'-3	SPIRAL	BT
RE-501	2	5'-6		ST
RE 601	4	5'-11		ST
RE-701	2	6 3		ST
RE-801	1	6'-6"		ST
RE-901	1	6'-10"		ST
RE-1101	1	7'-6		ST

SPIRAL REINFORCING LIST

MARK	NO	CORE DIA OF SPIRAL	LENGTH	PITCH	NO OF TURNS	WEIGHT
SP-401	4	2'-8	16'-3	4½	46	1014
SP 402	4	2'-8	20'1"	4½	57	1257
SP-403	4	2'-8	14'-0	4½	40	882
SPACERS	48					548
TOTAL						3701

GRAND TOTAL 146,957#

SPIRAL REINFORCING NOTES

THE LENGTH SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE DISTANCE FROM THE TOP OF THE FOOTING TO BOTTOM OF PIER CAPS. THE NUMBER OF TURNS SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE LENGTH DIVIDED BY THE PITCH PLUS THREE TURNS (TOTAL NUMBER OF CLOSED COILS) EXPRESSED AS THE NEAREST WHOLE NUMBER. SPIRAL REINFORCING BARS SHALL NOT HAVE DEFORMATIONS BUT SHALL IN OTHER RESPECTS CONFORM TO ITEM 5-4. ONE AND ONE HALF CLOSED COILS SHALL BE PROVIDED AT THE ENDS OF EACH SPIRAL UNIT. FOUR (4) STEEL CHANNEL, TEE OR ANGLE SPACERS WEIGHING APPROX. 0.68 LBS. PER LINEAL FT OF SPACERS SHALL BE PROVIDED FOR EACH SPIRAL UNIT. THEY SHALL BE EQUALLY SPACED ALONG THE PERIPHERY OF EACH COIL. THE NUMBER OF POUNDS OF THESE SPACERS, BASED ON 0.68 LBS PER LINEAL FT. WILL BE PAID FOR AS REINFORCING STEEL AND IS INCLUDED IN THE TABULATED QUANTITY OF SPIRAL BARS.

BAR SIZE: IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED AND THE FIRST TWO DIGITS WHERE FOUR ARE USED INDICATE THE BAR SIZE NUMBER. FOR EXAMPLE A-700 IS A NO 7 SIZE BAR AND A-1014 IS A NO 10 SIZE BAR.

REPLACEMENT BARS: IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABRITORY, TEST SAMPLES AS PROVIDED IN SECTION S-4.02 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.

RAILING REINFORCEMENT BARS WILL BE INCLUDED AS PART OF ITEM S-14 FOR PAYMENT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RAILING, DRAINAGE DETAILS & REINFORCING SCHEDULE

BRIDGE NO MAH-18-1761
UNDER STEEL ST
YOUNGSTOWN MAHONING COUNTY
STA. 929+98.87

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.A.K.	A.C.		D.H.C.			

FED. RD	STATE	PROJECT	
	OHIO		

340
492

MAH-18-17.20

CURVE DATA

$\Delta = 54°-44'-10"$ $\theta_s = 11°-00'-00"$
$D_c = 5°-30'-00"$ $T_s = 742.31'$
$L_s = 400'$ $E_s = 138.49'$
$R_c = 1041.74'$ $L_c = 598.20'$

PROPOSED STRUCTURE

TYPE: CONTINUOUS STEEL BEAM WITH REINFORCED CONC. DECK & SUBSTRUCTURE
SPANS: 60'-6", 74'-6", 75'-6", 47'-0" C/C BRGS.
ROADWAY: 28'-0" f/f PARAPETS
LOAD FREQUENCY: C.F. 2000 - ADEQUATE FOR A.A.S.H.O. ALTERNATE LOADING
SKEW: 36°-56'-19" L.F.
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLABS: 25' LONG AS-1-54
SUPERELEVATION: NONE
ALIGNMENT: TANGENT

TRAFFIC COUNT: NOT AVAILABLE

PROPOSED SILLIMAN STREET RAMP

FOUNDATION SOUNDINGS

FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF SOIL SAMPLING SOUNDINGS MADE AT THE SITE. THIS SOUNDING INFORMATION MAY BE INSPECTED IN THE OFFICE OF THE BUREAU OF BRIDGES IN COLUMBUS, OR IN THE DIVISION OFFICE, BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THEREOF.

SLOPE PROTECTION

1-10 CRUSHED AGGREGATE SLOPE PROTECTION

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


SITE PLAN
BRIDGE Nº MAH.-18-1776
UNDER SILLIMAN ST. RAMP
YOUNGSTOWN MAHONING COUNTY
STA. 937+92.11

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RH	W.B.H.		D.G.S.			


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

341
492



PLAN



ELEVATION

GENERAL NOTES

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF "DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES" OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS. DATE 8-1-57 TOGETHER WITH CURRENT REVISIONS THEREOF.

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE DECK SLAB. THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS, BETWEEN TRANSVERSE CONSTRUCTION JOINTS WHICH ARE PARALLEL TO TRANSVERSE REINFORCING STEEL AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

SLOPE PROTECTION: CRUSHED AGGREGATE, ITEM 1-10, EXTENDING FROM FACE OF ABUTMENT TO TOE OF SLOPE, SHALL BE PROVIDED AT EACH ABUTMENT FOR FULL WIDTH OF BRIDGE PLUS THREE FEET ON EACH SIDE OF BRIDGE & PARALLEL WITH ℄ OF SUPERSTRUCTURE.

EXCAVATION AND BACKFILL: EXCAVATION QUANTITY INCLUDES THE REMOVAL OF FILL MATERIAL BETWEEN THE SURFACE OF PROPOSED EMBANKMENT AND THE BOTTOM OF FOOTINGS.

MACHINE FINISH: The concrete bridge deck shall be finished as specified in the Proposal Note, "Machine Finishing of Bridge Slabs."

REFERENCE SHALL BE MADE TO STANDARD DRAWINGS:
RB-1-55 - REVISED-2-2-59, AR-1-57- REVISED-2-2-59.
CSB-2-56 SHEET Nº1 & Nº3 REVISED 2-2-59, & SUPPLEMENTAL SPECIFICATION S-101, DATED 12-2-59.

FOUNDATION BEARING PRESSURE: PIER FOOTINGS ARE DESIGNED FOR A MAXIMUM BEARING PRESSURE OF 2.5 TONS PER SQ.FT.
ABUTMENT FOOTINGS ARE DESIGNED FOR A MAXIMUM BEARING PRESSURE OF 1.1 TON PER SQ.FT.

GENERAL NOTES (CONT.)

ELECTRICAL GROUNDS: A SOLID Nº6 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON BOTH SIDES OF THE STRUCTURE AT PIER "2. THE LOWER END OF THE WIRE SHALL TERMINATE IN A 25 FT. LENGTH COILED UNDER THE FOOTING AND SEPARATED FROM THE CONCRETE BY TWO LAYERS OF TAR PAPER AND THE UPPER END SHALL EXTEND SUFFICIENTLY ABOVE THE CONCRETE TO PROVIDE A SUITABLE SPLICE & EXTENSION FOR CONNECTION TO THE SUPERSTRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE A Nº6 GAGE BARE, STRANDED, TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE & TO THE SOLID COPPER WIRE IN THE PIER SHAFT. PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM FOR ITEM S-25 ELECTRICAL LIGHTING SYSTEM.

ITEM S-25: ELECTRICAL LIGHTING SYSTEM INCLUDES EXPANSION FITTINGS AT ABUTMENTS.

LIGHTING DETAILS ARE SHOWN ON SHEET # 510

ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER.	ABUT.	PIERS	GEN.
E-2	467	CU.YDS.	UNCLASSIFIED EXCAVATION		237	230	
S-1	239	CU.YDS.	CLASS "C" CONCRETE SUPERSTRUCTURE	239			
S-1	107	CU.YDS.	CLASS "E" CONC. ABUTS. ABOVE FOOTINGS		107		
S-1	76	CU.YDS.	CLASS "C" CONC. PIERS ABOVE FOOTINGS			76	
S-1	116	CU.YDS.	CLASS "E" CONC. PIER & ABUT. FOOTINGS		43	73	
S-4	83,318	LBS.	REINFORCING STEEL	54,877	8301	20,140	
S-7	242,318	LBS.	STRUCTURAL STEEL	242,318			
S-8	242,318	LBS.	FIELD PAINTING OF STRUCT. STEEL, AS PER PLAN.	242,318			
S-14	584	LIN.FT.	RAILING (ALUM. RAIL & SUPPORTS, CONC. PARAPETS, END POSTS, REIN. STL.)	520	64		
S-25	LUMP	SUM	ELECTRICAL LIGHTING SYSTEM				
S-25	284	LIN.FT.	3" ℄ ELECTRICAL CONDUIT (GALV.)				
S-29	6	EACH	SCUPPERS		6		
S-29	40	CU.YDS.	POUROUS BACKFILL		40		
I-10	400	SQ.YDS.	CRUSHED AGGREGATE SLOPE PROTECTION			400	

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GENERAL PLAN & ELEVATION

BRIDGE NO. MAH-18-1776
UNDER SILLIMAN ST. RAMP
YOUNGSTOWN, MAHONING COUNTY
STA. 937+02.11

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
HAWKINS	STEFANOC					

FED. RD.	STATE	PROJECT		342 / 492
	OHIO			

MAH-18-17.20

NOTE-B
HORIZONTAL DIMENSION AT BASE OF BACKWALL

SEE SKETCH FOR SLOPE OF BACKWALL

NOTES AND DIMENSIONS NOT SHOWN SAME AS ABUTMENT #1

SKETCH
SHOWING SLOPE OF BACKWALL

ABUTMENT #1

ABUTMENT #2

36°-56'-19" SKEW

℄ STRUCTURE

℄ INT. BEAM

℄ EXT. BEAM

BASE LINE

3-SPS @ 9'-0" = 27'-0" - ℄ 4" ø WEEPHOLES

4-SPS @ 8'-0" = 32'-1½" ℄ BEAMS

4-SPS @ 8'-0" = 32'-1½" ℄ BEAMS = 25'-8" ℄ BEAMS = 29'-8"

2% SLOPE NORMAL TO FACE OF ABUTMENT - TYPICAL BETWEEN BEAM SEATS.

℄ RAILING

℄ BEARING

SEE NOTE-B

NOTE-A : THESE DIMENSIONS ARE GIVEN PARALLEL TO GRADE

PLAN OF ABUTMENT # 1

PLAN OF ABUTMENT # 2

VARIES - 1'-0" MAX. RADIAL DIMENSION

SECTION A-A

ELEVATION - WEST WINGWALL - ABUT. # 1

ELEVATION - WEST WINGWALL ABUT. # 2

DO NOT CHAMFER

SEE SECTION G-G FOR THESE BARS

SEE SECTION M-M FOR THESE BARS

SEE SECTION G-G

CONST. JOINT

CONST. JT.

2:1 NORMAL

EL. 913.48

EL. 903.19

36WF160

36WF150

CLEAR

2" AT 70°F.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


ABUTMENT DETAILS

BRIDGE NO. MAH-18-1776
UNDER SILLIMAN ST. RAMP
YOUNGSTOWN, MAHONING COUNTY
STA. 937+02.11

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RH	JK		cw			

FED. RD.	STATE	PROJECT	
	OHIO		


MA H-18-17.20




ELEVATION AS SHOWN FOR ABUTMENT #1

REFLECTED ELEVATION FOR ABUTMENT #2

ALL HORIZONTAL DIMENSIONS NORMAL TO ℄ OF STRUCTURE UNLESS OTHERWISE NOTED.




SECTION C-C




FOR NOTES AND DIMENSIONS NOT SHOWN SEE SECTION C-C

SECTION D-D


SECTION E-E



SECTION F-F



SECTION H-H



SECTION G-G

ELEVATION TABLE

	A	B	C	D	E	F*	G*	H	K	L	M	N	P
ABUTMENT #1	914.85	914.75	914.66	914.57	914.48	919.28	918.21	919.44	918.87	918.62	917.78	918.19	906.83
ABUTMENT #2	904.56	904.46	904.37	904.28	904.19	908.88	908.50	907.70	907.24	908.28	906.81	907.80	886.65

*ELEVATIONS GIVEN TO HEEL OF ANGLE

NOTE:

THE CONCRETE IN THE ABUTMENT BACKWALL SHALL NOT BE PLACED UNTIL AFTER STEEL WORK IS ERECTED, BUT SHALL BE PLACED BEFORE THE DECK SLAB IS PLACED.

POROUS BACKFILL, 2-FT. THICK FULL LENGTH OF ABUTMENT AND WINGS SHALL EXTEND UP TO THE UNDER SIDE OF APPROACH SLAB OR TO THE FINISHED GROUND SURFACE.

THE RAILING SHALL BE CONTINUOUS FOR A MINIMUM OF TWO PANELS ON THE WINGWALLS.


STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE NO. MA H-18-1776
UNDER SILLIMAN ST. RAMP
YOUNGSTOWN, MAHONING COUNTY
STA. 963+02.11

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RH	JK		aw			



FED. RD.	STATE	PROJECT		344 / 492
	OHIO			

M A H-18-17,20

REINFORCING STEEL SCHEDULE


MARK	NO	L'TH	WEIGHT	SH'P
ABUTMENTS				
A-501	4	38-3"	164	ST.
A-502	38	36-9"	1457	ST.
A-503	46	6'-4"	304	BT.
A-504	4	10'-5"	43	ST.
A-505	20	4'-11"	103	ST.
A-506	12	6'-6"	81	ST.
A-507	32	7'-11"	264	BT.
A-508	107	7'-5"	828	BT.
A-509	38	9'-0"	357	ST.
A-510	4	3'-9"	16	BT.
A-511	34	8'-4"	296	ST.
A-512	3	12'-10"	40	ST.
A-513	2	14'-6"	30	ST.
A-514	3	11'-8"	37	ST.
A-515	1	12'-3"	13	ST.
A-516	20	3'-6"	73	ST.
A-517	72	4'-5"	333	BT.
A-518	6	12'-6"	78	BT.
A-519	7	8'-6"	62	ST.
A-520	1	8'-10"	9	ST.
A-521	1	11'-0"	11	ST.
A-522	3	20'-4"	64	ST.
A-523	3	17'-4"	54	ST.
A-524	2	23'-0"	48	ST.
A-525	6	3'-0"	19	ST.
A-526	6	11'-3"	70	BT.
A-527	1	6'-0"	6	ST.
A-528	1	3'-9"	4	ST.
A-529	3	14'-0"	44	ST.
A-530	3	18'-10"	59	ST.
A-531	132	3'-10"	527	BT.
A-532	50	5'-11"	308	BT.
A-533	4	18'-3"	76	ST.
A-534	2	19'-0"	40	BT.
A-535	4	16'-4"	68	ST.
A-536	2	15'-10"	33	BT.
A-537		OPEN		
A-538	4	1'-9"	7	BT.
A-539	4	1'-11"	8	BT.
A-540	4	2'-0"	8	BT.
A-541	4	2'-1"	9	BT.
A-542	4	2'-2"	9	BT.
A-543	4	2'-3"	9	BT.
A-544	4	2'-4"	10	BT.
A-545	4	2'-5"	10	BT.
A-546	4	2'-6"	10	BT.
A-547	29	2'-7"	78	BT.
A-548	4	8'-0"	33	BT.
A-549		OPEN		
A-550	1	5'-6"	6	ST.
A-551		OPEN		
A-552	1	12'-6"	13	ST.
A-553	6	12'-3"	77	BT.
A-554	6	5'-0"	31	ST.
A-555	6	7'-10"	49	ST.
A-556	6	11'-3"	70	BT.
A-557	3	17'-1"	53	ST.
A-558	3	10'-10"	34	ST.
A-559	3	14'-0"	44	ST.
A-560	3	16'-4"	51	ST.
A-561	8	17'-7"	123	ST.
A-562	2	14'-7"	30	BT.
A-563	2	15'-4"	32	BT.
A-601	24	14'-3"	514	BT.
A-602	40	16'-0"	961	BT.
TOTAL ABUT'S			8301	#
PIERS				
P-301	84	7'-8"	672	BT.
P-302	96	7'-8"	768	ST.
P-601	6	32'-4"	291	ST.
P-701	48	9'-2"	900	ST.
P-901	36	18'-2"	2224	ST.
P-902	36	16'-2"	1979	ST.
P-903	36	17'-2"	2102	ST.
P-904	12	9'-3"	377	BT.
P-905	42	10'-5"	1488	BT.
P-906	108	6'-7"	2416	BT.
P-907	9	32'-3"	987	ST.


MARK	NO	L'TH	WEIGHT	SH'P
P-1001	21	25'-10"	2334	ST.
P-1002	24	12'-0"	1239	ST.
TOTAL PIERS			17,777	#
SUPERSTRUCTURE				
S-501	203	38'-4"	8116	ST.
S-502	376	5'-11"	2324	BT.
S-503	72	30'-0"	2253	ST.
S-504	296	4'-9"	1466	BT.
S-601	161	38'-8"	9351	ST.
S-602	273	29'-8"	12,166	ST.
SERIES OF S-603	2 SETS OF 20 BARS	VARY 27'-6" TO 34'-5" INC. 1'-6"	987	ST.
S-604	10	5'-0"	75	ST.
S-605	12	7'-8"	138	ST.
S-701	273	29'-8"	16,556	ST.
SERIES OF S-702	2 SETS OF 20 BARS	VARY 27'-6" TO 34'-5" INC. 1'-6"	1,343	ST.
S-703	10	5'-0"	102	ST
TOTAL SUPERST.			54,877	#
RAILING *				
R-401	4	18'-2"		ST.
R-402	4	16'-3"		ST.
R-403	16	12'-11"		ST.
R-404	112	16'-8"		ST.
R-405	8	14'-1"		ST.
REPLACEMENT BARS				
RE-401	1	5'-3" (SPIRAL)		BT
RE-402	1	5'-3"		ST.
RE-501	2	5'-6"		ST.
RE-601	2	5'-11"		ST.
RE-701	1	6'-3"		ST.
RE-901	1	7'-0"		ST.
RE-1001	1	7'-6"		ST.


SPIRAL REINFORCING LIST

MARK	NO	CORE DIA OF SPIRAL	LENGTH	PITCH	NO. OF TURNS	WEIGHT
SP-401	3	2'-8"	15'-2"	4½"	43	711
SP-402	3	2'-8"	13'-2"	4½"	38	628
SP-403	3	2'-8"	14'-2"	4½"	41	677
SPACERS	36					347
TOTAL						2363

GRAND TOTAL-83318 LBS







SPIRAL REINFORCING NOTES

THE LENGTH SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE DISTANCE FROM THE TOP OF THE FOOTING TO BOTTOM OF PIER CAPS.
THE NUMBER OF TURNS SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE LENGTH DIVIDED BY THE PITCH PLUS THREE TURNS (TOTAL NUMBER OF CLOSED COILS) EXPRESSED AS THE NEAREST WHOLE NUMBER.
SPIRAL REINFORCING BARS SHALL NOT HAVE DEFORMATIONS BUT SHALL IN OTHER RESPECTS CONFORM TO ITEM S-4.
ONE AND ONE HALF CLOSED COILS SHALL BE PROVIDED AT THE ENDS OF EACH SPIRAL UNIT.
FOUR (4) STEEL CHANNEL, TEE OR ANGLE SPACERS WEIGHING APPROX. 0.68 LBS. PER LINEAL FT. OF SPACERS SHALL BE PROVIDED FOR EACH SPIRAL UNIT. THEY SHALL BE EQUALLY SPACED ALONG THE PERIPHERY OF EACH COIL. THE NUMBER OF POUNDS OF THESE SPACERS, BASED ON 0.68 LBS. PER LINEAL FT. WILL BE PAID FOR AS REINFORCING STEEL AND IS INCLUDED IN THE TABULATED QUANTITY OF SPIRAL BARS.
BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED AND THE FIRST TWO DIGITS WHERE FOUR ARE USED INDICATE THE BAR SIZE NUMBER. FOR EXAMPLE A-700 IS A NO. 7 SIZE BAR AND A-1014 IS A NO. 10 SIZE BAR.

REPLACEMENT BARS : IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SECTION S-4.02 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.

*RAILING REINFORCEMENT BARS WILL BE INCLUDED AS PART OF ITEM S-14 FOR PAYMENT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAIL & REINFORCING SCHEDULE


BRIDGE NO. M A H-18-1776
UNDER SILLIMAN ST. RAMP
YOUNGSTOWN, MAHONING COUNTY
STA. 937+92.11

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RH	JK		cw			


FED. RD.	STATE	PROJECT	
	OHIO		

346
492


MA H-18-17.20



TRANSVERSE SECTION




SECTION D-D




SECTION C-C


SEE TRANSVERSE SECTION



PARTIAL SLAB REINFORCING PLAN




FRAMING PLAN




SECTION A-A

TOP MOMENT PLATE { 10½" x ½" x 15'-0" - PIER #1 & #3
10½" x ½" x 17'-4" - PIER #2



DETAIL - A

SECTION B-B



DETAIL - B

FOR DETAILS NOT SHOWN SEE DETAIL - A

BEAM SPLICE DETAILS

DEFLECTION & CAMBER

LOCATION	OUTSIDE BEAMS				INSIDE BEAMS			
SPAN	#1	#2	#3	#4	#1	#2	#3	#4
DEFLECTION DUE TO WT. OF STEEL	.03	.09	.13	.01	.03	.09	.13	.01
DEFLECTION DUE TO REMAINING DEAD LOAD	.13	.36	.54	.05	.11	.32	.47	.04
CONVEXITY REQUIRED FOR VERT. CURVE.	0	0	0	0	0	0	0	0
SUM OF DEFLECTION AND CONVEXITY	.16	.45	.67	.06	.14	.41	.60	.05
REQUIRED CAMBER	0"	0"	0"	0"	0"	0"	0"	0"

NOTES:

WELDING OF STRUCTURAL STEEL SHALL BE CLASS 'A' EXCEPT AS OTHERWISE SHOWN. WELD SHOWN AS FIELD WELDS MAY AT THE OPTION OF THE CONTRACTOR BE MADE IN THE SHOP.

BEAM SPLICE WELDING PROCEDURE:

1. RAISE END OF BEAM AT PIER #1 OR PIER #3 - 5/8"
2. BUTT WELD BEAM FLANGES AND WEB AT PIER #2 USING THE FOLLOWING SEQUENCE: MAKE TWO PASSES ON EACH FLANGE, THEN TWO ON THE WEB; REPEAT USING ONE PASS AT EACH LOCATION UNTIL WELDS ARE COMPLETED.
3. WELD TOP AND BOTTOM MOMENT PLATES AT PIER #2.
4. LOWER END OF BEAM AT PIER #1 OR PIER #3
5. MAKE SPLICE AT PIER #1 OR PIER #3 IN THE SAME MANNER RAISING THE END OF BEAMS - ⅜" AT THE ABUTMENTS.

PAINTING: AFTER ERECTION AND AFTER THE SHOP COAT HAS BEEN CLEANED, AND WHERE NECESSARY, REPAINTED IN ACCORDANCE WITH SEC. 8.04, AN ADDITIONAL COAT OF THE SAME PAINT AS USED IN THE SHOP SHALL BE APPLIED OVER THE OUTSIDE FACE OF THE OUTSIDE STEEL BEAMS AND ALL SIDES OF BOTTOM FLANGE.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING PLAN SLAB DETAILS


BRIDGE NO. MA H-18-1776
UNDER SILLIMAN ST. RAMP
YOUNGSTOWN, MAHONING COUNTY
STA. 937 + 02.11

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RH	JK		aw			


FED. RD.	STATE	PROJECT	
	OHIO		

345
492

MAH-18-17.20




PLAN




ELEVATION

A



SEC. A-A



SEC. B-B

PIER ELEVATION TABLE

	A	B	C	D	E	L
PIER #1	912.07	911.98	911.89	911.80	911.70	890.00
PIER #2	909.09	909.00	908.91	908.82	908.72	889.00
PIER #3	906.07	905.98	905.89	905.80	905.70	885.00

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS


BRIDGE NO. MAH-18-1776
UNDER SILLIMAN ST. RAMP
YOUNGSTOWN, MAHONING COUNTY
STA. 937+92.11

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RH.	E.S.S.					


FED. RD.	STATE	PROJECT	
	OHIO		

347
492


MA H-18-17.20



PART DECK PLAN



ELEVATION



SECTION A-A SECTION B-B

FOR DETAILS NOT SHOWN SEE STD. DRAWING CSB-2-56

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

DRAINAGE & RAILING DETAILS

BRIDGE NO. MA H-18-1776
UNDER SILLIMAN ST. RAMP
YOUNGSTOWN, MAHONING COUNTY
STA. 937+02.11

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.H.	R.P.S.		CW			

FED. RD.	STATE	PROJECT	
	OHIO		

348
492

MICROFILMED
SEP 10 '65

P.G. 900.83
STA. 51+22.50

EXISTING PROFILE GRADE ELEVATIONS

90.47

BRIDGE LIMITS - 163.33'

904.30

EXISTING PROFILE GRADE ELEVATIONS

RQ MIN. CLEAR 15.00'
ACTUAL MIN. CLEAR 16.13'

907.13

ESTIMATED PAY LENGTH OF PILES:
30'-0" ABUTMENT
20'-0" PIERS

STA 48+52.91
P.G. 908.46

ABANDONED SPUR LINE

35° SEG. BLOCK

Y.E. CURVE DATA #3
Δ = 60°-43'-03"
D_c = 5°-30'-00"
L_s = 400'
R_c = 1041.74'
θ = 11°-00'-00"
T_s = 813.68'
E_s = 172.95'
L_c = 703.95'

M.V.S.D. M.H.

EXISTING SALT SPRINGS RD.

NEW CONSTRUCTION
EXISTING CONSTRUCTION
EXPANSION JOINT

12" PE GAS
16" C.I.P.
8" C.I.P.
4" GAS
3" GAS

EXISTING BENTS TO REMAIN

END STRUCTURE
STA. 51+76.50

MILL CREEK POND BRIDGE
WINGWALL

RAMP "D"

DECELERATION LANE (FUTURE RAMP)

℄ WEST BOUND LANES

℄ SURVEY OF STATE ROUTE #18

℄ EAST BOUND LANES

ACCELERATION LANE (RAMP "C")

REMOVE AS EXISTING CONSTRUCTION

℄ OF EXISTING BENTS TO BE REMOVED

24" PIPE
30" PIPE

STA. 958+83.99
50+00

STA. 959+73.00

AERIAL CABLE

PT. OF MIN. CLEAR

EXISTING STRUCTURE
EQUIPMENT

30" PIPE

24" PIPE

BEGIN STRUCTURE
STA. 48+55.91
END APPROACH SLAB
STA. 48+55.45

E. MAHONING AVE.

RAMP E


PARK RD

EXISTING STRUCTURE
TYPE: SIMPLE SPAN STEEL BEAMS WITH CONCRETE FILLED STEEL GRID DECK. FRAMED STEEL SUBSTRUCTURE.
SPANS: BEGINNING AT ABUTMENT: 20'-3", 20'-0", REMAINING SPANS 30'-0"
ROADWAY: 32'-11" CURB TO CURB
SIDEWALK: 7'-11" ONE SIDE
ALIGNMENT: STRAIGHT

PROPOSED STRUCTURE
TYPE: 5-WEST SPANS CONTINUOUS STEEL BEAM
EAST SPAN SINGLE SPAN STEEL BEAM
WITH REINFORCED CONCRETE DECK & SUBSTR.
SPANS: 64'-0", 80'-0", 81'-9", 40'-9" ℄/4 BRGS.
ROADWAY: 32'-11" CURB-CURB
LOAD FREQUENCY: CF 2000 - ADEQUATE FOR A.A.S.H.O. ALTERNATE LOADING
SKEW: 43°-11'-21" L.F.
APPROACH SLABS 25'-0" LONG
WEARING SURFACE 1" MONOLITHIC
ALIGNMENT: SAME AS EXISTING STRUCTURE
TRAFFIC COUNT: 20,900 A.D.T. 1959

NOTE:
FOR COMBINED & STORM SEWERS SEE SHEET #4

FOUNDATION SOUNDINGS
FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF ROD SOUNDINGS AND SOIL SAMPLING SOUNDINGS MADE AT THE SITE. THIS SOUNDING INFORMATION MAY BE INSPECTED IN THE OFFICE OF THE BUREAU OF BRIDGES IN COLUMBUS, OR IN THE DISTRICT OFFICE, BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THEREOF.
SEE UTILITY DETAILS FOR SEWER & WATER RELOCATIONS.



STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES


DEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SITE PLAN
BRIDGE Nº MAH.-18-1815
UNDER MAHONING AVE.
YOUNGSTOWN MAHONING COUNTY
STA. 958+83.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	W.B.H.		D.G.S	DHC		

FED. RD.	STATE	PROJECT	
	OHIO		

349
492




— PLAN —

ALL EXISTING STRUCTURAL STEEL, WHEN REMOVED, SHALL BECOME THE PROPERTY OF MAHONING COUNTY, AND SHALL BE STORED WITHIN THE RIGHT OF WAY LIMITS.

— REMOVAL OF EXISTING STRUCTURE —

WHEN NO LONGER NEEDED TO MAINTAIN TRAFFIC THE EXISTING STRUCTURE SHALL BE REMOVED TO THIS POINT.



ELEVATION

ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER	ABUT.	PIERS	GEN.
E-2	374	CU.YDS.	UNCLASSIFIED EXCAVATION		198	176	
S-1	397	CU.YDS.	CLASS "C" CONCRETE-SUPERSTRUCTURE	397			
S-1	76	CU.YDS.	CLASS "E" CONCRETE-ABUTMENT		76		
S-1	139	CU.YDS.	CLASS "C" CONCRETE- PIERS ABOVE FOOTINGS			139	
S-1	136	CU.YDS.	CLASS "E" CONCRETE- PIER AND ABUT. FOOTINGS		52	84	
S-4	146,665	LBS	REINFORCING STEEL	100,797	8,090	37,778	
S-7	464,544	LBS.	STRUCTURAL STEEL	464,544			
S-8	464,544	LBS	FIELD PAINTING OF STRUCTURAL STEEL AS PER PLAN	464,544			
S-9	40	SQ.FT.	1" PREFORMED EXPANSION JOINT FILLER		40		
S-14	580	LIN.FT.	RAILING TYPE "A" (ALUMINUM RAIL-SUPPORTS AND CONC. PARAPET)	531	49		
S-14	313	LIN.FT.	RAILING TYPE "C" (ALUMINUM RAIL-SUPPORTS AND CONC. PARAPET)	289	24		
S-16	LUMP	SUM	FIRST TEST PILE				LUMP
S-18	2280	LIN.FT.	12" DIA. CAST-IN-PLACE REINFORCED CONCRETE PILES.		300	1980	
S-22	LUMP	SUM	REMOVAL OF PORTIONS OF EXISTING STRUCTURE				LUMP
S-25	LUMP	SUM	ELECTRICAL LIGHTING SYSTEM				
S-29	12	EACH	SCUPPERS	12			
S-29	43	CU.YDS.	POROUS BACKFILL		43		
I-10	281	SQ.YDS.	CRUSHED AGGREGATE SLOPE PROTECTION		281		

GENERAL NOTES

DESIGN SPECIFICATIONS : THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF "DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES" OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS, DATED 9-1-57 TOGETHER WITH CURRENT REVISIONS THEREOF.
CONCRETE DECK PLACING : IN ORDER TO FACILITATE WATER CURING OF THE DECK SLAB THE PLACING OF CONCRETE SHALL PROGRESS UP GRADE. THE SLAB MAY BE PLACED IN SECTIONS BETWEEN TRANSVERSE CONSTRUCTION JOINTS WHICH ARE PARALLEL TO TRANSVERSE REINFORCING STEEL AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

CRUSHED AGGREGATE SLOPE PROTECTION : ITEM I-10 EXTENDING FROM FACE OF ABUTMENT TO TOE OF SLOPE, SHALL BE PROVIDED AT WEST ABUTMENT FOR FULL WIDTH OF BRIDGE PLUS THREE FEET ON EACH SIDE OF BRIDGE PARALLEL WITH ℄ OF SUPERSTRUCTURE.
REMOVAL OF EXISTING STRUCTURE : WHEN NO LONGER NEEDED TO MAINTAIN TRAFFIC THE EXISTING STRUCTURE SHALL BE REMOVED AS INDICATED ON PLANS IN ACCORDANCE WITH SECTION S-22.

PILES : ALL PILES ARE 12" DIA. CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN TO A MINIMUM BEARING CAPACITY OF 40 TONS.
EXCAVATION AND BACKFILL : FOR THE ABUTMENT IN ADDITION TO THAT OUTLINED IN SEC. E-2.09 INCLUDES THE REMOVAL OF MATERIAL BOUNDED BY THE FRONT VERTICAL PLANE DESCRIBED IN SEC. E-2.09 AND BY THE FINISHED SLOPE CUT.

ITEM S-7 INCLUDES ALTERATIONS TO EXISTING STRUCTURE.

REFERENCE SHALL BE MADE TO STANDARD DRAWINGS :
AR-1-57, REVISED 2-2-59.
C.S.B-2-56, SHEET #2 & #3 REVISED 2-2-59
RB-1-55, REVISED 2-2-59.
SUPPLEMENTARY SPECIFICATIONS S-101, DATED 12-2-59

NOTES (CONT.)

ELECTRICAL GROUNDS: A SOLID N° 0 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON EACH SIDE OF THE STRUCTURE AT PIER N° 2. THE LOWER ENDS OF THE WIRES SHALL BE BRAZED TO THE STEEL SHELL OF ONE OF THE CAST-IN-PLACE CONCRETE PILES AND THE UPPER ENDS SHALL EXTEND SUFFICIENTLY ABOVE THE TOP OF THE CONCRETE TO PROVIDE FOR A SUITABLE SPLICE & EXTENSION FOR CONNECTION TO THE SUPERSTRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE A N° 6 GAGE, BARE, STRANDED TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE AND TO THE SOLID COPPER WIRE IN THE PIER SHAFT. THERE SHALL BE A TINNED N° 6 GAGE COPPER WIRE BRAZED TO THE ANCHOR BOLTS OF EACH LIGHT STANDARD AND THE OTHER END BRAZED OR BOLTED TO THE OUTSIDE BEAM FLANGE.
PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM BID FOR ITEM S-25 "ELECTRICAL LIGHTING SYSTEM."

ITEM S-25: ELECTRICAL LIGHTING SYSTEM INCLUDES 32 ANCHORBOLTS 1½" DIA. x 4'-1" LG.

MACHINE FINISH: The concrete bridge deck shall be finished as specified in the Proposal Note "Machine Finishing of Bridge Deck Slabs".

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


GENERAL PLAN & ELEVATION

BRIDGE NO. MAH-18-1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA. 958+83.99


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	J.N.P.		ew	DHC		7-28-60

FED. RD.	STATE	PROJECT	
	OHIO		


350
492



PLAN OF ABUTMENT



ELEVATION OF NORTH WINGWALL



ELEVATION OF SOUTH WINGWALL

NOTE: THE CONCRETE IN THE ABUTMENT BACKWALL SHALL NOT BE PLACED UNTIL AFTER STEEL WORK IS ERECTED, BUT SHALL BE PLACED BEFORE THE DECK SLAB IS PLACED.

POROUS BACKFILL, 2 FT. THICK FULL LENGTH OF ABUTMENT AND WING WALLS, SHALL EXTEND UP TO THE UNDERSIDE OF THE APPROACH SLAB, OR TO THE UNDERSIDE OF THE SIDEWALK SLAB.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT PLAN & DETAILS

BRIDGE NO. MAH-18-1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA 958+83.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	JK		aw	DHC		


FED. RD.	STATE	PROJECT	
	OHIO		

351
492


43'-3"
32'-11" - ROADWAY
7'-11"
1'-0"
2"
16'-5½"
16'-5½"
3"
10"
6'-10" SIDEWALK
3¼"
10½"
8½"
2'-8½"
℄ ROADWAY
1'-4"
⅜ PLATE - SEE DETAIL AT FRAMING PLAN.
1" TYP.
CONCRETE ABOVE THIS POINT TO BE PAID FOR AS PART OF ITEM S-14 (RAILING)
℄ EXISTING BENTS
EL. 907.96 AT FACE OF BACK WALL
EL. 908.56 HEEL OF L.
EL. 909.53 HEEL OF L.
EL. 906.90 AT FACE OF BACK WALL
EL. 908.25 HEEL OF L
A-504-F.S.
1'-4" TYP.
2-A-505-F.S. TELEPHONE CONDUITS
CONST. JT.
1'-4"
1'-8"
8½"
10½"
EL. 907.60 HEEL OF L
A-504-F.S.
1'-6"
17"
1'-6"
CONST. JT.
2"
10"
2"
1'-6"
2"
1"
44-A-604 ℄ 1'-0"
10-A-603 ℄ 1'-0"
3-A-541
A-539
4-A-603
1'-9"
EL. 903.07
EL. 903.34
EL. 903.61
EL. 903.75
EL. 903.92
EL. 904.07
A-514
5-A-511
5-A-509 ℄ 8" - TYPICAL UNDER EACH BEAM SEAT - UNLESS NOTED.
A-510
4-A-602 ℄ 1'-0"
4-A-601 ℄ 1'-0"
A-523
6"
8-A-503 N.S. ℄ 1'-0" F.S. ℄ 1'-0"
7-A-503
9-A-503-N.S.
8-A-503-F.S.
4-A-508 ℄ 8"
℄ 4" ϕ WEEPHOLES
A-532
33-A-520-N.S.25-A-520-F.S.
4-A-502 - TYPICAL
A-501-N.S. & F.S.
CONST. JT.
25-A-508-N.S.23-A-508-F.S.
A-520
1'-0"
3'-3"
EL. 896.54
5-SPACES ℄ 7'-11" = 39'-7" - ℄ TO ℄ BEAMS & PILES
44'-7" - 61'-1¾" ALONG SKEW ANGLE

ELEVATION OF ABUTMENT

ALL HORIZONTAL DIMENSIONS GIVEN NORMAL TO ℄ ROADWAY EXCEPT BAR SPACING AND DIMENSIONS AS NOTED.



SECTION A-A



SECTION B-B



SECTION Z-Z

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


ABUTMENT DETAILS

BRIDGE NO MAH-18-1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA. 958+83.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	JK		ew	DHC		


FED. RD.	STATE	PROJECT	
	OHIO		

352
492




SECTION C-C

SECTION E-E




SECTION F-F


FOR DIMENSIONS NOT SHOWN SEE SECTION E-E




SECTION G-G



SECTION D-D




SECTION H-H



SECTION K-K

FOR DIMENSIONS NOT SHOWN SEE SECTION H-H



SECTION L-L

SECTION M-M

FOR BARS IN THIS AREA SEE SECTION E-E

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


ABUTMENT DETAILS


BRIDGE NO MAH-18-1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA. 958+83.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	JK		ew.	DHC		

FED. RD.	STATE	PROJECT	
	OHIO		


353
492







PILE PLANS


PIER ELEVATION TABLE								
PIER NO.	A	B	C	D	E	F		G
1	901.72	901.57	901.42	901.27	900.99	900.72		878.00
2	899.41	899.26	899.11	898.95	898.68	898.41		876.50
3	897.31	897.16	897.01	896.85	896.58	896.30		870.50



CARE MUST BE TAKEN IN PLACING THE BARS IN TOP OF PIER #2 TO CLEAR ANCHOR BOLTS FOR BOLSTER PLATE.







STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS

BRIDGE NO MAH-18-1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA. 958+83.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	JLH		CW	DHC		


FED. RD.	STATE	PROJECT	
	OHIO		

354
492


NOTE: CONTRACTOR TO REMOVE MIN. AMOUNT OF PAVING & GRID THAT IS NECESSARY AND REPLACE WITH SAME MATERIAL AFTER EXP. DAM IS IN PLACE.

NOTE (2): THIS CONTACT SURFACE SHALL NOT BE PAINTED AND SHALL BE LUBRICATED WITH FLAKE GRAPHITE PRIOR TO BOLTING TOGETHER


NOTE (1): 5/8 ϕ BOLTS AT APPROX. 2'-0" C/C - REMOVE AFTER STEEL WORK IS WELDED




TRANSVERSE SECT. F-F
LOOKING EAST AT BENT NO. 27




SECTION J-J
FOR PARAPETS AT BENT "27




DETAIL OF CONNECTION
AT BENT "27




BLOW-UP DETAIL 'A'



SECTION H-H




PARTIAL SECTION C-C




SECTION 1-1


BEARING DETAIL AT BENT "27




FRAMING PLAN AND ELEVATION



SECTION A-A
END DIAPHRAGM WEST SIDE OF BENT "27




SECTION B-B
END DIAPHRAGM EAST SIDE OF BENT "27



SECTION E-E

WELDING SIMILAR TO SECTS A-A & E-E UNLESS OTHERWISE NOTED.



SECTION G-G

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


FRAMING PLAN & DETAILS

BRIDGE NO MAH-18-1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA. 958+83.99


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	JLH		aw	DHC		9-1-60

FED. RD.	STATE	PROJECT		355/492
	OHIO			


NOTE "B" - FOR SPACING OF RAILING BARS SEE RAILING DETAIL SHEET.




TRANSVERSE SECTION



SECTION A-A




SECTION B-B




SLAB REINFORCING PLAN

DETAIL OF SCUPPERS



PLAN OF REINFORCING IN SIDEWALK AND SAFETY CURB



DETAIL OF BAR STAGGERING ACROSS PIERS #1 & #2

CAMBER DIAGRAM - CONTINUOUS SPANS

	64'-0" SPAN		80'-0" SPAN		81'-9" SPAN	
	North Bm	Other Bm	North Bm	Other Bm	North Bm	Other Bm
DEFLECTION DUE TO WEIGHT OF STEEL	0.10	0.10	0.08	0.08	0.25	0.25
DEFLECTION DUE TO REMAINING DEAD LOAD	0.60	0.40	0.50	0.30	1.25	0.80
CONVEXITY REQUIRED FOR VERTICAL CURVE	0.00	0.00	0.00	0.00	0.00	0.00
SUM OF DEFLECTIONS AND CONVEXITY	0.70	0.50	0.58	0.38	1.50	1.05
REQUIRED CAMBER	0	0	0	0	1 1/2	1 1/4

CAMBER DIAGRAM - SIMPLE SPANS - EAST BAY

	53'-10 7/16" SPAN	46'-4 7/8" SPAN	38'-11 7/16" SPAN	31'-6 1/2" SPAN	24'-1 5/16" SPAN	16'-8 3/16" SPAN
DEFLECTION DUE TO WEIGHT OF STEEL	0.15	0.10	0.07	0.05	0.02	0.01
DEFLECTION DUE TO REMAINING DEAD LOAD	1.20	0.50	0.28	0.20	0.08	0.02
CONVEXITY REQUIRED FOR VERTICAL CURVE	0.00	0.00	0.00	0.00	0.00	0.00
SUM OF DEFLECTIONS AND CONVEXITY	1.35	0.60	0.35	0.25	0.10	0.03
REQUIRED CAMBER	1 3/8	0	0	0	0	0

DIMENSION "D" TABLE

BEAM	64'-0" SPAN		80'-0" SPAN		81'-9" SPAN		40'-8" SPAN	
	SIZE	"D"	SIZE	"D"	SIZE	"D"	SIZE	"D"
A	36"WF 230#	9 3/8"	36"WF 230#	9 3/8"	36"WF 280#	8 3/4"	36"WF 182#	8 7/8"
B	36"WF 230#	9 3/8"	36"WF 230#	9 3/8"	36"WF 280#	8 3/4"	36"WF 182#	8 7/8"
C	36"WF 230#	9 3/8"	36"WF 230#	9 3/8"	36"WF 280#	8 3/4"	36"WF 160#	9 1/4"
D	36"WF 230#	9 3/8"	36"WF 230#	9 3/8"	36"WF 280#	8 3/4"	36"WF 150#	9 3/8"
E	36"WF 230#	9 3/8"	36"WF 280#	9 3/8"	36"WF 280#	8 3/4"	36"WF 150#	9 3/8"
F	36"WF 230#	9 3/8"	36"WF 230#	9 3/8"	36"WF 280#	8 3/4"	36"WF 150#	9 3/8"

DIMENSION "D" = THICKNESS OF SLAB OVER BEAMS. THIS IS THE NOMINAL DIMENSION. THE QUANTITY OF DECK CONCRETE TO BE PAID FOR SHALL BE BASED ON THIS DIMENSION. EVEN THOUGH DEVIATION FROM IT MAY BE NECESSARY BECAUSE THE TOP FLANGE OF THE BEAM MAY NOT HAVE THE EXACT CAMBER OR CONFORMATION REQUIRED TO PLACE IT PARALLEL TO THE FINISHED GRADE.

NOTES

WELDING PROCEDURE: ① RAISE ENDS OF BEAMS 2 1/2" AT PIER "3. ② MAKE WELDED SPLICES AT PIER "2 USING THE FOLLOWING SEQUENCE, MAKE TWO PASSES ON EACH FLANGE, THEN TWO ON WEB, REPEAT USING ONE PASS AT EACH LOCATION UNTIL WELD IS COMPLETE. ③ - WELD TOP & BOTTOM MOMENT PLATES AT PIER "2. ④ - LOWER BEAM END INTO PLACE AT PIER "3. ⑤ RAISE BEAM ENDS 1/4" AT ABUTMENT. - ⑥ MAKE WELDED SPLICES AT PIER "1 USING SAME PROCEDURE AS AT PIER "2. ⑦ LOWER BEAM ENDS INTO PLACE AT ABUTMENT.

CONCRETE DECK PLACING. IN ORDER TO FACILITATE WATER CURING OF THE CONCRETE OF THE DECK SLAB, THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS BETWEEN TRANSVERSE CONSTRUCTION JOINTS WHICH ARE PARALLEL TO THE TRANSVERSE REINFORCING STEEL AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

SLAB THICKNESS. SLAB THICKNESS SHOWN INCLUDES 1" MONOLITHIC WEARING SURFACE.

WELDING STRUCTURAL STEEL. WELDING OF STRUCTURAL STEEL SHALL BE CLASS 'A' EXCEPT AS OTHERWISE SHOWN. ANY WELDS SHOWN AS FIELD WELDS MAY, AT THE OPTION OF THE CONTRACTOR MAY BE MADE IN THE SHOP.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING DETAILS


BRIDGE NO MAH-18 1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA. 956+83.99


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	JLH		cw	DHC		

FED. RD.	STATE	PROJECT		356 / 492
	OHIO			


(a) = 9" x 2½" x 0'-9" PLATE
(b) = 2-L3-6x6x1" x 2'-0¼"
(c) = 2⅞" x 3" x 0'-8¾" BAR
(d) = 5" x 1" x 5" PLATE
(e) = 2" x ½ x 0'-4" PLATE

FOR DETAILS OF END-DAMS SEE SECT'S. K-K & L-L







SECTION 4-4




BEARING DETAIL


HINGED SPLICE DETAIL






SECTION 5-5







SECTION 6-6

BEAM SPLICE DETAILS







SECTION 1-1



BEAM	"A"	"B"±
A	10½"	⅜"
B	11¼"	⅜"
C	11⅞"	¾"
D	1'-0⅛"	⅞"
E	11⅞"	⅞"
F	10⅝"	⅞"




SECTION 3-3





SECTION 2-2

DETAIL OF SUPPORT AT BENT #27




SECTION P-P






SECTION D-D



SECTION X-X



SECTION Y-Y

NOTES:


WHEREVER NEW STEEL CONNECTS TO EXISTING STEEL, FABRICATOR SHALL VERIFY DIMENSIONS OF EXISTING STEEL BEFORE FABRICATION OF NEW STEEL.

ALL RIVETS 1"ø UNLESS OTHERWISE NOTED. ALL HOLES IN EXISTING STEEL TO BE REAMED OUT TO TAKE 1"ø RIVETS.

PAINTING: AFTER ERECTION AND AFTER THE SHOP COAT HAS BEEN CLEANED AND WHERE NECESSARY REPAINTING IN ACCORDANCE WITH SEC. 8.04, AN ADDITIONAL COAT OF THE SAME PAINT AS USED IN THE SHOP SHALL BE APPLIED OVER THE OUTSIDE FACE OF OUTSIDE STEEL BEAMS AND ALL SIDES OF BOTTOM FLANGES.

SEE STATE OF OHIO STD. DWG # C.S.B.-2-56 SHEET # 2 FOR DETAILS AND NOTES NOT SHOWN.

DETAIL—B



SECTION R-R

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING DETAILS


BRIDGE NO MAH-18-1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA 958+83.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	JLM		ewl	DHC		


FED. RD.	STATE	PROJECT	
	OHIO		

357
492


SEE STATE OF OHIO STD. DWG. "CSB-2-56 SHEET #2 FOR DETAILS AND NOTES NOT SHOWN.




SECTION K-K




SECTION Q-Q




SECTION L-L




SECTION S-S




SECTION M-M




SECTION T-T



SECTION N-N




PLAN




DETAIL OF 11" LIGHT STANDARD SUPPORT (4 REQ'D.)

PLAN



SECTION 2-2

DETAIL OF 11" LIGHT STANDARD SUPPORT REQUIRED



SECTION 1-1

DETAIL OF 9' LIGHT STANDARD SUPPORT REQUIRED

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING DETAILS

BRIDGE NO MAH-18-1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA 958+83.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	EAK			DHC		

FED. RD.	STATE	PROJECT	
	OHIO		

358
492

℄ ABUTMENT BEARING — 11'-2⅝" — 2 @ 70° — 13 SPA. @ 16'-0" = 208'-0" — ℄ PIER #1 — ℄ PIER #2 — ℄ PIER #3 — 13'-0" — 2 @ 70° — 13'-0" — 2 SPA. @ 16'-0" = 32'-0" — 10'-8½" — 3½"±

A — A

2 @ 70° — 11'-1⅝" — FACE OF ABUTMENT — FACE OF BACKWALL AT ℄ OF RAIL — 5"×3½"@13.0 BULB L.

B — B

8'-0" — 14'-0" — 5"×3½"@13.0 BULB L. — FACE OF ABUTMENT — 8'-0" — 14'-0" — FACE OF CURB

5'-4¼" — 13'-0" — 13'-0" — 2 @ 70° — 2 SPA. @ 16'-0" = 32'-0" — 3'-11½"±

4 SPA. @ 8'-0" = 32'-0" — 3'-6" — ℄ EXISTING BENT #27

¼" GREY SPONGE RUBBER PREFORMED EXPANSION JOINT FILLER MEETING THE REQUIREMENTS OF SEC. M-10.02. TYPE NO.1. SPACE TWO PANEL LENGTHS APART. (INCLUDED WITH ITEM S-14 FOR PAYMENT)

FACE OF CURB — 5'-2½" — USE WELDED BEND & COUPLING — 45° — 2" — B

USE STD. ELBOW & COUPLING — 45° — 2"

5'-0" — 5'-0" — 3'-6" — ¼"±

℄ PIER #1 — ℄ PIER #2 — ℄ PIER #3 — ℄ HINGED SPLICES — 17'-5½"±

C — C

TYPE "C" RAILING
4" O.D. × 3/16 WALL TOP & 3½" O.D. × 5/16 WALL BOT. ALUMINUM TUBE. RAILING SHALL BE CONTINUOUS THRU FIRST POST AT EACH END OF NEW SUPERSTRUCTURE.

2 @ 70° — 11'-1⅞" — 13 SPA. @ 16'-0" = 208'-0" — 13'-0" — 2 @ 70° — 6 SPA. @ 8'-0" = 48'-0" ℄ TO ℄ RAILPOSTS — REFINISH EXISTING RAILING HERE. SEE NOTE BELOW — 5'-8½"±

PARTIAL DECK PLAN

2 @ 70° — 1'-0" — 1'-0" — 6'-2⅝" — 28 SPA. @ 8'-0" = 224'-0" ℄ TO ℄ RAILPOSTS — 1'-0" — 1'-0" — 1'-0"

2 R-505 — 8 S-502 — 8 S-510 — 7 SPA @ 1'-6" 10'-6" — 2 R-505 — 2 R-506 — 10 S-502 — 9 SPA @ 1'-8" = 15'-0" — 10 S-502 @ 1'-8", 10 S-510 @ 1'-8" — 2 R-506 — CONSTRUCTION JOINT — 2 R-507 — 8 SPA. @ 1'-6" = 12'-0" — 9 S-502 — 9 S-510 — 2 R-507 — 9 S-502 & 9 S-510 @ 1'-6" = 12'-0" — 2 R-507 — 2 R-506 — 9 SPA. @ 1'-8" = 15'-0" — 10 S-502 — 10 S-510 — 2 R-506 — 7 SPA @ 1'-5"-9-11" — 2 R-505 — 8 S-502 — 8 S-510 — CONSTRUCTION JOINT — SIDEWALK BRACKET RAIL POST & DIAG. BRACE FOR POST TO REMAIN IN PLACE — END OF PARAPET WALL — 3/16 — C-27

SECTION A-A

TYPE "A" RAILING
4" O.D. 3/16 WALL ALUMINUM TUBE. RAILING SHALL BE CONTINUOUS THRU FIRST POST AT EACH END OF NEW SUPERSTRUCTURE

2 @ 70° — 1'-0" — 1'-0" — 6'-1⅝" — 2-SP'S @ 3'-2" = 6'-4" — 2'-0" — 1'-8" — 4 SPA. @ 3'-2" = 12'-8" SIDEWALK DRAINS — 1'-8" TYPICAL FOR EACH 16'-0" PANEL SECT. B-B ONLY — 28 SPA. @ 8'-0" = 224'-0" ℄ TO ℄ RAILPOSTS — 1'-9" — 3-SP'S @ 3'-2" = 9'-6" SIDEWALK DRAINS — 1'-10" — TYPICAL FOR EACH 13'-0" PANEL, SECT. B-B ONLY — 5 SPA. @ 8'-0" = 40'-0" ℄ TO ℄ RAILPOSTS — SW. DRAINS — 6'-11½" — 11½" — 1'-6" — 1'-0" — 1½" — 1'-2"

2 R-505 — 8 S-503 — 7 SPA @ 1'-6" 10'-6" — 2 R-505 — 2 R-506 — 10 S-503 @ 1'-8" — 2 R-506 — SCUPPERS — 2 R-506 — 10 S-503 @ 1'-8" — 2 R-506 — 1'-0" — 2 R-507 — 8 SPA. @ 1'-6" = 12'-0" — 9 S-503 — 2 R-507 — SCUPPERS — 2 R-507 — 2 R-507 — 9 S-503 @ 1'-6" = 12'-0" — 2 R-507 — 5"×3½"@13" BULB L — 2 R-506 — 9 SPA. @ 1'-8" = 15'-0" — 10 S-503 — 2 R-506 — 2 R-508 — 3 S-503 @ 1'-6" — 2 R-509 — 45° — 2'-6"

2" DIA. STD. STL. PIPE DRAIN. WELD STUB END FULL PERIMETER TO BULB ANGLE.

SECTION B-B

NOTE: THE EXISTING RAILINGS SHALL BE CUT & FINISHED AS SHOWN. THE EXISTING PARAPETS, WHERE APPLICABLE, SHALL BE CUT BACK NEATLY ABOUT 18" FROM THE JOINT WITHOUT DAMAGE TO THE REINFORCING. THE REINFORCING SHALL THEN BE CUT TO HAVE 2" CLEARANCE FROM THE FINISHED SURFACE. THE NEW ENDS OF THE PARAPETS SHALL BE FORMED AND POURED WITHOUT CHAMFER TO DIMENSIONS SHOWN AND PROVIDING ANCHORBOLTS FOR RAILING POSTS AS REQUIRED.
ALL THIS WORK SHALL BE INCLUDED IN ITEM S-14 FOR PAYMENT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RAILING & DRAINAGE DETAILS


BRIDGE NO MAH-18-1815
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA. 958+83.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	J.L.H.		aw	DHC		

FED. RD.	STATE	PROJECT	
	OHIO		

359
497

TYPE "A" RAILING
4" O.D. 3/16" WALL ALUMINUM TUBE. RAILING SHALL BE CONTINUOUS THRU FIRST POST AT EACH END OF NEW SUPERSTRUCTURE.



2" DIA. STD. STL. PIPE DRAIN. WELD STUB END FULL PERIMETER TO BULB ANGLE.

REINFORCING STEEL SCHEDULE

MARK	NO.	LENGTH	WEIGHT	SHAPE	MARK	NO.	LENGTH	WEIGHT	SHAPE
	ABUTMENT								
A-501	4	31'-6"	131	ST.	A-601	3	10'-6"	47	BT.
A-502	24	8'-4"	209	BT.	A-602	4	7'-7"	46	BT.
A-503	32	30'-1"	1004	ST.	A-603	14	15'-3"	321	BT.
A-504	2	22'-10"	48	ST.	A-604	44	17'-4"	1146	BT.
A-505	8	8'-9"	73	ST.					
A-506	5	18'-0"	94	ST.	TOTAL ABUTMENT			8,090	
A-507	51	5'-6"	293	BT.	PIERS				
A-508	58	7'-2"	434	BT.	P-501	12	27'-0"	338	ST.
A-509	29	6'-8"	202	BT.					
A-510	3	6'-0"	19	ST.	P-601	138	8'-6"	1762	BT.
A-511	24	4'-0"	100	ST.	P-602	30	9'-10"	443	BT.
A-512	1	5'-0"	5	ST.	P-603	48	9'-2"	661	BT.
A-513	12	5'-4"	67	BT.					
A-514	3	13'-10"	43	ST.	P-701	108	8'-4"	1839	BT.
A-515	2	18'-6"	39	ST.					
A-516	4	11'-6"	48	ST.	P-801	120	10'-10"	3470	BT.
SERIES OF A-517	2 SETS OF 6 = 12	VARY 5'-7" TO 7'-3" INC. 4"	80	BT.					
A-518	32	8'-8"	289	ST.	P-901	21	7'-10"	559	BT
A-520	133	6'-3"	867	BT.	P-902	21	8'-10"	631	BT
A-521	6	9'-9"	61	BT.	P-903	12	9'-7"	391	BT.
A-522	7	17'-8"	129	ST.	P-904	144	6'-2"	3019	BT
A-523	18	6'-9"	127	ST.	P-905	48	19'-0"	3101	ST.
A-524	2	6'-5"	13	ST.	P-906	48	18'-3"	2978	ST
A-525	28	3'-9"	110	BT.	P-907	48	22'-1"	3604	ST.
SERIES OF A-526	2 - SETS OF 5 = 10	VARY- 4'-1 - 5'-5" INCR. 4"	50	BT.					
A-527	33	4'-4"	149	BT.	P-1001	60	27'-0"	6971	ST
A-528	5	17'-3"	90	ST	P-1002	30	16'-0"	2065	ST
A-529	12	3'-4"	42	ST	P-1003	30	15'-1"	1947	ST.
A-530	2	15'-1"	31	ST.					
A-531	1	21'-1"	22	ST.	TOTAL PIERS			33,779	
A-532	24	7'-10"	196	ST	SUPERSTRUCTURE				
A-533	4	29'-9"	124	ST.	S-501	82	34'-8"	2965	ST
A-534	4	26'-0"	108	ST	S-502	184	4'-9"	912	BT.
A-535	5	15'-2"	79	BT	S-503	337	4'-4"	1522	BT
A-536	5	10'-6"	55	ST.	S-504	211	10'-9"	2366	BT
A-539	1	16'-6"	17	ST	S-505	8	27'-4"	228	ST
A-541	3	25'-4"	79	ST	SERIES OF S-506	1 SET OF 4	VARY- 6'-7" - 10'-10" INC. 1'-5"	36	BT.
A-542	3	22'-9"	71	ST.	S-507	1	6'-0"	6	BT.
A-543	2	23'-6"	49	ST.	SERIES OF S-508	1 SET OF 8	VARY 22'-0" - 30'-2" INC. 14"	218	ST.
A-544	18	4'-9"	89	BT					
A-545	36	8'-8"	325	ST.					
SERIES OF A-546	2 SETS OF 4 = 8	VARY 1'-10" - 6'-1" INCR. 1'-5"	33	ST.					
SERIES OF A-547	2 SETS OF 7 = 14	VARY 22'-6 - 30'-0" INCR. 1'-5"	383	ST					
SERIES OF A-548	2 SETS OF 6 = 12	VARY 3'-5" - 5'-1" INCR. 4"	53	ST.					


MARK	NO	LENGTH	WEIGHT	SHAPE
S-509	2	16'-10"	36	ST.
S-510	184	2'-1"	399	BT.
S-511	158	3'-11"	646	BT.
S-601	490	35'-1"	25,818	ST
S-602	325	36'-0"	17,573	ST
S-603	52	34'-0"	2656	ST
S-604	174	9'-0"	2321	ST
SERIES OF S-605	1-SET OF 43	VARY- 3'-0" - 41'-6" INC. 11"	1437	ST
SERIES OF S-606	1-SET OF 27	VARY- 3'-2" - 35'-8" INC. 1'-5"	789	ST
SERIES OF S-607	3 SETS OF 39	VARY- 8'-1" - 35'-0" INC. 8½"	3786	ST
S-608	70	16'-5"	1726	ST.
S-609	32	9'-11"	480	BT
S-701	318	42'-7"	27,677	ST.
SERIES OF S-702	3 SETS OF 50	VARY- 6'-8½" - 41'-5" INC. 8½"	7378	ST
S-703	18	6'-0"	222	ST
TOTAL SUPERSTRUCTURE			100,797	
RAILING * SEE NOTE-2				
R-501	4	17'-9"		ST.
R-502	2	30'-3"		ST.
R-503	2	29'-11"		ST.
R-504	4	23'-4"		ST.
R-505	16	10'-7"		ST.
R-506	172	15'-7"		ST.
R-507	20	12'-7"		ST.
R-508	4	16'-10"		ST.
R-509	4	3'-5"		ST.
R-510	8	8'-8"		BT
R-511	16	10'-4"		BT
R-512	8	10'-5		BT
R-513	24	12'-2"		BT
REPLACEMENT BARS - SEE NOTE-1				
RE-401	1	5'-3"	(SPIRAL)	BT
RE-501	1	5'-6"		ST
RE-601	4	6'-0		ST
RE-701	2	6'-3"		ST
RE-801	1	6'-6"		ST
RE-901	1	7'-0"		ST
RE-1001	1	7'-3"		ST

SPIRAL REINFORCING LIST

MARK	NO REQ'D	CORE DIA OF SPIRAL	LENGTH OF SPIRAL	PITCH	NO. OF TURNS	WEIGHT
SP-401	4	2'-8"	15'-8⅜"	4"	50	1102
SP-402	4	2'-8"	14'-11"	4"	48	1058
SP-403	4	2'-8"	18'-9⅜"	4"	59	1300
SPACERS	48					539
					TOTAL:	3999

GRAND TOTAL 146665 LBS

ELEVATION C-C



SPIRAL REINFORCING NOTES

THE LENGTH SHOWN IN THE STEEL LIST FOR SPIRAL BARS IS THE DISTANCE FROM THE TOP OF THE FOOTING TO BOTTOM OF PIER CAPS. THE NUMBER OF TURNS SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE LENGTH DIVIDED BY THE PITCH PLUS THREE TURNS (TOTAL NUMBER OF CLOSED COILS) EXPRESSED AS THE NEAREST WHOLE NUMBER. SPIRAL REINFORCING BARS SHALL NOT HAVE DEFORMATIONS BUT SHALL IN OTHER RESPECTS CONFORM TO ITEM S-4. ONE AND HALF CLOSED COILS SHALL BE PROVIDED AT THE ENDS OF EACH SPIRAL UNIT. FOUR (4) STEEL CHANNEL, TEE OR ANGLE SPACERS WEIGHING APPROXIMATELY 0.68 LBS. PER LINEAL FT. OF SPACERS SHALL BE PROVIDED FOR EACH SPIRAL UNIT. THEY SHALL BE EQUALLY SPACED ALONG THE PERIPHERY OF EACH COIL. THE NUMBER OF POUNDS OF THESE SPACERS, BASED ON 0.68 LBS. PER LINEAL FT. WILL BE PAID FOR AS REINFORCING STEEL AND IS INCLUDED IN THE TABULATED QUANTITY OF SPIRAL BARS.

BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED AND THE FIRST TWO DIGITS WHERE FOUR ARE USED INDICATE THE BAR SIZE NUMBER. FOR EXAMPLE A-700 IS A NO. 7 SIZE BAR AND A-1014 IS A NO. 10 SIZE BAR.

① REPLACEMENT BARS: IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SECTION S-4.02 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.

② *RAILING REINFORCEMENT BARS WILL BE INCLUDED AS PART OF ITEM S-14 FOR PAYMENT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RAILING, DRAINAGE DETAILS & REINFORCING SCHEDULE

BRIDGE NO. MAH-18-18.15
UNDER MAHONING AVE
YOUNGSTOWN MAHONING COUNTY
STA. 958+83.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	JLH		aw	DHC		

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.

MAH-18-17.20

CURVE DATA NO. 3
Δ = 60° 43' 03" Lt. L_c = 703.95
D_c = 5° 30' 00" T_s = 813.68
L_s = 400.00' E_s = 172.95
R_c = 1041.74' C.S. STA. 965+77.01
θ_s = 11° 00' 00"

DRAINAGE DATA
HIGH WATER (50 YEAR): 841.5
Q=
DRAINAGE AREA: 68.4 SQ. MI.

PROPOSED STRUCTURE
TYPE: CONTINUOUS STEEL GIRDER WITH REINFORCED CONCRETE DECK AND SUBSTRUCTURE.
SPANS: 85' 106' 106' 106' 106' 85' 9/6 PIERS & ABUT.
ROADWAY: 94'-0" F/F 2'-3" SAFETY CURBS
SKEW: 00°-00'-00"
LOAD FREQUENCY: CF 2000 (57) ADEQUATE FOR AASHO ALTERNATE LOADING
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLAB: 25' LONG AS-1-54
ALIGNMENT: SEE CURVE DATA
SUPERELEVATION: VARIABLE .083% MAXIMUM
TRAFFIC COUNT: PRICE ROAD 4300 ADT 1979

FOUNDATION SOUNDINGS
FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF SOIL SAMPLING SOUNDINGS MADE AT THE SITE. THIS SOUNDING INFORMATION MAY BE INSPECTED IN THE OFFICE OF THE BUREAU OF BRIDGES IN COLUMBUS OR AT THE DIVISION OFFICE. BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THEREOF !!

PRICE ROAD PROFILE

DECELERATION LANE SAWTOOTH
RAMP "E"
END APPROACH & JAB STA. 962+48.25
P.C. STA. 963+96.94
S. PARK ROAD
BENCH EL. 875.7
PT. MIN. CLEARANCE
PRICE ROAD
42" SAN. SEWER
C.S. STA. 965+77.01
2.0' VARYING
16' CLEAR
SURVEY OF STATE ROUTE #7
TOP OF SPILLWAY EL. 838.34
DAM
MILL CREEK POND (LAKE GLACIER)
BENCH EL. 841.9
DECELERATION LANE (RAMP "D")
CURB
ACCELERATION LANE (RAMP "D")
BEGIN APPROACH SLAB STA. 968+46.25
MH
GENNETT AVE.
STA. 969+51.58
ACCELERATION LANE (RAMP "E")
BENCH EL. 884.5
106'-0"
85'-0"

BRIDGE LIMITS 598'-08

STA. 962+48.25 EL. 872.97 N.S
STA. 968+46.25 EL. 891.05
+0.94% GRADE
MIN. CLEARANCE
EL. 875.24 - F.S
EL. 876.62 - N.S
EL. 844.97
EL. 841.00
EL. 842.00
EXIST. WATER EL. 833.1
(50YR) HIGH WATER EL. 841.5
EL. 822.50
EL. 821.10
EL. 845.00 - N.S
EL. 842.00 - F.S
F.S EL. 844.00
AVERAGE ESTIMATED PAY LENGTH FOR PILES ARE 130

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES
BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SITE PLAN
BRIDGE Nº MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN MAHONING COUNTY
STA. 962+48.25 TO STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	D.G.S.		D.G.S.			

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

361
492

GENERAL NOTES

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF "DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES" OF THE STATE OF OHIO, DEPARTMENT OF HIGHWAYS, DATED 9-1-57. TOGETHER WITH CURRENT REVISIONS THEREOF.

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE CONCRETE OF THE DECK SLAB THE PLACING OF CONCRETE SHALL UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS BETWEEN THE TRANSVERSE CONSTRUCTION JOINTS WHICH ARE NORMAL TO THE CENTER-LINE OF THE BRIDGE AND ARE LOCATED NEAR THE CENTERLINE OF ANY SPAN.

WELDING OF STRUCTURAL STEEL: SHALL BE CLASS "A" EXCEPT AS OTHERWISE SHOWN. ANY WELDS SHOWN AS FIELD WELDS MAY AT THE OPTION OF THE CONTRACTOR BE MADE AT THE SHOP. PAYMENT FOR BACKFILL SHALL BE INCLUDED WITH ITEM E-2 "UNCLASSIFIED EXCAVATION."

EXCAVATION QUANTITY: INCLUDES THE REMOVAL OF MATERIAL BETWEEN THE SURFACE OF THE PROPOSED EMBANKMENT AND THE BOTTOM OF ABUTMENT.

ALL PILES SHALL BE 12"-BP-53* STEEL "H" PILES AND SHALL BE DRIVEN TO FIRM CONTACT WITH ROCK USING A HAMMER OF NOT LESS THAN 11,000 FT. LBS. PER BLOW. IF THE LENGTH OF PENETRATION IS APPROXIMATELY EQUAL TO THE DEPTH TO ROCK ACCORDING TO THE BRIDGE FOUNDATION INVESTIGATION REPORT, THE FIRM CONTACT SHALL BE CONSIDERED AS ATTAINED WHEN THE CAPACITY ACCORDING TO THE FORMULA IN SEC. S-18.05 IS NOT LESS THAN THE FOLLOWING VALUE FOR A PILE HAMMER OF THE INDICATED ENERGY RATING: 50 TONS PER PILE USING A 11,000 FT.LB HAMMER
45 TONS PER PILE USING A 15,000 FT. LB. OR GREATER HAMMER.
IF THE ENERGY RATING OF THE HAMMER IS BETWEEN THE RATINGS AS SHOWN ABOVE, THE REQUIRED FORMULA CAPACITY SHALL BE DETEPMINED BY INTERPOLATION. THE DESIGN LOAD IS 25 TONS PER PILE.

REFERENCE SHALL BE MADE TO STANDARD DRAWINGS:
AR-1-57, DATED 4-9-57, REVISED 2-2-59.
CSB-2-56-SHEET 2&3, DATED 12-5-56, REVISED 2-2-59.
RB-1-55, DATED 3-1-55, REVISED 2-2-59.
SUPPLEMENTAL SPECIFICATIONS S-101
DATED 12-2-59


AS-1-54 DATED 7-1-54, REVISED 12-1-54
1-15 NO. 2-A REVISED 5-21-59.
SUPPLEMENTAL SPEC. S-207 DATED 4-28-55

UTILITY LINES: ALL LABOR AND EXPENSE INVOLVED IN RELOCATING THE EFFECTED UTILITY LINES SHALL BE BORN BY THE OWNER. THE CONTRACTOR AND OWNER ARE REQUESTED TO COOPERATE BY ARRANGING THEIR WORK IN SUCH A MANNER THAT INCONVENIENCE TO EITHER WILL BE HELD TO A MINIMUM.

ELECTRICAL GROUNDS: A SOLID N°0 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON EACH SIDE OF THE STRUCTURE AT PIER N°3. THE LOWER END OF THE WIRE SHALL BE BRAZED TO ONE OF THE 12" BP 53 STEEL PILES AND THE UPPER END SHALL EXTEND SUFFICIENTLY ABOVE THE CONCRETE TO PROVIDE A SUITABLE SPLICE AND EXTENSION FOR CONNECTION TO THE SUPER-STRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE AN N°6 GAGE BARE STRANDED TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE AND TO THE SOLID COPPER WIRE IN THE PIER SHAFT. THERE SHALL BE A TINNED N°6 GAGE BARE COPPER WIRE BRAZED TO A ANCHOR BOLT OF EACH LIGHT STANDARD AND THE OTHER END BRAZED OR BOLTED TO THE OUTSIDE BEAM FLANGE.
PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM BID FOR ITEM S-25 "ELECTRICAL LIGHTING SYSTEM."

ITEM S-25: ELECTRICAL LIGHTING SYSTEM INCLUDES THE FOLLOWING ITEMS, 4 EXPANSION FITTINGS, 5 GALVANIZED CAST IRON BOXES AND 201 DIA. ANCHOR BOLTS.

LIGHTING DETAILS ARE SHOWN ON SHEET N° 310




PLAN

ESTIMATED QUANTITES:

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER	ABUT.#1	ABUT.#2	PIERS	GEN.		
E-2	LUMP	SUM	COFFERDAMS, CRIBS & SHEETING					LUMP.		
E-2	2293	CU.YDS.	UNCLASSIFIED EXCAVATION-EXCLUDING ROCK		977	150	1146			
E-2	832	CU.YDS.	ROCK EXCAVATION		488	250	94			
S-1	1869	CU.YDS.	CLASS "C" CONCRETE SUPERSTRUCTURE	1869						
S-1	655	CU.YDS.	CLASS "E" CONC. ABUTMENTS ABOVE FOOTING		499	156				
S-1	1382	CU.YDS.	CLASS "C" CONC. PIERS ABOVE FOOTINGS				1382			
S-1	743	CU.YDS.	CLASS "E" CONC. PIER & ABUT. FOOTINGS.		268	49	426			
S-3	90	LIN.FT.	WATER PROOFING PREMOLDED SEALING STRIP 6"		75	15				
S-4	722,078	LBS	REINFORCING STEEL	532,438	57,483	10,094	122,558			
S-7	1,999,446	LBS	STRUCTURAL STEEL	1,999,446						
S-8	1,999,446	LBS.	FIELD PAINTING OF STRUCT. STEEL AS PER PLAN	1,999,446						
S-9	302	SQ.FT.	1" PREFORMED EXP. JOINT FILLER		258	44				
S-14	1,337	LIN.FT.	RAILING (ALUM. RAIL & SUPPORTS, CONC PARAPETS,)	1,192	111	34				
S-16	LUMP	SUM	FIRST TEST PILE					LUMP		
S-18	3430	LIN.FT.	12 BP 53 STEEL PILES				3430			

ESTIMATED QUANTITIES CONTINUED

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER	ABUT.#1	ABUT.#2	PIERS	GEN.		
S-25	LUMP ❶	SUM	ELECTRICAL LIGHTING SYSTEM					LUMP		
S-25	1321	LIN. FT.	2" ELECTRICAL CONDUIT (GALV.)	1321						
S-29	251	CU.YDS.	POROUS BACKFILL		188	63				
S-29	54	EACH	SCUPPERS					LUMP		
S-14	556	LIN.FT	GUARD RAIL STL BEAM TYPE (DEEP) BARRIER DESIGN	556						



ELEVATION

MACHINE FINISH: *At the Contractor's option, the bridge deck slab may be machine finished. Machine finishing, if used, shall be in accordance with the Proposal Note," Machine Finishing of Bridge Deck Slabs."*

FOUNDATION BEARING PRESSURES (DESIGN)

ABUT. #1	3820#
ABUT. #2	4,800#
PIER #4	7150#
PIER #5	7,150#

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GENERAL PLAN & ELEVATION

BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+45.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED 1-12-60
D.H.C.	A.C.		ww			

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

362
492

NOTE ALL DIMENSIONS MARKED THUS ⊗ MEASURED ALONG WORLINE "C"

RADIAL LINES

32'-7⅞" - SECTION-F-F ⊗

96'-0" ALONG WORKLINE "C"

53'-4½" - SECTION-E-E ⊗

9'-10½" ⊗ SECTION-D-D

10'-6"

4'-4" ±

1'-5⅝" @ TOP OF WALL

4"

1'-6½" TOP OF WALL

1'-6¾" TOP OF WALL

1" EXPANSION JOINT

RADIAL LINES

STA. 961+85

STA. 961+50.74

91.66' RAD. TO WORKLINE "C"

8 - SP's @ 9'-0" = 72'-0" - 4" ◊ WEEPHOLES ⊗

℄ BEARINGS - ABUTMENT #1 RADIAL LINE

1" EXPANSION JOINT

1'-6" TOP OF WALL

WORKLINE "C"

℄ RAILING

℄ EXT. GIRDER

℄ GIRDER

℄ INT. GIRDER

℄ GIRDER

STA. 962+50.50

℄ GIRDER

6'-0"

2'-0"

2'-6"

4'-0" LEVEL

3'-4"

5'-1½"

1'-6"

13'-6" SECTION-D-D

55'-11⅛"

54'-2"

53'-3¾"

52'-6⅝"

51'-10⅛"

51'-1⅝"

50'-10⅝"

50'-6⅜"

50'-3⅜" 4 ◊ WEEPHOLES

50'-1½"

50'-1"

10-SP's @ 5'-0" = 50'-0"

5-SP's @ 8'-5⅜" = 44'-0¼" ℄ TO ℄ BEAMS

5-SP's @ 9'-0" = 45'-0"

5-SP's @ 9'-0" = 45'-0"

℄ S.R. 18

LOCAL TANGENT AT STA. 962+50.50

10'-0" 10'-0" 10'-0" 10'-0" 10'-0" 10'-0" 10'-0" 10'-0" 10'-0" 10'-0"

2'-5" 6" MEDIAN CURB 1" EXPANSION JOINT 3'-0"

2'-8¾" 3'-0" LEVEL 2'-0" 3'-0" LEVEL 3'-0" 3'-0" LEVEL

101'-4½"

51'-3¾"

31'-6" SECTION-B-B

36'-10½" SECTION-A-A

NOTE-A: ¾" SLOPE TO FACE OF ABUTMENT - TYPICAL BETWEEN BEAM SEATS

1" THICKNESS OF PREFORMED EXPANSION JOINT FILLER

EXPOSED FACE OF WALL

12" x ¾" PREFORMED SEALING STRIP IN 13" x ¾" RECESS

TYPICAL DETAIL OF EXPANSION JOINT

¾" SLOPE OF BACKWALL

SEE NOTE-A

℄ EXT. GIRDER

℄ RAILING

1'-5⅝"

6"

10"

2'-0"

97°16'-39"

WP.

20'-0" R

12"

4"

4'-4" ±

10'-6"

STRAIGHT WALL

18'-8" - SECTION A-A

PLAN OF ABUTMENT #1

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 PLAN


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 966+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C	JK		CW.			


FED. RD.	STATE	PROJECT	
	OHIO		

MA H-18-17.20


363
492




1 ELEVATION OF SOUTH WINGWALL




SECTION 1-1




SECTION X-X



SECTION 2-2



SECTION 3-3



PART ELEVATION OF ABUTMENT #1

NOTE : THE CONCRETE IN THE ABUTMENT BACKWALL SHALL NOT BE PLACED UNTIL AFTER STEEL WORK IS ERECTED, BUT SHALL BE PLACED BEFORE THE DECK SLAB IS PLACED.

POROUS BACKFILL 2 FT. THICK FULL LENGTH OF ABUTMENT AND WINGWALLS, SHALL EXTEND UP TO THE UNDERSIDE OF THE APPROACH SLAB OR TO THE FINISHED GROUND SURFACE.

ALL BARS SPACED @ 2'-0 ℄ UNLESS OTHERWISE NOTED.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAILS


BRIDGE NO. MA H-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	JK		aw.			

FED. RD.	STATE	PROJECT	
	OHIO		

364
492

MA H-18-17.20



PART ELEVATION OF NORTH WINGWALL

NOTE-B

THE RAILING ON THE WINGWALLS SHALL BE CONTINUOUS FOR A MINIMUM OF TWO PANELS.

NOTE-F

1" GRAY SPONGE RUBBER PREFORMED EXPANSION JOINT FILLER MEETING THE REQUIREMENTS OF SEC. M-10.02 TYPE NO. 1. SPACE TWO PANEL LENGTHS APART. INCLUDED WITH ITEM S-14 (RAILING) FOR PAYMENT.

NOTE-G

RUSTICATION GROOVES TO EXTEND A MIN. OF ONE FOOT BELOW GROUND LEVEL.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAILS


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	JK		C.J.W.			

FED. RD.	STATE	PROJECT	
	OHIO		

365/492

MA H-18-17,20



PART ELEVATION OF ABUTMENT - #1

SECTION 4-4

DETAIL OF RUSTICATION GROOVE
SEE NOTE - G

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAILS


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C	JK		CW.			


FED. RD.	STATE	PROJECT	
	OHIO		

M A H - 18 - 17, 20

366
492



PART ELEVATION OF NORTH WINGWALL



SECTION 5-5

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAILS


BRIDGE NO. M A H-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+45.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C	JK		C.D.W			


FED. RD.	STATE	PROJECT	
	OHIO		

M A H - 18 - 17.20

367
492




SECTION 6-6




FOR NOTES AND DIMENSIONS NOT SHOWN SEE SECTION 6-6

SECTION 7-7




FOR NOTES AND DIMENSIONS NOT SHOWN SEE SECTION 6-6 AND 8-8


SECTION 10-10



SECTION 11-11



SECTION 8-8



THE REST OF THE SECTION SAME AS SECTION 8-8

SECTION 9-9

NOTE : FOOTINGS SHALL EXTEND A MINIMUM OF 3" INTO SOLID ROCK, OR TO THE ELEVATION SHOWN, WHICHEVER IS LOWER.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAILS


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	JK					


FED. RD.	STATE	PROJECT	
	OHIO		

368
492


MAH-18-17.20



SECTION 12 – 12




SECTION 13 – 13



SECTION 14 – 14

NOTE: MATERIAL BELOW THE POROUS BACKFILL SHALL BE AN IMPERVIOUS MATERIAL.



SECTION 15 – 15

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAIL


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	JK		G.O.W.			

FED. RD.	STATE	PROJECT	
	OHIO		


369
492

M A H-18-17.20






PLAN OF ABUTMENT #2



A ← ELEVATION



A ← ELEVATION OF NORTH WINGWALL

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #2 PLAN & ELEVATION


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C	JK		aw			


FED. RD.	STATE	PROJECT	
	OHIO		

370
492

M A H-18 -17.20



ELEVATION OF ABUTMENT-2



DETAIL OF EXPANSION JOINT

NOTE: THE CONCRETE IN THE ABUTMENT BACKWALL SHALL NOT BE PLACED UNTIL AFTER STEEL WORK IS ERECTED, BUT SHALL BE PLACED BEFORE THE DECK SLAB IS PLACED.

POROUS BACKFILL, 2 FT. THICK, FULL LENGTH OF ABUTMENT AND WING WALLS, SHALL EXTEND UP TO THE UNDERSIDE OF THE APPROACH SLAB OR TO THE FINISHED GROUND SURFACE.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #2 DETAILS


BRIDGE NO. MA H-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	JK					


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

371
492




SECTION A-A




FOR DIMENSIONS NOT SHOWN SEE SECTION A-A


SECTION B-B




SECTION C-C



SECTION D-D




SECTION E-E




SECTION F-F

FOR DIMENSIONS NOT SHOWN SEE SECTION C-C




SECTION G-G




FOR SPACING OF A-601 & A-602 BARS SEE ELEVATION

SECTION H-H



SECTION K-K



SECTION L-L

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #2 DETAILS


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	JK		gw.			

FED. RD.	STATE	PROJECT	
	OHIO		


M A H-18-17.20

372
492




PLAN

THESE TWO ROW OF PILES BATTERED 1:4 IN DIRECTION INDICATED




KEY PLAN



ELEVATION

PIER	DIMENSION "H"	DIMENSION "J"	DIMENSION "K"
LEFT #1	24'-6 3/4"	26'-9 1/8"	3'-5 5/8"
RIGHT #1	25'-2 3/8"	27'-5 1/2"	3'-6"
LEFT #2	26'-6 3/4"	28'-9 1/8"	3'-5 1/2"
RIGHT #2	30'-2 3/8"	32'-5 1/2"	3'-6"
LEFT #3	26'-6 3/4"	28'-9 1/8"	3'-5 1/2"
RIGHT #3	30'-2 3/8"	32'-5 1/2"	3'-6"

CARE MUST BE TAKEN IN PLACING TOP REINFORCING STEEL TO CLEAR ANCHOR BOLTS FOR BOLSTERS (PIER #3 ONLY)



SECTION B-B

SECTION A-A

DIER ELEVATIONS

DIERS	A	B	C	D	E	F	G
LEFT #1	879.23	878.49	877.76	877.02	876.29	875.56	842.00
RIGHT #1	882.96	882.21	881.46	880.71	879.95	879.20	845.00
LEFT #2	880.22	879.49	878.75	878.02	877.28	876.55	841.00
RIGHT #2	883.96	883.21	882.46	881.71	880.95	880.20	841.00
LEFT #3	881.22	880.49	879.75	879.02	878.28	877.55	842.00
RIGHT #3	884.96	884.21	883.46	882.71	881.95	881.20	842.00

NOTE: ALL PILES 12" BP 53

2" CLEARANCE ON REINFORCING STEEL UNLESS OTHERWISE NOTED.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIERS #1 #2 & #3 DETAILS


BRIDGE NO. M A H-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	R.P.S.		a.o.w.			


FED. RD.	STATE	PROJECT	
	OHIO		

373
492


MAH-18-17.20



PLAN




KEY PLAN



ELEVATION

PIER	DIMENSION		
	"H"	"J"	"K"
LEFT #4	47'-8 1/2"	49'-6 1/4"	3'-2 3/8"
RIGHT #4	50'-8 3/8"	52'-7 1/4"	3'-3 1/4"
LEFT #5	51'-1 1/2"	52'-4 1/2"	2'-10 3/8"
RIGHT #5	53'-2 3/4	54'-7 1/2"	2'-11 1/8"



SECTION B-B

SECTION A-A

NOTE
2" CLEARANCE ON REINFORCING STEEL UNLESS OTHERWISE NOTED

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER #4 & #5 DETAILS


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+48.25


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	R.P.S.		E.W.			


FED. RD.	STATE	PROJECT	
	OHIO		


374
492


M A H - 18 - 17.20











*THE FLANGE SIZE IN THE FIRST 3'-0" FROM EACH END IS THAT OF GIRDER "A" OR "C" RESPECTIVELY SEE DETAIL OF GIRDER SPLICE

ALL PIERS AND ABUTMENTS ARE ON RADIAL ℄ S. ALL GIRDERS ARE PARALLEL IN THEIR RESPECTIVE SPANS

PAINTING : AFTER ERECTION AND AFTER THE SHOP COAT HAS BEEN CLEANED AND WHERE NECESSARY REPAINTED IN ACCORDANCE WITH SEC 514 AN ADDITIONAL COAT OF THE SAME PAINT AS USED IN THE SHOP SHALL BE APPLIED TO THE ENTIRE STRUCTURE.

SHOP DRAWINGS FOR THE GIRDERS SHALL INCLUDE AN OVERALL LAYOUT WITH DIMENSIONS SHOWING THE RELATIVE UNLOADED VERTICAL POSITION OF EACH GIRDER OR GIRDER SEGMENT WITH RESPECT TO THE OTHERS IN THE SAME GIRDER LINE AND WITH RESPECT TO A FULL LENGTH BASE OR WORK LINE TAKING IN THE ACCOUNT (CAMBER AND) THE PROFILE OF THE HIGHWAY.

SHOP ASSEMBLY : AT LEAST THREE ADJACENT GIRDER SEGMENTS SHALL BE ASSEMBLED IN THE SHOP IN THEIR CORRECT UNLOADED POSITIONS AS SHOWN ON THE SHOP DRAWING LAYOUT REQUIRED IN THE ABOVE NOTE, FOR REAMING OF HOLES FOR THE GIRDER SPLICES.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING PLAN


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+40.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	A.C.		C.W.			

FED. RD.	STATE	PROJECT	
	OHIO		

M A H-18-17, 20

375
492



CAMBER & DEFLECTION TABLE

	INTERIOR SPANS		END SPANS	
	INT. BEAMS	FACIA BEAMS	INT. BEAMS	FACIA BEAMS
DEFLECTION DUE TO WEIGHT OF STEEL	0.15	0.25	0.13	0.20
DEFLECTION DUE TO REMAINING DEAD LOAD	0.70	1.00	0.62	0.80
CONVEXITY REQUIRED FOR VERTICAL CURVE	0.00	0.00	0.00	0.00
SUM OF DEFLECTIONS & CONVEXITY	0.85	1.25	0.75	1.00
REQUIRED CAMBER	1"	1¼"	1"	1"

GIRDER SPLICE DETAIL
(⅞" ϕ HIGH STRENGTH BOLTS)

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SLAB & FRAMING DETAILS


BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	AC		C.D.S.			


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


376
492




TRANSVERSE SECTION



SECTION X-X



SECTION SHOWING BRACING OVER ℄ OF PIERS & AT ℄ OF SPLICES




SECTION C-C


FINISHED GRADES


SEE PLAN INDICATING SLOPE OF FINISHED SLAB

STATION	A	B	C	D*	STATION	A	B	C	D*
962+50.00	881.78	885.44	888.82	887.86	966+00	885.28	888.73	891.17	
962+75	882.01	885.66	888.13	888.09	966+25	885.70	888.81	891.22	
963+00	882.24	885.91	889.56	888.36	966+50	886.15	889.20	891.31	
963+25	882.48	886.15	889.51		966+53.66	886.22	889.23	891.31	
963+35.52	882.58	886.24	889.92		966+75	886.60	889.44	891.35	
963+50	882.71	886.35	890.05		967+00	887.04	889.67	891.39	
963+75	882.95	886.61	890.29		967+25	887.50	889.91	891.44	
964+00	883.18	886.85	890.54		967+50	887.94	890.14	891.48	
964+25	883.42	887.09	890.75		967+59.68	888.11	890.23	891.50	
964+41.09	883.58	887.19	890.88		967+75	888.38	890.36	891.52	
964+50	883.65	887.32	890.99		968+00	888.83	890.61	891.57	
964+75	883.89	887.56	891.22		968+25	889.28	890.85	891.61	891.05
965+00	884.12	887.79	891.46		968+44.68	889.63	891.03	891.63	891.24
965+25	884.36	888.03	891.69						
965+47.62	884.57	888.22	891.88						
965+50	884.60	888.26	891.89						
965+75	884.82	888.50	892.05						



PLAN INDICATING SLOPE OF FINISHED SLAB






BAR STAGGERING DETAIL OVER PIERS

NOTES:

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE CONCRETE OF THE DECK SLAB, THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS, BETWEEN TRANSVERSE CONST. JOINTS WHICH ARE PARALLEL TO TRANSVERSE REINF. STEEL AND ARE LOCATED NEAR THE ℄ OF ANY SPAN.

SLAB THICKNESS SHOWN INCLUDES 1" MONOLITHIC WEARING SURFACE.



MEDIAN STRIP DETAIL

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SLAB DETAILS

BRIDGE NO. MAH-18-1623
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+48.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	A C		ew			

FED. RD.	STATE	PROJECT	
	OHIO		

377
492

MAH-18-17.20

RADIOGRAPHIC EXAMINATION OF WELDS

THIS WORK SHALL CONSIST OF THE PERFORMANCE AND INTERPRETATION OF A RADIOGRAPHIC EXAMINATION OF BUTT WELDS AS REQUIRED BY THESE SPECIFICATIONS. IT SHALL INCLUDE THE PREPARATION AND POSITIONING OF WELDS FOR EXAMINATION, THE RADIOGRAPHING OF WELDS, THE PROCESSING AND EXAMINATION OF RADIOGRAPHS, THE INTERPRETATION OF RADIOGRAPHS FOR COMPLIANCE WITH THESE SPECIFICATIONS, AND THE PERFORMANCE AND INTERPRETATION OF ANY RETAKES OF RADIOGRAPHS REQUIRED FOR WELDS MADE TO REPLACE UNSATISFACTORY WELDS.

APPROVAL OF DIRECTOR

THE CONTRACTOR SHALL FURNISH EVIDENCE, ACCEPTABLE TO THE DIRECTOR, OF THE ADEQUACY OF THE EQUIPMENT TO BE USED AND THE COMPETENCE OF THE PERSONNEL.

THE INTERPRETATION OF RADIOGRAPHS AND THE CORRECTION OF DEFECTIVE WELDS SHALL BE SUBJECT TO THE APPROVAL OF THE DIRECTOR.

SCOPE OF EXAMINATION

BY MEANS OF RADIOGRAPHIC EXAMINATION, THE CONTRACTOR SHALL FURNISH EVIDENCE OF THE ACCEPTABLE QUALITY OF THE BUTT WELDS OF ALL GIRDERS. THE PARTS OF THESE MEMBERS TO BE RADIOGRAPHED ARE AS FOLLOWS:

1. THE COMPLETE BUTT WELDS IN THE FLANGES OF EACH GIRDER EXCEPT THE BOTTOM FLANGE OVER THE BEARING DEVICES.
2. ONE FOOT AT EACH END OF EACH OF THE WEB SPLICE WELDS.

THE SHOP EXAMINATION OF THE BUTT WELDS OF THE FLANGE PLATES AND OF THE WEB PLATES SHALL BE DETERMINED TO BE ACCEPTABLE BEFORE THESE FLANGE AND WEB PLATES ARE ASSEMBLED AND WELDED TO FORM THE GIRDERS. THE EXAMINATION OF FIELD WELDS SHALL BE MADE AS SOON AS PRACTICABLE AFTER WELDING AT EACH FIELD SPLICE IS COMPLETED.

WELD CONDITION

ALL WELDED JOINTS WHICH ARE TO BE RADIOGRAPHED SHALL BE FREE OF PAINT, SCALE AND GREASE AND SHALL BE GROUND FREE OF ALL WELD RIPPLES AND SURFACE IRREGULARITIES ON BOTH SIDES. THE DIRECTION OF GRINDING SHALL BE PERPENDICULAR TO THE LENGTH OF THE WELD. THE WELDS SHALL BE GROUND TO SUCH A DEGREE THAT THE RESULTING RADIOGRAPHIC CONTRAST, DUE TO REMAINING IRREGULARITIES, CANNOT MASK OR BE CONFUSED WITH THAT OF ANY OBJECTIONABLE DEFECT AND THAT THE WELD SURFACE WILL MERGE SMOOTHLY INTO THE PLATE SURFACE. UNLESS SPECIFIED TO BE GROUND FLUSH, THE FINISHED SURFACE OF THE REINFORCEMENT MAY HAVE A CROWN EQUAL TO ONE-EIGHTH THE THICKNESS OF THE METAL BUT NOT MORE THAN 1/8 INCH.

RADIOGRAPHIC TECHNIQUE

THE WELD SHALL BE RADIOGRAPHED WITH A TECHNIQUE WHICH WILL DETERMINE QUANTITATIVELY THE SIZE OF DEFECTS WITH THICKNESS EQUAL TO OR GREATER THAN 2 PER CENT OF THE THICKNESS OF THE BASE METAL. IN CASE IF A WELD JOINING PLATES OF UNEQUAL THICKNESS, BOTH PLATES MUST BE RADIOGRAPHED AT 2 PER CENT SENSITIVITY TOGETHER OR SINGLY, WITH THE WELD JUNCTION EVIDENT IN BOTH VIEWS.

TO DETERMINE WHETHER THE RADIOGRAPHIC TECHNIQUE EMPLOYED IS DETECTING DEFECTS OF A THICKNESS EQUAL TO OR GREATER THAN 2 PER CENT OF THE THICKNESS OF THE BASE MATERIAL, THICKNESS GAGES OR PENETRAMETERS OF THE TYPE HEREINAFTER SPECIFIED SHALL BE PLACED ON THE SIDE OF THE WELDED PLATE NEAREST THE SOURCE OF RADIATION AT AN EXTREME EDGE OF THE RADIOGRAPHIC PLATE OR FILM.

THE MATERIAL OF THE PENETRAMETER SHALL BE SUBSTANTIALLY THE SAME AS THAT OF THE WELDED PLATE.

THE THICKNESS OF THE PENETRAMETER SHALL BE NOT MORE THAN 2 PER CENT OF THE THICKNESS OF THE PLATE EXCLUSIVE OF ANY WELD REINFORCEMENT. PENETRAMETERS DESIGNED FOR INCREMENTS OF 1/8" OF PLATE THICKNESS ARE ACCEPTABLE.

IN EACH PENETRAMETER THERE SHALL BE THREE HOLES WITH DIAMETERS EQUAL RESPECTIVELY TO TWO, THREE AND FOUR TIMES THE PENETRAMETER THICKNESS, BUT IN NO CASE SHALL LESS THAN 1/16" DIAMETER BE USED.

EACH PENETRAMETER SHALL CARRY AN IDENTIFYING NUMBER REPRESENTING IN TWO SIGNIFICANT FIGURES THE MINIMUM THICKNESS IN INCHES OF THE PLATES FOR WHICH IT MAY BE USED. PENETRAMETERS MAY BE ESTABLISHED FOR DIFFERENCES IN THICKNESS NOT TO EXCEED 1/8" SO THAT A SET OF PENETRAMETERS VARYING FOR INCREMENTS OF PLATE THICKNESS OF 1/8" WILL BE ADEQUATE TO SERVE PLATES HAVING THICKNESSES BETWEEN THESE 1/8" DIMENSIONS.

THE IMAGES OF IDENTIFYING NUMBERS AND THE HOLES OF EACH PENETRAMETER MUST APPEAR CLEARLY ON THE RADIOGRAPH TO ESTABLISH THE 2 PER CENT SENSITIVITY.

FOR PLATES UP TO AND INCLUDING 2 1/2" IN THICKNESS, EACH PENETRAMETER SHALL BE 1 1/2" LONG AND 1/2" WIDE. FOR PLATES THICKER THAN 2 1/2" EACH PENETRAMETER SHALL BE 2 1/4" LONG AND 1" WIDE.

THE FILM DURING EXPOSURE SHALL BE AS CLOSE TO THE WELD AS PRACTICABLE. IF POSSIBLE, THIS DISTANCE SHALL BE NOT GREATER THAN 1 INCH. IN ANY EVENT, THE RATIO

DISTANCE FROM SOURCE OF RADIATION TO WELD SURFACE TOWARD RADIATION

DISTANCE FROM WELD SURFACE TOWARD RADIATION TO FILM

SHALL BE AT LEAST 7 TO 1.

ALL RADIOGRAPHS SHALL BE FREE FROM EXCESSIVE MECHANICAL PROCESSING DEFECTS WHICH WOULD INTERFERE WITH PROPER INTERPRETATION OF THE RADIOGRAPH.

IDENTIFICATION MARKERS, THE IMAGES OF WHICH WILL APPEAR ON THE FILM, SHALL BE PLACED ADJACENT TO THE WELD AND THEIR LOCATIONS SHALL BE ACCURATELY AND PERMANENTLY MARKED ON THE OUTSIDE SURFACE NEAR THE WELD SO THAT A DEFECT APPEARING ON THE RADIOGRAPH MAY BE ACCURATELY LOCATED.

THE SIZE OF FILM TO BE USED SHALL BE MIN. 4" WIDE X 15" LONG UNLESS PERMISSION TO USE A DIFFERENT SIZE IS OBTAINED IN WRITING FROM THE DIRECTOR.

STANDARDS OF ACCEPTABILITY

THE ACCEPTABILITY OF THE WELDS EXAMINED BY RADIOGRAPHY SHALL BE JUDGED BY THE FOLLOWING STANDARDS:

(1) CRACKS:

DEFINITION - A DISCONTINUITY RESULTING FROM A VERY NARROW SEPARATION OF METAL.

STANDARD --- NO WELD CONTAINING CRACKS REGARDLESS OF LENGTH, SIZE OR LOCATION SHALL BE CONSIDERED ACCEPTABLE.

(2) GAS POROSITY:

DEFINITION - GAS POCKETS OR VOIDS IN METAL.

STANDARD --- THE MAXIMUM DIMENSION OF ANY INDIVIDUAL GAS POCKET SHALL NOT EXCEED 1/8 INCH. THE MAXIMUM ACCUMULATION OF GAS POCKETS SHALL NOT EXCEED THAT SHOWN IN THE "POROSITY STANDARDS" OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS.

(3) SLAG INCLUSIONS:

DEFINITION - NON-METALIC, SOLID MATERIAL ENTRAPPED IN WELD OR BETWEEN WELD METAL AND BASE METAL.

STANDARD -A.-ELONGATED SLAG INCLUSION; NO ELONGATED SLAG INCLUSION SHALL EXCEED TWO-THIRDS OF THE THICKNESS OF THE THINNER PLATE OF THE JOINT IN LENGTH AND 1/16" IN WIDTH, EXCEPT THAT REGARDLESS OF THE PLATE THICKNESS NO SUCH INCLUSION SHALL BE LONGER THAN 3/4" AND EXCEPT THAT NO SUCH INCLUSION WHICH IS SHORTER THAN 1/4" SHALL BE CAUSE FOR REJECTION.

B.-ISOLATED SLAG INCLUSIONS; IN ANY 12 INCH LENGTH OF WELD THE MAXIMUM WIDTH OF ANY ISOLATED SLAG INCLUSION SHALL NOT EXCEED 1/8" INCH, THE SUMMATION OF LENGTHS OF ISOLATED SLAG INCLUSIONS SHALL NOT EXCEED 1 INCH, AND THERE SHALL BE NO MORE THAN FOUR ISOLATED INCLUSIONS OF THE MAXIMUM WIDTH OF 1/8 INCH. ANY TWO SUCH INCLUSIONS SHALL BE SEPARATED BY AT LEAST 2 INCHES OF SOUND WELD METAL.

(4) INCOMPLETE FUSION:

DEFINITION - FAILURE OF WELD METAL TO FUSE COMPLETELY WITH THE BASE METAL OR PRECEEDING BEADS.

STANDARD --- NO INDIVIDUAL LACK OF FUSION SHALL EXCEED 1/2 INCH IN LENGTH. IN ANY 12 INCH LENGTH OF WELD, THE SUMMATION OF LENGTHS OF LACK OF FUSION SHALL NOT EXCEED 3/4 INCH AND INDIVIDUAL DEFECTS SHALL BE SEPARATED BY AT LEAST 6 INCHES OF SOUND METAL.

(5) INCOMPLETE PENETRATION:

DEFINITION - ROOT PENETRATION WHICH IS LESS THAN COMPLETE OR FAILURE OF A ROOT PASS AND A BACKING PASS TO FUSE WITH EACH OTHER.

STANDARD --- NO INDIVIDUAL LACK OF PENETRATION SHALL EXCEED 1/2 INCH IN LENGTH. IN ANY 12 INCH LENGTH OF WELD, THE SUMMATION OF LENGTHS OF LACK OF PENETRATION SHALL NOT EXCEED 3/4 INCH AND INDIVIDUAL DEFECTS SHALL BE SEPARATED BY AT LEAST 6 INCHES OF SOUND METAL.

REPAIR OF DEFECTIVE WELDS

DEFECTIVE WELDS SHALL BE REPAIRED BY CHIPPING OR MELTING OUT SUCH DEFECTS FROM ONE OR BOTH SIDES OF THE JOINT AS REQUIRED, REMOVING ONLY SUFFICIENT WELD METAL TO CORRECT THE DEFECT. THE JOINT SHALL THEN BE REWELDED AND AGAIN RADIOGRAPHED.

ADDITIONAL RADIOGRAPHS

WHEREVER AN UNACCEPTABLE WELD OCCURS, A RADIOGRAPH SHALL BE MADE OF THE ADJOINING 12 INCH LENGTHS OF WELD TO DETERMINE IF THE FLAWS EXTEND BEYOND THE LIMITS OF THE ORIGINAL RADIOGRAPH. IF UNACCEPTABLE FLAWS OCCUR IN THESE ADJOINING LENGTHS OF WELD, THESE DEFECTIVE WELDS SHALL BE REPAIRED AND THIS ENTIRE PROCEEDURE REPEATED FOR THE NEXT ADJOINING 12 INCH LENGTH OF WELD.

CUSTODY OF RADIOGRAPHS

AS SOON AS THE RADIOGRAPHING OF THE WELDMANTS ON THE FULL LENGTH OF EACH FLANGE OR WEB PLATE BETWEEN FIELD SPLICES HAS BEEN COMPLETED, THE CONTRACTOR SHALL SEND TO THE STATE THE PROPOSED CONTACT FILM (THAT FILM CLOSEST TO THE SOURCE OF RADIATION) OF ALL ORIGINAL AND RETAKE RADIOGRAPHS. THESE RADIOGRAPHS SHALL BE ACCOMPANIED BY A CERTIFICATION FROM THE CONTRACTOR THAT THE RADIOGRAPHIC EXAMINATION WAS PERFORMED IN CONFORMANCE WITH THESE SPECIFICATIONS. THE RADIOGRAPHS SHALL BECOME THE PROPERTY OF THE STATE. EACH RADIOGRAPH SHALL BE CLEARLY IDENTIFIED TO SHOW THE LOCATION ON THE STRUCTURE AT WHICH IT WAS TAKEN. UNACCEPTABLE DEFECTS SHALL BE IDENTIFIED IN EACH RADIOGRAPH IN WHICH THEY OCCUR AND THE REPAIR OR REPLACEMENT OF EACH UNACCEPTABLE WELD DEFECT SHALL BE NOTED AND IDENTIFIED.

REPORT OF COST

AFTER THE COMPLETION OF THE RADIOGRAPHIC INSPECTION OF WELDS, THE CONTRACTOR SHALL FURNISH THE STATE A COMPLETE REPORT OF THE COST OF PERFORMING THIS WORK, SEPARATED INTO THE ITEMS MENTIONED IN THE FOLLOWING PARAGRAPH.

BASIS FOR PAYMENT

PAYMENT FOR THIS WORK, INCLUDING ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS, SHALL BE INCLUDED IN THE UNIT PRICE BID FOR S-7, STRUCTURAL STEEL.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RADIOGRAPHIC NOTES

BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 TO STA. 968+46.25


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	DV		DG,S,	DHC.		


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17,20


378
492

1/4" GREY SPONGE RUBBER PREFORMED EXPANSION JOINT FILLER MEETING THE REQUIRMENTS OF SEC. M-10.02 TYPE NO 1. SPACE TWO PANEL LENGTHS APART (INCLUDED WITH ITEM 5-14 FOR PAYMENT)






SECTION A-A
SCUPPER



SECTION C-C
DETAIL OF EXPANSION JOINT
(AT END POSTS ONLY)

PLAN



SECTION THRU GUARD RAIL
(SEE STANDARD DWG. I-15. NO. 2-A)

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

DRAINAGE & GUARD RAIL DETAILS

BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA 968+46.25


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DHC	AC		C.J.W			

FED. RD.	STATE	PROJECT	
	OHIO		

379
492

MAH-18-17.20

WEST



SOUTH ELEVATION


EAST

2" DIA. CONDUIT CONTINUOUS THRU. SLAB. SEE ROADWAY LIGHTING FOR DETAILS.

NOTE A:
¼" GREY SPONGE RUBBER PREFORMED EXPANSION JOINT FILLER MEETING THE REQUIRMENTS OF SECTION M-10.02, TYPE 1. TO BE PAID FOR AS PART OF ITEM S-14.

NOTE B:
TYPE "A" RAILING - 4" O.D. x 5/16 WALL ALUMINUM TUBE. RAILING SHALL BE CONTINUOUS THRU FIRST POST AT EACH END OF SUPERSTRUCTURE.

EAST




NORTH ELEVATION

WEST

RAILING SHALL BE CONTINUOUS FOR A MIN. OF TWO PANELS ON THE WINGWALLS


CONDUIT EXPANSION FITTING. SEE ROADWAY LIGHTING DETAILS.

2" DIA. STD. STEEL PIPE DRAIN AT THE ABUT. ENDS OF EACH BULB ANGLE AS INDICATED ON PLAN. WELD STUB END FULL PERIMETER TO BULB ANGLE




NOTE:
TYPICAL FOR SOUTH OPP HAND FOR NORTH SIDE.

DETAIL OF LIGHT STANDARD SUPPORT



SECTION A-A

LIGHT STANDARD	DIMENSION "1"	DIMENSION "2"
A	12'-9½"	5'-6½"
B	15'-7¾"	8'-4¾"
C	12'-9½"	5'-6½"
D	15'-7¾"	8'-4¾"
E	15'-7¾"	8'-4¾"



ANCHOR BOLT DETAIL

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RAILING DETAILS

BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	A.C.		cw.			


REINFORCING STEEL SCHEDULE


MARK	NO.	LENGTH	WEIGHT	SHAPE
WEST ABUTMENT.				
WA-501	15	12'-3"	186	ST.
WA-502	33	8'-6"	293	ST.
WA-503	15	4'-5"	68	BT.
WA-504	4	11'-10	49	BT.
WA-505	15	6'-0"	94	ST.
WA-506	2	9'-10"	21	BT.
WA-507	1	13'-1"	14	ST.
WA-508	11	8'-11	102	ST.
WA-509	29	4'-0"	121	ST.
WA-510	28	18'-4"	536	ST.
WA-511	3	14'-0"	44	ST
WA-512	122	3'-11"	497	BT.
WA-513	4	16'-1"	67	ST.
WA-514	2	13'-2"	27	ST.
WA-515	2	16-4	34	BT.
WA-516	2	2'-1"	4	BT.
WA-517	2	2'-9"	6	BT.
WA-518	2	3'-3"	7	BT.
WA-519	2	3'-7"	7	BT.
WA-520	2	3'-9"	8	BT.
WA-521	50	3'-10"	200	BT.
WA-522	62	6'-1"	394	BT.
WA-523	19	5'-0"	99	ST.
WA-524	12	14'-7"	182	ST.
WA-525	84	5'-5"	474	BT.
WA-526	3	13'-6"	42	ST.
WA-527	4	39'-6	156	ST.
WA-528	3	23'-8"	74	ST
WA-529	8	28'-5"	238	ST.
WA-530	16	9'-10"	164	ST.
WA-531	38	5'-4"	211	ST.
WA-532	7	8'-9	64	BT.
WA-533	11	8'-3	95	BT.
WA-534	109	10'-7"	1203	BT.
WA-535	30	26'-8	835	ST.
WA-536	11	8'-2"	94	ST.
WA-537	2	5'-11"	12	BT.
WA-538	2	4'-10"	10	BT.
WA-539	22	15'-2"	345	ST.
WA-540	5	24'-0"	200	ST.
WA-541	17	13'-2"	233	ST.
WA-542	10	19'-2"	200	ST.
WA-543	5	32'-8"	170	ST.
WA-544	19	16'-2"	321	ST.
WA-545	52	25'-6"	1383	ST.
WA-546	13	21'-6"	292	ST.
WA-547	16	7'-1"	118	ST.
WA-548	3	9'-6"	30	ST.
WA-549	10	7'-5"	77	ST.
WA-550	132	27'-4"	3763	ST.
WA-551	32	11'-6"	384	ST.
WA-552	29	32'-4"	978	ST.
WA-553	20	25'-2"	525	ST.
WA-554	2	21'-0"	44	ST.
WA-555	10	32'-3"	336	ST.
WA-556	1	38'-7"	40	ST
WA-557	2	32'-3"	67	BT.
WA-558	28	26'-0"	759	ST
WA-559	2	22'-4"	45	ST
WA-560	15	6'-3"	98	BT.
WA-561	13	10'-11"	148	BT.
WA-562	8	29'-3"	244	ST.
WA-563	2	3'-4"	7	ST
WA-601	42	8'-8"	548	ST
WA-602	21	11'-2"	352	BT
WA-603	5	9'-3"	68	BT
WA-604	11	8'-9"	145	BT
WA-605	26	16'-7"	648	BT
WA-606	73	18'-4"	2011	BT
WA-607	10	14'-6"	217	ST
WA-608	24	9'-8"	349	ST.
WA-609	4	20'-3"	122	ST.
WA-610	17	7'-5"	189	BT
WA-701	14	15'-3"	436	ST.
WA-702	41	9'-8"	810	ST.


MARK	NO.	LENGTH	WEIGHT	SHAPE
WA-801	95	16'-3"	4124	ST.
WA-802	32	17'-9"	1517	ST
WA-803	53	14'-8"	2076	ST
WA-804	17	18'-0"	817	ST
WA-901	21	8'-7"	613	BT
WA-902	21	15'-8"	1119	ST
WA-1001	17	13'-4"	975	BT
WA-1002	80	17'-8"	6093	ST.
WA-1003	35	14'-5"	2209	ST.
WA-1101	25	15'-8"	2081	ST.
WA-1102	10	10'-10"	576	BT.
WA-1103	10	15'-10"	841	BT.
WA-1104	17	9'-4"	843	BT
WA-1105	80	17'-8"	1510	ST
WA-1106	81	6'-10"	2936	BT.
WA-1107	63	11'-10"	3960	BT.
WA-1108	17	12'-10"	1159	BT.
WA-1109	4	10'-10"	230	BT
WA-1110	4	15'-10"	336	BT.
TOTAL WEST ABUT.			57,423	
EAST ABUTMENT.				
A-501	52	26'-0"	1410	ST.
A-502	48	25'-5"	1272	ST.
A-503	4	5'-10"	24	ST.
A-504	2	38'0"	79	ST.
A-505	2	7'-1"	15	ST.
A-506	2	4'-10"	10	BT
A-507	2	5'-11"	12	BT
A-508	108	7'-8"	863	BT.
A-509	86	8'-9"	785	BT
A-510	60	5'-6"	344	BT.
A-511	4	7'-8"	32	ST.
A-512	12	3'-6"	44	ST
A-513	4	26'-7"	111	ST
A-514	27	4'-6"	117	ST.
A-515	2	8'-2"	17	ST
A-516	2	11'-1"	23	ST.
A-517	2	5'-0"	10	ST.
A-518	14	10'-0"	146	BT
A-519	14	4'-6"	66	ST.
A-520	4	10'-8"	45	BT.
SERIES OF	2 SETS, OF 3 =	VARY 9'-11"-13'-11" INCR. 2'-0"	75	ST.
A-521	6-BARS			
SERIES OF	2-SETS, OF 3 =	VARY 5'-6"-9'-6" INCR. 2'-0"	50	ST.
A-522	6-BARS			
A-523	6	19'-0"	119	ST
A-524	6	14'-4"	90	ST.
A-525	32	4'-5"	147	BT.
A-526	16	10'-11"	182	ST.
SERIES OF	4-SETS OF 5 =	VARY 2'-9"-4'-9" INCR. 6"	78	ST.
A-527	20-BARS			
A-528	72	3'-5"	257	BT.
A-529	20	6'-1"	127	BT.
A-530	16	12'-6"	209	ST.
A-531	8	17'-0"	142	ST.
A-532	4	14'-6"	60	ST
A-533	4	17'-0"	71	BT.
A-534			OPEN	
A-535	2	2'-2"	5	BT.
A-536	2	2'-6"	5	BT.
A-537	2	2'-10"	6	BT.
A-538	2	3'-1"	6	BT.
A-539	2	3'-3"	7	BT.
A-540	2	3'-5"	7	BT.
A-541	2	3'-7"	7	BT.
A-542	2	3'-8"	8	BT.
A-543	2	3'-9"	8	BT.
A-544	16	3'-10"	64	BT.

MARK	NO.	LENGTH	WEIGHT	SHAPE
A-601	27	18'-3"	740	BT.
A-602	72	20'-4"	2199	BT.
TOTAL EAST ABUT.			10,094	
TOTAL ABUTMENTS			67,517	
PIERS.				
P-501	87	27'-10"	2526	ST.
P-502	174	29'-4"	5323	ST
P-503	87	30'-6"	2768	ST.
P-504	56	9'-0"	526	BT.
P-505			OPEN	
P-506			OPEN	
P-507	394	23'-0"	9452	ST.
P-508	394	7'-4"	3014	BT.
P-509			OPEN	
P-510	174	19'-0"	3448	ST.
P-511	29	31'-0"	938	ST.
P-512	29	31'-9"	960	ST.
P-513	58	33'-0"	1996	ST.
P-514	58	36'-9"	2223	ST.
P-515	84	9'-10"	862	BT.
P-601	40	24'-6"	1472	ST.
P-602	40	25'-0"	1502	ST.
P-603	20	26'-0"	781	ST
P-604	20	12'-6"	376	BT.
SERIES OF P-605	20-SETS OF 31' = 620-BARS	VARY 9'-0"-14'-0" INCR. 2"	10,709	BT.
P-606	620	7'-6"	6,984	BT.
P-607	580	5'-11"	5154	BT.
P-608	52	27'-8"	2161	ST.
P-609	66	32'-8"	3238	ST.
P-610	20	13'-1"	394	BT.
P-801	264	11'-8"	8224	ST.
P-1101	80	25'2	10,697	ST
P-1102	160	21'-7"	18,348	BT
P-1103	112	12'-8"	7,537	ST
P-1104	80	25'-9"	10,945	ST
TOTAL PIERS			122,558	
SLAB				
S-501	314	4'-5"	4210	BT
S-502	1786	5'-7"	10,401	BT
S-503	1786	5'-7"	10,401	BT
S-504	893	4'-4"	4036	BT.
S-505	893	5'-5"	5045	BT.
S-506	893	4'-6"	4191	BT.
S-507	893	5'-7"	5200	BT.
S-601	1320	39'-8"	78645	ST.
S-602	1350	41'-4"	83,817	ST
S-603	375	42'-0"	23,657	ST.
SERIES OF S-604	SET OF 38-BARS	VARY 4'-0"-31'-9" INCR. 3"	1020	ST.
SERIES OF S-605	SET OF 39-BARS	VARY 4'-0"-32'-6" INCR. 3"	1069	ST.
SERIES OF S-606	SET OF 50-BARS	VARY 4'-0"-28'-6" INCR. 6"	1220	ST.
SERIES OF S-607	SET OF 51-BARS	VARY 4'-0"-29'-0" INCR. 6"	1264	ST.
S-608	1786	47'-8"	127,869	ST.
S-609	80	8'-0"	961	ST.

MARK	NO.	LENGTH	WEIGHT	SHAPE
S-610	20	9'-7"	288	BT.
S-701	1786	46'-4"	169,144	ST.
TOTAL SLAB			532,438	
RAILING *				
R-501	8	12'-5"		ST.
R-502	292	15'-4"		ST.
R-503	8	10'-9"		ST.
R-504	8	16'-8"		ST.
R-505	4	15'-11"		ST
R-506	8	7'-6"		ST
R-507	8	11'-8"		ST.
R-508	8	14'-4"		ST
R-509	4	12'-8"		ST.
R-510	4	10'-5"		ST.
R-511	20	12'-10"		BT.
R-512	10	11'-5"		BT.
REPLACEMENT BARS.				
RE-501	6	5'-7" *		ST.
RE-601	19	5'-11"		ST.
RE-701	9	6'-3"		ST
RE-801	1	6'-6"		ST.
RE-1001	1	7'-3"		ST.
RE-1101	4	7'-6"		ST.
GRAND TOTAL			722078	LBS










FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18-17.20


380
492




















































NOTES: BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED AND THE FIRST TWO DIGITS WHERE FOUR ARE USED INDICATE THE BAR SIZE NUMBER. FOR EXAMPLE A-501 IS A NO. 5 SIZE BAR AND P-1101 IS A NO. 11 SIZE BAR.

REPLACEMENT BARS : IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SECTION S-4.02 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.

* RAILING REINFORCEMENT BARS WILL BE INCLUDED AS PART OF ITEM S-14 FOR PAYMENT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

REINFORCING SCHEDULE

BRIDGE NO. MAH-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.	JK		C.O.W.			

FED. RD.	STATE	PROJECT	
	OHIO		

M A H - 18 - 17.20

381
492



TABLE OF BEAM LENGTHS

MARK	LENGTH	MARK	LENGTH	MARK	LENGTH	MARK	LENGTH	MARK	LENGTH	MARK	LENGTH
A-1	81.185'	B-1	101.243'	C-1	101.243'	D-1	101.573'	E-1	102.786'	F-1	83.334'
A-2	81.905'	B-2	102.139'	C-2	102.139'	D-2	102.407'	E-2	103.391'	F-2	83.648'
A-3	82.622'	B-3	103.035'	C-3	103.035'	D-3	103.241'	E-3	103.997'	F-3	83.962'
A-4	83.340'	B-4	103.931'	C-4	103.931'	D-4	104.074'	E-4	104.602'	F-4	84.275'
A-5	84.057'	B-5	104.827'	C-5	104.827'	D-5	104.908'	E-5	105.207'	F-5	86.589'
A-6	84.775'	B-6	105.723'	C-6	105.723'	D-6	105.742'	E-6	105.813'	F-6	84.903'
A-7	85.245'	B-7	106.305'	C-7	106.305'	D-7	106.284'	E-7	106.206'	F-7	85.106'
A-8	85.982'	B-8	107.224'	C-8	107.224'	D-8	107.139'	E-8	106.827'	F-8	85.428'
A-9	86.719'	B-9	108.143'	C-9	108.143'	D-9	107.995'	E-9	107.448'	F-9	85.750'
A-10	87.456'	B-10	109.063'	C-10	109.063'	D-10	108.850'	E-10	108.069'	F-10	86.072'
A-11	88.193'	B-11	109.982'	C-11	109.982'	D-11	109.705'	E-11	108.690'	F-11	86.394'
A-12	88.930'	B-12	110.901'	C-12	110.900'	D-12	110.561'	E-12	109.311'	F-12	86.716'

GEOMETRIC LAYOUT

NOTE: ALL PIER AND ABUTMENT CENTERLINES ARE ON RADIAL LINES. ALL BEAMS ARE PARALLEL IN THEIR RESPECTIVE SPANS.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GEOMETRIC LAYOUT

BRIDGE NO. MA H-18-1823
OVER MILL CREEK POND
YOUNGSTOWN, MAHONING COUNTY
STA. 962+48.25 To STA. 968+46.25

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.H.C.		JK	RAH			

FED. RD.	STATE	PROJECT	
	OHIO		

382
492

MAH-18-17.26

DAM

MILL CREEK POND

EXISTING ℄ MARSHALL STREET

1+00 ℄ PROPOSED MARSHALL ST. 2+00

BEGIN APPROACH SLAB STA. 50+58.26

CURVE DATA
Δ = 60°-43'-03" | D = 11°-00'-00"
D_c = 5°-30'-00" | L_s = 813.68'
R_c = 1041.74 | L_c = 172.95
L_c = 703.95

PROPOSED STRUCTURE
TYPE - CONTINUOUS STEEL BEAM, WITH REINFORCED CONCRETE DECK AND CONCRETE SUB-STRUCTURE
SPAN - 56'-0" 70'-0" 56'-0" % BRGS.
ROADWAY - 48'-F/F CURB 5'-0" SIDEWALK BOTH SIDES
LOAD FREQUENCY - CF 2000 - ADEQUATE FOR A.A.S.H.O. ALTERNATE LOADING
SKEW - 5°-37'-35" L.F.
WEARING SURFACE - 1" MONOLITHIC
APPROACH SLAB - 25' LONG AS-1-54
SUPERELEVATION - NONE
TRAFFIC COUNT 22,400 ADT 1979

ACCELERATION LANE

BERM

CURB

10.57 MIN. CLEAR.

℄ PROPOSED GLENWOOD AVENUE RELOCATION

℄ EXISTING GLENWOOD AVE.

84°-22'-25"

STA. 969+31.98 = STA. 50+00.00

ST. 969+70.01

PT. MIN. CLEARANCE

10.95'

0.95'

℄ WEST-BOUND LANES

℄ SURVEY OF STATE ROUTE #18

℄ EAST-BOUND LANES

ENTRANCE RAMP ℄ (FUTURE)

END APPROACH SLAB STA. 48+71.74

MIN. CLEAR. 15.00 REQUIRED 15.06 ACTUAL

EL. 886.06

STA. 50+58.26 EL. 909.66

EL. 886.53

EL. 886.69

EL. 911.07

7.58% GRADE

MIN. CLEAR. 15.00 REQUIRED 15.06 ACTUAL

25° NORMAL

100' V.C.

EL. 921.66

P.V.I. STA. 49+00

EL. 923.49

STA. 48+71.74

+6.54% GRADE

902.71
306.50
910.29
914.08
BRIDGE LIMITS
917.87
921.53
924.94

50+00
49+00

6' SW | 7' | 40' | 7' | 6' SW

TYPICAL SECTION
EXISTING GLENWOOD AVE.

FOUNDATION SOUNDINGS

FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF SOIL SAMPLING SOUNDINGS MADE AT THE SITE, THIS SOUNDING INFORMATION MAY BE INSPECTED IN THE OFFICE OF THE BUREAU OF BRIDGES IN COLUMBUS, OR IN THE DIVISION OFFICE, BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THEREOF.

SLOPE PROTECTION

I-10 CRUSHED AGGREGATE SLOPE PROTECTION AT SOUTH ABUTMENT TO EXTEND FROM FACE ABUTMENT TO TOE OF SLOPE FOR FULL WIDTH OF BRIDGE PLUS 3 FT. ON EACH SIDE AND PARALLEL WITH ℄ BRIDGE.

889.67 | 890.14 | 890.61 | 891.05 | 891.55 | 892.02 | 892.49 | 892.96 | 893.43

940 / 920 / 900 / 880

EXISTING PROFILE

MIN. CLEAR. 15.00 REQUIRED 15.06 ACTUAL

+0.94% GRADE

967+00 | 968+00 | 969+00 | 970+00 | 971+00

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SITE PLAN
BRIDGE Nº MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN MAHONING COUNTY
STA. 969+31.98


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	W.B.H.		D.G.S.	D.C.		

MICROFILMED
SEP 19 1965


FED. RD.	STATE	PROJECT	
	OHIO		

383
492

MAH -18 -17.20



PLAN



ELEVATION

ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPERSTR	ABUT.	PIERS	GEN.		
E-2	656	CU.YDS.	UNCLASSIFIED EXCAVATION		540	116			
S-1	383	CU.YDS.	CLASS "C" CONCRETE, SUPERSTRUCTURE	383					
S-1	226	CU.YDS.	CLASS "E" CONCRETE ABUTMENTS ABOVE FOOTINGS.		226				
S-1	89	CU.YDS.	CLASS "C" CONCRETE PIERS ABOVE FOOTINGS.			89			
S-1	200	CU.YDS.	CLASS "E" CONCRETE PIER AND ABUT. FOOTINGS.		168	32			
S-3	21	SQ.YDS.	TYPE "B" WATERPROOFING		21				
S-4	144,189	LBS.	REINFORCING STEEL	93,505	25,017	25667			
S-7	313,700	LBS.	STRUCTURAL STEEL	313,700					
S-8	313,700	LBS.	FIELD PAINTING OF STRUCT. STEEL AS PER PLAN	313,700					

ITEM	TOTAL	UNIT	DESCRIPTION	SUPERSTR	ABUT.	PIERS	GEN.		
S-14	220	LIN.FT.	RAILING (ALUM. RAIL AND SUPPORTS AND						
			CONCRETE PARAPETS), Type C"	183	37				
S-25	LUMP	SUM	ELECTRICAL LIGHTING SYSTEM				LUMP		
S-29	155	CU.YDS.	POROUS BACKFILL		155				
S-29	70	LIN.FT.	6" STANDARD PIPE DOWNSPOUTS, GALVANIZED						
			STEEL OR WROUGHT IRON, INCLUDING SPECIALS.				70		
S-29	LUMP	SUM	SCUPPERS, INCLUDING SPECIALS.	LUMP					
S-29	36	LIN.FT.	8"ϕ PERFORATED BITUMINOUS COATED C.M.P.						
			INCLUDING SPECIALS.		36				
S-9	78	SQ. FT.	1" PREFORMED EXPANSION JOINT FILLER		78				
I-10	540	SQ.YDS.	CRUSHED AGGREGATE SLOPE PROTECTION				540		

—GENERAL NOTES—

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS, DATE 9-1-57 TOGETHER WITH CURRENT REVISIONS THEREOF

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE DECK SLAB, THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS, BETWEEN TRANSVERSE CONSTRUCTION JOINTS WHICH ARE NORMAL TO THE CENTERLINE OF BRIDGE AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

PAINTING: AFTER ERECTION AND AFTER THE SHOP COAT HAS BEEN CLEANED AND, WHERE NECESSARY, REPAINTED IN ACCORDANCE WITH SEC. 804, AN ADDITIONAL COAT OF THE SAME PAINT AS USED IN THE SHOP SHALL BE APPLIED OVER OUTSIDE FACE OF OUTSIDE STEEL BEAMS, & ALL SIDES OF BOTTOM FLANGE

SLOPE PROTECTION: CRUSHED AGGREGATE, ITEM I-10, EXTENDING FROM FACE OF ABUTMENT TO TOE OF SLOPE, SHALL BE PROVIDED AT SOUTH ABUTMENT FOR FULL WIDTH OF BRIDGE PLUS THREE FEET ON EACH SIDE OF BRIDGE ℄ PARALLEL WITH ℄ OF SUPERSTRUCTURE.

REFERENCE SHALL BE MADE TO STANDARD DRAWINGS
AR-1-57 DATED 2-2-59.
CSB-2-56 SHEETS #2 & 3 DATED 2-2-59
SUPPLEMENTAL SPECIFICATION S-101, DATED 12-2-59.

ELECTRICAL GROUNDS: A SOLID N°6 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON EACH SIDE OF THE STRUCTURE AT PIER N°2. THE LOWER ENDS OF THE WIRES SHALL TERMINATE IN A 25 FT. LENGTH COILED UNDER THE FOOTING AND SEPARATED FROM THE CONCRETE BY TWO LAYERS OF TAR PAPER AND THE UPPER ENDS SHALL EXTEND SUFFICIENTLY ABOVE THE TOP OF THE CONCRETE TO PROVIDE FOR A SUITABLE SPLICE AND EXTENSION FOR CONNECTION TO THE SUPERSTRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE A N°6 GAGE BARE STRANDED TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE AND TO THE SOLID COPPER WIRE IN THE PIER SHAFT. THERE SHALL BE A TINNED N°6 GAGE BARE COPPER WIRE BRAZED TO THE ANCHOR BOLTS OF THE LIGHT STANDARDS AND THE OTHER END BRAZED OR BOLTED TO THE OUTSIDE BEAM FLANGE. PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM BID FOR ITEM S-25 "ELECTRICAL LIGHTING SYSTEM."

ITEM S-25: ELECTRICAL LIGHTING SYSTEM INCLUDES 8 ANCHOR-BOLTS 1½"×4'-1" LG.

MACHINE FINISH: The concrete bridge deck shall be finished as specified in the Proposal Note, "Machine Finishing of Bridge Deck Slabs."

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GENERAL PLAN & ELEVATION

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 969+31.98


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	LWP					7-28-60

MICROFILMED
SEP 19 1955


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


384
492




PLAN OF SOUTH ABUTMENT




ELEVATION OF EAST WINGWALL
REFLECTED ELEVATION OF WEST WINGWALL



SECTION A-A



SECTION B-B



SECTION C-C

MAXIMUM DESIGN BEARING PRESSURE UNDER ABUTMENT #1 FOOTING = 2500 #/SQ.FT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAILS

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 969+31.98


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	JNP		D.C.	D.C,		

FED. RD.	STATE	PROJECT	
	OHIO		


MA H-18-17.20

385
492


MICROFILMED
SEP 19 1985




ELEVATION OF SOUTH ABUTMENT



SECTION D-D



SECTION E-E



SECTION F-F

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAILS

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 960+31.98


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	JNP		D.C.	D.C.		

FED. RD.	STATE	PROJECT	
	OHIO		


MA H-18-17.20

386/492


MICROFILMED
SEP 19 1985




PLAN (NORTH ABUTMENT)




DETAIL OF RUSTICATION GROOVE



CONTRACTION JOINT DETAIL



ELEVATION



SECTION - A-A AS SHOWN

SECTION A, A, OPP HAND

EXPANSION JOINT DETAIL

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT 2 DETAILS

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 969+31.98


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	JNP		D.C.	D.C.		

FED. RD.	STATE	PROJECT	
	OHIO		


387
492

MAH-18 -17.20

MICROFILMED
SEP 19 1985




SECTION - B-B




SECTION - C-C

DETAILS NOT SHOWN SAME AS SECTION B-B




VIEW D-D

(WEST WINGWALL SIMILAR)



FOR DETAILS NOT SHOWN SEE STANDARD DWG. Nº CSB-2-56 SHEET #2

END DAM DETAIL



SECTION - E-E

MAXIMUM DESIGN BEARING PRESSURE UNDER ABUTMENT Nº 2 FOOTINGS = 4000 LBS. PER SQ. FT.

ALL REINFORCING STEEL SHALL HAVE A 2" MINIMUM COVER UNLESS OTHERWISE NOTED.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT 2 DETAILS

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 969+31.08

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	JNP		D.C.	D.C.		

FED. RD.	STATE	PROJECT	
	OHIO		

388
492

MAH-18 -17,20

MICROFILMED
SEP 19 1985

PLAN

ELEVATION

RUSTICATIONS 7 SPA @ 4:0" = 28:0"

RUSTICATIONS 8 SPA @ 4:0" = 32:0"

DIMENSIONS AT OUTER FACE OF WALL

DIMENSIONS ALL GIVEN AT OUTSIDE FACE OF WING WALL. REINFORCING BARS SHALL BE SET RADIALLY FROM THESE POINTS.

A-501 & A-502 PROJECT FROM ABUTMENT FOOTING INTO WING WALL FOOTINGS. SEE ABUTMENT DETAIL

SEE SHEET No 386 FOR SECTION "A-A", "A1-A1" & RUSTICATION GROOVE DETAIL.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #2 WINGWALLS

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 969+31.98


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	JNP		D.C.	D.C.		

FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18 -17.20

389
492


MICROFILMED
SEP 19 1985




SECTION F F



SECTION G-G




SECTION H-H




SECTION J J

NOTES AND DIMENSIONS NOT SHOWN
SAME AS SECTION "H-H"




SECTION K-K


NOTES AND DIMENSIONS NOT SHOWN
SAME AS SECTION "G-G"



SECTION L-L

NOTES AND DIMENSIONS NOT SHOWN
SAME AS SECTION "F-F"





SECTION 1-1

NOTE:
8 ANCHOR BOLTS 1⅛" DIA. x 4'-1" LG. ARE INCLUDED FOR PAYMENT IN ITEM S-25

DETAIL OF LIGHT STANDARD SUPPORT

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #2 WINGWALLS

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 960+31.98


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	JNP		D.C.	D.C.		

FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18-17.20

390
492

MICROFILMED
SEP 19 1965



PLAN PIER #1 & #2



ELEVATION PIER #1 & #2


NOTE

ALL REINFORCING STEEL TO HAVE A 2" MINIMUM COVER EXCEPT WHERE OTHERWISE NOTED.

CARE MUST BE TAKEN IN PLACING REINFORCING STEEL IN THE PIER CAPS SO IT WILL NOT INTERFERE WITH THE BEARING PLATE ANCHOR BOLTS.

P_1 = PIER #1
P_2 = PIER #2.

MAXIMUM DESIGN BEARING PRESSURE UNDER PIER FOOTINGS = 10 TONS PER SQ. FT. (FOOTINGS ON ROCK)



SECTION A-A
SECTION C-C SAME EXCEPT AS NOTED

SECTION B-B

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 969+31.98

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.A.K.	J.N.P.		D.C.	D.C.		


FED. RD.	STATE	PROJECT	
	OHIO		

391
492


MAH-18-17.20

MICROFILMED
SEP 19 1985


THIS IS A NOMINAL DIMENSION. THE QUANTITY OF DECK CONCRETE TO BE PAID FOR SHALL BE BASED ON THIS DIMENSION, EVEN THOUGH DEVIATION FROM IT MAY BE NECESSARY BECAUSE THE TOP FLANGE OF THE BEAM MAY NOT HAVE THE EXACT CAMBER OR CONFORMATION REQUIRED TO PLACE IT PARALLEL TO THE FINISHED GRADE




TRANSVERSE SECTION




PARTIAL SLAB REINFORCING PLAN




BAR STAGGERING DETAIL OVER PIERS




FRAMING PLAN



ELEVATION - BEAM SPLICE DETAIL



SECTION B-B



SECTION A-A

LOCATION	DEFLECTION & CAMBER — OUTSIDE BEAMS			INSIDE BEAMS		
	NORTH SPAN (South)	SOUTH SPAN (North)	MIDDLE SPAN	NORTH SPAN (South)	SOUTH SPAN (North)	MIDDLE SPAN
DEFLECTION DUE TO WEIGHT OF STEEL	.05	.05	.10	.05	.05	.10
DEFLECTION DUE TO REMAINING DEAD LOAD	.55	.55	.70	.30	.30	.45
CONVEXITY REQUIRED FOR VERTICAL CURVE	.50	.00	.20	.50	.00	.20
SUM OF DEFLECTION & CONVEXITY	1.10	.60	1.00	.85	.35	.75
REQUIRED CAMBER	1 1/8"	0	1"	1"	0	1"

NOTES

1. SLAB THICKNESS SHOWN INCLUDES 1" MONOLITHIC WEARING SURFACE.
2. WELDING PROCEDURE:
   a.) RAISE BEAM ENDS AT ABUTMENTS 7".
   b.) BUTT WELD BEAM FLANGES AND WEB AT PIERS USING THE FOLLOWING SEQUENCE: MAKE TWO PASSES ON FLANGE, THEN TWO ON WEB, REPEAT USING ONE PASS AT EACH LOCATION UNTIL WELD IS COMPLETED.
   c.) WELD TOP AND BOTTOM MOMENT PLATES.
   d.) LOWER BEAM ENDS INTO FINAL POSITION AT ABUTMENTS.
3. WELDING OF STRUCTURAL STEEL SHALL BE CLASS "A" EXCEPT AS OTHERWISE SHOWN. ANY WELDS SHOWN AS FIELD WELDS MAY AT THE OPTION OF THE CONTRACTOR BE MADE IN THE SHOP.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

SEIBENBINGER, HOCH & ASSOCIATES AND BOBBY J. SCHRADER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING PLAN

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 969+31.98


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	J.N.P.		D.C.	D.C.		1-12-87

FED. RD.	STATE	PROJECT	
	OHIO		

392
492


MAH-18-17.20

MICROFILMED
SEP 19 1965




PARTIAL SLAB PLAN


DIMENSIONS MEASURED ON SIDEWALK SLOPE



DETAIL "A"
PARTIAL ELEVATION AT PIER #2
EAST SIDE SHOWN. WEST SIDE SIMILAR EXCEPT AS NOTED




ELEVATION



DETAIL "B"
PARTIAL ELEVATION AT ABUT #2
EAST SIDE SHOWN. WEST SIDE SIMILAR

SECTION - C-C



GUTTER SUPPORT DETAIL

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

DRAINAGE & RAILING DETAILS

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 969+31.98


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK.	JNP		D.C.	D.C.		

MICROFILMED
SEP 19 1995


FED. RD.	STATE	PROJECT	
	OHIO		

393
492


MAH-18-17.20




S-501




A-560




A-561




R-506




R-505




A-512




A-513




A-604




A-605







A-652




RE-401




P-904





P-1103





A-572





REINFORCING STEEL SCHEDULE

MARK	Nº	L'TH.	WEIGHT	SH'P.
PIERS "1" "2"				
P-501	208	8-2	1772	BT.
P-601	112	6'-10"	1154	BT
P-602	8	28-0	336	ST.
P-701	36	9-11	730	BT.
P-801	16	24-8	1055	ST.
P-802	16	25-0	1068	ST.
P-803	16	20-0	855	ST.
P-804	16	20-4	869	ST.
P-805	8	12-0	256	ST.
P-901	24	25-0	2040	ST.
P-902	24	20-4	1659	ST.
P-903	48	6-6	1061	BT.
P-904	8	10-8	290	BT.
P-1101	64	9-6	3230	BT.
P-1102	8	21-0	893	ST.
P-1103	12	21-3	1355	BT.
P-1104	8	39-0	1658	ST.
P-1105	16	13-0	1105	ST.
P-1106	6	27-0	861	ST.
P-1107	12	9-0	574	ST.
TOTAL PIERS INCLUDING SPIRALS			25,667	
REPLACEMENT BARS				
RE-401	1	5-3	SPIRAL	BT.
RE-501	1	5-6		ST.
RE-601	4	5-11		ST.
RE-701	2	6-3		ST.
RE-801	1	6-6		ST.
RE-901	1	7-0		ST.
RE-1101	1	7-6		ST.


MARK	Nº	L'TH.	WEIGHT	SH'P.
NORTH ABUTMENT "2"				
A-501	18	33-4	626	ST.
A-502	88	10-0	918	ST.
A-503	52	13-6	732	ST.
A-504	30	16-0	501	ST.
A-505	48	30-0	1,502	ST.
A-506	48	5-3	263	BT.
A-507	2	5'-0	10	BT.
A-510	6	6-4	40	ST
A-511	2	19-0	40	ST.
A-512	3	7-3	23	BT.
A-513	3	7-6	24	BT.
A-514	6	5'-0	31	BT
A-515	6	31-2	195	ST.
A-601	104	4-9	742	BT.
A-602	156	8-6	1992	ST
A-603	52	11-0	859	BT
A-604	8	12-2	146	BT.
A-605	44	13-5	887	BT.
A-606	2	6'-7"	14	BT
A-701	52	6-6	691	ST.
A-901	52	6-10	1208	BT.
A-902	52	9-10	1738	BT.
N. ABUT. TOTAL 13,182				
RAILING *				
R-501	16	12'-7		ST.
R-502	80	15'-6		ST.
R-503	8	16'-7"		ST.
R-504	8	4-8		ST.
R-505	8	10'-0		BT
R-506	4	8-8		BT


MARK	Nº	L'TH.	WEIGHT	SH'P.
SOUTH ABUTMENT "1"				
A-551	4	31'-10	133	ST.
A-552	111	7'-5"	859	BT.
A-553	40	30-10	1286	ST.
A-554	40	5'-10"	243	BT.
A-555	40	8'-2"	341	ST.
A-556	2	11'-6"	24	ST.
A-557	2	11'-0"	23	ST.
A-558	2	8'-6"	18	ST.
A-559	34	4'-11"	175	BT.
A-560	5	10'-4"	54	BT
A-561	5	10'-4	54	BT.
A-562	10	6'-6"	68	ST
A-563	32	4'-0"	134	ST.
A-564	2	10'-2"	21	ST.
A-565	2	8'-6"	18	ST.
A-566	6	18'-8"	117	ST.
A-567	6	16'-0"	100	ST.
A-568	34	3'-9"	118	BT.
A-569	68	3'-11	278	BT.
A-570	4	6'-3	26	BT
A-571	12	16'-6"	207	ST.
A-572	4	9'-7"	40	BT
A-573	20	5'-0	104	BT.
A-651	10	16'-3"	244	BT.
A-652	48	16'-6"	1190	BT
S. ABUT. TOTAL 5875				
SUPERSTRUCTURE				
S-501	276	8'-0"	2303	BT.
S-502	70	38'-0	2775	ST
S-503	280	5'-0	1460	BT
S-504	276	2'-2	624	BT
S-601	84	28'-0"	3533	ST.
S-602	550	27-0	22,305	ST.
S-603	430	38-6	24866	ST.
S-604	4	9'-7	58	BT
S-605	28	7'-4	308	ST.
S-701	550	31-3	35,132	ST
SUPERST. TOTAL. 93,505				

ABUTMENT TOTAL INCLUDING WING WALLS = 25,285

MARK	Nº	L'TH.	WEIGHT	SH'P.
N. ABUTMENT WINGWALLS				
W-501	1	9-4	10	BT
W-502	3	9-8	30	BT.
W-503	2	10-0	21	BT.
W-504	1	10-4	11	BT
W-505	2	11-0	23	BT.
W-506	6	11-4	71	BT.
W-507	4	11-9	49	BT.
W-508	4	12-2	51	BT.
W-509	2	12-7	26	BT.
W-510	2	8-4	17	BT.
W-511	2	8-9	18	BT.
W-512	6	9-2	57	BT.
W-513	4	9-6	40	BT.
W-514	2	10-0	21	BT.
W-515	2	10-5	22	BT.
W-516	1	13-0	14	BT.
W-517	3	13-6	42	BT.
W-518	2	14-0	29	BT.
W-519	1	14-6	15	BT.
W-520	17	3-7	64	BT.
W-521	18	5-1	96	BT.
W-522	3	27-7	87	BT.
SERIES OF W-523	1 SET OF 7 7 BARS	VARY 2-3 TO 26-9 4-3 INC.	106	BT.
W-524	3	9-9	30	BT
W-525	1	8-9	9	BT.
W-526	1	4-8	5	BT.
W-527	10	11-7	121	BT.
W-528	1	10-5	11	BT.
W-529	1	6'-4	7	BT
W-530	16	9-2	153	BT.
W-531	1	5-11	6	BT.
W-532	1	1-10	2	BT.
W-533	3	31-6	99	BT.
SERIES OF W-534	1 SET OF 7 7 BARS	VARY 2-3 TO 27-3 4-3 INC	110	BT.
W-535	1	6-8	7	BT.
W-536	1	2-7	3	BT.
W-537	1	11-0	11	BT.
W-538	1	6-11	7	BT.
W-539	1	2-10	3	BT.


MARK	Nº	L'TH.	WEIGHT	SH'P.
SERIES OF W-540	3	13-9	43	BT.
W-541	1	10-0	10	BT.
W-542	1	5-11	6	BT.
SERIES OF W-543	1 SET OF 4 4 BARS	VARY 6-3 TO 3-9 1-2 INC	34	ST.
SERIES OF W-544	1 SET OF 7 7 BARS	VARY 10-3 TO 13-9 7 INC	88	ST.
SERIES OF W-545	1 SET OF 8 8 BARS	VARY 14-5 TO 18-5 7 INC	136	ST.
SERIES OF W-546	1 SET OF 8 8 BARS	VARY 14-9 TO 18-10 7 INC	140	ST.
SERIES OF W-547	1 SET OF 7 7 BARS	VARY 10-10 TO 14-4 7 INC	93	ST.
SERIES OF W-548	1 SET OF 5 5 BARS	VARY 5-7 TO 10-3 1-2 INC	42	ST
SERIES OF W-604	1 SET OF 7 7 BARS	VARY 5-0 TO 8-6 7 INC	71	ST.
SERIES OF W-605	1 SET OF 7 7 BARS	VARY 9-0 TO 12-6 7 INC	113	ST.
SERIES OF W-606	1 SET OF 8 8 BARS	VARY 8-7 TO 12-8 7 INC	128	ST.
SERIES OF W-607	1 SET OF 8 8 BARS	VARY 3-0 TO 13-1 7 INC	133	ST.
SERIES OF W-608	1 SET OF 7 7 BARS	VARY 7-1 TO 12-7 7 INC	114	ST.
SERIES OF W-609	1 SET OF 10 10 BARS	VARY 3-3 TO 8-5 7 INC	88	ST.
W-701	16	4-3	145	BT.
W-702	32	7-4	480	BT.
W-703	16	7-7	248	BT.
W-801	16	12-0	513	BT.
W-901	14	9-4	445	BT.
WINGWALL TOTAL			5960	








SPIRAL REINFORCING LIST

MARK	Nº	CORE DIA. OF SPIRAL	LENGTH	PITCH	Nº OF TURNS	WEIGHT
SP-401	4	2'-6"	21'-8"	4½	61	1345
SP-402	4	2'-8	17'-0"	4½	49	1080
SPACERS	32					421
SPIRAL TOTAL						2846
GRAND TOTAL						144,189









SPIRAL REINFORCING NOTES

THE LENGTH SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE DISTANCE FROM THE TOP OF THE FOOTING TO BOTTOM OF THE PIER CAP.

THE NUMBER OF TURNS SHOWN IN THE STEEL LIST FOR SPIRAL BARS IS THE LENGTH DIVIDED BY THE PITCH PLUS THREE TURNS (TOTAL NUMBER OF CLOSED COILS) EXPRESSED AS THE NEAREST WHOLE NUMBER.

SPIRAL REINFORCING BARS SHALL NOT HAVE DEFORMATIONS BUT SHALL IN OTHER RESPECTS CONFORM TO ITEM S-4

ONE AND ONE HALF CLOSED COILS SHALL BE PROVIDED AT THE ENDS OF EACH SPIRAL UNIT. FOUR (4) STEEL CHANNEL, TEE, OR ANGLE SPACERS WEIGHING APPROX. 0.68 LBS. PER LINEAL FT. OF SPACERS SHALL BE PROVIDED FOR EACH SPIRAL UNIT. THEY SHALL BE EQUALLY SPACED ALONG THE PERIPHERY OF EACH COIL. THE NUMBER OF POUNDS OF THESE SPACERS, BASED ON 0.68 LBS. PER LINEAL FT. WILL BE PAID FOR AS REINFORCING STEEL AND IS INCLUDED IN THE TABULATED QUANTITY OF SPIRAL BARS.

BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED AND THE FIRST TWO DIGITS WHERE FOUR ARE USED INDICATE THE BAR SIZE NUMBER. FOR EXAMPLE A-700 IS A Nº 7 SIZE BAR AND A-1014 IS A Nº 10 SIZE BAR.

REPLACEMENT BARS: IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SECTION S-4.02 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.

* RAILING REINFORCEMENT BARS WILL BE INCLUDED AS PART OF ITEM S-14 FOR PAYMENT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

REINFORCING SCHEDULE

BRIDGE NO. MAH-18-1835
UNDER GLENWOOD AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 969+31.98

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	JNP		D.C.	D.C.		

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
2	OHIO		

394
492

MAH-18-17.20

¢ MARSHALL STREET

PROPOSED RAMP "C"

12" S.E.S. PIPE

6" C.I.P.

STA. 0+00

1+00

2+00

15" S.E.S. PIPE

3" GAS PIPE

6" C.I.P.

48'-0"

60'-0"

2:1

FUTURE CLEAR.

END APPROACH SLAB
STA. 979+19.25

BEGIN APPROACH SLAB
STA. 980+19.75

4' FUTURE SIDEWALK

¢ WEST BOUND LANES

¢ SURVEY OF STATE ROUTE 18

¢ EAST BOUND LANES

RAMP "F"

2T ROADWAY EXISTING

4' FUTURE SIDEWALK

SKEW

89° 43'

FUTURE CLEARANCE

POINT OF MIN. CLEARANCE

40' ROADWAY FUTURE EXPANSION

EDWARDS STREET

BRIDGE LIMITS 161'-6"

P.C.S.T. 981+00

5'-5¾" 27' F/F CURBS 5'-5¾" EXISTING

4¾" SW 40' F/F CURB 3¾" SW 4¾" FUTURE

TYPICAL SECTION
EDWARDS ST.

-12.85% P.V.I. STA. 5+60 EL. 874.13

-10.42%

MIN. CLEARANCE 14.50' REQUIRED

PROPOSED STRUCTURE

TYPE: CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE DECK AND SUBSTRUCTURE
SPANS: 48'-60'-48' ¢/¢ BRGS.
ROADWAY: 100'-0" F/F PARAPETS
LOAD FREQUENCY: C.F 2000 - ADEQUATE FOR A.A.S.H.O. ALTERNATE LOADING
SKEW: 0° 16' 06" R.F. BRIDGE SQUARE
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLAB: 25' LONG A.S-1-54
SUPERELEVATION: NONE
TRAFFIC COUNT: 3400 ADT 1979
ALIGNMENT: TANGENT

FOUNDATION SOUNDING

FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF SOIL-SAMPLING SOUNDINGS MADE AT THE SITE. THIS SOUNDING INFORMATION MAY BE INSPECTED IN THE OFFICE OF THE BUREAU OF BRIDGES IN COLUMBUS OR IN THE DIVISION OFFICE BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THEREOF.

SLOPE PROTECTION

I.-C CRUSHED AGGREGATE, SLOPE PROTECTION

200.01 200.48 200.05 201.42 201.85 202.36 202.83 203.30 202.77

+0.94% GRADE

14.68' ACTUAL MIN. CLEARANCE

14.50' REQUIRED MIN. CLEARANCE

AVERAGE ESTIMATED PAY LENGTH FOR PILE ARE
ABUTMENTS : 40'
PIERS : 85'

P.V.C. STA. 981+03.50

978+00 979+00 980+00 981+00 982+00

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

STEINMAN, HOGG & ASSOCIATES AND ROBERT J. SCHICKEL
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SITE PLAN
BRIDGE NO. MAH-18-1855
STRUCTURE OVER EDWARDS ST.
YOUNGSTOWN-MAHONING COUNTY
STA. 975+19.25 TO 980+79.75


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	D.G.S.		D.G.S.			

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

M A H-18 -17.20

395/492



PLAN



ELEVATION

ITEM 5-25: ELECTRICAL LIGHTING SYSTEM INCLUDES THE FOLLOWING; 4 EXPANSION FITTINGS, ONE GALV. CAST IRON BOX & 4-1"ø ANCHOR BOLTS.

LIGHTING DETAILS ARE SHOWN ON SHEET Nº 310

GENERAL NOTES

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS DATED 9-1-57 TOGETHER WITH CURRENT REVISIONS THEREOF.

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE CONCRETE OF THE DECK SLAB, THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE; THE SLAB MAY BE PLACED IN SECTIONS BETWEEN THE TRANSVERSE CONSTRUCTION JOINTS WHICH ARE NORMAL TO THE CENTERLINE OF THE BRIDGE AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

PAINTING: AFTER ERECTION AND AFTER THE SHOP COAT HAS BEEN CLEANED AND, WHERE NECESSARY, REPAINTED IN ACCORDANCE WITH SEC. 8.04, AN ADDITIONAL COAT OF THE SAME PAINT AS USED IN THE SHOP SHALL BE APPLIED OVER THE OUTSIDE FACE OF THE OUTSIDE STEEL BEAMS, ALL SIDES OF BOTTOM FLANGE.

CRUSHED AGGREGATE SLOPE PROTECTION: EXTENDING FROM FACE OF EACH ABUTMENT TO TOE OF SLOPE, SHALL BE PROVIDED AT EACH ABUTMENT FOR FULL WIDTH OF BRIDGE PLUS THREE FEET ON EACH SIDE OF BRIDGE AND PARALLEL WITH ℄ OF SUPERSTRUCTURE.

EXCAVATION QUANTITY: INCLUDES THE REMOVAL OF FILL MATERIAL BETWEEN THE SURFACE OF THE PROPOSED EMBANKMENT AND THE BOTTOM OF ABUTMENT.

MACHINE FINISH: The concrete bridge deck shall be finished as specified in the Proposal Note "Machine Finishing of Bridge Deck Slabs".

EMBANKMENT PROCEDURE: THE EMBANKMENT SHALL BE PLACED AND COMPACTED UP TO THE FINISHED SPILL THRU SLOPE AND TO THE LEVEL OF THE SUB-GRADE FOR A DISTANCE OF 200 FEET BACK OF THE ABUTMENTS, AFTER WHICH EXCAVATION SHALL BE MADE FOR THE ABUTMENTS.

ALL PILES TO BE 12" CAST IN PLACE REINFORCED CONCRETE PILES, DRIVEN TO A MINIMUM BEARING CAPACITY OF 40 TONS.

REFERENCE SHALL BE MADE TO STANDARD DRAWINGS:
AR-1-57, DATED 2-2-59 FOR ALUMINUM RAILING
CSB-2-56 SHEET 2 & 3, DATED 2-2-59
SUPPLEMENTAL SPECIFICATION S-101, DATED 12-2-59

ESTIMATED QUANTITIES

ITEM	TOTAL	SUM	DESCRIPTION	SUPERST.	ABUT'S	PIERS	GEN.
E-2	934	CU.YDS.	UNCLASSIFIED EXCAVATION.		440	494	
S-1	484	CU.YDS.	CLASS "C" CONCRETE SUPERSTRUCTURE.	484			
S-1	158	CU.YDS.	CLASS "E" CONCRETE ABUT'S ABOVE FOOTINGS.		158		
S-1	145	CU.YDS.	CLASS "C" CONCRETE PIERS ABOVE FOOTINGS.			145	
S-1	322	CU.YDS.	CLASS "E" CONCRETE ABUT. AND PIER FOOTINGS.		146	176	
S-4	217,718	LBS.	REINFORCING STEEL	146,343	14,346	57,029	
S-7	393,500	LBS.	STRUCTURAL STEEL	393,500			
S-8	393,500	LBS.	FIELD PAINTING OF STRUCTURAL STL. AS PER PLAN	393,500			
S-29	12	EACH	SCUPPERS	12			
I-10	825	SQ.YDS.	CRUSHED AGGREGATE SLOPE PROTECTION				825
S-14	358	LIN.FT.	RAILING (ALUM. RAIL AND SUPPORTS-CONCRETE PARAPET & END POST'S - REINFORCING STEEL)	315	43		
S-16	LUMP	SUM	FIRST TEST PILES				LUMP
S-18	5,200	LIN.FT.	12"ø CAST-IN-PLACE REINFORCED CONCRETE PILES		2,400	2,800	
S-25	LUMP	SUM	ELECTRICAL LIGHTING SYSTEM				
S-25	348	LIN.FT.	2" ELECTRICAL CONDUIT (GALV.)	348			
S-29	68	CU.YDS.	POROUS BACKFILL		68		
S-14	158	LIN.FT.	GUARD RAIL - STEEL BEAM TYPE (DEEP) BARRIER DESIGN	158			

GENERAL NOTES (CONT.)

ELECTRICAL GROUNDS: A SOLID Nº 0 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON EACH SIDE OF THE STRUCTURE AT PIER Nº 2. THE LOWER END OF THE WIRE SHALL BE BRAZED TO THE STEEL CASING OF ONE OF THE 12" CAST-IN-PLACE CONCRETE PILES AND THE UPPER END SHALL EXTEND SUFFICIENTLY ABOVE THE CONCRETE TO PROVIDE A SUITABLE SPLICE AND EXTENSION FOR CONNECTION TO THE SUPPERSTRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE A Nº 6 GAGE BARE, STRANDED, TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE AND TO THE SOLID COPPER WIRE IN THE PIER SHAFT. THERE SHALL BE A TINNED Nº 6 GAGE COPPER WIRE BRAZED TO A GROUNDING LUG INSIDE THE LAMP STANDARD AND THE OTHER END BRAZED OR BOLTED TO THE OUTSIDE BEAM FLANGE.

PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM BID FOR ITEM S-25, "ELECTRICAL LIGHTING SYSTEM"

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

SEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GENERAL PLAN & ELEVATION

BRIDGE NO. MAH-18-1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979+19.25 To STA. 980+79.75


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	S.S.					

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


396
492




PLAN OF ABUTMENT #1



PLAN OF ABUTMENT #1




ELEVATION



ELEVATION OF SOUTH W. W. ABUT. #1

REFLECTED ELEV. OF NORTH W. W. ABUT. #1



ELEVATION OF SOUTH WINGWALL ABUTMENT #2

REFLECTED ELEV. OF NORTH W. WALL ABUTMENT #2

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE NO. MAH-18-1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979+19.25 To STA. 980+79.75


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					


MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18 -17.20

397
492





ELEVATION OF ABUTMENT #1 — REFLECTED ELEVATION OF ABUTMENT #2



DETAIL OF EXPANSION JOINT

NOTE: THE CONCRETE IN THE ABUTMENT BACKWALL SHALL NOT BE PLACED UNTIL AFTER STEEL WORK IS ERECTED, BUT SHALL BE PLACED BEFORE THE DECK SLAB IS PLACED.

POROUS BACKFILL 2 FT. THICK, FULL LENGTH OF ABUTMENT AND WING WALLS, SHALL EXTEND UP TO THE UNDERSIDE OF THE APPROACH SLAB OR TO THE FINISHED GROUND SURFACE.

ELEVATION TABLE

	A	B	C	D	E	F	G	H	K	L	M	N	P	R	AA	BB×	CC	DD	EE×	FF×	GG×	HH	KK	LL
ABUTMENT #1	897.34	897.45	897.57	897.68	897.79	897.83	897.71	897.60	897.58	897.70	897.82	897.75	897.63	897.51	900.20	900.35	900.09	900.02	901.48	901.21	901.13	900.27	900.38	891.34
ABUTMENT #2	898.81	898.94	899.04	899.15	899.26	899.30	899.18	899.07	898.05	899.17	899.28	899.22	899.10	898.98	901.68	902.44	901.80	901.51	902.97	902.70	902.62	901.98	901.87	892.81

×ELEVATIONS GIVEN TO HEEL OF ANGLE

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE NO. MAH-18-1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979+19.25 To STA. 989+79.75


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					

MICROFILMED
SEP 19 1995


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


398
492



SECTION 2-2




SECTION 3-3




FOR NOTES AND DIMENSIONS NOT SHOWN SEE SECTION 3-3

SECTION 4-4



FOR NOTES AND DIMENSIONS NOT SHOWN SEE SECTION 3-3

SECTION 5-5




FOR NOTES AND DIMENSIONS NOT SHOWN SEE SECTION 4-4

SECTION 6-6

SECTION 7-7

SECTION 8-8

SECTION 9-9



SECTION 10-10

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE NO. MAH-18-1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979+19.25 To STA. 980+79.75


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

399
492




PLAN OF SECTION-I - PIER #1 & #2




SECTION - I


SECTION - II

ELEVATION OF PIER #1 & #2




ELEVATION OF SECTION-I





SECTION A-A




SECTION C-C

NOTES: REINFORCING STEEL TO HAVE A MINIMUM OF 2" COVER EXCEPT AS OTHERWISE NOTED.

ALL PILES TO BE 12" MINIMUM TOP DIA. CAST-IN-PLACE REINFORCED CONCRETE PILES.

SPECIAL CARE SHALL BE TAKEN IN PLACING REINFORCING STEEL UNDER BEAM BEARINGS IN ORDER TO CLEAR ANCHOR BOLTS WHERE THEY OCCUR.



SECTION B-B

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS


BRIDGE NO. MAH-18-1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979+19.25 To STA. 980+79.75

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					


MICROFILMED
SEP 19 1995

FED. RD.	STATE	
	OHIO	(400)

MAH-18 -17.20




PLAN OF SECTION - II - PIER #1 & #2




ELEVATION OF SECTION - II


SEE NOTE AT SECTION - I



SECTION E-E



SECTION G-G



SECTION F-F

ELEVATION TABLE

	A	B	C	D	E	F	G	H	K	L	M	N	P	R	S	T
PIER # 1	897.73	897.84	897.96	898.07	898.18	898.22	898.10	897.99	897.97	898.09	898.21	898.14	898.02	897.90	876.00	874.00
PIER # 2	898.38	898.49	898.61	898.72	898.83	898.87	898.75	898.64	898.62	898.74	898.86	898.79	898.67	898.55	876.00	874.00

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS


BRIDGE NO. MAH-18 -1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979 +19.25 To STA. 980+79.75

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


401/492




FRAMING PLAN




PARTIAL SLAB REINFORCING PLAN



PLAN



SECTION A-A




ANCHOR BOLT DETAIL

DETAIL OF LIGHT STANDARD SUPPORT

STATE ROUTE 18
DEFLECTION & CAMBER

LOCATION	OUTSIDE BEAMS		INSIDE BEAMS	
	END SPANS	MIDDLE SPANS	END SPANS	MIDDLE SPANS
DEFLECTION DUE TO WEIGHT OF STEEL	0.05	0.07	0.04	0.05
DEFLECTION DUE TO REMAINING DEAD LOAD	0.30	0.45	0.21	0.30
CONVEXITY REQUIRED FOR VERTICAL CURVE.	0.00	0.00	0.00	0.00
SUM OF DEFLECTION & CONVEXITY	0.35	0.50	0.25	0.35
REQUIRED CAMBER	0	0	0	0



BAR STAGGERING OVER PIERS
(S-603 BARS)

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING PLAN


BRIDGE NO. MAH-18-1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979+19.25 To STA. 980+79.75

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.H.	R.P.S.					


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


402
492




TRANSVERSE SECTION (WESTBOUND LANES)



TRANSVERSE SECTION (EASTBOUND LANES)



PLAN




SECTION C-C


DETAIL OF SCUPPERS

NOTES


1- SLAB THICKNESS SHOWN INCLUDE 1" MONOLITHIC WEARING SURFACE.
2- WELDING PROCEDURE:
a- RAISE END OF BEAMS AT ABUTMENTS 3/4".
B- BUTT-WELD BEAM FLANGES AND WEB AT PIERS USING THE FOLLOWING SEQUENCE; MAKE TWO PASSES ON EACH FLANGE, THEN TWO ON THE WEB; REPEAT, USING ONE PASS AT EACH LOCATION, UNTILL WELDS ARE COMPLETE.
C- WELD TOP AND BOTTOM FLANGE MOMENT PLATES AT PIERS.
d- LOWER BEAMS ENDS INTO FINAL POSITION AT ABUTMENTS.




DETAIL OF MEDIAN CURB




PARTIAL SECTION A-A





SECTION B-B



BEAM SPLICE DETAILS AT PIERS

CURB PLATE DETAILS FOR MEDIAN

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SLAB DETAILS

BRIDGE NO. MAH-18-1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979+19.25 To STA. 980+79.75

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.H.	R.P.S.					

MICROFILMED
SEP 19 1955

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18 -17.20

403
492

℄ BEARINGS

17" 3'-6" 12'-0" 12'-0" 12'-0" 3'-6"

45°

SCUPPER

FACE OF CURB

FACE OF MEDIAN CURB

SCUPPER
USE STD. CSB-2-56 ALONG MEDIAN

FACE OF ABUTMENT

A

A

11 - SPACES @ 12'-6" = 137'-6" ℄ TO ℄ GUARD RAIL POSTS.

1'-0" 2'-1" 2'-1" 1'-0"

FACE OF MEDIAN CURB

5"x3½"x13# BULB L

2"ϕ DRAIN PIPE

5"x3½"x13# BULB L

1" EXPANSION JOINT

FACE OF ABUTMENT

℄ SURVEY S.R. 18 AND GUARD RAIL

SCUPPERS
USE STD. CSB-2-56 ALONG MEDIAN

FACE OF CURB

℄ BEARINGS

2" AT 70° F. 1'-0" 8'-5" 13'-6" 8 - PANELS @ 16'-4" = 130'-8" 13'-6" 8'-5" 1'-0" 2" AT 70° F.

17 - SPACES @ 8'-2" = 138'-10" ℄ TO ℄ RAILING POSTS - TYPICAL

PART DECK PLAN

4" OD. 3/16 WALL ALUMINUM TUBE TYPE "A" RAILING SHALL BE CONTINUOUS THRU FIRST POST AT EACH END OF SUPERSTRUCTURE

¼ GREY SPONGE RUBBER PREFORMED EXPANSION JOINT FILLER MEETING THE REQUIREMENTS OF SEC. M-10.02 TYPE NO. 1. SPACE TWO PANEL LENGTHS APART. INCLUDED WITH ITEM S-14 FOR PAYMENT.

2-R-502 2-R-503 2-R-502

2" 10-SP'S @ 1'-4" = 13'-2" 2" 12-SP-S @ 1'-4" = 16'-0" 2" 10-SP'S @ 1'-4" = 13'-2" 2"

11-5-501 11-5-501

2-R-502

SCUPPER SCUPPER SCUPPER

2"ϕ STD. STL. PIPE DRAIN. WELD STUB END FULL PERIMETER TO BULB ANGLE.

2"ϕ CONDUIT CONTINUOUS THRU SLAB WITH EXPANSION FITTINGS AT ABUTMENTS. NS & FS SEE ROADWAY LIGHTING DETAILS

ELEVATION

GUARD RAIL - STEEL BEAM TYPE (DEEP) BARRIER DESIGN

℄ SURVEY SR. 18

6 WF 15.5 (GALVANIZING AS PER SPEC. M-7.4(d) OF THE SPECIFICATIONS)

1¼"ϕ SQUARE HEAD GALVANIZED ANCHOR BOLTS. 1'-0" LONG - PROJECTION 3" - THREADED 2½"

1" OPEN JOINT

2'-4"

10"

6"

1" 6"

7" 8ϕ HOLES

PL. 10x⅝x10 GALVANIZED

SECTION A-A

SEE STANDARD DWG. I-15. NO. 2-A

℄ 1¼"ϕ CONDUIT

℄ 33 WF 141

3'-2"

2-7/16" DIA. HOLES FOR 1¼" DIA. CONDUIT.

3" 6"

3x3x5/16 LS

2'-0"

SECTION Z-Z

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

DRAINAGE & RAILING DETAILS

BRIDGE NO. MAH-18 -1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979 +19.25 To STA. 980+79.75

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					

REINFORCING STEEL SCHEDULE

MARK	NO.	LENGTH	WEIGHT	SHAPE
ABUTMENTS				
A-501	8	29'-7"	247	ST.
A-502	32	29'-0"	1573	ST.
A-503	448	5'-11"	2766	BT.
A-504	140	5'-6"	803	BT.
A-505	4	12'-7	53	ST.
A-506	2	7'-1"	15	ST.
A-507	4	4'-11"	21	BT.
A-508	4	10'-5"	43	ST.
A-509	4	4'-6"	19	ST.
A-510	12	8'-5"	106	ST.
A-511	12	3'-6"	44	ST.
A-512	8	4'-2"	35	BT.
A-513	12	13'-6"	169	ST.
A-514	12	8'-10"	111	ST.
A-515	64	5'-4"	356	ST.
A-516	96	3'-10"	384	BT.
A-517	32	5'-11"	198	BT.
A-518	12	4'-0"	50	ST.
A-519	8	24'-3"	202	ST.
A-520	52	23'-6"	1275	ST.
A-521	2	8'-2"	17	ST.
A-522	4	6'-0"	25	BT.
A-523	2	40'-0"	83	ST.
A-524	2	28'-0"	59	ST.
A-525	32	3'-10"	128	ST.
A-526	16	11'-6"	192	ST.
A-527	112	8'-6"	983	BT.
A-528	8	11'-6	96	BT.
A-529	24	3'-11"	98	BT.
A-530	4	1'-8"	7	BT.
A-531	4	1'-10"	8	BT.
A-532	4	2'-0"	9	BT.
A-533	4	2'-2"	10	BT.
A-534	4	2'-4"	10	BT.
A-535	4	2'-6"	11	BT.
A-536	4	2'-7"	11	BT.
A-537	4	2'-8"	12	BT.
A-538	4	2'-9"	12	BT.
A-539	8	2'-10"	24	BT.
A-540	16	5'-6"	92	BT.
A-601	78	12'-5"	1435	BT.
A-602	120	14'-2"	2554	BT.
TOTAL ABUTMENTS			14,346	

MARK	NO.	LENGTH	WEIGHT	SHAPE
PIERS				
P-501	134	7'-8"	1072	ST.
P-502	296	7'-8"	2368	BT.
P-503	134	8'-10"	1234	BT
P-601	4	42'-2"	254	ST.
P-602	8	28'-4"	340	ST.
P-801	40	30'-8"	3276	BT.
P-901	168	5'-10"	3330	BT.
P-902	36	20'-6"	2509	ST.
P-903	36	21'-2"	2591	ST.
P-904	28	10'-0"	952	BT.
P-905	8	9'-6"	258	BT.
P-906	44	23'-5"	3,505	ST.
P-907	48	18'-4"	2992	ST.
P-908	48	19'-0"	3102	ST.
P-909	40	29'-7"	4023	ST.
P-910	32	14'-0"	1523	ST.
P-1101	44	25'-0"	5844	BT.
P-1102	4	40'-6	861	ST.
P-1103	14	20'-0"	1488	ST.
P-1104	6	27'-2"	866	BT
P-1105	4	38'-10"	825	ST.
P-1106	10	30'-7"	1626	ST.
P-1107	8	14'-4"	609	ST.
P-1108	0	P	E	N.
P-1109	4	24'-6"	521	ST.
P-1110	4	33'-10"	719	ST.
P-1111	6	31'-9"	1012	BT.
P-1112	6	24'-5"	778	BT.
P-1113	14	14'-5"	1084	ST.
P-1114	6	29'-0"	925	ST.
P-1115	6	26'-6"	845	ST.

MARK	NO	LENGTH	WEIGHT	SHAPE
P-1116	10	18'-4"	974	ST.
P-1117	8	12'-0"	510	ST.
	TOTAL		52,816	
	ADD SPIRALS		4213	
TOTAL PIERS			57,029	
SUPERSTRUCTURE				
S-501	252	4'-5"	1162	BT.
S-502	118	6'-6"	800	BT.
S-503	118	5'-5"	667	BT.
S-504	236	4'-10"	1190	BT.
S-505	236	1'-9"	512	BT.
S-601	472	23'-9"	16,838	ST.
S-602	950	33'-0"	47,088	ST.
S-603	162	24'-0"	5840	ST.
S-604	472	29'-4"	20,796	ST
S-605	4	9'-6"	57	BT
S-606	16	7'-6"	180	ST
S-701	472	23'-9"	22,913	ST.
S-702	472	29'-4"	28,300	ST
TOTAL SUPERSTRUCTURE = 146,343#				
RAILING *				
R-501	16	11'-2		ST
R-502	16	13'-2"		ST
R-503	64	16'-0"		ST
R-504	2	11'-5"		BT
R-505	4	12'-10		BT

SPIRAL REINFORCING LIST

MARK	NO. REQ'D	CORE DIA. OF SPIRAL	LENGTH OF SPIRAL	PITCH	NO. OF TURNS	WEIGHT
SP-401	3	2'-8"	17'-3"	4½"	45	810
SP-402	3	2'-8"	17'-10"	4½"	51	843
SP-403.	4	2'-8"	15'-0"	4½"	43	948
SP-404	4	2'-8"	15'-8"	4½"	45	992
SPACERS	56					620
					TOTAL	4213

GRAND TOTAL 217,718 LBS.


SPIRAL REINFORCING NOTES

THE LENGTH SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE DISTANCE FROM THE TOP OF THE FOOTING TO BOTTOM OF PIER CAPS. THE NUMBER OF TURNS SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE LENGTH DIVIDED BY THE PITCH PLUS THREE TURNS (TOTAL NUMBER OF CLOSED COILS) EXPRESSED AS THE NEAREST WHOLE NUMBER. SPIRAL REINFORCING BARS SHALL NOT HAVE DEFORMATIONS BUT SHALL IN OTHER RESPECTS CONFORM TO ITEM S-4. ONE AND HALF CLOSED COILS SHALL BE PROVIDED AT THE ENDS OF EACH SPIRAL UNIT. FOUR (4) STEEL CHANNEL, TEE OR ANGLE SPACERS WEIGHING APPROXIMATELY 0.68 LBS. PER LINEAL FT. OF SPACERS SHALL BE PROVIDED FOR EACH SPIRAL UNIT. THEY SHALL BE EQUALLY SPACED ALONG THE PERIPHERY OF EACH COIL. THE NUMBER OF POUNDS OF THESE SPACERS, BASED ON 0.68 LBS. PER LINEAL FT. WILL BE PAID FOR AS REINFORCING STEEL AND IS INCLUDED IN THE TABULATED QUANTITY OF SPIRAL BARS.


BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED AND THE FIRST TWO DIGITS WHERE FOUR ARE USED INDICATE THE BAR SIZE NUMBER. FOR EXAMPLE A-700 IS A NO. 7 SIZE BAR AND A-1014 IS A NO. 10 SIZE BAR.

REPLACEMENT BARS: IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SECTION S-4.02 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.


* RAILING REINFORCEMENT BARS WILL BE INCLUDED AS PART OF ITEM S-14 FOR PAYMENT.



R-504



R-505




S-605

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		


MA H-18-17.20


404
4.92




REPLACEMENT BARS


MARK	NO. REQD	LENGTH	SHAPE
RE-401	1	5'-3"	SPIRAL
RE-501	2	5'-6"	ST
RE-601	3	6'-0"	ST
RE-701	3	6'-3"	ST
RE-801	1	6'-6"	ST
RE-901	2	7'-0"	ST
RE-1101	1	7'-6"	ST








P-905
























A-512





S-504














STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

REINFORCING SCHEDULE

BRIDGE NO. MAH-18-1855
OVER EDWARDS ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 979+[illegible].25 To STA. 980+79.75

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					

FED. RD.	STATE	PROJECT	
	OHIO		

405
492

MAH-18-17.20

MICROFILMED
SEP 19 1985

CURVE DATA

$\Delta = 74°-52'-50"$ R
$D_c = 2°45'$
$R_c = 2083.48'$
$L_s = 300'$
$\Phi_s = 04°07'30"$
$L_c = 2422.93'$
$T_s = 1746.61'$
$E_s = 542.86'$

EXISTING PROFILE

848.44

852.05

857.56

AVERAGE ESTIMATED PAY LENGTH OF PILES: ABUTMENTS @ 35'. PIERS @ 25'.

15.00' REQUIRED CLEARANCE

15.16' CLEARANCE

WALTER ST

DECELERATION LANE (RAMP "J")

ACCELERATION LANE (RAMP "H")

BEGIN DECELERATION STA. 1004+76.74=1004.00

END ACCELERATION STA. 1004+32.74=1003.96

END APPROACH SLAB STA. 1005+07.94

BEGIN APPROACH SLAB STA. 1006+88.08

℄ RELOCATED PIKE ST.

℄ EXISTING STA 50+00.00

23°43'-27" SKEW

℄ LOCAL TRAFFIC STA. 501+00.00

STA. 1003+93.05

M.H. STA. 1006+09.21

36'-0" EXISTING

66'-0" LOCAL TRAFFIC TO LONDONDERRY @ ±1.5%

12" PROP. EXTENSION

℄ WESTBOUND LANE

℄ SURVEY OF S.R. = 18

℄ EASTBOUND LANE

4" GAS

6" C.I.P.

4'-6" CIRC. BRICK

FUTURE INT.
EXISTING INT.

POINT OF MIN. CLEARANCE

RETAINING WALL

FUTURE 6' SIDEWALK

FUTURE 28' ROAD

℄ FACE EXISTING CURB

4" GAS LINE

℄ FUTURE HIGH ST.

℄ EXISTING HIGH ST. S.F.S.

36" x 46" OVAL BRICK

M.H.

6'-0"

OAK HILL AVE.

℄ PROPOSED OAK HILL AVE.

DIKE ST

8" C.I.P.

2'-2" CIRC. BRICK

2:1

1:2

Foundation Sounding

FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF ROD SOUNDINGS & SOIL SAMPLING SOUNDINGS MADE AT THE SITE. THIS SOUNDING INFORMATION MAY BE INSPECTED IN THE OFFICE OF THE BUREAU OF BRIDGES IN COLUMBUS OR IN THE DIVISION OFFICE BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THEREOF.

Slope Protection

SLOPE PROTECTION AT EACH ABUTMENT TO EXTEND FROM FACE OF ABUTMENT TO TOE OF SLOPE FOR FULL WIDTH OF BRIDGE PLUS 3 FT. ON EACH SIDE AND PARALLEL WITH ℄ OF BRIDGE.

BRIDGE LIMITS 180.14

Proposed Structure

TYPE: STEEL BEAM WITH REINFORCED CONCRETE DECK AND SUBSTRUCTURE
SPAN: 49'-0"-70'-0"-56'-0" c/c BRGS.
ROADWAY: 88'-0" F/F PARAPETS
LOAD FREQUENCY: CF 2000 - ADEQUATE FOR A.A.S.H.O. ALTERNATE LOADING
SKEW: 23°-43'-27" R.F.
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLABS: 25' LONG AS-1-54
SUPERELEVATION: .06$\frac{1}{2}$"
ALIGNMENT: 2°45' RT.
TRAFFIC COUNT: 26,000 ADT 1979

48'-0" F/F CURBS
9.5' | 30' (18' EXIST. + 12' PROP.) | 18' EXIST. | 4' | 6'
℄ EXISTING 36' RD.

PROPOSED SECTION OAK HILL AVE.

867.27 | 868.50 | 870.53 | 872.16 | STA. 1005+07.94 871.42 | 873.79 | 875.42 | 877.05 | STA. 1006+88.08 EL 876.29 | 876.66 | 880.31

+3.26% GD.

15.00' REQUIRED MIN. CLEAR

15.0

2:1 NORMAL

2:1 NORMAL

900
880
860
840

1004+00 | 1005+00 | 1006+00 | 1007+00

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SITE PLAN
BRIDGE Nº MAH-18-1904
OVER OAK HILL AVE
YOUNGSTOWN MAHONING COUNTY
STA. 1005+07.94 TO STA. 1006+88.08


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGS	A.C.		D.S.	DHC		

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

406
492

MAH-18-17.20



GENERAL PLAN



ELEVATION

GENERAL NOTES

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS DATED 9-1-57. TOGETHER WITH REVISIONS THEREOF.

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE CONCRETE OF THE DECK SLAB, THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS BETWEEN THE TRANSVERSE CONSTRUCTION JOINTS WHICH ARE NORMAL TO THE CENTERLINE OF THE BRIDGE AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

WELDING OF STRUCTURAL STEEL: SHALL BE CLASS 'A' EXCEPT AS OTHERWISE SHOWN. ANY WELDS SHOWN AS FIELD WELDS MAY AT THE OPTION OF THE CONTRACTOR BE MADE IN THE SHOP.

CRUSHED AGGREGATE SLOPE PROTECTION: EXTENDING FROM FACE OF EACH ABUTMENT TO TOE OF SLOPE, SHALL BE PROVIDED AT EACH ABUTMENT FOR FULL WIDTH OF BRIDGE PLUS THREE FEET ON EACH SIDE OF BRIDGE AND PARALLEL WITH ℄ SUPERSTRUTURE.

EXCAVATION QUANTITY: INCLUDES THE REMOVAL OF FILL MATERIAL BETWEEN THE SURFACE OF THE PROPOSED EMBANKMENT AND THE BOTTOM OF ABUTMENT.

PAINTING: AFTER ERECTION & AFTER THE SHOP COAT HAS BEEN CLEANED AND WHERE NECESSARY REPAINTED IN ACCORDANCE WITH SEC. 804, AN ADDITIONAL OF THE SAME PAINT AS USED IN THE SHOP SHALL BE APPLIED OVER OUTSIDE FACE OF OUTSIDE STEEL BEAMS & ALL SIDES OF BOTTOM FLANGES.

EMBANKMENT PROCEDURE: THE EMBANKMENT SHALL BE PLACED AND COMPACTED UP TO THE FINISHED SPILL THRU SLOPE AND TO THE LEVEL OF THE SUB-GRADE FOR A DISTANCE OF 200 FT. BACK OF THE ABUTMENTS, AFTER WHICH EXCAVATION SHALL BE MADE FOR THE ABUTMENTS.

ALL PILES TO BE 12" CAST-IN-PLACE REINFORCED CONCRETE PILES DRIVEN TO A MINIMUM BEARING CAPACITY OF 40 TONS.

REFERENCE SHALL BE MADE TO STANDARD DRAWINGS:
AR-1-57, DATED 2-2-59 FOR ALUMINUM RAILING.
CSB-2-56, SHEET 2 & 3, DATE 2-2-59
SUPPLEMENTAL SPECIFICATIONS 8-101, DATED 12-2-55.

ELECTRICAL GROUNDS: A SOLID N°0 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON EACH SIDE OF THE STRUCTURE AT PIER N°2. THE LOWER ENDS OF THE WIRE SHALL BE BRAZED TO THE STEEL SHELL OF ONE OF THE CAST-IN-PLACE REINFORCED CONCRETE PILES AND THE UPPER END SHALL EXTEND SUFFICIENTLY ABOVE THE CONCRETE TO PROVIDE A SUITABLE SPLICE & EXTENSION FOR CONNECTION TO THE SUPERSTRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE A N°6 GAGE BARE, STRANDED, TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE AND TO THE SOLID COPPER WIRE IN THE PIER SHAFT. PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM BID FOR ITEM S-25 "ELECTRICAL LIGHTING SYSTEM."

ITEM S-25: ELECTRICAL LIGHTING SYSTEM INCLUDES THE FOLLOWING: 4 EXPANSION FITTINGS, 1-TRSF. BOX & 40 FT. OF 1¼" CONDUIT.
LIGHTING DETAILS ARE SHOWN ON SHEET #309 & 310

FOR ESTIMATED QUANTITIES TABLE - SEE SHEET #413

MACHINE FINISH: The concrete bridge deck shall be finished as specified in the Proposal Note, "Machine Finishing of Bridge Deck Slabs."

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GENERAL PLAN & ELEVATION

BRIDGE NO. MAH-18-1004
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.G.S.	GASKILL		HGH	DNC		


MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

407
492

MAH-18-17.20







NOTE: DIMENSIONS NOT SHOWN SAME AS ABUT. #1

NOTE: THE CONCRETE IN THE ABUTMENT BACKWALL SHALL NOT BE PLACED UNTIL AFTER STEEL WORK IS ERECTED, SHALL BE PLACED BEFORE THE DECK SLAB IS PLACED.

PLAN ABUT. #2

RAILING TO BE CONTINUOUS ON WINGWALLS





ELEVATION OF SOUTH W.W. - ABUT. #1

ELEVATION OF SOUTH W.W. ABUT. #2

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE NO. MAH-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGS	AC		HGH	DHC		

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


408
492



ALL LATERAL DIMENSIONS ARE NORMAL TO ℄ SUBSTRUCTURE UNLESS OTHERWISE NOTED.



ELEVATION OF ABUT. #1 - REFLECTED ELEV. OF ABUT. #2



ELEVATION OF NORTH W.W. ABUT. #1

NOTE: SEE ELEV. OF S. WINGWALL FOR NOTES & DIMENSIONS NOT SHOWN

ELEVATION TABLE

* ELEVATIONS GIVEN TO HEEL OF ANGLE

	A	B	C	D	E	F	G	H	J	K	L	M	AA	BB*	CC*	DD	EE*	FF*	GG*	HH	JJ
ABUT. #1	866.48	866.69	867.30	867.72	868.14	868.49	868.46	868.88	869.31	869.73	869.99	869.57	869.51	870.34	872.42	869.96	872.35	873.92	873.54	872.68	862.01
ABUT. #2	872.38	872.76	873.13	873.51	873.88	874.18	874.15	874.53	874.91	875.29	875.58	875.19	875.43	876.26	878.21	865.90	878.12	879.59	879.17	878.25	867.68

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE NO. MAH-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGS.	AC		H.G.H.	D.W.C.		

MICROFILMED
SEP 19 1995


FED. RD.	STATE	PROJECT	
	OHIO		

MA H-18-17.20


409
492




SECTION CC




SECTION DD




SECTION E-E




SECTION A-A




SECTION BB




SECTION F-F




SECTION C-C
FOR NOTES & DIMENSIONS NOT SHOWN-SEE SECTION F-F



SECTION H-H



SECTION J-J
FOR NOTES & DIMENSIONS NOT SHOWN-SEE SECTION H-H



ABUT. #1 ABUT. #2

SLOPE OF BACKWALL FACES

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE NO. MAH-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGS	AC		H.G.H	DHC.		

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MA H-18+17.20


410
492




SECTION K-K




SECTION L-L




SECTION M-M



SECTION N-N



SECTION P-P



EXPANSION JOINT
DETAIL

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE NO. MA H-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGS.	A C		HGH.	D.H.C.		

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


411
492




PLAN

ELEVATION SCHEDULE


	A	B	C	D	E	F	G	H	J	K	L	M	N	P	R	S	T	W	X	Y
PIER #1	871.25	871.60	871.23	870.82	870.41	870.00	870.10	869.70	869.29	868.88	868.48	868.07	867.60	867.50	866.60	866.10	865.30	864.55	845.0	847.0
PIER #2	873.60	873.91	873.54	873.15	872.75	872.36	872.47	872.08	871.70	871.31	870.91	870.53	869.80	869.80	868.90	868.50	867.75	867.00	846.5	848.0




ELEVATION



SECTION C-C



SECTION B-B



SECTION A-A

NOTE :
1. ALL REINFORCING STEEL SYMMETRICAL ABOUT ℄ PIER UNLESS OTHERWISE SHOWN.
2. ALL REINFORCING STEEL TO HAVE A 2" MIN. COVER UNLESS OTHERWISE NOTED.
3. PILES ARE TO BE 12" CAST-IN-PLACE REINFORCED CONCRETE.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS

BRIDGE NO. MAH-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.G.S.	GASKILL		H.G.H	D.H.C.		

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17,20

412
492

EXTERIOR BEAM BENT AT THIS PIER

EDGE OF SLAB

FACE OF CURB

8'-0"

3 1/16"

1'-1 1/16"

5-SPACES @ 8'-0" = 40'-0"

2'-8"

5-SPACES @ 8'-0" = 40'-0"

25° 43' 27" SKEW

BEAM SPLICES

36 WF 150

36 WF 170

LIGHT SUPPORT BRACKET FOR UNDERSTRUCTURE LIGHT

℄ SUPERSTRUCTURE

℄ SUBSTRUCTURE

FACE OF MEDIAN CURB

66°16'33"

END CROSSFRAMES - 4"x4"x 5/16" Ls
INTERMEDIATE CROSSFRAMES - 3"x3"x5/16" Ls

B

℄ ABUT. SLIDING BEARING

℄ PIER SLIDING BEARING

EDGE OF SLAB

℄ PIER FIXED BEARING

℄ ABUT. SLIDING BEARING

1'-5"

49'-0"

70'-0"


56'-0"


3'-7"

15 CROSSFRAMES - 12 SPACES @ 15'-0" = 180'-0"


FRAMING PLAN

DEFLECTION & CAMBER						
LOCATION	OUTSIDE BEAMS			INSIDE BEAMS		
	49' SPAN	70' SPAN	56' SPAN	49' SPAN	70' SPAN	56' SPAN
DEFLECTION DUE TO WEIGHT OF STEEL	0.04	0.13	0.08	0.02	0.09	0.05
DEFLECTION DUE TO REMAINING DEAD LOAD	0.18	0.67	0.42	0.13	0.44	0.28
CONVEXITY REQ'D FOR VERTICAL CURVE	0.00	0.00	0.00	0.00	0.00	0.00
SUM OF DEFLECTION AND CONVEXITY	0.22	0.80	0.50	0.15	0.53	0.33
REQUIRED CAMBER	0	1"	0	0	1"	0





BEAM SPLICE DETAILS



SECTION Z-Z

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING PLAN

BRIDGE NO. MAH-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGS	GASKILL		H.G.H.	D.H.C.		

NOTE: WHERE NECESSARY, FIELD BEND BARS TO MAINTAIN CLEAR DISTANCE TO FACE OF CONCRETE. (FIELD BENDING INCLUDED WITH ITEM S-4 FOR PAYMENT.)

THESE DIMENSIONS ARE NOMINAL. THE QUANTITY OF DECK CONCRETE TO BE PAID FOR SHALL BE BASED ON THESE DIMENSIONS, EVEN THOUGH DEVIATION FROM THEM MAY BE NECESSARY BECAUSE THE TOP FLANGE OF THE BEAM MAY NOT HAVE THE EXACT CAMBER OR CONFORMATION REQUIRED TO PLACE IT PARALLEL TO THE FINISHED GRADE.


MICROFILMED SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

M A H-18-17.20

413 / 492


SEE RAILING DETAIL SHEET FOR SPACING REINF. BARS IN PARAPET.




TRANSVERSE SECTION

ESTIMATED QUANTITIES


ITEM	TOTAL	SUM	DESCRIPTION	SUPERSTR.	ABUT'S	PIERS	GEN.		
E-2	815	CU. YD.	UNCLASSIFIED EXCAVATION		480	335			
S-1	494	CU. YD.	CLASS "C" CONCRETE SUPERSTRUCTURE	494					
S-1	187	CU. YD.	CLASS "E" CONCRETE ABUT'S. ABOVE FOOTINGS		187				
S-1	134	CU. YD.	CLASS "C" CONCRETE PIERS ABOVE FOOTINGS			134			
S-1	291	CU. YD.	CLASS "E" CONCRETE ABUT. & PIER FOOTINGS		142	149			
S-4	214,542	LBS	REINFORCING STEEL	149,279	14,918	50,345			
S-7	413,800	LBS	STRUCTURAL STEEL	413,800					
S-8	413,800	LBS	FIELD PAINTING OF STRUCTURAL STEEL (AS PER PLAN)	413,800					
I-10	945	SQ. YD.	CRUSHED AGGREGATE SLOPE PROTECTION				945		
S-14	404	LIN. FT.	RAILING (ALUM. RAIL & SUPPORTS.- CONCRETE PARAPET - REINFORCING STEEL)	352	52				
S-16	LUMP	SUM.	FIRST TEST PILE				LUMP		
S-18	3220	LIN. FT.	12" ⌀ CAST-IN-PLACE REINFORCED CONC. PILES		1820	1400			
S-25	LUMP	SUM.	ELECTRICAL LIGHTING SYSTEM						
S-25	350	LIN. FT.	2" DIA. ELECTRICAL CONDUIT (GALV.)	350					
S-29	80	CU. YDS.	POROUS BACKFILL		80				
S-14	176	LIN. FT.	GUARDRAIL-STEEL BEAM TYPE (DEEP) BARRIER	176					
S-25	14	EACH	SCUPPERS	14					



SECTION "B-B"



MEDIAN STRIP DETAIL



REINFORCING PLAN
MEDIAN STRIP

NOTES

1. CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF CONCRETE OF THE DECK SLAB, THE PLACING OF CONCRETE SHALL PROCEED UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS, BETWEEN TRANSVERSE CONSTRUCTION JOINTS WHICH ARE NORMAL TO THE CENTER LINE OF BRIDGE AND ARE LOCATED NEAR THE CENTER ANY SPAN.
2. WELDING PROCEDURE: a) RAISE BEAM ENDS 1" AT ABUTMENT #1 AND 1¼" AT ABUTMENT #2.
   b) BUTT WELD BEAM FLANGES AND WEB USING THE FOLLOWING SEQUENCE. MAKE TWO PASSES ON EACH FLANGE THEN TWO ON WEB, REPEAT; USING ONE PASS AT EACH LOCATION, UNTIL WELD IS COMPLETED.
   c) WELD TOP AND BOTTOM MOMENT PLATES.
   d) LOWER BEAM ENDS INTO PLACE AT ABUTMENTS.
3. WELDING OF STRUCTURAL STEEL SHALL BE CLASS 'A' EXCEPT AS OTHERWISE NOTED. ANY WELDS NOTED AS FIELD WELD MAY, AT THE OPTION OF THE CONTRACTOR, BE MADE IN THE SHOP.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SLAB DETAILS

BRIDGE NO. MA H-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
DGS	GASKILL		H.G.H.	D.H.C.		

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17,20

414/492

MICROFILMED
SEP 19 1985

TOP SER. S604 @ 7½" = 15'-0"
BOTTOM SER. S703 @ 7½" = 15'-0"

251 - S603 250 SPACES @ 7½" = 156'-3" TOP
251 - S702 250 SPACES @ 7½" = 156'-3" BOTTOM
139 SPACES @ 1'-3" = 175'-3" 140 S502 & 280 S503 IN CURB

EDGE OF SLAB (CURVED LINE)

5 S601 IN CURB

FAN 4-S606 TOP
4-S705 BOT.

S601 OR S701

S603 OR S702

S602

35 - S602 OVER PIERS
SEE BAR STAGGERING DETAIL
36 - S601 @ 15" = 45'-9" TOP
36 - S701 @ 15" = 45'-9" BOT.

EDGE OF CONCRETE
℄ ABUTMENT #1 BEARING

S601 OR S701

FAN 4-S606 TOP
4-S705 BOT.

FAN 4-S606 TOP
4-S705 BOT

S602 @ 1'-3" ℄ OVER PIER 28'-0" LG.

S602

36 - S602 OVER PIERS
SEE BAR STAGGERING DETAIL
37 - S601 @ 15" = 45'-0"
37 - S701 @ 15" = 45'-0"

S601 OR S701

℄ PIER

5 S601 IN CURB

EDGE OF SLAB (CURVED LINE)

℄ PIER

℄ ABUTMENT #2 BEARING

EDGE OF CONCRETE

S602

S603 OR S702

FAN 7-S607 TOP 7-S706 BOT.


141 SPACES @ 1'-3" = 176'-3" 142 S502 & 284 S503 IN CURB

253 - S603 252 SPACES @ 7½" = 157'-6" TOP
253 - S702 252 SPACES @ 7½" = 157'-6" BOTTOM

SER. S605 @ 7½" = 14'-4½" TOP
SER. S704 @ 7½" = 14'-4½" BOTTOM

SLAB REINFORCING PLAN


BAR STAGGERING DETAIL OVER PIERS



TYPE "A"

SECTION A-A

SCUPPER DETAILS



TYPE "B"

SECTION B-B


STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


SLAB DETAILS

BRIDGE NO. MA H-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005 + 07.94 To STA. 1006 + 88.08

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D&S.	GASKILL		H&H.	DJC.		



DECK PLAN



ELEVATION

SPIRAL REINFORCEMENT FOR PIERS							
MARK	Nº REQD	CORE DIA.	LGTH. SPIR.	PITCH	Nº TURNS	WEIGHT
SP401	2	2'-8"	20'-3½"	4½"	57	628
SP402	3	2'-8"	19'-7"	4½"	56	924
SP403	1	2'-8"	18'-7"	4½"	53	296
SP404	1	2'-8"	15'-3"	4½"	45	252
SP405	1	2'-8"	16'-1"	4½"	46	254
SP406	1	2'-8"	15'-3½"	4½"	44	242
SP407	1	2'-8"	14'-6½"	4½"	42	232
SP408	1	2'-8"	16'-6"	4½"	47	259
SP409	1	2'-8"	15'-0"	4½"	43	237
SPACERS	48					572
					SPIRAL TOTAL =	3896

SPIRAL REINFORCING NOTES

FOUR STEEL CHANNEL, TEE, OR ANGLE SPACERS WEIGHING APPROXIMATELY 0.68 LB PER LIN. FT., SHALL BE PROVIDED FOR EACH SPIRAL UNIT. THEY SHALL BE EQUALLY SPACED ALONG THE PERIPHERY OF THE COIL. THE NUMBER OF LBS. OF THESE SPACERS, BASED ON 0.68 LB PER LIN. FT., WILL BE PAID FOR AS REINFORCING STEEL AND IS INCLUDED IN TABULATED QUANTITY OF SPIRAL BARS.

THE LENGTH SHOWN IN THE SCHEDULE FOR SPIRAL BARS IS THE DISTANCE FROM THE TOP OF THE FOOTING TO THE BOTTOM OF THE PIER CAP.

THE Nº OF TURNS SHOWN IN THE SCHEDULE FOR SPIRAL BARS IS THE LGTH. DIVIDED BY THE PITCH PLUS THREE TURNS. (TOTAL NUMBER OF CLOSED COILS) EXPRESSED AS THE NEAREST WHOLE NUMBER.

SPIRAL REINFORCING BARS SHALL NOT HAVE DEFORMATIONS BUT SHALL IN OTHER RESPECTS CONFORM TO ITEM 5-4 (REINFORCING STEEL).

1½ CLOSED COILS SHALL BE PROVIDED AT THE END OF EACH SPIRAL UNIT.

NOTE: BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED, AND THE FIRST TWO DIGITS WHERE FOUR ARE USED, INDICATE THE BAR SIZE NUMBER. FOR EXAMPLE, A700 IS A #7 SIZE BAR & A1014 IS #10 SIZE.

REPLACEMENT BARS: IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SEC. 5-4.02 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.

MAH-18-17.20

FED. RD.	STATE	PROJECT	
	OHIO		

415 / 492


RAILING REINFORCEMENT BARS TO BE PAID FOR AS PART OF ITEM 5-14 (RAILING)

REINFORCING STEEL SCHEDULE

MARK	Nº REQ'D	LENGTH	WEIGHT	SHAPE
ABUTMENT				
A501	8	26'-6"	221	ST.
A502	8	25'-9"	215	ST.
A503	2	10'-11"	23	ST.
A504	2	7'-4"	15	ST.
A505	2	5'-8"	12	ST.
A506	14	4'-6"	66	ST.
A507	16	4'-6"	75	BT.
A508	96	7'-6"	751	BT.
A509	178	6'-6"	1207	BT.
A510	85	6'-0"	219	ST.
A511	112	3'-11"	458	BT.
A512	3	9'-7"	30	BT.
A513	3	8'-2"	26	ST.
A514	8	14'-0"	117	ST.
A515	3	9'-0"	28	ST.
A516	4	5'-9"	22	BT.
A517	9	4'-0"	38	ST.
A518	175	7'-3"	1324	BT.
A519	54	8'-0"	451	BT.
A520	32	7'-6"	250	BT.
A521	36	7'-0"	263	ST.
A522	4	9'-8"	41	BT.
A523	4	9'-5"	39	ST.
A524	3	12'-0"	39	ST.
A525	52	26'-0"	1410	ST.
A526	2	38'-4"	80	ST.
A527	2	13'-5"	28	ST.
A528	4	29'-6"	123	ST.
A529	4	11'-6"	48	ST.
A530	2	8'-11"	19	ST.
A531	118	6'-9"	831	BT.
A532	52	25'-0"	1356	ST.
A533	2	36'-3"	76	ST.
A534	2	7'-9"	16	ST.
A535	4	6'-1"	25	BT.
A536	4	7'-3"	31	BT.
A537	4	11'-4"	48	ST.
A538	2	10'-10"	23	BT.
A539	10	2'-10"	30	BT.
A540	4	2'-9"	11	BT.
A541	4	2'-8"	11	BT.
A542	4	2'-7"	11	BT.
A543	4	2'-6"	10	BT.
A544	4	2'-4"	10	BT.
A545	4	2'-2"	9	BT.
A546	4	2'-0"	8	BT.
A547	4	1'-10"	8	BT.
A548	4	1'-8"	7	BT.
A549	4	1'-6"	6	BT.

MARK	Nº REQ'D	LENGTH	WEIGHT	SHAPE
A550	2	17'-1"	25	BT.
A551	4	12'-2"	50	ST.
A552	2	3'-0"	6	BT.
A553	84	6'-2"	219	BT.
A554	2	11'-3"	23	ST.
A555	4	9'-11"	41	BT.
A556	4	8'-8"	36	ST.
A557	3	5'-10"	31	BT.
A558	3	10'-3"	57	BT.
A559	4	15'-10"	66	ST.
A560	4	10'-2"	43	ST.
A561	4	13'-6"	58	ST.
A562	2	13'-0"	27	BT.
A563	2	14'-6	30	BT.
A564	4	14'-2"	59	ST.
A565	4	7'-6"	32	BT.
A566	2	8'-0"	17	ST.
A601	76	13'-1"	1493	BT.
A602	108	15'-2"	2460	BT.
TOTAL FOR ABUTMENTS			14,918	
SLAB				
S501	280	4'-7"	1339	BT.
S502	282	1'-9"	515	ST.
S503	564	2'-1"	1225	BT.
S504	141	4'-3"	625	BT.
S505	141	4'-9"	699	BT.
S506	142	5'-4"	790	BT.
S507	142	5'-10"	864	BT.
S601	415	36'-11"	23015	ST.
S602	142	28'-0"	5972	ST.
S603	504	45'-4"	32804	ST.
SERIES	3 SETS 25 = 75	VARIES 6'-11" TO 40-11'@1'-5	2691	ST.
S604				
SERIES	24	VARIES 10'-0" TO 40-8'@1'-4	918	ST.
S605				
S606	12	6'-6"	117	ST.
S607	7	8'-6"	89	ST.
S701	365	37'-5"	27791	ST.
S702	504	45'-4"	44641	ST.
SERIES	3 SETS 25 = 75	VARIES 6'-11" TO 40-11'@1'-5	3666	ST.
S703				
SERIES	24	VARIES 10'-0" TO 40-8'@1'-4	1243	ST.
S704				
S705	12	6'-6"	160	ST.
S706	7	8'-6"	122	ST.
TOTAL FOR SLAB			148,279	

MARK	Nº REQ'D	LENGTH	WEIGHT	SHAPE
RAILINGS				
R501	4	11'-0"		ST.
R502	12	11'-9"		ST.
R505	18	12'-6"		ST.
R504	4	13'-0"		ST.
R505	4	13'-10"		ST.
R506	80	14'-10"		ST.
PIERS				
P501	184	7'-8"	1472	BT.
P502	224	7'-8"	1722	ST.
P601	160	7'-8"	1843	BT.
P901	24	23'-3"	1697	ST.
P902	36	22'-3"	2723	ST.
P903	12	21'-6"	877	ST.
P904	12	18'-8"	762	ST.
P905	12	19'-0"	775	ST.
P906	12	18'-2"	741	ST.
P907	12	17'-6"	714	ST.
P908	144	7'-11"	3468	BT.
P909	32	25'-0"	2720	ST.
P910	52	15'-0"	2652	ST.
P911	24	44'-0"	3550	BT.
P912	44	20'-0"	2992	ST.
P913	48	41'-6"	6773	ST.
P914	12	13'-4"	789	ST.
P915	12	17'-10"	725	ST.
P916	8	9'-0"	245	BT.
P1001	12	9'-10"	508	BT.
P1002	24	14'-0"	1446	ST.
P1003	16	41'-10"	2823	ST.
P1004	36	16'-5"	2543	ST.
P1005	28	13'-1"	1576	BT.
PIER TOTAL			46,449	
PIER TOTAL (INCL. SPIRALS)			50,345	
REPLACEMENT ST'L.				
RE401	1	5'-3"		BT.
RE501	2	5'-6"		ST.
RE601	4	6'-0"		ST.
RE701	4	6'-5"		ST.
RE901	2	6'-6"		ST.
RE1001	1	7'-2"		ST.
GRAND TOTAL FOR BRIDGE			214,542	



REINFORCING STEEL BENDING DIAGRAMS

SECTION A-A
(SEE STANDARD DWG. I-15 Nº 2A)

MICROFILMED
SEP 19 1985

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

REINFORCING SCHEDULE

BRIDGE NO. MAH-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	GASKILL		D.S.	DHC.		

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

416
492



GEOMETRIC LAYOUT

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GEOMETRIC LAYOUT

BRIDGE NO. MA H-18-1904
OVER OAK HILL AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1005+07.94 To STA. 1006+88.08

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
D.G.S.	GASKILL		H.G.H.	D.H.C.		


MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


417/492

RENNER BREWERY





SECTION A-A



SECTION B-B

CURVE DATA

$\Delta = 74°52'50"$
$D_c = 2°45'$
$R_c = 2088.48'$
$L_s = 300'$
$\Theta_s = 4°07'30"$
$L_c = 2422.99'$
$T_s = 1746.41'$
$E_s = 541.86'$
X = 299.84'
Y = 17.197'

FOUNDATION SOUNDINGS


FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF ROD SOUNDINGS AND SOIL-SAMPLING SOUNDINGS MADE AT THE SITE. THIS SOUNDING INFORMATION MAY BE INSPECTED AT THE OFFICE OF THE BUREAU OF BRIDGES IN COLUMBUS OR IN THE DIVISION OFFICE, BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THERE OF.

PROPOSED STRUCTURE

TYPE: CONTINUOUS CONCRETE SLAB DECK WITH CAPPED PILE SUBSTRUCTURES
SKEW: 0°00'
SPANS: TWO UNITS OF 28'-35'-35'-35'-30'-3.75' ℄ BRGS & EXP. JT.
ROADWAY: 47'-10" F/F CURBS WESTBOUND LANE
LOAD FREQUENCY: CF 2000 (ADEQUATE FOR AASHO ALT. LOADING)
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLABS: 25' LONG - AS-1-54
ALIGNMENT: SAME AS ROADWAY (SUBSTRUCTURE STRAIGHT)
SUPERELEVATION: VARIES

SLOPE PROTECTION

6'x6' PADS OF CRUSHED AGGREGATE SLOPE PROTECTION SHALL BE CENTERED UNDER EACH SCUPPER WHICH DRAINS ONTO SLOPE UNDER STRUCTURE.



ESTIMATED PAY LENGTH OF PILES
ABUT. 1 - PIER 5 = 30' EACH
PIER 6 - ABUT. 2 = 40' EACH

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SITE PLAN

BRIDGE Nº MAH-18-1923
RENNER BREWERY BYPASS BRIDGE
YOUNGSTOWN MAHONING COUNTY
STA. 1015+83.75 TO STA. 1019+18.75


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH	GASKILL		ew	DJC		

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

418
492

MICROFILMED
SEP 19 1985



PLAN

MACHINE FINISH: At the Contractor's option the top of the bridge deck slab maybe machine finished. Machane finishing, if used, shall be in accordance with the Proposal Note, "Machine Finishing of Bridge Deck Slabs".

GENERAL NOTES (CONT.)

ITEM S-25: ELECTRICAL LIGHTING SYSTEM INCLUDES THE FOLLOWING ITEMS; 1 EXPANSION FITTING, ONE GALV. CAST IRON BOX AND 4-1" DIA. ANCHOR BOLTS. LIGHTING DETAILS ARE SHOWN ON SHEET # 310


GENERAL NOTES

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS, DATED 9-1-57, TOGETHER WITH CURRENT REVISIONS THEREOF.

PILING: ALL PILES ARE TO BE 14" MIN. TOP DIAMETER CAST-IN-PLACE REINFORCED CONCRETE-DRIVEN TO A MIN. BEARING CAPACITY OF 30 TONS.

EXCAVATION QUANTITY INCLUDES THE REMOVAL OF MATERIAL BETWEEN THE SURFACE OF THE PROPOSED FINISHED GRADE AND THE BOTTOM OF THE ABUTMENT FOOTING FOR ABUT. #1 AND INCLUDES THE REMOVAL OF FILL MATERIAL BETWEEN THE SURFACE OF THE PROPOSED EMBANKMENT AND THE BOTTOM OF FOOTINGS FOR ABUT. #2.

PILE PROCEDURE AT PIERS: THE EXCAVATION & FILL SHALL BE AT GRADE LEVEL BEFORE THE DRIVING OF PILES.




ELEVATION

WELDING: WELDING OF STRUCTURAL STEEL SHALL BE CLASS "A" EXCEPT AS OTHERWISE SHOWN.

REFERENCE SHALL BE MADE TO STANDARD DWGS. CS-2-54 SHEETS 1 & 2 DATED 12-1-54 REVISED 2-2-59, P-1-54 DATED 7-1-54 REVISED 2-2-59, & AR-1-57 DATED 4-9-57 REVISED 2-2-59 SUPPLEMENTAL SPECIFICATION S-101 DATED 12-2-59

CONSTRUCTION JOINTS: ONE CONSTRUCTION JOINT IN THE MIDDLE OF EACH 35 FT. SPAN OR 1'-0"± OFF THE CENTER-LINE IF NECESSARY TO MISS ANY TRANSVERSE REINFORCING BARS. ONE LONGITUDINAL JOINT ON THE ℄ OF THE WEST BOUND LANES WILL BE PERMITTED


ELECTRICAL GROUNDS: A SOLID Nº 0 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE IMBEDDED IN THE PIER CAP ON THE EAST SIDE OF THE STRUCTURE AT PIER Nº 5. THE LOWER END OF WIRE SHALL BE BRAZED TO THE STEEL SHELL OF ONE OF THE 14" CAST-IN-PLACE CONCRETE PILES AND THE UPPER END SHALL EXTEND SUFFICIENTLY ABOVE THE TOP OF THE PIER CAP TO PROVIDE A SUITABLE SPLICE FOR CONNECTION TO A GROUNDING LUG INSIDE THE BASE OF THE LIGHT STANDARD. THE CONNECTION FROM THE LIGHT STANDARD TO THE SOLID COPPER WIRE IN THE PIER CAP SHALL BE A Nº 6 GAGE BARE TINNED COPPER WIRE. PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM BID FOR ITEM S-25 "ELECTRICAL LIGHTING SYSTEM"



REFERENCE DIAGRAM FOR FINISHED GRADE ELEVATIONS.

FINISHED GRADE ELEVATIONS

	STA.	PG	A	B	C
ABUT. #1	1015+84.50	907.51	907.72	908.10	909.06
PIER #1	1016+12.50	908.45	908.68	908.94	909.73
PIER #2	41.50	908.57	908.76	910.00	910.56
PIER #3	82.50	910.71	910.92	911.11	911.31
PIER #4	1017+17.50	911.85	912.06	912.25	912.13
PIER #5	41.50	912.83	913.04	913.25	912.91
℄ EXP.	1017+51.25	912.95	913.16	913.36	913.01
PIER #6	55.00	913.07	913.28	913.47	913.10
PIER #7	85.00	914.05	914.26	914.45	913.97
PIER #8	1018+20.00	915.19	915.40	915.59	915.11
PIER #9	55.00	916.33	916.54	916.73	916.25
PIER #10	90.00	917.47	917.68	917.87	917.39
ABUT. #2	1019+18.00	918.39	918.60	918.79	918.31



SECTION A-A

ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER	ABUT.	PIERS	GEN'L
E-2	157	CU.YDS	UNCLASSIFIED EXCAVATION		157		
S-1	1217	CU.YDS	CLASS "C" CONC. SUPSTR. & PIER CAPS	1217			
S-1	36	CU.YDS	CLASS "E" CONCRETE, ABUTMENTS		36		
S-1	25	CU.YDS	CLASS "E" CONC., ABUT. FOOTINGS		25		
S-9	355'	LIN. FT.	3"x1" PREFORMED EXP. JT. FILLER	355'			
S-4	268,898	LB	REINFORCING STEEL	234,753	4819	29,326	
S-9	2,070	LB	STRUCTURAL STEEL EXP. JOINT INCL. PAINTING	2,070			
S-14	354	LIN. FT.	RAILING (ALUM. RAIL & SUPPORTS CONC. PARAPETS, & REIN. STEEL.)	335	19		
S-16		LUMP	FIRST TEST PILE				
S-18	4760	LIN. FT.	14" DIA. CAST-IN-PLACE REIN. CONC. PILES		560	4200	
S-25	LUMP	SUM	ELECTRICAL LIGHTING SYSTEM ●				
S-25	368	LIN. FT.	2" ϕ ELECTRICAL CONDUIT (GALV.)	368			
S-29	16	CU.YDS.	POROUS BACKFILL		16		
S-29	33	EACH	SCUPPERS (WROUGHT IRON OR CAST IRON PIPE & INCIDENTALS)	33			
I-10	16	SQ. YDS	CRUSHED AGG. SLOPE PROTECTION				16

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GENERAL PLAN & ELEVATION

BRIDGE Nº MAH-18-1923

RENNER BREWERY BYPASS BRIDGE

YOUNGSTOWN MAHONING COUNTY


STA. 1015+83.75 TO STA. 1019+18.75

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH	A C		cw.	DMC		


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

419
492




PLAN
ABUT. #1




PLAN
ABUT. #2

NOTE:
FOR DIMENSIONS & DETAILS NOT SHOWN - SEE PLAN, ABUT. 1




SECTION C-C

MICROFILMED
SEP 19 1985




SECTION H-H
FOR DIMENSIONS & BAR NOS. NOT SHOWN - SEE SECTION C-C

NOTE: FOR SPACING OF RAILING POSTS, SEE DRAINAGE DWG. 423



ELEVATION - WINGWALL
ABUT. #2



ELEVATION - WINGWALL
ABUT. #1

NOTE:

PROCEDURE - THE EMBANKMENT SHALL BE PLACED AND COMPACTED UP TO THE FINISHED SPILL-THRU SLOPE AND TO THE LEVEL OF THE SUBGRADE FOR A DISTANCE OF 200 FT BACK OF ABUTMENT #2, AFTER WHICH EXCAVATION SHALL BE MADE FOR THE ABUTMENT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 & #2 PLAN & ELEVATION

BRIDGE No. MAH-18-1923
RENNER BREWERY BYPASS BRIDGE
YOUNGSTOWN MAHONING COUNTY
STA. 1015+83.75 To STA. 1019+18.75


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH	AC		aw	DJC		

FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18-17.20

420
492


MICROFILMED
SEP 19 1965




ELEVATION
ABUT. #1




PARTIAL ELEVATION
ABUT. #2



SECTION A-A




SECTION BB
FOR DIMENSIONS & BAR NUMBERS NOT SHOWN - SEE SECTION AA




FOR DIMENSIONS & BAR NUMBERS - SEE SECTION


SECTION C-C




SECTION E-E




SECTION D-D



SECTION J-J




SECTION K-K



SECTION F-F AS SHOWN
SECTION F'-F' SIMILAR BUT OPP. HAND.

PILE CUT-OFF ELEVATIONS

ABUT. #1	902.00
PIER #1	905.42
PIER #2	906.56
PIER #3	907.70
PIER #4	908.84
PIER #5	909.82
PIER #6	910.06
PIER #7	911.11
PIER #8	912.25
PIER #9	913.39
PIER #10	914.53
ABUT. #2	912.75



PILE PLAN

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT DETAILS

BRIDGE Nº MAH-18-1923
RENNER BREWERY BYPASS BRIDGE
YOUNGSTOWN MAHONING COUNTY
STA. 1015+83.75 TO STA. 1019+18.75


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH	AC		CW	DJC		

FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18-17.20

421
492


MICROFILMED
SEP 19 1965




PLAN




SECTION H-H




ELEVATION



SECTION G-G




SECTION D-D




PLAN


DETAIL "J"




SECTION 1-1



SECTION 2-2




DETAIL OF PILE ENCASEMENT




SECTION E-E

BAR NOS. S-904 & S-905 ARE SYMMETRICAL ABOUT ℄ OF SPAN.




SECTION 4-4




SKETCH SHOWING PILE ENCASEMENT

NOTE: FOR STEEL SPACING NOT SHOWN IN SECTIONS D-D, E-E OR F-F SEE SLAB PLAN & ELEVATION




SECTION F-F



DETAIL "K"

DETAIL "L" - OPPOSITE HAND, SIMILAR EXCEPT AS SHOWN



SECTION 5-5

PILE CASINGS: THE CASINGS OF CAST-IN-PLACE CONCRETE PILES SHALL BE OF THE TYPE THAT IS LEFT IN PLACE AND IS DESIGNED TO RESIST BOTH DIRECT COMPRESSION AND BENDING. THE PORTION ABOVE THE CIRCULAR CONCRETE ENCASEMENT SHALL BE OF UNIFORM DIAMETER (NOT TAPERED) AND SHALL HAVE A THICKNESS OF METAL NOT LESS THAN No. 7 GAUGE.

PILE ENCASEMENT AS SHOWN IN SKETCH BELOW AND ON STD. DWG. NO. P-1-64, MAY BE OMITTED PROVIDED THAT THE TAPERED PORTION, IF ANY, OF ALL PIER PILES DOES NOT EXTEND ABOVE THE PROPOSED SURFACE OF THE GROUND. IF THE TAPERED PORTION OF ANY PILES EXTENDS ABOVE THESE LIMITATIONS, THE ENCASEMENT WILL BE REQUIRED FOR ALL PIER PILES. IF THE ENCASEMENT IS OMITTED THE PILE CASINGS SHALL HAVE A THICKNESS OF METAL NOT LESS THAN NO. 7 GUAGE AND THE PAINTING OF THE PILES SHALL EXTEND TO AT LEAST ONE FOOT BELOW THE PROPOSED SURFACE OF THE GROUND.

PILE PAINTING: THE EXPOSED PORTION OF THE PILES, ABOVE THE ENCASEMENT, SHALL BE PAINTED IN ACCORDANCE WITH ITEM 5-8 APPLYING TWO COATS AS PER SECS. M-9.5, M-9.10 OR M-9.21 AND TWO COATS AS PER SEC. M-9.12. METAL FORMS, LEFT IN PLACE ON THE ENCASEMENT, UNLESS GALVANIZED, SHALL BE SIMILARLY PAINTED.

PAYMENT FOR PILES, PER LIN. FT. INCLUDES PAYMENT FOR THE ENCASEMENT (CONCRETE, REINFORCEMENT, FORMS, PAINTING, GALVANIZING AND EXCAVATING) AND THE PILE PAINTING. THE ELEVATION DESIGNATED, AS PER SEC. E-18.13, SHALL BE CONSIDERED AS BEING ABOVE THE BOTTOM OF THE CONCRETE CAP FOR CAST-IN-PLACE CONCRETE PILES.

FALSEWORK SUPPORT: THE PIER CAP SHALL NOT BE USED TO SUPPORT FALSEWORK FOR THE DECK SLAB.

HORIZONTAL CONSTRUCTION JOINT BETWEEN THE TOP OF THE PIER CAP AND BOTTOM OF SLAB WILL BE PERMITTED IF KEYS, AS SHOWN, ARE PROVIDED AT THE TOP OF THE CAP IF SUCH A JOINT IS NOT PROVIDED, THE CONCRETE IN THE SLAB AND CAP SHALL BE PLACED IN A CONTINUOUS OPERATION.

PIER CAP CONCRETE QUANTITY IS INCLUDED WITH SUPERSTRUCTURE CONCRETE FOR PAYMENT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BIENWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SUPERSTRUCTURE & PIER DETAILS

BRIDGE Nº MAH-18-1923
RENNER BREWERY BYPASS BRIDGE
YOUNGSTOWN MAHONING COUNTY
STA. 1015+83.75 TO STA. 1019+18.75


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	SHEET NO.
RDH	JLH		DWH	DJC		

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

422
492




SECTION B-B


B

SECTION A-A

A




DETAIL OF CONSTRUCTION JOINT



PORTIONS OF 4"x4"x½" ∠'S IN CONTACT WITH STEEL OR WITH CONCRETE WILL NOT BE PAINTED. ALL OTHER PORTIONS SHALL BE CLEANED AND GIVEN THE SHOP COAT AS WELL AS THE FIELD COATS.


NOTE: BAR NOS & LENGTHS ARE SYMMETRICAL ABOUT ℄ OF EXPANSION JOINT.




STEEL IN TOP OF SLAB

STEEL IN BOT. OF SLAB


PARTIAL PLAN



DETAIL OF LIGHT STANDARD SUPPORT



SECTION A-A



ANCHOR BOLT DETAIL

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SUPERSTRUCTURE DETAILS

BRIDGE Nº MAH-18-1923
RENNER-BREWERY BYPASS BRIDGE
YOUNGSTOWN MAHONING COUNTY
STA. 1015+83.75 TO STA. 1019+16.75


DESIGNED	DRAWN	TRACED	CHECKED	REVISED	DATE	REVISED
RBH	JLH			DAC		

MICROFILMED
SEP 19 1965


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

423
492




PLAN
(EAST SIDE) NORTH OF 2" OPEN JOINT




PLAN
(EAST SIDE) SOUTH OF EXPANSION JOINT

NOTE: FOR SCUPPER SPACING SEE GENERAL PLAN

SEE STANDARD DWG. AR-1-57 FOR ALUMINUM RAILING DETAILS



SECTION A-A



SECTION B-B


NOTES:


REPLACEMENT BARS: IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SEC. 401.3 WILL NOT BE FURNISHED & REPLACEMENT BARS WILL NOT BE REQUIRED.


BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST TWO NUMERALS, 3 DIGITS AND THE FIRST 2 DIGITS WHERE 4 DIGITS ARE USED INDICATES THE SIZE NUMBER. FOR EXAMPLE, S-701 IS A NUMBER 7 SIZE BAR & P-1101 IS A NUMBER 11 SIZE BAR.

RAILING BARS ARE INCLUDED WITH ITEM S-14 FOR PAYMENT

15'-0"	1'-1"	S-802
22'-9"	1'-1"	S-902
20'-0"	1'-1"	S-903
9'-6"	1'-3"	S-1006
7'-11"	1'-3"	S-1007
7'-11"	1'-5"	S-1101







REINFORCING STEEL SCHEDULE


MARK	No. PCS.	LENGTH	WEIGHT	SHP.
PIERS				
P-401	480	5'-3	1683	BT
P-501	40	6'-4	204	BT
P-502	40	25'-6	1064	ST
P-503	561	7'-6	2824	BT
P-504	48	9'-6	476	BT
P-505	17	10'-5	189	BT
P-506	84	9'-10	349	BT
P-701	720	4'-0"	5881	ST
P-901	80	26'-1"	7095	ST
P-1001	80	27'-7"	9,495	ST
TOTAL =			29,826#	
SLAB				
S-501	6	20'-7"	129	ST
S-502	36	18'-11"	710	ST
S-503	412	2'-10"	1218	BT
S-504	412	5'-8"	2435	BT
S-505	6	21'-4"	134	ST
S-506	412	2'-4"	1003	BT
S-507	12	13'-11"	174	ST
S-508	229	4'-5"	1036	BT
S-509	412	5'-4"	2292	BT


MARK	No. PCS.	LENGTH	WEIGHT	SHP.
S-601	460	26'-11"	18,597	ST
S-602	46	16'-6"	1,140	ST
S-603	46	8'-6"	587	ST
S-604	138	13'-8"	2,850	ST
S-605	16	5'-6"	132	ST
S-606	4	9'-7"	58	BT


REPLACEMENT BAR SCHEDULE			
RE-401	1	5'-3"	ST.
RE-501	1	5'-7"	ST.
RE-601	2	5'-11"	ST.
RE-701	2	6'-3"	ST.
RE-801	1	6'-6"	ST.
RE-901	6	2'-10"	ST.
RE-1001	4	7'-2"	ST.
RE-1101	1	7'-6"	ST.


MARK	No. PCS.	LENGTH	WEIGHT	SHP.
SLABS (CONT')				
S-701	588	27'-2"	32,651	ST
S-801	80	10'-3"	4,112	ST
S-802	20	14'-1"	752	BT
S-901	510	35'-6"	61,546	ST
S-902	48	23'-10"	3,893	BT
S-903	48	21'-1"	3,440	BT
S-904	192	22'-0"	14,361	ST
S-905	192	17'-2"	11,206	ST
S-1001	90	26'-7"	10,295	ST
S-1002	176	12'-3"	9,271	ST
S-1003	176	8'-10"	6,690	ST
S-1004	270	25'-2"	29,299	ST
S-1005	90	16'-2"	6,261	ST
S-1006	44	10'-11"	2,067	BT
S-1007	44	9'-2"	1,736	BT
S-1101	90	9'-4"	4,461	BT
TOTAL =			234,763#	
RAILING				
R-501	4	8'-6"		ST
R-502	32	17'-5"		ST
R-503	8	14'-1"		ST
R-504	32	17'-6"		ST
R-505	4	10'-1"		ST
R-506	4	11'-6"		ST
R-507	4	9'-7"		ST
R-508	2	11'-5"		ST
R-509	4	13'-1"		ST


MARK	No. PCS.	LENGTH	WEIGHT	SHP.
ABUTMENTS				
A-401	64	5'-3"	239	BT.
A-501	16	27'-5"	455	ST
A-502	104	2'-8"	289	ST
A-503	184	6'-0"	1151	BT
A-504	32	26'-9"	893	ST
A-505	2	36'-6"	73	ST
A-506	26	6'-6"	176	BT
A-507	25	8'-2"	213	BT
A-508	51	4'-10"	257	BT
A-509	23	7'-5"	178	BT
A-510	7	8'-10"	64	BT
A-511	4	7'-1"	30	ST
A-512	4	8'-9"	36	ST
A-513	7	5'-8"	41	ST
A-514	4	3'-8"	15	ST
A-515	14	2'-2"	32	ST
A-516	2	6'-1"	13	BT
A-517	2	10'-5"	22	BT
A-518	2	8'-0"	17	ST
A-519	36	3'-11"	147	BT
A-520	4	4'-6"	27	BT
A-521	11	4'-8"	51	BT
A-522	3	8'-1"	25	BT
A-523	12	7'-9"	97	BT
A-524	2	13'-6"	28	BT
A-525	2	10'-9"	22	ST
A-526	13	4'-0"	25	ST
A-527	6	7'-8"	48	ST
A-528	3	11'-0"	25	BT
SERIES A-529 VARYING FROM 11'-0" TO 11'-10½" INCR. OF 1½"				
A-530	4	10'-3"	43	ST
A-531	3	11'-0"	34	BT
SERIES A-532 VARYING FROM 1'-0" TO 1'-10" INCR. OF 1"				
A-533	2	4'-4"	9	BT
TOTAL ABUTMENTS = 4819#				
GRAND TOTAL = 268,800#				











STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RAILING DETAILS & REINFORCING SCHEDULE

BRIDGE No. MAH-18-1923
RENNER BREWERY BYPASS BRIDGE
YOUNGSTOWN MAHONING COUNTY
STA. 1015+83.75 To STA. 1019+18.75

DESIGNED	DRAWN	TRACED	CHECKED	REVISED	DATE	SHEET
ADH	JLH		ew	D&E		

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

424
492

MAH-18-17.26

MEDICAL BUILDING

RETAINING WALL

STANDARD 6" CURB

7+00

10'-02" MIN. CLEAR

PROP MIN. CLEAR.

BEGIN APP SLAB STA. 49+75.43

℄ EXIST. STATE ROUTE 18

℄ ENTRANCE RAMP "L"

5+00

6+00

END RAMP "N" STA. 1023+13.50

18+00

ACCELERATION LANE (RAMP N)

℄ WEST-BOUND LANES

℄ SURVEY OF STATE ROUTE 18

1024+00

1023+00

℄ EAST-BOUND LANES

960

EXIT RAMP "K"

10+00

9+00

8+00

7+00

6+00

SR 18 CURVE DATA
Δ = 53°49'25"
D = 5°45'00"
R = 400'
L = 996.45'
e = 11°30-00" 956
Ts = 708.91
E = 128.51
Lc = 536.06

15°27'25" SKEW

81'-6"

78'-0"

25'-5"

25'-5"

2:1

2:1

2:1

2:1

℄ PT STA 48+82.43

℄ PE STA 49+03.45

943.13

STA 49+75.43
944.14

945.04

946.44

947.31

947.60

947.65

948

949

950

951

952

953

954

955

956

957

958

959

960

961

962

963

964

965

966

967

968

969

970

971

972

973

974

975

976

977

978

979

980

981

982

983

984

985

986

987

988

989

990

991

992

993

994

995

996

997

998

999

1000

1001

1002

1003

1004

1005

1006

1007

1008

1009

1010

1011

1012

1013

1014

1015

1016

1017

1018

1019

1020

1021

1022

1023

1024

1025

1026

1027

1028

1029

1030

1031

1032

1033

1034

1035

1036

1037

1038

1039

1040

1041

1042

1043

1044

1045

1046

1047

1048

1049

1050

1051

1052

1053

1054

1055

1056

1057

1058

1059

1060

1061

1062

1063

1064

1065

1066

1067

1068

1069

1070

1071

1072

1073

1074

1075

1076

1077

1078

1079

1080

1081

1082

1083

1084

1085

1086

1087

1088

1089

1090

1091

1092

1093

1094

1095

1096

1097

1098

1099

1100

1101

1102

1103

1104

1105

1106

1107

1108

1109

1110

1111

1112

1113

1114

1115

1116

1117

1118

1119

1120

1121

1122

1123

1124

1125

1126

1127

1128

1129

1130

1131

1132

1133

1134

1135

1136

1137

1138

1139

1140

1141

1142

1143

1144

1145

1146

1147

1148

1149

1150

1151

1152

1153

1154

1155

1156

1157

1158

1159

1160

1161

1162

1163

1164

1165

1166

1167

1168

1169

1170

1171

1172

1173

1174

1175

1176

1177

1178

1179

1180

1181

1182

1183

1184

1185

1186

1187

1188

1189

1190

1191

1192

1193

1194

1195

1196

1197

1198

1199

1200

1201

1202

1203

1204

1205

1206

1207

1208

1209

1210

1211

1212

1213

1214

1215

1216

1217

1218

1219

1220

1221

1222

1223

1224

1225

1226

1227

1228

1229

1230

1231

1232

1233

1234

1235

1236

1237

1238

1239

1240

1241

1242

1243

1244

1245

1246

1247

1248

1249

1250

1251

1252

1253

1254

1255

1256

1257

1258

1259

1260

1261

1262

1263

1264

1265

1266

1267

1268

1269

1270

1271

1272

1273

1274

1275

1276

1277

1278

1279

1280

1281

1282

1283

1284

1285

1286

1287

1288

1289

1290

1291

1292

1293

1294

1295

1296

1297

1298

1299

1300

1301

1302

1303

1304

1305

1306

1307

1308

1309

1310

1311

1312

1313

1314

1315

1316

1317

1318

1319

1320

1321

1322

1323

1324

1325

1326

1327

1328

1329

1330

1331

1332

1333

1334

1335

1336

1337

1338

1339

1340

1341

1342

1343

1344

1345

1346

1347

1348

1349

1350

1351

1352

1353

1354

1355

1356

1357

1358

1359

1360

1361

1362

1363

1364

1365

1366

1367

1368

1369

1370

1371

1372

1373

1374

1375

1376

1377

1378

1379

1380

1381

1382

1383

1384

1385

1386

1387

1388

1389

1390

1391

1392

1393

1394

1395

1396

1397

1398

1399

1400

1401

1402

1403

1404

1405

1406

1407

1408

1409

1410

1411

1412

1413

1414

1415

1416

1417

1418

1419

1420

1421

1422

1423

1424

1425

1426

1427

1428

1429

1430

1431

1432

1433

1434

1435

1436

1437

1438

1439

1440

1441

1442

1443

1444

1445

1446

1447

1448

1449

1450

1451

1452

1453

1454

1455

1456

1457

1458

1459

1460

1461

1462

1463

1464

1465

1466

1467

1468

1469

1470

1471

1472

1473

1474

1475

1476

1477

1478

1479

1480

1481

1482

1483

1484

1485

1486

1487

1488

1489

1490

1491

1492

1493

1494

1495

1496

1497

1498

1499

1500

1501

1502

1503

1504

1505

1506

1507

1508

1509

1510

1511

1512

1513

1514

1515

1516

1517

1518

1519

1520

1521

1522

1523

1524

1525

1526

1527

1528

1529

1530

1531

1532

1533

1534

1535

1536

1537

1538

1539

1540

1541

1542

1543

1544

1545

1546

1547

1548

1549

1550

1551

1552

1553

1554

1555

1556

1557

1558

1559

1560

1561

1562

1563

1564

1565

1566

1567

1568

1569

1570

1571

1572

1573

1574

1575

1576

1577

1578

1579

1580

1581

1582

1583

1584

1585

1586

1587

1588

1589

1590

1591

1592

1593

1594

1595

1596

1597

1598

1599

1600

1601

1602

1603

1604

1605

1606

1607

1608

1609

1610

1611

1612

1613

1614

1615

1616

1617

1618

1619

1620

1621

1622

1623

1624

1625

1626

1627

1628

1629

1630

1631

1632

1633

1634

1635

1636

1637

1638

1639

1640

1641

1642

1643

1644

1645

1646

1647

1648

1649

1650

1651

1652

1653

1654

1655

1656

1657

1658

1659

1660

1661

1662

1663

1664

1665

1666

1667

1668

1669

1670

1671

1672

1673

1674

1675

1676

1677

1678

1679

1680

1681

1682

1683

1684

1685

1686

1687

1688

1689

1690

1691

1692

1693

1694

1695

1696

1697

1698

1699

1700

1701

1702

1703

1704

1705

1706

1707

1708

1709

1710

1711

1712

1713

1714

1715

1716

1717

1718

1719

1720

1721

1722

1723

1724

1725

1726

1727

1728

1729

1730

1731

1732

1733

1734

1735

1736

1737

1738

1739

1740

1741

1742

1743

1744

1745

1746

1747

1748

1749

1750

1751

1752

1753

1754

1755

1756

1757

1758

1759

1760

1761

1762

1763

1764

1765

1766

1767

1768

1769

1770

1771

1772

1773

1774

1775

1776

1777

1778

1779

1780

1781

1782

1783

1784

1785

1786

1787

1788

1789

1790

1791

1792

1793

1794

1795

1796

1797

1798

1799

1800

1801

1802

1803

1804

1805

1806

1807

1808

1809

1810

1811

1812

1813

1814

1815

1816

1817

1818

1819

1820

1821

1822

1823

1824

1825

1826

1827

1828

1829

1830

1831

1832

1833

1834

1835

1836

1837

1838

1839

1840

1841

1842

1843

1844

1845

1846

1847

1848

1849

1850

1851

1852

1853

1854

1855

1856

1857

1858

1859

1860

1861

1862

1863

1864

1865

1866

1867

1868

1869

1870

1871

1872

1873

1874

1875

1876

1877

1878

1879

1880

1881

1882

1883

1884

1885

1886

1887

1888

1889

1890

1891

1892

1893

1894

1895

1896

1897

1898

1899

1900

1901

1902

1903

1904

1905

1906

1907

1908

1909

1910

1911

1912

1913

1914

1915

1916

1917

1918

1919

1920

1921

1922

1923

1924

1925

1926

1927

1928

1929

1930

1931

1932

1933

1934

1935

1936

1937

1938

1939

1940

1941

1942

1943

1944

1945

1946

1947

1948

1949

1950

1951

1952

1953

1954

1955

1956

1957

1958

1959

1960

1961

1962

1963

1964

1965

1966

1967

1968

1969

1970

1971

1972

1973

1974

1975

1976

1977

1978

1979

1980

1981

1982

1983

1984

1985

1986

1987

1988

1989

1990

1991

1992

1993

1994

1995

1996

1997

1998

1999

2000

2001

2002

2003

2004

2005

2006

2007

2008

2009

2010

2011

2012

2013

2014

2015

2016

2017

2018

2019

2020

2021

2022

2023

2024

2025

2026

2027

2028

2029

2030

2031

2032

2033

2034

2035

2036

2037

2038

2039

2040

2041

2042

2043

2044

2045

2046

2047

2048

2049

2050

2051

2052

2053

2054

2055

2056

2057

2058

2059

2060

2061

2062

2063

2064

2065

2066

2067

2068

2069

2070

2071

2072

2073

2074

2075

2076

2077

2078

2079

2080

2081

2082

2083

2084

2085

2086

2087

2088

2089

2090

2091

2092

2093

2094

2095

2096

2097

2098

2099

2100

2101

2102

2103

2104

2105

2106

2107

2108

2109

2110

2111

2112

2113

2114

2115

2116

2117

2118

2119

2120

2121

2122

2123

2124

2125

2126

2127

2128

2129

2130

2131

2132

2133

2134

2135

2136

2137

2138

2139

2140

2141

2142

2143

2144

2145

2146

2147

2148

2149

2150

2151

2152

2153

2154

2155

2156

2157

2158

2159

2160

2161

2162

2163

2164

2165

2166

2167

2168

2169

2170

2171

2172

2173

2174

2175

2176

2177

2178

2179

2180

2181

2182

2183

2184

2185

2186

2187

2188

2189

2190

2191

2192

2193

2194

2195

2196

2197

2198

2199

2200

2201

2202

2203

2204

2205

2206

2207

2208

2209

2210

2211

2212

2213

2214

2215

2216

2217

2218

2219

2220

2221

2222

2223

2224

2225

2226

2227

2228

2229

2230

2231

2232

2233

2234

2235

2236

2237

2238

2239

2240

2241

2242

2243

2244

2245

2246

2247

2248

2249

2250

2251

2252

2253

2254

2255

2256

2257

2258

2259

2260

2261

2262

2263

2264

2265

2266

2267

2268

2269

2270

2271

2272

2273

2274

2275

2276

2277

2278

2279

2280

2281

2282

2283

2284

2285

2286

2287

2288

2289

2290

2291

2292

2293

2294

2295

2296

2297

2298

2299

2300

2301

2302

2303

2304

2305

2306

2307

2308

2309

2310

2311

2312

2313

2314

2315

2316

2317

2318

2319

2320

2321

2322

2323

2324

2325

2326

2327

2328

2329

2330

2331

2332

2333

2334

2335

2336

2337

2338

2339

2340

2341

2342

2343

2344

2345

2346

2347

2348

2349

2350

2351

2352

2353

2354

2355

2356

2357

2358

2359

2360

2361

2362

2363

2364

2365

2366

2367

2368

2369

2370

2371

2372

2373

2374

2375

2376

2377

2378

2379

2380

2381

2382

2383

2384

2385

2386

2387

2388

2389

2390

2391

2392

2393

2394

2395

2396

2397

2398

2399

2400

2401

2402

2403

2404

2405

2406

2407

2408

2409

2410

2411

2412

2413

2414

2415

2416

2417

2418

2419

2420

2421

2422

2423

2424

2425

2426

2427

2428

2429

2430

2431

2432

2433

2434

2435

2436

2437

2438

2439

2440

2441

2442

2443

2444

2445

2446

2447

2448

2449

2450

2451

2452

2453

2454

2455

2456

2457

2458

2459

2460

2461

2462

2463

2464

2465

2466

2467

2468

2469

2470

2471

2472

2473

2474

2475

2476

2477

2478

2479

2480

2481

2482

2483

2484

2485

2486

2487

2488

2489

2490

2491

2492

2493

2494

2495

2496

2497

2498

2499

2500

2501

2502

2503

2504

2505

2506

2507

2508

2509

2510

2511

2512

2513

2514

2515

2516

2517

2518

2519

2520

2521

2522

2523

2524

2525

2526

2527

2528

2529

2530

2531

2532

2533

2534

2535

2536

2537

2538

2539

2540

2541

2542

2543

2544

2545

2546

2547

2548

2549

2550

2551

2552

2553

2554

2555

2556

2557

2558

2559

2560

2561

2562

2563

2564

2565

2566

2567

2568

2569

2570

2571

2572

2573

2574

2575

2576

2577

2578

2579

2580

2581

2582

2583

2584

2585

2586

2587

2588

2589

2590

2591

2592

2593

2594

2595

2596

2597

2598

2599

2600

2601

2602

2603

2604

2605

2606

2607

2608

2609

2610

2611

2612

2613

2614

2615

2616

2617

2618

2619

2620

2621

2622

2623

2624

2625

2626

2627

2628

2629

2630

2631

2632

2633

2634

2635

2636

2637

2638

2639

2640

2641

2642

2643

2644

2645

2646

2647

2648

2649

2650

2651

2652

2653

2654

2655

2656

2657

2658

2659

2660

2661

2662

2663

2664

2665

2666

2667

2668

2669

2670

2671

2672

2673

2674

2675

2676

2677

2678

2679

2680

2681

2682

2683

2684

2685

2686

2687

2688

2689

2690

2691

2692

2693

2694

2695

2696

2697

2698

2699

2700

2701

2702

2703

2704

2705

2706

2707

2708

2709

2710

2711

2712

2713

2714

2715

2716

2717

2718

2719

2720

2721

2722

2723

2724

2725

2726

2727

2728

2729

2730

2731

2732

2733

2734

2735

2736

2737

2738

2739

2740

2741

2742

2743

2744

2745

2746

2747

2748

2749

2750

2751

2752

2753

2754

2755

2756

2757

2758

2759

2760

2761

2762

2763

2764

2765

2766

2767

2768

2769

2770

2771

2772

2773

2774

2775

2776

2777

2778

2779

2780

2781

2782

2783

2784

2785

2786

2787

2788

2789

2790

2791

2792

2793

2794

2795

2796

2797

2798

2799

2800

2801

2802

2803

2804

2805

2806

2807

2808

2809

2810

2811

2812

2813

2814

2815

2816

2817

2818

2819

2820

2821

2822

2823

2824

2825

2826

2827

2828

2829

2830

2831

2832

2833

2834

2835

2836

2837

2838

2839

2840

2841

2842

2843

2844

2845

2846

2847

2848

2849

2850

2851

2852

2853

2854

2855

2856

2857

2858

2859

2860

2861

2862

2863

2864

2865

2866

2867

2868

2869

2870

2871

2872

2873

2874

2875

2876

2877

2878

2879

2880

2881

2882

2883

2884

2885

2886

2887

2888

2889

2890

2891

2892

2893

2894

2895

2896

2897

2898

2899

2900

2901

2902

2903

2904

2905

2906

2907

2908

2909

2910

2911

2912

2913

2914

2915

2916

2917

2918

2919

2920

2921

2922

2923

2924

2925

2926

2927

2928

2929

2930

2931

2932

2933

2934

2935

2936

2937

2938

2939

2940

2941

2942

2943

2944

2945

2946

2947

2948

2949

2950

2951

2952

2953

2954

2955

2956

2957

2958

2959

2960

2961

2962

2963

2964

2965

2966

2967

2968

2969

2970

2971

2972

2973

2974

2975

2976

2977

2978

2979

2980

2981

2982

2983

2984

2985

2986

2987

2988

2989

2990

2991

2992

2993

2994

2995

2996

2997

2998

2999

3000

3001

3002

3003

3004

3005

3006

3007

3008

3009

3010

3011

3012

3013

3014

3015

3016

3017

3018

3019

3020

3021

3022

3023

3024

3025

3026

3027

3028

3029

3030

3031

3032

3033

3034

3035

3036

3037

3038

3039

3040

3041

3042

3043

3044

3045

3046

3047

3048

3049

3050

3051

3052

3053

3054

3055

3056

3057

3058

3059

3060

3061

3062

3063

3064

3065

3066

3067

3068

3069

3070

3071

3072

3073

3074

3075

3076

3077

3078

3079

3080

3081

3082

3083

3084

3085

3086

3087

3088

3089

3090

3091

3092

3093

3094

3095

3096

3097

3098

3099

3100

3101

3102

3103

3104

3105

3106

3107

3108

3109

3110

3111

3112

3113

3114

3115

3116

3117

3118

3119

3120

3121

3122

3123

3124

3125

3126

3127

3128

3129

3130

3131

3132

3133

3134

3135

3136

3137

3138

3139

3140

3141

3142

3143

3144

3145

3146

3147

3148

3149

3150

3151

3152

3153

3154

3155

3156

3157

3158

3159

3160

3161

3162

3163

3164

3165

3166

3167

3168

3169

3170

3171

3172

3173

3174

3175

3176

3177

3178

3179

3180

3181

3182

3183

3184

3185

3186

3187

3188

3189

3190

3191

3192

3193

3194

3195

3196

3197

3198

3199

3200

3201

3202

3203

3204

3205

3206

3207

3208

3209

3210

3211

3212

3213

3214

3215

3216

3217

3218

3219

3220

3221

3222

3223

3224

3225

3226

3227

3228

3229

3230

3231

3232

3233

3234

3235

3236

3237

3238

3239

3240

3241

3242

3243

3244

3245

3246

3247

3248

3249

3250

3251

3252

3253

3254

3255

3256

3257

3258

3259

3260

3261

3262

3263

3264

3265

3266

3267

3268

3269

3270

3271

3272

3273

3274

3275

3276

3277

3278

3279

3280

3281

3282

3283

3284

3285

3286

3287

3288

3289

3290

3291

3292

3293

3294

3295

3296

3297

3298

3299

3300

3301

3302

3303

3304

3305

3306

3307

3308

3309

3310

3311

3312

3313

3314

3315

3316

3317

3318

3319

3320

3321

3322

3323

3324

3325

3326

3327

3328

3329

3330

3331

3332

3333

3334

3335

3336

3337

3338

3339

3340

3341

3342

3343

3344

3345

3346

3347

3348

3349

3350

3351

3352

3353

3354

3355

3356

3357

3358

3359

3360

3361

3362

3363

3364

3365

3366

3367

3368

3369

3370

3371

3372

3373

3374

3375

3376

3377

3378

3379

3380

3381

3382

3383

3384

3385

3386

3387

3388

3389

3390

3391

3392

3393

3394

3395

3396

3397

3398

3399

3400

3401

3402

3403

3404

3405

3406

3407

3408

3409

3410

3411

3412

3413

3414

3415

3416

3417

3418

3419

3420

3421

3422

3423

3424

3425

3426

3427

3428

3429

3430

3431

3432

3433

3434

3435

3436

3437

3438

3439

3440

3441

3442

3443

3444

3445

3446

3447

3448

3449

3450

3451

3452

3453

3454

3455

3456

3457

3458

3459

3460

3461

3462

3463

3464

3465

3466

3467

3468

3469

3470

3471

3472

3473

3474

3475

3476

3477

3478

3479

3480

3481

3482

3483

3484

3485

3486

3487

3488

3489

3490

3491

3492

3493

3494

3495

3496

3497

3498

3499

3500

3501

3502

3503

3504

3505

3506

3507

3508

3509

3510

3511

3512

3513

3514

3515

3516

3517

3518

3519

3520

3521

3522

3523

3524

3525

3526

3527

3528

3529

3530

3531

3532

3533

3534

3535

3536

3537

3538

3539

3540

3541

3542

3543

3544

3545

3546

3547

3548

3549

3550

3551

3552

3553

3554

3555

3556

3557

3558

3559

3560

3561

3562

3563

3564

3565

3566

3567

3568

3569

3570

3571

3572

3573

3574

3575

3576

3577

3578

3579

3580

3581

3582

3583

3584

3585

3586

3587

3588

3589

3590

3591

3592

3593

3594

3595

3596

3597

3598

3599

3600

3601

3602

3603

3604

3605

3606

3607

3608

3609

3610

3611

3612

3613

3614

3615

3616

3617

3618

3619

3620

3621

3622

3623

3624

3625

3626

3627

3628

3629

3630

3631

3632

3633

3634

3635

3636

3637

3638

3639

3640

3641

3642

3643

3644

3645

3646

3647

3648

3649

3650

3651

3652

3653

3654

3655

3656

3657

3658

3659

3660

3661

3662

3663

3664

3665

3666

3667

3668

3669

3670

3671

3672

3673

3674

3675

3676

3677

3678

3679

3680

3681

3682

3683

3684

3685

3686

3687

3688

3689

3690

3691

3692

3693

3694

3695

3696

3697

3698

3699

3700

3701

3702

3703

3704

3705

3706

3707

3708

3709

3710

3711

3712

3713

3714

3715

3716

3717

3718

3719

3720

3721

3722

3723

3724

3725

3726

3727

3728

3729

3730

3731

3732

3733

3734

3735

3736

3737

3738

3739

3740

3741

3742

3743

3744

3745

3746

3747

3748

3749

3750

3751

3752

3753

3754

3755

3756

3757

3758

3759

3760

3761

3762

3763

3764

3765

3766

3767

3768

3769

3770

3771

3772

3773

3774

3775

3776

3777

3778

3779

3780

3781

3782

3783

3784

3785

3786

3787

3788

3789

3790

3791

3792

3793

3794

3795

3796

3797

3798

3799

3800

3801

3802

3803

3804

3805

3806

3807

3808

3809

3810

3811

3812

3813

3814

3815

3816

3817

3818

3819

3820

3821

3822

3823

3824

3825

3826

3827

3828

3829

3830

3831

3832

3833

3834

3835

3836

3837

3838

3839

3840

3841

3842

3843

3844

3845

3846

3847

3848

3849

3850

3851

3852

3853

3854

3855

3856

3857

3858

3859

3860

3861

3862

3863

3864

3865

3866

3867

3868

3869

3870

3871

3872

3873

3874

3875

3876

3877

3878

3879

3880

3881

3882

3883

3884

3885

3886

3887

3888

3889

3890

3891

3892

3893

3894

3895

3896

3897

3898

3899

3900

3901

3902

3903

3904

3905

3906

3907

3908

3909

3910

3911

3912

3913

3914

3915

3916

3917

3918

3919

3920

3921

3922

3923

3924

3925

3926

3927

3928

3929

3930

3931

3932

3933

3934

3935

3936

3937

3938

3939

3940

3941

3942

3943

3944

3945

3946

3947

3948

3949

3950

3951

3952

3953

3954

3955

3956

3957

3958

3959

3960

3961

3962

3963

3964

3965

3966

3967

3968

3969

3970

3971

3972

3973

3974

3975

3976

3977

3978

3979

3980

3981

3982

3983

3984

3985

3986

3987

3988

3989

3990

3991

3992

3993

3994

3995

3996

3997

3998

3999

4000

4001

4002

4003

4004

4005

4006

4007

4008

4009

4010

4011

4012

4013

4014

4015

4016

4017

4018

4019

4020

4021

4022

4023

4024

4025

4026

4027

4028

4029

4030

4031

4032

4033

4034

4035

4036

4037

4038

4039

4040

4041

4042

4043

4044

4045

4046

4047

4048

4049

4050

4051

4052

4053

4054

4055

4056

4057

4058

4059

4060

4061

4062

4063

4064

4065

4066

4067

4068

4069

4070

4071

4072

4073

4074

4075

4076

4077

4078

4079

4080

4081

4082

4083

4084

4085

4086

4087

4088

4089

4090

4091

4092

4093

4094

4095

4096

4097

4098

4099

4100

4101

4102

4103

4104

4105

4106

4107

4108

4109

4110

4111

4112

4113

4114

4115

4116

4117

4118

4119

4120

4121

4122

4123

4124

4125

4126

4127

4128

4129

4130

4131

4132

4133

4134

4135

4136

4137

4138

4139

4140

4141

4142

4143

4144

4145

4146

4147

4148

4149

4150

4151

4152

4153

4154

4155

4156

4157

4158

4159

4160

4161

4162

4163

4164

4165

4166

4167

4168

4169

4170

4171

4172

4173

4174

4175

4176

4177

4178

4179

4180

4181

4182

4183

4184

4185

4186

4187

4188

4189

4190

4191

4192

4193

4194

4195

4196

4197

4198

4199

4200

4201

4202

4203

4204

4205

4206

4207

4208

4209

4210

4211

4212

4213

4214

4215

4216

4217

4218

4219

4220

4221

4222

4223

4224

4225

4226

4227

4228

4229

4230

4231

4232

4233

4234

4235

4236

4237

4238

4239

4240

4241

4242

4243

4244

4245

4246

4247

4248

4249

4250

4251

4252

4253

4254

4255

4256

4257

4258

4259

4260

4261

4262

4263

4264

4265

4266

4267

4268

4269

4270

4271

4272

4273

4274

4275

4276

4277

4278

4279

4280

4281

4282

4283

4284

4285

4286

4287

4288

4289

4290

4291

4292

4293

4294

4295

4296

4297

4298

4299

4300

4301

4302

4303

4304

4305

4306

4307

4308

4309

4310

4311

4312

4313

4314

4315

4316

4317

4318

4319

4320

4321

4322

4323

4324

4325

4326

4327

4328

4329

4330

4331

4332

4333

4334

4335

4336

4337

4338

4339

4340

4341

4342

4343

4344

4345

4346

4347

4348

4349

4350

4351

4352

4353

4354

4355

4356

4357

4358

4359

4360

4361

4362

4363

4364

4365

4366

4367

4368

4369

4370

4371

4372

4373

4374

4375

4376

4377

4378

4379

4380

4381

4382

4383

4384

4385

4386

4387

4388

4389

4390

4391

4392

4393

4394

4395

4396

4397

4398

4399

4400

4401

4402

4403

4404

4405

4406

4407

4408

4409

4410

4411

4412

4413

4414

4415

4416

4417

4418

4419

4420

4421

4422

4423

4424

4425

4426

4427

4428

4429

4430

4431

4432

4433

4434

4435

4436

4437

4438

4439

4440

4441

4442

4443

4444

4445

4446

4447

4448

4449

4450

4451

4452

4453

4454

4455

4456

4457

4458

4459

4460

4461

4462

4463

4464

4465

4466

4467

4468

4469

4470

4471

4472

4473

4474

4475

4476

4477

4478

4479

4480

4481

4482

4483

4484

4485

4486

4487

4488

4489

4490

4491

4492

4493

4494

4495

4496

4497

4498

4499

4500

4501

4502

4503

4504

4505

4506

4507

4508

4509

4510

4511

4512

4513

4514

4515

4516

4517

4518

4519

4520

4521

4522

4523

4524

4525

4526

4527

4528

4529

4530

4531

4532

4533

4534

4535

4536

4537

4538

4539

4540

4541

4542

4543

4544

4545

4546

4547

4548

4549

4550

4551

4552

4553

4554

4555

4556

4557

4558

4559

4560

4561

4562

4563

4564

4565

4566

4567

4568

4569

4570

4571

4572

4573

4574

4575

4576

4577

4578

4579

4580

4581

4582

4583

4584

4585

4586

4587

4588

4589

4590

4591

4592

4593

4594

4595

4596

4597

4598

4599

4600

4601

4602

4603

4604

4605

4606

4607

4608

4609

4610

4611

4612

4613

4614

4615

4616

4617

4618

4619

4620

4621

4622

4623

4624

4625

4626

4627

4628

4629

4630

4631

4632

4633

4634

4635

4636

4637

4638

4639

4640

4641

4642

4643

4644

4645

4646

4647

4648

4649

4650

4651

4652

4653

4654

4655

4656

4657

4658

4659

4660

4661

4662

4663

4664

4665

4666

4667

4668

4669

4670

4671

4672

4673

4674

4675

4676

4677

4678

4679

4680

4681

4682

4683

4684

4685

4686

4687

4688

4689

4690

4691

4692

4693

4694

4695

4696

4697

4698

4699

4700

4701

4702

4703

4704

4705

4706

4707

4708

4709

4710

4711

4712

4713

4714

4715

4716

4717

4718

4719

4720

4721

4722

4723

4724

4725

4726

4727

4728

4729

4730

4731

4732

4733

4734

4735

4736

4737

4738

4739

4740

4741

4742

4743

4744

4745

4746

4747

4748

4749

4750

4751

4752

4753

4754

4755

4756

4757

4758

4759

4760

4761

4762

4763

4764

4765

4766

4767

4768

4769

4770

4771

4772

4773

4774

4775

4776

4777

4778

4779

4780

4781

4782

4783

4784

4785

4786

4787

4788

4789

4790

4791

4792

4793

4794

4795

4796

4797

4798

4799

4800

4801

4802

4803

4804

4805

4806

4807

4808

4809

4810

4811

4812

4813

4814

4815

4816

4817

4818

4819

4820

4821

4822

4823

4824

4825

4826

4827

4828

4829

4830

4831

4832

4833

4834

4835

4836

4837

4838

4839

4840

4841

4842

4843

4844

4845

4846

4847

4848

4849

4850

4851

4852

4853

4854

4855

4856

4857

4858

4859

4860

4861

4862

4863

4864

4865

4866

4867

4868

4869

4870

4871

4872

4873

4874

4875

4876

4877

4878

4879

4880

4881

4882

4883

4884

4885

4886

4887

4888

4889

4890

4891

4892

4893

4894

4895

4896

4897

4898

4899

4900

4901

4902

4903

4904

4905

4906

4907

4908

4909

4910

4911

4912

4913

4914

4915

4916

4917

4918

4919

4920

4921

4922

4923

4924

4925

4926

4927

4928

4929

4930

4931

4932

4933

4934

4935

4936

4937

4938

4939

4940

4941

4942

4943

4944

4945

4946

4947

4948

4949

4950

4951

4952

4953

4954

4955

4956

4957

4958

4959

4960

4961

4962

4963

4964

4965

4966

4967

4968

4969

4970

4971

4972

4973

4974

4975

4976

4977

4978

4979

4980

4981

4982

4983

4984

4985

4986

4987

4988

4989

4990

4991

4992

4993

4994

4995

4996

4997

4998

4999

5000

5001

5002

5003

5004

5005

5006

5007

5008

5009

5010

5011

5012

5013

5014

5015

5016

5017

5018

5019

5020

5021

5022

5023

5024

5025

5026

5027

5028

5029

5030

5031

5032

5033

5034

5035

5036

5037

5038

5039

5040

5041

5042

5043

5044

5045

5046

5047

5048

5049

5050

5051

5052

5053

5054

5055

5056

5057

5058

5059

5060

5061

5062

5063

5064

5065

5066

5067

5068

5069

5070

5071

5072

5073

5074

5075

5076

5077

5078

5079

5080

5081

5082

5083

5084

5085

5086

5087

5088

5089

5090

5091

5092

5093

5094

5095

5096

5097

5098

5099

5100

5101

5102

5103

5104

5105

5106

5107

5108

5109

5110

5111

5112

5113

5114

5115

5116

5117

5118

5119

5120

5121

5122

5123

5124

5125

5126

5127

5128

5129

5130

5131

5132

5133

5134

5135

5136

5137

5138

5139

5140

5141

5142

5143

5144

5145

5146

5147

5148

5149

5150

5151

5152

5153

5154

5155

5156

5157

5158

5159

5160

5161

5162

5163

5164

5165

5166

5167

5168

5169

5170

5171

5172

5173

5174

5175

5176

5177

5178

5179

5180

5181

5182

5183

5184

5185

5186

5187

5188

5189

5190

5191

5192

5193

5194

5195

5196

5197

5198

5199

5200

5201

5202

5203

5204

5205

5206

5207

5208

5209

5210

5211

5212

5213

5214

5215

5216

5217

5218

5219

5220

5221

5222

5223

5224

5225

5226

5227

5228

5229

5230

5231

5232

5233

5234

5235

5236

5237

5238

5239

5240

5241

5242

5243

5244

5245

5246

5247

5248

5249

5250

5251

5252

5253

5254

5255

5256

5257

5258

5259

5260

5261

5262

5263

5264

5265

5266

5267

5268

5269

5270

5271

5272

5273

5274

5275

5276

5277

5278

5279

5280

5281

5282

5283

5284

5285

5286

5287

5288

5289

5290

5291

5292

5293

5294

5295

5296

5297

5298

5299

5300

5301

5302

5303

5304

5305

5306

5307

5308

5309

5310

5311

5312

5313

5314

5315

5316

5317

5318

5319

5320

5321

5322

5323

5324

5325

5326

5327

5328

5329

5330

5331

5332

5333

5334

5335

5336

5337

5338

5339

5340

5341

5342

5343

5344

5345

5346

5347

5348

5349

5350

5351

5352

5353

5354

5355

5356

5357

5358

5359

5360

5361

5362

5363

5364

5365

5366

5367

5368

5369

5370

5371

5372

5373

5374

5375

5376

5377

5378

5379

5380

5381

5382

5383

5384

5385

5386

5387

5388

5389

5390

5391

5392

5393

5394

5395

5396

5397

5398

5399

5400

5401

5402

5403

5404

5405

5406

5407

5408

5409

5410

5411

5412

5413

5414

5415

5416

5417

5418

5419

5420

5421

5422

5423

5424

5425

5426

5427

5428

5429

5430

5431

5432

5433

5434

5435

5436

5437

5438

5439

5440

5441

5442

5443

5444

5445

5446

5447

5448

5449

5450

5451

5452

5453

5454

5455

5456

5457

5458

5459

5460

5461

5462

5463

5464

5465

5466

5467

5468

5469

5470

5471

5472

5473

5474

5475

5476

5477

5478

5479

5480

5481

5482

5483

5484

5485

5486

5487

5488

5489

5490

5491

5492

5493

5494

5495

5496

5497

5498

5499

5500

5501

5502

5503

5504

5505

5506

5507

5508

5509

5510

5511

5512

5513

5514

5515

5516

5517

5518

5519

5520

5521

5522

5523

5524

5525

5526

5527

5528

5529

5530

5531

5532

5533

5534

5535

5536

5537

5538

5539

5540

5541

5542

5543

5544

5545

5546

5547

5548

5549

5550

5551

5552

5553

5554

5555

5556

5557

5558

5559

5560

5561

5562

5563

5564

5565

5566

5567

5568

5569

5570

5571

5572

5573

5574

5575

5576

5577

5578

5579

5580

5581

5582

5583

5584

5585

5586

5587

5588

5589

5590

5591

5592

5593

5594

5595

5596

5597

5598

5599

5600

5601

5602

5603

5604

5605

5606

5607

5608

5609

5610

5611

5612

5613

5614

5615

5616

5617

5618

5619

5620

5621

5622

5623

5624

5625

5626

5627

5628

5629

5630

5631

5632

5633

5634

5635

5636

5637

5638

5639

5640

5641

5642

5643

5644

5645

5646

5647

5648

5649

5650

5651

5652

5653

5654

5655

5656

5657

5658

5659

5660

5661

5662

5663

5664

5665

5666

5667

5668

5669

5670

5671

5672

5673

5674

5675

5676

5677

5678

5679

5680

5681

5682

5683

5684

5685

5686

5687

5688

5689

5690

5691

5692

5693

5694

5695

5696

5697

5698

5699

5700

5701

5702

5703

5704

5705

5706

5707

5708

5709

5710

5711

5712

5713

5714

5715

5716

5717

5718

5719

5720

5721

5722

5723

5724

5725

5726

5727

5728

5729

5730

5731

5732

5733

5734

5735

5736

5737

5738

5739

5740

5741

5742

5743

5744

5745

5746

5747

5748

5749

5750

5751

5752

5753

5754

5755

5756

5757

5758

5759

5760

5761

5762

5763

5764

5765

5766

5767

5768

5769

5770

5771

5772

5773

5774

5775

5776

5777

5778

5779

5780

5781

5782

5783

5784

5785

5786

5787

5788

5789

5790

5791

5792

5793

5794

5795

5796

5797

5798

5799

5800

5801

5802

5803

5804

5805

5806

5807

5808

5809

5810

5811

5812

5813

5814

5815

5816

5817

5818

5819

5820

5821

5822

5823

5824

5825

5826

5827

5828

5829

5830

5831

5832

5833

5834

5835

5836

5837

5838

5839

5840

5841

5842

5843

5844

5845

5846

5847

5848

5849

5850

5851

5852

5853

5854

5855

5856

5857

5858

5859

5860

5861

5862

5863

5864

5865

5866

5867

5868

5869

5870

5871

5872

5873

5874

5875

5876

5877

5878

5879

5880

5881

5882

5883

5884

5885

5886

5887

5888

5889

5890

5891

5892

5893

5894

5895

5896

5897

5898

5899

5900

5901

5902

5903

5904

5905

5906

5907

5908

5909

5910

5911

5912

5913

5914

5915

5916

5917

5918

5919

5920

5921

5922

5923

5924

5925

5926

5927

5928

5929

5930

5931

5932

5933

5934

5935

5936

5937

5938

5939

5940

5941

5942

5943

5944

5945

5946

5947

5948

5949

5950

5951

5952

5953

5954

5955

5956

5957

5958

5959

5960

5961

5962

5963

5964

5965

5966

5967

5968

5969

5970

5971

5972

5973

5974

5975

5976

5977

5978

5979

5980

5981

5982

5983

5984

5985

5986

5987

5988

5989

5990

5991

5992

5993

5994

5995

5996

5997

5998

5999

6000

6001

6002

6003

6004

6005

6006

6007

6008

6009

6010

6011

6012

6013

6014

6015

6016

6017

6018

6019

6020

6021

6022

6023

6024

6025

6026

6027

6028

6029

6030

6031

6032

6033

6034

6035

6036

6037

6038

6039

6040

6041

6042

6043

6044

6045

6046

6047

6048

6049

6050

6051

6052

6053

6054

6055

6056

6057

6058

6059

6060

6061

6062

6063

6064

6065

6066

6067

6068

6069

6070

6071

6072

6073

6074

6075

6076

6077

6078

6079

6080

6081

6082

6083

6084

6085

6086

6087

6088

6089

6090

6091

6092

6093

6094

6095

6096

6097

6098

6099

6100

6101


6

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

425/492



PLAN



ELEVATION

General Notes

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES OF THE STATE OF OHIO DEPARTMENT OF HIGHWAYS, DATE: 9-1-57, TOGETHER WITH CURRENT REVISIONS THEREOF.

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE DECK SLAB, THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS, BETWEEN TRANSVERSE CONSTRUCTION JOINTS WHICH ARE NORMAL TO THE CENTERLINE OF AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

EXCAVATION QUANTITY: INCLUDES THE REMOVAL OF MATERIAL BETWEEN THE PROPOSED GRADE AND THE BOTTOM OF ABUTMENT.

ALL PILES TO BE 12" MINIMUM TOP DIAMETER CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN TO A MINIMUM BEARING CAPACITY OF 40 TONS.

REFERENCE SHALL BE MADE TO THE FOLLOWING STANDARD DRAWINGS:
AR-1-57 - REVISED 2-2-59.
CSB-2-56 SHEETS 2 & 3 - REVISED 2-2-59 AND SUPPLEMENTAL SPECIFICATIONS S-101, DATED 12-2-59.

ELECTRICAL GROUNDS: A SOLID Nº 0 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON EACH SIDE OF THE STRUCTURE AT THE PIER. THE LOWER ENDS OF THE WIRES SHALL BE BRAZED TO THE STEEL SHELL OF ONE OF THE CAST-IN-PLACE CONCRETE PILES AND THE UPPER ENDS SHALL EXTEND SUFFICIENTLY ABOVE THE TOP OF THE CONCRETE TO PROVIDE FOR A SUITABLE SPLICE AND EXTENSION FOR CONNECTION TO THE SUPERSTRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE A Nº 6 GAGE BARE STRANDED TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE AND TO THE SOLID COPPER WIRE IN THE PIER SHAFT. THERE SHALL BE A TINNED Nº 6 GAGE BARE COPPER WIRE BRASED TO THE ANCHOR BOLTS OF EACH LIGHT STANDARD AND THE OTHER ENDS BRAZED OR BOLTED TO A OUTSIDE BEAM FLANGE. PAYMENT FOR ELECTRICAL GROUNDS SHALL BE INCLUDED IN THE LUMP SUM BID FOR ITEM S-25 "ELECTRICAL LIGHTING SYSTEMS."

ITEM S-25: ELECTRICAL LIGHTING SYSTEM INCLUDES 8 ANCHORBOLTS 1½" DIA. x 4'-1" LG.

MACHINE FINISH: The concrete bridge deck shall be finished as specified in the Proposal Note, "Machine Finishing of Bridge Deck Slabs.

ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER.	ABUT.	PIERS	GEN.
E-2	LUMP	SUM	COFFERDAMS, CRIBS AND SHEETING				LUMP
E-2	780	SQ.FT.	STL. SHEET PILING, LEFT IN PLACE (35#/SQ.FT) INCLUDING ANCHORS		780		
E-2	1464	CU.YDS.	UNCLASSIFIED EXCAVATION		1380	84	
S-1	235	CU.YDS.	CLASS "C" CONCRETE SUPERSTRUCTURE	235			
S-1	320	CU.YDS.	CLASS "E" CONCRETE ABUTMENTS ABOVE FOOTINGS		320		
S-1	29	CU.YDS.	CLASS "C" CONCRETE PIERS ABOVE FOOTINGS			29	
S-1	299	CU.YDS.	CLASS "E" CONCRETE PIER AND ABUT. FOOTINGS		265	34	
S-3	60	SQ.YDS	TYPE "B" WATERPROOFING		60		
S-3	17	LIN.FT.	WATERPROOFING 12" x ½" PREFORMED SEALING STRIP		17		
S-4	102,882	LBS	REINFORCING STEEL	48,453	41,414	13,015	
S-7	264,200	LBS.	STRUCTURAL STEEL				

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER	ABUT.	PIERS	GEN.
S-8	264,200	LBS	FIELD PAINTING OF STRUCTURAL STEEL AS PER PLAN	264,200			
S-9	125	SQ.FT.	1" PREFORMED EXPANSION JOINT FILLER		125		
S-14	343	LIN.FT.	RAILING, ALUM. RAIL & SUPPORTS, CONCRETE PARAPETS	323	20		
S-16	LUMP	SUM	FIRST TEST PILE				LUMP
S-18	2220	LIN.FT.	12" CAST-IN-PLACE REINFORCED CONCRETE PILES		1860	360	
S-25	LUMP	SUM	ELECTRICAL LIGHTING SYSTEM ◉				LUMP
S-29	260	CU.YDS.	POROUS BACKFILL		260		
S-29	60	LIN.FT.	6" STD. PIPE DOWNSPOUT, GALVANIZED STEEL OR WROUGHT IRON INCLUDING SPECIALS.	60			
S-29	LUMP	SUM	SCUPPERS INCLUDING SPECIALS				LUMP
S-29	48	LIN.FT.	8" ϕ PERFORATED BITUMINOUS COATED C.M.P. WITH SPECIALS		48		

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GENERAL PLAN & ELEVATION

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH	JNP					7-28-60

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH - 18 - 17.20


426/492

ELEVATIONS MARKED THUS * GIVEN TO HEEL OF ANGLE


CONCRETE ABOVE THIS POINT TO BE INCLUDED WITH ITEM 511.4 FOR PAYMENT.



ELEVATION




VIEW "E"
(SOUTH WING WALL SIMILAR)



SECTION "DD"



DETAIL OF RUSTICATION GROOVE



SECTION "F-F" AS SHOWN
SECTION "F1-F1" OPP. HAND

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.00


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	CW					


MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

427
492








SECTION C-C
(DETAILS NOT SHOWN SAME AS SECTION B-B)

6'-0 LENGTH OF 8" ϕ PERFORATED BITUMINOUS COATED C.M.P., PROVIDE CAP WITH 3½" HOLE ITEM-S-29



NOTES:-

1. ALL REINFORCING STEEL SHALL HAVE A 2" MIN COVER UNLESS OTHERWISE NOTED.
2. POROUS BACKFILL, 2 FT. THICK, FULL LENGTH OF ABUTMENT AND WINGS SHALL EXTEND UP TO UNDERSIDE OF THE APPROACH SLAB OR TO FINISHED GROUND SURFACE.
3. ALL PILES TO BE 12"ϕ (MIN. TOP DIA) CAST IN PLACE REINFORCED CONCRETE PILES.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	aw					

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MA H - 18 - 17.20

428
492



NOTES:-

ALL REINFORCING STEEL TO HAVE A MIN. 2" COVER EXCEPT AS OTHERWISE SHOWN

DIMENSIONS MARKED THUS ⊕ GIVEN TO OUTSIDE FACE OF WALL

SEE SHEET Nº426 FOR SECTION F-F, F1-F1 AND DETAIL OF RUSTICATION GROOVES.

SEE SHEET Nº427 FOR DETAIL OF SHEET PILING.

ALL PILES TO BE 12" MIN. TOP DIA. CAST IN PLACE CONCRETE PILES

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 WINGWALLS

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

429
492

SECTION G-G

SECTION HH

SECTION J-J

SECTION K-K
(NOTES AND DIMENSIONS NOT SHOWN SAME AS SECTION J-J)

SECTION M-M
(NOTES AND DIMENSIONS NOT SHOWN SAME AS SECTION H-H)

SECTION N-N
(NOTES AND DIMENSIONS NOT SHOWN SAME AS SECTION G-G)

SECTION P-P

DETAIL OF LIGHT STANDARD SUPPORT
FOR LOCATION SEE SHT. #425

SECTION 1-1

NOTE:
8 ANCHORBOLTS 1½" DIA. × 4'-1" LG. INCLUDED FOR PAYMENT IN ITEM S-25

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 WINGWALL SECTIONS

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED


RECEIVED
SEP 29 1955

FED. RD.	STATE	PROJECT	
	OHIO		


MAH - 18 - 17.20

430
492

ELEVATIONS MARKED THUS * GIVEN TO HEEL OF ANGLE.




ELEVATION




SOUTH

VIEW EE


(NORTH WING WALL SIMILAR)



SECTION D-D



DETAIL OF RUSTICATION GROOVES



SECTION F-F AS SHOWN

SECTION F_1-F_1 OPP. HAND

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT # 2

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021 + 51.99


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.H.	ew					

FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18-17.20


431/492

MICROFILMED SEP 19 1985



GROOVE APPROX. 3" WIDE AND 1" MIN DEPTH, FULL LENGTH OF ABUTMENT SEAT FOR DRAINAGE. SLOPE 1/8"/FT TOWARD 4"℄ PIPE OUTLETS






SECTION C-C

(DETAILS NOT SHOWN SAME AS SEC BB).

6'-0 LENGTH OF 8" ℄ PERFORATED BITUMINOUS COATED C.M.P. PROVIDE CAP WITH 3½ ℄ HOLE - ITEM 5-29

END OF BARS A-551 FOOTING ONLY

FOR DETAIL OF WINGWALL SEE SHEET Nº



FOR GENERAL NOTES & DETAILS NOT SHOWN SEE STD. DRAWING CSB-2-56 SHEET Nº 2

- DETAIL A -

NOTES:-

1. ALL REINFORCING STEEL SHALL HAVE A 2" MIN. COVER UNLESS OTHERWISE NOTED.
2. POROUS BACKFILL 2FT. THICK FULL LENGTH OF ABUTMENT AND WINGS SHALL EXTEND UP TO APPROACH SLAB OR TO FINISHED GROUND SURFACE.
3. ALL PILES TO BE 12"℄ MIN. TOP DIA. CAST-IN-PLACE REINFORCED CONCRETE PILES.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT Nº 2

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.H.	C.W.					-

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MA H - 18-17.20


432
492




FOOTING PLAN




ELEVATION SOUTH WINGWALL
ABUTMENT Nº 2



SECTION "GG"



SECTION "HH"



SECTION "J-J"

NOTES:-

DIMENSIONS MARKED THUS ⊕ ARE CURVED DIMENSIONS MEASURED ON 50' RADIUS ON OUTSIDE FACE OF WALL.

SEE SHEET Nº430 FOR SECTION "FF" AND DETAIL OF RUSTICATION GROOVES.

ALL PILES SHALL BE 12" DIAMETER CAST-IN-PLACE REINFORCED CONCRETE PILES.

ALL REINFORCING STEEL TO HAVE A MIN. OF 2" COVER EXCEPT AS OTHERWISE SHOWN.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #2 WINGWALL

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED

MICROFILMED
SEP 19 1965

FED. RD.	STATE	PROJECT	
	OHIO		


MAH - 18-17.20

433
492




PLAN


NORTH



ELEVATION



SECTION A-A



SECTION B-B

SECTION C-C

— NOTE —

ALL REINFORCING STEEL TO HAVE A 2" MINIMUM COVER, EXCEPT WHERE OTHERWISE NOTED. CARE MUST BE TAKEN IN PLACING REINFORCING STEEL IN THE PIER CAP SO IT WILL NOT INTERFERE WITH THE BEARING PLATE ANCHOR BOLTS.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER

BRIDGE No. MAH-18-1034
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH	UNP					


MICROFILMED SEP 19 1955

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

434
492


* - THESE ARE NOMINAL DIMENSIONS. THE QUANTITY OF DECK CONCRETE TO BE PAID FOR SHALL BE BASED ON THESE DIMENSIONS, EVEN THOUGH DEVIATION FROM THEM MAY BE NECESSARY BECAUSE THE TOP FLANGE OF THE BEAM MAY NOT HAVE THE EXACT CAMBER OR CONFORMATION REQUIRED TO PLACE IT PARALLEL TO THE FINISHED GRADE.




TRANSVERSE SECTION

2 1/2 x 2 1/2 x 5/16 L's - 2 AT EACH SCUPPER 4'-0" ± 9" BETWEEN SCUPPERS

- GUTTER SUPPORT DETAIL -




SECTION B-B
TYPE "B" SCUPPER ONLY




SLAB REINFORCING PLAN

SEE TRANSVERSE SECTION FOR SPACINGS NOT SHOWN




FRAMING PLAN




SECTION B-B


SECTION X-X



- SECTION C-C -



SECTION A-A



BEAM	R" *
B-1	7/8"
B-2	1"
B-3	1"
B-4	1"
B-5	1 1/8"
B-6	1 1/4"

DEFLECTION & CAMBER

LOCATION	B-1 LEFT FASCIA BEAM		B-2 TO B-5 INSIDE BEAMS		B-6 RIGHT FASCIA BEAM	
	SPAN 1	SPAN 2	SPAN 1	SPAN 2	SPAN 1	SPAN 2
DEFLECTION DUE TO WEIGHT OF STEEL	.15"	.20"	.15"	.20"	.20"	.25"
DEFLECTION DUE TO REMAINING DEAD LOAD	.50"	.60"	.50"	.60"	.60"	.75"
CONVEXITY REQUIRED FOR VERTICAL CURVE	1.85"	1.90"	1.90"	2.20"	1.95"	2.50"
SUM OF DEFLECTION & CONVEXITY	2.5"	2.70"	2.55"	3.00"	2.75"	3.50"
REQUIRED CAMBER	2 1/2"	2 3/4"	2 5/8"	3"	2 3/4"	3 1/2"

NOTES

SLAB THICKNESS SHOWN INCLUDES 1" MONOLITHIC WEARING SURFACE.

* WELDING PROCEDURE: LIFT END OF BEAM R" (SEE TABLE THIS SHEET) AT ABUTMENT #1. BUTT-WELD THE BEAM FLANGES AND WEB AT PIERS, USING THE FOLLOWING SEQUENCE: MAKE 2 PASSES ON EACH FLANGE, THEN TWO ON THE WEB; REPEAT, USING ONE PASS AT EACH LOCATION UNTIL WELDS ARE COMPLETED, WELD THE BOTTOM & TOP MOMENT PLATES, LOWER THE BEAM ENDS TO FINAL POSITION.

WELDING OF STRUCTURAL STEEL SHALL BE CLASS "A" EXCEPT AS OTHERWISE SHOWN; ANY WELDS SHOWN AS FIELD WELDS MAY, AT THE OPTION OF THE CONTRACTOR, BE MADE IN THE SHOP.

REFERENCE SHALL BE MADE TO STD. DWG. CSB-2-56 SHT. #3 DATED 12-3-56, REVISED 2-2-59 FOR BEARING DETAILS.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING PLAN

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH	JNP					

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

435
492

MICROFILMED
SEP 19 1984

2" @ 70° F.

1'-0" 1'-0" 6'-8 7/8" 11'-10 3/8"

℄ BEARINGS ABUTMENT #1

155'-8 3/4"

17-SPACES @ 8'-3" = 140'-3" ℄ TO ℄ RAILING POSTS.

8-SPACES @ 16'-6" = 132'-0" ℄ TO ℄ 1/4" EXPANSION JOINTS

℄ PIER

16'-6"

6'-8 7/8" 11'-10 3/8" 1'-0" 1'-0"

℄ BEARINGS ABUTMENT #2

2" @ 70° F.

FACE OF ABUTMENT

FACE OF CURB

SCUPPERS 8'-0"

2 1/2" TYP.

5"x3 1/2"x13.0# BULB ANGLE

SCUPPERS 8'-0"

12" TYP.

FACE OF ABUTMENT

℄ RIDGE AVE.

8'-0" SCUPPERS

FACE OF CURB

5"x3 1/2"x13.0# BULB ANGLE

8'-0" SCUPPERS

TYPE "A" TYPICAL

TYPE "B" TYPICAL

17'-6"

13'-5 1/4" 8'-0 3/4" 1'-0" 1'-0"

8-SPACES @ 17'-6" = 140'-0" ℄ TO ℄ 1/4" EXP. JT.

17-SPACES @ 8'-3" = 148'-9" ℄ TO ℄ RAILING POSTS.

166'-10 1/2"

13'-5 1/4" 8'-0 3/4" 1'-0" 1'-0"

2" @ 70° F.

2" @ 70° F.

PART DECK PLAN

{2-R-502-NEAR PARAPET
2-R-503-FAR PARAPET}

{2-R-504-NEAR PARAPET
2-R-505-FAR PARAPET}

{2-R-502-NEAR PARAPET
2-R-503-FAR PARAPET.}

7-SP'S @ 1'-10" = 12'-10" - 8-S-505 3/4"
6-SP'S @ 1'-10" = 11'-0" - 7-S-505 5/8"

9-SP'S @ 1'-10" = 16'-6" - 10-S-505 -TYPICAL
8-SP'S @ 2'-0" = 16'-0" - 9-S-505-TYPICAL

7-SP'S @ 1'-10" = 12'-10" - 8-S-505
6-SP'S @ 1'-10" = 11'-0" - 7-S-505

NEAR PARAPET.
FAR PARAPET.

TYPE "C" RAILING 4" O.D. TOP RAIL, 3 1/2" O.D. BOTTOM RAIL 3/16 WALL ALUMINUM TUBE. RAILING SHALL BE CONTINUOUS THRU FIRST POST AT EACH END OF SUPERSTRUCTURE.

1" ℄ GREY SPONGE RUBBER, PREFORMED EXPANSION JOINT FILLER, MEETING THE REQUIREMENTS OF SECTION M-10.02-TYPE NO.-1. TO BE PAID FOR AS PART OF ITEM S-14.

8'-0"

TYPE "A" SCUPPER-TYP.

10°

SCUPPER TYPE "B"-TYP.

1/4" PLATE

TOP OF PIER CAP

8'-0"

SCUPPER

2"DIA. STD. STL. PIPE DRAIN AT THE ABUTMENT END OF EACH BULB ANGLE, AS INDICATED ON PLAN. WELD STUB END FULL PERIMETER TO BULB ANGLE.

TOP OF BEAM SEATS

SEE NOTE-A

NOTE-A: INCLUDE PIPE AND SPECIALS BELOW THIS LINE AS ITEM S-29-6" DOWNSPOUTS INCLUDING SPECIALS. FOR PAYMENT.

3/4" ℄ EXPANSION BOLTS

6"

6" ℄ OFFSET PIPE CLAMP @ MAX. 6'-0" C/C.

LIMIT OF PAY ITEM S-29 FOR CONTINUATION OF DRAINS SEE SHEET NO. 492

SHOULDER

DOWNSPOUTS SHALL BE 6" GALVANIZED OR WROUGHT IRON PIPE

10"x6" ECCENTRIC REDUCER

℄ COLUMN

SECTION X-X

SOUTH ELEVATION SHOWN
NORTH ELEVATION SIMILAR

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RAILING & DRAINAGE DETAILS

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					

FED. RD.	STATE	PROJECT	
	OHIO		

MAH - 18 - 17.20

436
492

MICROFILMED
SEP 19 1955




TABLE FOR PILE LOCATION

PILE Nº	"X"	"Y"	BATTER	PILE Nº	"X"	"Y"	BATTER
1	40'-9½	-19'-6	YES	24	14'-2¼"	- 1'-11¾	YES
2	38'-0½	-21'-6¼	NO	25	20'-0	- 0'-10½"	YES
3	37'-11¾	-16'-0½	YES	26	18'-10½	- 3'-7¾	YES
4	32'-11¼	-16'-7¼	NO	27	19'-4	- 9'-1¾	NO
5	33'-7	-10'-3½	YES	28	25'-4½	- 3'-5¼	YES
6	26'-4	-11'-10	NO	29	23'-11	- 6'-0¾"	YES
7	28'-1¾	-6'-2¾	YES	30	28'-10½"	- 6'-8½	YES
8	22'-1	-11'-9¼	YES	31	32'-7	- 9'-5½	YES
9	20'-9¾	- 4'-6	YES	32	29'-0	- 13'-10¼	NO
10	16'-10½	- 8'-0¾	NO	33	2'-1¾	- 4'-0½	YES
11	15'-4	+ 1'-10	YES	34	1'-11¾	+ 0'-0½"	YES
12	14'-2¼	- 1'-11¾	YES	35	4'-4¼	+ 6'-1½"	NO
13	9'-7	+ 3'-2½	YES	36	8'-6½	- 3'-4¾	YES
14	8'-10½	- 0'-8½"	YES	37	7'-10¾	+ 0'-6½"	YES
15	7'-9¼	- 6'-10	NO	38	15'-6½	- 0'-8¾"	YES
16	4'-0	+ 3'-11¼	YES	39	14'-7¾	+ 2'-1½"	YES
17	3'-8½	- 0'-0¾"	YES	40	13'-2¾	+ 6'-9"	NO
18	4'-0	+ 3'-11¼	YES	41	21'-6¼	+ 2'-7"	YES
19	3'-8½	- 0'-0¾"	YES	42	21'-0¼	+ 8'-7½	NO
20	9'-7	+ 3'-2½"	YES	43	28'-1	+ 6'-2	YES
21	8'-10½	- 0'-8½"	YES	44	28'-8¾	+ 13'-7½	NO
22	7'-9¼	- 6'-10	NO	45	34'-0½	+ 10'-8¼	YES
23	15'-4	+ 1'-10¼	YES				

NOTE:-
PILES MARKED THUS ◁ DENOTES DIRECTION OF BATTER.

CUT OFF ELEV. FOR 12"ϕ PILES WEST ABUT. = 920.50
CUT OFF ELEV. FOR 12"ϕ PILES PIER = 921.50
CUT OFF ELEV. FOR 12"ϕ PILES EAST ABUT. = 920.00.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


PILE PLAN

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021+51.99


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	CW.					

REINFORCING STEEL SCHEDULE

R-506



R-507




MARK	NO.	LENGTH	WEIGHT	SH'P OR RAD.
ABUTMENT #1				
A-501	20	23'-6"	490	ST.
A-502	32	41'-1"	1371	ST.
A-503	21	20'-4"	445	ST.
A-504	21	9'-9"	214	BT.
A-505	2	4'-2"	9	BT.
A-506	2	4'-0"	8	BT.
A-507	4	6'-0"	25	ST.
A-508	36	5'-3"	197	BT.
A-509	6	6'-7"	41	BT.
A-510	3	7'-4"	23	BT.
A-511	8	4'-7"	38	ST.
A-512	3	7'-9"	24	BT.
A-513	32	10'-0"	334	BT.
A-514	39	12'-6"	508	ST.
A-602	37	15'-0"	834	ST.
A-603	27	13'-10"	561	BT.
A-604	10	15'-8"	235	BT.
A-605	2	7'-7"	23	BT.
A-606	2	7'-4"	22	BT.
A-901	68	17'-0"	3,930	BT.
A-902	33	9'-0"	1,163	ST.
A-1101	37	6'-7"	1294	BT.
A-1102	39	14'-7"	3022	BT.
TOTAL ABUTMENT #1			14,811	
WINGWALLS AT ABUTMENT #1				
W-501	1	36'-3"	38	50-7"
W-502	1	34'-11	36	48-9"
W-503	1	33'-6"	35	46-9"
W-504	1	32'-5"	34	45-4"
W-505	1	18'-2"	19	45-0"
W-506	1	18'-11"	20	47-0"
W-507	1	19'-8"	21	49-0"
W-508	1	20'-4"	21	51-0"
W-509	1	12'-0"	12	58-6"
W-510	1	11'-1"	12	53-6"
W-511	1	9'-5"	10	48-10"
W-512	1	29'-0"	30	51-5"
W-513	4	15'-0	62	49-6"
W-514	1	15'-8"	16	44-6"
W-515	1	16'-5"	17	46-6"
W-516	1	17'-1"	18	48-6"
W-517	1	17'-10"	19	50-6"
W-518	2	19'-3"	40	54-6"
W-519	2	24'-4"	51	44-1"
W-520	2	25'-2"	52	45-6"
W-521	2	26'-0"	54	47-0"
W-522	2	26'-11"	57	48-9"
W-523	2	28'-0"	58	50-7"
W-524	1	28'-8"	30	51-9"
W-525	1	23'-2"	24	41-1"
W-526	11	10'-0"	115	48-8"
W-527	1	13'-0"	14	53-6"
W-528	2	21'-3"	44	46-7"
W-529	2	21'-10"	46	48-0"
W-530	2	22'-5"	47	48-6"
W-531	1	13'-0"	14	51-6"
W-534	1	15'-2"	16	52-6"
W-535	2	13'-3"	28	45-0"
W-536	8	7'-1"	59	BT.
W-537	3	5'-1"	16	BT.
W-538	2	34'-7"	72	69-10"
W-539	2	38'-7"	80	49-10"
W-540	8	SERIES OF 1-SET VARIES OF 7'-0"-36'-4 3/8" @ INC. 4'-2 3/8"	181	49-10"
W-541	9	10'-0"	94	47-10"
W-542	2	14'-10"	31	48-3"
W-543	8	12'-6"	104	48-10"
W-544	2	7'-5"	15	48-10"
W-545	18	16'-9"	314	48-2"
W-546	1	14'-6"	15	48-9"
W-547	1	10'-7"	11	48-5"
W-548	1	7'-3"	8	48-9"
W-549	7	27'-8"	202	49-10"
W-550	5	SERIES OF 1-SET VARIES OF 6'-8"-25'-4" @ INC. 4'-8"	83	49-10"
W-551	1	6'-11"	7	48-9"
W-552	3	18'-0"	38	48-9"
W-553	1	15'-8"	16	48-9"
W-554	1	5'-0"	5	48-9"
W-555	2	5'-6"	11	49-10"
W-556	1	12'-9"	13	49-10"
W-557	1	21'-11"	23	49-10"
W-558	2	23'-11"	50	49-10"
W-559	2	19'-5"	41	49-10"
W-560	6	11'-9"	74	47-10"
W-561	2	8'-0"	19	48-1"
W-562	1	11'-0"	11	48-9"
W-563	2	4'-5"	9	ST.
W-564	2	5'-4"	11	ST.
W-565	2	6'-4"	13	ST.
SERIES OF	1-SET OF	VARIES 9'-3"-12'-9" @ INC. 7"	80	ST.
W-566	7			
SERIES OF	1-SET OF	VARIES 12'-10 1/2"-16'-6" @ INC. 7 1/4"	107	ST.
W-567	7			
SERIES OF	1-SET OF	VARIES 16'-6"-22'-6" @ INC. 8"	403	ST.
W-568	10			
W-569	8	23'-6"	196	ST.
SERIES OF	1-SET OF	VARIES 17'-2 3/4"-22'-8" @ INC. 7 1/4"	208	ST.
W-570	10			
SERIES OF	1-SET OF	VARIES 13'-7"-17'-2 1/4" @ INC. 2 1/4"	129	ST.
W-571	8			
SERIES OF	1-SET OF	VARIES 10'-1 1/4"-13'-8" @ INC. 4 3/4"	124	ST.
W-572	10			
SERIES OF	1-SET OF	VARIES 8'-8 1/2"-10'-2" @ INC. 3 1/4"	59	ST.
W-573	6			
W-574	2	5'-8"	12	ST.
W-575	2	5'-2"	11	ST.
W-576	2	4'-8"	10	ST.
W-601	23	7'-3"	250	BT.
W-602	24	11'-8"	421	BT.
W-603	15	8'-5"	190	BT.
W-604	17	7'-2"	183	BT.
SERIES OF	1-SET OF	VARIES 7'-8"-11'-3" @ INC. 7"	100	ST.
W-605	7			
SERIES OF	1-SET OF	VARIES 7'-5"-10'-11" @ INC. 7"	96	ST.
W-606	7			
SERIES OF	1-SET OF	VARIES 8'-1"-14'-1" @ INC. 8"	166	ST.
W-607	10			
W-608	8	15'-0"	180	ST.
SERIES OF	1-SET OF	VARIES 8'-0"-14'-3" @ INC. 7"	175	ST.
W-609	10			
SERIES OF	1-SET OF	VARIES 8'-5"-11'-0" @ INC. 6"	120	ST.
W-610	8			
SERIES OF	1-SET OF	VARIES 8'-8"-12'-2 1/2" @ INC. 4 1/4"	157	ST.
W-611	10			
SERIES OF	1-SET OF	VARIES 7'-2"-8'-7 1/2" @ INC. 3 1/2"	50	ST.
W-612	6			
W-613	18	9'-6"	254	BT.
W-702	20	7'-6"	307	BT.
W-704	54	9'-6"	1049	BT.
W-705	52	14'-4"	1525	BT.
W-801	15	11'-11"	477	BT.
W-1001	26	9'-7"	1072	BT.
W-1002	28	15'-7"	1878	BT.
TOTAL WINGWALLS ABUT#1			12,928	
ABUTMENT #2				
A-551	20	24'-6"	511	ST.
A-552	50	23'-6"	1226	ST.
A-553	30	17'-0"	532	ST.
A-554	28	10'-4"	302	BT.
A-555	2	4'-1"	9	
A-556	2	3'-10"	8	
A-557	4	6'-6"	27	ST.
A-559	6	6'-7"	41	BT.
A-560	3	8'-6"	27	BT.
A-561	8	4'-7"	38	ST.
A-562	3	8'-7"	27	BT.
A-563	12	10'-0"	125	BT.
A-564	36	5'-3"	197	BT.
A-652	30	8'-6"	383	ST.
A-653	20	13'-8"	411	BT.
A-654	8	14'-0"	168	BT.
A-655	2	7'-6"	23	
A-656	2	7'-1"	21	
A-751	29	7'-4"	434	BT.
A-752	55	11'-7"	1302	BT.
A-1051	28	8'-7"	1034	BT.
A-1052	30	14'-7"	1882	BT.
TOTAL ABUTMENT #2			8,728	
WINGWALL AT ABUTMENT #2				
WW-501	2	8'-2"	17	42-8"
WW-502	2	17'-4"	36	44-2"
WW-503	1	34'-7"	36	46-7"
WW-504	1	35'-11"	37	48-5"
WW-505	1	37'-4"	38	50-8"
WW-506	1	21'-3"	22	51-11"
WW-507	1	10'-7"	11	54-6"
WW-508	1	12'-0"	13	53-6"
WW-509	2	19'-5"	40	45-0"
WW-510	1	22'-10"	24	52-7"
WW-511	2	18'-3"	38	46-7"
WW-512	2	10'-0"	40	48-5"
WW-513	2	19'-9"	41	50-3"
SERIES OF	1-SET OF	VARIES 8'-9"-11'-5" @ INC. 6"	108	ST.
WW-608	7			
SERIES OF	1-SET OF	VARIES 8'-7"-12'-7" @ INC. 4"	207	ST.
WW-609	13			
WW-701	15	9'-1"	279	BT.
WW-702	14	14'-2"	405	BT.
WW-703	12	7'-6"	184	BT.
WW-801	7	11'-11"	223	BT.
WW-901	8	9'-2"	249	BT.
WW-1001	7	9'-7"	289	BT.
WW-1002	8	15'-7"	536	BT.
TOTAL WINGWALL ABUT#2			4947	
PIER				
P-501	56	8'-4"	487	BT.
P-502	56	7'-6"	438	BT.
P-601	2	37'-6"	113	ST.
P-801	14	10'-8"	399	BT.
WW-514	3	35'-11"	112	49-10"
WW-515	2	39'-5"	82	49-10"
WW-516	1	35'-0"	37	48-10"
WW-517	1	25'-1"	26	48-10"
WW-518	1	18'-8"	19	49-10"
WW-519	1	13'-6"	14	49-10"
WW-520	2	8'-7"	18	49-10"
WW-521	2	3'-10"	8	49-10"
WW-522	9	9'-2"	86	48-0"
WW-523	7	11'-4"	83	48-0"
WW-524	1	10'-7"	11	48-9"
WW-525	1	5'-7"	6	48-9"
WW-526	3	17'-8"	55	48-0"
WW-527	2	21'-2"	44	48-4"
WW-528	1	16'-5"	17	48-5"
WW-529	1	7'-1"	7	48-5"
WW-530	4	20'-3"	84	ST.
SERIES OF	1-SET OF	VARIES 17'-10"-19'-4" @ INC. 6"	78	ST.
WW-531	4			
WW-532	7	@ INC. 6"		
SERIES OF	1-SET OF	VARIES 10'-4"-14'-4" @ INC. 6"	168	ST.
WW-533	13	@ INC. 4"		
WW-534	2	5'-3"	7	ST.
WW-535	2	4'-8"	10	ST.
WW-601	15	7'-8"	173	BT.
WW-602	12	11'-8"	210	BT.
WW-603	13	6'-6"	127	BT.
WW-604	14	9'-6"	200	BT.
WW-605	13	7'-3"	142	BT.
WW-606	4	11'-11"	72	ST.
SERIES OF	1-SET OF	VARIES 9'-2"-11'-2" @ INC. 4"	60	ST.
WW-607	4			
SERIES OF	1-SET OF	VARIES 8'-9"-11'-5" @ INC. 6"	108	ST.
WW-608	7			
SERIES OF	1-SET OF	VARIES 8'-7"-12'-7" @ INC. 4"	207	ST.
WW-609	13			
WW-701	15	9'-1"	279	BT.
WW-702	14	14'-2"	405	BT.
WW-703	12	7'-6"	184	BT.
WW-801	7	11'-11"	223	BT.
WW-901	8	9'-2"	249	BT.
WW-1001	7	9'-7"	289	BT.
WW-1002	8	15'-7"	536	BT.
TOTAL WINGWALL ABUT#2			4947	
PIER				
P-501	56	8'-4"	487	BT.
P-502	56	7'-6"	438	BT.
P-601	2	37'-6"	113	ST.
P-801	14	10'-8"	399	BT.


SPIRAL REINFORCING SCHEDULE


MARK	NO. REQ'D	CORE DIA OF SPIRAL	LENGTH OF SPIRAL	PITCH	NO. OF TURNS	WEIGHT
SP-401	3	2'-8"	15'-4 5/8"	4"	49	807
SPACERS	12					126
			TOTAL			933


GRAND TOTAL: 102,882 LBS




FOR LENGTH AND RADIUS OF WINGWALL BARS (MARK: W AND WW BARS) SEE REINF BAR SCHEDULE.










A-604 & A-654












A-513 & A-563







A-603




A-653



P-903




A-560




P-1104

S-506

W-601	6'-1"
W-702	6'-1"
W-801	10'-5"
W-901	7'-5"
W-1001	7'-7"
W-1002	13'-7"
WW-605	6'-1"
WW-703	6'-1"
WW-801	10'-5"
WW-901	7'-5"
WW-1001	7'-7"
WW-1002	13'-7"





A-751	6'-6"	10"	
W-604	6'-6"	8"	
W-603	7'-9"	8"	
W-704	8'-8"	10"	
W-537	4'-6"	7"	
WW-601	7'-0"	8"	
WW-603	5'-10"	8"	
WW-701	8'-3"	10"	

A-752	10"	9'-11"	10"
A-901	1'-3"	14'-6"	1'-3"
W-602	8"	10'-4"	8"
W-613	8"	8'-2"	8"
W-705	10"	12'-8"	10"
W-536	7"	5'-11"	7"
WW-602	8"	10'-4"	8"
WW-604	8"	8'-2"	8"
WW-702	10"	12'-6"	10"
P-501	7"	7'-2"	7"
P-1001	1'-5"	40'-10"	1'-5"

TOTAL SUPERSTRUCTURE		48,453	
RAILING *			
R-501	16	4'-6"	ST.
R-502	8	13'-1"	ST.
R-503	8	11'-6"	ST.
R-504	32	17'-2"	ST.
R-505	32	16'-2"	ST.
R-506	4	8'-8"	BT.
R-507	8	10'-4"	BT.
REPLACEMENT BARS			
RE-401	1	5'-3" SPIRAL	BT.
RE-501		5'-6"	ST.
RE-601		6'-0"	ST.
RE-701		6'-3"	ST.
RE-801		6'-6"	ST.
RE-901		7'-0"	ST.
RE-1001		7'-3"	ST.
RE-1101		7'-6"	ST.

SPIRAL REINFORCING NOTES

THE LENGTH SHOWN IN THE STEEL SCHEDULE FOR SPIRAL BARS IS THE DISTANCE FROM THE TOP OF THE FOOTING TO BOTTOM OF THE PIER CAP.
THE NUMBER OF TURNS SHOWN IN THE STEEL SCHEDULE FOR SPIRAL BARS IS THE LENGTH DIVIDED BY THE PITCH PLUS THREE TURNS (TOTAL NUMBER OF CLOSED COILS) EXPRESSED AS THE NEAREST WHOLE NUMBER.
SPIRAL REINFORCING BARS SHALL NOT HAVE DEFORMATIONS, BUT SHALL IN OTHER RESPECTS CONFORM TO ITEM S-4.
ONE AND ONE HALF CLOSED COILS SHALL BE PROVIDED AT THE ENDS OF EACH SPIRAL UNIT.
FOUR (4) STEEL CHANNEL, TEE OR ANGLE SPACERS WEIGHING APPROX. 0.68 LBS PER LINEAL FT. OF SPACERS SHALL BE PROVIDED FOR EACH SPIRAL UNIT. THEY SHALL BE EQUALLY SPACED ALONG THE PERIPHERY OF EACH COIL. THE NUMBER OF POUNDS OF THESE SPACERS BASED ON 0.68 LBS PER LINEAL FT. WILL BE PAID FOR AS REINFORCING STEEL AND IS INCLUDED IN THE TABULATED QUANTITY OF SPIRAL BARS.

BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED AND THE FIRST TWO DIGITS WHERE FOUR ARE USED INDICATE THE BAR SIZE NUMBER FOR EXAMPLE A-701 IS A NO. 7 SIZE BAR AND A-1001 IS A NO 10 SIZE BAR.

REPLACEMENT BARS: IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SECTION S-4.02 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL BE NOT REQUIRED.

* RAILING REINFORCEMENT BARS WILL BE INCLUDED AS PART OF ITEM S-14 FOR PAYMENT.

FED. RD.	STATE	PROJECT	
	OHIO		

437
492

MAH-18-17.20

MICROFILMED SEP 19 '66

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

REINFORCING SCHEDULE

BRIDGE No. MAH-18-1934
UNDER RIDGE AVENUE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1021 + 51.99

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	JK					

FED. RD.	STATE	PROJECT	
2	OHIO		

438
492

MAH-18-N.20

MICROFILMED
SEP 19 1985

CURVE DATA

Δ = 53°49'25"
Dc = 5°45'
Ls = 400'
Ts = 708.91
Es = 128.51
Xc = 398.39'
Yc = 210.68'

4+00

5+00 RAMP "L"

INLET

END TAPER STA. 1023+67.64

SLOPE WALLS

BEGIN APPROACH SLAB STA. 4+40.49

WOODLAND AVE.

WOODLAND & RELOCATED WOODLAND AVE.

BEGIN TAPER STA. 1027+17.64

RETAINING WALL

STA. 4+11.46

12' ACCELERATION LANE (RAMP "N")

℄ WESTBOUND LANE

℄ SURVEY OF S.R. #18

S.C. STA. 1025+55.38

1027+00

1028+00

℄ EASTBOUND LANE

PT STA. 13+24.72

STA. 1024+98.23

STA. 1025+08.02
℄ X-RD STA. 4+98.94

23°23'27"

M.H.

80' S&S PIPE

3" GAS LINE

18" S&S PIPE

CLEAR

WOODLAND & WILLIAMS STA. 9+99.56

50' E.

MIN. CLEARANCE

℄ RAMP "K"

12+00

13+00

14+00

FACE RETAINING WALL

℄ ORIGINAL WOODLAND

℄ RELOCATED WOODLAND

20°31'44" SKEW

55°17'15"

25' R.

℄ BROADWAY

WILLIAM ST.

FACE EXISTING CURB

APPROACH SLAB STA. 5+53.34

FACE EXISTING CURB

℄ OF STATIONING

10+00 935.04
10+50 936.34
11+00 937.64
11+50 938.94
12+00 940.24

15.75' ACTUAL MIN. CLEARANCE
15.00 REQUIRED MIN CLEAR.

P.C. RAMP "K" +2.60%

P.C. S.R. #18

800' V.C.

+3.12% P.V.I. STA. 1026+00 -2.72%
EL. 940.62

+4.35% 200' V.C. P.V.I. STA. 9+00 EL. 932.44 +2.60%
RAMP "K"

932.61
933.39
934.00
934.41
934.64

1024+00
1025+00
1026+00

960
940
920

STA. 4+40.49
EL. 954.00

954.42

956.64

STA. 5+53.34
EL. 960.77

961.00

963.27

EL. 926.60
EL. 926.65
EL. 933.00

+3.42% 100' V.C. EL. 950.00 +4.25%

+4.25% 938.89

15.00' REQ'D. MIN. CLEAR.

15.75' ACTUAL MIN. CLEAR.

320 340 360

4+00 5+00 6+00


950 952 956 960 962

9+00 10+00 11+00

2:1

FOUNDATION SOUNDING

FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF SOIL SAMPLING SOUNDINGS MADE AT THE SITE. THIS SOUNDING INFORMATION MAY BE INSPECTED IN THE OFFICE OF THE BUREAU OF BRIDGES IN COLUMBUS OR IN THE DIVISION OFFICE BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THEREOF.



TYPICAL SECTION
PROPOSED WOODLAND AVE.

PROPOSED STRUCTURE

TYPE: CONTINUOUS STEEL BEAM WITH REINF. CONCRETE DECK & SUBSTRUCTURE
SPANS: 38'-6" 51'-9" 56'-0" c/c BRGS.
ROADWAY: 48'-0" F/F CURBS 5'-0" SIDEWALK EACH SIDE
LOAD FREQUENCY: CF 2000
SKEW 23°23'27" R.F. FOR PIERS & ABUT. #1 - 20°31'44" RF FOR ABUT. #2
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLABS: 25' LONG AS-1-54
SUPERELEVATION: NONE
ALIGNMENT: TANGENT
TRAFFIC COUNT: 14,000 ADT 1979

AVERAGE ESTIMATED PAY LENGTH FOR PILES ARE:
ABUTMENTS @ 25
PIERS @ 25

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SITE PLAN
BRIDGE Nº MAH.-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN MAHONING COUNTY
STA. 1024+98.23


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
	AC		D.S.	DHC		

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

439
492

MAH-18-17.20



GENERAL PLAN

ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPER	ABUT	PIER	GEN		
E-2	LUMP	SUM	COFFERDAMS, CRIBS AND SHEETING				LUMP		
E-2	1898	SQ.FT.	STEEL SHEET PILING, LEFT IN PLACE						
			(32 # SQ.FT.) INCLUDING ANCHOR BARS*		1,898				
E-2	2,702	CU.YDS.	UNCLASSIFIED EXCAVATION		2,560	142			
S-1	349	CU.YDS.	CLASS "C" CONCRETE SUPERSTRUCTURE	349					
S-1	507	CU.YDS.	CLASS "E" CONCRETE ABUTMENT WALLS		507				
S-1	93	CU.YDS.	CLASS "C" CONCRETE PIER ABOVE FOOTINGS			93			
S-1	469	CU.YDS.	CLASS "E" CONCRETE PIER & ABUT. FOOTINGS		401	68			
S-3	16	SQ.YDS.	TYPE "B" WATERPROOFING		16				
S-3	126	LIN.FT.	WATER PROOFING PREMOLDED SEALING STRIP		126				
S-9	94	SQ.FT.	1" PREFORMED EXP. JOINT FILLER		94				
S-4	183,258	LBS.	REINFORCING STEEL	82,932	74,717	25609			
S-7	250,432	LBS.	STRUCTURAL STEEL	250,432					
S-8	250,432	LBS	FIELD PAINTING OF STRUCTURAL STEEL AS PER PLAN.	250,432					
S-14	321	LIN.FT.	RAILING (TYPE "C") (ALUM. RAIL & SUP'TS, CONCRETE PARAPET.)	301	20				
S-16	LUMP	SUM	FIRST TEST PILE				LUMP		
S-18	4925	LIN.FT.	12" CAST-IN-PLACE REINFORCED CONC. PILES		3725	1200			
S-25	LUMP	SUM	ELECTRICAL LIGHTING SYSTEM	LUMP					
S-29	LUMP	SUM	SCUPPERS	LUMP					
S-28	352	CU.YDS.	POROUS BACKFILL		352				
S-29	161	LIN.FT.	6" ϕ STD. WEIGHT PIPE GALV. OR W.I. (DOWN SPOUT) INCLUDING SPECIALS.				161		
S-29	126	LIN.FT.	8" ϕ PERFORATED BITUMINOUS COATED C.M.P. INCLUDING SPECIALS		126				

*WT. OF ANCHOR BARS = 203.0#

GENERAL NOTES

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF "DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES" OF THE STATE OF OHIO, DEPARTMENT OF HIGHWAYS, DATED 5-1-57 TOGETHER WITH CURRENT REVISIONS THEREOF.

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE CONCRETE OF THE DECK SLAB, THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE. THE SLAB MAY PLACED IN SECTIONS BETWEEN TRANSVERSE CONSTRUCTION JOINTS WHICH ARE PARALLEL TO TRANSVERSE REINFORCING STEEL AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

WELDING OF STRUCTURAL STEEL SHALL BE CLASS "A" EXCEPT AS OTHERWISE SHOWN. ANY WELDS SHOWN AS FIELD WELDS MAY AT THE OPTION OF THE CONTRACTOR BE MADE IN THE SHOP.

REFERENCE SHALL BE MADE TO STANDARD DRAWINGS:
AR-1-57, DATED 4-9-57, REVISED 12-2-59.
C.S.D.-2-56, SHEET 2 & 3, DATED 12-3-56, REVISED 2-2-59.
SUPPLEMENTAL SPECIFICATIONS S-101, DATED 12-2-59 AND S-207 DATED 5-28-55.


ELECTRICAL GROUNDS: A SOLID N°0 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON EACH SIDE OF THE STRUCTURE AT PIER N°2. THE LOWER ENDS OF THE WIRES SHALL BE BRAZED TO THE STEEL SHELL OF ONE OF THE CAST-IN-PLACE CONCRETE PILES AND THE UPPER ENDS SHALL EXTEND SUFFICIENTLY ABOVE THE TOP OF THE CONCRETE TO PROVIDE FOR A SUITABLE SPLICE AND EXTENSION FOR CONNECTION TO THE SUPERSTRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE A N°6 GAGE BARE STRANDED TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE AND TO THE SOLID COPPER WIRE IN THE PIER SHAFT, THERE SHALL BE A TINNED N°6 GAGE BARE COPPER WIRE BRAZED TO THE ANCHOR BOLTS OF EACH LIGHT STANDARD AND THE OTHER ENDS BRAZED OR BOLTED TO THE OUTSIDE BEAM FLANGE. PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM BID FOR ITEM S-25, "ELECTRICAL LIGHTING SYSTEM".

PILES: ALL PILES TO BE 12" DIA. CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN TO A MIN. BEARING CAPACITY OF 40 TONS.

SURFACE FINISH OF CONCRETE: ABUTMENT WALLS SHALL RECEIVE A RUBBED SURFACE FINISH. ALL OTHER EXPOSED SURFACES SHALL BE GOVERNED BY THE PROVISIONS OF ITEM S-1.

UTILITY LINES: ALL LABOR AND EXPENSE INVOLVED IN RELOCATING THE AFFECTED UTILITY LINES SHALL BE BORN BY THE OWNERS. THE CONTRACTOR AND OWNERS ARE REQUESTED TO COOPERATE BY ARRANGING THEIR WORK IN SUCH A MANNER THAT INCONVENIENCE TO EITHER WILL BE HELD TO A MINIMUM.

DOWN SPOUTS: SHALL BE 6" STANDARD WROUGHT IRON PIPE OR HOT DIPPED GALVANIZED STEEL PIPE. JOINTS SHALL BE MADE BY WELDING. ALL WELDING SHALL BE DONE BEFORE GALVANIZING. STRAPS OR CLAMPS SHALL BE WROUGHT IRON OR HOT DIPPED GALVANIZED STEEL. ON BOLTS GALVANIZING AS CALLED FOR IN SEC: M-10.30 WILL BE CONSIDERED SUFFICIENT.



ELEVATION

ITEM S-25: ELECTRICAL LIGHTING SYSTEM INCLUDES 8-1½ϕ x 4'-1" ANCHOR BOLTS.

MACHINE FINISH. At the Contractor's option the top of the bridge deck slab may be machine finished. Machine finishing, if used, shall be in accordance with the Proposed Note," Machine Finishing of Bridge Deck Slabs.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

WEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GENERAL PLAN & ELEVATION

BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025+08.02


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAH.	GASKILL		ew.	DHC.		

MICROFILMED
SEP 19 1965


FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18-17.20

440
492



PLAN





DETAIL OF RUSTICATION GROOVES

ELEVATIONS MARKED THUS * GIVEN TO HEEL OF ANGLE

NOTES:

ALL REINFORCING STEEL TO HAVE A 2" MIN. COVER UNLESS OTHERWISE NOTED

THE CONCRETE IN THE ABUTMENT BACKWALL SHALL NOT BE PLACED UNTIL AFTER STEELWORK IS ERECTED, BUT SHALL BE PLACED BEFORE THE DECK SLAB CONCRETE IS PLACED.

POROUS BACKFILL: 2 FT. THICK FULL LENGTH OF ABUTMENT AND WINGWALLS SHALL EXTEND UP TO THE UNDERSIDE OF THE APPROACH SLABS OR TO THE FINISHED GROUND SURFACE.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 PLAN & ELEVATION

BRIDGE NO. MAH-18-1041
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025 + 08.02


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	GASKILL AC		ew	DHC		

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


441
492




SECTION A-A



SECTION B-B
SOUTH WINGWALL SIMILAR




SECTION D-D




SECTION C-C
DETAILS NOT SHOWN SAME AS SECTION A-A

PREFORMED EXPANSION JOINT FILLER. WHERE RETAINING WALL JOINS ABUTMENT THE QUANTITY IS INCLUDED WITH THE WALL. IN CASE OF WINGWALLS THE QUANTITY IS INCLUDED WITH THE BRIDGE



SECTION E-E As Shown
SECTION E_2-E_2 Opp Hand



DETAIL OF CONTRACTION JOINT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAILS

BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025+08.02


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	AC		ecw	DHC		

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH.-18-17.20


442
492



FOOTER PLAN



DETAIL - "C"



FOR CONNECTION AT DETAIL "D" - THE TOP FE. OF THE 24 WF 76 IS PLACED 1 1/8" LOWER THEN THE TOP FE OF THE 36 WF 150. DETAIL "E" THE TOP FE OF BOTH BEAMS ARE LEVEL.

DETAIL "D" & "E"

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 DETAILS

BRIDGE NO. MAH-18-1041
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025+08.02


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	AC		EAK	DHC		

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		


443
492

MAH-18-17.20




PLAN VIEW

NOTE:
ALL DIMENSIONS ARE AT OUTER FACE OF WALL (50'-0" RAD.)




DETAIL A


ELEVATION VIEW
DEVELOPED LENGTH OF OUTER FACE OF WALL (50'-0" RAD.)
ALL HORIZONTAL DIMENSIONS AT OUTER FACE




SECTION A-A




SECTION B-B




SECTION C-C



SECTION D-D



DETAIL OF CONTRACTION JOINT



DETAIL OF RUSTICATION GROOVES

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 WINGWALL

BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025 + 08.02

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAH	AC		EJW	DHC		

MICROFILMED SEP 19 1955

FED. RD.	STATE	PROJECT		444 / 492
	OHIO			

MAH-18-17.20

NOTE: ELEVATION SHOWN THUS 959.88 IS GIVEN TO HEEL OF EXPANSION DAM ANGLE.

PLAN

ELEVATION

SECTION "A-A"
(VIEW OPP. HAND AT WING WALL END.)

DETAIL OF CONTRACTION JOINT

DETAIL OF RUSTICATION GROOVES

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT 2 PLAN & ELEVATION
BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025+08.02


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAR	Hagen		aw	DHC		

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MA H- 18-17.20


445
492




SECTION "B-B"




SECTION "E-E"



SECTION "G-G"
NORTH END OF ABUT. SIMILAR



SECTION "H-H"



SECTION "J-J"

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT # 2 DETAILS

BRIDGE NO. MAH-18-1041
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025 + 08.02


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
FAK	HAGER		CW	DHC		

MICROFILMED
SEP 19 1955

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

446
492



FOOTER PLAN

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT # 2 DETAILS

BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025 + 08.02

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAH				DHC		


MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

447
492

PLAN VIEW


N
BETHLEHEM SECTION DP-1 OR EQUAL
2'-8" ± %
2'-0"
4"
7/8"x3" ANCHOR BAR DO NOT WELD UNTIL AFTER BOTTOM BARS ARE PLACED
DETAIL OF SHEET PILING
50'-0" RADIUS (OUTER FACE OF WALL)
46'-1" R.
43'-3" R.
44'-5½" R.
46'-9⅞"
11'-6" AT TOP OF WALL
W.P.
118'-14" = 14'-8" @ 8" + 13-14'-4" + 14'-8" @ 8"
17-5P'S @ 1'-4" = 22'-8"
W-581 TOP & BOT.
W-582 TOP & BOT.
W-583 TOP & BOT.
W-584 TOP & BOT.
W-585 TOP & BOT.
W-586 BOT.
W-587 BOT.
W-588 TOP & BOT.
W-589 TOP & BOT.
W-590 TOP & BOT.
W-591 TOP & BOT.
W-592 BOT.
W-593 TOP
W-593 BOT
2'-0" LAP
10" SPACING
6'-0" (FOOTER 21'-8" WIDE)
6'-0" (4'-4" CONC. + 1'-8" SAND)
2'-0" SPACE
4'-0" SPACING - TYP.
W-575 TOP & BOT.
SHEET PILING
END OF ABUT. № 2 SHOWN DOTTED
20°-31'-44"
32'-5⅝"
W.P.
℄ BRGS.
FACE OF ABUT. WALL
EXTERIOR SEAM
3'-11¾"
3'-0"
THESE DIMENSIONS ALL AT OUTER FACE OF WALL (on 50'-0" RAD.)
W-576 TOP & BOT.
W-577 TOP & BOT.
W-578 TOP & BOT.
W-581 BOT.
OUTER FACE OF WALL
38-N-19 TYP. 4-SPACES @ 5'-0" = 20'-0" PILE SPACING
24'-0"
(FOOTER 13'-0" WIDE)
56'-0"
16'-0" (FOOTER 10'-10" WIDE)
5'-0"
3'-0"
2'-0"
W-575
W-577
W-578
W-581
W-582
W-583
W-584
W-585
W-586
W-587
W-588
W-589
W-590
W-591
W-592
W-593
W-594
W-595
W-596
W-597
W-598
W-599
W-600
W-601
W-602
W-603
W-604
W-605
W-606
W-607
W-608
W-609
W-610
W-611
W-612
W-613
W-614
W-615
W-616
W-617
W-618
W-619
W-620
W-621
W-622
W-623
W-624
W-625
W-626
W-627
W-628
W-629
W-630
W-631
W-632
W-633
W-634
W-635
W-636
W-637
W-638
W-639
W-640
W-641
W-642
W-643
W-644
W-645
W-646
W-647
W-648
W-649
W-650
W-651
W-652
W-653
W-654
W-655
W-656
W-657
W-658
W-659
W-660
W-661
W-662
W-663
W-664
W-665
W-666
W-667
W-668
W-669
W-670
W-671
W-672
W-673
W-674
W-675
W-676
W-677
W-678
W-679
W-680
W-681
W-682
W-683
W-684
W-685
W-686
W-687
W-688
W-689
W-690
W-691
W-692
W-693
W-694
W-695
W-696
W-697
W-698
W-699
W-700
W-701
W-702
W-703
W-704
W-705
W-706
W-707
W-708
W-709
W-710
W-711
W-712
W-713
W-714
W-715
W-716
W-717
W-718
W-719
W-720
W-721
W-722
W-723
W-724
W-725
W-726
W-727
W-728
W-729
W-730
W-731
W-732
W-733
W-734
W-735
W-736
W-737
W-738
W-739
W-740
W-741
W-742
W-743
W-744
W-745
W-746
W-747
W-748
W-749
W-750
W-751
W-752
W-753
W-754
W-755
W-756
W-757
W-758
W-759
W-760
W-761
W-762
W-763
W-764
W-765
W-766
W-767
W-768
W-769
W-770
W-771
W-772
W-773
W-774
W-775
W-776
W-777
W-778
W-779
W-780
W-781
W-782
W-783
W-784
W-785
W-786
W-787
W-788
W-789
W-790
W-791
W-792
W-793
W-794
W-795
W-796
W-797
W-798
W-799
W-800
W-801
W-802
W-803
W-804
W-805
W-806
W-807
W-808
W-809
W-810
W-811
W-812
W-813
W-814
W-815
W-816
W-817
W-818
W-819
W-820
W-821
W-822
W-823
W-824
W-825
W-826
W-827
W-828
W-829
W-830
W-831
W-832
W-833
W-834
W-835
W-836
W-837
W-838
W-839
W-840
W-841
W-842
W-843
W-844
W-845
W-846
W-847
W-848
W-849
W-850
W-851
W-852
W-853
W-854
W-855
W-856
W-857
W-858
W-859
W-860
W-861
W-862
W-863
W-864
W-865
W-866
W-867
W-868
W-869
W-870
W-871
W-872
W-873
W-874
W-875
W-876
W-877
W-878
W-879
W-880
W-881
W-882
W-883
W-884
W-885
W-886
W-887
W-888
W-889
W-890
W-891
W-892
W-893
W-894
W-895
W-896
W-897
W-898
W-899
W-900
W-901
W-902
W-903
W-904
W-905
W-906
W-907
W-908
W-909
W-910
W-911
W-912
W-913
W-914
W-915
W-916
W-917
W-918
W-919
W-920
W-921
W-922
W-923
W-924
W-925
W-926
W-927
W-928
W-929
W-930
W-931
W-932
W-933
W-934
W-935
W-936
W-937
W-938
W-939
W-940
W-941
W-942
W-943
W-944
W-945
W-946
W-947
W-948
W-949
W-950
W-951
W-952
W-953
W-954
W-955
W-956
W-957
W-958
W-959
W-960
W-961
W-962
W-963
W-964
W-965
W-966
W-967
W-968
W-969
W-970
W-971
W-972
W-973
W-974
W-975
W-976
W-977
W-978
W-979
W-980
W-981
W-982
W-983
W-984
W-985
W-986
W-987
W-988
W-989
W-990
W-991
W-992
W-993
W-994
W-995
W-996
W-997
W-998
W-999
W-1000
W-1001
W-1002
W-1003
W-1004
W-1005
W-1006
W-1007
W-1008
W-1009
W-1010
W-1011
W-1012
W-1013
W-1014
W-1015
W-1016
W-1017
W-1018
W-1019
W-1020
W-1021
W-1022
W-1023
W-1024
W-1025
W-1026
W-1027
W-1028
W-1029
W-1030
W-1031
W-1032
W-1033
W-1034
W-1035
W-1036
W-1037
W-1038
W-1039
W-1040
W-1041
W-1042
W-1043
W-1044
W-1045
W-1046
W-1047
W-1048
W-1049
W-1050
W-1051
W-1052
W-1053
W-1054
W-1055
W-1056
W-1057
W-1058
W-1059
W-1060
W-1061
W-1062
W-1063
W-1064
W-1065
W-1066
W-1067
W-1068
W-1069
W-1070
W-1071
W-1072
W-1073
W-1074
W-1075
W-1076
W-1077
W-1078
W-1079
W-1080
W-1081
W-1082
W-1083
W-1084
W-1085
W-1086
W-1087
W-1088
W-1089
W-1090
W-1091
W-1092
W-1093
W-1094
W-1095
W-1096
W-1097
W-1098
W-1099
W-1100
W-1101
W-1102
W-1103
W-1104
W-1105
W-1106
W-1107
W-1108
W-1109
W-1110
W-1111
W-1112
W-1113
W-1114
W-1115
W-1116
W-1117
W-1118
W-1119
W-1120
W-1121
W-1122
W-1123
W-1124
W-1125
W-1126
W-1127
W-1128
W-1129
W-1130
W-1131
W-1132
W-1133
W-1134
W-1135
W-1136
W-1137
W-1138
W-1139
W-1140
W-1141
W-1142
W-1143
W-1144
W-1145
W-1146
W-1147
W-1148
W-1149
W-1150
W-1151
W-1152
W-1153
W-1154
W-1155
W-1156
W-1157
W-1158
W-1159
W-1160
W-1161
W-1162
W-1163
W-1164
W-1165
W-1166
W-1167
W-1168
W-1169
W-1170
W-1171
W-1172
W-1173
W-1174
W-1175
W-1176
W-1177
W-1178
W-1179
W-1180
W-1181
W-1182
W-1183
W-1184
W-1185
W-1186
W-1187
W-1188
W-1189
W-1190
W-1191
W-1192
W-1193
W-1194
W-1195
W-1196
W-1197
W-1198
W-1199
W-1200
W-1201
W-1202
W-1203
W-1204
W-1205
W-1206
W-1207
W-1208
W-1209
W-1210
W-1211
W-1212
W-1213
W-1214
W-1215
W-1216
W-1217
W-1218
W-1219
W-1220
W-1221
W-1222
W-1223
W-1224
W-1225
W-1226
W-1227
W-1228
W-1229
W-1230
W-1231
W-1232
W-1233
W-1234
W-1235
W-1236
W-1237
W-1238
W-1239
W-1240
W-1241
W-1242
W-1243
W-1244
W-1245
W-1246
W-1247
W-1248
W-1249
W-1250
W-1251
W-1252
W-1253
W-1254
W-1255
W-1256
W-1257
W-1258
W-1259
W-1260
W-1261
W-1262
W-1263
W-1264
W-1265
W-1266
W-1267
W-1268
W-1269
W-1270
W-1271
W-1272
W-1273
W-1274
W-1275
W-1276
W-1277
W-1278
W-1279
W-1280
W-1281
W-1282
W-1283
W-1284
W-1285
W-1286
W-1287
W-1288
W-1289
W-1290
W-1291
W-1292
W-1293
W-1294
W-1295
W-1296
W-1297
W-1298
W-1299
W-1300
W-1301
W-1302
W-1303
W-1304
W-1305
W-1306
W-1307
W-1308
W-1309
W-1310
W-1311
W-1312
W-1313
W-1314
W-1315
W-1316
W-1317
W-1318
W-1319
W-1320
W-1321
W-1322
W-1323
W-1324
W-1325
W-1326
W-1327
W-1328
W-1329
W-1330
W-1331
W-1332
W-1333
W-1334
W-1335
W-1336
W-1337
W-1338
W-1339
W-1340
W-1341
W-1342
W-1343
W-1344
W-1345
W-1346
W-1347
W-1348
W-1349
W-1350
W-1351
W-1352
W-1353
W-1354
W-1355
W-1356
W-1357
W-1358
W-1359
W-1360
W-1361
W-1362
W-1363
W-1364
W-1365
W-1366
W-1367
W-1368
W-1369
W-1370
W-1371
W-1372
W-1373
W-1374
W-1375
W-1376
W-1377
W-1378
W-1379
W-1380
W-1381
W-1382
W-1383
W-1384
W-1385
W-1386
W-1387
W-1388
W-1389
W-1390
W-1391
W-1392
W-1393
W-1394
W-1395
W-1396
W-1397
W-1398
W-1399
W-1400
W-1401
W-1402
W-1403
W-1404
W-1405
W-1406
W-1407
W-1408
W-1409
W-1410
W-1411
W-1412
W-1413
W-1414
W-1415
W-1416
W-1417
W-1418
W-1419
W-1420
W-1421
W-1422
W-1423
W-1424
W-1425
W-1426
W-1427
W-1428
W-1429
W-1430
W-1431
W-1432
W-1433
W-1434
W-1435
W-1436
W-1437
W-1438
W-1439
W-1440
W-1441
W-1442
W-1443
W-1444
W-1445
W-1446
W-1447
W-1448
W-1449
W-1450
W-1451
W-1452
W-1453
W-1454
W-1455
W-1456
W-1457
W-1458
W-1459
W-1460
W-1461
W-1462
W-1463
W-1464
W-1465
W-1466
W-1467
W-1468
W-1469
W-1470
W-1471
W-1472
W-1473
W-1474
W-1475
W-1476
W-1477
W-1478
W-1479
W-1480
W-1481
W-1482
W-1483
W-1484
W-1485
W-1486
W-1487
W-1488
W-1489
W-1490
W-1491
W-1492
W-1493
W-1494
W-1495
W-1496
W-1497
W-1498
W-1499
W-1500
W-1501
W-1502
W-1503
W-1504
W-1505
W-1506
W-1507
W-1508
W-1509
W-1510
W-1511
W-1512
W-1513
W-1514
W-1515
W-1516
W-1517
W-1518
W-1519
W-1520
W-1521
W-1522
W-1523
W-1524
W-1525
W-1526
W-1527
W-1528
W-1529
W-1530
W-1531
W-1532
W-1533
W-1534
W-1535
W-1536
W-1537
W-1538
W-1539
W-1540
W-1541
W-1542
W-1543
W-1544
W-1545
W-1546
W-1547
W-1548
W-1549
W-1550
W-1551
W-1552
W-1553
W-1554
W-1555
W-1556
W-1557
W-1558
W-1559
W-1560
W-1561
W-1562
W-1563
W-1564
W-1565
W-1566
W-1567
W-1568
W-1569
W-1570
W-1571
W-1572
W-1573
W-1574
W-1575
W-1576
W-1577
W-1578
W-1579
W-1580
W-1581
W-1582
W-1583
W-1584
W-1585
W-1586
W-1587
W-1588
W-1589
W-1590
W-1591
W-1592
W-1593
W-1594
W-1595
W-1596
W-1597
W-1598
W-1599
W-1600
W-1601
W-1602
W-1603
W-1604
W-1605
W-1606
W-1607
W-1608
W-1609
W-1610
W-1611
W-1612
W-1613
W-1614
W-1615
W-1616
W-1617
W-1618
W-1619
W-1620
W-1621
W-1622
W-1623
W-1624
W-1625
W-1626
W-1627
W-1628
W-1629
W-1630
W-1631
W-1632
W-1633
W-1634
W-1635
W-1636
W-1637
W-1638
W-1639
W-1640
W-1641
W-1642
W-1643
W-1644
W-1645
W-1646
W-1647
W-1648
W-1649
W-1650
W-1651
W-1652
W-1653
W-1654
W-1655
W-1656
W-1657
W-1658
W-1659
W-1660
W-1661
W-1662
W-1663
W-1664
W-1665
W-1666
W-1667
W-1668
W-1669
W-1670
W-1671
W-1672
W-1673
W-1674
W-1675
W-1676
W-1677
W-1678
W-1679
W-1680
W-1681
W-1682
W-1683
W-1684
W-1685
W-1686
W-1687
W-1688
W-1689
W-1690
W-1691
W-1692
W-1693
W-1694
W-1695
W-1696
W-1697
W-1698
W-1699
W-1700
W-1701
W-1702
W-1703
W-1704
W-1705
W-1706
W-1707
W-1708
W-1709
W-1710
W-1711
W-1712
W-1713
W-1714
W-1715
W-1716
W-1717
W-1718
W-1719
W-1720
W-1721
W-1722
W-1723
W-1724
W-1725
W-1726
W-1727
W-1728
W-1729
W-1730
W-1731
W-1732
W-1733
W-1734
W-1735
W-1736
W-1737
W-1738
W-1739
W-1740
W-1741
W-1742
W-1743
W-1744
W-1745
W-1746
W-1747
W-1748
W-1749
W-1750
W-1751
W-1752
W-1753
W-1754
W-1755
W-1756
W-1757
W-1758
W-1759
W-1760
W-1761
W-1762
W-1763
W-1764
W-1765
W-1766
W-1767
W-1768
W-1769
W-1770
W-1771
W-1772
W-1773
W-1774
W-1775
W-1776
W-1777
W-1778
W-1779
W-1780
W-1781
W-1782
W-1783
W-1784
W-1785
W-1786
W-1787
W-1788
W-1789
W-1790
W-1791
W-1792
W-1793
W-1794
W-1795
W-1796
W-1797
W-1798
W-1799
W-1800
W-1801
W-1802
W-1803
W-1804
W-1805
W-1806
W-1807
W-1808
W-1809
W-1810
W-1811
W-1812
W-1813
W-1814
W-1815
W-1816
W-1817
W-1818
W-1819
W-1820
W-1821
W-1822
W-1823
W-1824
W-1825
W-1826
W-1827
W-1828
W-1829
W-1830
W-1831
W-1832
W-1833
W-1834
W-1835
W-1836
W-1837
W-1838
W-1839
W-1840
W-1841
W-1842
W-1843
W-1844
W-1845
W-1846
W-1847
W-1848
W-1849
W-1850
W-1851
W-1852
W-1853
W-1854
W-1855
W-1856
W-1857
W-1858
W-1859
W-1860
W-1861
W-1862
W-1863
W-1864
W-1865
W-1866
W-1867
W-1868
W-1869
W-1870
W-1871
W-1872
W-1873
W-1874
W-1875
W-1876
W-1877
W-1878
W-1879
W-1880
W-1881
W-1882
W-1883
W-1884
W-1885
W-1886
W-1887
W-1888
W-1889
W-1890
W-1891
W-1892
W-1893
W-1894
W-1895
W-1896
W-1897
W-1898
W-1899
W-1900
W-1901
W-1902
W-1903
W-1904
W-1905
W-1906
W-1907
W-1908
W-1909
W-1910
W-1911
W-1912
W-1913
W-1914
W-1915
W-1916
W-1917
W-1918
W-1919
W-1920
W-1921
W-1922
W-1923
W-1924
W-1925
W-1926
W-1927
W-1928
W-1929
W-1930
W-1931
W-1932
W-1933
W-1934
W-1935
W-1936
W-1937
W-1938
W-1939
W-1940
W-1941
W-1942
W-1943
W-1944
W-1945
W-1946
W-1947
W-1948
W-1949
W-1950
W-1951
W-1952
W-1953
W-1954
W-1955
W-1956
W-1957
W-1958
W-1959
W-1960
W-1961
W-1962
W-1963
W-1964
W-1965
W-1966
W-1967
W-1968
W-1969
W-1970
W-1971
W-1972
W-1973
W-1974
W-1975
W-1976
W-1977
W-1978
W-1979
W-1980
W-1981
W-1982
W-1983
W-1984
W-1985
W-1986
W-1987
W-1988
W-1989
W-1990
W-1991
W-1992
W-1993
W-1994
W-1995
W-1996
W-1997
W-1998
W-1999
W-2000
W-2001
W-2002
W-2003
W-2004
W-2005
W-2006
W-2007
W-2008
W-2009
W-2010
W-2011
W-2012
W-2013
W-2014
W-2015
W-2016
W-2017
W-2018
W-2019
W-2020
W-2021
W-2022
W-2023
W-2024
W-2025
W-2026
W-2027
W-2028
W-2029
W-2030
W-2031
W-2032
W-2033
W-2034
W-2035
W-2036
W-2037
W-2038
W-2039
W-2040
W-2041
W-2042
W-2043
W-2044
W-2045
W-2046
W-2047
W-2048
W-2049
W-2050
W-2051
W-2052
W-2053
W-2054
W-2055
W-2056
W-2057
W-2058
W-2059
W-2060
W-2061
W-2062
W-2063
W-2064
W-2065
W-2066
W-2067
W-2068
W-2069
W-2070
W-2071
W-2072
W-2073
W-2074
W-2075
W-2076
W-2077
W-2078
W-2079
W-2080
W-2081
W-2082
W-2083
W-2084
W-2085
W-2086
W-2087
W-2088
W-2089
W-2090
W-2091
W-2092
W-2093
W-2094
W-2095
W-2096
W-2097
W-2098
W-2099
W-2100
W-2101
W-2102
W-2103
W-2104
W-2105
W-2106
W-2107
W-2108
W-2109
W-2110
W-2111
W-2112
W-2113
W-2114
W-2115
W-2116
W-2117
W-2118
W-2119
W-2120
W-2121
W-2122
W-2123
W-2124
W-2125
W-2126
W-2127
W-2128
W-2129
W-2130
W-2131
W-2132
W-2133
W-2134
W-2135
W-2136
W-2137
W-2138
W-2139
W-2140
W-2141
W-2142
W-2143
W-2144
W-2145
W-2146
W-2147
W-2148
W-2149
W-2150
W-2151
W-2152
W-2153
W-2154
W-2155
W-2156
W-2157
W-2158
W-2159
W-2160
W-2161
W-2162
W-2163
W-2164
W-2165
W-2166
W-2167
W-2168
W-2169
W-2170
W-2171
W-2172
W-2173
W-2174
W-2175
W-2176
W-2177
W-2178
W-2179
W-2180
W-2181
W-2182
W-2183
W-2184
W-2185
W-2186
W-2187
W-2188
W-2189
W-2190
W-2191
W-2192
W-2193
W-2194
W-2195
W-2196
W-2197
W-2198
W-2199
W-2200
W-2201
W-2202
W-2203
W-2204
W-2205
W-2206
W-2207
W-2208
W-2209
W-2210
W-2211
W-2212
W-2213
W-2214
W-2215
W-2216
W-2217
W-2218
W-2219
W-2220
W-2221
W-2222
W-2223
W-2224
W-2225
W-2226
W-2227
W-2228
W-2229
W-2230
W-2231
W-2232
W-2233
W-2234
W-2235
W-2236
W-2237
W-2238
W-2239
W-2240
W-2241
W-2242
W-2243
W-2244
W-2245
W-2246
W-2247
W-2248
W-2249
W-2250
W-2251
W-2252
W-2253
W-2254
W-2255
W-2256
W-2257
W-2258
W-2259
W-2260
W-2261
W-2262
W-2263
W-2264
W-2265
W-2266
W-2267
W-2268
W-2269
W-2270
W-2271
W-2272
W-2273
W-2274
W-2275
W-2276
W-2277
W-2278
W-2279
W-2280
W-2281
W-2282
W-2283
W-2284
W-2285
W-2286
W-2287
W-2288
W-2289
W-2290
W-2291
W-2292
W-2293
W-2294
W-2295
W-2296
W-2297
W-2298
W-2299
W-2300
W-2301
W-2302
W-2303
W-2304
W-2305
W-2306
W-2307
W-2308
W-2309
W-2310
W-2311
W-2312
W-2313
W-2314
W-2315
W-2316
W-2317
W-2318
W-2319
W-2320
W-2321
W-2322
W-2323
W-2324
W-2325
W-2326
W-2327
W-2328
W-2329
W-2330
W-2331
W-2332
W-2333
W-2334
W-2335
W-2336
W-2337
W-2338
W-2339
W-2340
W-2341
W-2342
W-2343
W-2344
W-2345
W-2346
W-2347
W-2348
W-2349
W-2350
W-2351
W-2352
W-2353
W-2354
W-2355
W-2356
W-2357
W-2358
W-2359
W-2360
W-2361
W-2362
W-2363
W-2364
W-2365
W-2366
W-2367
W-2368
W-2369
W-2370
W-2371
W-2372
W-2373
W-2374
W-2375
W-2376
W-2377
W-2378
W-2379
W-2380
W-2381
W-2382
W-2383
W-2384
W-2385
W-2386
W-2387
W-2388
W-2389
W-2390
W-2391
W-2392
W-2393
W-2394
W-2395
W-2396
W-2397
W-2398
W-2399
W-2400
W-2401
W-2402
W-2403
W-2404
W-2405
W-2406
W-2407
W-2408
W-2409
W-2410
W-2411
W-2412
W-2413
W-2414
W-2415
W-2416
W-2417
W-2418
W-2419
W-2420
W-2421
W-2422
W-2423
W-2424
W-2425
W-2426
W-2427
W-2428
W-2429
W-2430
W-2431
W-2432
W-2433
W-2434
W-2435
W-2436
W-2437
W-2438
W-2439
W-2440
W-2441
W-2442
W-2443
W-2444
W-2445
W-2446
W-2447
W-2448
W-2449
W-2450
W-2451
W-2452
W-2453
W-2454
W-2455
W-2456
W-2457
W-2458
W-2459
W-2460
W-2461
W-2462
W-2463
W-2464
W-2465
W-2466
W-2467
W-2468
W-2469
W-2470
W-2471
W-2472
W-2473
W-2474
W-2475
W-2476
W-2477
W-2478
W-2479
W-2480
W-2481
W-2482
W-2483
W-2484
W-2485
W-2486
W-2487
W-2488
W-2489
W-2490
W-2491
W-2492
W-2493
W-2494
W-2495
W-2496
W-2497
W-2498
W-2499
W-2500
W-2501
W-2502
W-2503
W-2504
W-2505
W-2506
W-2507
W-2508
W-2509
W-2510
W-2511
W-2512
W-2513
W-2514
W-2515
W-2516
W-2517
W-2518
W-2519
W-2520
W-2521
W-2522
W-2523
W-2524
W-2525
W-2526
W-2527
W-2528
W-2529
W-2530
W-2531
W-2532
W-2533
W-2534
W-2535
W-2536
W-2537
W-2538
W-2539
W-2540
W-2541
W-2542
W-2543
W-2544
W-2545
W-2546
W-2547
W-2548
W-2549
W-2550
W-2551
W-2552
W-2553
W-2554
W-2555
W-2556
W-2557
W-2558
W-2559
W-2560
W-2561
W-2562
W-2563
W-2564
W-2565
W-2566
W-2567
W-2568
W-2569
W-2570
W-2571
W-2572
W-2573
W-2574
W-2575
W-2576
W-2577
W-2578
W-2579
W-2580
W-2581
W-2582
W-2583
W-2584
W-2585
W-2586
W-2587
W-2588
W-2589
W-2590
W-2591
W-2592
W-2593
W-2594
W-2595
W-2596
W-2597
W-2598
W-2599
W-2600
W-2601
W-2602
W-2603
W-2604
W-2605
W-2606
W-2607
W-2608
W-2609
W-2610
W-2611
W-2612
W-2613
W-2614
W-2615
W-2616
W-2617
W-2618
W-2619
W-2620
W-2621
W-2622
W-2623
W-2624
W-2625
W-2626
W-2627
W-2628
W-2629
W-2630
W-2631
W-2632
W-2633
W-2634
W-2635
W-2636
W-2637
W-2638
W-2639
W-2640
W-2641
W-2642
W-2643
W-2644
W-2645
W-2646
W-2647
W-2648
W-2649
W-2650
W-2651
W-2652
W-2653
W-2654
W-2655
W-2656
W-2657
W-2658
W-2659
W-2660
W-2661
W-2662
W-2663
W-2664
W-2665
W-2666
W-2667
W-2668
W-2669
W-2670
W-2671
W-2672
W-2673
W-2674
W-2675
W-2676
W-2677
W-2678
W-2679
W-2680
W-2681
W-2682
W-2683
W-2684
W-2685
W-2686
W-2687
W-2688
W-2689
W-2690
W-2691
W-2692
W-2693
W-2694
W-2695
W-2696
W-2697
W-2698
W-2699
W-2700
W-2701
W-2702
W-2703
W-2704
W-2705
W-2706
W-2707
W-2708
W-2709
W-2710
W-2711
W-2712
W-2713
W-2714
W-2715
W-2716
W-2717
W-2718
W-2719
W-2720
W-2721
W-2722
W-2723
W-2724
W-2725
W-2726
W-2727
W-2728
W-2729
W-2730
W-2731
W-2732
W-2733
W-2734
W-2735
W-2736
W-2737
W-2738
W-2739
W-2740
W-2741
W-2742
W-2743
W-2744
W-2745
W-2746
W-2747
W-2748
W-2749
W-2750
W-2751
W-2752
W-2753
W-2754
W-2755
W-2756
W-2757
W-2758
W-2759
W-2760
W-2761
W-2762
W-2763
W-2764
W-2765
W-2766
W-2767
W-2768
W-2769
W-2770
W-2771
W-2772
W-2773
W-2774
W-2775
W-2776
W-2777
W-2778
W-2779
W-2780
W-2781
W-2782
W-2783
W-2784
W-2785
W-2786
W-2787
W-2788
W-2789
W-2790
W-2791
W-2792
W-2793
W-2794
W-2795
W-2796
W-2797
W-2798
W-2799
W-2800
W-2801
W-2802
W-2803
W-2804
W-2805
W-2806
W-2807
W-2808
W-2809
W-2810
W-2811
W-2812
W-2813
W-2814
W-2815
W-2816
W-2817
W-2818
W-2819
W-2820
W-2821
W-2822
W-2823
W-2824
W-2825
W-2826
W-2827
W-2828
W-2829
W-2830
W-2831
W-2832
W-2833
W-2834
W-2835
W-2836
W-2837
W-2838
W-2839
W-2840
W-2841
W-2842
W-2843
W-2844
W-2845
W-2846
W-2847
W-2848
W-2849
W-2850
W-2851
W-2852
W-2853
W-2854
W-2855
W-2856
W-2857
W-2858
W-2859
W-2860
W-2861
W-2862
W-2863
W-2864
W-2865
W-2866
W-2867
W-2868
W-2869
W-2870
W-2871
W-2872
W-2873
W-2874
W-2875
W-2876
W-2877
W-2878
W-2879
W-2880
W-2881
W-2882
W-2883
W-2884
W-2885
W-2886
W-2887
W-2888
W-2889
W-2890
W-2891
W-2892
W-2893
W-2894
W-2895
W-2896
W-2897
W-2898
W-2899
W-2900
W-2901
W-2902
W-2903
W-2904
W-2905
W-2906
W-2907
W-2908
W-2909
W-2910
W-2911
W-2912
W-2913
W-2914
W-2915
W-2916
W-2917
W-2918
W-2919
W-2920
W-2921
W-2922
W-2923
W-2924
W-2925
W-2926
W-2927
W-2928
W-2929
W-2930
W-2931
W-2932
W-2933
W-2934
W-2935
W-2936
W-2937
W-2938
W-2939
W-2940
W-2941
W-2942
W-2943
W-2944
W-2945
W-2946
W-2947
W-2948
W-2949
W-2950
W-2951
W-2952
W-2953
W-2954
W-2955
W-2956
W-2957
W-2958
W-2959
W-2960
W-2961
W-2962
W-2963
W-2964
W-2965
W-2966
W-2967
W-2968
W-2969
W-2970
W-2971
W-2972
W-2973
W-2974
W-2975
W-2976
W-2977
W-2978
W-2979
W-2980
W-2981
W-2982
W-2983
W-2984
W-2985
W-2986
W-2987
W-2988
W-2989
W-2990
W-2991
W-2992
W-2993
W-2994
W-2995
W-2996
W-2997
W-2998
W-2999
W-3000
W-3001
W-3002
W-3003
W-3004
W-3005
W-3006
W-3007
W-3008
W-3009
W-3010
W-3011
W-3012
W-3013
W-3014
W-3015
W-3016
W-3017
W-3018
W-3019
W-3020
W-3021
W-3022
W-3023
W-3024
W-3025
W-3026
W-3027
W-3028
W-3029
W-3030
W-3031
W-3032
W-3033
W-3034
W-3035
W-3036
W-3037
W-3038
W-3039
W-3040
W-3041
W-3042
W-3043
W-3044
W-3045
W-3046
W-3047
W-3048
W-3049
W-3050
W-3051
W-3052
W-3053
W-3054
W-3055
W-3056
W-3057
W-3058
W-3059
W-3060
W-3061
W-3062
W-3063
W-3064
W-3065
W-3066
W-3067
W-3068
W-3069
W-3070
W-3071
W-3072
W-3073
W-3074
W-3075
W-3076
W-3077
W-3078
W-3079
W-3080
W-3081
W-3082
W-3083
W-3084
W-3085
W-3086
W-3087
W-3088
W-3089
W-3090
W-3091
W-3092
W-3093
W-3094
W-3095
W-3096
W-3097
W-3098
W-3099
W-3100
W-3101
W-3102
W-3103
W-3104
W-3105
W-3106
W-3107
W-3108
W-3109
W-3110
W-3111
W-3112
W-3113
W-3114
W-3115
W-3116
W-3117
W-3118
W-3119
W-3120
W-3121
W-3122
W-3123
W-3124
W-3125
W-3126
W-3127
W-3128
W-3129
W-3130
W-3131
W-3132
W-3133
W-3134
W-3135
W-3136
W-3137
W-3138
W-3139
W-3140
W-3141
W-3142
W-3143
W-3144
W-3145
W-3146
W-3147
W-3148
W-3149
W-3150
W-3151
W-3152
W-3153
W-3154
W-3155
W-3156
W-3157
W-3158
W-3159
W-3160
W-3161
W-3162
W-3163
W-3164
W-3165
W-3166
W-3167
W-3168
W-3169
W-3170
W-3171
W-3172
W-3173
W-3174
W-3175
W-3176
W-3177
W-3178
W-3179
W-3180
W-3181
W-3182
W-3183
W-3184
W-3185
W-3186
W-3187
W-3188
W-3189
W-3190
W-3191
W-3192
W-3193
W-3194
W-3195
W-3196
W-3197
W-3198
W-3199
W-3200
W-3201
W-3202
W-3203
W-3204
W-3205
W-3206
W-3207
W-3208
W-3209
W-3210
W-3211
W-3212
W-3213
W-3214
W-3215
W-3216
W-3217
W-3218
W-3219
W-3220
W-3221
W-3222
W-3223
W-3224
W-3225
W-3226
W-3227
W-3228
W-3229
W-3230
W-3231
W-3232
W-3233
W-3234
W-3235
W-3236
W-3237
W-3238
W-3239
W-3240
W-3241
W-3242
W-3243
W-3244
W-3245
W-3246
W-3247
W-3248
W-3249
W-3250
W-3251
W-3252
W-3253
W-3254
W-3255
W-3256
W-3257
W-3258
W-3259
W-3260
W-3261
W-3262
W-3263
W-3264
W-3265
W-3266
W-3267
W-3268
W-3269
W-3270
W-3271
W-3272
W-3273
W-3274
W-3275
W-3276
W-3277
W-3278
W-3279
W-3280
W-3281
W-3282
W-3283
W-3284
W-3285
W-3286
W-3287
W-3288
W-3289
W-3290
W-3291
W-3292
W-3293
W-3294
W-3295
W-3296
W-3297
W-3298
W-3299
W-3300
W-3301
W-3302
W-3303
W-3304
W-3305
W-3306
W-3307
W-3308
W-3309
W-3310
W-3311
W-3312
W-3313
W-3314
W-3315
W-3316
W-3317
W-3318
W-3319
W-3320
W-3321
W-3322
W-3323
W-3324
W-3325
W-3326
W-3327
W-3328
W-3329
W-3330
W-3331
W-3332
W-3333
W-3334
W-3335
W-3336
W-3337
W-3338
W-3339
W-3340
W-3341
W-3342
W-3343
W-3344
W-3345
W-3346
W-3347
W-3348
W-3349
W-3350
W-3351
W-3352
W-3353
W-3354
W-3355
W-3356
W-3357
W-3358
W-3359
W-3360
W-3361
W-3362
W-3363
W-3364
W-3365
W-3366
W-3367
W-3368
W-3369
W-3370
W-3371
W-3372
W-3373
W-3374
W-3375
W-3376
W-3377
W-3378
W-3379
W-3380
W-3381
W-3382
W-3383
W-3384
W-3385
W-3386
W-3387
W-3388
W-3389
W-3390
W-3391
W-3392
W-3393
W-3394
W-3395
W-3396
W-3397
W-3398
W-3399
W-3400
W-3401
W-3402
W-3403
W-3404
W-3405
W-3406
W-3407
W-3408
W-3409
W-3410
W-3411
W-3412
W-3413
W-3414
W-3415
W-3416
W-3417
W-3418
W-3419
W-3420
W-3421
W-3422
W-3423
W-3424
W-3425
W-3426
W-3427
W-3428
W-3429
W-3430
W-3431
W-3432
W-3433
W-3434
W-3435
W-3436
W-3437
W-3438
W-3439
W-3440
W-3441
W-3442
W-3443
W-3444
W-3445
W-3446
W-3447
W-3448
W-3449
W-3450
W-3451
W-3452
W-3453
W-3454
W-3455
W-3456
W-3457
W-3458
W-3459
W-3460
W-3461
W-3462
W-3463
W-3464
W-3465
W-3466
W-3467
W-3468
W-3469
W-3470
W-3471
W-3472
W-3473
W-3474
W-3475
W-3476
W-3477
W-3478
W-3479
W-3480
W-3481
W-3482
W-3483
W-3484
W-3485
W-3486
W-3487
W-3488
W-3489
W-3490
W-3491
W-3492
W-3493
W-3494
W-3495
W-3496
W-3497
W-3498
W-3499
W-3500
W-3501
W-3502
W-3503
W-3504
W-3505
W-3506
W-3507
W-3508
W-3509
W-3510
W-3511
W-3512
W-3513
W-3514
W-3515
W-3516
W-3517
W-3518
W-3519
W-3520
W-3521
W-3522
W-3523
W-3524
W-3525
W-3526
W-3527
W-3528
W-3529
W-3530
W-3531
W-3532
W-3533
W-3534
W-3535
W-3536
W-3537
W-3538
W-3539
W-3540
W-3541
W-3542
W-3543
W-3544
W-3545
W-3546
W-3547
W-3548
W-3549
W-3550
W-3551
W-3552
W-3553
W-3554
W-3555
W-3556
W-3557
W-3558
W-3559
W-3560
W-3561
W-3562
W-3563
W-3564
W-3565
W-3566
W-3567
W-3568
W-3569
W-3570
W-3571
W-3572
W-3573
W-3574
W-3575
W-3576
W-3577
W-3578
W-3579
W-3580
W-3581
W-3582
W-3583
W-3584
W-3585
W-3586
W-3587
W-3588
W-3589
W-3590
W-3591
W-3592
W-3593
W-3594
W-3595
W-3596
W-3597
W-3598
W-3599
W-3600
W-3601
W-3602
W-3603
W-3604
W-3605
W-3606
W-3607
W-3608
W-3609
W-3610
W-3611
W-3612
W-3613
W-3614
W-3615
W-3616
W-3617
W-3618
W-3619
W-3620
W-3621
W-3622
W-3623
W-3624
W-3625
W-3626
W-3627
W-3628
W-3629
W-3630
W-3631
W-3632
W-3633
W-3634
W-3635
W-3636
W-3637
W-3638
W-3639
W-3640
W-3641
W-3642
W-3643
W-3644
W-3645
W-3646
W-3647
W-3648
W-3649
W-3650
W-3651
W-3652
W-3653
W-3654
W-3655
W-3656
W-3657
W-3658
W-3659
W-3660
W-3661
W-3

MICROFILMED
SEP 19 1995

FED. RD.	STATE	PROJECT	
	OHIO		

448
492

MAH.-18-17.20

ELEVATION TABLE


ELEV.	A	B	C	D	E	F	G	H	J
PIER 1	952.71	952.68	952.65	952.62	952.48	952.21	951.94	951.68	928.00
PIER 2	955.13	955.10	955.06	955.02	954.94	954.73	954.47	954.01	930.50

NOTES


ALL REINFORCING STEEL TO HAVE A 2" MIN. COVER EXCEPT WHERE OTHERWISE NOTED.

REINFORCING STEEL MUST BE PLACED IN THE PIER CAP SO THAT IT WILL NOT INTERFERE WITH THE BEARING PLATE ANCHOR BARS.


ALL PILES TO BE 12" DIA. CAST IN PLACE REINFORCED CONCRETE PILES.




PLAN



ELEVATION



SECTION A-A



SECTION C-C

SECTION B-B

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS

BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025+08.02

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
FAK	AC		EW	DHC		

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

449/492

MAH-18-17.20


DEFLECTION AND CAMBER TABLE.

LOCATION OF SPAN	56.0' INT.	56.0' EXT.	51.75' INT.	51.75' EXT.	39.50' INT.	37.94' EXT.	41.06' EXT.	9.98' INT.	20.46' INT.	30.93' INT.	41.81' EXT.	24.98 EXT.
DEFLECTION DUE TO WEIGHT OF STEEL	0.066	0.066	0.009	0.009	0.016	0.016	0.021	0.001	0.005	0.015	0.076	0.005
DEFLECTION DUE TO REMAINING DEAD LOAD	0.414	0.824	0.066	0.130	0.113	0.223	0.287	0.040	0.067	0.136	0.691	0.072
CONVEXITY REQUIRED FOR VERTICAL CURVE	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	CONCAVE -0.005	-0.020	-0.023	0.00
SUM OF DEFLECTION AND VERTICAL CURVE.	0.480	0.890	0.075	0.139	0.129	0.239	0.308	0.041	0.067	0.131	0.744	0.077
REQUIRED CAMBER	0"	1"	0"	0"	0"	0"	0"	0"	0"	0"	0"	0"




GEOMETRIC DETAIL
FOR 39'-6" SPAN
(DIMENSIONS IN DECIMALS OF FOOT.)

FRAMING PLAN



BEAM SPLICE DETAILS AT PIER #1



BEAM SPLICE DETAILS AT PIER # 2

BEAM SPLICE WELDING PROCEDURE:

1. RAISE END OF BEAM AT ABUTMENT #1 - 3/8". RAISE END OF BEAM AT ABUTMENT #2 - 3/8".
2. BUTT WELD THE BEAM FLANGES AND WEB USING THE FOLLOWING SEQUENCE: MAKE TWO PASSES ON EACH FLANGE, THAN TWO ON THE WEB; REPEAT USING ONE PASS AT EACH LOCATION UNTIL WELDS ARE COMPLETED.
3. WELD THE BOTTOM AND TOP MOMENT PLATES.
4. LOWER THE BEAM ENDS TO FINAL POSITION.

NOTE: PAINTING - AFTER ERECTION AND AFTER THE SHOP COAT HAS BEEN CLEANED AND WHERE NECESSARY REPAINTED IN ACCORDANCE WITH SEC. 5.04, AN ADDITIONAL COAT OF THE SAME PAINT AS USED IN THE SHOP SHALL BE APPLIED OVER THE OUTSIDE FACE OF THE OUTSIDE STEEL BEAMS AND ALL SIDES OF BOTTOM FLANGE.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING PLAN
BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025+08.02

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
FAH	Hayes		CW	DHC		

MICROFILMED
SEP 19 1965

FED. RD.	STATE	PROJECT	
	OHIO		

450/492

MA H-18-17.20

36WF160

36WF150

DETAIL - "A"

59° 17' 15"

DETAIL - "B"

CENTER OF CURB RADIUS

EDGE OF SLAB

22'-2"

FAN 6 S-706

3 S-602 @ 2'-0"

43'-10" OUTSIDE RADIUS OF SLAB

S-603
S-604
S-605

4'-0" LAP

25 S-606
24 SPA. @ 12" = 24'-0"

℄ WILLIAMS

TRANSVERSE REINFORCING ON SOUTH SIDE

16 SPA. @ 8" = 10'-8"
17 S-707

16 SPA. @ 8" = 10'-8"
17 S-702

96 SPA. @ 8" = 64'-0"
97 S-701

20 SPA. @ 8" = 13'-4"
21 S-708

18 SPA. @ 8" = 12'-0"

19 S-709

3 S-601 @ 2'-0"
2 LENGTHS IN THIS SIDEWALK

3-S-602 @ 2'-0"

LAP VARIES (2'-0" MIN. THIS SIDE)

EDGE OF SLAB

2'-0" MIN. LAP THIS SIDE OF BRIDGE

4'-0" LAP

3'-0" LAP

31 SPA. @ 8" = 20'-8"
32 S-713

15 SPA. @ 8" = 7'-4"
12 S-712

12 SPA. @ 8" = 8'-0"
13 S-711

℄ BEAM

110 S-502 & 110 S-503 IN SIDEWALK THIS SIDE OF BRIDGE - SEE RAILING DRAWING FOR SPACING

FAN 2 S-704

50 SPA. @ 8" = 33'-4"
51 S-703

14 SPA. @ 8" = 9'-4"
15 S-710

20° 31' 44"

23° 23' 27"

59° 17' 15"

10"

2'-4" MIN. LAP

12'-2"

7"

60'-4" O/O OF SLAB

46 SPA. @ 12" = 46'-0"
49 S-601 ACROSS SLAB
4 LENGTHS

LAP VARIES (2'-4" MIN.)

℄ STRUCTURE ℄ RELOCATED WOODLAND AVE.

110 S-502 & 110 S-503 IN SIDEWALK THIS SIDE OF BRIDGE - SEE RAILING DRAWING FOR SPACING

5"

FAN 2 S-705

℄ ABUT. #1 BEARINGS

EDGE OF SLAB

℄ PIER #1

℄ PIER #2

℄ ABUT. #2 BEARINGS

TRANSVERSE REINFORCING ON NORTH SIDE

16 SPA. @ 8" = 10'-8"
17 S-707

136 SPA. @ 8" = 90'-8"
137 S-701

65 SPA. @ 8" = 43'-4"
66 S-702

14 SPA. @ 8" = 9'-4"
15 S-710

3 S-601 @ 2'-0"
4 LENGTHS IN CURB THIS SIDE

BEVEL FILL 1/2" THK. AT ℄ BEAM

C/3 C/3 C/3

1/4" 1/8" 1/4"

45°

PL 3/8" THK.

PL 3/8" THK.

1/4" 1/4" 1/4" 1/4"

ALL L 4x4x5/16"

36"WF-150 OR 36"WF-170

8'-4 1/4" ABUT. #1

8'-2 1/4" ABUT. #2

SECTION "B-B"

END CROSSFRAME (WOODLAND AVE. BEAMS)

3"x3"x5/16" L. WELD BOTH SIDES OF VERTICAL LEG AND ONE SIDE OF HORIZ. LEG TO BEAM WEB WITH 1/4" CONT. FILLET WELD.

1" CLEAR

7'-6"

36"WF-160

30"WF-116

SECTION "C-C"

INTERMEDIATE CROSSFRAME (WILLIAMS)

24"WF-76

1" CLEAR

7'-6"

30"WF-116

SECTION "D-D"

INTERMEDIATE CROSSFRAME (WILLIAMS)

36"WF-150

36"WF-150

1" CLEAR

6'-1"

3"x3"x5/16" L. WELD BOTH SIDES OF VERTICAL LEG AND ONE SIDE OF HORIZONTAL LEG TO BEAM WEB WITH 1/4" CONT. FILLET WELD.

SECTION "G-G"

REINFORCING STEEL IN BOTTOM OF SLAB

1'-4" 1'-6" 1'-4"

9" 9"

1'-6"

S-502

S-501

R-506

6-R-510

4-R-511

43-6298 @ BOT. OF SLAB

63-7/16 @ TOP OF SLAB

4-S-629 TOP OF SIDEWALK

PLAN

1" DIA HALF ROUND DRIP GROOVE

7'-4"

10" 1'-0" 6"

8" 8"

℄ LIGHT STANDARD

℄ HANDRAIL SUPPORT

R-511

R-506

S-502

S-501

S-614

S-601

S-629

S-714

S-609

S-701

S-503

S-633

4-S

SECTION 1-1

1 1/2" ø x 4'-1" ANCHOR BOLT

2'-9"

1'-4"

ANCHOR BOLT DETAIL (8 REQD.)

(INCLUDED IN S-25 FOR PAYMENT)

DETAIL OF LIGHT STANDARD SUPPORT - 2 REQ'D.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SLAB & FRAMING DETAILS

BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025+08.02

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.A.H.	Hoya		E.W.	D.H.C.		

FED. RD.	STATE	PROJECT	
	OHIO		

451
492

MAH-18-17.20

MICROFILMED SEP 19 1955

60'-8" OVERALL

℄ STRUCTURE ℄ RELOCATED WOODLAND AVE.

SEE RAILING DETAIL DRAWING FOR SPACING OF REINFORCING BARS IN PARAPET.

CONCRETE ABOVE THIS POINT TO BE PAID FOR AS PART OF ITEM 5-16 (RAILING)

S-501 @ 1'-4"
S-614 @ 1'-11" OVER PIERS
S-601 @ 1'-11"
S-614 @ 1'-4" OVER PIERS
S-601 @ 1'-4"
S-701 @ 8"
S-609 @ 8"
S-601 @ 12"
S-503 @ 1'-4"
S-502
S-601 @ 2'-0"

SLOPE 3/16"/FT. SLOPE 3/16"/FT.

1" MONOLITHIC WEARING SURF.
7½" SLAB
2" CLEAR
1" CLEAR

24'-0"

THIS IS A NOMINAL DIMENSION. THE QUANTITY OF DECK CONCRETE TO BE PAID FOR SHALL BE BASED ON THIS DIMENSION EVEN THOUGH DEVIATION FROM IT MAY BE NECESSARY BECAUSE OF THE TOP FLANGE OF THE BEAM MAY NOT HAVE THE EXACT CAMBER OR CONFORMATION REQUIRED TO PLACE IT PARALLEL TO GRADE.

1" ϕ ½ ROUND DRIP GROOVE 3"
2'-2½" x 1'-2" GUTTER & SCUPPER SUPPORT 13 SEE C.S.B. 2-56 SHT #3. TYP.
SCUPPER (FOR CONTINUATION OF DOWN SPOUT SEE RAILING AND DRAINAGE SHEET)
3'-4" 7'-8" 7'-8" 7'-8" 7'-8" 7'-8" 7'-8" 7'-8" 3'-4"
3" HAUNCH (TYP.).
2'-10"
36" WF-170 OR 36" WF-150
LEVEL
CONST. JTS. (LEVEL)
1" ϕ ½ ROUND DRIP GROOVE
INSIDE FACE OF PARAPET
SEE SECTION A-A ON RAILING DRAWING

INTERMEDIATE CROSSFRAME ⅄ 3"x3"x5/16". WELD BOTH SIDES OF VERTICAL LEG AND TOP SIDE OF HORIZONTAL LEG TO WEB OF BEAM WITH ¼" CONTINUOUS FILLET WELD.

TRANSVERSE SECTION "A-A"
SHOWING SLAB & INTERMEDIATE CROSSFRAME
(SEE SEC. "C-C" AND "D-D" FOR WILLIAMS ST.)

CENTER OF CURB RADIUS
43'-10" OUTSIDE RADIUS OF SLAB
S-623 S-624 S-625 S-626
FAN 3 S-501
22'-2"
℄ WILLIAMS
17 SPA. @ 1'-4" = 22'-8" 18 S-619
10'-0"
FAN 5 S-627
8 SPA. @ 10'-5" = 83'-4" 9 S-501
S-615 S-616 S-617 S-618
S-620 S-621 S-622 S-623 S-624
CENTER OVER PIER
4'-0"
8 SPA. @ 1'-4" AT CURB LINE 9 S-501
37 SPA. @ APPROX. 1'-4" 38 S-501 LOCATE RADIALLY
25 SPA. @ 1'-4" = 33'-4" 26 S-619
4'-0"
6"
℄ BEAM
NOTE S-610 BARS TO EXTEND 2'-0" BEYOND ℄ BEAM
FAN 3 S-614 OVER PIER
13 S-608
8"
12 SP. @ 8" = 8'-8"
20°31'-44"
59°17'-15"
23°23'-27"
10"
2'-0" LAP
LAP
7"

4 S-601 @ 1'-11" IN TOP OF SIDEWALK (USE 2 LENGTHS AT THIS END OF BRIDGE)
3 S-614 OVER PIER ALT. WITH S-601
FAN 2 S-501
65 SPA. @ 1'-4" = 86'-8" 66 S-501
FAN 2 S-627
8"
14 SPACES @ 8" = 9'-4" 15 S-607
114 SPA. @ 8" = 76'-0" 115 S-609
8"
24 SPA. @ 8" = 16'-0" 25 S-611
8"
65 SPA. @ 8" = 43'-4" 66 S-610
23°23'-27"
2'-0" LAP
℄ RELOCATED WOODLAND
36 SPA. @ 1'-4" = 48'-0" 37 S-601 ACROSS SLAB 4 LENGTHS
60'-4" O/O OF SLAB
10'-8"
7"
4 S-601 @ 1'-11" IN TOP OF SIDEWALK (4 LENGTHS)
1 S-501
39 S-614 @ 1'-4" OVER EACH PIER (ALT. WITH S-601 & STAGGER AS SHOWN)
12'-6" 15'-6" 15'-6" 12'-6" 12'-6" 15'-6" 15'-6" 12'-6"
TRANSVERSE ST. THIS SIDE OF ℄
14 SP. @ 8" = 9'-4" 15 S-607
℄ ABUT. #1 BEARINGS
107 SPA. @ 1'-4" = 142'-8" 108 S-501
℄ PIER #1
189 SPA. @ 8" = 126'-0" ⅄ 190 S-609
℄ PIER #2
13 SP. @ 8" = 8'-8"
12 SP. @ 8" = 8'-0"
14 S-610 13 S-608
℄ ABUT. #2 BEARINGS
FAN 2 S-627
FAN 2 S-501

REINFORCING STEEL IN TOP OF SLAB

SECTION "E-E"
END CROSSFRAME (WILLIAMS ST. BEAMS)

BEVEL FILL ½" THK. AT ℄ BEAMS
C = 9'-7 7/16"
C/3
BEVEL FILL ½" THK. AT ℄ BEAMS
C = 9'-7 7/16"
C' = 9'-10 3/16"
C/3
ℓ 3/8" THK.
MATCH LINE "X"
24" WF-76
ALL ∠ 4"x4"x5/16"
C/2
30" WF-116
36" WF-160

SECTION "F-F"
END CROSSFRAME (WILLIAMS ST. BEAMS)

℄ STRUCTURE

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES
BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

DECK DETAILS
BRIDGE NO. MAH.-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025-08.02


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
FAIL	Hoyer		aw	JHC		


FED. RD.	STATE	PROJECT	
	OHIO		

452
492


MAH.-18-17.20

MICROFILMED
SEP 19 1955






NORTH ELEVATION



SECTION-A-A
(FOR SIDEWALKS ONLY)
(SEE O.S. STD. DWG. # C.S.B.-2-56 SHT. #2 FOR SEC. THRU ROADWAY DAN)



SOUTH ELEVATION

TYPE "C" RAILING. 4" O.D. TOP RAIL, 3½" OD. BOTTOM RAIL, 3/16" WALL ALUMINUM TUBE. RAILING SHALL BE CONTINUOUS THRU FIRST POST AT EACH END OF SUPERSTRUCTURE.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

RAILING & DRAINAGE DETAILS

BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025 + 08.02

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EMK	UNP		EW	DHC		

REINFORCING STEEL SCHEDULE

MARK	NO	LGTH.	WGT.	SHP
WING WALL #1				
SER W-501	1 SET OF 5 - 5 BARS	VARY 5'6 TO 10'2 @ 1'2 INC.	43	ST.
SER. W-502	1 SET OF 8 - 8 BARS	VARY 10'5 TO 14'6 7"	104	ST.
SER. W-503	1 SET OF 5 - 2 BARS	VARY 14'4 TO 19'0 7"	155	ST.
SER. W-504	1 SET OF 8 - 8 BARS	VARY 19'4 TO 23'5 7"	178	ST
W-505	5	5'-1"	27	BT.
W-506	10	7'-3"	76	BT.
W-507	11	21'-6"	247	BT.
W-508	11	12'-6"	143	BT.
W-509	1	19'-0"	20	BT.
W-510	1	10'-0"	10	BT.
W-511	1	14'-4"	15	BT.
W-512	1	5'-4"	6	BT.
W-513	1	9'-8"	10	BT.
W-514	16	10'-2"	270	BT.
W-515	1	5'-0"	5	BT.
W-516	1	4'-10"	5	BT.
W-517				
W-518				
W-519	1	16'-8"	17	BT.
W-520	1	7'-10"	8	BT.
W-521	1	12'-0"	13	BT.
W-522	1	3'-0"	3	BT.
W-523	1	2'-8"	3	BT.
W-524	1	2'-6"	3	BT.
W-525	1	7'-4"	8	BT.
W-526	1	7'-1"	7	BT.
W-527	1	12'-8"	13	BT.
W-528	2	12'-11"	27	BT.
W-529	2	12'-5"	26	BT.
W-530	2	12'-0"	25	BT.
W-531	1	12'-6"	13	BT.
W-532	2	13'-1"	27	BT.
W-533	4	12'-7"	52	BT.
W-534	2	12'-1"	25	BT.
W-535	2	11'-8"	24	BT.
W-536	1	13'-11"	15	BT.
W-537	1	13'-5"	14	BT.
W-538	2	13'-0"	27	BT.
W-539	8	10'-0"	83	BT.
W-540	2	12'-2"	25	BT.
W-541	2	11'-10"	25	BT.
W-542	2	11'-4"	24	BT.
W-543	1	11'-7"	12	BT.
W-544	1	11'-2"	12	BT.
W-545	2	10'-5"	22	BT.
W-546	2	10'-4"	22	BT.
W-547	2	9'-11"	21	BT.
W-548	2	9'-6"	20	BT.
W-549	2	9'-1"	19	BT.
SER W-601	1 SET OF 9 - 9 BARS	VARY 3'7 TO 8'5 @ 7"	81	ST
SER W-602	1 SET OF 8 - 8 BARS	VARY 8'-1 TO 13'-0 7"	132	ST.
SER W-603	1 SET OF 9 - 9 BARS	VARY 8'-3 TO 13'-5 7"	150	ST.
SER. W-604	1 SET OF 8 - 8 BARS	VARY 10'-1 TO 14'-6 7"	152	ST.
W-605	9	7'-4"	99	B.T.
W-606	9	8'-2"	110	B.T.
W-607	12	11'-10"	213	BT.
W-608	9	7'-2"	97	BT.
W-701	16	7'-7"	248	BT.
W-702	18	14'-4"	527	BT
W-703	9	5'-10"	181	BT.
W-704	10	10'-0"	204	BT.
W-801	9	12'-0"	221	B.T

MARK	NO	LGTH.	WGT.	SHP
W-901	8	9'-3"	252	BT.
W-1001	8	15'-6"	534	BT.
W-1002	8	9'-6"	327	BT.
W.W. #1 TOTAL = 5,477				
WING WALL #2				
SER. W-551	1 SET OF 9 - 9 BARS	VARY 21'-3 TO 23'-5	209	ST.
SER. W-552	1 SET OF 9 - 9 BARS	VARY 16'-10 TO 20'-6	173	ST.
SER. W-553	1 SET OF 12 - 12 BARS	VARY 13'-2 TO 16'-0	181	ST.
SER W-554	1 SET OF 11 - 11 BARS	VARY 11'-11 TO 13'-2	144	ST
W-555	1	11'-11"	12	ST.
SER. W-556	1 SET OF 4 - 4 BARS	VARY 5'-0 TO 7'-3	26	ST.
W-557	8	31'-6	253	BT.
W-558	1	23'-9"	25	BT.
W-559	1	17'-3"	18	BT.
W-560	1	12'-0"	13	BT.
W-561	1	3'-6"	4	BT.
W-562	2	22'-6"	47	BT.
W-563	1	25'-10"	27	BT.
W-564	3	28'-2"	88	BT.
W-565	1	5'-6"	6	BT.
W-566	9	22'-4"	210	BT.
W-567	8	9'-6"	79	BT.
W-568	1	17'-4"	18	BT.
W-569	1	12'-1"	13	BT.
W-570	1	3'-9"	4	BT.
W-571	2	16'-3"	34	BT.
W-572	1	18'-10"	20	BT.
W-573	3	21'-6"	67	BT.
W-574	1	5'-4"	6	BT.
W-575	2	20'-1"	42	BT.
W-576	2	21'-1"	44	BT.
W-577	2	22'-0"	46	BT.
W-578	2	23'-0"	48	BT.
W-579	2	23'-11"	50	BT.
W-580	1	24'-11"	26	BT.
W-581	1	25'-10"	27	BT.
W-582	2	14'-10"	31	BT.
W-583	2	16'-5"	34	BT.
W-584	2	17'-1"	36	BT.
W-585	2	17'-9"	37	BT.
W-586	1	18'-4"	19	BT.
W-587	1	18'-5"	19	BT.
W-588	2	16'-2"	34	BT.
W-589	2	16'-10"	35	BT.
W-590	2	17'-5"	36	BT.
W-591	2	18'-1"	38	BT.
W-592	1	18'-8"	19	BT.
W-593	12	10'-0"	130	BT.
W-594	6	7'-4"	46	BT.
SER. W-651	1 SET OF 9 - 9 BARS	VARY 12'-6 TO 14'-8 7/8	252	ST
SER W-652	1 SET OF 9 - 9 BARS	VARY 8'-3 TO 11'-11 @ 5"	136	ST
SER W-653	1 SET OF 12 - 12 BARS	VARY 7'-5 1/2 TO 10'-5 @ 3/8	161	ST
W-654	12	11'-7"	209	ST.
W-655	11	7'-4"	121	BT.
W-656	12	7'-8"	138	BT.
W-657	27	11'-10"	480	BT.
W-658	12	7'-2"	129	BT.
SER W-659	1 SET OF 4 - 4 BARS	VARY 5'-0 TO 7'-3 @ 7/8	37	ST

MARK	NO	LGTH.	WGT.	SHP
W-851	12	12'-0	384	BT
W-951	12	2'-3	377	BT.
W-1051	18	15'-6	1201	BT.
W-1052	18	5'-4	736	BT.
W.W. #2 TOTAL 8599				
ABUTMENT #1				
A-501	6	5'-2"	32	ST
A-502				
A-503	3	8'-5"	26	BT.
A-504	3	8'-2"	26	BT.
A-505	8	31'-5	263	ST.
A-506	48	32'-10	1644	ST.
A-507	34	19'-6"	692	ST.
A-508	48	6'-3"	313	BT.
A-509	28	35'-1"	941	ST
A-510	15	10'-0"	156	ST.
A-511	8	4'-8"	39	ST.
A-512	6	6'-10"	43	BT.
A513 ~ OPEN ~				
A514 ~ OPEN ~				
A-515	15	10'-0	156	BT.
A-601	12	13'-9"	248	BT
A-602	10	10'-6"	158	BT
A-603	66	7'-8"	960	ST
A-604	14	11'-9"	247	BT
A-605 ~ OPEN ~				
A-606 ~ OPEN ~				
A-701	66	16'-5"	3,684	BT.
A-702	66	5'-3"	2076	BT.
A-1001	66	5'-9"	2651	BT
A-1002	66	6'-4"	1799	BT.
ABUT. #1 TOTAL 23,580				
ABUTMENT #2				
A-551	33	38'-11"	1340	ST.
A-552	66	32'-3"	2220	ST.
A-553	31	19'-0"	614	ST.
A-554	22	20'-3"	464	ST
A-555				
A-556	31	36'-0	1164	ST.
A-557	11	38'-0"	436	ST.
A-558	72	6'-3"	469	BT.
A-559	6	5'-2"	32	ST.
A-560				
A-561	3	9'-3"	29	BT.
A-562	3	5'-2"	26	BT.
A563	8	4'-8"	39	ST.
A-564 ~ OPEN ~				
A-565 ~ OPEN ~				
A-566 ~ OPEN ~				
A567 ~ OPEN ~				
A-568	6	6'10"	43	BT
A-569	30	10'-0	313	ST
A-570	15	10'-0"	156	BT.


MARK	NO	LGTH.	WGT.	SHP
A-651	104	8'-0"	1250	ST
A-652				
A-653	13	13'-3"	259	BT.
A-654				
A-655	49	14'-2"	1042	BT.
A-656	43	15'-2"	978	BT.
A-657	31	10'-6"	489	BT
A-658	22	11'-0"	348	BT.
A-659	~ OPEN ~			
A-660	~ OPEN ~			
A-851	104	13'10"	3,481	ST.
A-852	104	10'10"	3,008	ST.
A-853	105	11'-6"	3224	ST.
A-951	104	16'-5"	5,005	BT
A-952	104	9'-3"	3,271	BT.
A-1051	104	9'-4"	4,179	BT.
A-1052	104	6'-4	2,834	BT.
ABUT. #2 TOTAL 37,061				
SUPERSTRUCTURE				
S-501	229	8'-2"	1950	BT.
S-502	235	5'-1"	1245	BT.
S-503	235	2'-2"	531	BT
S-601	386	38'-10"	22,514	ST
S-602	6	45'-0"	405	ST
S-603	2	28'-3"	84	BT
S-604	2	29'-3"	88	BT
S-605	2	30'-4"	91	BT
SER S-606	1 SET OF 25 - 25 BARS	VARY 5'-3 TO 38'-9 @ 1'-4 3/4	825	ST.
SER. S-607	2 SETS OF 15 - 30 BARS	VARY 5'-3 TO 26'-10 @ 1'-4 3/4	723	ST.
SER S-608	2 SETS OF 13 - 26 BARS	VARY 7'-2 TO 28'-5 @ 1'-4 3/4	695	
S-609	305	26'-6"	12,190	ST.
S-610	80	25'-10"	3,585	ST.
SER. S-611	1 SET OF 25 - 25 BARS	VARY 26'-6 TO 30'-6 @ 1'-6	1,061	ST.
SER. S-612	1 SET OF 27 - 27 BARS	VARY 7'-0" TO 29'-4 @ 1'-6	765	ST.
SER S-613	1 SET OF 26 - 26 BARS	VARY 8'-2" TO 30'-0 @ 1'-6	765	ST.
S-614	84	28'-0"	3,532	ST.
S-615	2	28'-3"	84	BT
S-616	2	29'-3"	88	BT
S-617	2	30'-3"	91	BT
S-618	2	31'-3"	94	BT
SER. S-619	1 SET OF 18 - 18 BARS	VARY 7'-12 TO 28'-0 @ 1'-6	624	ST
S-620	1	28'-0"	42	BT
S-621	1	28'-0"	42	BT
S-622	1	28'-0"	42	BT
S-623	2	15'-0"	45	ST.
S-624	2	14'-0"	42	ST
S-625	2	12'-6"	38	ST
S-626	2	11'-0"	33	ST
S-627	10	8'-0"	120	ST.
S-628	4	9'-9"	59	BT
S-629	16	7'-2"	172	ST.
S-701	234	31'-2"	14,907	ST.
S-702	83	29'-0"	4,920	ST.
S-703	51	36'-8"	3,134	ST.
S-704	2	5'-7"	23	ST.
S-705	2	6'-11"	28	ST
S-706	6	6'-0"	25	ST.
SER S-707	2 SETS OF 17 - 34 BARS	VARY 6'-9 TO 31'-5 @ 1'-6	663	ST.


MARK	NO	LGTH.	WGT.	SHP
SER S-708	1 SET OF 21 - 21 BARS	VARY 31'-2 TO 33'-8	1391	ST.
SER S-709	1 SET OF 19 - 19 BARS	VARY 34'-1 TO 40'-5	1447	ST.
SER. S-710	2 SETS OF 15 - 30 BARS	VARY 5'-8 TO 36'-6	1110	ST.
SER. S-711	1 SET OF 13 - 13 BARS	VARY 21'-5 TO 23'-7	392	ST
SER S-712	1 SET OF 12 - 12 BARS	VARY 24'-11 TO 35'-0	735	ST.
SER S-713	1 SET OF 32 - 32 BARS	VARY 7'-0 TO 32'-6	1303	ST
S-714	12	8'-0	196	ST.
SUPER ST. TOTAL 82,932				
PIERS #1 & 2				
P-501	164	8'-4"	1,425	BT.
P-502	112	7'-10"	915	BT.
P-601	8	30'-4"	364	ST.
P-701	28	5'-7"	280	BT.
P-801	8	11-6	246	ST.
P-901	48	10'-2"	3,128	ST.
P-902	48	20'-0"	3,264	ST.
P-903				
P-904	96	6'-7"	2,189	BT
P-905				
P-906				
P-907				
P-1001	64	13'-6"	3718	BT.
P-1002	16	11'-0"	759	ST.
P-1101	16	15'-0"	1275	ST.
P-1102	6	30'-6"	972	ST.
P-1103	12	23'-3"	1482	BT.
P-1104	8	21'-6"	967	ST.
P-1105	8	41'-0"	1743	ST.
P-1106	8	11'-7"	492	ST.
PIERS #1 & 2 TOTAL 23,177				
* RAILING				
R-501	8	13'-4"		ST.
R-502	28	16'10"		ST.
R-503	8	13'-11"		ST.
R-504	16	17'-6"		ST.
R-505	4	17'-6"		BT.
R-506	4	17'-6"		BT.
R-507	4	17'-6"		BT.
R-508				
R-509	16	4'7"		ST.
R-510	12	10'-4"		BT.
R-511	8	8'-8"		BT
RAILING TOTAL				
REPLACEMENT BARS				
RE-401	1	5'-3"	SPIRAL	BT.
RE-501	2	5'7"		ST.
RE-601	3	5'-11"		ST.
RE-701	2	6'-3"		ST.
RE-801	1	6'-6"		ST.
RE-901	2	7'-0"		ST.
RE-1001	1	7'-3"		ST.
RE-1101	1	7'-6"		ST.


SPIRAL REINFORCING LIST.

MARK	NO.	CORE DIA OF SPIRAL	LGTH	PITCH	NO OF TURNS	WEIGHT
SP-401	4	2'-8"	16'-2	4½	46	1013
SP-402	4	2'-8"	17'-0"	4½	48	1058
SPACERS	32					361


GRAND TOTAL 183,258 #










A-504





A-503





























SPIRAL REINFORCING NOTES

THE LENGTH SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE DISTANCE FROM THE TOP OF THE FOOTING TO BOTTOM OF THE PIER CAP.
THE NUMBER OF TURNS SHOWN IN THE STEEL LIST FOR SPIRAL BARS IS THE LENGTH DIVIDED BY THE PITCH PLUS THREE TURNS (TOTAL NUMBER OF CLOSED COILS) EXPRESSED AS THE NEAREST WHOLE NUMBER.
SPIRAL REINFORCING BARS SHALL NOT HAVE DEFORMATIONS BUT SHALL IN OTHER RESPECTS CONFORM TO ITEM S-4
ONE AND ONE HALF CLOSED COILS SHALL BE PROVIDED AT THE ENDS OF EACH SPIRAL UNIT. FOUR 4 STEEL CHANNEL, TEE, OR ANGLE SPACERS WEIGHING APPROX. 0.68 LBS. PER LINEAL FT. OF SPACERS SHALL BE PROVIDED FOR EACH SPIRAL UNIT. THEY SHALL BE EQUALLY SPACED ALONG THE PERIPHERY OF EACH COIL. THE NUMBER OF POUNDS OF THESE SPACERS BASED ON 0.68 LBS. PER LINEAL FT. WILL BE PAID FOR AS REINFORCING STEEL AND IS INCLUDED IN THE TABULATED QUANTITY OF SPIRAL BARS.
BAR SIZE IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE THREE DIGITS ARE USED AND THE FIRST TWO DIGITS WHERE FOUR ARE USED INDICATE THE BAR SIZE NUMBER FOR EXAMPLE A-700 IS A NO 7 SIZE BAR AND A-1014 IS A NO 10 SIZE BAR.
REPLACEMENT BARS: IF REINFORCING BARS ARE FABRICATED FROM STOCK WHICH HAS PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SECTION S-4.02 NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.
* RAILING REINFORCEMENT BARS WILL BE INCLUDED AS PART OF ITEM S-14 FOR PAYMENT

MARK	RADIUS	MARK	RADIUS
RE-401	1'-3½	W-544	52'-7
R-506	44'-4"	W-545	50'-7
S-620	44'-10½	W-546	48'-7
S-621	46'-9½	W-547	46'-7
S-622	48'-8½	W-548	44'-7"
W-507	49'-10	W-549	42'-7"
W-508	48'-5	W-557	49'-0"
W-509	49'10	W-558	49'-10"
W-510	48'-5	W-559	49'-10"
W-511	49'-10	W-560	49'-10"
W-512	48'-5	W-561	49'-10"
W-513	49'-10	W-562	49'-10"
W-514	48'-4	W-563	49'-10"
W-515	49'10	W-564	49'-10"
W-516	48'-4	W-565	49'-10"
		W-566	47'-11"
		W-567	48'-4"
W-519	49'-10	W-568	48'-9"
W-520	48'-2	W-569	48'-9"
W-521	49'-10	W-570	48'-9"
W-522	48'-2	W-571	48'-1"
W-523	49'-10	W-572	48'-3"
W-524	48'-1	W-573	48'-7"
W-525	49'-10	W-574	48'-9"
W-526	48'-1	W-575	48'-7"
W-527	51'-7	W-576	48'-7"
W-528	49'-10	W-577	46'-7"
W-529	47'-10	W-578	48'-7"
W-530	46'-2	W-579	50'-7"
W-531	52'-7	W-580	52'-7"
W-532	50'-7	W-581	52'-7"
W-533	48'-7	W-582	53'-8"
W-534	46'-7	W-583	45'-8"
W-535	44'-11	W-584	47'-8"
W-536	53'-7	W-585	49'-8"
W-537	51'-7	W-586	51'-8"
W-538	50'-1	W-587	53'-8"
W-539	OPEN	W-588	44'-9"
W-540	47'-1"	W-589	46'-9"
W-541	45'-7	W-590	48'-9"
W-542	43'-5	W-591	50'-9"
W-543	54'-7	W-592	52'-9"
		W-593	50'-0"
		W-594	48'-4"

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

REINFORCING SCHEDULE

BRIDGE NO. MAH-18-1941
UNDER WOODLAND AVE.
YOUNGSTOWN, MAHONING COUNTY
STA. 1025+08.02

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
EAK	JNP		aw	DHL		

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

453
492

MICROFILMED
SEP 19 1985

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

454
492

MAH-18-17.20

FIRESTONE TIRE AND RUBBER CO. STORE

EXCEL AUTO GLASS STORE & WAREHOUSE

PARKING AREA

Y.E. CURVE DATA
Δ = 53°45'25" Lt
D_c = 5°45'
R_c = 996.45'
L_s = 400'
Θ_s = 11°30'
L_c = 536.06'
T_s = 706.91'
E_s = 128.51'

EL. 944.87

STA. 50+58.16
EL. 946.46

EL. 919.00

REQD. MIN. CLEAR. = 15.00'
ACTUAL MIN. CLEAR = 15.12'

EL. 923.00 RT. PIER
EL. 925.25 LT. PIER

BRIDGE LIMITS 138.82'

EL. 948.75

EL. 951.85

EL. 952.63

EL. 925.50

RETAINING WALL

MIN. CLEAR.

3'-6"

VARIES

3+00

1028+00

1029+00 ℄ MARKET ST.

D_c = 5°45'

82°38'50"

9°43'37"

4°51'37"

7°21'10"

1°14'36"

83°53'47"

℄ PIER

℄ PIER

LOCAL TANGENT AT ℄ MARKET ST.

STA. 1030+29.49 = SR-18 ST. 50+00 - MARKET ST.

DETAIL "A"

CURB

RAMP "K"

15+00

4:1

PROP. GD. -2.85%

STA. 49+20.19

STA. 15+82.30

℄ PIER

STA. 1030+50

P.C.C. STA. 1030+50

MAIN CONDUIT - 6' MTD.

BEGIN APPROACH SLAB STA. 50+59.01

8" CLAY BRICK

5+00

6" GAS

6" GAS

944

948

952

954

956

SEE DETAIL A

82°38'50"

50+00

1030+00

1030+29.49

7°21'-10"

85°53'47"

℄ PIER, MIN. CLEARANCE

6°06'13"

83°53'47"

EXPANSION JOINT

5+00

7°26'10"

47'-0"

10.2'

MIN. CLEAR

6+00

7+00

RAMP "M"

18'

CURB

RETAINING WALL

EXISTING PARKING AREA

958

960

30' MIN.

ECONOMY ELECTRIC COMPANY

2:1

DECELERATION LANE (RAMP "N")

CURB

10.17'

MIN. CLEAR

℄ WEST BOUND LANES

℄ SURVEY OF STATE ROUTE #18

1033+00

℄ EAST BOUND LANES

1032+00

1031+00

4°-51'-37"

1°-14'-36"

END APPROACH SLAB STA. 49+20.19

℄ MARKET STREET

49+00 M.H.

48" CONCRETE PIPE RELOCATED SEWER

30'-0"

68' EXIST. ROAD

FOUNDATION SOUNDINGS:

FOUNDATION DESIGN & FOUNDATION QUANTITIES ARE BASED ON A STUDY OF SOIL-SAMPLING SOUNDINGS MADE AT THE SITE. THIS SOUNDING INFORMATION MAY BE INSPECTED IN THE OFFICE OF THE BUREAU OF BRIDGES IN COLUMBUS OR IN THE DIVISION OFFICE BUT THE STATE DOES NOT GUARANTEE THE ACCURACY THEREOF.

AVERAGE ESTIMATED PAY LENGTH FOR PIER AREA = 25 FEET.

13' 34' 34' 13'

TYPICAL SECTION EXISTING MARKET ST.

970 / 950 / 930 / 910

932.09 | 931.01 | 929.74 | 928.50 | 927.50

PVT STA. 1030+00

REQD. MIN. CLEARANCE = 15.00'
ACTUAL MIN. CLEAR. 15.12'

-2.72 % PROPOSED GRADE

48" RELOCATED SEWER

+3.26% GRADE PVI STA. 1028+00 -2.72% GRADE
800' V.C. EL. 940.82

-2.72% GRADE PVI STA. 1033+00 +3.00% GRADE
600' V.C. EL. 921.58

1029+00 | 1030+00 | 1031+00

PROPOSED STRUCTURE

TYPE: CONTINUOUS STEEL BEAM WITH REINFORCED CONCRETE DECK & SUBSTRUCTURE.
SPANS: 77'-6"-56'-9" c/c BRGS. ALONG ℄
ROADWAY: 68'-0" F/F 12' SIDEWALKS
LOAD FREQUENCY: 2000 C.F.(57) ADEQUATE FOR AASHO ALTERNATE LOADING
WEARING SURFACE: 1" MONOLITHIC
APPROACH SLAB: 25' LONG AS I-54
ALIGNMENT: TANGENT.
SUPERELEVATION: NONE
SKEW: VARIES
TRAFFIC COUNT: 64,000 ADT 1979

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SITE PLAN

BRIDGE Nº MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN MAHONING COUNTY
STA. 1030+29.49


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
P.D.H.	D.G.S.		D.G.S.			

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		


MA H-18-17.20

455/492



PLAN

ELECTRICAL GROUNDS: A SOLID N°0 GAGE BARE COPPER WIRE ELECTRICAL GROUND SHALL BE EMBEDDED IN THE OUTSIDE COLUMN ON EACH SIDE OF THE STRUCTURE AT THE PIER. THE LOWER ENDS OF THE WIRES SHALL BE BRAZED TO THE STEEL SHELL OF ONE OF THE CAST-IN-PLACE CONCRETE PILES AND THE UPPER ENDS SHALL EXTEND SUFFICIENTLY ABOVE THE TOP OF THE CONCRETE TO PROVIDE FOR A SUITABLE SPLICE AND EXTENSION FOR CONNECTION TO THE SUPERSTRUCTURE. THE CONNECTION TO THE SUPERSTRUCTURE SHALL BE AN N°6 GAGE BARE, STRANDED, TINNED COPPER WIRE BRAZED OR BOLTED TO A BEAM FLANGE AND TO THE SOLID COPPER WIRE IN THE PIER SHAFT.
PAYMENT FOR ELECTRICAL GROUNDS IS INCLUDED IN THE LUMP SUM BID FOR ITEM S-25 "ELECTRICAL LIGHTING SYSTEM."



ELEVATION

MACHINE FINISH: The concrete bridge deck shall be finished as specified in the Proposal Note, "Machine Finishing of Bridge Deck Slabs."

GENERAL NOTES

DESIGN SPECIFICATONS: THIS STRUCTURE CONFORMS TO THE REQUIREMENTS OF "DESIGN SPECIFICATIONS FOR HIGHWAY STRUCTURES" OF THE STATE OF OHIO, DEPARTMENT OF HIGHWAYS, DATED 9-1-57, AND CURRENT REVISIONS THERE OF.

WELDING OF STRUCTURAL STEEL: SHALL BE CLASS "A" EXCEPT AS OTHERWISE SHOWN. ANY WELDS SHOWN AS FIELD WELDS MAY, AT THE OPTION OF THE CONTRACTOR, BE MADE IN THE SHOP.

DOWNSPOUTS: SHALL BE 6" Φ GALV. ST. OR W.I. PIPE. ITEM S-29 (DOWNSPOUTS INCLUDES PIPE & INCIDENTALS BELOW LIMITS SHOWN ON RAILING & DRAINAGE DETAILS.

SCUPPERS: ITEM S-29 SCUPPERS INCLUDES 6" Φ GALV. ST. OR W.I. PIPE & INCIDENTALS ABOVE LIMITS SHOWN ON RAILING & DRAINAGE DETAILS. METAL GUTTERS ARE INCLUDED IN ITEM S-7 FOR PAYMENT.

UTILITY LINES: ALL LABOR AND EXPENSE INVOLVED IN RELOCATING THE AFFECTED UTILITY LINES SHALL BE BORNE BY THE OWNERS. THE CONTRACTOR AND OWNERS ARE REQUESTED TO COOPERATE BY ARRANGING THIER WORK IN SUCH A MANNER THAT INCONVENIENCE TO EITHER WILL BE HELD TO A MINIMUM.

REFERENCE SHALL BE MADE TO STD. DRAWINGS; AR-1-57, DATED 2-2-59, CSB-2-56, REV. 2-2-59 SHTS. 2 & 3, & SUPPLEMENTAL SPECIFICATION S-101, DATED 12-2-59.

EXCAVATION QUANTITY: INCLUDES THE REMOVAL OF MATERIAL BETWEEN THE SURFACE OF THE PROPOSED GRADE AND THE BOTTOM OF ABUTMENTS.

POROUS BACKFILL, 2 FT. THICK, FULL LENGTH OF ABUTMENTS AND WINGS SHALL EXTEND UP TO THE UNDERSIDE OF THE APPROACH SLAB OR TO THE FINISHED GROUND SURFACE.

ALL PILES SHALL BE 12" CAST-IN-PLACE REINFORCED CONCRETE PILES DRIVEN TO A MINIMUM BEARING CAPACITY OF 40 TONS.

ESTIMATED QUANTITIES

ITEM	TOTAL	UNIT	DESCRIPTION	SUPERST.	ABUTS.	PIERS	GEN.
E-2	2,638	CU. YDS.	UNCLASSIFIED EXCAVATION		2,465	173	
S-1	500	CU. YDS.	CLASS "C" CONC. SUPERSTRUCTURE	500			
S-1	478	CU. YDS.	CLASS "E" CONC. ABUTS. & WINGWALLS ABOVE FTGS		478		
S-1	58	CU. YDS.	CLASS "C" CONC. PIERS ABOVE FOOTINGS			58	
S-1	440	CU. YDS.	CLASS "E" CONC. ABUT., WINGWALL, & PIER FTGS.		369	71	
S-3	27	SQ. YDS.	TYPE "B" WATERPROOFING		27		
S-3	50	LIN. FT.	12" x ½" PREMOLDED SEALING STRIP		50		
S-4	209,476	LBS.	REINFORCING STEEL	107,136	74,661	27,679	
S-7	462,293	LBS.	STRUCTURAL STEEL	462,293			
S-8	462,293	LBS.	FIELD PAINTING OF STR. ST., AS PER PLAN	462,293			
S-9	130	SQ. FT.	1" x 10" PREFORMED EXPANSION JOINT FILLER	130			
S-9	98	SQ. FT.	1" PREFORMED EXPANSION JOINT FILLER		98		
S-9	136	LIN. FT.	FOLDED COPPER STRIP (12" WIDE, 16 OZ.)	136			
S-14	292	LIN. FT.	RAILING (ALUM. RAIL AND SUPPORTS - CONCRETE PARAPET - REINFORCING STEEL)	272	20		
S-16	LUMP	SUM	FIRST TEST PILE				
S-18	4,250	LIN. FT.	12" Φ CAST-IN-PLACE REINFORCED CONC. PILES		3200	1050	
S-25	LUMP	SUM	ELECTRICAL LIGHTING SYSTEM	LUMP			
S-29	305	CU. YDS.	POROUS BACKFILL		305		
S-29	72	LIN. FT.	8" C.M.P. INCLUDING SPECIALS		72		
S-29	8	EACH	SCUPPERS	8			
S-29	100	LIN. FT.	6" STANDARD PIPE DOWNSPOUTS, GALV. ST. OR W.I., INCLUDING SPECIALS.				100
E-2	LUMP	SUM	COFFERDAMS, CRIBS & SHEETING				LUMP

PAINTING: AFTER ERECTION & AFTER THE SHOP COAT HAS BEEN CLEANED AND WHERE NECESSARY REPAINTED IN ACCORDANCE WITH SEC. 604 AN ADDITIONAL COAT OF THE SAME PAINT AS USED IN THE SHOP SHALL BE APPLIED OVER OUTSIDE FACE OF OUTSIDE STEEL BEAMS AND ALL SIDES OF BOTTOM FLANGES.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

GENERAL PLAN ELEVATION

BRIDGE NO. MAH-18-1050
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+20.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	R.D.H		D.H.C.			

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MAH - 18 - 17.20

456
492

68'-0" F/F OF SIDEWALKS

34'-0" 34'-0"

13'-2" 11'-10" 2" 2" 1'-8" 2" 2" 11'-10" 13'-2"

12°-33'-50" SKEW

℄ TELEPHONE CONDUITS

℄ ROW #3

2-A507 2-A507

7 SPA. @ 11"

2'-6"

5'-0" 4'-11" 1" 4'-11" 5'-0"

A513 A520 A521

G-A501 UNDER EACH BEAM - SPC. @ 4" ± TO CLEAR ANCHOR BOLTS

1'-6" 1'-6"

℄ ROW #2

℄ ROW #1

2 SPACES @ 16'-0" = 32'-0" 3" PIPE OUTLETS 8'-0" 8'-0" 2 SPACES @ 16'-0" = 32'-0" 3" PIPE OUTLETS

3'-9⅞" 4'-10⅛"

4'-9" 12 BEARING SEATS @ 8'-0⅝" = 88'-3⅜" 3'-11⅝"

48'-3½" CONTRACTION JOINT 48'-3½"

96'-7"

℄ SUBSTRUCTURE ℄ SURVEY MARKET ST.

℄ RELOC. SEWER 30'-0"

PLAN

10¼" 11 SPACES @ 1'-1" = 11'-11" A606 1'-1" 31 SPACES @ 1'-1" = 33'-7" A605 10¼"

EAST EL. 950.62

EL. 951.55* EL. 951.79* EL. 950.22 EL. 950.97*

TELEPHONE CONDUITS

WEST EL. 949.83

EL. 947.64 EL. 947.58 EL. 947.61 EL. 947.67 EL. 947.72 EL. 947.78 EL. 947.71 EL. 947.52 EL. 947.14 EL. 947.33 EL. 946.97 EL. 946.90

7"

A516 VARIES 8 SPACES @ 2'-0" = 16'-0"

10¼" 43 SPACES @ 1'-1" = 46'-7" A601

10¼" 43 SPACES @ 1'-1" = 46'-7" A514 (BACK)

RUSTICATION GROOVES 11 SPACES @ 4'-0" = 44'-0" 4'-3½"

CONTRACTION JOINT

ALL REINFORCING STEEL BARS & SPACING SYMMETRICAL ABOUT CONTRACTION JOINT UNLESS OTHERWISE NOTED.

1'-1¾" 23 SPACES @ 2'-0" = 46'-0" A515 (FRONT)

10¼" 43 SPACES @ 1'-1" = 46'-7" A1102 (BACK)

3¾" 44 SPACES @ 1'-1" = 47'-8" A701 (BACK)

3¾" 44 SPACES @ 1'-1" = 47'-8" A1101 (BACK)

10'-0" 12'-0" 12'-0"

4" ϕ WEEP HOLES

1'-9" MIN. TYP.

3'-0" 3¾" 44 SPACES @ 1'-1" = 47'-8" A602 (TOP)

A516 A517 A512 A516 A516 A1001 A512

5'-0" 3'-0"

21 SPCS. @ 1'-3" = 12'-3"

EL. 925.50

PILE SPC. FOR ROW #3	3'-11½"	4'-1½"	16'-4¾"	4'-9¾"	6'-4"	6'-4"	6'-4"	6'-4"	6'-4"	6'-4"	6'-4"	6'-4"	6'-4"	6'-4"	6'-4"	6'-4"	3'-11½"				
PILE SPC. FOR ROW #2	3'-3½"	3'-3½"	3'-3½"	16'-4¾"	3'-0¼"	3'-0"	3'-0"	3'-0"	5'-0"	5'-0"	5'-0"	5'-0"	5'-0"	5'-0"	5'-0"	5'-0"	5'-0"	5'-0"	5'-0"	3'-3½"	
PILE SPC. FOR ROW #1	3'-3½"	3'-3½"	4'-2¼"	16'-4¾"	5'-1½"	3'-0"	3'-0"	11 SPACES @ 5'-0" = 55'-0"												3'-3½"	

ELEVATION

* ELEVATIONS GIVEN TO FINISHED GRADE AT FACE OF ABUTMENT BACKWALL

NOTES:

FOR DETAILS NOT SHOWN SEE SHT 458

ALL PILES SHALL BE 12" CAST-IN-PLACE CONCRETE WITH 40 TON BEARING CAPACITY.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 PLAN & ELEVATION

BRIDGE NO. MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	R.D.H.		O.H.C.			

5/10

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

456A
4/12

68'-0" F/F OF SIDEWALKS

34'-0" | 34'-0"

12°-33'-50" SKEW

4 TELEPHONE CONDUITS

13'-2" | 11'-10" | 2" | 1'-0"

2" | 13'-2" | 11'-10" | 1'-0" | 2"

℄ ROW #3

℄ ROW #2

℄ ROW #1

2-A507

2-A507

3 SPA. @ 11"

2'-6"

5'-0" | 4'-11"

4'-11" | 5'-0"

A513

A520

A521

A513

6-A501 UNDER EACH BEAM - SPC. @ 4" ± TO CLEAR ANCHOR BOLTS

1'-6" | 1'-6"

2 SPACES @ 16'-0" = 32'-0" 3" PIPE OUTLETS

8'-0"

8'-0"

2 SPACES @ 16'-0" = 32'-0" 3" PIPE OUTLETS

3'-9⅞"

4'-10⅛"

4'-9"

12 BEARING SEATS @ 8'-0⅝" = 88'-3⅜"

48'-3½"

CONTRACTION JOINT 3"

48'-3½"

3'-11⅜"

96'-7"

℄ SUBSTRUCTURE

℄ SURVEY MARKET ST.

℄ RELOC. SEWER

30'-0"

PLAN

℄ PROP. 48" COMB. SEW.

10⅛" | 11 SPACES @ 1'-1" = 11'-11" A606 | 1'-6"

31 SPACES @ 1'-1" = 33'-7" A605

10⅛"

A

F

TELEPHONE CONDUITS

EAST
EL. 950.62

EL. 951.55*

EL. 951.79*

EL. 950.22

EL. 950.97*

WEST
EL. 949.85

EL. 947.14

7"

EL. 947.64 | EL. 947.58 | EL. 947.61 | EL. 947.67 | EL. 947.74 | EL. 947.78 | EL. 947.71 | EL. 947.52 | EL. 947.33 | EL. 946.97 | EL. 946.90

A516

8 SPACES @ 2'-0" = 16'-0"

W 8 | 35

10⅛" | 43 SPACES @ 1'-1" = 46'-7" A601

10⅛" | 43 SPACES @ 1'-1" = 46'-7" A514 (BACK)

10¼"

10¼"

RUSTICATION GROOVES 11 SPACES @ 4'-0" = 44'-0"

4'-3½"

CONTRACTION JOINT

ALL REINFORCING STEEL BARS & SPACING SYMMETRICAL ABOUT CONTRACTION JOINT UNLESS OTHERWISE NOTED.

23	SPACES @ 2'-0" = 46'-0"	A515	(FRONT)
43	SPACES @ 1'-1" = 46'-7"	A1102	(BACK)
44	SPACES @ 1'-1" = 47'-8"	A701	(BACK)
44	SPACES @ 1'-1" = 47'-8"	A1101	(BACK)

1'-1¾" | 10½" | 3½" | 3⅜"

1'-1¾" | 10¼" | 3¾" | 3¾"

10'-0" | 12'-0" | 12'-0"

4" ℄ WEEP HOLES

1'-6" MIN. TYP.

3'-0"

3'-0"

44 SPACES @ 1'-1" = 47'-8" A602 (TOP)

A516 | A517 | A512 | A516 | A516 | A1001 | A512

5'-0" | 5'-0"

EL. 925.50

5 SPACES 2'-1" 10'-5"

PILE SPC. FOR ROW #3 | 3'-1½" | 4'-1½" | 16'-4½" | 3 SPACES 6'-0" 18'-0" | 8'-9" | 7 SPACES 5'-11"-41'-5"

PILE SPC. FOR ROW #2 | 3'-3½" | 3'-3½" | 3'-3½" | 16'-5" | 6 SPACES 3'-0" 18'-0" | 8'-10" | 5'-9" | 7 SPACES 5'-11" 34'-5"

PILE SPC. FOR ROW #1 | 3'-3½" | 3'-3½" | 4'-2½" | 16'-1½" | 5'-1½" | 5 SPACES 3'-0" 9'-0" | 4'-5" | 4'-5"

3'-11½"

3'-3½"

3'-3½"

A

ELEVATION

* ELEVATION GIVEN TO FINISHED GRADE AT FACE OF ABUTMENT BEYOND
** A-1001 SLANTED BETWEEN PILES

NOTES:

FOR DETAILS NOT SHOWN SEE SHT 458

ALL PILES SHALL BE 12" CAST-IN-PLACE CONCRETE WITH 40 TON BEARING CAPACITY.

MINIMUM CLEAR DISTANCE BETWEEN REINFORCING STEEL BARS IN THE FOOTING IS 2½".

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 PLAN & ELEVATION

BRIDGE NO. MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	E.D.H.		D.H.C.			

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

457
492

68'-0" F/F SIDEWALKS

13'-2" | 2" | 34'-0" | 34'-0" | 2" | 11'-10" | 1'-6" 2"

TELEPHONE CONDUITS

6°-28'-17" SKEW

℄ ROW #3

℄ ROW #2

℄ ROW #1

C

D

A513
A510

A510

A513

5'-0" | 4'-11" | 1" | 4'-11" | 5'-0"

6-A501 UNDER EACH BEAM - SPC. @ 4" ± TO CLEAR ANCHOR BOLTS

1'-6" 1'-6"

2 SPACES @ 16'-0" = 32'-0" 3" PIPE OUTLETS | 8'-0" | 8'-0" | 2 SPACES @ 16'-0" = 32'-0" 3" PIPE OUTLETS

3'-9⅛" | 3'-11⅝"

4'-0⅞" | 47'-4⅞" | 12 BEARING SEATS | 11 SPCS. @ 7'-10⅝" = 86'-8⅝" | 47'-4⅞" | 4'-0"

CONTRACTION JOINT 1⅜"

94'-9¾"

℄ SUBSTRUCTURE

℄ SURVEY MARKET ST.

PLAN

30'-0"

℄ RELOC. SEWER

11¾" | 10 SPACES @ 1'-1" = 10'-10" A606 | 1'-1" | 31 SPACES @ 1'-1" = 33'-7" A605 | 11½"

NORMAL TO CURB 7 SPA. @ 11" | 2'-6"

TELEPHONE CONDUITS

WEST EL. 944.96

EL. 945.82*

EL. 941.91

EL. 941.88

EL. 944.79

EL. 946.50*

EL. 946.12*

EAST EL. 945.16

EL. 942.05 | EL. 942.21 | EL. 942.37 | EL. 942.52 | EL. 942.56 | EL. 942.47 | EL. 942.38 | EL. 942.29 | EL. 942.22 | EL. 942.26

A

B

VARIES

A504 — 9 SPACES @ 2'-0" = 18'-0"

8"

3'-0"

11¾" 42 SPACES @ 1'-1" = 45'-6" A601

11¾" 42 SPACES @ 1'-1" = 45'-6" A502 (BACK)

8¾" 23 SPACES @ 2'-0" = 46'-0" A503 (FRONT)

11¾" 42 SPACES @ 1'-1" = 45'-6" A1102 (BACK)

4⅞" 43 SPACES @ 1'-1" = 46'-7" A701 (BACK)

4⅞" 43 SPACES @ 1'-1" = 46'-7" A1101 (BACK)

4⅞" 43 SPACES @ 1'-1" = 46'-7" A602 (TOP)

11½" RUSTICATION GROOVES 11 SPACES @ 4'-0" = 44'-0" 3'-4⅞"

11½" CONTRACTION JOINT

B

E

E

ALL REINFORCING STEEL BARS AND SPACING SYMMETRICAL ABOUT CONTRACTION JOINT UNLESS OTHERWISE NOTED.

8½" 10'-0" | 12'-0" | 12'-0"

5" 4" Φ WEEP HOLES

1'-6" MIN TYP.

A504 | A1001 | A511 | A512 | A504 | A504 | A512

5'-0" | 5'-0"

EL. 919.00

23 SPCS. @ 7" = 13'-5"

PILE SPC. FOR ROW #3 3'-0⅞" | 6'-4" | 6'-4" | 6'-4" | 6'-4" | 6'-4" | 6'-4" | 6'-4" | 6'-4" | 6'-4" | 6'-4" | 4'-4" | 4'-6¾" | 16'-1¼" | 6'-8" | 3'-0⅞"

PILE SPC. FOR ROW #2 2'-4⅞" | 5'-0" | 5'-0" | 5'-0" | 5'-0" | 5'-0" | 5'-0" | 5'-0" | 5'-0" | 5'-0" | 5'-0" | 5'-0" | 3'-9" | 3'-8½" | 16'-1¼" | 3'-5¼" | 3'-0" | 2'-4⅞"

PILE SPC. FOR ROW #1 2'-4⅞" | 12 SPACES @ 5'-0" = 60'-0" | 3'-9" | 4'-2" | 16'-1¼" | 2'-11¾" | 3'-0" | 2'-4⅞"

ELEVATION

*ELEVATIONS GIVEN TO FINISHED GRADE AT FACE OF ABUTMENT BACKWALL

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #2 PLAN & ELEVATION

BRIDGE NO. MAH-18-1050
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030 + 29.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	RDH		D.H.C.			

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

457A
417

6/10

68'-0" F/F SIDEWALKS

13'-2" | 2" | 34'-0" | 34'-0" | 2" | 11'-10" | 1'-6" | 2"

2'-0" | 11'-10" | TELEPHONE CONDUITS | 6°-28'-17" SKEW

5'-0" | 4'-11" | 4'-11" | 5'-0"

A513 | A510 | A510 | A513

6-A501 UNDER EACH BEAM - SPC. @ 4" ± TO CLEAR ANCHOR BOLTS

2 SPACES @ 16'-0" = 32'-0" 3" PIPE OUTLETS | 8'-0" | 8'-0" | 2 SPACES @ 16'-0" = 32'-0" 3" PIPE OUTLETS

1'-6" | 1'-6"

℄ ROW #3 | ℄ ROW #2 | ℄ ROW #1

4'-0⅞" | 47'-4⅞" | 12 BEARING SEATS @ 7'-10⅝" = 86'-8⅝" | 47'-4⅞" | 4'-0"

3'-9 15/16" | 3'-11 7/16" | 1½" | CONTRACTION JOINT

94'-9¾"

℄ SUBSTRUCTURE | ℄ SURVEY MARKET ST.

PROP. 48" COMB. SEW.

PLAN

30'-0"

℄ RELOC. SEWER

11⅜" | 10 SPACES @ 1'-1" = 10'-10" | 1'-1" | A606 | 31 SPACES @ 1'-1" = 33'-7" A605 | 11½"

NORMAL 10 CURB | 7 SPA. @ 11" | 2'-6" | TELEPHONE CONDUITS

WEST EL. 944.96

EL. 945.82* | EL. 944.79 | EL. 946.50* | EL. 946.12* | EAST EL. 945.16

EL. 941.91 | EL. 941.88 | EL. 942.05 | EL. 942.21 | EL. 942.37 | EL. 942.52 | EL. 942.56 | EL. 942.47 | EL. 942.38 | EL. 942.29 | EL. 942.22 | EL. 942.26

VARIES | 11⅜" | 42 SPACES @ 1'-1" = 45'-6" A601 | 11½" | RUSTICATION GROOVES 11 SPACES @ 4'-0" = 44'-0" | 3'-4⅞"

11⅜" | 42 SPACES @ 1'-1" = 45'-6" A502 (BACK) | 11½"

A504 | 9 SPACES @ 2'-0" = 18'-0" | CONTRACTION JOINT

8⅜" | 23 SPACES @ 2'-0" = 46'-0" A503 (FRONT) | 8½"

11⅜" | 42 SPACES @ 1'-1" = 45'-6" A1102 (BACK) | 11½"

4⅞" | 43 SPACES @ 1'-1" = 46'-7" A701 (BACK) | 5"

4⅞" | 43 SPACES @ 1'-1" = 46'-7" A1101 (BACK) | 5"

8'-0" | 3'-0" | 4⅞" | 43 SPACES @ 1'-1" = 46'-7" A602 (TOP) | 5"

ALL REINFORCING STEEL BARS AND SPACING SYMMETRICAL ABOUT CONTRACTION JOINT UNLESS OTHERWISE NOTED.

10'-0" | 12'-0" | 12'-0" | 4" Φ WEEP HOLES | 1'-6" MIN TYP.

A504 | A1001 | A511 | A512 | A504 | A504 | 5'-0" | 5'-0" | A512

EL. 919.00

PILE SPC. FOR ROW #3 3'-0⅛"

PILE SPC. FOR ROW #2 2'-4⅝"

PILE SPC. FOR ROW #1 2'-4⅝"

6 SPA. @ 6'-7" = 39'-6" | 8-4⅛" | 4 SPA. @ 4'-6" = 18'-0" | 16-1⅛" | 6'-8" | 3'-0⅞"

9 SPA. @ 5'-7" = 50'-3" | 8-5" | 5'-0" | 2 SPA. @ 4'-5" 8-10" | 3-11½" | 16-1⅛" | 3-5⅛" | 3'-0" | 2-4⅝"

8 SPA. @ 4'-7½" = 36'-6" | 5'-0" | 8'-7" | 4 SPA. @ 4'-5" = 17'-8" | 16-1⅝" | 2-11⅝" | 3'-0" | 2-4⅝"

4 SPA. @ 1'-9" = 7'-0"

ELEVATION

*ELEVATIONS GIVEN TO FINISHED GRADE AT FACE OF ABUTMENT BACKWALL

A | B | B | A | E | E

NOTES:

MINIMUM CLEAR DISTANCE BETWEEN REINFORCING STEEL BARS IN THE FOOTING IS 2½".

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #2 PLAN & ELEVATION

BRIDGE NO. MAH-18-1050
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030 + 29.49


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	RDH		D.H.C.			

MICROFILMED
SEP 19 1965


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18 -17.20


458
492




SECTION C-C




SECTIONS SHOWING SLOPE OF BACKWALLS




SECTION D-D
(WEST CURB SIMILAR)




SECTION G-G
(EAST CURB SIMILAR)




DETAIL OF RUSTICATION GROOVES




SECTION B-B




SECTION A-A



SECTION F-F



DETAIL OF CONTRACTION JOINT



SECTION E-E

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 & #2 DETAILS

BRIDGE NO. MAH-18-1050
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+20.49


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	RDH		D.H.C.			

MICROFILMED SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20


459
492




ELEVATION



SECTION A-A



SECTION B-B



SECTION C-C

NOTES:
QUANTITIES ARE INCLUDED WITH ABUTMENT QUANTITIES FOR SECTION E-E AND RUSTICATION GROOVE DETAILS SEE SHT.
ALL PILES ARE 12" CAST IN PLACE CONCRETE WITH A BEARING CAPACITY OF 40 TON.
N.S. DENOTES NEAR SIDE
F.S. DENOTES FAR SIDE

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT #1 WINGWALL

BRIDGE NO. MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+20.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	R.D.H.		D.H.C.			

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MA H-18-17.20

460/492

28'-2¾"

BOT. W-568 W-567 W-566 W-565 W-564 W-563 W-562
TOP W-571 W-570 W-569 W-568
BOT. W-573 W-572
TOP W-576 W-575 W-574 W-572
BOT W-577
TOP W-581 W-580 W-579 W-578

6°28'17" SKEW
42'-1" R.
43'-3" R.
44'-5½" R.
50'-0" R.
OUTER FACE OF WALL
W.P.
DIMENSIONS AT OUTER FACE OF WALL
8'-8 13/16"
EXP. JT. FILLER
VARIES 1'-6"
W.P.
FACE OF ABUTMENT
1"
2'-6" 2'-6" 10'-0" 2'-6" 2'-6" 2'-6" 2'-6" 10'-0" 2'-6" 2'-6" 30'-0"

1"
2'-9-11" (DEVELOPED LENGTH)
4'-0"
6 SPA @ 4'-0" = 24'-0" ℄ TO ℄ RUSTICATION GROOVES
1'-11"
6"
W-557 F.S.
EL. 945.16
A
EL. 941.92
B
C
SERIES OF W-552 N.S.
W-556 N.S.
3 W-551 NS
SERIES OF W-559 F.S.
3 W-651 F.S.
44 SPACES @ 8" = 29'-4"
4"
SERIES OF W-652 F.S.
EL. 936.46
W-560 F.S.
SERIES OF W-653 F.S.
W-561 F.S.
7 W-558 F.S.
SERIES OF W-654 F.S.
EL. 931.00
7 W-1052 F.S.
8 W-851 F.S.
8 W-1051 F.S.
7 W-951 F.S.
5 W-553 F.S.
15 W-751 F.S.
11 SPA @ 2'-0" = 22'-0" N.S. & F.S.
SERIES OF W-559 N.S.
10 W-555 F.S.
5 W-554 N.S.
6"
EL. 919.00
D
D
8 W-752 TOP
12 W-753 BOT
7 W-655 TOP
12 W-657 BOT
8 W-656 TOP
12 W-754 BOT.

ELEVATION

1'-6"
VARIES
9 SPA @ 2'-0" = 18'-0" N.S. & F.S.
10 W-555 F.S.
SERIES OF W-553 N.S.
W-651 OR SERIES OF W-652
¾"
12"
W-551 OR SERIES OF W-552
2'-0" LAP
W-1052
5 W-554 N.S.
W-1051
11'-9"
5'-1"
VARIES
VARIES
W-570
W-569
W-568
W-753
W-752
11"
6"
W-571
2'-6" 2'-6" 2'-6"
3'-2"
3" CLEAR
W-563 W-564 W-565 W-566 W-567
2'-11"
1'-0"
W-562
6" 1'-6" 2'-4" 1'-4½" 4" 2'-9" 1'-6" 1'-3½" 2'-9" 6" 1'-6"
4'-0"
6'-0"
13'-0"
4"

SECTION A-A

DETAIL OF RUSTICATION GROOVES

3'-0" WIDE TYPE "B" WATERPROOFING
1" PREFORMED EXPANSION JOINT FILLER.. JT. FILLER TO BE PAID FOR BY SQ. FT. IN PLACE.

SECTION D-D

1'-6"
VARIES
5 SPA @ 2'-0" = 10'-0" N.S. & F.S.
5 W-554 N.S.
5 W-556 F.S.
SERIES OF W-553
SERIES OF W-561
SERIES OF W-552
SERIES OF W-654
¾"
12"
2'-0" LAP
4'-0"
3'-1½"
VARIES
VARIES
W-580
W-579
W-578
W-754
11"
W-751
W-656
W-581
1'-6" 1'-6" 1'-6"
2'-8" 3" CLEAR
W-564
2'-5"
1'-0"
W-567
W-566
W-565
W-577
10½" 1'-6" 2'-9" 1'-6" 1'-3½" 1'-6" 10½"
5'-8"
8'-8"

SECTION C-C

7 SPA @ 2'-0" = 14'-0" N.S. & F.S.
8 W-555 F.S.
SERIES OF W-553
5 W-554 N.S.
SERIES OF W-552
SERIES OF W-653
¾"
12"
2'-0" LAP
W-851
8'-0"
W-951
5'-0"
4'-1"
VARIES
VARIES
W-575
W-574
W-572
W-657
11"
W-655
8"
3'-0" 3" CLEAR
W-576
W-564
2'-0" 2'-0" 2'-0"
W-565
W-566
W-567
2'-9"
1'-0"
W-573
6" 1'-6" 2'-8½" 2'-9" 1'-6" 1'-3½" 1'-7" 6"
3'-0"
4'-10"
10'-10"

SECTION B-B

ALL PILES ARE 12" DIA. CAST-IN-PLACE CONCRETE WITH A BEARING CAPACITY OF 40 TON.
QUANTITIES ARE INCLUDED IN ABUT. QUANTITIES.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

ABUTMENT 2 WINGWALL

BRIDGE NO. MAH-18-1050
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	JLH		D.H.C.			

MICROFILMED
SEP 19 1985


FED. RD.	STATE	PROJECT	
	OHIO		

461
492


MAH-18-17.20




PLAN OF SECTION I




C ELEVATION OF SECTION I




PIER ELEVATION



PIER PLAN.



SECTION A-A



SECTION B-B

TABLE OF ELEVATIONS

POINT	A	B	C	D	E	F	G	H	K	L	M	N	P	R
ELEV.	944.07	944.11	944.26	944.42	944.58	944.74	944.77	944.68	944.58	944.48	944.41	944.43	924.[illegible]	923.00


NOTES

REINFORCING STEEL TO HAVE A MINIMUM OF 2" COVER EXCEPT AS OTHERWISE NOTED.

SPECIAL CARE SHALL BE TAKEN IN PLACING REINFORCING STEEL UNDER BEAM BEARINGS IN ORDER TO CLEAR ANCHOR BOLTS WHERE THEY OCCUR.

SECTION I SHOWN, SECTION II SIMILAR EXCEPT AS NOTED OR SHOWN.

ALL PILES ARE 12" CAST IN PLACE CONCRETE WITH 40 TON BEARING CAPACITY.



SECTION C-C

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT I. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS


BRIDGE NO. MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	R.D.H.		D.H.C.			


FED. RD.	STATE	PROJECT	
	OHIO		


MAH-18-17.20


46(A)
412



PLAN OF SECTION I










TABLE OF ELEVATIONS

POINT	A	B	C	D	E	F	G	H	K	L	M	N	P	R
ELEV.	944.07	944.11	944.26	944.42	944.58	944.74	944.77	944.68	944.58	944.48	944.41	944.43	924.25	923.00

NOTES

REINFORCING STEEL TO HAVE A MINIMUM OF 2" COVER EXCEPT AS OTHERWISE NOTED.

SPECIAL CARE SHALL BE TAKEN IN PLACING REINFORCING STEEL UNDER BEAM BEARINGS IN ORDER TO CLEAR ANCHOR BOLTS WHERE THEY OCCUR.

SECTION I SHOWN, SECTION II SIMILAR EXCEPT AS NOTED OR SHOWN.

ALL PILES ARE 12" CAST IN PLACE CONCRETE WITH 40 TON BEARING CAPACITY.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PIER DETAILS

BRIDGE NO. MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	R.D.H.		D.H.C.			

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		


462/492

MAH-18-17.20




NOTE: ALL BEAMS ARE PARALLEL TO ℄ MARKET ST. AND ALL ANGLES ARE GIVEN TO ℄ PIER OR ℄ ABUTMENT BEARINGS.

GEOMETRIC LAYOUT



FRAMING PLAN




⅞"x1½" BOLTS, 1'-6" MAX. % - SEE NOTES FOR SIMILAR BOLTS ON STD. DWG. CSB-25G SHEET #2

SECTION C-C

BEAM SPLICE DETAILS

DEFLECTION & CAMBER				
LOCATION	B1 – B10		B11 & B12	
	SPAN NO.1	SPAN NO.2	SPAN NO.1	SPAN NO.2
DEFLECTION DUE TO WT. OF STEEL	0.17"	0.01"	0.18"	0.01"
DEFLECTION DUE TO REMAINING DEAD LOAD	0.68"	0.05"	1.15"	0.07"
COVEXITY REQUIRED FOR VERTICAL CURVE	0.00"	0.00"	0.00"	0.00"
SUM OF DEFLECTION AND CONVEXITY	0.85"	0.06"	1.33"	0.08"
REQUIRED CAMBER	1"	0	1⅜"	0

BEAM	R
B1, B2, B3	1½"
B4, B5, B6	1⅝"
B7, B8, B9	1⅞"
B10, B11, B12	2"



SECTION B-B

NOTES

CONCRETE DECK PLACING: IN ORDER TO FACILITATE WATER CURING OF THE CONCRETE OF THE DECK SLAB THE PLACING OF CONCRETE SHALL PROGRESS UPGRADE. THE SLAB MAY BE PLACED IN SECTIONS BETWEEN THE TRANSVERSE CONSTRUCTION JOINTS WHICH ARE NORMAL TO THE CENTERLINE OF THE BRIDGE AND ARE LOCATED NEAR THE CENTER OF ANY SPAN.

SLAB THICKNESS INCLUDES 1" MONOLITHIC WEARING SURFACE.

WELDING PROCEDURE: LIFT END OF BEAM R" (SEE TABLE THIS SHEET) AT ABUTMENT #2, BUTT-WELD THE BEAM FLANGES AND WEB, USING THE FOLLOWING SEQUENCE: MAKE TWO PASSES ON EACH FLANGE, THEN TWO ON THE WEB; REPEAT, USING ONE PASS AT EACH LOCATION UNTIL WELDS ARE COMPLETED. WELD THE BOTTOM AND TOP MOMENT PLATES, LOWER THE BEAM END TO FINAL POSITION AT ABUTMENT.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

FRAMING PLAN

BRIDGE NO. MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.D.H.	JK		D.H.C.			


MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		


463
492

MAH-18-17.20

℄ SURVEY OF MARKET STREET ℄ SUPERSTRUCTURE




TRANSVERSE SECTION
SYMMETRICAL ABOUT ℄




FOLDED COPPER DETAIL
12" WIDE 16 OZ.

S603 BARS IN TOP OF SLAB ACROSS PIERS
S504 BARS IN TOP OF SIDEWALK ACROSS PIERS
(SEE TRANSVERSE SECTION FOR SPACING)




BAR STAGGERING DETAIL OVER PIERS



SLAB REINFORCING PLAN

LAP	S 503	1'-6" MIN.
LAP	S602	1'-11" MIN.



DETAIL OF LIGHT STANDARD SUPPORT
INCL. FOR PAYMENT WITH ITEM S-25

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

SLAB DETAIL

BRIDGE NO. MAH-18-1950
UNDER MARKET ST
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49


DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
E.D.H.	RDH		D.H.C.			

MICROFILMED SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

464 / 492

MAH-18-17.20



PILE CUT-OFF ELEVATIONS	
ABUT. # 1	926.50
LT. PIER	925.25
RT. PIER	924.00
ABUT. # 2	920.00

PILE PLAN

○ INDICATES BATTERED PILE (1":4)

● INDICATES VERTICAL PILE

PILE COORDINATES FOR PILES IN WINGWALLS

PILE NO.	COORDINATES X	Y
1	4'-0" RT.	2'-0"
2	3'-7" RT.	7'-4"
3	1'-11" RT.	11'-0"
4	0'-7" RT.	16'-0"
5	1'-7" LT.	19'-4"
6	3'-9" LT.	24'-0"
7	0'-7" RT.	1'-10"
8	0'-4" LT.	6'-9"
9	1'-0" LT.	10'-4"
10	2'-3" LT.	15'-2"
11	6'-1" LT.	3'-10"
12	6'-3" LT.	11'-6"
13	7'-10" LT.	19'-4"
14	4'-0" RT.	2'-8"
15	3'-10" RT.	5'-4"
16	3'-6" RT.	8'-0"
17	1'-5" RT.	13'-0"
18	0'-1" LT.	18'-0"
19	3'-0" LT.	22'-8"
20	5'-8" LT.	21'-0"
21	0'-0"	2'-6"
22	0'-6" LT.	7'-8"
23	1'-8" LT.	12'-3"
24	2'-11" LT.	17'-0"
25	6'-2" LT.	4'-8"
26	6'-9" LT.	9'-3"
27	9'-2" LT.	22'-0"

NOTES:

-ALL PILES SHALL BE 12" CAST-IN-PLACE REINFORCED CONCRETE DRIVEN TO 40 TON MINIMUM BEARING CAPACITY.

PILES ADJACENT TO THE SEWER SHALL BE DRIVEN IN PREBORED HOLES TO A DEPTH OF 3' BELOW THE BOTTOM OF THE SEWER. CARE SHALL BE TAKEN SO AS TO INSURE A MINIMUM CLEAR DISTANCE OF 4" BETWEEN SEWER & PILE

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

PILE PLAN


BRIDGE NO. MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	R.D.H.		O.H.C.			

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

404
492



PILE CUT-OFF ELEVATIONS	
ABUT. #1	926.50
LT. PIER	925.25
RT. PIER	924.00
ABUT #2	920.00

PILE PLAN

○ INDICATES BATTERED PILE (1:4)
● INDICATES VERTICAL PILE

PILE COORDINATES FOR PILES IN WINGWALLS

PILE NO.	COORDINATES X		Y
1	4'-0"	RT.	2'-0"
2	3'-7"	RT.	7'-4"
3	1'-11"	RT.	11'-0"
4	0'-7"	RT.	16'-0"
5	1'-7"	LT.	19'-4"
6	3'-9"	LT.	24'-0"
7	0'-1"	RT.	1'-10"
8	0'-4	LT.	6'-9"
9	1'-0"	LT.	10'-4"
10	2'-3"	LT.	15'-2"
11	6'-1"	LT.	3'-10"
12	6'-3"	LT.	11'-6"
13	7'-10	LT.	19'-4"
14	4'-0"	RT.	2'-8"
15	3'-10"	RT.	5'-4"
16	3'-6"	RT.	8'-0"
17	1'-5"	RT.	12'-0"
18	0'-1"	LT.	18'-0"
19	3'-0"	LT.	22'-5"
20	5'-6"	LT.	27'-0"
21	0'-0"		2'-6"
22	0'-6"	LT.	7'-5"
23	1'-5"	LT.	12'-3"
24	2'-11"	LT.	17'-0"
25	6'-2"	LT.	4'-4"
26	6'-9"	LT.	13'-3"
27	9'-2"	LT.	22'-0"

NOTES:
ALL PILES SHALL BE 12" CAST-IN-PLACE REINFORCED CONCRETE DRIVEN TO 40 TON MINIMUM BEARING CAPACITY. PILES ADJACENT TO THE EXISTING 48" RELOCATED SEWER SHALL BE PRE-BORED TO A DEPTH OF THREE FEET (3') BELOW THE BOTTOM OF THE SEWER. CARE SHALL BE TAKEN SO AS TO PROVIDE A MINIMUM CLEAR DISTANCE OF FOUR FEET (4') BETWEEN THE EXISTING 48" SEWER AND THE PILES.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO


PILE PLAN

BRIDGE NO. MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H.	R.D.H.		D.H.C.			

MAH-18-17.20
MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		



PART DECK PLAN
(OPP. HAND SIMILAR EXCEPT AS NOTED OR SHOWN)

ELEVATION

PIPE ANCHORAGE DETAIL AT PIER

NOTES:
TYPE "C" RAILING: TOP RAIL 4" O.D. × ⅜" WALL ALUMINUM TUBE RAILING, ℄ BOTT. RAIL 3½" × ⅜" WALL ALUMINUM TUBE RAILING SHALL BE CONTINUOUS THRU FIRST POST AT EACH END OF SUPERSTRUCTURE.
E.P. DENOTES EAST PARAPET
W.P. DENOTES WEST PARAPET
B.P. DENOTES BOTH PARAPETS

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

DRAINAGE & RAILING DETAILS

BRIDGE NO. MAH-18-1950
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
RDH	R.D.H.		D.H.C.			

MICROFILMED
SEP 19 1985

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

466
492

REINFORCING STEEL SCHEDULE

MARK	NO. REQD	LENGTH	WEIGHT	SHP
ABUTMENT #1				
A-501	72	5'-3"	394	BT
A-502				
A-503				
A-504				
A-505	8	4'-7"	38	ST
A-506	6	7'-0"	44	BT
A-507	4	12'-8"	53	ST
A-508		OPEN		
A-509		OPEN		
A-510				
A-511				
A-512	29	10'-0"	303	ST
A-513	8	8'-0"	67	ST
A-514	88	10'-3"	941	ST
A-515	48	18'-4"	918	ST
A-516	148	24'-10"	3833	ST
A-517	12	27'-0"	338	ST
A-518		OPEN		
A519		OPEN		
A-520	3	7'-7"	24	BT
A-521	3	8'-0"	25	BT
A-601	88	11'-1"	1465	BT
A-602	90	10'-6"	1420	ST
A-603		OPEN		
A-604		OPEN		
A-605	64	15'-1"	1450	BT
A-606	24	13'-1"	472	BT
A-701	90	15'-0"	2760	ST
A-1001	130	15'-11"	8905	BT
A-1101	90	6'-4"	3029	BT
A-1102	88	14'-10"	6935	BT
TOTAL ABUTMENT #1 = 33,414				
ABUTMENT #2				
A-501	72	5'-3"	394	BT
A-502	86	11'-6"	1032	ST
A-503	48	19'-9"	989	ST
A-504	156	24'-4"	3960	ST
A-505	8	4'-7"	38	ST
A-506	6	7'-0"	44	BT
A-507	4	12'-8"	53	ST

MARK	NO. REQD	LENGTH	WEIGHT	SHP
ABUTMENT #2 (CONT.)				
A-508		OPEN		
A-509		OPEN		
A-510	6	7'-5"	47	BT
A-511	12	26'-4"	330	ST
A-512	29	10'-0"	303	ST
A-513	8	8'-0"	67	ST
A-601	86	11'-1"	1432	BT
A-602	88	10'-6"	1388	ST
A-603		OPEN		
A-604		OPEN		
A-605	64	15'-1"	1450	BT
A-606	22	13'-1"	483	BT
A-701	88	15'-0"	2698	ST
A-1001	132	15'-11"	9042	BT
A-1101	88	6'-4"	2961	BT
A-1102	86	14'-10"	6778	BT
TOTAL ABUTMENT #2 = 33,439				
WING WALL NO. 1				
W-501	3	21'-0"	66	ST
SERIES OF W-502	1 SET OF 4 BARS	VARY FROM 20'-7 TO 18'-10 IN INC. OF 7"	82	ST
SERIES OF W-503	1 SET OF 6 BARS	VARY FROM 18'-2 TO 14'-10 IN INC. OF 8"	103	ST
SERIES OF W-504	1 SET OF 7 BARS	VARY FROM 14'-4 TO 10'-4 IN INC. OF 8"	90	ST
SERIES OF W-505	1 SET OF 6 BARS	VARY FROM 24'-1 TO 4'-6 IN INC. OF 3'-11	90	BT
W-506	5	25'-7"	133	BT
W-507	10	8'-0"	84	BT
W-508	1	4'-6"	5	BT
W-509	12	10'-4"	129	BT
W-510	1	9'-9"	10	BT
W-511	1	5'-10"	6	BT
W-512	1	8'-9"	9	BT
W-513	1	4'-10"	5	BT
W-514	1	26'-2"	27	BT
W-515	1	24'-8"	26	BT
W-516	1	24'-0"	25	BT
W-517	1	23'-3"	24	BT
W-518	1	8'-8"	9	BT
W-519	1	9'-1"	10	BT
W-520	1	7'-1"	8	BT
W-521	1	8'-4"	9	BT
W-522	1	7'-10"	8	BT
W-523	1	7'-6"	8	BT
W-524	1	7'-1"	8	BT

MARK	NO. REQD	LENGTH	WEIGHT	SHP
WING WALLS (CONT.)				
W-525	1	11'-5"	12	BT
W-526	1	9'-4"	10	BT
W-527	1	10'-7"	11	BT
W-528	1	10'-2"	11	BT
W-529	1	9'-9"	10	BT
W-530	1	9'-4"	10	BT
W-531	1	11'-2"	12	BT
W-532	1	10'-6"	11	BT
W-533	1	10'-2"	11	BT
W-534	1	9'-10"	10	BT
W-535	1	9'-3"	10	BT
W-601	3	11'-9"	53	ST
SERIES OF W-602	1 SET OF 3 BARS	VARY FROM 11'-2 TO 9'-10 IN INC. OF 8"	47	ST
SERIES OF W-603	1 SET OF 7 BARS	VARY FROM 12'-9 TO 8'-9 IN INC. OF 8"	113	ST
SERIES OF W-604	1 SET OF 6 BARS	VARY FROM 12'-10 TO 8'-8 IN INC. OF 10"	97	ST
W-605	7	7'-4"	77	BT
W-606	6	7'-4"	66	ST
W-607	10	11'-0"	165	BT
W-608	7	6'-0"	63	ST
W-701	6	7'-7"	95	BT
W-702	7	8'-6"	122	ST
W-703	10	13'-4"	273	BT
W-704	10	9'-0"	184	BT
W-801	7	12'-4"	230	BT
W-901	6	9'-4"	191	BT
W-1001	7	9'-8"	291	BT
W-1002	6	16'-2"	422	BT
TOTAL WING WALL NO. 1 = 3581				
PIERS				
P-501	144	7'-4"	1102	BT
P-502	116	7'-2"	867	ST
P-601	4	19'-7"	118	ST
P-602	4	24'-5"	146	ST
P-801	8	9'-4"	200	ST
S-701	387	34'-6"	27,291	ST
SERIES OF S-701A	2 SETS OF 10 BARS	VARY FROM 33'-6 TO 3'-6 IN INC. OF 3'-0	756	ST
SERIES OF S-701B	2 SETS OF 6 BARS	VARY FROM 35'-0 TO 3'-10 IN INC. OF 5'-10	501	ST
S-801	403	7'-6"	8070	ST
TOTAL SUPERSTRUCTURE = 107,136				
WING WALL NO. 2				
W-551	3	22'-10"	103	ST
SERIES OF W-552	1 SET OF 20 BARS	VARY FROM 22'-8 TO 9'-8 IN INC. OF 8"	333	ST
SERIES OF W-553	1 SET OF 7 BARS	VARY FROM 24'-5 TO 4'-6 IN INC. OF 3'-8	113	BT
W-554	5	29'-7"	154	BT
W-555	10	9'-0"	94	BT
W-556	1	7'-6"	8	BT

MARK	NO. REQD	LENGTH	WEIGHT	SHP
PIERS (CONT.)				
P-904	36	18'-1"	2213	ST
P-1001	8	17'-0"	585	ST
P-1002	8	31'-6"	1084	ST
P-1101	14	14'-0"	1041	ST
P-1102	20	12'-2"	1293	ST
P-1103	10	20'-2"	1072	ST
P-1104	4	25'-0"	532	ST
P-1105	6	25'-9"	821	BT
P-1106	6	26'-5"	842	BT
P-1107	4	8'-10"	188	BT
P-1108	24	22'-6"	2869	ST
P-1109	16	24'-1"	2048	BT
P-1110	16	24'-5"	2076	BT
P-1111	24	23'-1"	2943	ST
		TOTAL =	26,111	
		SPIRALS =	1568	
TOTAL PIERS = 27,679				
RAILINGS				
R-501	8	13'-0"		ST
R-502	4	3'-8"		ST
R-503	56	16'-0"		ST
R-504	4	12'-2"		ST
R-505	16	4'-7"		ST
SUPERSTRUCTURE				
S-501	184	5'-6"	1056	BT
S-502	410	12'-6"	5346	ST
S-503	84	36'-0"	3154	ST
S-503A	14	28'-3"	413	ST
S-503B	14	36'-6"	533	ST
S-504	12	28'-0"	351	ST
S-505	202	8'-1"	1703	BT
S-506	410	14'-11"	6879	BT
S-507	406	3'-4"	1412	BT
S-508	408	2'-10"	1191	BT
S-601	387	36'-6"	21217	ST
SERIES OF S-601A	2 SETS OF 10 BARS	VARY FROM 33'-6 TO 3'-6 IN INC. OF 3'-0	556	ST
SERIES OF S-601B	2 SETS OF 6 BARS	VARY FROM 35'-0 TO 5'-10 IN INC. OF 5'-10	368	ST
S-602	348	36'-0"	18,817	ST
SERIES OF S-602A	1 SET OF 54 BARS	VARY FROM 39'-0 TO 29'-0 IN INC. OF 2'-6	2760	ST
SERIES OF S-602B	1 SET OF 62 BARS	VARY FROM 39'-0 TO 20'-10 IN INC. OF 2"	3,159	ST
S-603	30	28'-0"	2,103	ST

FED. RD.	STATE	PROJECT	
	OHIO		

MAH-18-17.20

REINFORCING STEEL SCHEDULE

MARK	NO. REQD	LENGTH	WEIGHT	SHP
ABUTMENT "1				
A-501	72	5'-3"	394	BT
A-502				
A-503				
A-504				
A-505	8	4'-7"	38	ST
A-506	6	7'-0"	44	BT
A-507	4	12'-8	53	ST
A-508		OPEN		
A-509		OPEN		
A-510				
A-511				
A-512	29	10'-0	303	ST
A-513	8	8'-0	67	ST
A-514	88	10'-3"	941	ST
A-515	48	18'-4	918	ST
A-516	148	24-10	3858	ST
A-517	12	27'-0	338	ST
A-518		OPEN		
A-519		OPEN		
A-520	3	7'-7"	24	BT
A-521	3	8'-0"	25	BT
A-601	88	11'-1"	1462	BT
A-602	90	10'-6	1479	ST
A-603		OPEN		
A-604		OPEN		
A-605	64	15'-1	1450	BT
A-606	24	13'-1"	472	BT
A-1001	132	15'-11	9042	BT
A-1101	90	6'-4	3029	BT
A-1102	38	14-10	6935	BT
TOTAL ABUTMENT "1= 33,451				
ABUTMENT "2				
A-501	72	5'-3"	394	BT
A-502	86	11'-6"	1032	ST
A-505	48	19'-9"	989	ST
A-504	156	24'-4	3960	ST
A-505	8	4'-1"	38	ST
A-506	6	7'-0"	44	BT
A-507	4	12'-8	53	ST


MARK	NO. REQD	LENGTH	WEIGHT	SHP
ABUTMENT "2 (CONT.)				
A-508		OPEN		
A-509		OPEN		
A-510	6	7'-5	47	BT
A-511	12	26'-4	330	ST
A-512	29	10'-0	303	ST
A-513	8	8'-0"	67	ST
A-601	86	11'-1"	1457	BT
A-602	88	10'-6"	1396	ST
A-603		OPEN		
A-604		OPEN		
A-605	64	15'-1"	1480	BT
A-606	22	13'-1"	482	BT
A-701	88	15'-0"	2644	ST
A-1001	130	15'-11	8905	BT
A-1101	83	6'-4	2901	BT
A-1102	86	14-10	6778	BT
TOTAL ABUTMENT "2= 38,402				
WING WALL NO. 1				
W-501	3	21'-0"	66	ST
SERIES OF W-502	1 SET OF 4 BARS	VARY FROM 20'-7 TO 18'-10 IN INC. OF 7	82	ST
SERIES OF W-503	1 SET OF 6 BARS	VARY FROM 13'-2 TO 11'-10 IN INC. OF 3"	103	ST
SERIES OF W-504	1 SET OF 7 BARS	VARY FROM 14'-4 TO 10'-1 IN INC. OF 8"	90	ST
SERIES OF A-701	1 SET OF 6 BARS	VARY FROM 24'-1 TO 4'-6 IN INC. OF 3'-11	93	BT
W-505	5	25'-7"	133	BT
W-506	10	8'-0	84	BT
W-508	1	4'-6	5	BT
W-509	12	10'-4"	129	BT
W-510	1	9'-9"	10	BT
W-511	1	5'-10	6	BT
W-512	1	8'-9	9	BT
W-513	1	4'-10	5	BT
W-514	1	26'-2	27	BT
W-515	1	24'-8"	26	BT
W-516	1	24'-0"	25	BT
W-517	1	23'-3"	24	BT
W-518	1	8'-8	9	BT
W-519	1	9'-1	10	BT
W-520	1	7'-1	8	BT
W-521	1	8'-4	9	BT
W-522	1	7'-10	8	BT
W-523	1	7'-6	8	BT
W-524	1	7'-1	8	BT


MARK	NO. REQD	LENGTH	WEIGHT	SHP
WING WALLS (CONT.)				
W-525	1	11'-5"	12	BT
W-526	1	9'-4"	10	BT
W-527	1	10'-7"	11	BT
W-528	1	10'-2	11	BT
W-529	1	9'-9	10	BT
W-530	1	9'-4	10	BT
W-531	1	11'-2"	12	BT
W-532	1	10'-6	11	BT
W-533	1	10'-2	11	BT
W-534	1	9'-10	10	BT
W-535	1	9'-5	10	BT
W-601	3	11'-9"	53	ST
SERIES OF W-602	1 SET OF 3 BARS	VARY FROM 11'-2 to 9'-10 IN INC. OF 8"	47	ST
SERIES OF W-603	1 SET OF 7 BARS	VARY FROM 12'-9 to 8'-9 IN INC. OF 5	113	ST
SERIES OF W-604	1 SET OF 6 BARS	VARY FROM 12'-10 to 8'-8 IN INC. OF 10	97	ST
W-605	7	7'-4	77	BT
W-606	6	7'-4"	66	ST
W-607	10	11'-0"	165	BT
W-608	7	6'-0	63	ST
W-701	6	7'-7	95	BT
W-702	7	8'-6"	124	ST
W-703	10	13-4	273	BT
W-704	10	9'-0	184	BT
W-801	7	12'-4	230	BT
W-901	6	9-4	191	BT
W-1001	7	2'-5	241	BT
W-1002	6	16'-2	402	BT
TOTAL WING WALL NO. 1 = 3581				
PIERS				
P-501	144	7'-4	1102	BT
P-502	116	7'-2	867	ST
P-601	4	19'-7	118	ST
P-602	4	24'-3	146	ST
P-801	8	9'-4	200	ST
P-901	14	10'-6	500	FT
P-902	36	16'-6"	2020	ST
P-903	72	6'-4"	1151	BT


MARK	NO. REQD	LENGTH	WEIGHT	SHP
PIERS (CONT.)				
P-904	36	18'-1"	2213	ST
P-1001	8	17'-0"	585	ST
P-1002	8	21'-6"	1084	ST
P-1101	14	14'-0"	1041	ST
P-1102	20	12'-2"	1293	ST
P-1103	10	20'-2"	1072	ST
P-1104	4	25'-0"	534	ST
P-1105	6	25'-9"	841	BT
P-1106	6	26'-5"	842	BT
P-1107	4	8'-1"	188	BT
P-1108	24	22'-4"	2969	ST
P-1109	16	24'-1"	2048	BT
P-1110	16	24'-5"	2076	BT
P-1111	24	23'-1"	2943	ST
		TOTAL	26,111	
		SPIRALS	1568	
TOTAL PIERS = 27,679				
RAILINGS				
R-501	8	13'-0"		ST
R-502	4	3-8"		ST
R-503	56	16'-0		ST
R-504	4	12-2		ST
R-505	16	4'-7"		ST
SUPERSTRUCTURE				
S-501	184	5'-6"	1056	BT
S-502	410	12-6	5846	ST
S-503	84	36'-0	3154	ST
S-503A	14	28'-8	413	ST
S-503B	14	36'-6	535	ST
S-504	12	28'-0	351	ST
S-505	202	8'-1	1708	BT
S-506	410	14-11	6279	BT
S-507	406	3'-4	1412	BT
S-508	403	2-10	1191	BT
S-601	387	36-6	21217	ST
SERIES OF S-601A	2 SETS OF 10 BARS	VARY FROM 33'-6 to 5'-6 IN INC. OF 3'-0"	556	ST
SERIES OF S-601B	2 SETS OF 6 BARS	VARY FROM 35'-0 to 5'-10 IN INC. OF 5'-3	368	ST
S-602	348	36'-0	18,817	ST
SERIES OF S-602A	1 SET OF 54 BARS	VARY FROM 39'-0 to 29'-0 IN INC. OF 2'-6	2760	ST
SERIES OF S-602B	1 SET OF 62 BARS	VARY FROM 39'-0 to 20'-0 IN INC. OF 2'-6	3,159	ST
S-603	50	28'-0	2,103	ST
S-701	387	34'-6	27,291	ST
SERIES OF S-701A	2 SETS OF 10 BARS	VARY FROM 33'-6 to 5'-6 IN INC. OF 3'-0"	1560	ST
SERIES OF S-701B	2 SETS OF 6 BARS	VARY FROM 35'-0 to 5'-10 IN INC. OF 5'-3	1031	ST
S-801	403	7'-6	8070	ST
TOTAL SUPERSTRUCTURE = 107,136 #				
WING WALL NO. 2				
W-551	3	22'-10"	103	ST
SERIES OF W-552	1 SET OF 20 BARS	VARY FROM 22'-5 to 9'-2 IN INC. OF 8½	325	ST
SERIES OF W-553	1 SET OF 7 BARS	VARY FROM 26'-6 to 4'-6 IN INC. OF 3'-8"	113	BT
W-554	5	29-7"	154	BT
W-555	10	9'-0"	94	BT
W-556	1	7'-6"	8	BT


MARK	NO. REQD	LENGTH	WEIGHT	SHP
WING WALL NO. 2 (CONT.)				
W-557	1	4'-6	5	BT
W-558	12	11'-0	138	BT
SERIES OF W-559	1 SET OF 3 BARS	VARY FROM 10'-7 to 9'-5 IN INC. OF 3'-8	22	BT
W-560	1	4'-4"	5	BT
W-561	1	8'-0"	8	BT
W-562	1	10'-7"	11	BT
W-563	1	9'-11"	10	BT
W-564	1	30'-2	32	BT
W-565	1	28'-6	30	BT
W-566	1	27'-5	29	BT
W-567	1	26'-10"	28	BT
W-568	2	8'-2"	17	BT
W-569	1	8'-8"	9	BT
W-570	1	9'-2"	10	BT
W-571	1	9'-6"	10	BT
W-572	2	9'-9"	21	BT
W-573	1	11'-8"	12	BT
W-574	1	10'-2"	11	BT
W-575	1	10'-6"	11	BT
W-576	1	10'-11"	11	BT
W-577	1	11'-5"	12	BT
W-578	1	10'-0"	10	BT
W-579	1	10'-8	11	ST
W-580	1	10'-6"	11	ST
W-581	1	10'-10	12	BT
W-651	3	18'-8"	69	ST
SERIES OF W-652	1 SET OF 4 BARS	VARY FROM 12'-11 to 10'-5 IN INC. OF 9"	71	ST
SERIES OF W-653	1 SET OF 5 BARS	VARY FROM 13'-10 to 8'-7 IN INC. OF 9"	135	ST
SERIES OF W-654	1 SET OF 7 BARS	VARY FROM 12'-4 to 7'-10 IN INC. OF 9"	106	ST
W-655	7	7'-4	77	ST
W-656	8	6'-0	72	ST
W-657	12	11'-0	198	ST
W-751	15	7'-7	238	ST
W-752	8	7'-10	128	ST
W-753	12	13'-4	327	BT
W-754	12	9'-0	221	ST
W-851	8	12'-4	163	BT
W-951	7	9'-2	224	BT
W-1051	8	9'-9	323	BT
W-1052	7	16'-2	487	BT
TOTAL WINGWALL NO. 2 = 4227				

GRAND TOTAL 209,476 LBS.












S-505




S-506




P-1107









RE-401

BENDING RADII			
MARK	RADIUS	MARK	RADIUS
SERIES OF W-505	49'-10	W-520	42'-7"
W-506	49'-10	W-521	49-11
W-507	48'-0	W-522	47'-5
W-508	48'-10	W-525	44'-11
W-509	48'-0	W-524	42'-6
W-510	48'-4"	W-525	53'-7
W-511	48'-6	W-526	43'-9"
W-512	48'-9	W-527	49'-8
W-513	48'-10	W-528	47'-8
W-514	50'-11	W-529	45'-8
W-515	48'-2	W-530	43'-8
W-516	46'-8	W-531	52'-3"
W-517	45'-4	W-532	49'-4
W-518	52'-3"	W-533	47'-10
W-519	54'-7"	W-534	46'-4
		W-535	44-10

BENDING RADII			
MARK	RADIUS	MARK	RADIUS
SERIES OF W-568	49'-10	W-567	45'-4"
W-554	49'-10	W-568	42'-7"
W-555	48'-0"	W-569	44'-11
W-556	49'-10	W-570	47'-5"
W-557	45'-9	W-571	49'-11"
W-558	48'-7	W-572	43'-9"
SERIES OF W-559	48'-4"	W-573	53'-7"
W-560	48'-3	W-574	45'-3
W-561	48'-3	W-575	47'-8"
W-562	54'-7"	W-576	49'-8"
W-563	52'-3	W-577	52'-3"
W-564	50'-11	W-578	47'-10
W-565	48'-2	W-581	49'-4"
W-566	46'-8"		

REPLACEMENT BARS			
MARK	NO. REQD	LENGTH	SHP
RE-401	1	5'-3	F
RE-501	3	5'-6	ST
RE-601	4	6-0	ST
RE-701	2	6'-3	ST
RE-801	1	6'-6	ST
RE-901	1	6'-10	ST
RE-1001	2	7'-2	ST
RE-1101	2	7'-6	ST

SPIRAL REINFORCING LIST						
MARK	NO REQD.	CORE DIA. OF SPIRAL	LENGTH OF SPIRAL	PITCH	NO. OF TURNS	WEIGHT
SP-401	5	2'-9	12'-2"	4½	38	628
SP-402	3	2'-8	14'-9"	4½	48	712
24 SPACERS						228
TOTAL SPIRALS						1568

NOTES

1. SPIRAL REINFORCING: 4 STEEL CHANNELS TEES OR ANGLE SPACERS WEIGHING APPROXIMATELY 0.68 LBS. PER LIN. FT. OF SPACER SHALL BE PROVIDED FOR EACH SPIRAL UNIT. THEY SHALL BE EQUALLY SPACED ALONG THE PERIPHERY OF THE COIL. THE NUMBER OF POUNDS OF THESE SPACERS BASED ON 0.68 LBS. PER LIN. FT. WILL BE PAID FOR AS REINFORCING STEEL AND IS INCLUDED IN THE TABULATED QUANTITY OF SPIRAL BARS.
THE LENGTH SHOWN IN THE STEEL LIST FOR THE SPIRAL BARS IS THE DISTANCE FROM THE TOP OF FOOTING TO THE TOP OF THE COLUMN.
THE NUMBER OF TURNS SHOWN IN THE STEEL LIST FOR SPIRAL BARS IS THE LENGTH DIVIDED BY THE PITCH PLUS THREE TURNS (TOTAL NUMBER OF TURNS = COILS EXPRESSED AS THE NEAREST WHOLE NUMBER.
SPIRAL REINFORCING BARS SHALL NOT HAVE DEFORMATIONS BUT SHALL IN OTHER RESPECTS CONFORM TO ITEM 3-4.
1½ CLOSED COILS SHALL BE PROVIDED AT THE ENDS OF EACH SPIRAL UNIT.
2. REPLACEMENT BARS: IF REINFORCING BARS ARE FABRICATED FROM STOCK LENGTHS THAT HAVE PREVIOUSLY BEEN TESTED AND APPROVED BY THE OHIO HIGHWAY TESTING LABORATORY, TEST SAMPLES AS PROVIDED IN SEC. 3-4.03, NEED NOT BE FURNISHED AND REPLACEMENT BARS WILL NOT BE REQUIRED.
3. BAR SIZE: IS INDICATED IN THE BAR MARK. THE FIRST DIGIT WHERE 5 DIGITS ARE USED AND THE FIRST TWO DIGITS WHERE 4 DIGITS ARE USED INDICATES THE BAR SIZE NUMBER; FOR EXAMPLE, S-701 IS A NUMBER 7 SIZE BAR & P-1101 IS A NUMBER 11 SIZE BAR.
4. REINFORCING BARS ARE DIMENSIONED FROM OUT TO OUT.
5. RAILING REINFORCING BARS ARE PAID FOR AS PART OF ITEM 3-14.

STATE OF OHIO
DEPARTMENT OF HIGHWAYS
BUREAU OF BRIDGES

BEISWENGER, HOCH & ASSOCIATES AND ROBERT J. SCHOMER
CONSULTING ENGINEERS
3600 MARKET ST. YOUNGSTOWN, OHIO

REINFORCING SCHEDULE

BRIDGE NO. MAH-18-1050
UNDER MARKET ST.
YOUNGSTOWN, MAHONING COUNTY
STA. 1030+29.49

DESIGNED	DRAWN	TRACED	CHECKED	REVIEWED	DATE	REVISED
R.D.H	J.L.H		D.H.C.			

R/W SHEET 1 OF 26 18-MAH-17.20

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

467
492

LOCATION PLAT

MAH 18-17.20 & MAH 7-14.80

MAHONING COUNTY

CITY OF YOUNGSTOWN

SCALE: 1"= 500'

CURVE DATA No. 1

P. I. Sta.
Δ = 43° 47' 40" Lt. Y = 25.53'
Dc = 5° 30' 00" L.T. = 267.18'
Ls = 400.00' S.T. = 133.80'
Rc = 1041.74' L.C. = 399.34'
θs = 11° 00' 00" Ts = 621.04'
P = 6.39' Es = 87.89'
K = 199.76' Lc = 396.26'
X = 398.53' Δc = 21° 47' 40"

CURVE DATA No. 2

P. I. Sta.
Δ = 54° 44' 10" Rt. Y = 25.53'
Dc = 5° 30' 00" L.T. = 267.18'
Ls = 400.00' S.T. = 133.80'
Rc = 1041.74' L.C. = 399.34'
θs = 11° 00' 00" Ts = 742.31'
P = 6.39' Es = 138.49'
K = 199.76' Lc = 595.20'
X = 398.53' Δc = 32° 44' 10"

CURVE DATA No. 3

P. I. Sta.
Δ = 60° 43' 03" Lt. Y = 25.53'
Dc = 5° 30' 00" L.T. = 267.18'
Ls = 400.00' S.T. = 133.80'
Rc = 1041.74' L.C. = 399.34'
θs = 11° 00' 00" Ts = 813.68'
P = 6.39' Es = 172.95'
K = 199.76' Lc = 703.95'
X = 398.53' Δc = 38° 43' 03"

CURVE DATA No. 4


P. I. Sta.
Δ = 74° 52' 50" Rt. Y = 7.20'
Dc = 2° 45' 00" L.T. = 200.06'
Ls = 300.00' S.T. = 100.05'
Rc = 2083.48' L.C. = 299.93'
θs = 4° 07' 30" Ts = 1746.61'
P = 1.80' Es = 542.86'
K = 149.97' Lc = 2422.93'
X = 299.84' Δc = 66° 37' 50"

CURVE DATA No. 5

P. I. Sta.
Δ = 53° 49' 25" Lt. Y = 26.68'
Dc = 5° 45' 00" L.T. = 267.23'
Ls = 400.00' S.T. = 133.85'
Rc = 996.45' L.C. = 399.28'
θs = 11° 30' 00" Ts = 708.91'
P = 6.68' Es = 128.51'
K = 199.73' Lc = 536.06'
X = 398.39' Δc = 30° 49' 25"

CURVE DATA No. 6

P. I. Sta.
Δ = 68° 53' 50" Rt. Y = 34.74'
Dc = 7° 30' 00" L.T. = 267.63'
Ls = 400.00' S.T. = 134.21'
Rc = 763.94' L.C. = 398.78'
θs = 15° 00' 00" Ts = 729.54'
P = 8.70' Es = 173.01'
K = 199.54' Lc = 518.63'
X = 397.27' Δ = 38° 53' 50"



LIMITED ACCESS HIGHWAY

I HEREBY CERTIFY THIS PLAT TO BE CORRECT

SIGNED BY Robert J. Schomer

Robert J. Schomer Reg. No. 713

RECEIVED FOR RECORD May 29 1959

RECORDED, VOL. 44 PAGE 45&46 OF THE MAHONING COUNTY RECORDS

AT 2:10 PM

William D. Hoff
RECORDER

CERTIFICATE OF APPROVAL

SIGNED BY James C. Ryan
CITY ENGINEER


SIGNED BY Paul Rappaport
DIVISION ENGINEER


MONUMENTS WILL BE SET ON CENTERLINE AT FOLLOWING STATIONS


STATION	DESCRIPTION	OFFSET
908+16.00	P.O.T.	
918+03.16	T.S.	
922+03.16	S.C.	
925+99.42	C.S.	5'Rt.
929+99.42	S.T.	5'Rt.
937+46.56	T.S.	5'Rt.
941+46.56	S.C.	5'Rt.
947+41.76	C.S.	5'Rt.
951+41.76	S.T.	5'Rt.
954+73.06	T.S.	5'Rt.
958+73.06	S.C.	5'Rt.
965+77.01	C.S.	
969+77.01	S.T.	5'Rt.
975+00	P.O.T.	
980+00	P.O.T.	
986+75.49	T.S.	5'Rt.
989+75.49	S.C.	5'Rt.

STATION	DESCRIPTION	OFFSET
994+00	P.O.C.	5'Rt.
999+00	P.O.C.	5'Rt.
1005+50	P.O.C.	
1013+98.42	C.S.	5'Rt.
1016+98.42	S.T.	5'Rt.
1018+50	P.O.T.	
1021+55.38	T.S.	5'Rt.
1025+55.38	S.C.	5'Rt.
1030+91.44	C.S.	5'Rt.
1034+91.44 } (Equation) 806+88.34	S.T.	5'Rt.
800+79.03	C.S.	5'Lt.
795+60.40	S.C.	5'Lt.
791+60.40	T.S.	5'Lt.
781+44.00	P.O.T.	

STATION	DESC.	OFFSET
962+00	P.O.C.	5'Rt.
978+50	P.O.T.	5'Rt.
1005+00	P.O.C.	5'Rt.
1010+00	P.O.C.	5'Rt.
804+79.03	S.T.	5'Lt.
784+00	P.O.T.	5'Lt.







NOTE: THIS CENTERLINE PLAT VOIDS AND SUPERSEDES PREVIOUS RECORDING OF CENTERLINE PLAT IN PLAT BOOK VOL. 44, PAGES 45 & 46 ON JUNE 1, 1959 - PER MONUMENT ASSEMBLY RELOCATIONS (℄ R/W I-680)

APPROVED _____ 19____

DEPUTY DIRECTOR OF PUBLIC WORKS

APPROVED _____ 19____

DIVISION DEPUTY DIRECTOR

RECEIVED _____ 19____

RE-RECORDED _____ 19____

BOOK _____, PAGE _____

COUNTY RECORDER

R238

$118.00

FED. RD.	STATE	PROJECT	
2	OHIO	MAH.-18-17.20	

468
492

SUMMARY OF R/W REQUIRED

CITY OF YOUNGSTOWN

PROJECT MAH-18-17.20

PARCEL NO.	OWNER	EXIST. BLDGS.	LOT NUMBER	AREA SQ.FT.	SHEET NO.	REMARKS
1-LA	Luigi Fulciniti	NO	17998	5,778	6	
2-LA	Peter & Helen Mikita	Yes	17999	5,000	6	
3-LA	William Pupa	Yes	18000	4,090	6	
3-WA	William Pupa	—	18000	—	6	Fill Basement
4-LA	Steve Dolak, Mary Dolak	Yes	18001	2,120	6	Take Shed
4-A-LA	Elizabeth Pedak	NO	18002	261	6	
6-LA	Mollie Barta	Yes	18011	5,625	6	
7-LA	Franciska Ondash	Yes	18012	5,000	6	
8-LA	Mathew A. Stankish, Mary Lou Stankish	Yes	18013	5,000	6	
9-LA	John Iwaniuk, Wasylyna Iwaniuk	Yes	18014	6,250	6	
10-LA	Frank Deak, Elizabeth Deak	Yes	18015	4,770	6	
11-LA	Mary Garcar	Yes	18016	2,850	6	
12-LA	John Krupa, Mary Krupa	NO	18017	136	6	
13-LA	Albert Fuzy, William A. Ambrose Mrs. Julia Karaka, Paul Fuzy	Yes	18024, 18025	6,728	6	
13-WA	Albert Fuzy, William A. Ambrose Mrs. Julia Karaka, Paul Fuzy	Yes	18025	—	6	Remove Garage Foundation
15-LA	Anne Chabala Leson	Yes	18026	5,000	6	
16-LA	Anne Shuster	Yes	18027	7,500	6	
18-LA	Mike Seman, Mary Seman	Yes	30896	3,750	6	
19-LA	Peter Kantor Jr., Ethel Moszaros	Yes	18029	6,250	6	
20-LA	Helen Kravec	Yes	18030	5,000	6	
26-LA	Andrew Anthol, Ann Cizmar Paul Anthol, Helen Yash	Yes	18031, 18032	3,820	6	
26-WA	Andrew Anthol, Ann Cizmar Paul Anthol, Helen Yash	Yes	18032	—	6	Remove Shed
22-LA	Mitro Mica, Annie Mica	NO	18043, 18044	4,950	6	
24-LA	James K. Walters	Yes	18046, 18047	11,849	6	
25-LA	Helen M. Bugno	Yes	18048	7,406	6	
28-LA	Anna Gonda	Yes	18037	5,000	6	
29-LA	Mary L. Adams	Yes	18038	5,000	6	
30-LA	Paul Bednarik	Yes	18039	4,100	6	
30-WA	Paul Bednarik	Yes	18039	—	6	Remove Garage Foundation
31-LA	Veronica Bundash	Yes	18040	2,050	6	
31A-LA	Michael Behun, Mary Behun	Yes	18040	403	6	
31-WA	Michael Behun, Mary Behun	Yes	18040	—	6	Fill Basement.
33-LA	Mickey Hanuschak, Flora J. Hanuschak	Yes	18142	3,400	6	
34-LA	John F. Tobin, Katherine Tobin	Yes	18142	1,438	6	
34-WA	John F. & Katherine Tobin	Yes	18142	—	6	Fill Basement
35-LA	Steve Matyl, Annie Matyl	Yes	18143	5,000	6	
36-LA	Sue K. Furden, Julia Kuni	Yes	18144	5,000	6	
37-LA	Joe Valush	Yes	18145	4,000	6	
38-LA	Anna Gaydos	Yes	18146	4,000	6	
39-LA	Andrew & Susie Lengyel	Yes	30200	4,125	6	
40-LA	Anna, John S., Joseph Yuhasz	Yes	18147	3,680	6	
41-LA	The Portland Land Co.	NO	43196, 18148	6,432	6	
43-LA	Annie Nelson	NO	18149	1,420	6	
46-LA	George Zahdrery, Elizabeth Zahdrery	Yes	33954	5,490	6	
46-WA	George Zahdrery, Elizabeth Zahdrery	Yes	33954	—	6	Fill Basement
47-LA	Anna Pavlik	No	33955	3,240	6	
48-LA	Mary Selenk	No	33956	689	6	
49-LA	Helen M. Cohn	NO	O.L. 421	68,111	6	
58-C-LA	Joseph S. Petrick, Maria Petrick	NO	33960	—	6	Loss of Access to Lakeview Ave.
58F-LA	Steven N. Bobovnych & Mary Bobovnych	NO	33961	3,808	6	
49A-LA	Joe Ince, Anna Ince	NO	18161	251	7	
51-LA	Betty Joe Yohman	NO	18162	1,203	7	
52-LA	Andrew Kosar, Helen Kosar	Yes	18163	2,080	7	
53-LA	Michael Nagy Jr.	Yes	28806	2,762	7	
53-A	Michael Nagy Jr.	Yes	28806	1,398	7	
54-LA	Margaret Bada	Yes	18164	3,672	7	
54-A	Margaret Bada	Yes	18164	488	7	
55-LA	Vincent F. Halko, Mary Ann Halko.	Yes	18165	5,000	7	
56-LA	Andy Lukac, Mary Lukac	Yes	18166	5,000	7	
57-LA	Alexander Barich, Mildred Barich	Yes	18167	13,720	7	
58E-LA	Mary Pauline Williams	NO	O.L. 422	20,600	7	
59-LA	Ginolamarca 1/2, Louise Lamarca	Yes	O.L. 421, 19654	6,265	7	
59A-LA	Ugo Dibacco 1/2, Anna Dibacco	Yes	19654	2,774	7	
60-LA	Paul Semai, Joan Semai	Yes	19655	5,000	7	
61-LA	Paul Gloval, Mary Gloval	Yes	19656	5,000	7	
64-SL	Andrew Tarkanich, Susie Tarkanich	NO	28810	23	7	Slope
62-LA	Dafini Negroff	Yes	18179	64	7	
62-S	Dafini Negroff	Yes	18179	256	7	
62-WA	Dafini Negroff	Yes	18179	—	7	Fill Basement
63-LA	Barbala or Barbara Burcsak	Yes	18180	705	7	
63-WA	Barbala or Barbara Burcsak	Yes	18180	—	7	Fill Basement
63-S	Barbala or Barbara Burcsak	Yes	18180	335	7	
67-LA	Mary Mazyrski	Yes	19657	5000	7	
71-LA	Andy L. & Anna C. Leskovec	NO	18188	360	7	
72-LA	Helen & Julianna Brogli	Yes	18189	980	7	
72-WA	Helen & Julianna Brogli	Yes	18189	—	7	Fill Basement
73-LA	Charles R. Kelly, Leona Code	Yes	18190	1,440	7	
73-WA	Charles R. Kelly, Leona Code	Yes	18190	—	7	Fill Basement
74-LA	Thomas A. & Bridget L. Denehy	Yes	18190, 18191	2,090	7	
75-LA	Andrew & Anna Bodnar	Yes	18191	1,950	7	
76-LA	Joseph Bankovitch	Yes	18192	3,040	7	
77-LA	John & Barbola Paul	Yes	18193	3,500	7	
79-LA	John & Anna Bobanich	Yes	19658, 19658	7,728	7	
80-LA	Anna Mozzy, Mary Bartell, Michael & Andrew Cycyk	Yes	19660	2,000	7	
80-WA	Anna Mozzy, Mary Bartell Michael & Andrew Cycyk	Yes	19660	—	7	Fill Basement
81-LA	John R., Charles E., Joseph T. Mary Ann, Catherine T. & Jennie S. March	Yes	19661	960	7	
81-WA	John, Charles, Joseph, Mary Ann, Catherine & Jennie March	Yes	19661	—	7	Fill Basement
83-LA	John Stun	Yes	38034	3,180	7	
84-LA	Aster Sklepko	Yes	19639	3,750	7	
85-LA	John & Anni Dzuroff	Yes	19640	5,000	7	
86-LA	Michael Sabol Jr., Martin Sabol, Mary Kavanaugh	Yes	19641	5,000	7	
87-LA	Mary Barolak, Roman, Edward, Emil, Joseph T. Barolak.	Yes	19642	5,000	7	
88-LA	Theresa Tobis or Therisa Tobis	Yes	19643	5,000	7	
89-LA	John J. & Agnes Bacak	Yes	19644	5,000	7	
90-LA	Joseph, Joseph E., Bernard, & George C. Knapic, Frances K. Acri.	Yes	19645	5,000	7	
91-LA	Wallace & Hilda Marie Dorko	Yes	19646	5,000	7	
92-LA	Martin & Anna Harchar	Yes	19647	5,000	7	
93-LA	Mary D. Olsavsky	Yes	19648	5,000	7	
94-LA	Karol & Anna Butek	Yes	19649	5,000	7	
95-LA	Mari or Mary Majorsky	Yes	19650	5,000	7	
96-LA	Veronica Missik	Yes	19652	5,000	7	
97-LA	John & Elizabeth Kiss	Yes	19653	5,000	7	
98-LA	George Bodnar Jr., Helen Bodnar	Yes	18284, 18285	10,680	7	
100-LA	Mary Adams	Yes	18286	5,000	7	
101-LA	John M. & Agnes Sudzina	Yes	18287	5,250	7	
102-LA	Bridget L. Ruane	Yes	18288	5,250	7	
103-LA	John & Barta Fetzer	Yes	18289	5,250	7	
104-LA	Zvonimir Roy & Rose M. Vulyak	Yes	18290	5,250	7	
105-LA	Anna Kachmar or Kachmer	Yes	18291	5,250	7	
106-LA	Michael & Elizabeth Yacko	Yes	18292	5,250	7	
107-LA	Peter & Mary Leman	Yes	18293	5,000	7	
108-LA	Valent Ledinko	Yes	18294	5,000	7	
109-LA	Gabor & Susie Toth	Yes	18295	5,000	7	
110-LA	Mathew & Anna G. Hamborsky	Yes	18296	5,000	7	
111-LA	Frank Barolak	Yes	18297	5,000	7	
112-LA	Joseph Andrews	Yes	18298	10,612	7	
113-LA	Michael Luzan	Yes	6783	6,142	8	
113-SA	Michael Luzan	Yes	6783	3,088	8	
114-LA	Julia Kun	Yes	6787	3,300	8	
114-SA	Julia Kun	Yes	6787	1,810	8	
115-LA	Mike & Mary Potocnak	Yes	6786	3,220	8	
115-SA	Mike & Mary Potocnak	Yes	6786	1,980	8	
116-LA	John & Catherine Smith	Yes	6785	3,106	8	
116-SA	John & Catherine Smith	Yes	6785	2,094	8	
117-LA	Frank Ferko	Yes	6782	2,964	8	
117-SA	Frank Ferko	Yes	6782	2,236	8	
118-LA	Paul & Anna Matuscak	Yes	6781	2,800	8	
118-SA	Paul & Anna Matuscak	Yes	6781	2,400	8	
119-LA	Bertha Hohos	Yes	6780	2,680	8	
119-SA	Bertha Hohos	Yes	6780	2,520	8	
121-LA	George A. & Catherine Bozich	Yes	6779	2,660	8	
121-SA	George A. & Catherine Bozich	Yes	6779	2,600	8	
122-LA	Joe & Mary Pisansky	Yes	6778	2,700	8	
122-SA	Joe & Mary Pisansky	Yes	6778	2,500	8	
123-LA	Andrew & Mary Tamboli	Yes	6778	2,740	8	
123-LA	Andrew & Mary Tambori	Yes	6778	2,460	8	
124-LA	Frank & Helen Paliga	Yes	6777	2,660	8	
124-SA	Frank & Helen Paliga	Yes	6777	2,540	8	
125-LA	Katarina Giba	Yes	11782	3,209	8	
125-SA	Katarina Giba	Yes	11782	5,880	8	
127-LA	Paul & Irene Koval	Yes	42446	8,840	8	
128-LA	Susanna Kramer	Yes	42447	5,200	8	
129-LA	George Lutza Jr.	Yes	42448	5,200	8	
130-LA	Mathew & Anna Koval	Yes	42449	1,540	8	
130-SA	Mathew & Anna Koval	Yes	42449	720	8	
130-WA	Mathew & Anna Koval	Yes	42449	—	8	Fill Basement
131-LA	Stevan & Anna Hoffman	Yes	42450	3,180	8	
131-SA	Stevan & Anna Hoffman	Yes	42450	6,204	8	
131-WA	Stevan & Anna Hoffman	Yes	42450	—	8	Fill Basement
133-LA	St. Michaels Russ. Orth. Gr. Cath. Church	Yes	O.L. 145	48,376	8	
133	St. Michaels Russ. Orth. Gr. Cath. Church	Yes	O.L. 145	750	8	
133-WA	St. Michaels Russ. Orth. Gr. Cath. Church	Yes	O.L. 145	—	8	Remove Foundation
134-LA	Mahoning Valley Sanitary District	No	O.L. 415, 416, 420	50,220	8	
135-LA	John Sahlica	No	O.L. 415	12,982	8	
136-LA	Serbian Eastern Orth. Congregation	No	O.L. 416	130,633	8	
136-S	Serbian Eastern Orth. Congregation			715	8	
140-LA	Berkeley, Bertha, Irving & Bernice Fromkin	Yes	O.L. 420	307,525	8	
140-SA	Berkeley, Bertha, Irving & Bernice Fromkin	No	O.L. 420	9,080	8	
143-LA	Geisi & Christina Passarella	No	O.L. 419	362,655	9	
144-LA	Baltimore & Ohio R.R.	No	—		9	
144-S	Baltimore & Ohio R.R.	No	—		9	
145-LA	Angelo, Mark, John, & Joseph Passarelli	No	O.L. 419	39,920	9	
146-LA	Gohgie Realty Co.	Yes	O.L. 428	42,742	9	146-19,400± Eligible for Federal Part.
146A-LA	Baltimore & Ohio R.R.	No	—		9	
147-LA	Joe Maskulka, Gemma Badino	Yes	O.L. 428	30,050	9	
148-LA	Sam Margolis	Yes	O.L. 428	71,000	9	148-9000± Eligible for Federal Part.
149-LA	John & Andrew Fusco	Yes	O.L. 495	43,560	10	
150-LA	Joseph & Robert Jenkins	Yes	O.L. 410	50,701	10	
150-WA	Joseph & Robert Jenkins	Yes	O.L. 410	—	10	Fill Basement
150A-LA	Paul Pagac	No	O.L. 410	4,290	10	
150B-LA	Ella Louise Wick	No	O.L. 410	333	10	
151-LA	Theodore Saroka, Gino Parisi	Yes	O.L. 496	12,550	10	
154-LA	Margaret B. Sittinger	Yes	12145	2,350	10	
155-LA	The Youngstown Dunbrik Co.	Yes	O.L. 497	55,321	10	
154-A	John R. McGee	No	O.L. 447	377.5	10	
159-LA	Vince Minor	No	12150	8,118	10	
160-LA	Bernard Bruss	Yes	12152	4,590	10	
161-LA	Leo & Bernard Bruss	Yes	O.L. 408	33,350	10	
161-SA	Leo & Bernard Bruss	Yes	O.L. 408	65,080	10	

Fill Basement

Pcl. 64-SL	Added	10-6-61
Pcl. 49-LA	Name Change	10-5-60
Parcel 133-S	To 133	7-6-60
Parcel 125-LA	Area Revised	7-6-60
Parcel 151-LA	Area Revised	7-6-60
Parcel 149-LA	Area Revised	7-6-60
Parcel 125-S	Revised	6-30-60
Parcel 149-LA	Revised	6-27-60
Parcel 154-A	Revised	6-23-60
Parcel 185-LA	Area Revised	5-10-60
158-LA	Deleted	4-21-60
Sheet Reference No. 3	Revised	4-20-60
Added Fed. Part. Pcls. 146LA & 148LA.		5-7-60

FED. RD.	STATE	PROJECT	
2	OHIO	MAH. 18-17.20	

469 492

SUMMARY OF R/W REQUIRED

CITY OF YOUNGSTOWN
PROJECT MAH.-18-17.20

PARCEL NO.	OWNER	EXIST. BLDG.	LOT NO.	AREA S.F.	SHEET NO.	REMARKS
170-LA	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.483-489	113,590	11	CONSTRUCTION OF PARK ROAD
170-T	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.484	134,950	11	
170-AERIAL	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.480	55,167	11	
170	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.484	1,578	11	
170-B	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.480	1,578	11	
170-C	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.480	1,578	11	
170-D	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.480	1,578	11	
171-LA	CALIXTE JOSEPH GAUDET, EDNA MAY GAUDET	YES	6826,6827	15,960	11	
173-LA	WILLIAM W. NEFF, ARMIDA NEFF	YES	6828	7,625	12	
174-LA	HAROLD AND ETHEL GASKINS	YES	6829	7,625	12	
175-LA	JOHN J. CIKA, DOROTHY A. CIKA	YES	14285	2,290	12	
176-LA	JAMES A. POTTER, PAULINE POTTER	YES	14285	2,290	12	
177-LA	ISALY DAIRY COMPANY	YES	6831	10,215	12	
178-LA	THE DOLLAR SAVINGS & TRUST COMPANY TRUSTEE	YES	2475	7,634	12	
179-LA	JOHN WILLIAMS, LOU GENIA WILLIAMS	YES	2476	6,940	12	
180-LA	DOUGLAS JONES, CHESTINA JONES	YES	2477	6,940	12	
181-LA	BESSIE AGRENOVITZ	YES	2478	6,940	12	
182-LA	JESSIE DOUGLAS, CHRISTINE DOUGLAS	YES	2360,2479	5,028	12	
183-LA	MARY G. REITZELL, FLORA A. REITZELL	YES	2480,2360	6,940	12	
184-LA	BENJAMIN VERNON, CLARA VERNON	YES	2481	3,960	12	
185-LA	GILSON T. GRAHAM	YES	2479	3,300	12	
186-LA	ANNIE K. HARPER ROBINSON, ALIAS ANNIE SIMMONS	YES	2481	1,560	12	
187-LA	S & G REALTY COMPANY	YES	6837	7,640	11	
188-LA	EULALIAM M. LUTHER	YES	6836	5,900	12	
189-LA	ROSINA SCHNEIDER	YES	6835	6,000	12	
190-LA	JAMES ARTHUR ROSS, ANNIE B. ROSS	YES	6834	6,250	12	
191-LA	ETHEL GILFILLAN	YES	6830	3,300	12	
192-LA	D.N. GARVER, MARTHA E. GARVER	YES	14285	7,695	12	
193-LA	CLYDE E. TRUITT, DOROTHY C. TRUITT	YES	6833	3,630	12	
194-LA	TUFIC SAADI	YES	6832	5,066	12	
195-LA	CHARLOTTE BYERS	YES	6832	5,066	12	
196-LA	MARTIN BOKESCH, CHRISTINA BOKESCH	YES	2488	3,924	12	
197-LA	IRENE H. VANMETER	YES	2488	3,252	12	
198-LA	JOSEPH STOKAN	YES	2487	~~6,940~~	12	
200-LA	KATHLEEN WATKINS	YES	2485	6,940	12	
201-LA	KATHERINE B. WILSON	YES	2484	6,940	12	
202-LA	JAMES ANDERSON	YES	2482,2483	4,500	12	
203-LA-204-LA	FLORENCE APPEL DORFF, HELEN APPEL LEWIS, CLARA APPEL CASSESE	YES	2482,2483	9,300	12	
205-LA	CLARENCE C. MCKELRY, ELIZABETH MCKELRY	YES	3411	9,000	12	
206-LA	THOMAS A. MUMFORD	YES	3412	7,500	12	
207-LA	LILLIAN B. JONES RAFE	YES	3413	6,000	12	
208-LA	JESUS HERNANDEZ, MARY E. HERNANDEZ	YES	O.L.374	3,108	12	
209-LA	LEONARD HALLEWELL, ESTELLA HALLEWELL	YES	O.L.374	3,009	12	
209-A-LA	JAMES BROWN	YES	O.L.374	2,549	12	
210-LA	FREDERICK LEROY TAYLOR, GRACE VERA TAYLOR	YES	O.L.374	6,425	12	
211-LA	JOSEPH ANDROSEK, WALSH AND ROBERTS INC.	YES	O.L.374	3,606	12	
211-A-LA	FREDA C. ANDERSON	YES	O.L.374	2,903	12	
211-B-LA	JAMES DOMINIC PRECURATO, MARY DELORES PRECURATO	YES	3659	4,902	12	
212-LA	T. SAADI	YES	3679	4,500	12	
213-LA	HOWARD JAMES, WILLIE MAY JAMES	YES	3409	2,910	12	
214-LA	ARTHUR I. WALDMAN	YES	3409	7,275	12	
215-LA	JAMES MONROE LONG	YES	3410	~~4,940~~	12	
216-LA	ROY F. MORT	YES	3414	9,675	12	
217-LA	WILLIAM J. AND MARY G. PETRANSKY	YES	3408	3,300	13	
217-A-LA	JOSEPH AND LOUISE C. PETRANSKY	YES	3408	1,700	13	
218-LA	FLORENCE POTOR	YES	5677	5,000	13	
219-LA	JOSEPH GIERCHAK, ANGELINE GIERCHAK	YES	5678	5,000	13	
220-LA	BESSIE AND HARRY WILLIAMS	YES	9507	6,000	13	
221-LA	GUS COHEN, RUTH D. COHEN	YES	9507	7,163	13	
222-LA	THOMAS J. MYERS	YES	3964	7,500	13	
223-LA	WM. F. AND HELEN MOSKOSKY	YES	3966	7,500	13	
224-LA	OTTO C. BROOKS	YES	3968	5,000	13	
225-LA	ARTHUR AND LESSIE MARTIN	YES	3968	8,920	13	
226-LA	WILLIAM AND SUSIE M. KIDD	YES	3970,10108	12,291	13	
227-LA	WILLIAM DUDLEY	YES	10371	11,449	13	
228-LA	MATTIE MCPETERS	YES	10370	11,734	13	
229-LA	WILLIAM VONKENNEN JR.	YES	3972,10369	11,000	13	
230-LA	MIKE AND BERTHA GLAVIES	YES	3973	7,500	13	
231-LA	MARY ELIZ. MCKLUSKY	YES	3974	6,825	13	
232-LA	MARGARET M. MAIN, MARGARET L. TRIGG	YES	3974,3975	8,325	13	
233-LA	HILDEGARD HUEBERGER COURT	YES	10369	9,672	13	
233-A-LA	GEORGE F. MAIN	NO	19766	25,160	13	
234-A	CAROLINE THRASH	YES	O.L.382	3,395	13	
170-A-LA	BOARD OF PARK COMMISSIONERS OF YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L. 489	7,735	11	
170-B-LA	UNION NATIONAL BANK OF YOUNGSTOWN ET-AL	YES	5747	3,210	10	
199-LA	JOSEPH STOKAN	YES	2486	6940	12	
236-LA	JACKSON STEWART, ANNE STEWART	NO	11226	110	13	
237-LA	WILLIAM H. WILLIAMS, EVELYN L. WILLIAMS	YES	11227	5,313	13	
238-LA	OTTO GEISHLER, EMMA GEISHLER	YES	19708	6,000	13	
239-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	NO	2366	6,206	13	
240-LA	JULIA KICZ	YES	2365	5,029	13	
241-LA	DAVID SCOTT	YES	2364,872	5,776	13	
241-A-LA	CLARENCE DANIEL	NO	57185	1,608	13	
242-LA	CLARENCE DANIEL	YES	874	~~2,144~~	13	
242-A-LA	RUTH FRANKLIN	YES	873	6,420	13	
242-B-LA	MARGARET BIELER	NO	874	697	13	
243-A-LA	Alex JONES	YES	55603	5,242	13	
244-LA	BOSS JACKSON, OLLIE JACKSON	YES	11349	2,360	13	
245-LA	ZORA PRISBY	YES	11348	4,800	13	
245-A-LA	MARGARET M. MAIN, MARGARET L. TRIGG	NO	19771-2-3, 19770	12,978	13	
246-LA	MAMIE L. CODY	NO	4821	4,000	13	
249-LA	MILTON A ROEMISCH (TRUSTEE)	NO	4822,39292	8,565	13	
250-LA	MARY K. KING ET-AL	YES	39293	5,000	13	
251-LA	Y.Z. ADAMS, THELMA ADAMS	YES	39294	5,000	13	
251-A-LA	ELIGHA KING, ANITA KING	YES	39296	4,369	13	
252-LA	CARL H. HOLQUIST, MARY E. HOLQUIST	YES	2361	5,000	13	
252-A-LA	OZZIE CURRY	YES	2359	675	13	
252-WA	CARL H. HOLQUIST, MARY E. HOLQUIST	YES	2361		13	REMOVE GARAGE FOUNDATION
252-A-WA	OZZIE CURRY	YES	2359		13	REMOVE GARAGE FOUNDATION
253-LA	ELLA RODGERS	YES	2362	960	13	
253-A-LA	W.J. WADKINS, MAUDE S. WADKINS	YES	11222	5,450	13	
253-B-LA	ALEXANDER WILLIAMS, EDITH WILLIAMS	YES	11221	4,653	13	
253-C-LA	SAM D. CLARK, KATIE CLARK	YES	9436	1,299	13	
253-D-LA	JULIUS DICKENS, BERTHA DICKENS	YES	4754	3,690	13	
253-D-A	JULIUS DICKENS, BERTHA DICKENS					
253-F-LA	LOUIS E. CAPPELLO	YES	9436	1,148	13	
253-G-LA	LUCY BEVERLY	YES	9435	1,800	13	
253-H-LA	THE CENTRAL DISTRICT OF THE LUTH. CHURCH MO. SYNOD INC.	YES	30330	1,936	13	
253-I-LA	WALTER NORTH, LYDIA NORTH	NO	9437	510	13	
253-K-LA	RAYMOND WALLACE, LOUISE WALLACE	YES	55605	1,457	13	
253-L-LA	COURTLAND ALLEN, ROSE ALLEN	YES	9435	1,140	13	
253-M-LA	DR. NELSON INGRAM, THELMA INGRAM	YES	4755	3,780	13	
253-M-A	DR. NELSON INGRAM, THELMA INGRAM				13	
253-P-A	ROBERT H. AND EDNA KING				13	
253-A-A	W.J. WADKINS, MAUDE S. WADKINS	YES	11222		13	
253-B-A	ALEXANDER WILLIAMS, EDITH WILLIAMS	NO	11221		13	
253-H-A	THE CENTRAL DISTRICT OF THE LUTH. CHURCH MO. SYNOD INC.	YES	30330		13	
253-J-A	WALTER NORTH, LYDIA NORTH	YES	9437	5,440	13	
253-L-A	COURTLAND ALLEN, ROSE ALLEN	YES	9435		13	
253-WA	ELLA RODGERS	YES	2362		13	FILL BASEMENT
253-A-LA	BESSIE THOMAS	YES	55604	1,631	13	
255-LA	CLARENCE FRANKLIN	YES	3915	5,200	13	
256-LA	WILLIAM B. ROSS, MARY I. ROSS	YES	3918	4,600	13	
258-LA	FLORENCE LULA TAYLOR	NO	15906,15907	6,700	13	
259-LA	BESSIE E. MOORE	YES	15908	3,600	13	
260-LA	JOHN HAYMAN	YES	3919	3,600	13	
261-LA	CHARLES POLISKY ET AL	YES	3919	4,000	13	
262-LA	BESSIE WALKER	YES	877	15,000	13	
262-A-LA	UNION NATIONAL BANK OF YOUNGSTOWN	NO	39295	400	13	
262-C-LA	ALLEN J. STUMP, VIOLA V. STUMP	YES	877	5,427	14	
262-D-LA	LOUIS H. MAUSER	YES	5666	5,720	14	
262-E-LA	EDWARD VELAR	YES	2351	6,000	14	
262-F-LA	TUFIC SAADI	YES	876	6,889	14	
262-H-LA	LAURA GARDNER	YES	2352	3,580	14	
262-I-LA	GEORGE SUBER, PEARL SUBER	NO	2353	306	14	
262-C-WA	ALLEN J. STUMP, VIOLA V. STUMP	YES	877		14	REMOVE GARAGE FOUNDATION
262-F-WA	TUFIC SAADI	NO	876		14	FILL BASEMENT
262-H-WA	LAURA GARDNER	YES	2352		14	REMOVE GARAGE FOUNDATION
263-LA	UMBERTO TURSINI	YES	56002	2,530	14	
264-LA	WILLIAM MOSKOSKY, HELEN MOSKOSKY	NO	O.L.122	48,620	14	
265-LA	ALTON L. KEMP, ALICE L. KEMP	YES	56003	11,109	14	
265-A-LA	MARY LUNDY	YES	56004	7,511	14	
265-B-LA	FRANK J. COLLA	YES	56005	7,508	14	
266-LA	JAMES LADIGO	YES	56006	7,462	14	
266-B-LA	JOSEPH M. ALLISON, MARIAN A. ALLISON	YES	56007	7,459	14	
266-C-LA	THOMAS HOOD	YES	56008		14	
267-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	YES	O.L.125	68,502	14	
267-A-LA	ESTER MEYER	NO	55066	1,262	14	
267-B-LA	VANCE WAGNER	YES	5661	1,826	14	
267-C-LA		NO	55067	690	14	
267-D-LA	MINNIE MAUSER	YES	876	1,000	14	
267-E-LA		YES	55072	3,855	14	
267-D-WA	MINNIE MAUSER	YES	876		14	
268-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	NO	55070	5,202	14	FILL BASEMENT
268-A-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	NO	55069	278	14	
269-LA	INEZ PARKER	YES	10969	4,200	14	
271-LA	HARRY AND NELLIE MEYERS	YES	36391	2,400	14	
271-A-LA	GOLDEN AGE BEVERAGE CORPORATION	NO	36392	1,050	14	
271-B-LA		YES	55078		14	
271-WA	HARRY AND NELLIE MEYERS	NO	36391		14	
272-LA	MALACHI STOKES, THELMA STOKES	YES	10966	3,702	14	FILL BASEMENT
273-LA	JOHN G. SPATHOLT	YES	10965	1,800	14	
273-A-LA	JOHN G. SPATHOLT	YES	10966	2,080	14	
273-B-LA	JOHN G. SPATHOLT	YES	10966	1,870	14	
276-A-LA	FRED AND ROISE PERKINS ET-AL			767		
243-LA	CLARENCE DANIEL	YES	874	3,216	13	

Parcel 243-LA Added 12-15-60
Parcel 242-LA Revised 12-15-60
Parcel 199-LA Added 12-15-60
Parcel 198-LA Revised 12-15-60
Parcel 215-LA Revised 7-13-60
Parcels 253-1A & 253-K-LA Revised 7-13-60
Removed House Pcl. 253-J-LA Added House 253-I-A 7-8-60
Pcls. 268-LA & 268-A-LA Added Names & Area 7-6-60
Parcels 271-A-LA & 276-A-LA Names Changed & Area 7-6-60
Parcel 170-T Changed From Work Agree. To Temp. 7-6-60
Parcel 170-B-LA Revised 6-27-60
Parcel 170-B-1-LA Revised 6-27-60
Parcel 250-LA, 242-B-1-LA Revised 6-27-60
Parcels 253-LA & 253-K-LA Revised 6-15-60
Parcel 170-LA, 170-T Revised, 170-B, 170-B-1-A Added 4-21-60
Sheet Reference Nos Revised 4-20-60

I-680 R/W SHEET 4 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH.-18-17.20	

470 / 492

SUMMARY OF R/W REQUIRED

CITY OF YOUNGSTOWN
PROJECT MAH.-18-17.20

PARCEL NO.	OWNER	EXIST. BLDG.	LOT NO.	AREA S.F.	SHEET NO.	
273-C-LA	JOHN G. SPATHOLT	YES	10967	3,150	14	
274-LA	JOHN H. LOGAN, LULA LOGAN	YES	10964	2,230	14	
275-LA	LEROY SMITH, NETTIE SMITH	YES	10964	1,625	14	
275-A-LA	JOHNNIE PEARL REED	YES	10965	1,587	14	
276-LA	FRED AND ROSIE PERKINS	YES	10963	1,932	14	
277-LA	THEODORE COTTON JR. AND CARRIE COTTON	YES	10962	1,613	14	
279-LA	ANN KAUFMAN, BETTY LABEL	YES	5619	4,950	14	
280-LA	GOLDEN AGE BEVERAGE CORP.	YES	846	19,557	14	
283-B-LA	HOWARD BURKES, MILLERNEE BURKES	YES	5619	2,600	14	
283-B-WA	HOWARD BURKES, MILLERNEE BURKES	YES	5619		14	FILL BASEMENT
284-LA	EUGENE ROBINSON, JR., LAURA B. ROBINSON	YES	8141	2,200	15	
284-A-LA	LILTON MORRIS	YES	8141	891	15	
284-A-WA	EUGENE ROBINSON, LAURA ROBINSON	NO	8141		15	FILL BASEMENT
285-LA	BOOKER T. AND MARY HELEN WRIGHT	YES	843	3,900	15	
285-A-LA	EDWARD AND SUSIE MCELROY	YES	843	1,200	15	
286-LA	ANAM ABDO	YES	5646	3,555	15	
286-B-LA	MATHILDA WIEDMAN	NO	5647	1,550	15	
287-LA	GOLDEN AGE BEVERAGE CORP.	NO	5645,842	9,025	15	
287-A-LA		NO	841		15	
287-B-LA	*ROBINA POWELL*	YES	840	300	15	
287-C-LA		YES	842		15	
287-B-WA		YES	940		15	FILL BASEMENT
289-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	NO	55071	3,600	14	
289-A-LA	WALDEMAR NISCHWITZ, EARL H. HARRIS	NO	10971	1,157	14	
290-LA	ETHEL MCDANIELS SPEAKS	YES	10970	2,948	14	
291-LA	ELIZABETH BUEHRLE	NO	55075	2,282	14	
292-LA	WALDEMAR NISCHWITZ, EARL H. HARRIS	YES	2249	5,939	14	
294-LA	WILLIAM AILEN, ANNIE ALLEN	YES	2248	3,943	14	
295-LA	MARY PEAY	YES	2247	4,180	14	
296-LA	ELIDA MOELLERING	YES	2246	4,350	14	
297-LA	WILLIAM E. AND PEARLE HERRING	YES	2245	4,750	15	
298-LA	CORA B. SCHEIBLE	YES	2244	5,200	15	
299-LA	LILLIE M. BUYCK	YES	2243	5,450	15	
299-A-LA	*JOHANNA SPRAGUE*	NO	850	476	15	
300-LA	MICHEAL F. AND BLOSSOM W. MEENACHAN	YES	2242	5,450	15	
300-A-LA	MILDRED D. PLANIN (PLANINA)	NO	1575	1,323	15	
301-LA	RICHARD L. AND LEO BENNETT	YES	2241	5,600	15	
302-LA	HENRY AND ARTHOLS BARNES	YES	2240	5,450	15	
303-LA	BEN H. CATLEY	NO	851	1,953	15	
304-LA	H.K. ZIEGLER	YES	2239	5,720	15	
305-LA	UNDEPENDENT INVESTMENT COMPANY	NO	852	2,320	15	
306-LA	ELLEN LEWIS	YES	2237	4,189	15	
307-LA	LAVERNE BOWENS	YES	2238	2,860	15	
308-LA	JULIA KICZ	YES	36651	1,824	15	
309-LA	MINNIE WILBURN	YES	853	3,884	15	
310-LA	THIRD BAPTIST CHURCH OF YOUNGSTOWN	YES	2237	9,360	15	
311-LA	CELIA BERNSTEIN	YES	854	11,925	15	
312-LA	WILLA MAE (RICE) AND HUGHES CAMPBELL	YES	2238	1,976	15	
313-LA	LAKE ERIE AND EASTERN RAILROAD	YES	1550	10,600	15	
313-A-LA	LAKE ERIE AND EASTERN RAILROAD	YES	1550	14,375	19	
313-A	LAKE ERIE AND EASTERN RAILROAD	YES	1550	40,511	19	
313-B- A	THE SPUR DISTRIBUTING COMPANY	YES	1549	*10,000*	19	
313-WA	LAKE ERIE AND EASTERN RAILROAD	YES			19	REMOVE CONCRETE SILO
314-LA	RUBE AND MARY F. SMITH	YES	1557	24,000	15	
315-LA	W.E. STANKIEWICZ	YES	1568	9,120	15	
315-WA	W.E. STANKIEWICZ				15	FILL BASEMENT
316-LA	HAROLD STEIN, SAM SIMON, MILTON H. SIMON	YES	1552	17,355	15	
316-A	HAROLD STEIN, SAM SIMON, MILTON H. SIMON	NO	1552	1,005	15	
318-LA	YOUNGSTOWN HOSP. ASSOC.	YES	1568	158,970	16	
318-WA	YOUNGSTOWN HOSP. ASSOC.	YES	11100,11101		16	FILL BASEMENT
319-LA	THE RENNER CO.	YES	1559,1560	32,670 or 0.75	16	
319-WA	THE RENNER CO.	YES	1559		16	REMOVE FOUNDATION
320-A-LA	ANNA M.PATTERSON	YES	11097	4,500 4/1/66	16	
321-LA	PHILIP GREIN	YES	11095,11096	9,140	16	
321-WA	PHILIP GREIN	YES	11094		16	REMOVE FOUNDATION
322-LA	JOHN BOGGANS, ET AL	YES	1561,5617	18,780	16	
323-LA	EUGENE AND ESTER RUSNAK	YES	11093,11094	2,600	16	
323-WA	EUGENE AND ESTER RUSNAK	YES	11094		16	REMOVE FOUNDATION
326-LA	RIDGE MEDICAL BLDG. CO.	YES	3211,5622	42,609	17	
326-WA	RIDGE MEDICAL BLDG. CO.	YES	3211		17	REVISE DRIVEWAY
327-LA	ELIZABETH GEORGE	YES	3335	8,956	17	
328-LA	LUCY S. MIKITA	YES	3336	6,350	17	
329-LA	LESLIE H. SABO, ELIZABETH H. SABO	YES	3337	3,409	17	
329-A-LA	M. VERA HERSCHEL	YES	3337		17	
330-LA	ANTHONY P. JULIUS	YES	3338	6,250	17	
331-LA	JOSEPH SARISKY	YES	3339	5,666	17	
332-LA	MYRTLE I. MILLER, VIRGINIA VIETS CRAMER, DOROTHY VIETS GLINES	YES	3340	6,600	17	
332-WA	MYRTLE I.MILLER,VIRGINIA VIETS CRAMER,DOROTHY VIETS GLINES	YES	3340,3341		17	FILL BASEMENT
333-A-LA	JOHN DORLOSAN, MARY DORLOSAN	YES	3327	1,250	17	
333-WA	JOHN DORLOSAN, MARY DORLOSAN	YES	3327		17	FILL BASEMENT
333-B-LA	GERALD CARROLL AND ALICE CARROLL	YES	3327		17	
334-LA	TUFIC SAADI	YES	3328	7,500	17	
335-LA	LALE GRAHOVAC	YES	3329	7,500	17	
336-LA	JOSEPH THURIK, MARY THURIK	YES	3330	7,500	17	
337-LA	THE INCORPORATED TRUSTEES OF THE GOSPEL WORKER SOC.	YES	3331,5628	7,500	17	
338-LA	MILDRED MCDONALD	YES	3332	7,000	17	
339-LA	RALPH A. KELLY, ISABELLA M. KELLY	YES	3333	7,344	17	
339-WA	RAL.H A. KELLY, ISABELLA M. KELLY	YES	3333,5176		17	REMOVE FOUNDATION
340-LA	CHARLOTTA FISLAK	YES	5176	5,436	17	
341-LA	JOHN W. TOMALKA SR., MARY HAZEL TOMALKA	YES	5179	2,675	17	
342-LA	ELIZABETH HILLOSKY,SR.	YES	5181	2,225	17	

PARCEL NO.	OWNER	EXIST. BLDG.	LOT NO.	AREA S.F.	SHEET NO.	
342-A-LA	FLORENCE L. EVANS	YES	5183	1,573	17	
342-WA	ELIZABETH HILLOSKY, SR.	YES	5181		17	FILL BASEMENT
342-A-WA	FLORENCE L. EVANS	YES	5183		17	FILL BASEMENT
344-LA	FRANK JAMES COLLA	YES	55466	3,724	17	
344-A	THE GREEK COMM. AGLOS LOANNIS ORTHODOX CHURCH	NO	O.L.363	336	17	
344-B-LA	FRANK JAMES COLLA	NO	55466	315	17	
345-LA	MARY DEVAN	YES	55467	5,366	17	
346-LA	CLARA ANDERSON	YES	55466	7,335	17	
347-LA	FRANK JAMES COLLA	YES	55469	3,525	17	
* 348-LA	JOHN PAUL	YES	2308	3,150	17	
* 350-LA	JOHN BUDAKER, ANN BUDAKER	YES	2309	4,100	17	
352-LA	LEROY E. BILLIG	YES	5185	1,025	17	
352-WA	LEROY E. BILLIG	YES	5185		17	FILL BASEMENT
352-A-WA		YES	5186		17	FILL BASEMENT
352-A-LA	MARY J. COMINOS	YES	5186	320	17	
353-LA	MORTON, RAYMOND D. AND BERNARD WHITE	YES	2899	5,000	17	
353-WA	RALPH A. KELLY, ISABELLE M. KELLY	YES	2899		17	REMOVE FOUNDATION
356-LA	THE GENERAL ELECTRIC COMPANY	NO	2314,2315,2296,2298	37,700	17	
356-TS	THE GENERAL ELECTRIC COMPANY	NO	2313,2314, 2296,2298	4960	17	CONST. EQUI.. ACCESS
358-LA	THE ROAD OF REMEMBRANCE POST #472 AM. LEGION DEPT. OF OHIO	YES	2314	10,750	17	
359-LA	JAMES E. & WENDELL H. BENNETT, IDA JOSEPHINE DATSON	YES	2313	7,325	17	
359-A-LA	JAMES E. & WENDELL H. BENNETT, IDA JOSEPHINE DATSON	NO	2313	1,050	17	
360-LA	HAROLD P. SMITH, EMILY E. SMITH	YES	2313	3,950	17	
360-WA	HAROLD P. SMITH, EMILY E. SMITH	NO	2313		17	FILL BASEMENT
361-C-LA	*NORTHERN INVESTMENT COMPANY*	NO	2311	125	17	
362-LA	TINCO DE CARPENTIER	YES	3346	31,857	19	
362-WA	TINCO DE CARPENTIER	YES	3346		19	FILL BASEMENT
363-LA	RALPH E. GOFF, AGNES E. GOFF	YES	3344	9,750	19	
364-LA	JOHN COMEK, MARY COMEK	YES	3369	4,430	19	
365-LA	SARAH KLATMAN, HANNAH KLATMAN	YES	3369	2,275	19	
366-LA	FAY KIRKORSKY	YES	3368	4,748	19	
367-LA	IDEALIA HOWELL, EUALEE HOWELL	YES	3368	5,080	19	
368-LA	JAMES DAVIS, EULA MAE DAVIS	YES	3367	5,420	19	
369-LA	CARRIE E. WATSON	YES	3366	5,840	19	
370-LA	THE ECONOMY ELECTRIC COMPANY	YES	3349	3,094	19	
370-WA	THE ECONOMY ELECTRIC COMPANY	YES	3349		19	REMOVE FOUNDATION AND GRADE AREA
371-LA	DOROTHY MOHN	YES	3365	6,200	19	
372-LA	DEMETRIOS AND MAVRIKIS	YES	3365	5,063	19	
373-LA	SOPHIA MARGOLIS	YES	3364	5,687	19	
374-LA	EDWARD PARKMAN, MYRTLE L. PARKMAN	YES	3363,3364	5,871	19	
375-LA	JOHN SPANOS, ALEXANDRA SPANOS	YES	3363	5,731	19	
376-LA	MARY H. MENEGAY, CLARA L. PAAR	YES	3362	6,000	19	
377-LA	NICHOLAS GLAROS, NIKI GLAROS	YES	3361	6,780	19	
378-LA	JOHN SERINO AND MARY MARZULLO	YES	3360	5,467	19	
378-WA	JOHN SERINO AND MARY MARZULLO	YES	3360		19	FILL BASEMENT
379-LA	ROSE KNABEL	YES	11061	2,650	19	
379-WA	ROSE KNOBEL	YES	11061		19	FILL BASEMENT
380-LA	MARY DEVAN	YES	3359	8,180	19	
381-LA	HENRY B. GESSAMAN, VIRGINIA GESSAMAN	YES	3358	3,518	19	
382-LA	NORQUIST LAND COMPANY	YES	3358	3,468	19	
383-LA	JOHN J. VERNELLO, EDNA M. VERNELLO	YES	3357	3,350	19	
383-B-LA	MARY C. CARTWRIGHT, MARGARET CONROY	YES	3357	3,252	19	
384-LA	WILMA V. GING	YES	3356	6,090	19	
384-WA	WILMA V. GING	YES	3356		19	FILL BASEMENT
387-LA	THE BOARD OF EDUCATION OF YOUNGSTOWN CITY SCHOOL DISTRICT	YES	3355	26,418	19	
390-LA	FREDRIKA H. BOGGS, MINTER B. BOGGS	YES	3375	3,750	19	
390-A-LA	JAMES WALSH JR.	YES	3375		19	
391-LA	ROSE EVELYN STRAWDERMAN	YES	3376	2,000	19	
391-A-LA	MILTON KIBBLE, MARY LOU KIBBLE	YES	3375		19	
392-LA	GIUSEPPE CHIRCHIGLIA, ROSE CHIRCHIGLIA	YES	3376	2,000	19	
393-LA	FAY KIRORSKY	YES	3377	1,875	19	
394-LA	MATTIE B. TERRELL	YES	3377	3,750	19	
395-LA	EVA WILLIAMS, ROBERT WILLIAMS	YES	3378	3,750	19	
397-LA	CHESTER V. LONG, MARGARET F. LONG	YES	3379	3,675	19	
406-LA	CLOYDE JAMES FRY, ROBERTA MARION FRY	YES	36130	4,600	19	
406-A-LA, 406-B-LA, 406-B-WA	UNCLAIMED	YES	1695		19	
407-LA	LOUIS HARRINGTON, JULIA HARRINGTON	YES	1696		19	
425-LA	SOPHIE COHEN	YES	1695,1696		19	FILL BASEMENT
426-LA	GEORGE BRADLEY, FRANCES JUNE BRADLEY	YES	1701	10,593	19	
427-LA	HELEN BUGNO	YES	1700	10,923	19	
428-LA	EDWARD WILLIAMS, J.B. WILLIAMS	YES	1700	5,958	19	
428-LA	GRANT BARNETT, JOSEPHINE BARNETT	YES	1697	4,377	19	
429-WA	GRANT BARNETT, JOSEPHINE BARNETT	YES	1694	2,160	19	
430-LA	JOHN MCCARTY SCHWARTZ	YES	1694	1,485	19	
430-WA	JOHN MCCARTY SCHWARTZ	YES	1694		19	FILL BASEMENT
431-LA	ARNOLD AND CATHERINE HOWELL	YES	5567	592	19	
431-WA	ARNOLD AND CATHERINE HOWELL	YES	5567		19	FILL BASEMENT
432-LA	JEAN WEISER, ANDREW ROSENFELD	YES	3497	543	19	
432-WA	JEAN WEISER, ANDREW ROSENFELD	YES	3497		19	FILL BASEMENT
433-LA	WILLIE JAMES TALLEY	YES	34916	464	19	
433-A-LA	RUTH B. ROBINS	YES	34916		19	FILL BASEMENT
433-WA	WILLIE JAMES TALLEY	YES	34915	342	19	
433-A-WA	RUTH B. ROBINS	YES	34914	3,321	19	
354-A-LA	*THE GENERAL ELECTRIC COMPANY*	YES	34915		19	FILL BASEMENT
393-A-LA	*F.KIRKORSKY AND C.& E. BENTLEY*	YES	34914		19	REMOVE FOUNDATION
		YES	2311,2312		17	
		YES	3377	1,875	19	

ELIGIBLE FOR FEDERAL PARTICIPATION
* 348-A — THE CITY OF YOUNGSTOWN (FORMERLY JOHN PAUL) — NO — 2308 (PART) — 450 — 17
* 350-A — THE CITY OF YOUNGSTOWN (FORMERLY JOHN BUDAKER) — NO — 2309 (PART) — 744 — 17

RECEIVED R/W NOV 29 1962 State Highway Dept. Dis. No. 4

Parcel 344 A Area Revised 11-19-62
ADDED PCL-356-TS DELETED 356-WA 2-22-61
Pcl. 393-LA Revised Deed 12-15-60
Pcl. 393-A-LA Added 12-15-60
Pcl. 318-LA Revised Area 10-18-60
Pcl. 285-A-LA Changed Area & Sta. 8-23-60
Parcels 356-LA & 356-A-LA Added Name & Areas 7-6-60
Parcel 320-A-LA Added Area 7-6-60
Parcel 287-LA Added Area 7-6-60
Parcel 361-C-LA Revised 6-30-60
Parcel 344-A Revised 6-30-60
Parcel 339-LA Revised 6-27-60
Parcel 299-A-LA Revised 6-27-60
Parcel 313-B-A Added Area 6-24-60
Parcel 287-B-LA Deed Information Added 6-24-60
Parcels 316-A & 316-LA Area Revised 6-16-60
Sheet Reference Nos. Revised 4-20-60
Parcel 330-LA Revised 4-18-60
Parcel 344B-LA Revised 4-12-60

ADDED PCLS. 348-A & 350-A PER GUZIAK 6-3-68. J.R.B.

Deleted Pcl. 347-LA, Combined with 347-LA 3-4-65.
12-16-63
Warranty Deed 1017 Pg 637 Case No 2168065
Pcl-319 Aerial Deleted, Area rev Pcl 319-LA 12/16/63

FED. RD.	STATE	PROJECT	
2	OHIO		

471 / 492

MAH-18-17.20

SUMMARY OF R/W REQUIRED

CITY OF YOUNGSTOWN
PROJECT MAH.-18-17.20

PARCEL Nº	OWNER	LOT Nº	AREA SQ. FT.	SHEET Nº	REMARKS
C-1 WA	MARGARET C. BOWREY	18181		22	
C-2 WA	ELIZ. LESKO ZAVACAN	18182		22	
C-3 WA	JOHN & WASYLYNA IWANUIK	18183		22	
C-4 WA	THEO. & NANCY HASSAY	18184		22	
C-5 WA	KOLAR & KURTA	18185		22	
C-6 WA	GUSSIE L. HEYMAN	18186		22	
C-7 WA	CHARLES & FLO L. PALISEN	18187		22	
C-9 WA	CHAS. & JUSTINE SEREDNESKY	6788		22	
C-10 WA	MARY KNAPIK	15348		22	
C-11 WA	JOHN & SOPHIE TOPORCER	15350		22	
C-12 WA	JOHN LEJBA	15351		22	
C-13 WA	ALEX & ADA HODORY	15352		22	
C-14 WA	MARY & JOHN SKLEPKO	15353		22	
C-15 WA	PAUL & MARY KISSEL	15354		22	
C-16 WA	MARY PODRAEZKY	6789		22	
C-17 WA	JOHN & HELEN NESTERUK	6790		22	
C-18 WA	PAUL & JULIA ANTEL	6791		22	
C-19 WA	CHARLES F. SEMPLE	11781		22	
C-20 A	THE ISALY DAIRY CO.	9487		23	
C-20 WA	THE ISALY DAIRY CO.	"		23	
C-22 WA	T. SAADI	3921		25	
C-23 WA	T. SAADI	3920		25	
C-24 A	EXIE SCRUGGS	2363		25	
C-25 A	EMMA JANE McCORKLE	2357		25	
C-26 WA	CLIFTON DOUGLAS-LUCY ANN PARKER	2327		25	
C-27 WA	RUBY B. CHEIRS	2326		25	
C-28 WA	HATTIE BRADLEY	1929		25	
C-29 A	J. B. & H. COLLIER	2355		25	
C-30 A	LOWRENCE & BEATRICE SMITH	2356		25	
C-31 A	TOFFIC SAADI	876		25	
C-33 A	WALTER & WILLO LEE FLIPPING	5662		25	
C-33 WA	"	"		25	
C-34 A	IDA BELLE PEARSON	5663		25	
C-34 WA	"	"		25	
C-35 A	MARY CANNELL	5664		25	
C-35 B		5665		25	
C-35 WA	MARY CANNELL	5664		25	
C-36 A	ANNA CENTRIC	5724		25	
C-37 A	ALVIN & JOSEPHINE CLARK	5725		25	
C-38 A	ANDERSON & OLA MAE JOHNSON	55074		25	
C-39 A	MATTIE HART	55077		25	
C-39 WA	"	"		25	
C-40 A	CLARA WASHINGTON	848		25	
C-40 WA	"	"		25	
C-41 A	UNION NAT'L BANK TRUST	5650		25	
C-42 WA	DOZIER RENAH - JAMES JACKSON	1578		25	
C-43 WA	EMIL E. RESTLE	5668		25	
C-44 A	LINDSAY CARRIE	57454		25	
C-44 WA		57454		25	
C-45 WA		57455		25	
C-46 A	NAT'L CITY BANK OF CLEVE. TR.	2316		26	
C-46 WA		2316		26	
C-47 A	FIRESTONE TIRE & RUBBER CO., AKRON, O.	2900		26	
C-47 WA		2900		26	
C-49 A	FLORENCE MACE	3171		24	
C-50 A	MILITARY ORDER OF COOTIE, PUP TENT #5	3172		24	
C-50 BA	FRANK P. SANDERS	3172		24	
C-51 A	GEORGE A. GRIEN	3173		24	
C-52 A	ISALY DAIRY CO.	2653		24	
C-52 BA	MOFFET L. T. & B.	2653		24	
C-53 A	ISALY DAIRY CO.	3407		24	
C-53 BA	DOLLAR SAVINGS & TRUST CO.	3407		24	
C-54 A	BENJAMIN F. LEWIS	9508		24	
C-54 CA	RALPH M. Mc CRACKEN	9508		24	
C-55 A		5721		24	
C-55 WA		5721		24	

PARCEL Nº	OWNER	LOT Nº	AREA SQ. FT.	SHEET Nº	REMARKS
C-56 A	LEONA LOUISE CALER	5722		24	
C-56 BA	RALPH M. McCRACKEN	5722		24	
C-56 WA	LEONA LOUISE CALER	5722		24	
C-56 B-WA	RALPH M. McCRACKEN	5722		24	
C-57 A	CALVIN & MARTHA WESTON	O.L. 379		24	
C-57 BA	D.H. LEVY & S. DUNGER	"		24	
C-57 B-WA		"		24	
C-57 WA	CALVIN & MARTHA WESTON	O.L. 379		24	
C-58 A	NAPOLEAN & DOROTHY BURT	30332		24	
C-60 A	THEO. R. CLAPP	3371		26	
C-60 WA	"	"		26	
C-61 A	FRED SHUTRUMP	10101		26	
C-61 WA	"	"		26	
C-62 A	BEATRICE B. LOPEZ	1692		26	
C-62 WA	"	"		26	
C-63 A	NATHAM DARSKY	1691		26	
C-63 WA	"	"		26	
C-64 A	FRED WALLACE HUGHES	1690		26	
C-64 WA	"	"		26	
C-65 A	GEORGE & K. KONIESCKY	1689		26	
C-65 WA		"		26	
348 A	JOHN PAUL	2308		26	
348 WA	"	"		26	
350 A	JOHN & ANN BUDAKER	2309		26	
350 WA		"		26	

Sheet Reference Nos. Revised 4-20-60

I-680 R/W SHEET 6 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

472 / 492



PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING SQ.FT.
1-LA	LUIGI FULCINITI	—	—	—	5778
2-LA	PETER & HELEN MIKITA	2-ST.FR.	10×16 FR.	5×6 FR. SHED	5000
3-LA	WILLIAM PUPA	2-ST.FR.	10×16 FR. SHED	7×14 FR. SHED	4090
4-LA	STEVE DOLAK MARY DOLAK	2-ST.FR.	—	8×8 FR. SHED	2120
4-A-LA	ELIZABETH PEDAK	2-ST.FR.	—	—	261
6-LA	MOLLIE BARTA	2-ST.FR.	40×20 FR.	—	5625
7-LA	FRANCISKA ONDASH	2-ST.FR.	8×8 FR. SHED	7×12 BR. SHED	5000
8-LA	MATHEW A. STANKICH MARY LOU STANKICH	2-ST.FR.	12×16 FR.	9×12 FR. SHED	5000
9-LA	JOHN IWANIUK WASYLYNA IWANIUK	2-ST.FR.	—	6×8 FR. SHED	6250
10-LA	FRANK DEAK ELIZABETH DEAK	2-ST.FR.	—	9×6 FR. SHED	4770
11-LA	MARY GARCAR	2-ST.FR.	—	7×12 FR. SHED	2850
12-LA	JOHN KRUPA MARY KRUPA	2-ST.BR.	12×16 FR.	—	136
13-LA	ALBERT FUZY, WM. A. AMBROSE MRS. JULIA KARAKA, PAUL FUZY	2-ST. FR.	36×18 FR.	—	6728
15-LA	ANNE CHABALA LESON	2-ST.FR.	—	6×8 FR. SHED	5000
16-LA	ANNE SHUSTER	2-ST.FR.	10×18 FR.	—	7500
18-LA	MIKE SEMAN MARY SEMAN	2-ST.FR.	—	—	3750
19-LA	PETER KANTOR JR. ETHEL MASZAROS	2-ST.FR.	13×18 FR.	—	6250
20-LA	HELEN KRAVEC	—	16×22 FR.	—	5000
26-LA	ANDREW ANTHOL, ANN CIZMAR PAUL ANTHOL, HELEN YASH	2-ST.FR.	11×15 FR.	7×14 FR. SHED	3820
22-LA	MITRO MICA ANNIE MICA	1-ST.FR.	—	11×18 FR. SHED	4950
24-LA	JAMES K. WALTERS	2-ST.FR.	12×18 FR.	8×10 FR. SHED	11.849
25-LA	HELEN M. BUGNO	1-ST.BR.	11×15 FR.	6×6 FR. SHED	7406

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING SQ.FT.
28-LA	ANNA GONDA	2-ST.BR.	20×20 FR.	—	5000
29-LA	MARY L. ADAMS	2-ST.BR.	14×20 FR.	—	5000
30-LA	PAUL BEDNARIK	2-ST.FR.	12×18 FR.	6×8 FR. SHED	4100
31-LA	VERONICA BUNDASH	2-ST.FR.	14×20 FR.	—	2050
31-A-LA	MICHAEL BEHUN MARY BEHUN	2-ST.FR.	14×22 FR.	—	403
33-LA	MICKEY HANUSCHAK FLORA JEAN HANUSCHAK	1-ST.BR.	—	—	3400
34-LA	JOHN F. TOBIN KATHERINE TOBIN	1-ST.BR.	—	—	1438
35-LA	STEVE MATYL ANNIE MATYL	1-ST.FR.	—	7×9 FR. SHED	5000
36-LA	SUE K. FURDEN JULIA KUNI	1-ST.FR.	—	7×7 FR. SHED	5000
37-LA	JOE VALUSH	1-ST.FR.	—	5×8 FR. SHED	4000

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING SQ.FT.
38-LA	ANNA GAYDOS	1-ST.FR.	12×20 FR.	11×8 FR. SHED	4000
39-LA	ANDREW & SUSIE LENGYEL	1-ST.FR.	—	8×8 SHED	4125
40-LA	ANNA, JOHN S. & JOSEPH YUHASZ	1-ST.FR.	—	8×9 SHED	3680
46-LA	GEORGE ZAHDRERY ELIZABETH ZAHDRERY	2-ST.FR.	—	6×8 FR. SHED	5490
47-LA	ANNA PAVLIK	2-ST.FR.	—	8×8 FR. SHED	3240
48-LA	MARY SELENK	2-ST.FR.	—	9×10 FR. C.C.	689
58-C-LA	JOSEPH S. PETRICK MARIA PETRICK	LOSS OF ACCESS TO LAKEVIEW AVE.			
58-F-LA	STEVEN N. BOBOVNYCK MARY BOBOVNYCK	2-ST.FR.	—	—	3808

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING SQ.FT.
41-LA	THE PORTLAND LAND CO.	—	—	—	6432
43-LA	ANNIE NELSON	—	—	—	1420
49-LA	HELEN W. COHN	—	—	—	68,711

WORK AGREEMENT

PARCEL №	NAME	DESCRIPTION
26-WA	ANDREW ANTHAL, ANN CIZMAR PAUL ANTHAL, HELEN YASH	REMOVE SHED
3-WA	WILLIAM PUPA	FILL BASEMENT
13-WA	ALBERT FUZY, WM. A. AMBROSE JULIA KARAKA, PAUL FUZY	REMOVE GAR. FD'N.
30-WA	PAUL BEDNARIK	REMOVE GAR. FD'N.
31-A-WA	VERONICA BUNDISH	FILL BASEMENT
46-WA	GEORGE ZAHDRERY ELIZABETH ZAHDRERY	FILL BASEMENT
34-WA	JOHN F. TOBIN CATHERINE TOBIN	FILL BASEMENT

REV. NO.	NATURE OF REVISION	DATE	MADE BY
Pcl. 49-LA	Name Change	10-5-60	S.S.
Pcl. 1-A LA	Removed From Taking	12-30-59	J.E.P.
Pcl. 49-LA	Coordinates Added	6-7-60	T.A.B.
	Deleted Parcels 21A-LA	DATE COMP.	
	Added 26WA, 3WA, 13WA, 30WA, 31A-WA, 46WA, 34WA, 58ATS.		
Pcl. 34-LA	Revised Area of Taking	12-1-60	B.H.
Pcl. 49-LA	Revised Area of Taking	1-21-60	B.H.
	REVISED 58-ATS TO 58C-LA	3-25-60	J.D.P.

8-82


I-680

R/W SHEET 7 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

473
492

REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
PCL 84LA	CORRECTED LOT Nos & PR	6-17-59	E.COMISKEY
PCL'S.	62LA-63LA REVISED 82LA DELETED	10-20-59	
PCL'S.	53A-54A ADDED, 62LA-63LA-62SA-63SA REV. 62AS. DELETED	11-10-59	
# 1	ADDED BARRICADES AT SILLIMAN	12-30-59	J.G.P.
# 2	RELOC. 1/A AT LAKEVIEW & STEEL	12-30-59	J.G.P.
	ADDED PR & FENCE	3-25-59	J.D.P.



PARCEL NO	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
49-A-LA	JOE INCE ANNA INCE	2-ST. FR.	10x18 FR.		231
51-LA	BETTY JOE YOHMAN	2-ST. FR.	10x16 FR.		1203
52-LA	ANDREW KOSAR HELEN KOSAR	2-ST. FR.	10x16 FR.		2080
53-LA	MICHAEL NAGY JR.	2-ST. FR.	12x20 FR.	8x10 FR. SHED	2762
54-LA	MARGARET BADA	2-ST. FR.	12x20 FR.		3672
55-LA	VINCENT F. HALKO MARY ANN HALKO	2-ST. FR.	12x12 FR.		5000
56-LA	ANDY LUKAC MARY LUKAC	1-ST. FR.			5000
57-LA	ALEXANDER BARICH MILDRED BARICH	2-ST. BR.	20x20 TILE		13720
58-LA	MARY PAULINE WILLIAMS				20,690
59-LA	GINO LAMARCA ½ LOUISE LAMARCA ½	2-ST. FR.	20x22 FR.		6265
59-A-LA	UGO DIBACCO ½ ANNA DIBACCO ½	2-ST. FR.			2774

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
60-LA	PAUL SEMAI JOAN SEMAI	1-ST. BR.	14x20 FR.	6x12 FR. SHED	5000
61-LA	PAUL GLOVA MARY GLOVA	2-ST. FR.		6x10 FR. SHED	5000
67-LA	MARY MACYNSKI	1½ ST. BR.		6x16 FR. SHED	5000
79-LA	JOHN BOBANICH ANNA BOBANICH	2-ST. BR.	12x20 FR.		7728
80-LA	ANNA MOZZY-MARY BARTELL-MICHAEL & ANDREW CYCYK	2-ST. BR.			2000
81-LA	JOHN R.-CHARLES E.-JOSEPH T.-MARY ANN-CATHERINE T. & JENNIE S. MARCH	2-ST. FR.	18x20 FR.	6x10 FR. SHED	960
62-LA	DAFINI NEGROFF	2-ST. FR.	12x20 FR.		64
63-LA	BARBALA OR BARBARA BURCSAK	2-ST. FR.		8x10 FR. SHED	705
83-LA	JOHN STUN	1-ST. FR.	14x18 FR.		3189
84-LA	ASTER SKLEPKO	1-ST. FR.	12x20 FR.		3750

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
85-LA	JOHN DZUROFF ANNI DZUROFF	2-ST. FR.	14x20 FR.		5000
86-LA	MICHAEL SABOL JR.-MARTIN SABOL & MARY B. KAVANAUGH	2-ST. FR.			5000
87-LA	MARY BAROLAK ROMAN-EDWARD-EMIL-JOSEPH T. BAROLAK	1½-ST. FR.	20x20 FR.		5000
88-LA	THERESA TOBIS OR THERISA TOBIAS	2-ST. FR.			5000
89-LA	JOHN J. BRCAK AGNES BACAK	2-ST. FR.	12x16 FR.		5000
90-LA	JOSEPH-JOSEPH S.-BERNARD R.-GEORGE C. KNAPIC-FRANCES K. ACRI	1½-ST. FR.	1 CAR		5000
91-LA	WALLACE DORKO HILDA MARIE DORKO	1½-ST. FR.	12x18 FR.		5000
92-LA	MARTIN HARCHAR ANNA HARCHAR	2-ST. FR.	12x18 FR.		5000
93-LA	MARY D. OLSAVSKY	2-ST. FR.	14x18 FR.		5000
94-LA	KAROL BUREK ANNA BUREK	2-ST. FR.	12x18 FR.		5000
95-LA	MARI OR MARY MAJOVSKY				5000
96-LA	VERONICA MISSIK	2-ST. BR.		6x10 FR. SHED	5000
97-LA	JOHN KISS ELIZABETH KISS	2-ST. BR.	28x20 FR.		5000
62-S	DAFINI NEROFF				750
63-S	BARBALA OR BARBARA BURCSAK				335

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
62-A-SA					80
64-SL	ANDREW TARKANICH SUSIE TARKANICH				25
71-LA	ANDY L. LESKOVEC ANNA C. LESKOVEC	2-ST. FR.	12x18 FR.		360
72-LA	HELEN BROGLI JULIANNA BROGLI	2-ST. FR.	10x18 FR.		980
73-LA	CHARLES R. KELLY LEONA CODE	1½-ST. FR.	10x18 FR.	14x18 FR. SHED	1440
74-LA	THOMAS A. DENEHY BRIDGET L. DENEHY	2-ST. FR.	12x18 FR.		2090
75-LA	ANDREW BODNAR ANNA BODNAR	2-ST. FR.	12x18 FR.		1950
76-LA	JOSEPH BANKOVITCH	2-ST. FR.	12x18 FR.		3040
77-LA	JOHN PAUL BARBOLA, PAUL	2-ST. FR.	22x24 FR.		3500
98-LA	GEORGE BODNAR JR. HELEN BODNAR	2-ST. FR.	18x22 FR.		10680
100-LA	MARY ADAMS	2-ST. FR.	15x18 FR.		5000
101-LA	JOHN M. SUDZINA AGNES SUDZINA	2-ST. FR.	18x20 FR.		5250
102-LA	BRIDGET L. RUANE	2-ST. FR.	18x18 FR.		5250

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
103-LA	JOHN FETZER BARTA FETZER	2-ST. FR.	12x18 FR.		5250
104-LA	ZVONIMIR ROY VULYAK ROSE M. VULYAK	2-ST. FR.	12x18 FR.		5250
105-LA	ANNA KACHMAR OR ANNA KACHMER	2-ST. FR.			5250
106-LA	MICHAEL YACKO ELIZABETH YACKO	2-ST. FR.	10x16 FR.		5250
107-LA	PETER ZEMAN MARY ZEMAN	2-ST. FR.	12x16 FR.		5000
108-LA	VALENT LEDINKO	2-ST. FR.	12x18 FR.		5000
109-LA	GABOR TOTH SUSIE TOTH	2-ST. FR.	12x17 FR.		5000
110-LA	MATHEW HAMBORSKY ANNA G. HAMBORSKY	2-ST. FR.	12x18 FR.		5000
111-LA	FRANK BAROLAK	2-ST. FR.	12x18 FR.		5000
112-LA	JOSEPH ANDREWS	2-ST. BR.			10612
53-A	MICHAEL NAGY, JR.				1398
54-A	MARGARET BADA				488


WORK AGREEMENTS

PARCEL Nos	NAME	DESCRIPTION
62-WA	DAFINI NEGROFF	FILL BASEMENT
63-WA	BARBALA OR BARBARA BURCSAK	FILL BASEMENT
80-WA	ANNA MOZZY - MARY BARTELL MICHAEL & ANDREW CYCYK	FILL BASEMENT
81-WA	JOHN-CHARLES-JOSEPH-MARY ANN-CATHERINE & JENNIE MARCH	FILL BASEMENT
72-WA	HELEN BROGLI JULIANNA BROGLI	FILL BASEMENT
73-WA	CHARLES R. KELLY LEONA CODE	FILL BASEMENT

Revised 64-SL 10-6-61
Revised 58-F&A 6-23-60

FED. RD.	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

474
432



PARCEL NO.	NAME	BUILDINGS HOUSES	GAR.	MISC.	AREA OF TAKING
113-LA	MICHAEL ZUZAN	2-ST. BR.	20X24 TILE	6'6" x 6'	6142
114-LA	JULIA KUN	2-ST. FR.	10X20 C.B.		3390
115-LA	MIKE POTOCNAK MARY POTOCNAK	2-ST. FR.		6X12 FR. SHED	3220
116-LA	JOHN SMITH CATHERINE SMITH	2-ST. FR.	12X18 FR.		3106
117-LA	FRANK FERKO	2-ST. FR.	12X18 FR.		2964
118-LA	PAUL MATUSCAK ANNA MATUSCAK	2-ST. FR.		FR. SHED	2800
119-LA	BERTHA HOHOS	2-ST. FR.	12X20 BR.		2680
121-LA	GEORGEA. BOZICK CATHERINE BOZICK	2-ST. FR.		6X12 FR. SHED	2660
122-LA	JOE PISANSKY MARY PISANSKY	2-ST. FR.	12X22 C.B.	6'6" FR. SHED	2700
123-LA	ANDREW ZAMBORI MARY ZAMBORI		12X22 C.B.	6'10 FR. SHED	2740
124-LA	FRANK PALIGA HELEN PALIGA		13X20 BRICK	7'X18 FR. SHED	2660
125-LA	KATARINA GIBA		14'X23 C.B.	9'X13 C.B. SHED	3209
127-LA	PAUL KOVAL IRENE KOVAL	2-ST. FR.	14X20 BR.	6'X10 FR. SHED	8840
128-LA	SUSANNA KRAMER	1-ST. FR.	12X18 FR.		5200
129-LA	GEORGE LUTZA JR.	2-ST. FR.	14'X20 C.B.	8'X14 FR. SHED	5200
130-LA	MATTHEW KOVAL ANNA KOVAL	2-ST. FR.	10X16 FR.		1540
131-LA	STEVAN HOFFMAN ANNA HOFFMAN	2-ST. FR.	12'X20 BR.	8'X16 FR. BARN	3180
133-LA	ST. MICHAELS RUSS. ORTH. GR. CATH. CHURCH			30'X7' BR. BLDG.	48,376
134-LA	MAHONING VALLEY SANITARY DISTRICT				50,220
135-LA	JOHN SAHLICA				12882
136-LA	SERBIAN EASTERN ORTH. CONGREGATION	1-ST. BR.			130,633

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BARN	AREA OF TAKING
140-LA	BERKELEY-BERTHA-IRVING & BERNICE FROMKIN				307,525
113-SA	MICHAEL ZUZAN				3088
114-SA	JULIA KUN				1810
115-SA	MIKE POTOCNAK MARY POTOCNAK				1980
116-SA	JOHN SMITH CATHERINE SMITH				2094
117-SA	FRANK FERKO				2236
118-SA	PAUL MATUSCAK ANNA MATUSCAK				2400
119-SA	BERTHA HOHOS				2520
121-SA	GEORGE A. BOZICK CATHERINE BOZICK				2600
122-SA	JOE PISANSKY MARY PISANSKY				2500
123-SA	ANDREW ZAMBORI MARY ZAMBORI				2460

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BARN	AREA OF TAKING
124-SA	FRANK PALIGA HELEN PALIGA				2540
125-SA	KATARINA GIBA				5880
130-SA	MATTHEW KOVAL ANNA KOVAL				720
131-SA	STEVAN HOFFMAN ANNA HOFFMAN				6204
140-SA	BERKELEY-BERTHA-IRVING & BERNICE FROMKIN	1-ST. FR. House			9080
133	ST. MICHAELS RUSS. ORTH. GR. CATH. CHURCH				750

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
134	ST. MICHAELS RUSS. ORTH. GR. CATH. CHURCH				240
136	SERBIAN EASTERN ORTH. CONGREGATION				715

WORK AGREEMENT

PARCEL Nº	NAME	DESCRIPTION
133-WA	ST. MICHAELS RUSS. ORTH. GR. CATH. CHURCH	REMOVE FOUNDATION
130-WA	MATHEW KOVAL ANNA KOVAL	FILL BASEMENT
131-WA	STEVAN HOFFMAN ANNA HOFFMAN	FILL BASEMENT

REVISIONS

REV. Nº	NATURE OF REVISION	DATE	MADE BY
9	Added Pcl. 134 LA, ALA, BLA, & CLA	6-25-65	
6	Parcel 136-S Revised Sewer	7-7-60	S.S.
5	Parcel 133-S To 133	7-6-60	S.S.
4	Parcel 136-S Revised	6-30-60	S.S.
8	ADDED PARCEL 134	4-17-61	T.J.
7	Rev. Corr. Parcel 133	3-28-61	T.J.
#1	ADDED M.V.S.D. FEEDER MAIN	12-30-59	J.E.P.
	REVISED L/A LINE AT STEEL ST.		
	ADDED 131WA, 130WA, 133, 133WA		
	136 S		
#2	REVISED FENCE - ADD PL	3-28-60	J.D.P.
#3	Parcel 135-LA Area Revised	5-10-60	

1138767

THE MAHONING VALLEY SANITARY DISTRICT RIGHT-OF-WAY PLAT

Graphic Scale, (Original Tracing)

CITY OF YOUNGSTOWN
MAHONING COUNTY, STATE OF OHIO
MAH. 18-17.20 -YOUNGSTOWN EXPRESSWAY

APPROVED BY:
BOARD OF CONTROL
MAYOR _____ 3/18/64
SIGNATURE DATE
LAW DIRECTOR _____ 3/14/64
SIGNATURE DATE
FINANCE DIRECTOR _____ 3/18/64
SIGNATURE DATE

DEPT. OF PUBLIC WORKS
COMM. OF ENGINEERING _____ 3/18/64
SIGNATURE DATE

THE M.V.S.D. BOARD OF DIRECTORS

PRESIDENT _____ A. I. KIDSTON 12-5-63
SIGNATURE DATE
MEMBER _____ W. F. MacQUEEN 12-5-63
SIGNATURE DATE
SECRETARY _____ D. D. HEFFELFINGER 12-5-63
SIGNATURE DATE

RECEIVED FOR RECORD ON THE 11TH DAY OF FEB. 1965
AT 3:05 O'CLOCK P.M. RECORDED IN VOL. 55 PAGES 247 OF
THE MAHONING COUNTY RECORD OF DEEDS ON THE 15 DAY
OF February, 1964.
Horace G. Tetlow
MAHONING COUNTY RECORDER

Needs no transfer
2-11-65
F. D.

NOTE
ALL STATIONS AND BEARINGS SHOWN REFER TO EXPRESSWAY DATA EXCEPT WHERE MARKED M.V.S.D. OR EXISTING STATION.

DWG. No. D-6-X 140.1
Acc. No. 9194
File - V-11-85

REVISED: NOV. 6, 1963 - TRIPP
* - DENOTES REVISION OR ADDED INFORMATION
Added Pcls. 134 LA, 134 ALA, 134 BLA, 134 CLA. 8-17-65
Rev. Nov. 21, 1963 — * DENOTES ADDITIONAL DATA By M.V.S.D. REG. SURVEYOR, No. 3263, John T. Santagata

E.O.N.D.

I-680

R/W SHEET 9 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

475/492

SS-18 644 L.F. TYPE "C" FENCE

AREA OF FEDERAL PART. (LAND FEE TITLE)


** (148) 9000 Sq. Ft. ELIGIBLE OUT OF ORIGINAL 71000 Sq. Ft. IN LA.

* (146) 14,400 Sq. Ft. " " " " 42,742 " " " ".

REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
#1	ADDED M.V.S.D. FEEDER MAIN	12-30-59	J.E.P.
	REVISED R/S, LA LINE		
	ADDED PARCELS 1405, 1445		
#2	REVISED R/W FENCE-ADDED R/S	3-28-60	J.D.P.
#3	Added Bldg & Well Parcel 147 LA	8-15-60	S.S.
#4	Revised P.O.S. 146 LA & 148 LA to Show Federal Participation PER STRAHL.	5-7-68	J.R.B.

PARCEL NO.	NAME	BUILDINGS HOUSES	BUILDINGS OTHER		AREA OF TAKING	
143-LA	GEISI PASSARELLI CHRISTINA PASSARELLI	-	-	-	362,635	
144-LA	BALTIMORE & OHIO RAILROAD					
145-LA	ANGELO, MARK, JOHN & JOSEPH PASSARELLI	-	-	-	39,920	
146-LA	GORGIE REALTY CO.	1 ST.C.B. 65 x 48	TILE 12x16 SHED		42,742	*
147-LA	JOE MASKULKA GEMMA BADINO	1 ST.C.B. 15x20 1 ST.C.B. 50x35			30,050	
148-LA	SAM MARGOLIS	1ST.C.B. 52x40			71,000	**
136-LA	SEE SHEET #3					
140-LA	SEE SHEET #3					
146-A-LA	BALTIMORE & OHIO R.R.	-	-	-		
1405	BERKELEY-BERTHA-IRVING & BERNICE FROMKIN					
1445	BALTIMORE & OHIO R.R.					

NOTE: FOR INVENTORY, SEE SHEET



I-680

R/W SHEET 10 OF 26

FED. RD	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

476 / 492

FINAL SURVEY	SURVEYED	BY
	PLOTTED	
	CHECKED	DATE
NOTE BOOK	AREAS	
NO.	AREAS CHECKED	

MAHONING RIVER

BEGIN SHEET ~ STA. 950+00

END SHEET ~ STA. 00+096.27

1337 L.F. TYPE "C" FENCE

WORK AGREEMENT		
PARCEL Nº	NAME	DESCRIPTION
150-WA	JOSEPH & ROBERT F. JENKINS	FILL BASEMENT
170-T	BOARD OF PARK COMMISSIONERS YOUNGSTOWN TWP. PARK DISTRICT	CONSTRUCTION OF PARK ROAD

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
143-LA	THRU 148-LA SEE SHEET 9				
149-LA	JOHN & ANDREW FUSCO			18×18 SHED	4,530
151-LA	THEODORE SAROKA GINO PARISI		1-S.C.B. 35×50		12,298 (13,398)
150-LA	JOSEPH E. & ROBT. F. JENKINS		50×96 Block Bldg.		50,701
154-LA	MARGARET B. SITTINGER	22×28 1-S.FR.			2,350
155-LA	THE YOUNGSTOWN DUNBRIK CO.		1-S.C.B. 45×80		53,789 (53,789)
170B-LA	UNION NATIONAL BANK OF YOUNGSTOWN ET-AL			SHED	3,210
159-LA	VINCE MINOR				8,118
160-LA	BERNARD BRUSS	2-S. FR.	12×18 FR.		4,590
161-LA	LEO & BERNARD BRUSS	LUMBER YD. BLDGS.	SEE SHSA		8,400
150-A-LA	PAUL PAGAC				4,290
161-SA	LEO & BERNARD BRUSS				33,350
150-B-LA	ELLA LOUISE WICK				333
170-LA	See sheet 11				
154-A	LORIETTA McGEE				377.5


REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
# 2	REVISED FENCE-ADDED PR.	3-28-60	J.D.P.
#3	Parcels 170-LA, 170-T, 170B-LA	4-20-60	T.A.B.
#4	Revised Parcel 154-A	6-23-60	S.I.S.
	ADDED PARCEL 154 A	12-30-59	
#1	ADDED 42" MVSD WATER LINES Revised	12-30-59	J.E.P.
Parcels 150-LA, 150-A-LA, 150-B-LA, 155-LA Revised		7-27-59	

Parcel 170-T	Changed From Work Agreement To Temporary	7-6-60	
Parcel 155-LA	Area Revised	7-6-60	
Parcel 151-LA	Area Revised	7-6-60	
Parcel 149-LA	Area Revised	7-6-60	
Parcel 170B-LA	Revised	7-5-60	
Parcel 149-LA	Revised	6-27-60	
Parcel 170-B-LA	Revised	6-27-60	

I-680


FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

477
492


ACCESS FOR UTILITIES MAINTAINED
MAIN COLLECTING CHAMBER
AVENUE
MAHONING
BEGIN SHEET — STA. 960+00
960+53
104'
961+41
112'
OL 493
OL 494
N
TIMBER
OL. 490
OL 495+00
DAM
963+45
107'
963+45
55'
963+45
85'
963+45
85'
963+45
85

FED. RD.	STATE	PROJECT	
2	OHIO	MAH. 18-17.20	

478/492



1685 L.F. TYPE "C" FENCE

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
171-LA	SEE SHEET No 6				
173-LA	WILLIAM W. NEFF ARMIDA NEFF	2-ST. BR. 2-ST. FR.	18x18 FR.		7625
174-LA	HAROLD & ETHEL GASKINS	2-ST. FR.	12x18 FR.	18x18 FR. SHED	7625
175-LA	JOHN J. CIKA DOROTHY A. CIKA	2-ST. FR.			2920
176-LA	JAMES A. POTTER PAULINE POTTER	2-ST. FR.			2920
177-LA	I SALY DAIRY CO.	2-ST. FR.	IN BASM'T.		10215
178-LA	THE DOLLAR SAVINGS & TRUST CO. TRUSTEE	2-ST. FR.			7634
179-LA	JOHN WILLIAMS LOU GENIA WILLIAMS	2-ST. FR.			6940
180-LA	DOUGLAS JONES CHESTINA JONES	2-ST. FR.	12x18 FR.		6940
181-LA	BESSIE AGRENOVITZ	2-ST. FR.	20x16 BR. SHED	7x12 FR. SHED	6940
182-LA	JESSIE DOUGLAS CHRISTINE DOUGLAS	2-ST. FR.			5028
183-LA	MARY G. REITZELL FLORA A. REITZELL	2-ST. FR.			6940
184-LA	BENJAMIN VERNON CLARA VERNON	2-ST. FR.			3960
185-LA	GILSON T. GRAHAM				3300
186-LA	ANNIE K. HARPER ROBINSON ALIAS ANNIE SIMMONS	2-ST. FR.			1560
188-LA	EULALIA M. LUTHER	2-ST. FR.	20x20 FR.		5900
189-LA	ROSINA SCHNEIDER	2-ST. FR.		8x16 FR. SHED	6000
190-LA	JAMES ARTHUR ROSS ANNIE B. ROSS	2-ST. FR.	18x18 FR.		6250
191-LA	ETHEL GILFILLAN	2-ST. FR.	12x18 FR.		3300
192-LA	D. N. GARVER MARTHA E. GARVER	2-ST. FR.			7695
193-LA	CLYDE E. TRUITT DOROTHY C. TRUITT	2-ST. FR.	12x18 FR.		3630
194-LA	TUFIC SAADI	2-ST. FR.	10x12 FR.		5066
195-LA	CHARLOTTE BYERS	2-ST. FR.	12x18 FR.		5066

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
196-LA	MARTIN BOKESCH CHRISTINA BOKESCH	2-ST. FR.			3924
197-LA	IRENE H. VANMETER	2-ST. FR.		12x16 FR. SHED	3252
198-LA	JOSEPH STOKAN	2-ST. FR.			6940
200-LA	KATHLEEN WATKINS	2-ST. FR.	12x20 FR. 16x20 FR.		6940
201-LA	KATHERINE B. WILSON	2-ST. FR.	16x18 FR.		6940
202-LA	JAMES ANDERSON	2-ST. FR.			4500
203-LA & 204-LA	FLORENCE APPEL DORFF HELEN APPEL LEWIS CLARA APPEL CASSESE	2-ST. FR. 1-ST. FR.			9300
205-LA	CLARENCE C. McKELRY ELIZABETH McKELRY	2-ST. FR.	18x18 FR. 10x16 FR.	4x10 FR. SHED	18x20 FR. BARN 9000
206-LA	THOMAS A. MUMFORD	2-ST. FR.		8x20 FR. SHED	7500
207-LA	LILLIAN B. JONES RAFE	2-ST. FR.	12x20 C.B.	8x14 FR. SHED	6000
212-LA	T SAADI	2-ST. FR.			4500
213-LA	HOWARD JAMES WILLIE MAE JAMES	2-ST. FR.			2910
214-LA	ARTHUR I. WALDMAN	2-ST. BR.			7275
215-LA	JAMES MONROE LONG	2-ST. FR.			4340
208-LA	JESUS HERNANDEZ MARY E. HERNANDEZ	2-ST. FR.			3108
209-LA	LEONARD HALLEWELL ESTELLA HALLEWELL	2-ST. FR.			3009
209-A-LA	JAMES BROWN	2-ST. FR.	12'x16' FR.		2549
210-LA	FREDERICK LEROY TAYLOR GRACE VERA TAYLOR	2-ST. FR.			6425
211-LA	JOSEPH ANDROSEK 7/8 WALSH & ROBERTS INC. 2/8	2-ST. FR.			3806
211-A-LA	FREDA C. ANDERSON	2-ST. FR.			2903
211-B-LA	JAMES DOMINIC PRECURATO MARY DELORES PRECURATO	2-ST. FR.	14'x20' C.B.	6x12 FR. SHED	4902
216-LA	ROY F. MORT	2-ST. FR.	12'x16' FR.	5x12 FR. SHED	9675
199-LA	JOSEPH STOKAN	2-ST. FR.			6940

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING


REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
#1	Parcels 203LA, 204LA Revised	6-25-59	E.J.C.
	ADDED SEWER	1-19-60	
#2	ADDED PL	3-28-60	J.D.P.
#3	Parcel 215-LA Revised	7-13-60	S.S.
#4	ADDED 199-LA	12-15-60	P.H.


I-680 R/W SHEET 13 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

479 492

DIV. 4 R/W RECORD SECTION FEB 26 1963 RECD. ..... RWD.


EDWARDS STREET
MARSHALL STREET
984 L.F. TYPE "C" FENCE
PROPOSED R/W LINE
2409 L.F. TYPE "C" FENCE
WEST AVE.
WALL
BEGIN SHEET ~ STA. 980+00
END SHEET ~ STA. 990+00
980+24.5
110'
RAMP "F"
PLUM ST.
TIMBER
BUILDING IMPINGEMENT
RAMP "H"
BARRICADE
BURNS ST.
HIGH STREET
PROPOSED R/W LINE
T.S. STA. 0+88.12
981
982
983
984
985
986
987
988
989
5678
5677
5506
5507
5508
5121
5722
9440
9439
9438
9437
30332
30331
5457
4822
4521
30255
30254
30253
30252
2362
2363
2357
2356
2350
2351
2354
2355
2360
2361
2428
2429
2430
2431
2432
2433
2434
2435
2436
2437
2438
2439
2440
2441
2442
2443
2444
2445
2446
2447
2448
2449
2450
2451
2452
2453
2454
2455
2456
2457
2458
2459
2460
2461
2462
2463
2464
2465
2466
2467
2468
2469
2470
2471
2472
2473
2474
2475
2476
2477
2478
2479
2480
2481
2482
2483
2484
2485
2486
2487
2488
2489
2490
2491
2492
2493
2494
2495
2496
2497
2498
2499
2500
2501
2502
2503
2504
2505
2506
2507
2508
2509
2510
2511
2512
2513
2514
2515
2516
2517
2518
2519
2520
2521
2522
2523
2524
2525
2526
2527
2528
2529
2530
2531
2532
2533
2534
2535
2536
2537
2538
2539
2540
2541
2542
2543
2544
2545
2546
2547
2548
2549
2550
2551
2552
2553
2554
2555
2556
2557
2558
2559
2560
2561
2562
2563
2564
2565
2566
2567
2568
2569
2570
2571
2572
2573
2574
2575
2576
2577
2578
2579
2580
2581
2582
2583
2584
2585
2586
2587
2588
2589
2590
2591
2592
2593
2594
2595
2596
2597
2598
2599
2600
2601
2602
2603
2604
2605
2606
2607
2608
2609
2610
2611
2612
2613
2614
2615
2616
2617
2618
2619
2620
2621
2622
2623
2624
2625
2626
2627
2628
2629
2630
2631
2632
2633
2634
2635
2636
2637
2638
2639
2640
2641
2642
2643
2644
2645
2646
2647
2648
2649
2650
2651
2652
2653
2654
2655
2656
2657
2658
2659
2660
2661
2662
2663
2664
2665
2666
2667
2668
2669
2670
2671
2672
2673
2674
2675
2676
2677
2678
2679
2680
2681
2682
2683
2684
2685
2686
2687
2688
2689
2690
2691
2692
2693
2694
2695
2696
2697
2698
2699
2700
2701
2702
2703
2704
2705
2706
2707
2708
2709
2710
2711
2712
2713
2714
2715
2716
2717
2718
2719
2720
2721
2722
2723
2724
2725
2726
2727
2728
2729
2730
2731
2732
2733
2734
2735
2736
2737
2738
2739
2740
2741
2742
2743
2744
2745
2746
2747
2748
2749
2750
2751
2752
2753
2754
2755
2756
2757
2758
2759
2760
2761
2762
2763
2764
2765
2766
2767
2768
2769
2770
2771
2772
2773
2774
2775
2776
2777
2778
2779
2780
2781
2782
2783
2784
2785
2786
2787
2788
2789
2790
2791
2792
2793
2794
2795
2796
2797
2798
2799
2800
2801
2802
2803
2804
2805
2806
2807
2808
2809
2810
2811
2812
2813
2814
2815
2816
2817
2818
2819
2820
2821
2822
2823
2824
2825
2826
2827
2828
2829
2830
2831
2832
2833
2834
2835
2836
2837
2838
2839
2840
2841
2842
2843
2844
2845
2846
2847
2848
2849
2850
2851
2852
2853
2854
2855
2856
2857
2858
2859
2860
2861
2862
2863
2864
2865
2866
2867
2868
2869
2870
2871
2872
2873
2874
2875
2876
2877
2878
2879
2880
2881
2882
2883
2884
2885
2886
2887
2888
2889
2890
2891
2892
2893
2894
2895
2896
2897
2898
2899
2900
2901
2902
2903
2904
2905
2906
2907
2908
2909
2910
2911
2912
2913
2914
2915
2916
2917
2918
2919
2920
2921
2922
2923
2924
2925
2926
2927
2928
2929
2930
2931
2932
2933
2934
2935
2936
2937
2938
2939
2940
2941
2942
2943
2944
2945
2946
2947
2948
2949
2950
2951
2952
2953
2954
2955
2956
2957
2958
2959
2960
2961
2962
2963
2964
2965
2966
2967
2968
2969
2970
2971
2972
2973
2974
2975
2976
2977
2978
2979
2980
2981
2982
2983
2984
2985
2986
2987
2988
2989
2990
2991
2992
2993
2994
2995
2996
2997
2998
2999
3000
3001
3002
3003
3004
3005
3006
3007
3008
3009
3010
3011
3012
3013
3014
3015
3016
3017
3018
3019
3020
3021
3022
3023
3024
3025
3026
3027
3028
3029
3030
3031
3032
3033
3034
3035
3036
3037
3038
3039
3040
3041
3042
3043
3044
3045
3046
3047
3048
3049
3050
3051
3052
3053
3054
3055
3056
3057
3058
3059
3060
3061
3062
3063
3064
3065
3066
3067
3068
3069
3070
3071
3072
3073
3074
3075
3076
3077
3078
3079
3080
3081
3082
3083
3084
3085
3086
3087
3088
3089
3090
3091
3092
3093
3094
3095
3096
3097
3098
3099
3100
3101
3102
3103
3104
3105
3106
3107
3108
3109
3110
3111
3112
3113
3114
3115
3116
3117
3118
3119
3120
3121
3122
3123
3124
3125
3126
3127
3128
3129
3130
3131
3132
3133
3134
3135
3136
3137
3138
3139
3140
3141
3142
3143
3144
3145
3146
3147
3148
3149
3150
3151
3152
3153
3154
3155
3156
3157
3158
3159
3160
3161
3162
3163
3164
3165
3166
3167
3168
3169
3170
3171
3172
3173
3174
3175
3176
3177
3178
3179
3180
3181
3182
3183
3184
3185
3186
3187
3188
3189
3190
3191
3192
3193
3194
3195
3196
3197
3198
3199
3200
3201
3202
3203
3204
3205
3206
3207
3208
3209
3210
3211
3212
3213
3214
3215
3216
3217
3218
3219
3220
3221
3222
3223
3224
3225
3226
3227
3228
3229
3230
3231
3232
3233
3234
3235
3236
3237
3238
3239
3240
3241
3242
3243
3244
3245
3246
3247
3248
3249
3250
3251
3252
3253
3254
3255
3256
3257
3258
3259
3260
3261
3262
3263
3264
3265
3266
3267
3268
3269
3270
3271
3272
3273
3274
3275
3276
3277
3278
3279
3280
3281
3282
3283
3284
3285
3286
3287
3288
3289
3290
3291
3292
3293
3294
3295
3296
3297
3298
3299
3300
3301
3302
3303
3304
3305
3306
3307
3308
3309
3310
3311
3312
3313
3314
3315
3316
3317
3318
3319
3320
3321
3322
3323
3324
3325
3326
3327
3328
3329
3330
3331
3332
3333
3334
3335
3336
3337
3338
3339
3340
3341
3342
3343
3344
3345
3346
3347
3348
3349
3350
3351
3352
3353
3354
3355
3356
3357
3358
3359
3360
3361
3362
3363
3364
3365
3366
3367
3368
3369
3370
3371
3372
3373
3374
3375
3376
3377
3378
3379
3380
3381
3382
3383
3384
3385
3386
3387
3388
3389
3390
3391
3392
3393
3394
3395
3396
3397
3398
3399
3400
3401
3402
3403
3404
3405
3406
3407
3408
3409
3410
3411
3412
3413
3414
3415
3416
3417
3418
3419
3420
3421
3422
3423
3424
3425
3426
3427
3428
3429
3430
3431
3432
3433
3434
3435
3436
3437
3438
3439
3440
3441
3442
3443
3444
3445
3446
3447
3448
3449
3450
3451
3452
3453
3454
3455
3456
3457
3458
3459
3460
3461
3462
3463
3464
3465
3466
3467
3468
3469
3470
3471
3472
3473
3474
3475
3476
3477
3478
3479
3480
3481
3482
3483
3484
3485
3486
3487
3488
3489
3490
3491
3492
3493
3494
3495
3496
3497
3498
3499
3500
3501
3502
3503
3504
3505
3506
3507
3508
3509
3510
3511
3512
3513
3514
3515
3516
3517
3518
3519
3520
3521
3522
3523
3524
3525
3526
3527
3528
3529
3530
3531
3532
3533
3534
3535
3536
3537
3538
3539
3540
3541
3542
3543
3544
3545
3546
3547
3548
3549
3550
3551
3552
3553
3554
3555
3556
3557
3558
3559
3560
3561
3562
3563
3564
3565
3566
3567
3568
3569
3570
3571
3572
3573
3574
3575
3576
3577
3578
3579
3580
3581
3582
3583
3584
3585
3586
3587
3588
3589
3590
3591
3592
3593
3594
3595
3596
3597
3598
3599
3600
3601
3602
3603
3604
3605
3606
3607
3608
3609
3610
3611
3612
3613
3614
3615
3616
3617
3618
3619
3620
3621
3622
3623
3624
3625
3626
3627
3628
3629
3630
3631
3632
3633
3634
3635
3636
3637
3638
3639
3640
3641
3642
3643
3644
3645
3646
3647
3648
3649
3650
3651
3652
3653
3654
3655
3656
3657
3658
3659
3660
3661
3662
3663
3664
3665
3666
3667
3668
3669
3670
3671
3672
3673
3674
3675
3676
3677
3678
3679
3680
3681
3682
3683
3684
3685
3686
3687
3688
3689
3690
3691
3692
3693
3694
3695
3696
3697
3698
3699
3700
3701
3702
3703
3704
3705
3706
3707
3708
3709
3710
3711
3712
3713
3714
3715
3716
3717
3718
3719
3720
3721
3722
3723
3724
3725
3726
3727
3728
3729
3730
3731
3732
3733
3734
3735
3736
3737
3738
3739
3740
3741
3742
3743
3744
3745
3746
3747
3748
3749
3750
3751
3752
3753
3754
3755
3756
3757
3758
3759
3760
3761
3762
3763
3764
3765
3766
3767
3768
3769
3770
3771
3772
3773
3774
3775
3776
3777
3778
3779
3780
3781
3782
3783
3784
3785
3786
3787
3788
3789
3790
3791
3792
3793
3794
3795
3796
3797
3798
3799
3800
3801
3802
3803
3804
3805
3806
3807
3808
3809
3810
3811
3812
3813
3814
3815
3816
3817
3818
3819
3820
3821
3822
3823
3824
3825
3826
3827
3828
3829
3830
3831
3832
3833
3834
3835
3836
3837
3838
3839
3840
3841
3842
3843
3844
3845
3846
3847
3848
3849
3850
3851
3852
3853
3854
3855
3856
3857
3858
3859
3860
3861
3862
3863
3864
3865
3866
3867
3868
3869
3870
3871
3872
3873
3874
3875
3876
3877
3878
3879
3880
3881
3882
3883
3884
3885
3886
3887
3888
3889
3890
3891
3892
3893
3894
3895
3896
3897
3898
3899
3900
3901
3902
3903
3904
3905
3906
3907
3908
3909
3910
3911
3912
3913
3914
3915
3916
3917
3918
3919
3920
3921
3922
3923
3924
3925
3926
3927
3928
3929
3930
3931
3932
3933
3934
3935
3936
3937
3938
3939
3940
3941
3942
3943
3944
3945
3946
3947
3948
3949
3950
3951
3952
3953
3954
3955
3956
3957
3958
3959
3960
3961
3962
3963
3964
3965
3966
3967
3968
3969
3970
3971
3972
3973
3974
3975
3976
3977
3978
3979
3980
3981
3982
3983
3984
3985
3986
3987
3988
3989
3990
3991
3992
3993
3994
3995
3996
3997
3998
3999
4000
4001
4002
4003
4004
4005
4006
4007
4008
4009
4010
4011
4012
4013
4014
4015
4016
4017
4018
4019
4020
4021
4022
4023
4024
4025
4026
4027
4028
4029
4030
4031
4032
4033
4034
4035
4036
4037
4038
4039
4040
4041
4042
4043
4044
4045
4046
4047
4048
4049
4050
4051
4052
4053
4054
4055
4056
4057
4058
4059
4060
4061
4062
4063
4064
4065
4066
4067
4068
4069
4070
4071
4072
4073
4074
4075
4076
4077
4078
4079
4080
4081
4082
4083
4084
4085
4086
4087
4088
4089
4090
4091
4092
4093
4094
4095
4096
4097
4098
4099
4100
4101
4102
4103
4104
4105
4106
4107
4108
4109
4110
4111
4112
4113
4114
4115
4116
4117
4118
4119
4120
4121
4122
4123
4124
4125
4126
4127
4128
4129
4130
4131
4132
4133
4134
4135
4136
4137
4138
4139
4140
4141
4142
4143
4144
4145
4146
4147
4148
4149
4150
4151
4152
4153
4154
4155
4156
4157
4158
4159
4160
4161
4162
4163
4164
4165
4166
4167
4168
4169
4170
4171
4172
4173
4174
4175
4176
4177
4178
4179
4180
4181
4182
4183
4184
4185
4186
4187
4188
4189
4190
4191
4192
4193
4194
4195
4196
4197
4198
4199
4200
4201
4202
4203
4204
4205
4206
4207
4208
4209
4210
4211
4212
4213
4214
4215
4216
4217
4218
4219
4220
4221
4222
4223
4224
4225
4226
4227
4228
4229
4230
4231
4232
4233
4234
4235
4236
4237
4238
4239
4240
4241
4242
4243
4244
4245
4246
4247
4248
4249
4250
4251
4252
4253
4254
4255
4256
4257
4258
4259
4260
4261
4262
4263
4264
4265
4266
4267
4268
4269
4270
4271
4272
4273
4274
4275
4276
4277
4278
4279
4280
4281
4282
4283
4284
4285
4286
4287
4288
4289
4290
4291
4292
4293
4294
4295
4296
4297
4298
4299
4300
4301
4302
4303
4304
4305
4306
4307
4308
4309
4310
4311
4312
4313
4314
4315
4316
4317
4318
4319
4320
4321
4322
4323
4324
4325
4326
4327
4328
4329
4330
4331
4332
4333
4334
4335
4336
4337
4338
4339
4340
4341
4342
4343
4344
4345
4346
4347
4348
4349
4350
4351
4352
4353
4354
4355
4356
4357
4358
4359
4360
4361
4362
4363
4364
4365
4366
4367
4368
4369
4370
4371
4372
4373
4374
4375
4376
4377
4378
4379
4380
4381
4382
4383
4384
4385
4386
4387
4388
4389
4390
4391
4392
4393
4394
4395
4396
4397
4398
4399
4400
4401
4402
4403
4404
4405
4406
4407
4408
4409
4410
4411
4412
4413
4414
4415
4416
4417
4418
4419
4420
4421
4422
4423
4424
4425
4426
4427
4428
4429
4430
4431
4432
4433
4434
4435
4436
4437
4438
4439
4440
4441
4442
4443
4444
4445
4446
4447
4448
4449
4450
4451
4452
4453
4454
4455
4456
4457
4458
4459
4460
4461
4462
4463
4464
4465
4466
4467
4468
4469
4470
4471
4472
4473
4474
4475
4476
4477
4478
4479
4480
4481
4482
4483
4484
4485
4486
4487
4488
4489
4490
4491
4492
4493
4494
4495
4496
4497
4498
4499
4500
4501
4502
4503
4504
4505
4506
4507
4508
4509
4510
4511
4512
4513
4514
4515
4516
4517
4518
4519
4520
4521
4522
4523
4524
4525
4526
4527
4528
4529
4530
4531
4532
4533
4534
4535
4536
4537
4538
4539
4540
4541
4542
4543
4544
4545
4546
4547
4548
4549
4550
4551
4552
4553
4554
4555
4556
4557
4558
4559
4560
4561
4562
4563
4564
4565
4566
4567
4568
4569
4570
4571
4572
4573
4574
4575
4576
4577
4578
4579
4580
4581
4582
4583
4584
4585
4586
4587
4588
4589
4590
4591
4592
4593
4594
4595
4596
4597
4598
4599
4600
4601
4602
4603
4604
4605
4606
4607
4608
4609
4610
4611
4612
4613
4614
4615
4616
4617
4618
4619
4620
4621
4622
4623
4624
4625
4626
4627
4628
4629
4630
4631
4632
4633
4634
4635
4636
4637
4638
4639
4640
4641
4642
4643
4644
4645
4646
4647
4648
4649
4650
4651
4652
4653
4654
4655
4656
4657
4658
4659
4660
4661
4662
4663
4664
4665
4666
4667
4668
4669
4670
4671
4672
4673
4674
4675
4676
4677
4678
4679
4680
4681
4682
4683
4684
4685
4686
4687
4688
4689
4690
4691
4692
4693
4694
4695
4696
4697
4698
4699
4700
4701
4702
4703
4704
4705
4706
4707
4708
4709
4710
4711
4712
4713
4714
4715
4716
4717
4718
4719
4720
4721
4722
4723
4724
4725
4726
4727
4728
4729
4730
4731
4732
4733
4734
4735
4736
4737
4738
4739
4740
4741
4742
4743
4744
4745
4746
4747
4748
4749
4750
4751
4752
4753
4754
4755
4756
4757
4758
4759
4760
4761
4762
4763
4764
4765
4766
4767
4768
4769
4770
4771
4772
4773
4774
4775
4776
4777
4778
4779
4780
4781
4782
4783
4784
4785
4786
4787
4788
4789
4790
4791
4792
4793
4794
4795
4796
4797
4798
4799
4800
4801
4802
4803
4804
4805
4806
4807
4808
4809
4810
4811
4812
4813
4814
4815
4816
4817
4818
4819
4820
4821
4822
4823
4824
4825
4826
4827
4828
4829
4830
4831
4832
4833
4834
4835
4836
4837
4838
4839
4840
4841
4842
4843
4844
4845
4846
4847
4848
4849
4850
4851
4852
4853
4854
4855
4856
4857
4858
4859
4860
4861
4862
4863
4864
4865
4866
4867
4868
4869
4870
4871
4872
4873
4874
4875
4876
4877
4878
4879
4880
4881
4882
4883
4884
4885
4886
4887
4888
4889
4890
4891
4892
4893
4894
4895
4896
4897
4898
4899
4900
4901
4902
4903
4904
4905
4906
4907
4908
4909
4910
4911
4912
4913
4914
4915
4916
4917
4918
4919
4920
4921
4922
4923
4924
4925
4926
4927
4928
4929
4930
4931
4932
4933
4934
4935
4936
4937
4938
4939
4940
4941
4942
4943
4944
4945
4946
4947
4948
4949
4950
4951
4952
4953
4954
4955
4956
4957
4958
4959
4960
4961
4962
4963
4964
4965
4966
4967
4968
4969
4970
4971
4972
4973
4974
4975
4976
4977
4978
4979
4980
4981
4982
4983
4984
4985
4986
4987
4988
4989
4990
4991
4992
4993
4994
4995
4996
4997
4998
4999
5000
5001
5002
5003
5004
5005
5006
5007
5008
5009
5010
5011
5012
5013
5014
5015
5016
5017
5018
5019
5020
5021
5022
5023
5024
5025
5026
5027
5028
5029
5030
5031
5032
5033
5034
5035
5036
5037
5038
5039
5040
5041
5042
5043
5044
5045
5046
5047
5048
5049
5050
5051
5052
5053
5054
5055
5056
5057
5058
5059
5060
5061
5062
5063
5064
5065
5066
5067
5068
5069
5070
5071
5072
5073
5074
5075
5076
5077
5078
5079
5080
5081
5082
5083
5084
5085
5086
5087
5088
5089
5090
5091
5092
5093
5094
5095
5096
5097
5098
5099
5100
5101
5102
5103
5104
5105
5106
5107
5108
5109
5110
5111
5112
5113
5114
5115
5116
5117
5118
5119
5120
5121
5122
5123
5124
5125
5126
5127
5128
5129
5130
5131
5132
5133
5134
5135
5136
5137
5138
5139
5140
5141
5142
5143
5144
5145
5146
5147
5148
5149
5150
5151
5152
5153
5154
5155
5156
5157
5158
5159
5160
5161
5162
5163
5164
5165
5166
5167
5168
5169
5170
5171
5172
5173
5174
5175
5176
5177
5178
5179
5180
5181
5182
5183
5184
5185
5186
5187
5188
5189
5190
5191
5192
5193
5194
5195
5196
5197
5198
5199
5200
5201
5202
5203
5204
5205
5206
5207
5208
5209
5210
5211
5212
5213
5214
5215
5216
5217
5218
5219
5220
5221
5222
5223
5224
5225
5226
5227
5228
5229
5230
5231
5232
5233
5234
5235
5236
5237
5238
5239
5240
5241
5242
5243
5244
5245
5246
5247
5248
5249
5250
5251
5252
5253
5254
5255
5256
5257
5258
5259
5260
5261
5262
5263
5264
5265
5266
5267
5268
5269
5270
5271
5272
5273
5274
5275
5276
5277
5278
5279
5280
5281
5282
5283
5284
5285
5286
5287
5288
5289
5290
5291
5292
5293
5294
5295
5296
5297
5298
5299
5300
5301
5302
5303
5304
5305
5306
5307
5308
5309
5310
5311
5312
5313
5314
5315
5316
5317
5318
5319
5320
5321
5322
5323
5324
5325
5326
5327
5328
5329
5330
5331
5332
5333
5334
5335
5336
5337
5338
5339
5340
5341
5342
5343
5344
5345
5346
5347
5348
5349
5350
5351
5352
5353
5354
5355
5356
5357
5358
5359
5360
5361
5362
5363
5364
5365
5366
5367
5368
5369
5370
5371
5372
5373
5374
5375
5376
5377
5378
5379
5380
5381
5382
5383
5384
5385
5386
5387
5388
5389
5390
5391
5392
5393
5394
5395
5396
5397
5398
5399
5400
5401
5402
5403
5404
5405
5406
5407
5408
5409
5410
5411
5412
5413
5414
5415
5416
5417
5418
5419
5420
5421
5422
5423
5424
5425
5426
5427
5428
5429
5430
5431
5432
5433
5434
5435
5436
5437
5438
5439
5440
5441
5442
5443
5444
5445
5446
5447
5448
5449
5450
5451
5452
5453
5454
5455
5456
5457
5458
5459
5460
5461
5462
5463
5464
5465
5466
5467
5468
5469
5470
5471
5472
5473
5474
5475
5476
5477
5478
5479
5480
5481
5482
5483
5484
5485
5486
5487
5488
5489
5490
5491
5492
5493
5494
5495
5496
5497
5498
5499
5500
5501
5502
5503
5504
5505
5506
5507
5508
5509
5510
5511
5512
5513
5514
5515
5516
5517
5518
5519
5520
5521
5522
5523
5524
5525
5526
5527
5528
5529
5530
5531
5532
5533
5534
5535
5536
5537
5538
5539
5540
5541
5542
5543
5544
5545
5546
5547
5548
5549
5550
5551
5552
5553
5554
5555
5556
5557
5558
5559
5560
5561
5562
5563
5564
5565
5566
5567
5568
5569
5570
5571
5572
5573
5574
5575
5576
5577
5578
5579
5580
5581
5582
5583
5584
5585
5586
5587
5588
5589
5590
5591
5592
5593
5594
5595
5596
5597
5598
5599
5600
5601
5602
5603
5604
5605
5606
5607
5608
5609
5610
5611
5612
5613
5614
5615
5616
5617
5618
5619
5620
5621
5622
5623
5624
5625
5626
5627
5628
5629
5630
5631
5632
5633
5634
5635
5636
5637
5638
5639
5640
5641
5642
5643
5644
5645
5646
5647
5648
5649
5650
5651
5652
5653
5654
5655
5656
5657
5658
5659
5660
5661
5662
5663
5664
5665
5666
5667
5668
5669
5670
5671
5672
5673
5674
5675
5676
5677
5678
5679
5680
5681
5682
5683
5684
5685
5686
5687
5688
5689
5690
5691
5692
5693
5694
5695
5696
5697
5698
5699
5700
5701
5702
5703
5704
5705
5706
5707
5708
5709
5710
5711
5712
5713
5714
5715
5716
5717
5718
5719
5720
5721
5722
5723
5724
5725
5726
5727
5728
5729
5730
5731
5732
5733
5734
5735
5736
5737
5738
5739
5740
5741
5742
5743
5744
5745
5746
5747
5748
5749
5750
5751
5752
5753
5754
5755
5756
5757
5758
5759
5760
5761
5762
5763
5764
5765
5766
5767
5768
5769
5770
5771
5772
5773
5774
5775
5776
5777
5778
5779
5780
5781
5782
5783
5784
5785
5786
5787
5788
5789
5790
5791
5792
5793
5794
5795
5796
5797
5798
5799
5800
5801
5802
5803
5804
5805
5806
5807
5808
5809
5810
5811
5812
5813
5814
5815
5816
5817
5818
5819
5820
5821
5822
5823
5824
5825
5826
5827
5828
5829
5830
5831
5832
5833
5834
5835
5836
5837
5838
5839
5840
5841
5842
5843
5844
5845
5846
5847
5848
5849
5850
5851
5852
5853
5854
5855
5856
5857
5858
5859
5860
5861
5862
5863
5864
5865
5866
5867
5868
5869
5870
5871
5872
5873
5874
5875
5876
5877
5878
5879
5880
5881
5882
5883
5884
5885
5886
5887
5888
5889
5890
5891
5892
5893
5894
5895
5896
5897
5898
5899
5900
5901
5902
5903
5904
5905
5906
5907
5908
5909
5910
5911
5912
5913
5914
5915
5916
5917
5918
5919
5920
5921
5922
5923
5924
5925
5926
5927
5928
5929
5930
5931
5932
5933
5934
5935
5936
5937
5938
5939
5940
5941
5942
5943
5944
5945
5946
5947
5948
5949
5950
5951
5952
5953
5954
5955
5956
5957
5958
5959
5960
5961
5962
5963
5964
5965
5966
5967
5968
5969
5970
5971
5972
5973
5974
5975
5976
5977
5978
5979
5980
5981
5982
5983
5984
5985
5986
5987
5988
5989
5990
5991
5992
5993
5994
5995
5996
5997
5998
5999
6000
6001
6002
6003
6004
6005
6006
6007
6008
6009
6010
6011
6012
6013
6014
6015
6016
6017
6018
6019
6020
6021
6022
6023
6024
6025
6026
6027
6028
6029
6030
6031
6032
6033
6034
6035
6036
6037
6038
6039
6040
6041
6042
6043
6044
6045
6046
6047
6048
6049
6050
6051
6052
6053
6054
6055
6056
6057
6058
6059
6060
6061
6062
6063
6064
6065
6066
6067
6068
6069
6070
6071
6072
6073
6074
6075
6076
6077
6078
6079
6080
6081
6082
6083
6084
6085
6086
6087
6088
6089
6090
6091
6092
6093
6094
6095
6096
6097
6098
6099
6100
6101
6102
6103
6104
6105
6106
6107
6108
6109
6110
6111
6112
6113
6114
6115
6116
6117
6118
6119
6120
6121
6122
6123
6124
6125
6126
6127
6128
6129
6130
6131
6132
6133
6134
6135
6136
6137
6138
6139
6140
6141
6142
6143
6144
6145
6146
6147
6148
6149
6150
6151
6152
6153
6154
6155
6156
6157
6158
6159
6160
6161
6162
6163
6164
6165
6166
6167
6168
6169
6170
6171
6172
6173
6174
6175
6176
6177
6178
6179
6180
6181
6182
6183
6184
6185
6186
6187
6188
6189
6190
6191
6192
6193
6194
6195
6196
6197
6198
6199
6200
6201
6202
6203
6204
6205
6206
6207
6208
6209
6210
6211
6212
6213
6214
6215
6216
6217
6218
6219
6220
6221
6222
6223
6224
6225
6226
6227
6228
6229
6230
6231
6232
6233
6234
6235
6236
6237
6238
6239
6240
6241
6242
6243
6244
6245
6246
6247
6248
6249
6250
6251
6252
6253
6254
6255
6256
6257
6258
6259
6260
6261
6262
6263
6264
6265
6266
6267
6268
6269
6270
6271
6272
6273
6274
6275
6276
6277
6278
6279
6280
6281
6282
6283
6284
6285
6286
6287
6288
6289
6290
6291
6292
6293
6294
6295
6296
6297
6298
6299
6300
6301
6302
6303
6304
6305
6306
6307
6308
6309
6310
6311
6312
6313
6314
6315
6316
6317
6318
6319
6320
6321
6322
6323
6324
6325
6326
6327
6328
6329
6330
6331
6332
6333
6334
6335
6336
6337
6338
6339
6340
6341
6342
6343
6344
6345
6346
6347
6348
6349
6350
6351
6352
6353
6354
6355
6356
6357
6358
6359
6360
6361
6362
6363
6364
6365
6366
6367
6368
6369
6370
6371
6372
6373
6374
6375
6376
6377
6378
6379
6380
6381
6382
6383
6384
6385
6386
6387
6388
6389
6390
6391
6392
6393
6394
6395
6396
6397
6398
6399
6400
6401
6402
6403
6404
6405
6406
6407
6408
6409
6410
6411
6412
6413
6414
6415
6416
6417
6418
6419
6420
6421
6422
6423
6424
6425
6426
6427
6428
6429
6430
6431
6432
6433
6434
6435
6436
6437
6438
6439
6440
6441
6442
6443
6444
6445
6446
6447
6448
6449
6450
6451
6452
6453
6454
6455
6456
6457
6458
6459
6460
6461
6462
6463
6464
6465
6466
6467
6468
6469
6470
6471
6472
6473
6474
6475
6476
6477
6478
6479
6480
6481
6482
6483
6484
6485
6486
6487
6488
6489
6490
6491
6492
6493
6494
6495
6496
6497
6498
6499
6500
6501
6502
6503
6504
6505
6506
6507
6508
6509
6510
6511
6512
6513
6514
6515
6516
6517
6518
6519
6520
6521
6522
6523
6524
6525
6526
6527
6528
6529
6530
6531
6532
6533
6534
6535
6536
6537
6538
6539
6540
6541
6542
6543
6544
6545
6546
6547
6548
6549
6550
6551
6552
6553
6554
6555
6556
6557
6558
6559
6560
6561
6562
6563
6564
6565
6566
6567
6568
6569
6570
6571
6572
6573
6574
6575
6576
6577
6578
6579
6580
6581
6582
6583
6584
6585
6586
6587
6588
6589
6590
6591
6592
6593
6594
6595
6596
6597
6598
6599
6600
6601
6602
6603
6604
6605
6606
6607
6608
6609
6610
6611
6612
6613
6614
6615
6616
6617
6618
6619
6620
6621
6622
6623
6624
6625
6626
6627
6628
6629
6630
6631
6632
6633
6634
6635
6636
6637
6638
6639
6640
6641
6642
6643
6644
6645
6646
6647
6648
6649
6650
6651
6652
6653
6654
6655
6656
6657
6658
6659
6660
6661
6662
6663
6664
6665
6666
6667
6668
6669
6670
6671
6672
6673
6674
6675
6676
6677
6678
6679
6680
6681
6682
6683
6684
6685
6686
6687
6688
6689
6690
6691
6692
6693
6694
6695
6696
6697
6698
6699
6700
6701
6702
6703
6704
6705
6706
6707
6708
6709
6710
6711
6712
6713
6714
6715
6716
6717
6718
6719
6720
6721
6722
6723
6724
6725
6726
6727
6728
6729
6730
6731
6732
6733
6734
6735
6736
6737
6738
6739
6740
6741
6742
6743
6744
6745
6746
6747
6748
6749
6750
6751
6752
6753
6754
6755
6756
6757
6758
6759
6760
6761
6762
6763
6764
6765
6766
6767
6768
6769
6770
6771
6772
6773
6774
6775
6776
6777
6778
6779
6780
6781
6782
6783
6784
6785
6786
6787
6788
6789
6790
6791
6792
6793
6794
6795
6796
6797
6798
6799
6800
6801
6802
6803
6804
6805
6806
6807
6808
6809
6810
6811
6812
6813
6814
6815
6816
6817
6818
6819
6820
6821
6822
6823
6824
6825
6826
6827
6828
6829
6830
6831
6832
6833
6834
6835
6836
6837
6838
6839
6840
6841
6842
6843
6844
6845
6846
6847
6848
6849
6850
6851
6852
6853
6854
6855
6856
6857
6858
6859
6860
6861
6862
6863
6864
6865
6866
6867
6868
6869
6870
6871
6872
6873
6874
6875
6876
6877
6878
6879
6880
6881
6882
6883
6884
6885
6886
6887
6888
6889
6890
6891
6892
6893
6894
6895
6896
6897
6898
6899
6900
6901
6902
6903
6904
6905
6906
6907
6908
6909
6910
6911
6912
6913
6914
6915
6916
6917
6918
6919
6920
6921
6922
6923
6924
6925
6926
6927
6928
6929
6930
6931
6932
6933
6934
6935
6936
6937
6938
6939
6940
6941
6942
6943
6944
6945
6946
6947
6948
6949
6950
6951
6952
6953
6954
6955
6956
6957
6958
6959
6960
6961
6962
6963
6964
6965
6966
6967
6968
6969
6970
6971
6972
6973
6974
6975
6976
6977
6978
6979
6980
6981
6982
6983
6984
6985
6986
6987
6988
6989
6990
6991
6992
6993
6994
6995
6996
6997
6998
6999
7000
7001
7002
7003
7004
7005
7006
7007
7008
7009
7010
7011
7012
7013
7014
7015
7016
7017
7018
7019
7020
7021
7022
7023
7024
7025
7026
7027
7028
7029
7030
7031
7032
7033
7034
7035
7036
7037
7038
7039
7040
7041
7042
7043
7044
7045
7046
7047
7048
7049
7050
7051
7052
7053
7054
7055
7056
7057
7058
7059
7060
7061
7062
7063
7064
7065
7066
7067
7068
7069
7070
7071
7072
7073
7074
7075
7076
7077
7078
7079
7080
7081
7082
7083
7084
7085
7086
7087
7088
7089
7090
7091
7092
7093
7094
7095
7096
7097
7098
7099
7100
7101
7102
7103
7104
7105
7106
7107
7108
7109
7110
7111
7112
7113
7114
7115
7116
7117
7118
7119
7120
7121
7122
7123
7124
7125
7126
7127
7128
7129
7130
7131
7132
7133
7134
7135
7136
7137
7138
7139
7140
7141
7142
7143
7144
7145
7146
7147
7148
7149
7150
7151
7152
7153
7154
7155
7156
7157
7158
7159
7160
7161
7162
7163
7164
7165
7166
7167
7168
7169
7170
7171
7172
7173
7174
7175
7176
7177
7178
7179
7180
7181
7182
7183
7184
7185
7186
7187
7188
7189
7190
7191
7192
7193
7194
7195
7196
7197
7198
7199
7200
7201
7202
7203
7204
7205
7206
7207
7208
7209
7210
7211
7212
7213
7214
7215
7216
7217
7218
7219
7220
7221
7222
7223
7224
7225
7226
7227
7228
7229
7230
7231
7232
7233
7234
7235
7236
7237
7238
7239
7240
7241
7242
7243
7244
7245
7246
7247
7248
7249
7250
7251
7252
7253
7254
7255
7256
7257
7258
7259
7260
7261
7262
7263
7264
7265
7266
7267
7268
7269
7270
7271
7272
7273
7274
7275
7276
7277
7278
7279
7280
7281
7282
7283
7284
7285
7286
7287
7288
7289
7290
7291
7292
7293
7294
7295
7296
7297
7298
7299
7300
7301
7302
7303
7304
7305
7306
7307
7308
7309
7310
7311
7312
7313
7314
7315
7316
7317
7318
7319
7320
7321
7322
7323
7324
7325
7326
7327
7328
7329
7330
7331
7332
7333
7334
7335
7336
7337
7338
7339
7340
7341
7342
7343
7344
7345
7346
7347
7348
7349
7350
7351
7352
7353
7354
7355
7356
7357
7358
7359
7360
7361
7362
7363
7364
7365
7366
7367
7368
7369
7370
7371
7372
7373
7374
7375
7376
7377
7378
7379
7380
7381
7382
7383
7384
7385
7386
7387
7388
7389
7390
7391
7392
7393
7394
7395
7396
7397
7398
7399
7400
7401
7402
7403
7404
7405
7406
7407
7408
7409
7410
7411
7412
7413
7414
7415
7416
7417
7418
7419
7420
7421
7422
7423
7424
7425
7426
7427
7428
7429
7430
7431
7432
7433
7434
7435
7436
7437
7438
7439
7440
7441
7442
7443
7444
7445
7446
7447
7448
7449
7450
7451
7452
7453
7454
7455
7456
7457
7458
7459
7460
7461
7462
7463
7464
7465
7466
7467
7468
7469
7470
7471
7472
7473
7474
7475
7476
7477
7478
7479
7480
7481
7482
7483
7484
7485
7486
7487
7488
7489
7490
7491
7492
7493
7494
7495
7496
7497
7498
7499
7500
7501
7502
7503
7504
7505
7506
7507
7508
7509
7510
7511
7512
7513
7514
7515
7516
7517
7518
7519
7520
7521
7522
7523
7524
7525
7526
7527
7528
7529
7530
7531
7532
7533
7534
7535
7536
7537
7538
7539
7540
7541
7542
7543
7544
7545
7546
7547
7548
7549
7550
7551
7552
7553
7554
7555
7556
7557
7558
7559
7560
7561
7562
7563
7564
7565
7566
7567
7568
7569
7570
7571
7572
7573
7574
7575
7576
7577
7578
7579
7580
7581
7582
7583
7584
7585
7586
7587
7588
7589
7590
7591



NOTE: DEED INFORMATION MISSING ON PARCELS MARKED WITH ASTERISKS.

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BYRES	AREA OF TAKING
262-C-LA	ALLEN J. STUMP VIOLA V. STUMP	2-S. FR.	10×18 FR.		5,427
262-D-LA	LOUIS H. MAUSER	2-S. FR.	10×20 FR.	12×16 SHED	5,720
262-E-LA	EDWARD VELAR	2-S. FR.			6,000
262-F-LA	TUFIC SAADI	2-S. FR.	12×18 FR.		6,889
262-H-LA	LAURA GARDNER	2-S. FR.	12×20 FR.		3,580
262-J-LA	GEORGE SUBER PEARL SUBER	2-S. FR.	20×18 FR.		306
263-LA	UMBERTO TURSINI ANNA TURSINI	2-S. STUCCO			2,530
264-LA	WILLIAM MOSKOSKY HELEN MOSKOSKY				48,620
265-LA	ALTON L. KEMP ALICE L. KEMP	2-S. STUCCO			11,109
265-A-LA	MARY LUNDY	2-S. STUCCO			7,511
265-B-LA	FRANK J COLLA	2-S. STUCCO			7,508
266-LA	JAMES LADIGO	2-S. STUCCO			7,462
266-B-LA	JOSEPH M. ALLISON MARIAN A. ALLISON	2-S. STUCCO			7,459

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BYRES	AREA OF TAKING
266-C-LA	THOMAS HOOD	2-S. STUCCO			
267-LA	BESSIE P CONNELL THOMAS H. CONNELL			18×17 ST. HSE	68,502
267-A-LA	ESTHER MEYER				1,262
267-B-LA	VANCE WAGNER	2-S. FR.			1,826
* 267-C-LA					690
* 267-D-LA	MINNIE MAUSER	2-S. FR.	10×20 FR.	12×16 SHED	1,000
* 267-E-LA					3,855
268-LA	BESSIE P CONNELL THOMAS H. CONNELL				5,202
* 268-A-LA	*BESSIE P. CONNELL THOMAS H. CONNELL*				278
269-LA	INEZ PARKER	2-S. FR.	10×18 FR.		4,200
271-LA	HARRY & NELLIE MEYERS	2-S. FR.			2,400
271-A-LA	*GOLDEN AGE BEVERAGE CORP.*				1,050
* 271-B-LA	YOUNGSTOWN FURNACE CO.				

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BYRES	AREA OF TAKING
272-LA	MALACHI STOKES THELMA STOKES	2-S. FR.	12×18 BR.		3,702
273-LA	JOHN G. SPATHOLT	2-S. FR.			1,800
274-LA	JOHN H. LOGAN LULA LOGAN	2-S. FR.			2,230
275-LA	LEROY SMITH NETTIE SMITH	2-S. FR.			1,625
275-A-LA	JOHNNIE PEARL REED	2-S. FR.			1,587
276-LA	FRED & ROISE PERKINS	2-S. FR.			1,932
277-LA	THEODORE COTTON JR. CARRIE COTTON	2-2 ST. B.R.			1,813
279-LA	ANN KAUFMAN BETTY LABEL	2-2 ST. FR.			4,950
280-LA	GOLDEN AGE BEVERAGE CORP.			72×125 C.B.	19,657
283-B-LA	HOWARD BURKES MILLERNEE BURKES	1½-S. FR.			2,600
289-LA	BESSIE P. CONNELL THOMAS H. CONNELL				3,600
* 289-A-LA	WALDEMAR NISCHWITZ EARL H. HARRIS	2-S. FR.			1,157
290-LA	ETHEL McDANIELS SPEAKS	1-S. FR.		12×18 SHED	2,948

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BYRES	AREA OF TAKING
291-LA	ELIZABETH BUEHRLE				2,282
292-LA	WALDEMAR NISCHWITZ EARL H. HARRIS	2-S. FR. 1-S. FR.	14×22 C.B.		5,939
294-LA	WILLIAM ALLEN ANNIE ALLEN	2-S. FR. 2-S. FR.			3,943
295-LA	MARY PEAY	2-S. FR.		8×6 FR. SHED	4,180
296-LA	ELIDA MOELLERING	2-S. FR.			4,350
273-A-LA	JOHN G. SPATHOLT	2-S. FR.			2,080
273-B-LA	JOHN G. SPATHOLT	2-S. FR.			1,870
273-C-LA	JOHN G. SPATHOLT	2-S. FR.			3,150
276-A-LA	*FRED AND ROISE PERKINS ETAL*				767

WORK AGREEMENT


PARCEL NO.	NAME	DESCRIPTION
262-H-WA	LAURA GARDNER	REMOVE GAR. FD'N.
271-WA	HARRY & NELLIE MEYERS	FILL BASEMENT
283-B-WA	HOWARD BURKES MILLERNEE BURKES	FILL BASEMENT
267-D-WA	MINNIE MAUSER	FILL BASEMENT
262-F-WA	TUFIC SAADI	FILL BASEMENT
262-C-WA	ALLEN J. STUMP VIOLA V. STUMP	REMOVE GAR. FD'N.

REVISIONS

REV. NO.	NATURE OF REVISION	DATE COMP DATE	MADE BY
# 1	ADDED RET. WALL & BARRICADE	12-30-59	J.E.P.
	REVISED ℄ ALINE FOR RET. WALL		
# 2	ADDED R.	3-29-60	J.D.P.
	Added Names Pcls. 271-A-LA & 276-A-LA-Area	7-6-60	S.S.
	Pcls. 268-A-LA & 268-LA Added Name & Area	7-6-60	S.S.


FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	


481
492


BEGIN SHEET — STA. 1000+00
END SHEET — STA. 1010+00
55-18 1853 L.F. TYPE "C" FENCE
551 L.F. TYPE "C" FENCE
591 L.F. TYPE "C" FENCE
422 L.F. TYPE "C" FENCE
288 L.F. TYPE "C" FENCE
WALTER STREET
HIGH STREET
PIKE
OAK HILL AVE.
FILLING STATION
CHURCH
SCRUB
TIMBER
PARKING AREA
PARKING AREA
RETAINING WALL
WALL
WALL
L.A. LIMIT
S. 5° 54' 34" E.
N.
1548
1549
1550
1551
1552
1553
1568
1569
5621
43581
842
843
844
839
838
849
853
854
852
851
850
2240
2239
2238
2237
2242
2241
2243
2245
1575
1007
1008
1009
1010
1011
1012
1013
1014
1015
1016
1017
1018
1019
1020
1021
1022
1023
1024
1025
1026
1027
1028
1029
1030
1031
1032
1033
1034
1035
1036
1037
1038
1039
1040
1041
1042
1043
1044
1045
1046
1047
1048
1049
1050
1051
1052
1053
1054
1055
1056
1057
1058
1059
1060
1061
1062
1063
1064
1065
1066
1067
1068
1069
1070
1071
1072
1073
1074
1075
1076
1077
1078
1079
1080
1081
1082
1083
1084
1085
1086
1087
1088
1089
1090
1091
1092
1093
1094
1095
1096
1097
1098
1099
1100
1101
1102
1103
1104
1105
1106
1107
1108
1109
1110
1111
1112
1113
1114
1115
1116
1117
1118
1119
1120
1121
1122
1123
1124
1125
1126
1127
1128
1129
1130
1131
1132
1133
1134
1135
1136
1137
1138
1139
1140
1141
1142
1143
1144
1145
1146
1147
1148
1149
1150
1151
1152
1153
1154
1155
1156
1157
1158
1159
1160
1161
1162
1163
1164
1165
1166
1167
1168
1169
1170
1171
1172
1173
1174
1175
1176
1177
1178
1179
1180
1181
1182
1183
1184
1185
1186
1187
1188
1189
1190
1191
1192
1193
1194
1195
1196
1197
1198
1199
1200
1201
1202
1203
1204
1205
1206
1207
1208
1209
1210
1211
1212
1213
1214
1215
1216
1217
1218
1219
1220
1221
1222
1223
1224
1225
1226
1227
1228
1229
1230
1231
1232
1233
1234
1235
1236
1237
1238
1239
1240
1241
1242
1243
1244
1245
1246
1247
1248
1249
1250
1251
1252
1253
1254
1255
1256
1257
1258
1259
1260
1261
1262
1263
1264
1265
1266
1267
1268
1269
1270
1271
1272
1273
1274
1275
1276
1277
1278
1279
1280
1281
1282
1283
1284
1285
1286
1287
1288
1289
1290
1291
1292
1293
1294
1295
1296
1297
1298
1299
1300
1301
1302
1303
1304
1305
1306
1307
1308
1309
1310
1311
1312
1313
1314
1315
1316
1317
1318
1319
1320
1321
1322
1323
1324
1325
1326
1327
1328
1329
1330
1331
1332
1333
1334
1335
1336
1337
1338
1339
1340
1341
1342
1343
1344
1345
1346
1347
1348
1349
1350
1351
1352
1353
1354
1355
1356
1357
1358
1359
1360
1361
1362
1363
1364
1365
1366
1367
1368
1369
1370
1371
1372
1373
1374
1375
1376
1377
1378
1379
1380
1381
1382
1383
1384
1385
1386
1387
1388
1389
1390
1391
1392
1393
1394
1395
1396
1397
1398
1399
1400
1401
1402
1403
1404
1405
1406
1407
1408
1409
1410
1411
1412
1413
1414
1415
1416
1417
1418
1419
1420
1421
1422
1423
1424
1425
1426
1427
1428
1429
1430
1431
1432
1433
1434
1435
1436
1437
1438
1439
1440
1441
1442
1443
1444
1445
1446
1447
1448
1449
1450
1451
1452
1453
1454
1455
1456
1457
1458
1459
1460
1461
1462
1463
1464
1465
1466
1467
1468
1469
1470
1471
1472
1473
1474
1475
1476
1477
1478
1479
1480
1481
1482
1483
1484
1485
1486
1487
1488
1489
1490
1491
1492
1493
1494
1495
1496
1497
1498
1499
1500
1501
1502
1503
1504
1505
1506
1507
1508
1509
1510
1511
1512
1513
1514
1515
1516
1517
1518
1519
1520
1521
1522
1523
1524
1525
1526
1527
1528
1529
1530
1531
1532
1533
1534
1535
1536
1537
1538
1539
1540
1541
1542
1543
1544
1545
1546
1547
1548
1549
1550
1551
1552
1553
1554
1555
1556
1557
1558
1559
1560
1561
1562
1563
1564
1565
1566
1567
1568
1569
1570
1571
1572
1573
1574
1575
1576
1577
1578
1579
1580
1581
1582
1583
1584
1585
1586
1587
1588
1589
1590
1591
1592
1593
1594
1595
1596
1597
1598
1599
1600
1601
1602
1603
1604
1605
1606
1607
1608
1609
1610
1611
1612
1613
1614
1615
1616
1617
1618
1619
1620
1621
1622
1623
1624
1625
1626
1627
1628
1629
1630
1631
1632
1633
1634
1635
1636
1637
1638
1639
1640
1641
1642
1643
1644
1645
1646
1647
1648
1649
1650
1651
1652
1653
1654
1655
1656
1657
1658
1659
1660
1661
1662
1663
1664
1665
1666
1667
1668
1669
1670
1671
1672
1673
1674
1675
1676
1677
1678
1679
1680
1681
1682
1683
1684
1685
1686
1687
1688
1689
1690
1691
1692
1693
1694
1695
1696
1697
1698
1699
1700
1701
1702
1703
1704
1705
1706
1707
1708
1709
1710
1711
1712
1713
1714
1715
1716
1717
1718
1719
1720
1721
1722
1723
1724
1725
1726
1727
1728
1729
1730
1731
1732
1733
1734
1735
1736
1737
1738
1739
1740
1741
1742
1743
1744
1745
1746
1747
1748
1749
1750
1751
1752
1753
1754
1755
1756
1757
1758
1759
1760
1761
1762
1763
1764
1765
1766
1767
1768
1769
1770
1771
1772
1773
1774
1775
1776
1777
1778
1779
1780
1781
1782
1783
1784
1785
1786
1787
1788
1789
1790
1791
1792
1793
1794
1795
1796
1797
1798
1799
1800
1801
1802
1803
1804
1805
1806
1807
1808
1809
1810
1811
1812
1813
1814
1815
1816
1817
1818
1819
1820
1821
1822
1823
1824
1825
1826
1827
1828
1829
1830
1831
1832
1833
1834
1835
1836
1837
1838
1839
1840
1841
1842
1843
1844
1845
1846
1847
1848
1849
1850
1851
1852
1853
1854
1855
1856
1857
1858
1859
1860
1861
1862
1863
1864
1865
1866
1867
1868
1869
1870
1871
1872
1873
1874
1875
1876
1877
1878
1879
1880
1881
1882
1883
1884
1885
1886
1887
1888
1889
1890
1891
1892
1893
1894
1895
1896
1897
1898
1899
1900
1901
1902
1903
1904
1905
1906
1907
1908
1909
1910
1911
1912
1913
1914
1915
1916
1917
1918
1919
1920
1921
1922
1923
1924
1925
1926
1927
1928
1929
1930
1931
1932
1933
1934
1935
1936
1937
1938
1939
1940
1941
1942
1943
1944
1945
1946
1947
1948
1949
1950
1951
1952
1953
1954
1955
1956
1957
1958
1959
1960
1961
1962
1963
1964
1965
1966
1967
1968
1969
1970
1971
1972
1973
1974
1975
1976
1977
1978
1979
1980
1981
1982
1983
1984
1985
1986
1987
1988
1989
1990
1991
1992
1993
1994
1995
1996
1997
1998
1999
2000
2001
2002
2003
2004
2005
2006
2007
2008
2009
2010
2011
2012
2013
2014
2015
2016
2017
2018
2019
2020
2021
2022
2023
2024
2025
2026
2027
2028
2029
2030
2031
2032
2033
2034
2035
2036
2037
2038
2039
2040
2041
2042
2043
2044
2045
2046
2047
2048
2049
2050
2051
2052
2053
2054
2055
2056
2057
2058
2059
2060
2061
2062
2063
2064
2065
2066
2067
2068
2069
2070
2071
2072
2073
2074
2075
2076
2077
2078
2079
2080
2081
2082
2083
2084
2085
2086
2087
2088
2089
2090
2091
2092
2093
2094
2095
2096
2097
2098
2099
2100
2101
2102
2103
2104
2105
2106
2107
2108
2109
2110
2111
2112
2113
2114
2115
2116
2117
2118
2119
2120
2121
2122
2123
2124
2125
2126
2127
2128
2129
2130
2131
2132
2133
2134
2135
2136
2137
2138
2139
2140
2141
2142
2143
2144
2145
2146
2147
2148
2149
2150
2151
2152
2153
2154
2155
2156
2157
2158
2159
2160
2161
2162
2163
2164
2165
2166
2167
2168
2169
2170
2171
2172
2173
2174
2175
2176
2177
2178
2179
2180
2181
2182
2183
2184
2185
2186
2187
2188
2189
2190
2191
2192
2193
2194
2195
2196
2197
2198
2199
2200
2201
2202
2203
2204
2205
2206
2207
2208
2209
2210
2211
2212
2213
2214
2215
2216
2217
2218
2219
2220
2221
2222
2223
2224
2225
2226
2227
2228
2229
2230
2231
2232
2233
2234
2235
2236
2237
2238
2239
2240
2241
2242
2243
2244
2245
2246
2247
2248
2249
2250
2251
2252
2253
2254
2255
2256
2257
2258
2259
2260
2261
2262
2263
2264
2265
2266
2267
2268
2269
2270
2271
2272
2273
2274
2275
2276
2277
2278
2279
2280
2281
2282
2283
2284
2285
2286
2287
2288
2289
2290
2291
2292
2293
2294
2295
2296
2297
2298
2299
2300
2301
2302
2303
2304
2305
2306
2307
2308
2309
2310
2311
2312
2313
2314
2315
2316
2317
2318
2319
2320
2321
2322
2323
2324
2325
2326
2327
2328
2329
2330
2331
2332
2333
2334
2335
2336
2337
2338
2339
2340
2341
2342
2343
2344
2345
2346
2347
2348
2349
2350
2351
2352
2353
2354
2355
2356
2357
2358
2359
2360
2361
2362
2363
2364
2365
2366
2367
2368
2369
2370
2371
2372
2373
2374
2375
2376
2377
2378
2379
2380
2381
2382
2383
2384
2385
2386
2387
2388
2389
2390
2391
2392
2393
2394
2395
2396
2397
2398
2399
2400
2401
2402
2403
2404
2405
2406
2407
2408
2409
2410
2411
2412
2413
2414
2415
2416
2417
2418
2419
2420
2421
2422
2423
2424
2425
2426
2427
2428
2429
2430
2431
2432
2433
2434
2435
2436
2437
2438
2439
2440
2441
2442
2443
2444
2445
2446
2447
2448
2449
2450
2451
2452
2453
2454
2455
2456
2457
2458
2459
2460
2461
2462
2463
2464
2465
2466
2467
2468
2469
2470
2471
2472
2473
2474
2475
2476
2477
2478
2479
2480
2481
2482
2483
2484
2485
2486
2487
2488
2489
2490
2491
2492
2493
2494
2495
2496
2497
2498
2499
2500
2501
2502
2503
2504
2505
2506
2507
2508
2509
2510
2511
2512
2513
2514
2515
2516
2517
2518
2519
2520
2521
2522
2523
2524
2525
2526
2527
2528
2529
2530
2531
2532
2533
2534
2535
2536
2537
2538
2539
2540
2541
2542
2543
2544
2545
2546
2547
2548
2549
2550
2551
2552
2553
2554
2555
2556
2557
2558
2559
2560
2561
2562
2563
2564
2565
2566
2567
2568
2569
2570
2571
2572
2573
2574
2575
2576
2577
2578
2579
2580
2581
2582
2583
2584
2585
2586
2587
2588
2589
2590
2591
2592
2593
2594
2595
2596
2597
2598
2599
2600
2601
2602
2603
2604
2605
2606
2607
2608
2609
2610
2611
2612
2613
2614
2615
2616
2617
2618
2619
2620
2621
2622
2623
2624
2625
2626
2627
2628
2629
2630
2631
2632
2633
2634
2635
2636
2637
2638
2639
2640
2641
2642
2643
2644
2645
2646
2647
2648
2649
2650
2651
2652
2653
2654
2655
2656
2657
2658
2659
2660
2661
2662
2663
2664
2665
2666
2667
2668
2669
2670
2671
2672
2673
2674
2675
2676
2677
2678
2679
2680
2681
2682
2683
2684
2685
2686
2687
2688
2689
2690
2691
2692
2693
2694
2695
2696
2697
2698
2699
2700
2701
2702
2703
2704
2705
2706
2707
2708
2709
2710
2711
2712
2713
2714
2715
2716
2717
2718
2719
2720
2721
2722
2723
2724
2725
2726
2727
2728
2729
2730
2731
2732
2733
2734
2735
2736
2737
2738
2739
2740
2741
2742
2743
2744
2745
2746
2747
2748
2749
2750
2751
2752
2753
2754
2755
2756
2757
2758
2759
2760
2761
2762
2763
2764
2765
2766
2767
2768
2769
2770
2771
2772
2773
2774
2775
2776
2777
2778
2779
2780
2781
2782
2783
2784
2785
2786
2787
2788
2789
2790
2791
2792
2793
2794
2795
2796
2797
2798
2799
2800
2801
2802
2803
2804
2805
2806
2807
2808
2809
2810
2811
2812
2813
2814
2815
2816
2817
2818
2819
2820
2821
2822
2823
2824
2825
2826
2827
2828
2829
2830
2831
2832
2833
2834
2835
2836
2837
2838
2839
2840
2841
2842
2843
2844
2845
2846
2847
2848
2849
2850
2851
2852
2853
2854
2855
2856
2857
2858
2859
2860
2861
2862
2863
2864
2865
2866
2867
2868
2869
2870
2871
2872
2873
2874
2875
2876
2877
2878
2879
2880
2881
2882
2883
2884
2885
2886
2887
2888
2889
2890
2891
2892
2893
2894
2895
2896
2897
2898
2899
2900
2901
2902
2903
2904
2905
2906
2907
2908
2909
2910
2911
2912
2913
2914
2915
2916
2917
2918
2919
2920
2921
2922
2923
2924
2925
2926
2927
2928
2929
2930
2931
2932
2933
2934
2935
2936
2937
2938
2939
2940
2941
2942
2943
2944
2945
2946
2947
2948
2949
2950
2951
2952
2953
2954
2955
2956
2957
2958
2959
2960
2961
2962
2963
2964
2965
2966
2967
2968
2969
2970
2971
2972
2973
2974
2975
2976
2977
2978
2979
2980
2981
2982
2983
2984
2985
2986
2987
2988
2989
2990
2991
2992
2993
2994
2995
2996
2997
2998
2999
3000
3001
3002
3003
3004
3005
3006
3007
3008
3009
3010
3011
3012
3013
3014
3015
3016
3017
3018
3019
3020
3021
3022
3023
3024
3025
3026
3027
3028
3029
3030
3031
3032
3033
3034
3035
3036
3037
3038
3039
3040
3041
3042
3043
3044
3045
3046
3047
3048
3049
3050
3051
3052
3053
3054
3055
3056
3057
3058
3059
3060
3061
3062
3063
3064
3065
3066
3067
3068
3069
3070
3071
3072
3073
3074
3075
3076
3077
3078
3079
3080
3081
3082
3083
3084
3085
3086
3087
3088
3089
3090
3091
3092
3093
3094
3095
3096
3097
3098
3099
3100
3101
3102
3103
3104
3105
3106
3107
3108
3109
3110
3111
3112
3113
3114
3115
3116
3117
3118
3119
3120
3121
3122
3123
3124
3125
3126
3127
3128
3129
3130
3131
3132
3133
3134
3135
3136
3137
3138
3139
3140
3141
3142
3143
3144
3145
3146
3147
3148
3149
3150
3151
3152
3153
3154
3155
3156
3157
3158
3159
3160
3161
3162
3163
3164
3165
3166
3167
3168
3169
3170
3171
3172
3173
3174
3175
3176
3177
3178
3179
3180
3181
3182
3183
3184
3185
3186
3187
3188
3189
3190
3191
3192
3193
3194
3195
3196
3197
3198
3199
3200
3201
3202
3203
3204
3205
3206
3207
3208
3209
3210
3211
3212
3213
3214
3215
3216
3217
3218
3219
3220
3221
3222
3223
3224
3225
3226
3227
3228
3229
3230
3231
3232
3233
3234
3235
3236
3237
3238
3239
3240
3241
3242
3243
3244
3245
3246
3247
3248
3249
3250
3251
3252
3253
3254
3255
3256
3257
3258
3259
3260
3261
3262
3263
3264
3265
3266
3267
3268
3269
3270
3271
3272
3273
3274
3275
3276
3277
3278
3279
3280
3281
3282
3283
3284
3285
3286
3287
3288
3289
3290
3291
3292
3293
3294
3295
3296
3297
3298
3299
3300
3301
3302
3303
3304
3305
3306
3307
3308
3309
3310
3311
3312
3313
3314
3315
3316
3317
3318
3319
3320
3321
3322
3323
3324
3325
3326
3327
3328
3329
3330
3331
3332
3333
3334
3335
3336
3337
3338
3339
3340
3341
3342
3343
3344
3345
3346
3347
3348
3349
3350
3351
3352
3353
3354
3355
3356
3357
3358
3359
3360
3361
3362
3363
3364
3365
3366
3367
3368
3369
3370
3371
3372
3373
3374
3375
3376
3377
3378
3379
3380
3381
3382
3383
3384
3385
3386
3387
3388
3389
3390
3391
3392
3393
3394
3395
3396
3397
3398
3399
3400
3401
3402
3403
3404
3405
3406
3407
3408
3409
3410
3411
3412
3413
3414
3415
3416
3417
3418
3419
3420
3421
3422
3423
3424
3425
3426
3427
3428
3429
3430
3431
3432
3433
3434
3435
3436
3437
3438
3439
3440
3441
3442
3443
3444
3445
3446
3447
3448
3449
3450
3451
3452
3453
3454
3455
3456
3457
3458
3459
3460
3461
3462
3463
3464
3465
3466
3467
3468
3469
3470
3471
3472
3473
3474
3475
3476
3477
3478
3479
3480
3481
3482
3483
3484
3485
3486
3487
3488
3489
3490
3491
3492
3493
3494
3495
3496
3497
3498
3499
3500
3501
3502
3503
3504
3505
3506
3507
3508
3509
3510
3511
3512
3513
3514
3515
3516
3517
3518
3519
3520
3521
3522
3523
3524
3525
3526
3527
3528
3529
3530
3531
3532
3533
3534
3535
3536
3537
3538
3539
3540
3541
3542
3543
3544
3545
3546
3547
3548
3549
3550
3551
3552
3553
3554
3555
3556
3557
3558
3559
3560
3561
3562
3563
3564
3565
3566
3567
3568
3569
3570
3571
3572
3573
3574
3575
3576
3577
3578
3579
3580
3581
3582
3583
3584
3585
3586
3587
3588
3589
3590
3591
3592
3593
3594
3595
3596
3597
3598
3599
3600
3601
3602
3603
3604
3605
3606
3607
3608
3609
3610
3611
3612
3613
3614
3615
3616
3617
3618
3619
3620
3621
3622
3623
3624
3625
3626
3627
3628
3629
3630
3631
3632
3633
3634
3635
3636
3637
3638
3639
3640
3641
3642
3643
3644
3645
3646
3647
3648
3649
3650
3651
3652
3653
3654
3655
3656
3657
3658
3659
3660
3661
3662
3663
3664
3665
3666
3667
3668
3669
3670
3671
3672
3673
3674
3675
3676
3677
3678
3679
3680
3681
3682
3683
3684
3685
3686
3687
3688
3689
3690
3691
3692
3693
3694
3695
3696
3697
3698
3699
3700
3701
3702
3703
3704
3705
3706
3707
3708
3709
3710
3711
3712
3713
3714
3715
3716
3717
3718
3719
3720
3721
3722
3723
3724
3725
3726
3727
3728
3729
3730
3731
3732
3733
3734
3735
3736
3737
3738
3739
3740
3741
3742
3743
3744
3745
3746
3747
3748
3749
3750
3751
3752
3753
3754
3755
3756
3757
3758
3759
3760
3761
3762
3763
3764
3765
3766
3767
3768
3769
3770
3771
3772
3773
3774
3775
3776
3777
3778
3779
3780
3781
3782
3783
3784
3785
3786
3787
3788
3789
3790
3791
3792
3793
3794
3795
3796
3797
3798
3799
3800
3801
3802
3803
3804
3805
3806
3807
3808
3809
3810
3811
3812
3813
3814
3815
3816
3817
3818
3819
3820
3821
3822
3823
3824
3825
3826
3827
3828
3829
3830
3831
3832
3833
3834
3835
3836
3837
3838
3839
3840
3841
3842
3843
3844
3845
3846
3847
3848
3849
3850
3851
3852
3853
3854
3855
3856
3857
3858
3859
3860
3861
3862
3863
3864
3865
3866
3867
3868
3869
3870
3871
3872
3873
3874
3875
3876
3877
3878
3879
3880
3881
3882
3883
3884
3885
3886
3887
3888
3889
3890
3891
3892
3893
3894
3895
3896
3897
3898
3899
3900
3901
3902
3903
3904
3905
3906
3907
3908
3909
3910
3911
3912
3913
3914
3915
3916
3917
3918
3919
3920
3921
3922
3923
3924
3925
3926
3927
3928
3929
3930
3931
3932
3933
3934
3935
3936
3937
3938
3939
3940
3941
3942
3943
3944
3945
3946
3947
3948
3949
3950
3951
3952
3953
3954
3955
3956
3957
3958
3959
3960
3961
3962
3963
3964
3965
3966
3967
3968
3969
3970
3971
3972
3973
3974
3975
3976
3977
3978
3979
3980
3981
3982
3983
3984
3985
3986
3987
3988
3989
3990
3991
3992
3993
3994
3995
3996
3997
3998
3999
4000
4001
4002
4003
4004
4005
4006
4007
4008
4009
4010
4011
4012
4013
4014
4015
4016
4017
4018
4019
4020
4021
4022
4023
4024
4025
4026
4027
4028
4029
4030
4031
4032
4033
4034
4035
4036
4037
4038
4039
4040
4041
4042
4043
4044
4045
4046
4047
4048
4049
4050
4051
4052
4053
4054
4055
4056
4057
4058
4059
4060
4061
4062
4063
4064
4065
4066
4067
4068
4069
4070
4071
4072
4073
4074
4075
4076
4077
4078
4079
4080
4081
4082
4083
4084
4085
4086
4087
4088
4089
4090
4091
4092
4093
4094
4095
4096
4097
4098
4099
4100
4101
4102
4103
4104
4105
4106
4107
4108
4109
4110
4111
4112
4113
4114
4115
4116
4117
4118
4119
4120
4121
4122
4123
4124
4125
4126
4127
4128
4129
4130
4131
4132
4133
4134
4135
4136
4137
4138
4139
4140
4141
4142
4143
4144
4145
4146
4147
4148
4149
4150
4151
4152
4153
4154
4155
4156
4157
4158
4159
4160
4161
4162
4163
4164
4165
4166
4167
4168
4169
4170
4171
4172
4173
4174
4175
4176
4177
4178
4179
4180
4181
4182
4183
4184
4185
4186
4187
4188
4189
4190
4191
4192
4193
4194
4195
4196
4197
4198
4199
4200
4201
4202
4203
4204
4205
4206
4207
4208
4209
4210
4211
4212
4213
4214
4215
4216
4217
4218
4219
4220
4221
4222
4223
4224
4225
4226
4227
4228
4229
4230
4231
4232
4233
4234
4235
4236
4237
4238
4239
4240
4241
4242
4243
4244
4245
4246
4247
4248
4249
4250
4251
4252
4253
4254
4255
4256
4257
4258
4259
4260
4261
4262
4263
4264
4265
4266
4267
4268
4269
4270
4271
4272
4273
4274
4275
4276
4277
4278
4279
4280
4281
4282
4283
4284
4285
4286
4287
4288
4289
4290
4291
4292
4293
4294
4295
4296
4297
4298
4299
4300
4301
4302
4303
4304
4305
4306
4307
4308
4309
4310
4311
4312
4313
4314
4315
4316
4317
4318
4319
4320
4321
4322
4323
4324
4325
4326
4327
4328
4329
4330
4331
4332
4333
4334
4335
4336
4337
4338
4339
4340
4341
4342
4343
4344
4345
4346
4347
4348
4349
4350
4351
4352
4353
4354
4355
4356
4357
4358
4359
4360
4361
4362
4363
4364
4365
4366
4367
4368
4369
4370
4371
4372
4373
4374
4375
4376
4377
4378
4379
4380
4381
4382
4383
4384
4385
4386
4387
4388
4389
4390
4391
4392
4393
4394
4395
4396
4397
4398
4399
4400
4401
4402
4403
4404
4405
4406
4407
4408
4409
4410
4411
4412
4413
4414
4415
4416
4417
4418
4419
4420
4421
4422
4423
4424
4425
4426
4427
4428
4429
4430
4431
4432
4433
4434
4435
4436
4437
4438
4439
4440
4441
4442
4443
4444
4445
4446
4447
4448
4449
4450
4451
4452
4453
4454
4455
4456
4457
4458
4459
4460
4461
4462
4463
4464
4465
4466
4467
4468
4469
4470
4471
4472
4473
4474
4475
4476
4477
4478
4479
4480
4481
4482
4483
4484
4485
4486
4487
4488
4489
4490
4491
4492
4493
4494
4495
4496
4497
4498
4499
4500
4501
4502
4503
4504
4505
4506
4507
4508
4509
4510
4511
4512
4513
4514
4515
4516
4517
4518
4519
4520
4521
4522
4523
4524
4525
4526
4527
4528
4529
4530
4531
4532
4533
4534
4535
4536
4537
4538
4539
4540
4541
4542
4543
4544
4545
4546
4547
4548
4549
4550
4551
4552
4553
4554
4555
4556
4557
4558
4559
4560
4561
4562
4563
4564
4565
4566
4567
4568
4569
4570
4571
4572
4573
4574
4575
4576
4577
4578
4579
4580
4581
4582
4583
4584
4585
4586
4587
4588
4589
4590
4591
4592
4593
4594
4595
4596
4597
4598
4599
4600
4601
4602
4603
4604
4605
4606
4607
4608
4609
4610
4611
4612
4613
4614
4615
4616
4617
4618
4619
4620
4621
4622
4623
4624
4625
4626
4627
4628
4629
4630
4631
4632
4633
4634
4635
4636
4637
4638
4639
4640
4641
4642
4643
4644
4645
4646
4647
4648
4649
4650
4651
4652
4653
4654
4655
4656
4657
4658
4659
4660
4661
4662
4663
4664
4665
4666
4667
4668
4669
4670
4671
4672
4673
4674
4675
4676
4677
4678
4679
4680
4681
4682
4683
4684
4685
4686
4687
4688
4689
4690
4691
4692
4693
4694
4695
4696
4697
4698
4699
4700
4701
4702
4703
4704
4705
4706
4707
4708
4709
4710
4711
4712
4713
4714
4715
4716
4717
4718
4719
4720
4721
4722
4723
4724
4725
4726
4727
4728
4729
4730
4731
4732
4733
4734
4735
4736
4737
4738
4739
4740
4741
4742
4743
4744
4745
4746
4747
4748
4749
4750
4751
4752
4753
4754
4755
4756
4757
4758
4759
4760
4761
4762
4763
4764
4765
4766
4767
4768
4769
4770
4771
4772
4773
4774
4775
4776
4777
4778
4779
4780
4781
4782
4783
4784
4785
4786
4787
4788
4789
4790
4791
4792
4793
4794
4795
4796
4797
4798
4799
4800
4801
4802
4803
4804
4805
4806
4807
4808
4809
4810
4811
4812
4813
4814
4815
4816
4817
4818
4819
4820
4821
4822
4823
4824
4825
4826
4827
4828
4829
4830
4831
4832
4833
4834
4835
4836
4837
4838
4839
4840
4841
4842
4843
4844
4845
4846
4847
4848
4849
4850
4851
4852
4853
4854
4855
4856
4857
4858
4859
4860
4861
4862
4863
4864
4865
4866
4867
4868
4869
4870
4871
4872
4873
4874
4875
4876
4877
4878
4879
4880
4881
4882
4883
4884
4885
4886
4887
4888
4889
4890
4891
4892
4893
4894
4895
4896
4897
4898
4899
4900
4901
4902
4903
4904
4905
4906
4907
4908
4909
4910
4911
4912
4913
4914
4915
4916
4917
4918
4919
4920
4921
4922
4923
4924
4925
4926
4927
4928
4929
4930
4931
4932
4933
4934
4935
4936
4937
4938
4939
4940
4941
4942
4943
4944
4945
4946
4947
4948
4949
4950
4951
4952
4953
4954
4955
4956
4957
4958
4959
4960
4961
4962
4963
4964
4965
4966
4967
4968
4969
4970
4971
4972
4973
4974
4975
4976
4977
4978
4979
4980
4981
4982
4983
4984
4985
4986
4987
4988
4989
4990
4991
4992
4993
4994
4995
4996
4997
4998
4999
5000
5001
5002
5003
5004
5005
5006
5007
5008
5009
5010
5011
5012
5013
5014
5015
5016
5017
5018
5019
5020
5021
5022
5023
5024
5025
5026
5027
5028
5029
5030
5031
5032
5033
5034
5035
5036
5037
5038
5039
5040
5041
5042
5043
5044
5045
5046
5047
5048
5049
5050
5051
5052
5053
5054
5055
5056
5057
5058
5059
5060
5061
5062
5063
5064
5065
5066
5067
5068
5069
5070
5071
5072
5073
5074
5075
5076
5077
5078
5079
5080
5081
5082
5083
5084
5085
5086
5087
5088
5089
5090
5091
5092
5093
5094
5095
5096
5097
5098
5099
5100
5101
5102
5103
5104
5105
5106
5107
5108
5109
5110
5111
5112
5113
5114
5115
5116
5117
5118
5119
5120
5121
5122
5123
5124
5125
5126
5127
5128
5129
5130
5131
5132
5133
5134
5135
5136
5137
5138
5139
5140
5141
5142
5143
5144
5145
5146
5147
5148
5149
5150
5151
5152
5153
5154
5155
5156
5157
5158
5159
5160
5161
5162
5163
5164
5165
5166
5167
5168
5169
5170
5171
5172
5173
5174
5175
5176
5177
5178
5179
5180
5181
5182
5183
5184
5185
5186
5187
5188
5189
5190
5191
5192
5193
5194
5195
5196
5197
5198
5199
5200
5201
5202
5203
5204
5205
5206
5207
5208
5209
5210
5211
5212
5213
5214
5215
5216
5217
5218
5219
5220
5221
5222
5223
5224
5225
5226
5227
5228
5229
5230
5231
5232
5233
5234
5235
5236
5237
5238
5239
5240
5241
5242
5243
5244
5245
5246
5247
5248
5249
5250
5251
5252
5253
5254
5255
5256
5257
5258
5259
5260
5261
5262
5263
5264
5265
5266
5267
5268
5269
5270
5271
5272
5273
5274
5275
5276
5277
5278
5279
5280
5281
5282
5283
5284
5285
5286
5287
5288
5289
5290
5291
5292
5293
5294
5295
5296
5297
5298
5299
5300
5301
5302
5303
5304
5305
5306
5307
5308
5309
5310
5311
5312
5313
5314
5315
5316
5317
5318
5319
5320
5321
5322
5323
5324
5325
5326
5327
5328
5329
5330
5331
5332
5333
5334
5335
5336
5337
5338
5339
5340
5341
5342
5343
5344
5345
5346
5347
5348
5349
5350
5351
5352
5353
5354
5355
5356
5357
5358
5359
5360
5361
5362
5363
5364
5365
5366
5367
5368
5369
5370
5371
5372
5373
5374
5375
5376
5377
5378
5379
5380
5381
5382
5383
5384
5385
5386
5387
5388
5389
5390
5391
5392
5393
5394
5395
5396
5397
5398
5399
5400
5401
5402
5403
5404
5405
5406
5407
5408
5409
5410
5411
5412
5413
5414
5415
5416
5417
5418
5419
5420
5421
5422
5423
5424
5425
5426
5427
5428
5429
5430
5431
5432
5433
5434
5435
5436
5437
5438
5439
5440
5441
5442
5443
5444
5445
5446
5447
5448
5449
5450
5451
5452
5453
5454
5455
5456
5457
5458
5459
5460
5461
5462
5463
5464
5465
5466
5467
5468
5469
5470
5471
5472
5473
5474
5475
5476
5477
5478
5479
5480
5481
5482
5483
5484
5485
5486
5487
5488
5489
5490
5491
5492
5493
5494
5495
5496
5497
5498
5499
5500
5501
5502
5503
5504
5505
5506
5507
5508
5509
5510
5511
5512
5513
5514
5515
5516
5517
5518
5519
5520
5521
5522
5523
5524
5525
5526
5527
5528
5529
5530
5531
5532
5533
5534
5535
5536
5537
5538
5539
5540
5541
5542
5543
5544
5545
5546
5547
5548
5549
5550
5551
5552
5553
5554
5555
5556
5557
5558
5559
5560
5561
5562
5563
5564
5565
5566
5567
5568
5569
5570
5571
5572
5573
5574
5575
5576
5577
5578
5579
5580
5581
5582
5583
5584
5585
5586
5587
5588
5589
5590
5591
5592
5593
5594
5595
5596
5597
5598
5599
5600
5601
5602
5603
5604
5605
5606
5607
5608
5609
5610
5611
5612
5613
5614
5615
5616
5617
5618
5619
5620
5621
5622
5623
5624
5625
5626
5627
5628
5629
5630
5631
5632
5633
5634
5635
5636
5637
5638
5639
5640
5641
5642
5643
5644
5645
5646
5647
5648
5649
5650
5651
5652
5653
5654
5655
5656
5657
5658
5659
5660
5661
5662
5663
5664
5665
5666
5667
5668
5669
5670
5671
5672
5673
5674
5675
5676
5677
5678
5679
5680
5681
5682
5683
5684
5685
5686
5687
5688
5689
5690
5691
5692
5693
5694
5695
5696
5697
5698
5699
5700
5701
5702
5703
5704
5705
5706
5707
5708
5709
5710
5711
5712
5713
5714
5715
5716
5717
5718
5719
5720
5721
5722
5723
5724
5725
5726
5727
5728
5729
5730
5731
5732
5733
5734
5735
5736
5737
5738
5739
5740
5741
5742
5743
5744
5745
5746
5747
5748
5749
5750
5751
5752
5753
5754
5755
5756
5757
5758
5759
5760
5761
5762
5763
5764
5765
5766
5767
5768
5769
5770
5771
5772
5773
5774
5775
5776
5777
5778
5779
5780
5781
5782
5783
5784
5785
5786
5787
5788
5789
5790
5791
5792
5793
5794
5795
5796
5797
5798
5799
5800
5801
5802
5803
5804
5805
5806
5807
5808
5809
5810
5811
5812
5813
5814
5815
5816
5817
5818
5819
5820
5821
5822
5823
5824
5825
5826
5827
5828
5829
5830
5831
5832
5833
5834
5835
5836
5837
5838
5839
5840
5841
5842
5843
5844
5845
5846
5847
5848
5849
5850
5851
5852
5853
5854
5855
5856
5857
5858
5859
5860
5861
5862
5863
5864
5865
5866
5867
5868
5869
5870
5871
5872
5873
5874
5875
5876
5877
5878
5879
5880
5881
5882
5883
5884
5885
5886
5887
5888
5889
5890
5891
5892
5893
5894
5895
5896
5897
5898
5899
5900
5901
5902
5903
5904
5905
5906
5907
5908
5909
5910
5911
5912
5913
5914
5915
5916
5917
5918
5919
5920
5921
5922
5923
5924
5925
5926
5927
5928
5929
5930
5931
5932
5933
5934
5935
5936
5937
5938
5939
5940
5941
5942
5943
5944
5945
5946
5947
5948
5949
5950
5951
5952
5953
5954
5955
5956
5957
5958
5959
5960
5961
5962
5963
5964
5965
5966
5967
5968
5969
5970
5971
5972
5973
5974
5975
5976
5977
5978
5979
5980
5981
5982
5983
5984
5985
5986
5987
5988
5989
5990
5991
5992
5993
5994
5995
5996
5997
5998
5999
6000
6001
6002
6003
6004
6005
6006
6007
6008
6009
6010
6011
6012
6013
6014
6015
6016
6017
6018
6019
6020
6021
6022
6023
6024
6025
6026
6027
6028
6029
6030
6031
6032
6033
6034
6035
6036
6037
6038
6039
6040
6041
6042
6043
6044
6045
6046
6047
6048
6049
6050
6051
6052
6053
6054
6055
6056
6057
6058
6059
6060
6061
6062
6063
6064
6065
6066
6067
6068
6069
6070
6071
6072
6073
6074
6075
6076
6077
6078
6079
6080
6081
6082
6083
6084
6085
6086
6087
6088
6089
6090
6091
6092
6093
6094
6095
6096
6097
6098
6099
6100
6101
6102
6103
6104
6105
6106
6107
6108
6109
6110
6111
6112
6113
6114
6115
6116
6117
6118
6119
6120
6121
6122
6123
6124
6125
6126
6127
6128
6129
6130
6131
6132
6133
6134
6135
6136
6137
6138
6139
6140
6141
6142
6143
6144
6145
6146
6147
6148
6149
6150
6151
6152
6153
6154
6155
6156
6157
6158
6159
6160
6161
6162
6163
6164
6165
6166
6167
6168
6169
6170
6171
6172
6173
6174
6175
6176

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

482
492





DETAIL "A"


SS-18 - 1793 L.F. TYPE "C" FENCE

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
313-LA	SEE SHEET #10				
318-LA	YOUNGSTOWN HOSP. ASSOC	MISC. BLD'GS.	HOSPITAL BLD'GS.		158,970
319-LA	THE RENNER CO.	BREWERY BUILDINGS			0.754Ac
321-LA	PHILLIP GREIN	2 ST. BR.	18x18 FR.	12x62 C.B.	9,140
322-LA	JOHN BOGGANS, ET AL	1 ST. FR. 2 FR. ABANDONED		SHED	18,780
323-LA	EUGENE & ESTHER RUSNAK	2 ST. FR. 3 ST. BR.	20x18 20x30 18x18	STUCCO FR. BR.	2,600
326-LA	SEE SHEET #12				
320A-LA	ANNA M. PATTERSON	2-ST. FR.	29x16 FR.		4,500

NOTE: DEED INFORMATION MISSING ON PARCELS MARKED WITH ASTERISKS.

NOTE: SEE SHEET FOR INVENTORY.

NOTE:
THE HORIZONTAL CLEARANCE FROM LIMITED ACCESS LINE TO THE OUTSIDE FACE OF THE DRIVEN PILE IS CALCULATED AT A DISTANCE OF 24.50 FEET BELOW GROUND ELEVATION.



DETAIL "B" ~ DELETED
(No Scale)

WORK AGREEMENT		
PARCEL Nº	NAME	DESCRIPTION
323-WA	EUGENE & ESTHER RUSNAK	REMOVE FD'N.
321-WA	PHILLIP GREIN	REMOVE FD'N.
318-WA	YOUNGSTOWN HOSP. ASSOC.	FILL BASEMENT
319-WA	THE RENNER CO.	REMOVE FD'N.
313-WA	SEE SHEET #15	REMOVE SILO'S

Rev. Nº 8, Deleted 319-Aerial, Revised L.A. Line and Area Pcl. 319-LA Per Warranty Deed Vol 1017 Pg 657 & Case Nº 168065 12/16/63


REVISIONS				REVISIONS			DATE COMP.
REV Nº	NATURE	DATE	MADE BY	REV. NO.	NATURE OF REVISION	DATE	MADE BY
#3	ADDED SEWER EASEM'T Pcl 3195	4-10-61	T.J.	#1	ADDED BRIDGE	2-30-59	J.E.P.
#4	ADDED DETAIL "A" Pcl 319 S	4-18-61	T.J.		REVISED PIKE ST.	1-20-60	
#5	ADDED PARCEL 319 AERIAL	11-6-61	T.J.		REVISED ℄ LINE PARCEL 319-LA	1-20-60	
	REVISE AREA OF TAKING PARCEL 319-LA	11-6-61	T.J.	#2	ADDED R - ADDED TOPO	3-29-60	J.D.P.
#6	REVISED PARCEL 319 AERIAL & REVISED AREA OF TAKING, PARCEL 319 LA & 319 AERIAL	12-11-61			Pcl. 320-A-LA ADDED AREA	7-6-60	S.S.
#7	ADDED BUILDING & CROSS HATCHED	4-5-62			Pcl 318-LA Revised Area & Added Tails	10-18-60	S.S.

I-680

R/W SHEET NO. 17 OF 29

FED. RD.	STATE	PROJECT	
2	OHIO	MAH.-18-17.20	

483
492



SEE DETAIL SHEET No 16 FOR PARCEL 356-LA

WORK AGREEMENT		
PARCEL	NAME	DESCRIPTION
326-WA	RIDGE MEDICAL BLD'G. CO.	REVISE DRIVEWAY
333-WA	JOHN DORLOSAN MARY DORLOSAN	FILL BASEMENT
332-WA	MYRTLE I. MILLER VIRGINIA VIETS CRAMER DOROTHY VIETS GLINES	FILL BASEMENT
342-WA	ELIZABETH HILLOSKY, SR..	FILL BASEMENT
342-A-WA	FLORENCE L. EVANS	FILL BASEMENT
352-WA	LEROY E. BILLIG	FILL BASEMENT
352-A-WA		FILL BASEMENT
350-WA	RALPH A. KELLY ISABELLA M. KELLY	REMOVE FD'N.
353-WA	MORTON, RAYMOND D. & BERNARD WHITE	REMOVE FD'N.
340-WA	HAROLD P. SMITH EMILY E. SMITH	FILL BASEMENT

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
326-LA	RIDGE MEDICAL BLD'G. CO.	1 ST. BR.			42,609
327-LA	ELIZABETH GEORGE	2 ST. FR.	24×20 FR.		8,956
328-LA	LUCY S. MIKITA	2 ST. FR.	36×18 FR.		6,350
329-LA	LESLIE H. SABO ELIZABETH M. SABO	2 ST. FR.			3,409
329-A-LA	M. VERA HERSCHEL	2 ST. FR.	12×16 FR.	10×16 SHED	
330-LA	ANTHONY P. JULIUS	2 ST. FR.			6,250
331-LA	JOSEPH SARISKY	2 ST. FR.			5,686
332-LA	MYRTLE I. MILLER VIRGINIA VIETS CRAMER DOROTHY VIETS GLINES	2 ST. FR.	12×18 FR.	5×14 SHED	6,600
333-A-LA	JOHN DORLOSAN MARY DORLOSAN	2 ST. FR.	12×18 FR.	5×14 SHED	1,250
333-B-LA	GEARLD CARROLL & ALICE CARROLL	2 ST. FR.		8×8 SHED	
334-LA	TUFIC SAADI	1½ ST. FR.	26×16 FR.	22×16 SHED	7,500
335-LA	LALE GRAHOVAC	2 ST. FR.	20×18 FR.		7,500
336-LA	JOSEPH THURIK MARY THURIK	2 ST. FR.			7,500
337-LA	THE INCORPORATED TRUSTEES OF THE GOSPEL WORKER SOC.	2-1 ST. FR.			7,500
338-LA	MILDRED McDONALD	2 ST. FR.	24×20 FR.	10×16 SHED	7,000
339-LA	RALPH A. KELLY ISABELLA M. KELLY	2 ST. FR.	24×18 2 ST. FR.	16×16 SHED	7,344 *
340-LA	CHARLOTTA PISLAK	2 ST. FR.	26×18 2 ST. FR.		5,436
341-LA	JOHN W. TOMALKA, SR. MARY HAZEL TOMALKA	2 ST. FR.			2,875
342-LA	ELIZABETH HILLOSKY, SR.	2 ST. FR.	19×20 FR.		2,225
342-A-LA	FLORENCE L. EVANS	2 ST. FR.	14×18 FR.		1,575

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
344-LA	FRANK JAMES COLLA	2 ST. FR.			3,724
344-A	THE GREEK COMM. AGIOI IOANNIS ORTHODOX CHURCH		39/56		336
345-LA	MARY DEVAN	2 ST. FR.			5,366
346-LA	CLARA ANDERSON	2 ST. FR.	20×20 FR.		7,335
347-LA	FRANK JAMES COLLA	2 ST. FR.			3525
348-LA	JOHN PAUL	3-2 ST. FR.			3,150
350-LA	JOHN BUDAKER ANN BUDAKER	2-2 ST. FR.	12×20 FR.		4,100
352-LA	LEROY E. BILLIG	2 ST. FR.	28×20 20×16		1,025
353-LA	MORTON, RAYMOND D. & BERNARD WHITE	14×12 OFFICE			5,000
352-A-LA	MARY J. COMINOS	2 ST FR			320
356-LA	THE GENERAL ELECTRIC CO.				41,612
358-LA	THE ROAD OF REMEMBRANCE POST #472 AM. LEGION, DEPT. OF OHIO	2 ST. FR.	24×46 FR.		10,750
359-LA	JAMES E. & WENDELL H. BENNETT, IDA JOSEPHINE DATSON	2 ST. FR.			7,325
360-LA	HAROLD P. SMITH EMILY E. SMITH	4 ST. FR.			3,950

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
359-A-LA	JAMES E. & WENDELL H. BENNETT IDA JOSEPHINE DAWSON				1050
344-D-LA	FRANK JAMES COLLA				315
361C LA	NORTHERN INVESTMENT COMPANY				SEE R/W SHEET 19
356-A-LA	THE GENERAL ELECTRIC CO.				SEE R/W SHEET 18
356-T5	" " " "				4,960
348-A	THE CITY OF YOUNGSTOWN (FORMERLY JOHN PAUL)				450
350-A	THE CITY OF YOUNGSTOWN (FORMERLY JOHN BUDAKER)				744

REVISIONS		DATE	COMP. BY
REV. NO.	NATURE OF REVISION		
#3	DELETED 322WA, ADDED 342-A-WA		
	& 360-WA, ADDED R, REVISED R/W		
	FENCE	3-29-60	J.D.P.
#4	Parcels 344B-LA, 359-LA Revised	4-12-60	T.A.B.
#5	Parcel 339-LA Revised	4-18-60	T.A.B.
#6	ADDED PCLS. 348A & 350-A & SHOWED FEDERAL PARTICIPATION PER GUZIAK 6-3-68	6-3-68	J.R.B.

NOTE: DEED INFORMATION MISSING ON PARCELS MARKED WITH ASTERISKS.

REVISIONS		DATE	COMP. BY
REV. NO.	NATURE OF REVISION		
#1	ADDED RETAINING WALLS	12-30-59	J.E.P.
	REVISED ¼ AT PARCEL 326 LA	1-20-60	
	ADDED SEWER & PARCELS 355-A-LA & 341 LA.		
	REVISED 356-LA, 358-LA & 360-LA		
	DELETED 361-LA, ADDED W/AS.		
#2	ADDED 346A LA, 347ALA, REV. 352ALA		

Deleted Pcl. 347ALA, Combined with 347LA. 3-4-65
Revised Pcl. 344 A to include the area upon which the proposed sidewalk was constructed 11-19-62 @
ADDED PCL. 356-T5, DELETED 356-WA 2-22-60 S.S.
Parcel 344-A Revised 6-30-60 S.S.
Parcel 339-LA Revised 6-27-60 S.S.

RECEIVED NOV 23 1962 STATE HIGHWAY DEPT. DIV. NO. 1

FED. RD.	STATE	PROJECT	
2	OHIO		


484/492

MAH-18-17.20

PARCEL 356 LA

GENERAL ELECTRIC CO.

SCALE: 1" = 30'



	STATION	GROUND ELEV.	TOP ELEV.
BEGIN RETAINING WALL	11+77.85	935.66	958.72
	12+40	941.28	963.5
	13+00	942.84	963.5
	14+03.87	945.54	960.61
	14+47	946.68	959.11
	15+13	948.40	956.87
END RETAINING WALL	15+81	950.27	954.58

ADDED PCL-356-TS 1-21-61

Rev. 356-LA & 356-A-LA Revised 7-6-60

I-680

R/W SHEET NO. 19 OF 20

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

485
492

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
356-A-LA	THE GENERAL ELECTRIC CO.				SEE R/W SHEET 18
361-C-LA	NORTHERN INVESTMENT COMPANY				125
362-LA	TINCO DE CARPENTIER	2 ST. BR. JOINING	APTS WITH GARAGES	(AD-	31,857
363-LA	RALPH E. GOFF AGNES E. GOFF	1 ST. C.B.			9,750
364-LA	JOHN COMEK MARY COMEK	2 ST. FR.			4,430
365-LA	SARAH KLATMAN HANNAH KLATMAN	2 ST. FR.			2,275
366-LA	FAY KIRKORSKY	2 ST. FR.	20×20 FR.		4,748
367-LA	IDEALIA HOWELL EUALEE HOWELL	2 ST. FR.	18×15 FR.	5×18 SHED	5,080
368-LA	JAMES DAVIS EULA MAE DAVIS	2 ST. FR.	12×18 FR.		5,420
369-LA	CARRIE E. WATSON	2 ST. FR.	18×16 FR.		5,840
370-LA	THE ECONOMY ELECTRIC CO.	3-2 ST. BR. 1 ST. TILE, 1 ST. BR.			3,094
371-LA	DOROTHY MOHN	2 ST. FR.			6,200
372-LA	DEMETRIOS G. MAVRIKIS	2 ST. FR.		5×8 SHED	5,053
373-LA	SOPHIA MARGOLIS	2 ST. FR.			6,507
374-LA	EDWARD PARKMAN MYRTLE L. PARKMAN	2 ST. FR.			5,871
375-LA	JOHN SPANOS ALEXANDRA SPANOS	2 ST. FR.	12×20 FR.	10×12 FR.	5,731
376-LA	MARY H. MENEGAY CLARA L. PAAR	2 ST. FR.	12×16 FR.		6,000
377-LA	NICHOLAS GLAROS NIKI GLAROS	2 ST. FR.	20×18 FR.		6,780
378-LA	JOHN SERINO & MARY MARZULLO	2 ST. FR.	20×16 FR.		5,467
379-LA	ROSE KNABEL	2 ST. FR.			2,650
380-LA	MARY DEVAN	2 ST. FR.	28×16 FR.		8,180
381-LA	HENRY B. GESSAMAN VIRGINIA GESSAMAN	2 ST. FR.	14×18 FR.		3,518
382-LA	NORQUIST LAND CO.				3,468
383-LA	JOHN J. VERNELLO EDNA M. VERNELLO	2 ST. FR.			3,350
383-B-LA	MARY C. CARTWRIGHT MARGARET CONROY	2 ST. FR.	13×21 C.B.		3,252
384-LA	WILMA V. GING	5-2 ST. FR.	10×16 FR.		6,090
387-LA	THE BOARD OF EDUCATION OF YOUNGSTOWN CITY SCHOOL DIST.	BRICK SCHOOL BLDG.			26,418

55-18 2438 L.F. TYPE "C" FENCE

BEGIN SHEET STA. 1030+00

END SHEET STA. 802+00

MARKET STREET

HAYES AVE

FULTON STREET

MARL Z STREET

PROJECT END MAH-18-17.80

PROJECT BEG. MAH-7-14.20

PARKING AREA

RAMP "N"

TEMPORARY CONSTRUCTION LIMITS

THIS RIGHT-OF-WAY ACQUIRED UNDER PROJECT MAH-7-14.80

4076 L.F. TYPE "C" FENCE

482 L.F. TYPE "C" FENCE

610 L.F. TYPE "C" FENCE

Temporary Easement Line

NOTE: DEED INFORMATION MISSING ON PARCELS MARKED WITH ASTERISKS.

TEMPORARY EASEMENTS AREAS
370-T 5213 Sq Ft.
372-T 616 Sq Ft.

WORK AGREEMENT

PARCEL No.	NAME	DESCRIPTION
433-A-WA	RUTH . B. ROBINS	REMOVE FDT'N.
433-WA	WILLIE JAMES TALLEY	FILL BASEMENT
432-WA	JEAN WEISER ANDREW ROSENFELD	FILL BASEMENT
431-WA	ARNALD & CATHERINE HOWELL	FILL BASEMENT
430-WA	JOHN McCARTY SCHWARTZ	FILL BASEMENT
429-WA	GRANT BARNETT JOSEPHINE BARNETT	FILL BASEMENT
406-B-WA		FILL BASEMENT
378-WA	JOHN SERINO & MARY MARZULLO	FILL BASEMENT
379-WA	ROSE KNOBEL	FILL BASEMENT
362-WA	TINCO DE CARPENTIER	FILL BASEMENT
370-WA	THE ECONOMY ELECTRIC CO.	REMOVE FDT'N. & GRADE AREA
384-WA	WILMA V. GING	FILL BASEMENT

REVISIONS		DATE COMP.	
REV. NO	NATURE OF REVISION	DATE	MADE BY
8	REVISED AREA OF TAKING, FENCE CONSTRUCTION LIMITS & L/A LINE	9/18/61	T.J.
	PARCELS 373-LA, 374-LA, 375-LA, 380-LA 381-LA, 382-LA, 383-LA, 383-B-LA, 384-LA		
9	Added Parcels 370-T, 372-T & Areas	1-11-62	GF

REVISIONS		DATE COMP.	
NO.	NATURE OF REVISION	DATE	MADE BY
#1	ADDED PARCEL 393-A-LA (LAND CONTRACT SALE)	9-17-59	
#2	REVISED PARCELS 390-A-LA, 391-A-LA	11-27-59	
#3	REVISED PARCEL 363-LA	12-11-59	
#4	ADDED RETAINING WALL	12-30-59	J.E.P.
#5	REV. 372-LA, 373-LA, 374-LA, 375-LA, 376-LA, 380-LA		
	381-LA, 382-LA, 383-LA, 383-B-LA, 384-LA, 387-LA		
	ADDED WORK AGREEMENTS		
	PCL. 372-LA, 373-LA, ADDED WORK		
#6	ADDED 384-WA - INCLUDED GRADING		
	UNDER 370-WA - ADDED R.	3-30-60	J.D.P.
#7	ADDED PARCEL 393-A-LA	12-15-60	R.H.

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
390-LA	FREDRIKA I. BOGGS MINTER B. BOGGS	2 ST. FR.	12×18 FR.		3,750
* 390-A-LA	JAMES WALSH JR.				
391-LA	ROSE EVELYN STRAWDERMAN	2 ST. FR.			2,000
* 391-A-LA	MILTON KIBBLE MARY LOU KIBBLE				
392-LA	GIUSEPPE CHIRCHIGLIA ROSE CHIRCHIGLIA	2 ST. FR.			2,000
393-LA	FAY KIRKORSKY	2 ST. FR.			1,875
394-LA	MATTIE B. TERRELL	2 ST. FR.			3,750
395-LA	EVA WILLIAMS ROBERT WILLIAMS	2 ST. FR.	12×16 TILE		3,750
397-LA	CHESTER V. LONG MARGARET F. LONG	3 ST. FR. APT.			3,875
406-LA	CLOYDE JAMES FRY ROBERTA MARIAN FRY	2 ST. FR.	9×20 18×24		4,800
* 406-A-LA		2-2 ST. FR.	6-4×20		
* 406-B-LA		2 ST. FR.			

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
407-LA	LOUIS HARRINGTON JULIA HARRINGTON	3-2 ST. FR.			10,593
425-LA	SOPHIE COHEN	3 ST. BR. 2 ST. BR.	6-0×16 FR.		10,923
426-LA	GEORGE BRADLEY FRANCES JUNE BRADLEY	2 ST. FR.			5,958
427-LA	HELEN BUGNO	2 ST. FR.			4,377
428-LA	EDWARD WILLIAMS J. B. WILLIAMS	1 ST. FR.			2,160
429-LA	GRANT BARNETT JOSEPHINE BARNETT	1 ST. FR.			1,485
430-LA	JOHN McCARTY SCHWARTZ	2 ST. FR.			592
431-LA	ARNOLD & CATHERINE HOWELL	2 ST. FR.			543
432-LA	JEAN WEISER ANDREW ROSENFELD				464
433-LA	WILLIE JAMES TALLEY	2 ST. FR.			342
433-A-LA	RUTH B. ROBINS	2 ST. BR. WAREHOUSE			3,231
393-A-LA	F. KIRKORSKY & C. & E. BENTLEY	2 ST. FR.			1,875

FED. RD	STATE	PROJECT	
2	OHIO	MAH-18-17.20	


486
492

LAKE ERIE & EASTERN RAILROAD RIGHT-OF-WAY PLAT

SCALE: 1" = 50'

PARCEL	OWNER	ACRES
313-LA	L. E. & E. R.R.	0.25
313-A-LA	L. E. & E. R.R.	0.33
313-A	L. E. & E. R.R.	0.93

313-WA	L. E. & E. R.R.	REMOVAL OF CONCRETE SILO



BEGIN DESCRIPTION PARCEL 313-LA
271.17' FROM R.R. STA. 264+63.56
@ AN ANGLE OF 102° 02'
(RAILROAD INFORMATION)
69.97' LEFT OF EXP'WY
STA. 1006+01.95 (ON A RADIAL LINE)

CURVE DATA - PROPOSED PIKE ST. RELOCATION

CURVE Nº 1	CURVE Nº 2	CURVE Nº 3
Δ: 28°	Δ: 8° 02' 44"	Δ: 11° 20' 50"
R: 200'	R: 1432.39'	R: 1056.88'
Dc: 28° 38' 52"	Dc: 4°	Dc: 5° 25' 16"
T: 49.87'	T: 100.73'	T: 105'
Lc: 97.74'	Lc: 201.14'	Lc: 209.31'

CURVE DATA FOR ARC IN LA LINE
Δ: 8° 02' 44"
R: 1415.89'
Dc: 4° 02' 47"
T: 99.57'
Lc: 198.82'

NOTE:
—℄— EXISTING R.R. PROPERTY LINE
—LA— LIMIT OF TAKING FOR EXP'WY
—RW— LIMIT OF TAKING FOR PIKE ST. RELOC.

I-680 R/W SHEET 21 of 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

487
492

BALTIMORE & OHIO RAILROAD RIGHT-OF-WAY PLAT

SCALE: 1"=100'


NOTE:
BEARINGS APPEARING IN BOXED PORTION ARE RELATED TO THE BALTIMORE & OHIO RAILROAD. ALL REMAINING BEARINGS ARE RELATED TO THE YOUNGSTOWN-TOWN EXPRESSWAY, S.R. 18.

EXISTING R.R. PROPERTY LINE
LIMIT OF TAKING FOR EXP'WY

PARCEL	OWNER	ACRES
146-A-LA	BALTIMORE & OHIO R.R.	0.11
164-LA	BALTIMORE & OHIO R.R.	2.60

EASEMENT		
144-S	BALTIMORE & OHIO R.R.	0.06


PARCEL	OWNER	ACRES
C-146-B	BALTIMORE & OHIO R.R.	0.07
C-146-C	BALTIMORE & OHIO R.R.	0.10




Revised 7/11/60 R.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

488
492



RIGHT-OF-WAY OAKWOOD AVENUE					
PARCEL Nº	LOT Nº	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
C-1WA	18181	MARGARET C. BOWREY		YES		HEDGE
C-2WA	18182	ELIZ. LESKO ZAVACAN		YES	YES	CONC. STEPS
C-3WA	18183	JOHN & WASYLYNA IWANIUK		YES	YES	WALL
C-4WA	18184	THEO. & NANCY HASSAY		YES	YES	CONC. STEPS
C-5WA	18185	KOLAR & KURTA		YES	YES	CONC. STEPS
C-6WA	18186	GUSSIE L. HEYMAN		YES	YES	
C-7WA	18187	CHARLES & FLO L. PALISEN		YES	YES	



RIGHT-OF-WAY SILLIMAN STREET					
PARCEL Nº	LOT Nº	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
C-9WA	6788	CHAS. & JUSTINE SEREDNESKY		YES	YES	
C-10WA	15349	MARY KNAPIK		YES	YES	
C-11WA	15350	JOHN & SOPHIE TOPORCER		YES	YES	
C-12WA	15351	JOHN LEJBA		YES	YES	
C-13WA	15352	ALEX & ADA HODORY		YES		
C-14WA	15353	MARY & JOHN SKLEPKO		YES	YES	
C-15WA	15354	PAUL & MARY KISSEL		YES	YES	
C-16WA	6789	MARY PODRAEZKY		YES	YES	
C-17WA	6790	JOHN & HELEN NESTERUK		YES	YES	
C-18WA	6791	PAUL & JULIA ANTEL		YES	YES	
C-19WA	11781	CHARLES F. SEMPLE		YES		
C-B	6784	CHARLES SR & CHRISTINA SEREDNESKY				

REVISIONS			DATE COMP.
REV. NO.	NATURE OF REVISION	DATE	MADE BY
# 1	DELETED PARCELS C-1A, C-2A, C-3A C-4A, C-5A, C-6A, C-7A	3-30-60	J.D.P.
# 2	REVISED R/W LINE ON OAKWOOD	4-4-60	J.D.P.


-LEGEND-
EXISTING R/W ———————
PROPOSED R/W ———————
SLOPE EASEMENT & WORK AGREEMENT LIMITS — — — —

SILLIMAN STREET

R/W OAKWOOD AVE. & SILLIMAN ST.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH.-18-17.20	

483
492



RIGHT-OF-WAY MARSHALL STREET

PARCEL No.	LOT No.	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK SLOPE	AGREEMENT DRIVEWAY	OTHER	
C-20A	9487	THE ISALY DAIRY CO.	34.4 SQ. FT.	YES	YES		
C-20WA		" " " "		YES			

REVISIONS


REV. NO.	NATURE OF REVISION	DATE	DATE COMP. MADE BY
#1	DELETED PARCEL C-21-WA		


-LEGEND-
EXISTING R/W
PROPOSED R/W
SLOPE EASEMENT & WORK AGREEMENT LIMITS

R/W MARSHALL ST.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

490
492





RIGHT-OF-WAY EDWARDS STREET

PARCEL Nº	LOT Nº	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
C-49A	3171	FLORENCE MACE	300 SQ. FT.			
C-50A	3172	MILITARY ORDER OF COOTIE, PUP TENT #5	100 SQ. FT.			
C-51A	3173	GEORGE A. GREIN	300 SQ. FT.			
C-52A	2653	ISALY DAIRY CO.	64 SQ. FT.			
C-53A	3407	ISALY DAIRY CO.	146 SQ. FT.			
C-54A	9508	BENJAMIN F. LEWIS	180 SQ. FT.			
C-55A	5721	RALPH M. McCRACKEN	150 SQ. FT.			
C-55WA	5721	" " "		YES		
C-56A	5722	LEONA LOUISE CALER	204 SQ. FT.			
C-56WA	5722	" " "		YES	YES	
C-57A	OL 379	CALVIN & MARTHA WESTON	164 SQ. FT.			
C-57WA	OL 379	" " "		YES	YES	
C-58A	30332	NAPOLEAN & DOROTHY BURT	200 SQ. FT.			
C-50BA	3172	FRANK P. SANDERS	110 SQ. FT.			
C-52BA	2653	MOFFET L.T. & B	70 SQ. FT.			
C-53BA	3407	DOLLAR SAVINGS & TRUST CO.	20 SQ. FT.			
C-54CA	9508	RALPH M. McCRACKEN	70 SQ. FT.			
C-56BA	5722	" " "	8 SQ. FT.			
C-57BA	OL 379	D.H. LEVY & S. DUNGER	164 SQ. FT.			
C57B-WA	OL 379	" " " "		YES	YES	
C56B-WA	5722	RALPH M. McCRACKEN		YES		

-LEGEND-
EXISTING R/W ————————
PROPOSED R/W ————————
SLOPE EASEMENT & WORK AGREEMENT LIMITS — — — — —

RIGHT-OF-WAY SALT SPRINGS ROAD

PARCEL Nº	LOT Nº	NAME	AREA OF TAKING HIGHWAY EASEMENT


REVISIONS


REV. NO.	NATURE OF REVISION	DATE	MADE BY	DATE COMP.
# 1	DELETED - C-55-A, C-53-B-WA, C-53-WA 221-A, C-54-BA	3-31-60	J.D.P.	

R/W EDWARDS ST.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

491
492





℄ CURVE DATA

Δ = 21°40'12"
R = 261.24'
T = 50.00'
L℄ = 98.80'

-LEGEND-

EXISTING R/W ————————
PROPOSED R/W ————————
SLOPE EASEMENT & WORK AGREEMENT LIMITS — — — — —

RIGHT-OF-WAY HIGH STREET


PARCEL NO	LOT NO	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	WORK AGREEMENT DRIVEWAY	WORK AGREEMENT OTHER
C-22WA	3921	T. SAADI			YES	
C-23WA	3920	T. SAADI			YES	
C-24A	2363	EXIE SCRUGGS	500 SQ. FT.			
C-25A	2357	EMMA JANE MCCORKLE	500 SQ. FT.			
C-26WA	2327	CLIFTON DOUGLAS-LUCY ANN PARKER			YES	
C-27WA	2326	RUBY B. CHEIRS			YES	
C-28WA	1929	HATTIE BRADLEY			YES	
C-29A	2355	J.B. & H. COLLIER	250 SQ. FT.			
C-30A	2356	LAWRENCE & BEATRICE SMITH	250 SQ. FT.			
C-31A	876	TOFFIC SAADI	415 SQ. FT.			
C-33A	5662	WALTER & WILLO LEE FLIPPING	143 SQ. FT.			
C-33WA	5662	" " " "		YES		RETAIN. WALL
C-34A	5663	IDA BELLE PEARSON	188 SQ. FT.			
C-34WA	5663	" " "		YES	YES	
C-35A	5664	MARY CANNELL	200 SQ. FT.			
C-35WA	5664	" "		YES		CONC. STEPS
C-36A	5724	ANNA CENTRIC	300 SQ. FT.			
C-37A	5725	ALVIN & JOSEPHINE CLARK	300 SQ. FT.			
C-38A	55074	ANDERSON & OLA MAE JOHNSON	415 SQ. FT.			
C-39A	55077	MATTIE HART	57 SQ. FT.			
C-39WA	55077	" "		YES		
C-40A	848	CLARA WASHINGTON	437 SQ. FT.			
C-40WA	848	" "		YES		
C-41A	5650	UNION NATIONAL BANK TRUST	256 SQ. FT.			
C-42WA	1578	DOZIER RENAH-JAMES JACKSON		YES		
C-43WA	5668	EMIL E. RESTLE		YES		
C-44A	57454	LINDSAY CARRIE	71 SQ. FT.			
C-44WA	57454	" "		YES	YES	
C-45WA	57455	" " "		YES		
C-35B	5665		200 SQ. FT.			


REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
# 1	REVISED AREA OF TAKING PC'LS. C-24-A C-25-A, C-34-A, C-41-A, C-44-A		

R/W HIGH ST.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	


492/492





RIGHT OF WAY WOODLAND AVE. WEST

BUILDINGS	PARCEL NO.	LOT NO.	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
	C-46A	2316	NATIONAL CITY BANK OF CLEVE., TR.	1370 SQ. FT.			
	C-46WA	2316	" " " " "		YES	YES	WALL
	C-47A	2000	FIRESTONE TIRE & RUBBER, AKRON, OHIO	450 SQ. FT.			
	348A	2308	JOHN PAUL	450 SQ. FT.			
	348WA	2308	" "		YES	YES	
PORCH	350A	2300	JOHN & ANN BUDAKER	744 SQ. FT.			
	350-WA	2305	"			YES	
	C-47WA	2000	FIRESTONE TIRE & RUBBER, AKRON, OHIO		YES		




RIGHT OF WAY WOODLAND AVE. EAST

PARCEL NO.	LOT NO.	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
C-60A	3371	THEO. R. CLAPP	372 SQ. FT.			
C-60WA	3371	" " "		YES		
C-61A	10101	FRED SHUTRUMP	268 SQ. FT.			
C-61WA	10101	" "		YES		
C-62A	1692	BEATRICE B. LOPEZ	630 SQ. FT.			
C-62WA	1692	" " "		YES		
C-63A	1691	NATHAM DARSKY	662 SQ. FT.			GARAGE
C-63WA	1691	" "		YES		
C-64A	1690	FRED WALLACE HUGHES	662 SQ. FT.			
C-64WA	1690	" " "		YES		
C-65A	1689	GEORGE & K. KONIESCKY	662 SQ. FT.			
C-65WA	1689	" " " "		YES	YES	

REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
# 1	ADDED 350-WA; ADDED W/A FOR DRIVES FOR C-348-WA, C-65-WA. DELETED C-66-A	3-31-60	J.D.P.

-LEGEND-
EXISTING R/W ———
PROPOSED R/W ———
SLOPE EASEMENT & WORK AGREEMENT LIMITS — — — —

R/W WOODLAND AVE. WEST & EAST



R/W SHEET 1 OF 26 18-MAH-17.20

FED. RD.	STATE	PROJECT	
2	OHIO		

MAH-18-17.20

467
492

LOCATION PLAT

MAH 18-17.20 & MAH 7-14.80

MAHONING COUNTY

CITY OF YOUNGSTOWN

SCALE: 1"= 500'

CURVE DATA No. 1

P. I. Sta.
Δ = 43° 47' 40" Lt. Y = 25.53'
Dc = 5° 30' 00" L.T. = 267.18'
Ls = 400.00' S.T. = 133.80'
Rc = 1041.74' L.C. = 399.34'
θs = 11° 00' 00" Ts = 621.04'
P = 6.39' Es = 87.89'
K = 199.76' Lc = 396.26'
X = 398.53' Δc = 21° 47' 40"

CURVE DATA No. 2

P. I. Sta.
Δ = 54° 44' 10" Rt. Y = 25.53'
Dc = 5° 30' 00" L.T. = 267.18'
Ls = 400.00' S.T. = 133.80'
Rc = 1041.74' L.C. = 399.34'
θs = 11° 00' 00" Ts = 742.31'
P = 6.39' Es = 138.49'
K = 199.76' Lc = 595.20'
X = 398.53' Δc = 32° 44' 10"

CURVE DATA No. 3

P. I. Sta.
Δ = 60° 43' 03" Lt. Y = 25.53'
Dc = 5° 30' 00" L.T. = 267.18'
Ls = 400.00' S.T. = 133.80'
Rc = 1041.74' L.C. = 399.34'
θs = 11° 00' 00" Ts = 813.68'
P = 6.39' Es = 172.95'
K = 199.76' Lc = 703.95'
X = 398.53' Δc = 38° 43' 03"

CURVE DATA No. 4


P. I. Sta.
Δ = 74° 52' 50" Rt. Y = 7.20'
Dc = 2° 45' 00" L.T. = 200.06'
Ls = 300.00' S.T. = 100.05'
Rc = 2083.48' L.C. = 299.93'
θs = 4° 07' 30" Ts = 1746.61'
P = 1.80' Es = 542.86'
K = 149.97' Lc = 2422.93'
X = 299.84' Δc = 66° 37' 50"

CURVE DATA No. 5

P. I. Sta.
Δ = 53° 49' 25" Lt. Y = 26.68'
Dc = 5° 45' 00" L.T. = 267.23'
Ls = 400.00' S.T. = 133.85'
Rc = 996.45' L.C. = 399.28'
θs = 11° 30' 00" Ts = 708.91'
P = 6.68' Es = 128.51'
K = 199.73' Lc = 536.06'
X = 398.39' Δc = 30° 49' 25"

CURVE DATA No. 6

P. I. Sta.
Δ = 68° 53' 50" Rt. Y = 34.74'
Dc = 7° 30' 00" L.T. = 267.63'
Ls = 400.00' S.T. = 134.21'
Rc = 763.94' L.C. = 398.78'
θs = 15° 00' 00" Ts = 729.54'
P = 8.70' Es = 173.01'
K = 199.54' Lc = 518.63'
X = 397.27' Δ = 38° 53' 50"



LIMITED ACCESS HIGHWAY

I HEREBY CERTIFY THIS PLAT TO BE CORRECT

SIGNED BY Robert J. Schomer

Robert J. Schomer Reg. No. 713

RECEIVED FOR RECORD May 29 1959

RECORDED, VOL. 44 PAGE 45&46 OF THE MAHONING COUNTY RECORDS

AT 2:10 PM

William D. Hoff
RECORDER

CERTIFICATE OF APPROVAL

SIGNED BY James C. Ryan
CITY ENGINEER


SIGNED BY Paul Rappaport
DIVISION ENGINEER


MONUMENTS WILL BE SET ON CENTERLINE AT FOLLOWING STATIONS


STATION	DESCRIPTION	OFFSET
908+16.00	P.O.T.	
918+03.16	T.S.	
922+03.16	S.C.	
925+99.42	C.S.	5'Rt.
929+99.42	S.T.	5'Rt.
937+46.56	T.S.	5'Rt.
941+46.56	S.C.	5'Rt.
947+41.76	C.S.	5'Rt.
951+41.76	S.T.	5'Rt.
954+73.06	T.S.	5'Rt.
958+73.06	S.C.	5'Rt.
965+77.01	C.S.	
969+77.01	S.T.	5'Rt.
975+00	P.O.T.	
980+00	P.O.T.	
986+75.49	T.S.	5'Rt.
989+75.49	S.C.	5'Rt.

STATION	DESCRIPTION	OFFSET
994+00	P.O.C.	5'Rt.
999+00	P.O.C.	5'Rt.
1005+50	P.O.C.	
1013+98.42	C.S.	5'Rt.
1016+98.42	S.T.	5'Rt.
1018+50	P.O.T.	
1021+55.38	T.S.	5'Rt.
1025+55.38	S.C.	5'Rt.
1030+91.44	C.S.	5'Rt.
1034+91.44 } (Equation) 806+88.34	S.T.	5'Rt.
800+79.03	C.S.	5'Lt.
795+60.40	S.C.	5'Lt.
791+60.40	T.S.	5'Lt.
781+44.00	P.O.T.	

STATION	DESC.	OFFSET
962+00	P.O.C.	5'Rt.
978+50	P.O.T.	5'Rt.
1005+00	P.O.C.	5'Rt.
1010+00	P.O.C.	5'Rt.
804+79.03	S.T.	5'Lt.
784+00	P.O.T.	5'Lt.







NOTE: THIS CENTERLINE PLAT VOIDS AND SUPERSEDES PREVIOUS RECORDING OF CENTERLINE PLAT IN PLAT BOOK VOL. 44, PAGES 45 & 46 ON JUNE 1, 1959 - PER MONUMENT ASSEMBLY RELOCATIONS (℄ R/W I-680)

APPROVED _____ 19____

DEPUTY DIRECTOR OF PUBLIC WORKS

APPROVED _____ 19____

DIVISION DEPUTY DIRECTOR

RECEIVED _____ 19____

RE-RECORDED _____ 19____

BOOK _____, PAGE _____

COUNTY RECORDER

R238

$118.00

FED. RD.	STATE	PROJECT	
2	OHIO	MAH.-18-17.20	

468
492

SUMMARY OF R/W REQUIRED

CITY OF YOUNGSTOWN

PROJECT MAH-18-17.20

PARCEL NO.	OWNER	EXIST. BLDGS.	LOT NUMBER	AREA SQ.FT.	SHEET NO.	REMARKS
1-LA	Luigi Fulciniti	NO	17998	5,778	6	
2-LA	Peter & Helen Mikita	Yes	17999	5,000	6	
3-LA	William Pupa	Yes	18000	4,090	6	
3-WA	William Pupa	—	18000	—	6	Fill Basement
4-LA	Steve Dolak, Mary Dolak	Yes	18001	2,120	6	Take Shed
4-A-LA	Elizabeth Pedak	NO	18002	261	6	
6-LA	Mollie Barta	Yes	18011	5,625	6	
7-LA	Franciska Ondash	Yes	18012	5,000	6	
8-LA	Mathew A. Stankish, Mary Lou Stankish	Yes	18013	5,000	6	
9-LA	John Iwaniuk, Wasylyna Iwaniuk	Yes	18014	6,250	6	
10-LA	Frank Deak, Elizabeth Deak	Yes	18015	4,770	6	
11-LA	Mary Garcar	Yes	18016	2,850	6	
12-LA	John Krupa, Mary Krupa	NO	18017	136	6	
13-LA	Albert Fuzy, William A. Ambrose Mrs. Julia Karaka, Paul Fuzy	Yes	18024, 18025	6,728	6	
13-WA	Albert Fuzy, William A. Ambrose Mrs. Julia Karaka, Paul Fuzy	Yes	18025	—	6	Remove Garage Foundation
15-LA	Anne Chabala Leson	Yes	18026	5,000	6	
16-LA	Anne Shuster	Yes	18027	7,500	6	
18-LA	Mike Seman, Mary Seman	Yes	30896	3,750	6	
19-LA	Peter Kantor Jr., Ethel Moszaros	Yes	18029	6,250	6	
20-LA	Helen Kravec	Yes	18030	5,000	6	
26-LA	Andrew Anthol, Ann Cizmar Paul Anthol, Helen Yash	Yes	18031, 18032	3,820	6	
26-WA	Andrew Anthol, Ann Cizmar Paul Anthol, Helen Yash	Yes	18032	—	6	Remove Shed
22-LA	Mitro Mica, Annie Mica	NO	18043, 18044	4,950	6	
24-LA	James K. Walters	Yes	18046, 18047	11,849	6	
25-LA	Helen M. Bugno	Yes	18048	7,406	6	
28-LA	Anna Gonda	Yes	18037	5,000	6	
29-LA	Mary L. Adams	Yes	18038	5,000	6	
30-LA	Paul Bednarik	Yes	18039	4,100	6	
30-WA	Paul Bednarik	Yes	18039	—	6	Remove Garage Foundation
31-LA	Veronica Bundash	Yes	18040	2,050	6	
31A-LA	Michael Behun, Mary Behun	Yes	18040	403	6	
31-WA	Michael Behun, Mary Behun	Yes	18040	—	6	Fill Basement.
33-LA	Mickey Hanuschak, Flora J. Hanuschak	Yes	18142	3,400	6	
34-LA	John F. Tobin, Katherine Tobin	Yes	18142	1,438	6	
34-WA	John F. & Katherine Tobin	Yes	18142	—	6	Fill Basement
35-LA	Steve Matyl, Annie Matyl	Yes	18143	5,000	6	
36-LA	Sue K. Furden, Julia Kuni	Yes	18144	5,000	6	
37-LA	Joe Valush	Yes	18145	4,000	6	
38-LA	Anna Gaydos	Yes	18146	4,000	6	
39-LA	Andrew & Susie Lengyel	Yes	30200	4,125	6	
40-LA	Anna, John S., Joseph Yuhasz	Yes	18147	3,680	6	
41-LA	The Portland Land Co.	NO	43196, 18148	6,432	6	
43-LA	Annie Nelson	NO	18149	1,420	6	
46-LA	George Zahdrery, Elizabeth Zahdrery	Yes	33954	5,490	6	
46-WA	George Zahdrery, Elizabeth Zahdrery	Yes	33954	—	6	Fill Basement
47-LA	Anna Pavlik	No	33955	3,240	6	
48-LA	Mary Selenk	No	33956	689	6	
49-LA	Helen M. Cohn	NO	O.L. 421	68,111	6	
58-C-LA	Joseph S. Petrick, Maria Petrick	NO	33960	—	6	Loss of Access to Lakeview Ave.
58F-LA	Steven N. Bobovnych & Mary Bobovnych	NO	33961	3,808	6	
49A-LA	Joe Ince, Anna Ince	NO	18161	251	7	
51-LA	Betty Joe Yohman	NO	18162	1,203	7	
52-LA	Andrew Kosar, Helen Kosar	Yes	18163	2,080	7	
53-LA	Michael Nagy Jr.	Yes	28806	2,762	7	
53-A	Michael Nagy Jr.	Yes	28806	1,398	7	
54-LA	Margaret Bada	Yes	18164	3,672	7	
54-A	Margaret Bada	Yes	18164	488	7	
55-LA	Vincent F. Halko, Mary Ann Halko.	Yes	18165	5,000	7	
56-LA	Andy Lukac, Mary Lukac	Yes	18166	5,000	7	
57-LA	Alexander Barich, Mildred Barich	Yes	18167	13,720	7	
58E-LA	Mary Pauline Williams	NO	O.L. 422	20,600	7	
59-LA	Ginolamarca 1/2, Louise Lamarca	Yes	O.L. 421, 19654	6,265	7	
59A-LA	Ugo Dibacco 1/2, Anna Dibacco	Yes	19654	2,774	7	
60-LA	Paul Semai, Joan Semai	Yes	19655	5,000	7	
61-LA	Paul Gloval, Mary Gloval	Yes	19656	5,000	7	
64-SL	Andrew Tarkanich, Susie Tarkanich	NO	28810	23	7	Slope
62-LA	Dafini Negroff	Yes	18179	64	7	
62-S	Dafini Negroff	Yes	18179	256	7	
62-WA	Dafini Negroff	Yes	18179	—	7	Fill Basement
63-LA	Barbala or Barbara Burcsak	Yes	18180	705	7	
63-WA	Barbala or Barbara Burcsak	Yes	18180	—	7	Fill Basement
63-S	Barbala or Barbara Burcsak	Yes	18180	335	7	
67-LA	Mary Mazyrski	Yes	19657	5000	7	
71-LA	Andy L. & Anna C. Leskovec	NO	18188	360	7	
72-LA	Helen & Julianna Brogli	Yes	18189	980	7	
72-WA	Helen & Julianna Brogli	Yes	18189	—	7	Fill Basement
73-LA	Charles R. Kelly, Leona Code	Yes	18190	1,440	7	
73-WA	Charles R. Kelly, Leona Code	Yes	18190	—	7	Fill Basement
74-LA	Thomas A. & Bridget L. Denehy	Yes	18190, 18191	2,090	7	
75-LA	Andrew & Anna Bodnar	Yes	18191	1,950	7	
76-LA	Joseph Bankovitch	Yes	18192	3,040	7	
77-LA	John & Barbola Paul	Yes	18193	3,500	7	
79-LA	John & Anna Bobanich	Yes	19658, 19658	7,728	7	
80-LA	Anna Mozzy, Mary Bartell, Michael & Andrew Cycyk	Yes	19660	2,000	7	
80-WA	Anna Mozzy, Mary Bartell Michael & Andrew Cycyk	Yes	19660	—	7	Fill Basement
81-LA	John R., Charles E., Joseph T. Mary Ann, Catherine T. & Jennie S. March	Yes	19661	960	7	
81-WA	John, Charles, Joseph, Mary Ann, Catherine & Jennie March	Yes	19661	—	7	Fill Basement
83-LA	John Stun	Yes	38034	3,180	7	
84-LA	Aster Sklepko	Yes	19639	3,750	7	
85-LA	John & Anni Dzuroff	Yes	19640	5,000	7	
86-LA	Michael Sabol Jr., Martin Sabol, Mary Kavanaugh	Yes	19641	5,000	7	
87-LA	Mary Barolak, Roman, Edward, Emil, Joseph T. Barolak.	Yes	19642	5,000	7	
88-LA	Theresa Tobis or Therisa Tobis	Yes	19643	5,000	7	
89-LA	John J. & Agnes Bacak	Yes	19644	5,000	7	
90-LA	Joseph, Joseph E., Bernard, & George C. Knapic, Frances K. Acri.	Yes	19645	5,000	7	
91-LA	Wallace & Hilda Marie Dorko	Yes	19646	5,000	7	
92-LA	Martin & Anna Harchar	Yes	19647	5,000	7	
93-LA	Mary D. Olsavsky	Yes	19648	5,000	7	
94-LA	Karol & Anna Butek	Yes	19649	5,000	7	
95-LA	Mari or Mary Majorsky	Yes	19650	5,000	7	
96-LA	Veronica Missik	Yes	19652	5,000	7	
97-LA	John & Elizabeth Kiss	Yes	19653	5,000	7	
98-LA	George Bodnar Jr., Helen Bodnar	Yes	18284, 18285	10,680	7	
100-LA	Mary Adams	Yes	18286	5,000	7	
101-LA	John M. & Agnes Sudzina	Yes	18287	5,250	7	
102-LA	Bridget L. Ruane	Yes	18288	5,250	7	
103-LA	John & Barta Fetzer	Yes	18289	5,250	7	
104-LA	Zvonimir Roy & Rose M. Vulyak	Yes	18290	5,250	7	
105-LA	Anna Kachmar or Kachmer	Yes	18291	5,250	7	
106-LA	Michael & Elizabeth Yacko	Yes	18292	5,250	7	
107-LA	Peter & Mary Leman	Yes	18293	5,000	7	
108-LA	Valent Ledinko	Yes	18294	5,000	7	
109-LA	Gabor & Susie Toth	Yes	18295	5,000	7	
110-LA	Mathew & Anna G. Hamborsky	Yes	18296	5,000	7	
111-LA	Frank Barolak	Yes	18297	5,000	7	
112-LA	Joseph Andrews	Yes	18298	10,612	7	
113-LA	Michael Luzan	Yes	6783	6,142	8	
113-SA	Michael Luzan	Yes	6783	3,088	8	
114-LA	Julia Kun	Yes	6787	3,300	8	
114-SA	Julia Kun	Yes	6787	1,810	8	
115-LA	Mike & Mary Potocnak	Yes	6786	3,220	8	
115-SA	Mike & Mary Potocnak	Yes	6786	1,980	8	
116-LA	John & Catherine Smith	Yes	6785	3,106	8	
116-SA	John & Catherine Smith	Yes	6785	2,094	8	
117-LA	Frank Ferko	Yes	6782	2,964	8	
117-SA	Frank Ferko	Yes	6782	2,236	8	
118-LA	Paul & Anna Matuscak	Yes	6781	2,800	8	
118-SA	Paul & Anna Matuscak	Yes	6781	2,400	8	
119-LA	Bertha Hohos	Yes	6780	2,680	8	
119-SA	Bertha Hohos	Yes	6780	2,520	8	
121-LA	George A. & Catherine Bozich	Yes	6779	2,660	8	
121-SA	George A. & Catherine Bozich	Yes	6779	2,600	8	
122-LA	Joe & Mary Pisansky	Yes	6778	2,700	8	
122-SA	Joe & Mary Pisansky	Yes	6778	2,500	8	
123-LA	Andrew & Mary Tamboli	Yes	6778	2,740	8	
123-LA	Andrew & Mary Tambori	Yes	6778	2,460	8	
124-LA	Frank & Helen Paliga	Yes	6777	2,660	8	
124-SA	Frank & Helen Paliga	Yes	6777	2,540	8	
125-LA	Katarina Giba	Yes	11782	3,209	8	
125-SA	Katarina Giba	Yes	11782	5,880	8	
127-LA	Paul & Irene Koval	Yes	42446	8,840	8	
128-LA	Susanna Kramer	Yes	42447	5,200	8	
129-LA	George Lutza Jr.	Yes	42448	5,200	8	
130-LA	Mathew & Anna Koval	Yes	42449	1,540	8	
130-SA	Mathew & Anna Koval	Yes	42449	720	8	
130-WA	Mathew & Anna Koval	Yes	42449	—	8	Fill Basement
131-LA	Stevan & Anna Hoffman	Yes	42450	3,180	8	
131-SA	Stevan & Anna Hoffman	Yes	42450	6,204	8	
131-WA	Stevan & Anna Hoffman	Yes	42450	—	8	Fill Basement
133-LA	St. Michaels Russ. Orth. Gr. Cath. Church	Yes	O.L. 145	48,376	8	
133	St. Michaels Russ. Orth. Gr. Cath. Church	Yes	O.L. 145	750	8	
133-WA	St. Michaels Russ. Orth. Gr. Cath. Church	Yes	O.L. 145	—	8	Remove Foundation
134-LA	Mahoning Valley Sanitary District	No	O.L. 415, 416, 420	50,220	8	
135-LA	John Sahlica	No	O.L. 415	12,982	8	
136-LA	Serbian Eastern Orth. Congregation	No	O.L. 416	130,633	8	
136-S	Serbian Eastern Orth. Congregation			715	8	
140-LA	Berkeley, Bertha, Irving & Bernice Fromkin	Yes	O.L. 420	307,525	8	
140-SA	Berkeley, Bertha, Irving & Bernice Fromkin	No	O.L. 420	9,080	8	
143-LA	Geisi & Christina Passarella	No	O.L. 419	362,655	9	
144-LA	Baltimore & Ohio R.R.	No	—		9	
144-S	Baltimore & Ohio R.R.	No	—		9	
145-LA	Angelo, Mark, John, & Joseph Passarelli	No	O.L. 419	39,920	9	
146-LA	Gohgie Realty Co.	Yes	O.L. 428	42,742	9	146-19,400± Eligible for Federal Part.
146A-LA	Baltimore & Ohio R.R.	No	—		9	
147-LA	Joe Maskulka, Gemma Badino	Yes	O.L. 428	30,050	9	
148-LA	Sam Margolis	Yes	O.L. 428	71,000	9	148-9000± Eligible for Federal Part.
149-LA	John & Andrew Fusco	Yes	O.L. 495	43,560	10	
150-LA	Joseph & Robert Jenkins	Yes	O.L. 410	50,701	10	
150-WA	Joseph & Robert Jenkins	Yes	O.L. 410	—	10	Fill Basement
150A-LA	Paul Pagac	No	O.L. 410	4,290	10	
150B-LA	Ella Louise Wick	No	O.L. 410	333	10	
151-LA	Theodore Saroka, Gino Parisi	Yes	O.L. 496	12,550	10	
154-LA	Margaret B. Sittinger	Yes	12145	2,350	10	
155-LA	The Youngstown Dunbrik Co.	Yes	O.L. 497	55,321	10	
154-A	John R. McGee	No	O.L. 447	377.5	10	
159-LA	Vince Minor	No	12150	8,118	10	
160-LA	Bernard Bruss	Yes	12152	4,590	10	
161-LA	Leo & Bernard Bruss	Yes	O.L. 408	33,350	10	
161-SA	Leo & Bernard Bruss	Yes	O.L. 408	65,080	10	

Fill Basement

Pcl. 64-SL	Added	10-6-61
Pcl. 49-LA	Name Change	10-5-60
Parcel 133-S	To 133	7-6-60
Parcel 125-LA	Area Revised	7-6-60
Parcel 151-LA	Area Revised	7-6-60
Parcel 149-LA	Area Revised	7-6-60
Parcel 125-S	Revised	6-30-60
Parcel 149-LA	Revised	6-27-60
Parcel 154-A	Revised	6-23-60
Parcel 185-LA	Area Revised	5-10-60
158-LA	Deleted	4-21-60
Sheet Reference No. 3	Revised	4-20-60
Added Fed. Part. Pcls. 146LA & 148LA.		5-7-60

FED. RD.	STATE	PROJECT	
2	OHIO	MAH. 18-17.20	

469 492

SUMMARY OF R/W REQUIRED

CITY OF YOUNGSTOWN
PROJECT MAH.-18-17.20

PARCEL NO.	OWNER	EXIST. BLDG.	LOT NO.	AREA S.F.	SHEET NO.	REMARKS
170-LA	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.483-489	113,590	11	CONSTRUCTION OF PARK ROAD
170-T	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.484	134,950	11	
170-AERIAL	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.480	55,167	11	
170	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.484	1,578	11	
170-B	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.480	1,578	11	
170-C	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.480	1,578	11	
170-D	BOARD OF PARK COMMISSION YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L.480	1,578	11	
171-LA	CALIXTE JOSEPH GAUDET, EDNA MAY GAUDET	YES	6826,6827	15,960	11	
173-LA	WILLIAM W. NEFF, ARMIDA NEFF	YES	6828	7,625	12	
174-LA	HAROLD AND ETHEL GASKINS	YES	6829	7,625	12	
175-LA	JOHN J. CIKA, DOROTHY A. CIKA	YES	14285	2,290	12	
176-LA	JAMES A. POTTER, PAULINE POTTER	YES	14285	2,290	12	
177-LA	ISALY DAIRY COMPANY	YES	6831	10,215	12	
178-LA	THE DOLLAR SAVINGS & TRUST COMPANY TRUSTEE	YES	2475	7,634	12	
179-LA	JOHN WILLIAMS, LOU GENIA WILLIAMS	YES	2476	6,940	12	
180-LA	DOUGLAS JONES, CHESTINA JONES	YES	2477	6,940	12	
181-LA	BESSIE AGRENOVITZ	YES	2478	6,940	12	
182-LA	JESSIE DOUGLAS, CHRISTINE DOUGLAS	YES	2360,2479	5,028	12	
183-LA	MARY G. REITZELL, FLORA A. REITZELL	YES	2480,2360	6,940	12	
184-LA	BENJAMIN VERNON, CLARA VERNON	YES	2481	3,960	12	
185-LA	GILSON T. GRAHAM	YES	2479	3,300	12	
186-LA	ANNIE K. HARPER ROBINSON, ALIAS ANNIE SIMMONS	YES	2481	1,560	12	
187-LA	S & G REALTY COMPANY	YES	6837	7,640	11	
188-LA	EULALIAM M. LUTHER	YES	6836	5,900	12	
189-LA	ROSINA SCHNEIDER	YES	6835	6,000	12	
190-LA	JAMES ARTHUR ROSS, ANNIE B. ROSS	YES	6834	6,250	12	
191-LA	ETHEL GILFILLAN	YES	6830	3,300	12	
192-LA	D.N. GARVER, MARTHA E. GARVER	YES	14285	7,695	12	
193-LA	CLYDE E. TRUITT, DOROTHY C. TRUITT	YES	6833	3,630	12	
194-LA	TUFIC SAADI	YES	6832	5,066	12	
195-LA	CHARLOTTE BYERS	YES	6832	5,066	12	
196-LA	MARTIN BOKESCH, CHRISTINA BOKESCH	YES	2488	3,924	12	
197-LA	IRENE H. VANMETER	YES	2488	3,252	12	
198-LA	JOSEPH STOKAN	YES	2487	~~6,940~~	12	
200-LA	KATHLEEN WATKINS	YES	2485	6,940	12	
201-LA	KATHERINE B. WILSON	YES	2484	6,940	12	
202-LA	JAMES ANDERSON	YES	2482,2483	4,500	12	
203-LA-204-LA	FLORENCE APPEL DORFF, HELEN APPEL LEWIS, CLARA APPEL CASSESE	YES	2482,2483	9,300	12	
205-LA	CLARENCE C. MCKELRY, ELIZABETH MCKELRY	YES	3411	9,000	12	
206-LA	THOMAS A. MUMFORD	YES	3412	7,500	12	
207-LA	LILLIAN B. JONES RAFE	YES	3413	6,000	12	
208-LA	JESUS HERNANDEZ, MARY E. HERNANDEZ	YES	O.L.374	3,108	12	
209-LA	LEONARD HALLEWELL, ESTELLA HALLEWELL	YES	O.L.374	3,009	12	
209-A-LA	JAMES BROWN	YES	O.L.374	2,549	12	
210-LA	FREDERICK LEROY TAYLOR, GRACE VERA TAYLOR	YES	O.L.374	6,425	12	
211-LA	JOSEPH ANDROSEK, WALSH AND ROBERTS INC.	YES	O.L.374	3,606	12	
211-A-LA	FREDA C. ANDERSON	YES	O.L.374	2,903	12	
211-B-LA	JAMES DOMINIC PRECURATO, MARY DELORES PRECURATO	YES	3659	4,902	12	
212-LA	T. SAADI	YES	3679	4,500	12	
213-LA	HOWARD JAMES, WILLIE MAY JAMES	YES	3409	2,910	12	
214-LA	ARTHUR I. WALDMAN	YES	3409	7,275	12	
215-LA	JAMES MONROE LONG	YES	3410	~~4,940~~	12	
216-LA	ROY F. MORT	YES	3414	9,675	12	
217-LA	WILLIAM J. AND MARY G. PETRANSKY	YES	3408	3,300	13	
217-A-LA	JOSEPH AND LOUISE C. PETRANSKY	YES	3408	1,700	13	
218-LA	FLORENCE POTOR	YES	5677	5,000	13	
219-LA	JOSEPH GIERCHAK, ANGELINE GIERCHAK	YES	5678	5,000	13	
220-LA	BESSIE AND HARRY WILLIAMS	YES	9507	6,000	13	
221-LA	GUS COHEN, RUTH D. COHEN	YES	9507	7,163	13	
222-LA	THOMAS J. MYERS	YES	3964	7,500	13	
223-LA	WM. F. AND HELEN MOSKOSKY	YES	3966	7,500	13	
224-LA	OTTO C. BROOKS	YES	3968	5,000	13	
225-LA	ARTHUR AND LESSIE MARTIN	YES	3968	8,920	13	
226-LA	WILLIAM AND SUSIE M. KIDD	YES	3970,10108	12,291	13	
227-LA	WILLIAM DUDLEY	YES	10371	11,449	13	
228-LA	MATTIE MCPETERS	YES	10370	11,734	13	
229-LA	WILLIAM VONKENNEN JR.	YES	3972,10369	11,000	13	
230-LA	MIKE AND BERTHA GLAVIES	YES	3973	7,500	13	
231-LA	MARY ELIZ. MCKLUSKY	YES	3974	6,825	13	
232-LA	MARGARET M. MAIN, MARGARET L. TRIGG	YES	3974,3975	8,325	13	
233-LA	HILDEGARD HUEBERGER COURT	YES	10369	9,672	13	
233-A-LA	GEORGE F. MAIN	NO	19766	25,160	13	
234-A	CAROLINE THRASH	YES	O.L.382	3,395	13	
170-A-LA	BOARD OF PARK COMMISSIONERS OF YOUNGSTOWN TWP. PARK DISTRICT	NO	O.L. 489	7,735	11	
170-B-LA	UNION NATIONAL BANK OF YOUNGSTOWN ET-AL	YES	5747	3,210	10	
199-LA	JOSEPH STOKAN	YES	2486	6940	12	
236-LA	JACKSON STEWART, ANNE STEWART	NO	11226	110	13	
237-LA	WILLIAM H. WILLIAMS, EVELYN L. WILLIAMS	YES	11227	5,313	13	
238-LA	OTTO GEISHLER, EMMA GEISHLER	YES	19708	6,000	13	
239-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	NO	2366	6,206	13	
240-LA	JULIA KICZ	YES	2365	5,029	13	
241-LA	DAVID SCOTT	YES	2364,872	5,776	13	
241-A-LA	CLARENCE DANIEL	NO	57185	1,608	13	
242-LA	CLARENCE DANIEL	YES	874	~~2,144~~	13	
242-A-LA	RUTH FRANKLIN	YES	873	6,420	13	
242-B-LA	MARGARET BIELER	NO	874	697	13	
243-A-LA	Alex JONES	YES	55603	5,242	13	
244-LA	BOSS JACKSON, OLLIE JACKSON	YES	11349	2,360	13	
245-LA	ZORA PRISBY	YES	11348	4,800	13	
245-A-LA	MARGARET M. MAIN, MARGARET L. TRIGG	NO	19771-2-3, 19770	12,978	13	
246-LA	MAMIE L. CODY	NO	4821	4,000	13	
249-LA	MILTON A ROEMISCH (TRUSTEE)	NO	4822,39292	8,565	13	
250-LA	MARY K. KING ET-AL	YES	39293	5,000	13	
251-LA	Y.Z. ADAMS, THELMA ADAMS	YES	39294	5,000	13	
251-A-LA	ELIGHA KING, ANITA KING	YES	39296	4,369	13	
252-LA	CARL H. HOLQUIST, MARY E. HOLQUIST	YES	2361	5,000	13	
252-A-LA	OZZIE CURRY	YES	2359	675	13	
252-WA	CARL H. HOLQUIST, MARY E. HOLQUIST	YES	2361		13	REMOVE GARAGE FOUNDATION
252-A-WA	OZZIE CURRY	YES	2359		13	REMOVE GARAGE FOUNDATION
253-LA	ELLA RODGERS	YES	2362	960	13	
253-A-LA	W.J. WADKINS, MAUDE S. WADKINS	YES	11222	5,450	13	
253-B-LA	ALEXANDER WILLIAMS, EDITH WILLIAMS	YES	11221	4,653	13	
253-C-LA	SAM D. CLARK, KATIE CLARK	YES	9436	1,299	13	
253-D-LA	JULIUS DICKENS, BERTHA DICKENS	YES	4754	3,690	13	
253-D-A	JULIUS DICKENS, BERTHA DICKENS					
253-F-LA	LOUIS E. CAPPELLO	YES	9436	1,148	13	
253-G-LA	LUCY BEVERLY	YES	9435	1,800	13	
253-H-LA	THE CENTRAL DISTRICT OF THE LUTH. CHURCH MO. SYNOD INC.	YES	30330	1,936	13	
253-I-LA	WALTER NORTH, LYDIA NORTH	NO	9437	510	13	
253-K-LA	RAYMOND WALLACE, LOUISE WALLACE	YES	55605	1,457	13	
253-L-LA	COURTLAND ALLEN, ROSE ALLEN	YES	9435	1,140	13	
253-M-LA	DR. NELSON INGRAM, THELMA INGRAM	YES	4755	3,780	13	
253-M-A	DR. NELSON INGRAM, THELMA INGRAM				13	
253-P-A	ROBERT H. AND EDNA KING				13	
253-A-A	W.J. WADKINS, MAUDE S. WADKINS	YES	11222		13	
253-B-A	ALEXANDER WILLIAMS, EDITH WILLIAMS	NO	11221		13	
253-H-A	THE CENTRAL DISTRICT OF THE LUTH. CHURCH MO. SYNOD INC.	YES	30330		13	
253-J-A	WALTER NORTH, LYDIA NORTH	YES	9437	5,440	13	
253-L-A	COURTLAND ALLEN, ROSE ALLEN	YES	9435		13	
253-WA	ELLA RODGERS	YES	2362		13	FILL BASEMENT
253-A-LA	BESSIE THOMAS	YES	55604	1,631	13	
255-LA	CLARENCE FRANKLIN	YES	3915	5,200	13	
256-LA	WILLIAM B. ROSS, MARY I. ROSS	YES	3918	4,600	13	
258-LA	FLORENCE LULA TAYLOR	NO	15906,15907	6,700	13	
259-LA	BESSIE E. MOORE	YES	15908	3,600	13	
260-LA	JOHN HAYMAN	YES	3919	3,600	13	
261-LA	CHARLES POLISKY ET AL	YES	3919	4,000	13	
262-LA	BESSIE WALKER	YES	877	15,000	13	
262-A-LA	UNION NATIONAL BANK OF YOUNGSTOWN	NO	39295	400	13	
262-C-LA	ALLEN J. STUMP, VIOLA V. STUMP	YES	877	5,427	14	
262-D-LA	LOUIS H. MAUSER	YES	5666	5,720	14	
262-E-LA	EDWARD VELAR	YES	2351	6,000	14	
262-F-LA	TUFIC SAADI	YES	876	6,889	14	
262-H-LA	LAURA GARDNER	YES	2352	3,580	14	
262-I-LA	GEORGE SUBER, PEARL SUBER	NO	2353	306	14	
262-C-WA	ALLEN J. STUMP, VIOLA V. STUMP	YES	877		14	REMOVE GARAGE FOUNDATION
262-F-WA	TUFIC SAADI	NO	876		14	FILL BASEMENT
262-H-WA	LAURA GARDNER	YES	2352		14	REMOVE GARAGE FOUNDATION
263-LA	UMBERTO TURSINI	YES	56002	2,530	14	
264-LA	WILLIAM MOSKOSKY, HELEN MOSKOSKY	NO	O.L.122	48,620	14	
265-LA	ALTON L. KEMP, ALICE L. KEMP	YES	56003	11,109	14	
265-A-LA	MARY LUNDY	YES	56004	7,511	14	
265-B-LA	FRANK J. COLLA	YES	56005	7,508	14	
266-LA	JAMES LADIGO	YES	56006	7,462	14	
266-B-LA	JOSEPH M. ALLISON, MARIAN A. ALLISON	YES	56007	7,459	14	
266-C-LA	THOMAS HOOD	YES	56008		14	
267-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	YES	O.L.125	68,502	14	
267-A-LA	ESTER MEYER	NO	55066	1,262	14	
267-B-LA	VANCE WAGNER	YES	5661	1,826	14	
267-C-LA		NO	55067	690	14	
267-D-LA	MINNIE MAUSER	YES	876	1,000	14	
267-E-LA		YES	55072	3,855	14	
267-D-WA	MINNIE MAUSER	YES	876		14	
268-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	NO	55070	5,202	14	FILL BASEMENT
268-A-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	NO	55069	278	14	
269-LA	INEZ PARKER	YES	10969	4,200	14	
271-LA	HARRY AND NELLIE MEYERS	YES	36391	2,400	14	
271-A-LA	GOLDEN AGE BEVERAGE CORPORATION	NO	36392	1,050	14	
271-B-LA		YES	55078		14	
271-WA	HARRY AND NELLIE MEYERS	NO	36391		14	
272-LA	MALACHI STOKES, THELMA STOKES	YES	10966	3,702	14	FILL BASEMENT
273-LA	JOHN G. SPATHOLT	YES	10965	1,800	14	
273-A-LA	JOHN G. SPATHOLT	YES	10966	2,080	14	
273-B-LA	JOHN G. SPATHOLT	YES	10966	1,870	14	
276-A-LA	FRED AND ROISE PERKINS ET-AL			767		
243-LA	CLARENCE DANIEL	YES	874	3,216	13	

Parcel 243-LA Added 12-15-60
Parcel 242-LA Revised 12-15-60
Parcel 199-LA Added 12-15-60
Parcel 198-LA Revised 12-15-60
Parcel 215-LA Revised 7-13-60
Parcels 253-1A & 253-K-LA Revised 7-13-60
Removed House Pcl. 253-J-LA Added House 253-I-A 7-8-60
Pcls. 268-LA & 268-A-LA Added Names & Area 7-6-60
Parcels 271-A-LA & 276-A-LA Names Changed & Area 7-6-60
Parcel 170-T Changed From Work Agree. To Temp. 7-6-60
Parcel 170-B-LA Revised 6-27-60
Parcel 170-B-1-LA Revised 6-27-60
Parcel 250-LA, 242-B-1-LA Revised 6-27-60
Parcels 253-LA & 253-K-LA Revised 6-15-60
Parcel 170-LA, 170-T Revised, 170-B, 170-B-1-A Added 4-21-60
Sheet Reference Nos Revised 4-20-60

I-680 R/W SHEET 4 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH.-18-17.20	

470 / 492

SUMMARY OF R/W REQUIRED

CITY OF YOUNGSTOWN
PROJECT MAH.-18-17.20

PARCEL NO.	OWNER	EXIST. BLDG.	LOT NO.	AREA S.F.	SHEET NO.	
273-C-LA	JOHN G. SPATHOLT	YES	10967	3,150	14	
274-LA	JOHN H. LOGAN, LULA LOGAN	YES	10964	2,230	14	
275-LA	LEROY SMITH, NETTIE SMITH	YES	10964	1,625	14	
275-A-LA	JOHNNIE PEARL REED	YES	10965	1,587	14	
276-LA	FRED AND ROSIE PERKINS	YES	10963	1,932	14	
277-LA	THEODORE COTTON JR. AND CARRIE COTTON	YES	10962	1,613	14	
279-LA	ANN KAUFMAN, BETTY LABEL	YES	5619	4,950	14	
280-LA	GOLDEN AGE BEVERAGE CORP.	YES	846	19,557	14	
283-B-LA	HOWARD BURKES, MILLERNEE BURKES	YES	5619	2,600	14	
283-B-WA	HOWARD BURKES, MILLERNEE BURKES	YES	5619		14	FILL BASEMENT
284-LA	EUGENE ROBINSON, JR., LAURA B. ROBINSON	YES	8141	2,200	15	
284-A-LA	LILTON MORRIS	YES	8141	891	15	
284-A-WA	EUGENE ROBINSON, LAURA ROBINSON	NO	8141		15	FILL BASEMENT
285-LA	BOOKER T. AND MARY HELEN WRIGHT	YES	843	3,900	15	
285-A-LA	EDWARD AND SUSIE MCELROY	YES	843	1,200	15	
286-LA	ANAM ABDO	YES	5646	3,555	15	
286-B-LA	MATHILDA WIEDMAN	NO	5647	1,550	15	
287-LA	GOLDEN AGE BEVERAGE CORP.	NO	5645,842	9,025	15	
287-A-LA		NO	841		15	
287-B-LA	*ROBINA POWELL*	YES	840	300	15	
287-C-LA		YES	842		15	
287-B-WA		YES	940		15	FILL BASEMENT
289-LA	BESSIE P. CONNELL, THOMAS H. CONNELL	NO	55071	3,600	14	
289-A-LA	WALDEMAR NISCHWITZ, EARL H. HARRIS	NO	10971	1,157	14	
290-LA	ETHEL MCDANIELS SPEAKS	YES	10970	2,948	14	
291-LA	ELIZABETH BUEHRLE	NO	55075	2,282	14	
292-LA	WALDEMAR NISCHWITZ, EARL H. HARRIS	YES	2249	5,939	14	
294-LA	WILLIAM AILEN, ANNIE ALLEN	YES	2248	3,943	14	
295-LA	MARY PEAY	YES	2247	4,180	14	
296-LA	ELIDA MOELLERING	YES	2246	4,350	14	
297-LA	WILLIAM E. AND PEARLE HERRING	YES	2245	4,750	15	
298-LA	CORA B. SCHEIBLE	YES	2244	5,200	15	
299-LA	LILLIE M. BUYCK	YES	2243	5,450	15	
299-A-LA	*JOHANNA SPRAGUE*	NO	850	476	15	
300-LA	MICHEAL F. AND BLOSSOM W. MEENACHAN	YES	2242	5,450	15	
300-A-LA	MILDRED D. PLANIN (PLANINA)	NO	1575	1,323	15	
301-LA	RICHARD L. AND LEO BENNETT	YES	2241	5,600	15	
302-LA	HENRY AND ARTHOLS BARNES	YES	2240	5,450	15	
303-LA	BEN H. CATLEY	NO	851	1,953	15	
304-LA	H.K. ZIEGLER	YES	2239	5,720	15	
305-LA	UNDEPENDENT INVESTMENT COMPANY	NO	852	2,320	15	
306-LA	ELLEN LEWIS	YES	2237	4,189	15	
307-LA	LAVERNE BOWENS	YES	2238	2,860	15	
308-LA	JULIA KICZ	YES	36651	1,824	15	
309-LA	MINNIE WILBURN	YES	853	3,884	15	
310-LA	THIRD BAPTIST CHURCH OF YOUNGSTOWN	YES	2237	9,360	15	
311-LA	CELIA BERNSTEIN	YES	854	11,925	15	
312-LA	WILLA MAE (RICE) AND HUGHES CAMPBELL	YES	2238	1,976	15	
313-LA	LAKE ERIE AND EASTERN RAILROAD	YES	1550	10,600	15	
313-A-LA	LAKE ERIE AND EASTERN RAILROAD	YES	1550	14,375	19	
313-A	LAKE ERIE AND EASTERN RAILROAD	YES	1550	40,511	19	
313-B- A	THE SPUR DISTRIBUTING COMPANY	YES	1549	*10,000*	19	
313-WA	LAKE ERIE AND EASTERN RAILROAD	YES			19	REMOVE CONCRETE SILO
314-LA	RUBE AND MARY F. SMITH	YES	1557	24,000	15	
315-LA	W.E. STANKIEWICZ	YES	1568	9,120	15	
315-WA	W.E. STANKIEWICZ				15	FILL BASEMENT
316-LA	HAROLD STEIN, SAM SIMON, MILTON H. SIMON	YES	1552	17,355	15	
316-A	HAROLD STEIN, SAM SIMON, MILTON H. SIMON	NO	1552	1,005	15	
318-LA	YOUNGSTOWN HOSP. ASSOC.	YES	1568	158,970	16	
318-WA	YOUNGSTOWN HOSP. ASSOC.	YES	11100,11101		16	FILL BASEMENT
319-LA	THE RENNER CO.	YES	1559,1560	32,670 or 0.75	16	
319-WA	THE RENNER CO.	YES	1559		16	REMOVE FOUNDATION
320-A-LA	ANNA M.PATTERSON	YES	11097	4,500 4/1/66	16	
321-LA	PHILIP GREIN	YES	11095,11096	9,140	16	
321-WA	PHILIP GREIN	YES	11094		16	REMOVE FOUNDATION
322-LA	JOHN BOGGANS, ET AL	YES	1561,5617	18,780	16	
323-LA	EUGENE AND ESTER RUSNAK	YES	11093,11094	2,600	16	
323-WA	EUGENE AND ESTER RUSNAK	YES	11094		16	REMOVE FOUNDATION
326-LA	RIDGE MEDICAL BLDG. CO.	YES	3211,5622	42,609	17	
326-WA	RIDGE MEDICAL BLDG. CO.	YES	3211		17	REVISE DRIVEWAY
327-LA	ELIZABETH GEORGE	YES	3335	8,956	17	
328-LA	LUCY S. MIKITA	YES	3336	6,350	17	
329-LA	LESLIE H. SABO, ELIZABETH H. SABO	YES	3337	3,409	17	
329-A-LA	M. VERA HERSCHEL	YES	3337		17	
330-LA	ANTHONY P. JULIUS	YES	3338	6,250	17	
331-LA	JOSEPH SARISKY	YES	3339	5,666	17	
332-LA	MYRTLE I. MILLER, VIRGINIA VIETS CRAMER, DOROTHY VIETS GLINES	YES	3340	6,600	17	
332-WA	MYRTLE I.MILLER,VIRGINIA VIETS CRAMER,DOROTHY VIETS GLINES	YES	3340,3341		17	FILL BASEMENT
333-A-LA	JOHN DORLOSAN, MARY DORLOSAN	YES	3327	1,250	17	
333-WA	JOHN DORLOSAN, MARY DORLOSAN	YES	3327		17	FILL BASEMENT
333-B-LA	GERALD CARROLL AND ALICE CARROLL	YES	3327		17	
334-LA	TUFIC SAADI	YES	3328	7,500	17	
335-LA	LALE GRAHOVAC	YES	3329	7,500	17	
336-LA	JOSEPH THURIK, MARY THURIK	YES	3330	7,500	17	
337-LA	THE INCORPORATED TRUSTEES OF THE GOSPEL WORKER SOC.	YES	3331,5628	7,500	17	
338-LA	MILDRED MCDONALD	YES	3332	7,000	17	
339-LA	RALPH A. KELLY, ISABELLA M. KELLY	YES	3333	7,344	17	
339-WA	RAL.H A. KELLY, ISABELLA M. KELLY	YES	3333,5176		17	REMOVE FOUNDATION
340-LA	CHARLOTTA FISLAK	YES	5176	5,436	17	
341-LA	JOHN W. TOMALKA SR., MARY HAZEL TOMALKA	YES	5179	2,675	17	
342-LA	ELIZABETH HILLOSKY,SR.	YES	5181	2,225	17	

PARCEL NO.	OWNER	EXIST. BLDG.	LOT NO.	AREA S.F.	SHEET NO.	
342-A-LA	FLORENCE L. EVANS	YES	5183	1,573	17	
342-WA	ELIZABETH HILLOSKY, SR.	YES	5181		17	FILL BASEMENT
342-A-WA	FLORENCE L. EVANS	YES	5183		17	FILL BASEMENT
344-LA	FRANK JAMES COLLA	YES	55466	3,724	17	
344-A	THE GREEK COMM. AGLOS LOANNIS ORTHODOX CHURCH	NO	O.L.363	336	17	
344-B-LA	FRANK JAMES COLLA	NO	55466	315	17	
345-LA	MARY DEVAN	YES	55467	5,366	17	
346-LA	CLARA ANDERSON	YES	55466	7,335	17	
347-LA	FRANK JAMES COLLA	YES	55469	3,525	17	
* 348-LA	JOHN PAUL	YES	2308	3,150	17	
* 350-LA	JOHN BUDAKER, ANN BUDAKER	YES	2309	4,100	17	
352-LA	LEROY E. BILLIG	YES	5185	1,025	17	
352-WA	LEROY E. BILLIG	YES	5185		17	FILL BASEMENT
352-A-WA		YES	5186		17	FILL BASEMENT
352-A-LA	MARY J. COMINOS	YES	5186	320	17	
353-LA	MORTON, RAYMOND D. AND BERNARD WHITE	YES	2899	5,000	17	
353-WA	RALPH A. KELLY, ISABELLE M. KELLY	YES	2899		17	REMOVE FOUNDATION
356-LA	THE GENERAL ELECTRIC COMPANY	NO	2314,2315,2296,2298	37,700	17	
356-TS	THE GENERAL ELECTRIC COMPANY	NO	2313,2314, 2296,2298	4960	17	CONST. EQUI.. ACCESS
358-LA	THE ROAD OF REMEMBRANCE POST #472 AM. LEGION DEPT. OF OHIO	YES	2314	10,750	17	
359-LA	JAMES E. & WENDELL H. BENNETT, IDA JOSEPHINE DATSON	YES	2313	7,325	17	
359-A-LA	JAMES E. & WENDELL H. BENNETT, IDA JOSEPHINE DATSON	NO	2313	1,050	17	
360-LA	HAROLD P. SMITH, EMILY E. SMITH	YES	2313	3,950	17	
360-WA	HAROLD P. SMITH, EMILY E. SMITH	NO	2313		17	FILL BASEMENT
361-C-LA	*NORTHERN INVESTMENT COMPANY*	NO	2311	125	17	
362-LA	TINCO DE CARPENTIER	YES	3346	31,857	19	
362-WA	TINCO DE CARPENTIER	YES	3346		19	FILL BASEMENT
363-LA	RALPH E. GOFF, AGNES E. GOFF	YES	3344	9,750	19	
364-LA	JOHN COMEK, MARY COMEK	YES	3369	4,430	19	
365-LA	SARAH KLATMAN, HANNAH KLATMAN	YES	3369	2,275	19	
366-LA	FAY KIRKORSKY	YES	3368	4,748	19	
367-LA	IDEALIA HOWELL, EUALEE HOWELL	YES	3368	5,080	19	
368-LA	JAMES DAVIS, EULA MAE DAVIS	YES	3367	5,420	19	
369-LA	CARRIE E. WATSON	YES	3366	5,840	19	
370-LA	THE ECONOMY ELECTRIC COMPANY	YES	3349	3,094	19	
370-WA	THE ECONOMY ELECTRIC COMPANY	YES	3349		19	REMOVE FOUNDATION AND GRADE AREA
371-LA	DOROTHY MOHN	YES	3365	6,200	19	
372-LA	DEMETRIOS AND MAVRIKIS	YES	3365	5,063	19	
373-LA	SOPHIA MARGOLIS	YES	3364	5,687	19	
374-LA	EDWARD PARKMAN, MYRTLE L. PARKMAN	YES	3363,3364	5,871	19	
375-LA	JOHN SPANOS, ALEXANDRA SPANOS	YES	3363	5,731	19	
376-LA	MARY H. MENEGAY, CLARA L. PAAR	YES	3362	6,000	19	
377-LA	NICHOLAS GLAROS, NIKI GLAROS	YES	3361	6,780	19	
378-LA	JOHN SERINO AND MARY MARZULLO	YES	3360	5,467	19	
378-WA	JOHN SERINO AND MARY MARZULLO	YES	3360		19	FILL BASEMENT
379-LA	ROSE KNABEL	YES	11061	2,650	19	
379-WA	ROSE KNOBEL	YES	11061		19	FILL BASEMENT
380-LA	MARY DEVAN	YES	3359	8,180	19	
381-LA	HENRY B. GESSAMAN, VIRGINIA GESSAMAN	YES	3358	3,518	19	
382-LA	NORQUIST LAND COMPANY	YES	3358	3,468	19	
383-LA	JOHN J. VERNELLO, EDNA M. VERNELLO	YES	3357	3,350	19	
383-B-LA	MARY C. CARTWRIGHT, MARGARET CONROY	YES	3357	3,252	19	
384-LA	WILMA V. GING	YES	3356	6,090	19	
384-WA	WILMA V. GING	YES	3356		19	FILL BASEMENT
387-LA	THE BOARD OF EDUCATION OF YOUNGSTOWN CITY SCHOOL DISTRICT	YES	3355	26,418	19	
390-LA	FREDRIKA H. BOGGS, MINTER B. BOGGS	YES	3375	3,750	19	
390-A-LA	JAMES WALSH JR.	YES	3375		19	
391-LA	ROSE EVELYN STRAWDERMAN	YES	3376	2,000	19	
391-A-LA	MILTON KIBBLE, MARY LOU KIBBLE	YES	3375		19	
392-LA	GIUSEPPE CHIRCHIGLIA, ROSE CHIRCHIGLIA	YES	3376	2,000	19	
393-LA	FAY KIRORSKY	YES	3377	1,875	19	
394-LA	MATTIE B. TERRELL	YES	3377	3,750	19	
395-LA	EVA WILLIAMS, ROBERT WILLIAMS	YES	3378	3,750	19	
397-LA	CHESTER V. LONG, MARGARET F. LONG	YES	3379	3,675	19	
406-LA	CLOYDE JAMES FRY, ROBERTA MARION FRY	YES	36130	4,600	19	
406-A-LA, 406-B-LA, 406-B-WA	UNCLAIMED	YES	1695		19	
407-LA	LOUIS HARRINGTON, JULIA HARRINGTON	YES	1696		19	
425-LA	SOPHIE COHEN	YES	1695,1696		19	FILL BASEMENT
426-LA	GEORGE BRADLEY, FRANCES JUNE BRADLEY	YES	1701	10,593	19	
427-LA	HELEN BUGNO	YES	1700	10,923	19	
428-LA	EDWARD WILLIAMS, J.B. WILLIAMS	YES	1700	5,958	19	
428-LA	GRANT BARNETT, JOSEPHINE BARNETT	YES	1697	4,377	19	
429-WA	GRANT BARNETT, JOSEPHINE BARNETT	YES	1694	2,160	19	
430-LA	JOHN MCCARTY SCHWARTZ	YES	1694	1,485	19	
430-WA	JOHN MCCARTY SCHWARTZ	YES	1694		19	FILL BASEMENT
431-LA	ARNOLD AND CATHERINE HOWELL	YES	5567	592	19	
431-WA	ARNOLD AND CATHERINE HOWELL	YES	5567		19	FILL BASEMENT
432-LA	JEAN WEISER, ANDREW ROSENFELD	YES	3497	543	19	
432-WA	JEAN WEISER, ANDREW ROSENFELD	YES	3497		19	FILL BASEMENT
433-LA	WILLIE JAMES TALLEY	YES	34916	464	19	
433-A-LA	RUTH B. ROBINS	YES	34916		19	FILL BASEMENT
433-WA	WILLIE JAMES TALLEY	YES	34915	342	19	
433-A-WA	RUTH B. ROBINS	YES	34914	3,321	19	
354-A-LA	*THE GENERAL ELECTRIC COMPANY*	YES	34915		19	FILL BASEMENT
393-A-LA	*F.KIRKORSKY AND C.& E. BENTLEY*	YES	34914		19	REMOVE FOUNDATION
		YES	2311,2312		17	
		YES	3377	1,875	19	

ELIGIBLE FOR FEDERAL PARTICIPATION
* 348-A — THE CITY OF YOUNGSTOWN (FORMERLY JOHN PAUL) — NO — 2308 (PART) — 450 — 17
* 350-A — THE CITY OF YOUNGSTOWN (FORMERLY JOHN BUDAKER) — NO — 2309 (PART) — 744 — 17

RECEIVED R/W NOV 29 1962 State Highway Dept. Dis. No. 4

Parcel 344 A Area Revised 11-19-62
ADDED PCL-356-TS DELETED 356-WA 2-22-61
Pcl. 393-LA Revised Deed 12-15-60
Pcl. 393-A-LA Added 12-15-60
Pcl. 318-LA Revised Area 10-18-60
Pcl. 285-A-LA Changed Area & Sta. 8-23-60
Parcels 356-LA & 356-A-LA Added Name & Areas 7-6-60
Parcel 320-A-LA Added Area 7-6-60
Parcel 287-LA Added Area 7-6-60
Parcel 361-C-LA Revised 6-30-60
Parcel 344-A Revised 6-30-60
Parcel 339-LA Revised 6-27-60
Parcel 299-A-LA Revised 6-27-60
Parcel 313-B-A Added Area 6-24-60
Parcel 287-B-LA Deed Information Added 6-24-60
Parcels 316-A & 316-LA Area Revised 6-16-60
Sheet Reference Nos. Revised 4-20-60
Parcel 330-LA Revised 4-18-60
Parcel 344B-LA Revised 4-12-60

ADDED PCLS. 348-A & 350-A PER GUZIAK 6-3-68. J.R.B.

Deleted Pcl. 347-LA, Combined with 347-LA 3-4-65.
12-16-63
Warranty Deed 1017 Pg 637 Case No 2168065
Pcl-319 Aerial Deleted, Area rev Pcl 319-LA 12/16/63

FED. RD.	STATE	PROJECT	
2	OHIO		

471 / 492

MAH-18-17.20

SUMMARY OF R/W REQUIRED

CITY OF YOUNGSTOWN
PROJECT MAH.-18-17.20

PARCEL Nº	OWNER	LOT Nº	AREA SQ. FT.	SHEET Nº	REMARKS
C-1 WA	MARGARET C. BOWREY	18181		22	
C-2 WA	ELIZ. LESKO ZAVACAN	18182		22	
C-3 WA	JOHN & WASYLYNA IWANUIK	18183		22	
C-4 WA	THEO. & NANCY HASSAY	18184		22	
C-5 WA	KOLAR & KURTA	18185		22	
C-6 WA	GUSSIE L. HEYMAN	18186		22	
C-7 WA	CHARLES & FLO L. PALISEN	18187		22	
C-9 WA	CHAS. & JUSTINE SEREDNESKY	6788		22	
C-10 WA	MARY KNAPIK	15348		22	
C-11 WA	JOHN & SOPHIE TOPORCER	15350		22	
C-12 WA	JOHN LEJBA	15351		22	
C-13 WA	ALEX & ADA HODORY	15352		22	
C-14 WA	MARY & JOHN SKLEPKO	15353		22	
C-15 WA	PAUL & MARY KISSEL	15354		22	
C-16 WA	MARY PODRAEZKY	6789		22	
C-17 WA	JOHN & HELEN NESTERUK	6790		22	
C-18 WA	PAUL & JULIA ANTEL	6791		22	
C-19 WA	CHARLES F. SEMPLE	11781		22	
C-20 A	THE ISALY DAIRY CO.	9487		23	
C-20 WA	THE ISALY DAIRY CO.	"		23	
C-22 WA	T. SAADI	3921		25	
C-23 WA	T. SAADI	3920		25	
C-24 A	EXIE SCRUGGS	2363		25	
C-25 A	EMMA JANE McCORKLE	2357		25	
C-26 WA	CLIFTON DOUGLAS-LUCY ANN PARKER	2327		25	
C-27 WA	RUBY B. CHEIRS	2326		25	
C-28 WA	HATTIE BRADLEY	1929		25	
C-29 A	J. B. & H. COLLIER	2355		25	
C-30 A	LOWRENCE & BEATRICE SMITH	2356		25	
C-31 A	TOFFIC SAADI	876		25	
C-33 A	WALTER & WILLO LEE FLIPPING	5662		25	
C-33 WA	"	"		25	
C-34 A	IDA BELLE PEARSON	5663		25	
C-34 WA	"	"		25	
C-35 A	MARY CANNELL	5664		25	
C-35 B		5665		25	
C-35 WA	MARY CANNELL	5664		25	
C-36 A	ANNA CENTRIC	5724		25	
C-37 A	ALVIN & JOSEPHINE CLARK	5725		25	
C-38 A	ANDERSON & OLA MAE JOHNSON	55074		25	
C-39 A	MATTIE HART	55077		25	
C-39 WA	"	"		25	
C-40 A	CLARA WASHINGTON	848		25	
C-40 WA	"	"		25	
C-41 A	UNION NAT'L BANK TRUST	5650		25	
C-42 WA	DOZIER RENAH - JAMES JACKSON	1578		25	
C-43 WA	EMIL E. RESTLE	5668		25	
C-44 A	LINDSAY CARRIE	57454		25	
C-44 WA		57454		25	
C-45 WA		57455		25	
C-46 A	NAT'L CITY BANK OF CLEVE. TR.	2316		26	
C-46 WA		2316		26	
C-47 A	FIRESTONE TIRE & RUBBER CO., AKRON, O.	2900		26	
C-47 WA		2900		26	
C-49 A	FLORENCE MACE	3171		24	
C-50 A	MILITARY ORDER OF COOTIE, PUP TENT #5	3172		24	
C-50 BA	FRANK P. SANDERS	3172		24	
C-51 A	GEORGE A. GRIEN	3173		24	
C-52 A	ISALY DAIRY CO.	2653		24	
C-52 BA	MOFFET L. T. & B.	2653		24	
C-53 A	ISALY DAIRY CO.	3407		24	
C-53 BA	DOLLAR SAVINGS & TRUST CO.	3407		24	
C-54 A	BENJAMIN F. LEWIS	9508		24	
C-54 CA	RALPH M. Mc CRACKEN	9508		24	
C-55 A		5721		24	
C-55 WA		5721		24	

PARCEL Nº	OWNER	LOT Nº	AREA SQ. FT.	SHEET Nº	REMARKS
C-56 A	LEONA LOUISE CALER	5722		24	
C-56 BA	RALPH M. McCRACKEN	5722		24	
C-56 WA	LEONA LOUISE CALER	5722		24	
C-56 B-WA	RALPH M. McCRACKEN	5722		24	
C-57 A	CALVIN & MARTHA WESTON	O.L. 379		24	
C-57 BA	D.H. LEVY & S. DUNGER	"		24	
C-57 B-WA		"		24	
C-57 WA	CALVIN & MARTHA WESTON	O.L. 379		24	
C-58 A	NAPOLEAN & DOROTHY BURT	30332		24	
C-60 A	THEO. R. CLAPP	3371		26	
C-60 WA	"	"		26	
C-61 A	FRED SHUTRUMP	10101		26	
C-61 WA	"	"		26	
C-62 A	BEATRICE B. LOPEZ	1692		26	
C-62 WA	"	"		26	
C-63 A	NATHAM DARSKY	1691		26	
C-63 WA	"	"		26	
C-64 A	FRED WALLACE HUGHES	1690		26	
C-64 WA	"	"		26	
C-65 A	GEORGE & K. KONIESCKY	1689		26	
C-65 WA		"		26	
348 A	JOHN PAUL	2308		26	
348 WA	"	"		26	
350 A	JOHN & ANN BUDAKER	2309		26	
350 WA		"		26	

Sheet Reference Nos. Revised 4-20-60

I-680 R/W SHEET 6 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

472 / 492



PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING SQ.FT.
1-LA	LUIGI FULCINITI	—	—	—	5778
2-LA	PETER & HELEN MIKITA	2-ST.FR.	10×16 FR.	5×6 FR. SHED	5000
3-LA	WILLIAM PUPA	2-ST.FR.	10×16 FR. SHED	7×14 FR. SHED	4090
4-LA	STEVE DOLAK MARY DOLAK	2-ST.FR.	—	8×8 FR. SHED	2120
4-A-LA	ELIZABETH PEDAK	2-ST.FR.	—	—	261
6-LA	MOLLIE BARTA	2-ST.FR.	40×20 FR.	—	5625
7-LA	FRANCISKA ONDASH	2-ST.FR.	8×8 FR. SHED	7×12 BR. SHED	5000
8-LA	MATHEW A. STANKICH MARY LOU STANKICH	2-ST.FR.	12×16 FR.	9×12 FR. SHED	5000
9-LA	JOHN IWANIUK WASYLYNA IWANIUK	2-ST.FR.	—	6×8 FR. SHED	6250
10-LA	FRANK DEAK ELIZABETH DEAK	2-ST.FR.	—	9×6 FR. SHED	4770
11-LA	MARY GARCAR	2-ST.FR.	—	7×12 FR. SHED	2850
12-LA	JOHN KRUPA MARY KRUPA	2-ST.BR.	12×16 FR.	—	136
13-LA	ALBERT FUZY, WM. A. AMBROSE MRS. JULIA KARAKA, PAUL FUZY	2-ST. FR.	36×18 FR.	—	6728
15-LA	ANNE CHABALA LESON	2-ST.FR.	—	6×8 FR. SHED	5000
16-LA	ANNE SHUSTER	2-ST.FR.	10×18 FR.	—	7500
18-LA	MIKE SEMAN MARY SEMAN	2-ST.FR.	—	—	3750
19-LA	PETER KANTOR JR. ETHEL MASZAROS	2-ST.FR.	13×18 FR.	—	6250
20-LA	HELEN KRAVEC	—	16×22 FR.	—	5000
26-LA	ANDREW ANTHOL, ANN CIZMAR PAUL ANTHOL, HELEN YASH	2-ST.FR.	11×15 FR.	7×14 FR. SHED	3820
22-LA	MITRO MICA ANNIE MICA	1-ST.FR.	—	11×18 FR. SHED	4950
24-LA	JAMES K. WALTERS	2-ST.FR.	12×18 FR.	8×10 FR. SHED	11.849
25-LA	HELEN M. BUGNO	1-ST.BR.	11×15 FR.	6×6 FR. SHED	7406

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING SQ.FT.
28-LA	ANNA GONDA	2-ST.BR.	20×20 FR.	—	5000
29-LA	MARY L. ADAMS	2-ST.BR.	14×20 FR.	—	5000
30-LA	PAUL BEDNARIK	2-ST.FR.	12×18 FR.	6×8 FR. SHED	4100
31-LA	VERONICA BUNDASH	2-ST.FR.	14×20 FR.	—	2050
31-A-LA	MICHAEL BEHUN MARY BEHUN	2-ST.FR.	14×22 FR.	—	403
33-LA	MICKEY HANUSCHAK FLORA JEAN HANUSCHAK	1-ST.BR.	—	—	3400
34-LA	JOHN F. TOBIN KATHERINE TOBIN	1-ST.BR.	—	—	1438
35-LA	STEVE MATYL ANNIE MATYL	1-ST.FR.	—	7×9 FR. SHED	5000
36-LA	SUE K. FURDEN JULIA KUNI	1-ST.FR.	—	7×7 FR. SHED	5000
37-LA	JOE VALUSH	1-ST.FR.	—	5×8 FR. SHED	4000

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING SQ.FT.
38-LA	ANNA GAYDOS	1-ST.FR.	12×20 FR.	11×8 FR. SHED	4000
39-LA	ANDREW & SUSIE LENGYEL	1-ST.FR.	—	8×8 SHED	4125
40-LA	ANNA, JOHN S. & JOSEPH YUHASZ	1-ST.FR.	—	8×9 SHED	3680
46-LA	GEORGE ZAHDRERY ELIZABETH ZAHDRERY	2-ST.FR.	—	6×8 FR. SHED	5490
47-LA	ANNA PAVLIK	2-ST.FR.	—	8×8 FR. SHED	3240
48-LA	MARY SELENK	2-ST.FR.	—	9×10 FR. C.C.	689
58-C-LA	JOSEPH S. PETRICK MARIA PETRICK	LOSS OF ACCESS TO LAKEVIEW AVE.			
58-F-LA	STEVEN N. BOBOVNYCK MARY BOBOVNYCK	2-ST.FR.	—	—	3808

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING SQ.FT.
41-LA	THE PORTLAND LAND CO.	—	—	—	6432
43-LA	ANNIE NELSON	—	—	—	1420
49-LA	HELEN W. COHN	—	—	—	68,711

WORK AGREEMENT

PARCEL №	NAME	DESCRIPTION
26-WA	ANDREW ANTHAL, ANN CIZMAR PAUL ANTHAL, HELEN YASH	REMOVE SHED
3-WA	WILLIAM PUPA	FILL BASEMENT
13-WA	ALBERT FUZY, WM. A. AMBROSE JULIA KARAKA, PAUL FUZY	REMOVE GAR. FD'N.
30-WA	PAUL BEDNARIK	REMOVE GAR. FD'N.
31-A-WA	VERONICA BUNDISH	FILL BASEMENT
46-WA	GEORGE ZAHDRERY ELIZABETH ZAHDRERY	FILL BASEMENT
34-WA	JOHN F. TOBIN CATHERINE TOBIN	FILL BASEMENT

REV. NO.	NATURE OF REVISION	DATE	MADE BY
Pcl. 49-LA	Name Change	10-5-60	S.S.
Pcl. 1-A LA	Removed From Taking	12-30-59	J.E.P.
Pcl. 49-LA	Coordinates Added	6-7-60	T.A.B.
	Deleted Parcels 21A-LA	DATE COMP.	
	Added 26WA, 3WA, 13WA, 30WA, 31A-WA, 46WA, 34WA, 58ATS.		
Pcl. 34-LA	Revised Area of Taking	12-1-60	B.H.
Pcl. 49-LA	Revised Area of Taking	1-21-60	B.H.
	REVISED 58-ATS TO 58C-LA	3-25-60	J.D.P.

8-82


I-680

R/W SHEET 7 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

473
492

REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
PCL 84LA	CORRECTED LOT Nos & PR	6-17-59	E.COMISKEY
PCL'S.	62LA-63LA REVISED 82LA DELETED	10-20-59	
PCL'S.	53A-54A ADDED, 62LA-63LA-62SA-63SA REV. 62AS. DELETED	11-10-59	
# 1	ADDED BARRICADES AT SILLIMAN	12-30-59	J.G.P.
# 2	RELOC. 1/A AT LAKEVIEW & STEEL	12-30-59	J.G.P.
	ADDED PR & FENCE	3-25-59	J.D.P.



PARCEL NO	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
49-A-LA	JOE INCE ANNA INCE	2-ST. FR.	10x18 FR.		231
51-LA	BETTY JOE YOHMAN	2-ST. FR.	10x16 FR.		1203
52-LA	ANDREW KOSAR HELEN KOSAR	2-ST. FR.	10x16 FR.		2080
53-LA	MICHAEL NAGY JR.	2-ST. FR.	12x20 FR.	8x10 FR. SHED	2762
54-LA	MARGARET BADA	2-ST. FR.	12x20 FR.		3672
55-LA	VINCENT F. HALKO MARY ANN HALKO	2-ST. FR.	12x12 FR.		5000
56-LA	ANDY LUKAC MARY LUKAC	1-ST. FR.			5000
57-LA	ALEXANDER BARICH MILDRED BARICH	2-ST. BR.	20x20 TILE		13720
58-LA	MARY PAULINE WILLIAMS				20,690
59-LA	GINO LAMARCA ½ LOUISE LAMARCA ½	2-ST. FR.	20x22 FR.		6265
59-A-LA	UGO DIBACCO ½ ANNA DIBACCO ½	2-ST. FR.			2774

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
60-LA	PAUL SEMAI JOAN SEMAI	1-ST. BR.	14x20 FR.	6x12 FR. SHED	5000
61-LA	PAUL GLOVA MARY GLOVA	2-ST. FR.		6x10 FR. SHED	5000
67-LA	MARY MACYNSKI	1½ ST. BR.		6x16 FR. SHED	5000
79-LA	JOHN BOBANICH ANNA BOBANICH	2-ST. BR.	12x20 FR.		7728
80-LA	ANNA MOZZY-MARY BARTELL-MICHAEL & ANDREW CYCYK	2-ST. BR.			2000
81-LA	JOHN R.-CHARLES E.-JOSEPH T.-MARY ANN-CATHERINE T. & JENNIE S. MARCH	2-ST. FR.	18x20 FR.	6x10 FR. SHED	960
62-LA	DAFINI NEGROFF	2-ST. FR.	12x20 FR.		64
63-LA	BARBALA OR BARBARA BURCSAK	2-ST. FR.		8x10 FR. SHED	705
83-LA	JOHN STUN	1-ST. FR.	14x18 FR.		3189
84-LA	ASTER SKLEPKO	1-ST. FR.	12x20 FR.		3750

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
85-LA	JOHN DZUROFF ANNI DZUROFF	2-ST. FR.	14x20 FR.		5000
86-LA	MICHAEL SABOL JR.-MARTIN SABOL & MARY B. KAVANAUGH	2-ST. FR.			5000
87-LA	MARY BAROLAK ROMAN-EDWARD-EMIL-JOSEPH T. BAROLAK	1½-ST. FR.	20x20 FR.		5000
88-LA	THERESA TOBIS OR THERISA TOBIAS	2-ST. FR.			5000
89-LA	JOHN J. BRCAK AGNES BACAK	2-ST. FR.	12x16 FR.		5000
90-LA	JOSEPH-JOSEPH S.-BERNARD R.-GEORGE C. KNAPIC-FRANCES K. ACRI	1½-ST. FR.	1 CAR		5000
91-LA	WALLACE DORKO HILDA MARIE DORKO	1½-ST. FR.	12x18 FR.		5000
92-LA	MARTIN HARCHAR ANNA HARCHAR	2-ST. FR.	12x18 FR.		5000
93-LA	MARY D. OLSAVSKY	2-ST. FR.	14x18 FR.		5000
94-LA	KAROL BUREK ANNA BUREK	2-ST. FR.	12x18 FR.		5000
95-LA	MARI OR MARY MAJOVSKY				5000
96-LA	VERONICA MISSIK	2-ST. BR.		6x10 FR. SHED	5000
97-LA	JOHN KISS ELIZABETH KISS	2-ST. BR.	28x20 FR.		5000
62-S	DAFINI NEROFF				750
63-S	BARBALA OR BARBARA BURCSAK				335

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
62-A-SA					80
64-SL	ANDREW TARKANICH SUSIE TARKANICH				25
71-LA	ANDY L. LESKOVEC ANNA C. LESKOVEC	2-ST. FR.	12x18 FR.		360
72-LA	HELEN BROGLI JULIANNA BROGLI	2-ST. FR.	10x18 FR.		980
73-LA	CHARLES R. KELLY LEONA CODE	1½-ST. FR.	10x18 FR.	14x18 FR. SHED	1440
74-LA	THOMAS A. DENEHY BRIDGET L. DENEHY	2-ST. FR.	12x18 FR.		2090
75-LA	ANDREW BODNAR ANNA BODNAR	2-ST. FR.	12x18 FR.		1950
76-LA	JOSEPH BANKOVITCH	2-ST. FR.	12x18 FR.		3040
77-LA	JOHN PAUL BARBOLA, PAUL	2-ST. FR.	22x24 FR.		3500
98-LA	GEORGE BODNAR JR. HELEN BODNAR	2-ST. FR.	18x22 FR.		10680
100-LA	MARY ADAMS	2-ST. FR.	15x18 FR.		5000
101-LA	JOHN M. SUDZINA AGNES SUDZINA	2-ST. FR.	18x20 FR.		5250
102-LA	BRIDGET L. RUANE	2-ST. FR.	18x18 FR.		5250

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING Sq.Ft.
103-LA	JOHN FETZER BARTA FETZER	2-ST. FR.	12x18 FR.		5250
104-LA	ZVONIMIR ROY VULYAK ROSE M. VULYAK	2-ST. FR.	12x18 FR.		5250
105-LA	ANNA KACHMAR OR ANNA KACHMER	2-ST. FR.			5250
106-LA	MICHAEL YACKO ELIZABETH YACKO	2-ST. FR.	10x16 FR.		5250
107-LA	PETER ZEMAN MARY ZEMAN	2-ST. FR.	12x16 FR.		5000
108-LA	VALENT LEDINKO	2-ST. FR.	12x18 FR.		5000
109-LA	GABOR TOTH SUSIE TOTH	2-ST. FR.	12x17 FR.		5000
110-LA	MATHEW HAMBORSKY ANNA G. HAMBORSKY	2-ST. FR.	12x18 FR.		5000
111-LA	FRANK BAROLAK	2-ST. FR.	12x18 FR.		5000
112-LA	JOSEPH ANDREWS	2-ST. BR.			10612
53-A	MICHAEL NAGY, JR.				1398
54-A	MARGARET BADA				488


WORK AGREEMENTS

PARCEL Nos	NAME	DESCRIPTION
62-WA	DAFINI NEGROFF	FILL BASEMENT
63-WA	BARBALA OR BARBARA BURCSAK	FILL BASEMENT
80-WA	ANNA MOZZY - MARY BARTELL MICHAEL & ANDREW CYCYK	FILL BASEMENT
81-WA	JOHN-CHARLES-JOSEPH-MARY ANN-CATHERINE & JENNIE MARCH	FILL BASEMENT
72-WA	HELEN BROGLI JULIANNA BROGLI	FILL BASEMENT
73-WA	CHARLES R. KELLY LEONA CODE	FILL BASEMENT

Revised 64-SL 10-6-61
Revised 58-F&A 6-23-60

FED. RD.	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

474
432



PARCEL NO.	NAME	BUILDINGS HOUSES	GAR.	MISC.	AREA OF TAKING
113-LA	MICHAEL ZUZAN	2-ST. BR.	20X24 TILE	6'6" x 6'	6142
114-LA	JULIA KUN	2-ST. FR.	10X20 C.B.		3390
115-LA	MIKE POTOCNAK MARY POTOCNAK	2-ST. FR.		6X12 FR. SHED	3220
116-LA	JOHN SMITH CATHERINE SMITH	2-ST. FR.	12X18 FR.		3106
117-LA	FRANK FERKO	2-ST. FR.	12X18 FR.		2964
118-LA	PAUL MATUSCAK ANNA MATUSCAK	2-ST. FR.		FR. SHED	2800
119-LA	BERTHA HOHOS	2-ST. FR.	12X20 BR.		2680
121-LA	GEORGEA. BOZICK CATHERINE BOZICK	2-ST. FR.		6X12 FR. SHED	2660
122-LA	JOE PISANSKY MARY PISANSKY	2-ST. FR.	12X22 C.B.	6'6" FR. SHED	2700
123-LA	ANDREW ZAMBORI MARY ZAMBORI		12X22 C.B.	6'10 FR. SHED	2740
124-LA	FRANK PALIGA HELEN PALIGA		13X20 BRICK	7'X18 FR. SHED	2660
125-LA	KATARINA GIBA		14'X23 C.B.	9'X13 C.B. SHED	3209
127-LA	PAUL KOVAL IRENE KOVAL	2-ST. FR.	14X20 BR.	6'X10 FR. SHED	8840
128-LA	SUSANNA KRAMER	1-ST. FR.	12X18 FR.		5200
129-LA	GEORGE LUTZA JR.	2-ST. FR.	14'X20 C.B.	8'X14 FR. SHED	5200
130-LA	MATTHEW KOVAL ANNA KOVAL	2-ST. FR.	10X16 FR.		1540
131-LA	STEVAN HOFFMAN ANNA HOFFMAN	2-ST. FR.	12'X20 BR.	8'X16 FR. BARN	3180
133-LA	ST. MICHAELS RUSS. ORTH. GR. CATH. CHURCH			30'X7' BR. BLDG.	48,376
134-LA	MAHONING VALLEY SANITARY DISTRICT				50,220
135-LA	JOHN SAHLICA				12882
136-LA	SERBIAN EASTERN ORTH. CONGREGATION	1-ST. BR.			130,633

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BARN	AREA OF TAKING
140-LA	BERKELEY-BERTHA-IRVING & BERNICE FROMKIN				307,525
113-SA	MICHAEL ZUZAN				3088
114-SA	JULIA KUN				1810
115-SA	MIKE POTOCNAK MARY POTOCNAK				1980
116-SA	JOHN SMITH CATHERINE SMITH				2094
117-SA	FRANK FERKO				2236
118-SA	PAUL MATUSCAK ANNA MATUSCAK				2400
119-SA	BERTHA HOHOS				2520
121-SA	GEORGE A. BOZICK CATHERINE BOZICK				2600
122-SA	JOE PISANSKY MARY PISANSKY				2500
123-SA	ANDREW ZAMBORI MARY ZAMBORI				2460

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BARN	AREA OF TAKING
124-SA	FRANK PALIGA HELEN PALIGA				2540
125-SA	KATARINA GIBA				5880
130-SA	MATTHEW KOVAL ANNA KOVAL				720
131-SA	STEVAN HOFFMAN ANNA HOFFMAN				6204
140-SA	BERKELEY-BERTHA-IRVING & BERNICE FROMKIN	1-ST. FR. House			9080
133	ST. MICHAELS RUSS. ORTH. GR. CATH. CHURCH				750

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
134	ST. MICHAELS RUSS. ORTH. GR. CATH. CHURCH				240
136	SERBIAN EASTERN ORTH. CONGREGATION				715

WORK AGREEMENT

PARCEL Nº	NAME	DESCRIPTION
133-WA	ST. MICHAELS RUSS. ORTH. GR. CATH. CHURCH	REMOVE FOUNDATION
130-WA	MATHEW KOVAL ANNA KOVAL	FILL BASEMENT
131-WA	STEVAN HOFFMAN ANNA HOFFMAN	FILL BASEMENT

REVISIONS

REV. Nº	NATURE OF REVISION	DATE	MADE BY
9	Added Pcl. 134 LA, ALA, BLA, & CLA	6-25-65	
6	Parcel 136-S Revised Sewer	7-7-60	S.S.
5	Parcel 133-S To 133	7-6-60	S.S.
4	Parcel 136-S Revised	6-30-60	S.S.
8	ADDED PARCEL 134	4-17-61	T.J.
7	Rev. Corr. Parcel 133	3-28-61	T.J.
#1	ADDED M.V.S.D. FEEDER MAIN	12-30-59	J.E.P.
	REVISED L/A LINE AT STEEL ST.		
	ADDED 131WA, 130WA, 133, 133WA		
	136 S		
#2	REVISED FENCE - ADD PL	3-28-60	J.D.P.
#3	Parcel 135-LA Area Revised	5-10-60	

1138767

THE MAHONING VALLEY SANITARY DISTRICT RIGHT-OF-WAY PLAT

Graphic Scale, (Original Tracing)

CITY OF YOUNGSTOWN
MAHONING COUNTY, STATE OF OHIO
MAH. 18-17.20 -YOUNGSTOWN EXPRESSWAY

APPROVED BY:
BOARD OF CONTROL
MAYOR _____ 3/18/64
SIGNATURE DATE
LAW DIRECTOR _____ 3/14/64
SIGNATURE DATE
FINANCE DIRECTOR _____ 3/18/64
SIGNATURE DATE

DEPT. OF PUBLIC WORKS
COMM. OF ENGINEERING _____ 3/18/64
SIGNATURE DATE

THE M.V.S.D. BOARD OF DIRECTORS

PRESIDENT _____ A. I. KIDSTON 12-5-63
SIGNATURE DATE
MEMBER _____ W. F. MacQUEEN 12-5-63
SIGNATURE DATE
SECRETARY _____ D. D. HEFFELFINGER 12-5-63
SIGNATURE DATE

RECEIVED FOR RECORD ON THE 11TH DAY OF FEB. 1965
AT 3:05 O'CLOCK P.M. RECORDED IN VOL. 55 PAGES 247 OF
THE MAHONING COUNTY RECORD OF DEEDS ON THE 15 DAY
OF February, 1964.
Horace G. Tetlow
MAHONING COUNTY RECORDER

Needs no transfer
2-11-65
F. D.

NOTE
ALL STATIONS AND BEARINGS SHOWN REFER TO EXPRESSWAY DATA EXCEPT WHERE MARKED M.V.S.D. OR EXISTING STATION.

DWG. No. D-6-X 140.1
Acc. No. 9194
File - V-11-85

REVISED: NOV. 6, 1963 - TRIPP
* - DENOTES REVISION OR ADDED INFORMATION
Added Pcls. 134 LA, 134 ALA, 134 BLA, 134 CLA. 8-17-65
Rev. Nov. 21, 1963 — * DENOTES ADDITIONAL DATA By M.V.S.D. REG. SURVEYOR, No. 3263, John T. Santagata

E.O.N.D.

I-680

R/W SHEET 9 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

475/492

SS-18 644 L.F. TYPE "C" FENCE

AREA OF FEDERAL PART. (LAND FEE TITLE)


** (148) 9000 Sq. Ft. ELIGIBLE OUT OF ORIGINAL 71000 Sq. Ft. IN LA.

* (146) 14,400 Sq. Ft. " " " " 42,742 " " " ".

REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
#1	ADDED M.V.S.D. FEEDER MAIN	12-30-59	J.E.P.
	REVISED R/S, LA LINE		
	ADDED PARCELS 1405, 1445		
#2	REVISED R/W FENCE-ADDED R/S	3-28-60	J.D.P.
#3	Added Bldg & Well Parcel 147 LA	8-15-60	S.S.
#4	Revised P.O.S. 146 LA & 148 LA to Show Federal Participation PER STRAHL.	5-7-68	J.R.B.

PARCEL NO.	NAME	BUILDINGS HOUSES	BUILDINGS OTHER		AREA OF TAKING	
143-LA	GEISI PASSARELLI CHRISTINA PASSARELLI	-	-	-	362,635	
144-LA	BALTIMORE & OHIO RAILROAD					
145-LA	ANGELO, MARK, JOHN & JOSEPH PASSARELLI	-	-	-	39,920	
146-LA	GORGIE REALTY CO.	1 ST.C.B. 65 x 48	TILE 12x16 SHED		42,742	*
147-LA	JOE MASKULKA GEMMA BADINO	1 ST.C.B. 15x20 1 ST.C.B. 50x35			30,050	
148-LA	SAM MARGOLIS	1ST.C.B. 52x40			71,000	**
136-LA	SEE SHEET #3					
140-LA	SEE SHEET #3					
146-A-LA	BALTIMORE & OHIO R.R.	-	-	-		
1405	BERKELEY-BERTHA-IRVING & BERNICE FROMKIN					
1445	BALTIMORE & OHIO R.R.					

NOTE: FOR INVENTORY, SEE SHEET



I-680

R/W SHEET 10 OF 26

FED. RD	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

476 / 492

FINAL SURVEY	SURVEYED	BY
	PLOTTED	
	CHECKED	DATE
NOTE BOOK	AREAS	
NO.	AREAS CHECKED	

MAHONING RIVER

BEGIN SHEET ~ STA. 950+00

END SHEET ~ STA. 00+096.27

1337 L.F. TYPE "C" FENCE

WORK AGREEMENT		
PARCEL Nº	NAME	DESCRIPTION
150-WA	JOSEPH & ROBERT F. JENKINS	FILL BASEMENT
170-T	BOARD OF PARK COMMISSIONERS YOUNGSTOWN TWP. PARK DISTRICT	CONSTRUCTION OF PARK ROAD

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
143-LA	THRU 148-LA SEE SHEET 9				
149-LA	JOHN & ANDREW FUSCO			18×18 SHED	4,530
151-LA	THEODORE SAROKA GINO PARISI		1-S.C.B. 35×50		12,298 (13,398)
150-LA	JOSEPH E. & ROBT. F. JENKINS		50×96 Block Bldg.		50,701
154-LA	MARGARET B. SITTINGER	22×28 1-S.FR.			2,350
155-LA	THE YOUNGSTOWN DUNBRIK CO.		1-S.C.B. 45×80		53,789 (53,789)
170B-LA	UNION NATIONAL BANK OF YOUNGSTOWN ET-AL			SHED	3,210
159-LA	VINCE MINOR				8,118
160-LA	BERNARD BRUSS	2-S. FR.	12×18 FR.		4,590
161-LA	LEO & BERNARD BRUSS	LUMBER YD. BLDGS.	SEE SHSA		8,400
150-A-LA	PAUL PAGAC				4,290
161-SA	LEO & BERNARD BRUSS				33,350
150-B-LA	ELLA LOUISE WICK				333
170-LA	See sheet 11				
154-A	LORIETTA McGEE				377.5


REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
# 2	REVISED FENCE-ADDED PR.	3-28-60	J.D.P.
#3	Parcels 170-LA, 170-T, 170B-LA	4-20-60	T.A.B.
#4	Revised Parcel 154-A	6-23-60	S.I.S.
	ADDED PARCEL 154 A	12-30-59	
#1	ADDED 42" MVSD WATER LINES Revised	12-30-59	J.E.P.
Parcels 150-LA, 150-A-LA, 150-B-LA, 155-LA Revised		7-27-59	

Parcel 170-T	Changed From Work Agreement To Temporary	7-6-60	
Parcel 155-LA	Area Revised	7-6-60	
Parcel 151-LA	Area Revised	7-6-60	
Parcel 149-LA	Area Revised	7-6-60	
Parcel 170B-LA	Revised	7-5-60	
Parcel 149-LA	Revised	6-27-60	
Parcel 170-B-LA	Revised	6-27-60	

I-680


FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

477
492


ACCESS FOR UTILITIES MAINTAINED
MAIN COLLECTING CHAMBER
AVENUE
MAHONING
BEGIN SHEET — STA. 960+00
960+53
104'
961+41
112'
OL 493
OL 494
N
TIMBER
OL. 490
OL 495+00
DAM
963+45
107'
963+45
55'
963+45
85'
963+45
85'
963+45
85

FED. RD.	STATE	PROJECT	
2	OHIO	MAH. 18-17.20	

478/492



1685 L.F. TYPE "C" FENCE

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
171-LA	SEE SHEET No 6				
173-LA	WILLIAM W. NEFF ARMIDA NEFF	2-ST. BR. 2-ST. FR.	18x18 FR.		7625
174-LA	HAROLD & ETHEL GASKINS	2-ST. FR.	12x18 FR.	18x18 FR. SHED	7625
175-LA	JOHN J. CIKA DOROTHY A. CIKA	2-ST. FR.			2920
176-LA	JAMES A. POTTER PAULINE POTTER	2-ST. FR.			2920
177-LA	I SALY DAIRY CO.	2-ST. FR.	IN BASM'T.		10215
178-LA	THE DOLLAR SAVINGS & TRUST CO. TRUSTEE	2-ST. FR.			7634
179-LA	JOHN WILLIAMS LOU GENIA WILLIAMS	2-ST. FR.			6940
180-LA	DOUGLAS JONES CHESTINA JONES	2-ST. FR.	12x18 FR.		6940
181-LA	BESSIE AGRENOVITZ	2-ST. FR.	20x16 BR. SHED	7x12 FR. SHED	6940
182-LA	JESSIE DOUGLAS CHRISTINE DOUGLAS	2-ST. FR.			5028
183-LA	MARY G. REITZELL FLORA A. REITZELL	2-ST. FR.			6940
184-LA	BENJAMIN VERNON CLARA VERNON	2-ST. FR.			3960
185-LA	GILSON T. GRAHAM				3300
186-LA	ANNIE K. HARPER ROBINSON ALIAS ANNIE SIMMONS	2-ST. FR.			1560
188-LA	EULALIA M. LUTHER	2-ST. FR.	20x20 FR.		5900
189-LA	ROSINA SCHNEIDER	2-ST. FR.		8x16 FR. SHED	6000
190-LA	JAMES ARTHUR ROSS ANNIE B. ROSS	2-ST. FR.	18x18 FR.		6250
191-LA	ETHEL GILFILLAN	2-ST. FR.	12x18 FR.		3300
192-LA	D. N. GARVER MARTHA E. GARVER	2-ST. FR.			7695
193-LA	CLYDE E. TRUITT DOROTHY C. TRUITT	2-ST. FR.	12x18 FR.		3630
194-LA	TUFIC SAADI	2-ST. FR.	10x12 FR.		5066
195-LA	CHARLOTTE BYERS	2-ST. FR.	12x18 FR.		5066

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
196-LA	MARTIN BOKESCH CHRISTINA BOKESCH	2-ST. FR.			3924
197-LA	IRENE H. VANMETER	2-ST. FR.		12x16 FR. SHED	3252
198-LA	JOSEPH STOKAN	2-ST. FR.			6940
200-LA	KATHLEEN WATKINS	2-ST. FR.	12x20 FR. 16x20 FR.		6940
201-LA	KATHERINE B. WILSON	2-ST. FR.	16x18 FR.		6940
202-LA	JAMES ANDERSON	2-ST. FR.			4500
203-LA & 204-LA	FLORENCE APPEL DORFF HELEN APPEL LEWIS CLARA APPEL CASSESE	2-ST. FR. 1-ST. FR.			9300
205-LA	CLARENCE C. McKELRY ELIZABETH McKELRY	2-ST. FR.	18x18 FR. 10x16 FR.	4x10 FR. SHED	18x20 FR. BARN 9000
206-LA	THOMAS A. MUMFORD	2-ST. FR.		8x20 FR. SHED	7500
207-LA	LILLIAN B. JONES RAFE	2-ST. FR.	12x20 C.B.	8x14 FR. SHED	6000
212-LA	T SAADI	2-ST. FR.			4500
213-LA	HOWARD JAMES WILLIE MAE JAMES	2-ST. FR.			2910
214-LA	ARTHUR I. WALDMAN	2-ST. BR.			7275
215-LA	JAMES MONROE LONG	2-ST. FR.			4340
208-LA	JESUS HERNANDEZ MARY E. HERNANDEZ	2-ST. FR.			3108
209-LA	LEONARD HALLEWELL ESTELLA HALLEWELL	2-ST. FR.			3009
209-A-LA	JAMES BROWN	2-ST. FR.	12'x16' FR.		2549
210-LA	FREDERICK LEROY TAYLOR GRACE VERA TAYLOR	2-ST. FR.			6425
211-LA	JOSEPH ANDROSEK 7/8 WALSH & ROBERTS INC. 2/8	2-ST. FR.			3806
211-A-LA	FREDA C. ANDERSON	2-ST. FR.			2903
211-B-LA	JAMES DOMINIC PRECURATO MARY DELORES PRECURATO	2-ST. FR.	14'x20' C.B.	6x12 FR. SHED	4902
216-LA	ROY F. MORT	2-ST. FR.	12'x16' FR.	5x12 FR. SHED	9675
199-LA	JOSEPH STOKAN	2-ST. FR.			6940

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING


REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
#1	Parcels 203LA, 204LA Revised	6-25-59	E.J.C.
	ADDED SEWER	1-19-60	
#2	ADDED PL	3-28-60	J.D.P.
#3	Parcel 215-LA Revised	7-13-60	S.S.
#4	ADDED 199-LA	12-15-60	P.H.


I-680 R/W SHEET 13 OF 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH 18-17.20	

479 492

DIV. 4 R/W RECORD SECTION FEB 26 1963 RECD. ..... RWD.


EDWARDS STREET
MARSHALL STREET
984 L.F. TYPE "C" FENCE
PROPOSED R/W LINE
2409 L.F. TYPE "C" FENCE
WEST AVE.
WALL
BEGIN SHEET ~ STA. 980+00
END SHEET ~ STA. 990+00
980+24.5
110'
RAMP "F"
PLUM ST.
TIMBER
BUILDING IMPINGEMENT
RAMP "H"
BARRICADE
BURNS ST.
HIGH STREET
PROPOSED R/W LINE
T.S. STA. 0+88.12
981
982
983
984
985
986
987
988
989
5678
5677
5506
5507
5508
5121
5722
9440
9439
9438
9437
30332
30331
5457
4822
4521
30255
30254
30253
30252
2362
2363
2357
2356
2350
2351
2354
2355
2360
2361
2428
2429
2430
2431
2432
2433
2434
2435
2436
2437
2438
2439
2440
2441
2442
2443
2444
2445
2446
2447
2448
2449
2450
2451
2452
2453
2454
2455
2456
2457
2458
2459
2460
2461
2462
2463
2464
2465
2466
2467
2468
2469
2470
2471
2472
2473
2474
2475
2476
2477
2478
2479
2480
2481
2482
2483
2484
2485
2486
2487
2488
2489
2490
2491
2492
2493
2494
2495
2496
2497
2498
2499
2500
2501
2502
2503
2504
2505
2506
2507
2508
2509
2510
2511
2512
2513
2514
2515
2516
2517
2518
2519
2520
2521
2522
2523
2524
2525
2526
2527
2528
2529
2530
2531
2532
2533
2534
2535
2536
2537
2538
2539
2540
2541
2542
2543
2544
2545
2546
2547
2548
2549
2550
2551
2552
2553
2554
2555
2556
2557
2558
2559
2560
2561
2562
2563
2564
2565
2566
2567
2568
2569
2570
2571
2572
2573
2574
2575
2576
2577
2578
2579
2580
2581
2582
2583
2584
2585
2586
2587
2588
2589
2590
2591
2592
2593
2594
2595
2596
2597
2598
2599
2600
2601
2602
2603
2604
2605
2606
2607
2608
2609
2610
2611
2612
2613
2614
2615
2616
2617
2618
2619
2620
2621
2622
2623
2624
2625
2626
2627
2628
2629
2630
2631
2632
2633
2634
2635
2636
2637
2638
2639
2640
2641
2642
2643
2644
2645
2646
2647
2648
2649
2650
2651
2652
2653
2654
2655
2656
2657
2658
2659
2660
2661
2662
2663
2664
2665
2666
2667
2668
2669
2670
2671
2672
2673
2674
2675
2676
2677
2678
2679
2680
2681
2682
2683
2684
2685
2686
2687
2688
2689
2690
2691
2692
2693
2694
2695
2696
2697
2698
2699
2700
2701
2702
2703
2704
2705
2706
2707
2708
2709
2710
2711
2712
2713
2714
2715
2716
2717
2718
2719
2720
2721
2722
2723
2724
2725
2726
2727
2728
2729
2730
2731
2732
2733
2734
2735
2736
2737
2738
2739
2740
2741
2742
2743
2744
2745
2746
2747
2748
2749
2750
2751
2752
2753
2754
2755
2756
2757
2758
2759
2760
2761
2762
2763
2764
2765
2766
2767
2768
2769
2770
2771
2772
2773
2774
2775
2776
2777
2778
2779
2780
2781
2782
2783
2784
2785
2786
2787
2788
2789
2790
2791
2792
2793
2794
2795
2796
2797
2798
2799
2800
2801
2802
2803
2804
2805
2806
2807
2808
2809
2810
2811
2812
2813
2814
2815
2816
2817
2818
2819
2820
2821
2822
2823
2824
2825
2826
2827
2828
2829
2830
2831
2832
2833
2834
2835
2836
2837
2838
2839
2840
2841
2842
2843
2844
2845
2846
2847
2848
2849
2850
2851
2852
2853
2854
2855
2856
2857
2858
2859
2860
2861
2862
2863
2864
2865
2866
2867
2868
2869
2870
2871
2872
2873
2874
2875
2876
2877
2878
2879
2880
2881
2882
2883
2884
2885
2886
2887
2888
2889
2890
2891
2892
2893
2894
2895
2896
2897
2898
2899
2900
2901
2902
2903
2904
2905
2906
2907
2908
2909
2910
2911
2912
2913
2914
2915
2916
2917
2918
2919
2920
2921
2922
2923
2924
2925
2926
2927
2928
2929
2930
2931
2932
2933
2934
2935
2936
2937
2938
2939
2940
2941
2942
2943
2944
2945
2946
2947
2948
2949
2950
2951
2952
2953
2954
2955
2956
2957
2958
2959
2960
2961
2962
2963
2964
2965
2966
2967
2968
2969
2970
2971
2972
2973
2974
2975
2976
2977
2978
2979
2980
2981
2982
2983
2984
2985
2986
2987
2988
2989
2990
2991
2992
2993
2994
2995
2996
2997
2998
2999
3000
3001
3002
3003
3004
3005
3006
3007
3008
3009
3010
3011
3012
3013
3014
3015
3016
3017
3018
3019
3020
3021
3022
3023
3024
3025
3026
3027
3028
3029
3030
3031
3032
3033
3034
3035
3036
3037
3038
3039
3040
3041
3042
3043
3044
3045
3046
3047
3048
3049
3050
3051
3052
3053
3054
3055
3056
3057
3058
3059
3060
3061
3062
3063
3064
3065
3066
3067
3068
3069
3070
3071
3072
3073
3074
3075
3076
3077
3078
3079
3080
3081
3082
3083
3084
3085
3086
3087
3088
3089
3090
3091
3092
3093
3094
3095
3096
3097
3098
3099
3100
3101
3102
3103
3104
3105
3106
3107
3108
3109
3110
3111
3112
3113
3114
3115
3116
3117
3118
3119
3120
3121
3122
3123
3124
3125
3126
3127
3128
3129
3130
3131
3132
3133
3134
3135
3136
3137
3138
3139
3140
3141
3142
3143
3144
3145
3146
3147
3148
3149
3150
3151
3152
3153
3154
3155
3156
3157
3158
3159
3160
3161
3162
3163
3164
3165
3166
3167
3168
3169
3170
3171
3172
3173
3174
3175
3176
3177
3178
3179
3180
3181
3182
3183
3184
3185
3186
3187
3188
3189
3190
3191
3192
3193
3194
3195
3196
3197
3198
3199
3200
3201
3202
3203
3204
3205
3206
3207
3208
3209
3210
3211
3212
3213
3214
3215
3216
3217
3218
3219
3220
3221
3222
3223
3224
3225
3226
3227
3228
3229
3230
3231
3232
3233
3234
3235
3236
3237
3238
3239
3240
3241
3242
3243
3244
3245
3246
3247
3248
3249
3250
3251
3252
3253
3254
3255
3256
3257
3258
3259
3260
3261
3262
3263
3264
3265
3266
3267
3268
3269
3270
3271
3272
3273
3274
3275
3276
3277
3278
3279
3280
3281
3282
3283
3284
3285
3286
3287
3288
3289
3290
3291
3292
3293
3294
3295
3296
3297
3298
3299
3300
3301
3302
3303
3304
3305
3306
3307
3308
3309
3310
3311
3312
3313
3314
3315
3316
3317
3318
3319
3320
3321
3322
3323
3324
3325
3326
3327
3328
3329
3330
3331
3332
3333
3334
3335
3336
3337
3338
3339
3340
3341
3342
3343
3344
3345
3346
3347
3348
3349
3350
3351
3352
3353
3354
3355
3356
3357
3358
3359
3360
3361
3362
3363
3364
3365
3366
3367
3368
3369
3370
3371
3372
3373
3374
3375
3376
3377
3378
3379
3380
3381
3382
3383
3384
3385
3386
3387
3388
3389
3390
3391
3392
3393
3394
3395
3396
3397
3398
3399
3400
3401
3402
3403
3404
3405
3406
3407
3408
3409
3410
3411
3412
3413
3414
3415
3416
3417
3418
3419
3420
3421
3422
3423
3424
3425
3426
3427
3428
3429
3430
3431
3432
3433
3434
3435
3436
3437
3438
3439
3440
3441
3442
3443
3444
3445
3446
3447
3448
3449
3450
3451
3452
3453
3454
3455
3456
3457
3458
3459
3460
3461
3462
3463
3464
3465
3466
3467
3468
3469
3470
3471
3472
3473
3474
3475
3476
3477
3478
3479
3480
3481
3482
3483
3484
3485
3486
3487
3488
3489
3490
3491
3492
3493
3494
3495
3496
3497
3498
3499
3500
3501
3502
3503
3504
3505
3506
3507
3508
3509
3510
3511
3512
3513
3514
3515
3516
3517
3518
3519
3520
3521
3522
3523
3524
3525
3526
3527
3528
3529
3530
3531
3532
3533
3534
3535
3536
3537
3538
3539
3540
3541
3542
3543
3544
3545
3546
3547
3548
3549
3550
3551
3552
3553
3554
3555
3556
3557
3558
3559
3560
3561
3562
3563
3564
3565
3566
3567
3568
3569
3570
3571
3572
3573
3574
3575
3576
3577
3578
3579
3580
3581
3582
3583
3584
3585
3586
3587
3588
3589
3590
3591
3592
3593
3594
3595
3596
3597
3598
3599
3600
3601
3602
3603
3604
3605
3606
3607
3608
3609
3610
3611
3612
3613
3614
3615
3616
3617
3618
3619
3620
3621
3622
3623
3624
3625
3626
3627
3628
3629
3630
3631
3632
3633
3634
3635
3636
3637
3638
3639
3640
3641
3642
3643
3644
3645
3646
3647
3648
3649
3650
3651
3652
3653
3654
3655
3656
3657
3658
3659
3660
3661
3662
3663
3664
3665
3666
3667
3668
3669
3670
3671
3672
3673
3674
3675
3676
3677
3678
3679
3680
3681
3682
3683
3684
3685
3686
3687
3688
3689
3690
3691
3692
3693
3694
3695
3696
3697
3698
3699
3700
3701
3702
3703
3704
3705
3706
3707
3708
3709
3710
3711
3712
3713
3714
3715
3716
3717
3718
3719
3720
3721
3722
3723
3724
3725
3726
3727
3728
3729
3730
3731
3732
3733
3734
3735
3736
3737
3738
3739
3740
3741
3742
3743
3744
3745
3746
3747
3748
3749
3750
3751
3752
3753
3754
3755
3756
3757
3758
3759
3760
3761
3762
3763
3764
3765
3766
3767
3768
3769
3770
3771
3772
3773
3774
3775
3776
3777
3778
3779
3780
3781
3782
3783
3784
3785
3786
3787
3788
3789
3790
3791
3792
3793
3794
3795
3796
3797
3798
3799
3800
3801
3802
3803
3804
3805
3806
3807
3808
3809
3810
3811
3812
3813
3814
3815
3816
3817
3818
3819
3820
3821
3822
3823
3824
3825
3826
3827
3828
3829
3830
3831
3832
3833
3834
3835
3836
3837
3838
3839
3840
3841
3842
3843
3844
3845
3846
3847
3848
3849
3850
3851
3852
3853
3854
3855
3856
3857
3858
3859
3860
3861
3862
3863
3864
3865
3866
3867
3868
3869
3870
3871
3872
3873
3874
3875
3876
3877
3878
3879
3880
3881
3882
3883
3884
3885
3886
3887
3888
3889
3890
3891
3892
3893
3894
3895
3896
3897
3898
3899
3900
3901
3902
3903
3904
3905
3906
3907
3908
3909
3910
3911
3912
3913
3914
3915
3916
3917
3918
3919
3920
3921
3922
3923
3924
3925
3926
3927
3928
3929
3930
3931
3932
3933
3934
3935
3936
3937
3938
3939
3940
3941
3942
3943
3944
3945
3946
3947
3948
3949
3950
3951
3952
3953
3954
3955
3956
3957
3958
3959
3960
3961
3962
3963
3964
3965
3966
3967
3968
3969
3970
3971
3972
3973
3974
3975
3976
3977
3978
3979
3980
3981
3982
3983
3984
3985
3986
3987
3988
3989
3990
3991
3992
3993
3994
3995
3996
3997
3998
3999
4000
4001
4002
4003
4004
4005
4006
4007
4008
4009
4010
4011
4012
4013
4014
4015
4016
4017
4018
4019
4020
4021
4022
4023
4024
4025
4026
4027
4028
4029
4030
4031
4032
4033
4034
4035
4036
4037
4038
4039
4040
4041
4042
4043
4044
4045
4046
4047
4048
4049
4050
4051
4052
4053
4054
4055
4056
4057
4058
4059
4060
4061
4062
4063
4064
4065
4066
4067
4068
4069
4070
4071
4072
4073
4074
4075
4076
4077
4078
4079
4080
4081
4082
4083
4084
4085
4086
4087
4088
4089
4090
4091
4092
4093
4094
4095
4096
4097
4098
4099
4100
4101
4102
4103
4104
4105
4106
4107
4108
4109
4110
4111
4112
4113
4114
4115
4116
4117
4118
4119
4120
4121
4122
4123
4124
4125
4126
4127
4128
4129
4130
4131
4132
4133
4134
4135
4136
4137
4138
4139
4140
4141
4142
4143
4144
4145
4146
4147
4148
4149
4150
4151
4152
4153
4154
4155
4156
4157
4158
4159
4160
4161
4162
4163
4164
4165
4166
4167
4168
4169
4170
4171
4172
4173
4174
4175
4176
4177
4178
4179
4180
4181
4182
4183
4184
4185
4186
4187
4188
4189
4190
4191
4192
4193
4194
4195
4196
4197
4198
4199
4200
4201
4202
4203
4204
4205
4206
4207
4208
4209
4210
4211
4212
4213
4214
4215
4216
4217
4218
4219
4220
4221
4222
4223
4224
4225
4226
4227
4228
4229
4230
4231
4232
4233
4234
4235
4236
4237
4238
4239
4240
4241
4242
4243
4244
4245
4246
4247
4248
4249
4250
4251
4252
4253
4254
4255
4256
4257
4258
4259
4260
4261
4262
4263
4264
4265
4266
4267
4268
4269
4270
4271
4272
4273
4274
4275
4276
4277
4278
4279
4280
4281
4282
4283
4284
4285
4286
4287
4288
4289
4290
4291
4292
4293
4294
4295
4296
4297
4298
4299
4300
4301
4302
4303
4304
4305
4306
4307
4308
4309
4310
4311
4312
4313
4314
4315
4316
4317
4318
4319
4320
4321
4322
4323
4324
4325
4326
4327
4328
4329
4330
4331
4332
4333
4334
4335
4336
4337
4338
4339
4340
4341
4342
4343
4344
4345
4346
4347
4348
4349
4350
4351
4352
4353
4354
4355
4356
4357
4358
4359
4360
4361
4362
4363
4364
4365
4366
4367
4368
4369
4370
4371
4372
4373
4374
4375
4376
4377
4378
4379
4380
4381
4382
4383
4384
4385
4386
4387
4388
4389
4390
4391
4392
4393
4394
4395
4396
4397
4398
4399
4400
4401
4402
4403
4404
4405
4406
4407
4408
4409
4410
4411
4412
4413
4414
4415
4416
4417
4418
4419
4420
4421
4422
4423
4424
4425
4426
4427
4428
4429
4430
4431
4432
4433
4434
4435
4436
4437
4438
4439
4440
4441
4442
4443
4444
4445
4446
4447
4448
4449
4450
4451
4452
4453
4454
4455
4456
4457
4458
4459
4460
4461
4462
4463
4464
4465
4466
4467
4468
4469
4470
4471
4472
4473
4474
4475
4476
4477
4478
4479
4480
4481
4482
4483
4484
4485
4486
4487
4488
4489
4490
4491
4492
4493
4494
4495
4496
4497
4498
4499
4500
4501
4502
4503
4504
4505
4506
4507
4508
4509
4510
4511
4512
4513
4514
4515
4516
4517
4518
4519
4520
4521
4522
4523
4524
4525
4526
4527
4528
4529
4530
4531
4532
4533
4534
4535
4536
4537
4538
4539
4540
4541
4542
4543
4544
4545
4546
4547
4548
4549
4550
4551
4552
4553
4554
4555
4556
4557
4558
4559
4560
4561
4562
4563
4564
4565
4566
4567
4568
4569
4570
4571
4572
4573
4574
4575
4576
4577
4578
4579
4580
4581
4582
4583
4584
4585
4586
4587
4588
4589
4590
4591
4592
4593
4594
4595
4596
4597
4598
4599
4600
4601
4602
4603
4604
4605
4606
4607
4608
4609
4610
4611
4612
4613
4614
4615
4616
4617
4618
4619
4620
4621
4622
4623
4624
4625
4626
4627
4628
4629
4630
4631
4632
4633
4634
4635
4636
4637
4638
4639
4640
4641
4642
4643
4644
4645
4646
4647
4648
4649
4650
4651
4652
4653
4654
4655
4656
4657
4658
4659
4660
4661
4662
4663
4664
4665
4666
4667
4668
4669
4670
4671
4672
4673
4674
4675
4676
4677
4678
4679
4680
4681
4682
4683
4684
4685
4686
4687
4688
4689
4690
4691
4692
4693
4694
4695
4696
4697
4698
4699
4700
4701
4702
4703
4704
4705
4706
4707
4708
4709
4710
4711
4712
4713
4714
4715
4716
4717
4718
4719
4720
4721
4722
4723
4724
4725
4726
4727
4728
4729
4730
4731
4732
4733
4734
4735
4736
4737
4738
4739
4740
4741
4742
4743
4744
4745
4746
4747
4748
4749
4750
4751
4752
4753
4754
4755
4756
4757
4758
4759
4760
4761
4762
4763
4764
4765
4766
4767
4768
4769
4770
4771
4772
4773
4774
4775
4776
4777
4778
4779
4780
4781
4782
4783
4784
4785
4786
4787
4788
4789
4790
4791
4792
4793
4794
4795
4796
4797
4798
4799
4800
4801
4802
4803
4804
4805
4806
4807
4808
4809
4810
4811
4812
4813
4814
4815
4816
4817
4818
4819
4820
4821
4822
4823
4824
4825
4826
4827
4828
4829
4830
4831
4832
4833
4834
4835
4836
4837
4838
4839
4840
4841
4842
4843
4844
4845
4846
4847
4848
4849
4850
4851
4852
4853
4854
4855
4856
4857
4858
4859
4860
4861
4862
4863
4864
4865
4866
4867
4868
4869
4870
4871
4872
4873
4874
4875
4876
4877
4878
4879
4880
4881
4882
4883
4884
4885
4886
4887
4888
4889
4890
4891
4892
4893
4894
4895
4896
4897
4898
4899
4900
4901
4902
4903
4904
4905
4906
4907
4908
4909
4910
4911
4912
4913
4914
4915
4916
4917
4918
4919
4920
4921
4922
4923
4924
4925
4926
4927
4928
4929
4930
4931
4932
4933
4934
4935
4936
4937
4938
4939
4940
4941
4942
4943
4944
4945
4946
4947
4948
4949
4950
4951
4952
4953
4954
4955
4956
4957
4958
4959
4960
4961
4962
4963
4964
4965
4966
4967
4968
4969
4970
4971
4972
4973
4974
4975
4976
4977
4978
4979
4980
4981
4982
4983
4984
4985
4986
4987
4988
4989
4990
4991
4992
4993
4994
4995
4996
4997
4998
4999
5000
5001
5002
5003
5004
5005
5006
5007
5008
5009
5010
5011
5012
5013
5014
5015
5016
5017
5018
5019
5020
5021
5022
5023
5024
5025
5026
5027
5028
5029
5030
5031
5032
5033
5034
5035
5036
5037
5038
5039
5040
5041
5042
5043
5044
5045
5046
5047
5048
5049
5050
5051
5052
5053
5054
5055
5056
5057
5058
5059
5060
5061
5062
5063
5064
5065
5066
5067
5068
5069
5070
5071
5072
5073
5074
5075
5076
5077
5078
5079
5080
5081
5082
5083
5084
5085
5086
5087
5088
5089
5090
5091
5092
5093
5094
5095
5096
5097
5098
5099
5100
5101
5102
5103
5104
5105
5106
5107
5108
5109
5110
5111
5112
5113
5114
5115
5116
5117
5118
5119
5120
5121
5122
5123
5124
5125
5126
5127
5128
5129
5130
5131
5132
5133
5134
5135
5136
5137
5138
5139
5140
5141
5142
5143
5144
5145
5146
5147
5148
5149
5150
5151
5152
5153
5154
5155
5156
5157
5158
5159
5160
5161
5162
5163
5164
5165
5166
5167
5168
5169
5170
5171
5172
5173
5174
5175
5176
5177
5178
5179
5180
5181
5182
5183
5184
5185
5186
5187
5188
5189
5190
5191
5192
5193
5194
5195
5196
5197
5198
5199
5200
5201
5202
5203
5204
5205
5206
5207
5208
5209
5210
5211
5212
5213
5214
5215
5216
5217
5218
5219
5220
5221
5222
5223
5224
5225
5226
5227
5228
5229
5230
5231
5232
5233
5234
5235
5236
5237
5238
5239
5240
5241
5242
5243
5244
5245
5246
5247
5248
5249
5250
5251
5252
5253
5254
5255
5256
5257
5258
5259
5260
5261
5262
5263
5264
5265
5266
5267
5268
5269
5270
5271
5272
5273
5274
5275
5276
5277
5278
5279
5280
5281
5282
5283
5284
5285
5286
5287
5288
5289
5290
5291
5292
5293
5294
5295
5296
5297
5298
5299
5300
5301
5302
5303
5304
5305
5306
5307
5308
5309
5310
5311
5312
5313
5314
5315
5316
5317
5318
5319
5320
5321
5322
5323
5324
5325
5326
5327
5328
5329
5330
5331
5332
5333
5334
5335
5336
5337
5338
5339
5340
5341
5342
5343
5344
5345
5346
5347
5348
5349
5350
5351
5352
5353
5354
5355
5356
5357
5358
5359
5360
5361
5362
5363
5364
5365
5366
5367
5368
5369
5370
5371
5372
5373
5374
5375
5376
5377
5378
5379
5380
5381
5382
5383
5384
5385
5386
5387
5388
5389
5390
5391
5392
5393
5394
5395
5396
5397
5398
5399
5400
5401
5402
5403
5404
5405
5406
5407
5408
5409
5410
5411
5412
5413
5414
5415
5416
5417
5418
5419
5420
5421
5422
5423
5424
5425
5426
5427
5428
5429
5430
5431
5432
5433
5434
5435
5436
5437
5438
5439
5440
5441
5442
5443
5444
5445
5446
5447
5448
5449
5450
5451
5452
5453
5454
5455
5456
5457
5458
5459
5460
5461
5462
5463
5464
5465
5466
5467
5468
5469
5470
5471
5472
5473
5474
5475
5476
5477
5478
5479
5480
5481
5482
5483
5484
5485
5486
5487
5488
5489
5490
5491
5492
5493
5494
5495
5496
5497
5498
5499
5500
5501
5502
5503
5504
5505
5506
5507
5508
5509
5510
5511
5512
5513
5514
5515
5516
5517
5518
5519
5520
5521
5522
5523
5524
5525
5526
5527
5528
5529
5530
5531
5532
5533
5534
5535
5536
5537
5538
5539
5540
5541
5542
5543
5544
5545
5546
5547
5548
5549
5550
5551
5552
5553
5554
5555
5556
5557
5558
5559
5560
5561
5562
5563
5564
5565
5566
5567
5568
5569
5570
5571
5572
5573
5574
5575
5576
5577
5578
5579
5580
5581
5582
5583
5584
5585
5586
5587
5588
5589
5590
5591
5592
5593
5594
5595
5596
5597
5598
5599
5600
5601
5602
5603
5604
5605
5606
5607
5608
5609
5610
5611
5612
5613
5614
5615
5616
5617
5618
5619
5620
5621
5622
5623
5624
5625
5626
5627
5628
5629
5630
5631
5632
5633
5634
5635
5636
5637
5638
5639
5640
5641
5642
5643
5644
5645
5646
5647
5648
5649
5650
5651
5652
5653
5654
5655
5656
5657
5658
5659
5660
5661
5662
5663
5664
5665
5666
5667
5668
5669
5670
5671
5672
5673
5674
5675
5676
5677
5678
5679
5680
5681
5682
5683
5684
5685
5686
5687
5688
5689
5690
5691
5692
5693
5694
5695
5696
5697
5698
5699
5700
5701
5702
5703
5704
5705
5706
5707
5708
5709
5710
5711
5712
5713
5714
5715
5716
5717
5718
5719
5720
5721
5722
5723
5724
5725
5726
5727
5728
5729
5730
5731
5732
5733
5734
5735
5736
5737
5738
5739
5740
5741
5742
5743
5744
5745
5746
5747
5748
5749
5750
5751
5752
5753
5754
5755
5756
5757
5758
5759
5760
5761
5762
5763
5764
5765
5766
5767
5768
5769
5770
5771
5772
5773
5774
5775
5776
5777
5778
5779
5780
5781
5782
5783
5784
5785
5786
5787
5788
5789
5790
5791
5792
5793
5794
5795
5796
5797
5798
5799
5800
5801
5802
5803
5804
5805
5806
5807
5808
5809
5810
5811
5812
5813
5814
5815
5816
5817
5818
5819
5820
5821
5822
5823
5824
5825
5826
5827
5828
5829
5830
5831
5832
5833
5834
5835
5836
5837
5838
5839
5840
5841
5842
5843
5844
5845
5846
5847
5848
5849
5850
5851
5852
5853
5854
5855
5856
5857
5858
5859
5860
5861
5862
5863
5864
5865
5866
5867
5868
5869
5870
5871
5872
5873
5874
5875
5876
5877
5878
5879
5880
5881
5882
5883
5884
5885
5886
5887
5888
5889
5890
5891
5892
5893
5894
5895
5896
5897
5898
5899
5900
5901
5902
5903
5904
5905
5906
5907
5908
5909
5910
5911
5912
5913
5914
5915
5916
5917
5918
5919
5920
5921
5922
5923
5924
5925
5926
5927
5928
5929
5930
5931
5932
5933
5934
5935
5936
5937
5938
5939
5940
5941
5942
5943
5944
5945
5946
5947
5948
5949
5950
5951
5952
5953
5954
5955
5956
5957
5958
5959
5960
5961
5962
5963
5964
5965
5966
5967
5968
5969
5970
5971
5972
5973
5974
5975
5976
5977
5978
5979
5980
5981
5982
5983
5984
5985
5986
5987
5988
5989
5990
5991
5992
5993
5994
5995
5996
5997
5998
5999
6000
6001
6002
6003
6004
6005
6006
6007
6008
6009
6010
6011
6012
6013
6014
6015
6016
6017
6018
6019
6020
6021
6022
6023
6024
6025
6026
6027
6028
6029
6030
6031
6032
6033
6034
6035
6036
6037
6038
6039
6040
6041
6042
6043
6044
6045
6046
6047
6048
6049
6050
6051
6052
6053
6054
6055
6056
6057
6058
6059
6060
6061
6062
6063
6064
6065
6066
6067
6068
6069
6070
6071
6072
6073
6074
6075
6076
6077
6078
6079
6080
6081
6082
6083
6084
6085
6086
6087
6088
6089
6090
6091
6092
6093
6094
6095
6096
6097
6098
6099
6100
6101
6102
6103
6104
6105
6106
6107
6108
6109
6110
6111
6112
6113
6114
6115
6116
6117
6118
6119
6120
6121
6122
6123
6124
6125
6126
6127
6128
6129
6130
6131
6132
6133
6134
6135
6136
6137
6138
6139
6140
6141
6142
6143
6144
6145
6146
6147
6148
6149
6150
6151
6152
6153
6154
6155
6156
6157
6158
6159
6160
6161
6162
6163
6164
6165
6166
6167
6168
6169
6170
6171
6172
6173
6174
6175
6176
6177
6178
6179
6180
6181
6182
6183
6184
6185
6186
6187
6188
6189
6190
6191
6192
6193
6194
6195
6196
6197
6198
6199
6200
6201
6202
6203
6204
6205
6206
6207
6208
6209
6210
6211
6212
6213
6214
6215
6216
6217
6218
6219
6220
6221
6222
6223
6224
6225
6226
6227
6228
6229
6230
6231
6232
6233
6234
6235
6236
6237
6238
6239
6240
6241
6242
6243
6244
6245
6246
6247
6248
6249
6250
6251
6252
6253
6254
6255
6256
6257
6258
6259
6260
6261
6262
6263
6264
6265
6266
6267
6268
6269
6270
6271
6272
6273
6274
6275
6276
6277
6278
6279
6280
6281
6282
6283
6284
6285
6286
6287
6288
6289
6290
6291
6292
6293
6294
6295
6296
6297
6298
6299
6300
6301
6302
6303
6304
6305
6306
6307
6308
6309
6310
6311
6312
6313
6314
6315
6316
6317
6318
6319
6320
6321
6322
6323
6324
6325
6326
6327
6328
6329
6330
6331
6332
6333
6334
6335
6336
6337
6338
6339
6340
6341
6342
6343
6344
6345
6346
6347
6348
6349
6350
6351
6352
6353
6354
6355
6356
6357
6358
6359
6360
6361
6362
6363
6364
6365
6366
6367
6368
6369
6370
6371
6372
6373
6374
6375
6376
6377
6378
6379
6380
6381
6382
6383
6384
6385
6386
6387
6388
6389
6390
6391
6392
6393
6394
6395
6396
6397
6398
6399
6400
6401
6402
6403
6404
6405
6406
6407
6408
6409
6410
6411
6412
6413
6414
6415
6416
6417
6418
6419
6420
6421
6422
6423
6424
6425
6426
6427
6428
6429
6430
6431
6432
6433
6434
6435
6436
6437
6438
6439
6440
6441
6442
6443
6444
6445
6446
6447
6448
6449
6450
6451
6452
6453
6454
6455
6456
6457
6458
6459
6460
6461
6462
6463
6464
6465
6466
6467
6468
6469
6470
6471
6472
6473
6474
6475
6476
6477
6478
6479
6480
6481
6482
6483
6484
6485
6486
6487
6488
6489
6490
6491
6492
6493
6494
6495
6496
6497
6498
6499
6500
6501
6502
6503
6504
6505
6506
6507
6508
6509
6510
6511
6512
6513
6514
6515
6516
6517
6518
6519
6520
6521
6522
6523
6524
6525
6526
6527
6528
6529
6530
6531
6532
6533
6534
6535
6536
6537
6538
6539
6540
6541
6542
6543
6544
6545
6546
6547
6548
6549
6550
6551
6552
6553
6554
6555
6556
6557
6558
6559
6560
6561
6562
6563
6564
6565
6566
6567
6568
6569
6570
6571
6572
6573
6574
6575
6576
6577
6578
6579
6580
6581
6582
6583
6584
6585
6586
6587
6588
6589
6590
6591
6592
6593
6594
6595
6596
6597
6598
6599
6600
6601
6602
6603
6604
6605
6606
6607
6608
6609
6610
6611
6612
6613
6614
6615
6616
6617
6618
6619
6620
6621
6622
6623
6624
6625
6626
6627
6628
6629
6630
6631
6632
6633
6634
6635
6636
6637
6638
6639
6640
6641
6642
6643
6644
6645
6646
6647
6648
6649
6650
6651
6652
6653
6654
6655
6656
6657
6658
6659
6660
6661
6662
6663
6664
6665
6666
6667
6668
6669
6670
6671
6672
6673
6674
6675
6676
6677
6678
6679
6680
6681
6682
6683
6684
6685
6686
6687
6688
6689
6690
6691
6692
6693
6694
6695
6696
6697
6698
6699
6700
6701
6702
6703
6704
6705
6706
6707
6708
6709
6710
6711
6712
6713
6714
6715
6716
6717
6718
6719
6720
6721
6722
6723
6724
6725
6726
6727
6728
6729
6730
6731
6732
6733
6734
6735
6736
6737
6738
6739
6740
6741
6742
6743
6744
6745
6746
6747
6748
6749
6750
6751
6752
6753
6754
6755
6756
6757
6758
6759
6760
6761
6762
6763
6764
6765
6766
6767
6768
6769
6770
6771
6772
6773
6774
6775
6776
6777
6778
6779
6780
6781
6782
6783
6784
6785
6786
6787
6788
6789
6790
6791
6792
6793
6794
6795
6796
6797
6798
6799
6800
6801
6802
6803
6804
6805
6806
6807
6808
6809
6810
6811
6812
6813
6814
6815
6816
6817
6818
6819
6820
6821
6822
6823
6824
6825
6826
6827
6828
6829
6830
6831
6832
6833
6834
6835
6836
6837
6838
6839
6840
6841
6842
6843
6844
6845
6846
6847
6848
6849
6850
6851
6852
6853
6854
6855
6856
6857
6858
6859
6860
6861
6862
6863
6864
6865
6866
6867
6868
6869
6870
6871
6872
6873
6874
6875
6876
6877
6878
6879
6880
6881
6882
6883
6884
6885
6886
6887
6888
6889
6890
6891
6892
6893
6894
6895
6896
6897
6898
6899
6900
6901
6902
6903
6904
6905
6906
6907
6908
6909
6910
6911
6912
6913
6914
6915
6916
6917
6918
6919
6920
6921
6922
6923
6924
6925
6926
6927
6928
6929
6930
6931
6932
6933
6934
6935
6936
6937
6938
6939
6940
6941
6942
6943
6944
6945
6946
6947
6948
6949
6950
6951
6952
6953
6954
6955
6956
6957
6958
6959
6960
6961
6962
6963
6964
6965
6966
6967
6968
6969
6970
6971
6972
6973
6974
6975
6976
6977
6978
6979
6980
6981
6982
6983
6984
6985
6986
6987
6988
6989
6990
6991
6992
6993
6994
6995
6996
6997
6998
6999
7000
7001
7002
7003
7004
7005
7006
7007
7008
7009
7010
7011
7012
7013
7014
7015
7016
7017
7018
7019
7020
7021
7022
7023
7024
7025
7026
7027
7028
7029
7030
7031
7032
7033
7034
7035
7036
7037
7038
7039
7040
7041
7042
7043
7044
7045
7046
7047
7048
7049
7050
7051
7052
7053
7054
7055
7056
7057
7058
7059
7060
7061
7062
7063
7064
7065
7066
7067
7068
7069
7070
7071
7072
7073
7074
7075
7076
7077
7078
7079
7080
7081
7082
7083
7084
7085
7086
7087
7088
7089
7090
7091
7092
7093
7094
7095
7096
7097
7098
7099
7100
7101
7102
7103
7104
7105
7106
7107
7108
7109
7110
7111
7112
7113
7114
7115
7116
7117
7118
7119
7120
7121
7122
7123
7124
7125
7126
7127
7128
7129
7130
7131
7132
7133
7134
7135
7136
7137
7138
7139
7140
7141
7142
7143
7144
7145
7146
7147
7148
7149
7150
7151
7152
7153
7154
7155
7156
7157
7158
7159
7160
7161
7162
7163
7164
7165
7166
7167
7168
7169
7170
7171
7172
7173
7174
7175
7176
7177
7178
7179
7180
7181
7182
7183
7184
7185
7186
7187
7188
7189
7190
7191
7192
7193
7194
7195
7196
7197
7198
7199
7200
7201
7202
7203
7204
7205
7206
7207
7208
7209
7210
7211
7212
7213
7214
7215
7216
7217
7218
7219
7220
7221
7222
7223
7224
7225
7226
7227
7228
7229
7230
7231
7232
7233
7234
7235
7236
7237
7238
7239
7240
7241
7242
7243
7244
7245
7246
7247
7248
7249
7250
7251
7252
7253
7254
7255
7256
7257
7258
7259
7260
7261
7262
7263
7264
7265
7266
7267
7268
7269
7270
7271
7272
7273
7274
7275
7276
7277
7278
7279
7280
7281
7282
7283
7284
7285
7286
7287
7288
7289
7290
7291
7292
7293
7294
7295
7296
7297
7298
7299
7300
7301
7302
7303
7304
7305
7306
7307
7308
7309
7310
7311
7312
7313
7314
7315
7316
7317
7318
7319
7320
7321
7322
7323
7324
7325
7326
7327
7328
7329
7330
7331
7332
7333
7334
7335
7336
7337
7338
7339
7340
7341
7342
7343
7344
7345
7346
7347
7348
7349
7350
7351
7352
7353
7354
7355
7356
7357
7358
7359
7360
7361
7362
7363
7364
7365
7366
7367
7368
7369
7370
7371
7372
7373
7374
7375
7376
7377
7378
7379
7380
7381
7382
7383
7384
7385
7386
7387
7388
7389
7390
7391
7392
7393
7394
7395
7396
7397
7398
7399
7400
7401
7402
7403
7404
7405
7406
7407
7408
7409
7410
7411
7412
7413
7414
7415
7416
7417
7418
7419
7420
7421
7422
7423
7424
7425
7426
7427
7428
7429
7430
7431
7432
7433
7434
7435
7436
7437
7438
7439
7440
7441
7442
7443
7444
7445
7446
7447
7448
7449
7450
7451
7452
7453
7454
7455
7456
7457
7458
7459
7460
7461
7462
7463
7464
7465
7466
7467
7468
7469
7470
7471
7472
7473
7474
7475
7476
7477
7478
7479
7480
7481
7482
7483
7484
7485
7486
7487
7488
7489
7490
7491
7492
7493
7494
7495
7496
7497
7498
7499
7500
7501
7502
7503
7504
7505
7506
7507
7508
7509
7510
7511
7512
7513
7514
7515
7516
7517
7518
7519
7520
7521
7522
7523
7524
7525
7526
7527
7528
7529
7530
7531
7532
7533
7534
7535
7536
7537
7538
7539
7540
7541
7542
7543
7544
7545
7546
7547
7548
7549
7550
7551
7552
7553
7554
7555
7556
7557
7558
7559
7560
7561
7562
7563
7564
7565
7566
7567
7568
7569
7570
7571
7572
7573
7574
7575
7576
7577
7578
7579
7580
7581
7582
7583
7584
7585
7586
7587
7588
7589
7590
7591



NOTE: DEED INFORMATION MISSING ON PARCELS MARKED WITH ASTERISKS.

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BYRES	AREA OF TAKING
262-C-LA	ALLEN J. STUMP VIOLA V. STUMP	2-S. FR.	10×18 FR.		5,427
262-D-LA	LOUIS H. MAUSER	2-S. FR.	10×20 FR.	12×16 SHED	5,720
262-E-LA	EDWARD VELAR	2-S. FR.			6,000
262-F-LA	TUFIC SAADI	2-S. FR.	12×18 FR.		6,889
262-H-LA	LAURA GARDNER	2-S. FR.	12×20 FR.		3,580
262-J-LA	GEORGE SUBER PEARL SUBER	2-S. FR.	20×18 FR.		306
263-LA	UMBERTO TURSINI ANNA TURSINI	2-S. STUCCO			2,530
264-LA	WILLIAM MOSKOSKY HELEN MOSKOSKY				48,620
265-LA	ALTON L. KEMP ALICE L. KEMP	2-S. STUCCO			11,109
265-A-LA	MARY LUNDY	2-S. STUCCO			7,511
265-B-LA	FRANK J COLLA	2-S. STUCCO			7,508
266-LA	JAMES LADIGO	2-S. STUCCO			7,462
266-B-LA	JOSEPH M. ALLISON MARIAN A. ALLISON	2-S. STUCCO			7,459

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BYRES	AREA OF TAKING
266-C-LA	THOMAS HOOD	2-S. STUCCO			
267-LA	BESSIE P CONNELL THOMAS H. CONNELL			18×17 ST. HSE	68,502
267-A-LA	ESTHER MEYER				1,262
267-B-LA	VANCE WAGNER	2-S. FR.			1,826
* 267-C-LA					690
* 267-D-LA	MINNIE MAUSER	2-S. FR.	10×20 FR.	12×16 SHED	1,000
* 267-E-LA					3,855
268-LA	BESSIE P CONNELL THOMAS H. CONNELL				5,202
* 268-A-LA	*BESSIE P. CONNELL* *THOMAS H. CONNELL*				278
269-LA	INEZ PARKER	2-S. FR.	10×18 FR.		4,200
271-LA	HARRY & NELLIE MEYERS	2-S. FR.			2,400
271-A-LA	*GOLDEN AGE BEVERAGE CORP.*				1,050
* 271-B-LA	YOUNGSTOWN FURNACE CO.				

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BYRES	AREA OF TAKING
272-LA	MALACHI STOKES THELMA STOKES	2-S. FR.	12×18 BR.		3,702
273-LA	JOHN G. SPATHOLT	2-S. FR.			1,800
274-LA	JOHN H. LOGAN LULA LOGAN	2-S. FR.			2,230
275-LA	LEROY SMITH NETTIE SMITH	2-S. FR.			1,625
275-A-LA	JOHNNIE PEARL REED	2-S. FR.			1,587
276-LA	FRED & ROISE PERKINS	2-S. FR.			1,932
277-LA	THEODORE COTTON JR. CARRIE COTTON	2-2 ST. B.R.			1,813
279-LA	ANN KAUFMAN BETTY LABEL	2-2 ST. FR.			4,950
280-LA	GOLDEN AGE BEVERAGE CORP.			72×125 C.B.	19,657
283-B-LA	HOWARD BURKES MILLERNEE BURKES	1½-S. FR.			2,600
289-LA	BESSIE P. CONNELL THOMAS H. CONNELL				3,600
* 289-A-LA	WALDEMAR NISCHWITZ EARL H. HARRIS	2-S. FR.			1,157
290-LA	ETHEL McDANIELS SPEAKS	1-S. FR.		12×18 SHED	2,948

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	BYRES	AREA OF TAKING
291-LA	ELIZABETH BUEHRLE				2,282
292-LA	WALDEMAR NISCHWITZ EARL H. HARRIS	2-S. FR. 1-S. FR.	14×22 C.B.		5,939
294-LA	WILLIAM ALLEN ANNIE ALLEN	2-S. FR. 2-S. FR.			3,943
295-LA	MARY PEAY	2-S. FR.		8×6 FR. SHED	4,180
296-LA	ELIDA MOELLERING	2-S. FR.			4,350
273-A-LA	JOHN G. SPATHOLT	2-S. FR.			2,080
273-B-LA	JOHN G. SPATHOLT	2-S. FR.			1,870
273-C-LA	JOHN G. SPATHOLT	2-S. FR.			3,150
276-A-LA	*FRED AND ROISE PERKINS ETAL*				767

WORK AGREEMENT


PARCEL NO.	NAME	DESCRIPTION
262-H-WA	LAURA GARDNER	REMOVE GAR. FD'N.
271-WA	HARRY & NELLIE MEYERS	FILL BASEMENT
283-B-WA	HOWARD BURKES MILLERNEE BURKES	FILL BASEMENT
267-D-WA	MINNIE MAUSER	FILL BASEMENT
262-F-WA	TUFIC SAADI	FILL BASEMENT
262-C-WA	ALLEN J. STUMP VIOLA V. STUMP	REMOVE GAR. FD'N.

REVISIONS

REV. NO.	NATURE OF REVISION	DATE COMP DATE	MADE BY
# 1	ADDED RET. WALL & BARRICADE	12-30-59	J.E.P.
	REVISED ℄ ALINE FOR RET. WALL		
# 2	ADDED R.	3-29-60	J.D.P.
	Added Names Pcls. 271-A-LA & 276-A-LA Area	7-6-60	S.S.
	Pcls. 268-A-LA & 268-LA Added Name & Area	7-6-60	S.S.


FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	


481
492


BEGIN SHEET — STA. 1000+00
END SHEET — STA. 1010+00
55-18 1853 L.F. TYPE "C" FENCE
551 L.F. TYPE "C" FENCE
591 L.F. TYPE "C" FENCE
422 L.F. TYPE "C" FENCE
288 L.F. TYPE "C" FENCE
WALTER STREET
HIGH STREET
PIKE
OAK HILL AVE.
FILLING STATION
CHURCH
SCRUB
TIMBER
PARKING AREA
PARKING AREA
RETAINING WALL
WALL
WALL
L.A. LIMIT
S. 5° 54' 34" E.
N.
1548
1549
1550
1551
1552
1553
1568
1569
5621
43581
842
843
844
839
838
849
853
854
852
851
850
2240
2239
2238
2237
2242
2241
2243
2245
1575
1007
1008
1009
1010
1011
1012
1013
1014
1015
1016
1017
1018
1019
1020
1021
1022
1023
1024
1025
1026
1027
1028
1029
1030
1031
1032
1033
1034
1035
1036
1037
1038
1039
1040
1041
1042
1043
1044
1045
1046
1047
1048
1049
1050
1051
1052
1053
1054
1055
1056
1057
1058
1059
1060
1061
1062
1063
1064
1065
1066
1067
1068
1069
1070
1071
1072
1073
1074
1075
1076
1077
1078
1079
1080
1081
1082
1083
1084
1085
1086
1087
1088
1089
1090
1091
1092
1093
1094
1095
1096
1097
1098
1099
1100
1101
1102
1103
1104
1105
1106
1107
1108
1109
1110
1111
1112
1113
1114
1115
1116
1117
1118
1119
1120
1121
1122
1123
1124
1125
1126
1127
1128
1129
1130
1131
1132
1133
1134
1135
1136
1137
1138
1139
1140
1141
1142
1143
1144
1145
1146
1147
1148
1149
1150
1151
1152
1153
1154
1155
1156
1157
1158
1159
1160
1161
1162
1163
1164
1165
1166
1167
1168
1169
1170
1171
1172
1173
1174
1175
1176
1177
1178
1179
1180
1181
1182
1183
1184
1185
1186
1187
1188
1189
1190
1191
1192
1193
1194
1195
1196
1197
1198
1199
1200
1201
1202
1203
1204
1205
1206
1207
1208
1209
1210
1211
1212
1213
1214
1215
1216
1217
1218
1219
1220
1221
1222
1223
1224
1225
1226
1227
1228
1229
1230
1231
1232
1233
1234
1235
1236
1237
1238
1239
1240
1241
1242
1243
1244
1245
1246
1247
1248
1249
1250
1251
1252
1253
1254
1255
1256
1257
1258
1259
1260
1261
1262
1263
1264
1265
1266
1267
1268
1269
1270
1271
1272
1273
1274
1275
1276
1277
1278
1279
1280
1281
1282
1283
1284
1285
1286
1287
1288
1289
1290
1291
1292
1293
1294
1295
1296
1297
1298
1299
1300
1301
1302
1303
1304
1305
1306
1307
1308
1309
1310
1311
1312
1313
1314
1315
1316
1317
1318
1319
1320
1321
1322
1323
1324
1325
1326
1327
1328
1329
1330
1331
1332
1333
1334
1335
1336
1337
1338
1339
1340
1341
1342
1343
1344
1345
1346
1347
1348
1349
1350
1351
1352
1353
1354
1355
1356
1357
1358
1359
1360
1361
1362
1363
1364
1365
1366
1367
1368
1369
1370
1371
1372
1373
1374
1375
1376
1377
1378
1379
1380
1381
1382
1383
1384
1385
1386
1387
1388
1389
1390
1391
1392
1393
1394
1395
1396
1397
1398
1399
1400
1401
1402
1403
1404
1405
1406
1407
1408
1409
1410
1411
1412
1413
1414
1415
1416
1417
1418
1419
1420
1421
1422
1423
1424
1425
1426
1427
1428
1429
1430
1431
1432
1433
1434
1435
1436
1437
1438
1439
1440
1441
1442
1443
1444
1445
1446
1447
1448
1449
1450
1451
1452
1453
1454
1455
1456
1457
1458
1459
1460
1461
1462
1463
1464
1465
1466
1467
1468
1469
1470
1471
1472
1473
1474
1475
1476
1477
1478
1479
1480
1481
1482
1483
1484
1485
1486
1487
1488
1489
1490
1491
1492
1493
1494
1495
1496
1497
1498
1499
1500
1501
1502
1503
1504
1505
1506
1507
1508
1509
1510
1511
1512
1513
1514
1515
1516
1517
1518
1519
1520
1521
1522
1523
1524
1525
1526
1527
1528
1529
1530
1531
1532
1533
1534
1535
1536
1537
1538
1539
1540
1541
1542
1543
1544
1545
1546
1547
1548
1549
1550
1551
1552
1553
1554
1555
1556
1557
1558
1559
1560
1561
1562
1563
1564
1565
1566
1567
1568
1569
1570
1571
1572
1573
1574
1575
1576
1577
1578
1579
1580
1581
1582
1583
1584
1585
1586
1587
1588
1589
1590
1591
1592
1593
1594
1595
1596
1597
1598
1599
1600
1601
1602
1603
1604
1605
1606
1607
1608
1609
1610
1611
1612
1613
1614
1615
1616
1617
1618
1619
1620
1621
1622
1623
1624
1625
1626
1627
1628
1629
1630
1631
1632
1633
1634
1635
1636
1637
1638
1639
1640
1641
1642
1643
1644
1645
1646
1647
1648
1649
1650
1651
1652
1653
1654
1655
1656
1657
1658
1659
1660
1661
1662
1663
1664
1665
1666
1667
1668
1669
1670
1671
1672
1673
1674
1675
1676
1677
1678
1679
1680
1681
1682
1683
1684
1685
1686
1687
1688
1689
1690
1691
1692
1693
1694
1695
1696
1697
1698
1699
1700
1701
1702
1703
1704
1705
1706
1707
1708
1709
1710
1711
1712
1713
1714
1715
1716
1717
1718
1719
1720
1721
1722
1723
1724
1725
1726
1727
1728
1729
1730
1731
1732
1733
1734
1735
1736
1737
1738
1739
1740
1741
1742
1743
1744
1745
1746
1747
1748
1749
1750
1751
1752
1753
1754
1755
1756
1757
1758
1759
1760
1761
1762
1763
1764
1765
1766
1767
1768
1769
1770
1771
1772
1773
1774
1775
1776
1777
1778
1779
1780
1781
1782
1783
1784
1785
1786
1787
1788
1789
1790
1791
1792
1793
1794
1795
1796
1797
1798
1799
1800
1801
1802
1803
1804
1805
1806
1807
1808
1809
1810
1811
1812
1813
1814
1815
1816
1817
1818
1819
1820
1821
1822
1823
1824
1825
1826
1827
1828
1829
1830
1831
1832
1833
1834
1835
1836
1837
1838
1839
1840
1841
1842
1843
1844
1845
1846
1847
1848
1849
1850
1851
1852
1853
1854
1855
1856
1857
1858
1859
1860
1861
1862
1863
1864
1865
1866
1867
1868
1869
1870
1871
1872
1873
1874
1875
1876
1877
1878
1879
1880
1881
1882
1883
1884
1885
1886
1887
1888
1889
1890
1891
1892
1893
1894
1895
1896
1897
1898
1899
1900
1901
1902
1903
1904
1905
1906
1907
1908
1909
1910
1911
1912
1913
1914
1915
1916
1917
1918
1919
1920
1921
1922
1923
1924
1925
1926
1927
1928
1929
1930
1931
1932
1933
1934
1935
1936
1937
1938
1939
1940
1941
1942
1943
1944
1945
1946
1947
1948
1949
1950
1951
1952
1953
1954
1955
1956
1957
1958
1959
1960
1961
1962
1963
1964
1965
1966
1967
1968
1969
1970
1971
1972
1973
1974
1975
1976
1977
1978
1979
1980
1981
1982
1983
1984
1985
1986
1987
1988
1989
1990
1991
1992
1993
1994
1995
1996
1997
1998
1999
2000
2001
2002
2003
2004
2005
2006
2007
2008
2009
2010
2011
2012
2013
2014
2015
2016
2017
2018
2019
2020
2021
2022
2023
2024
2025
2026
2027
2028
2029
2030
2031
2032
2033
2034
2035
2036
2037
2038
2039
2040
2041
2042
2043
2044
2045
2046
2047
2048
2049
2050
2051
2052
2053
2054
2055
2056
2057
2058
2059
2060
2061
2062
2063
2064
2065
2066
2067
2068
2069
2070
2071
2072
2073
2074
2075
2076
2077
2078
2079
2080
2081
2082
2083
2084
2085
2086
2087
2088
2089
2090
2091
2092
2093
2094
2095
2096
2097
2098
2099
2100
2101
2102
2103
2104
2105
2106
2107
2108
2109
2110
2111
2112
2113
2114
2115
2116
2117
2118
2119
2120
2121
2122
2123
2124
2125
2126
2127
2128
2129
2130
2131
2132
2133
2134
2135
2136
2137
2138
2139
2140
2141
2142
2143
2144
2145
2146
2147
2148
2149
2150
2151
2152
2153
2154
2155
2156
2157
2158
2159
2160
2161
2162
2163
2164
2165
2166
2167
2168
2169
2170
2171
2172
2173
2174
2175
2176
2177
2178
2179
2180
2181
2182
2183
2184
2185
2186
2187
2188
2189
2190
2191
2192
2193
2194
2195
2196
2197
2198
2199
2200
2201
2202
2203
2204
2205
2206
2207
2208
2209
2210
2211
2212
2213
2214
2215
2216
2217
2218
2219
2220
2221
2222
2223
2224
2225
2226
2227
2228
2229
2230
2231
2232
2233
2234
2235
2236
2237
2238
2239
2240
2241
2242
2243
2244
2245
2246
2247
2248
2249
2250
2251
2252
2253
2254
2255
2256
2257
2258
2259
2260
2261
2262
2263
2264
2265
2266
2267
2268
2269
2270
2271
2272
2273
2274
2275
2276
2277
2278
2279
2280
2281
2282
2283
2284
2285
2286
2287
2288
2289
2290
2291
2292
2293
2294
2295
2296
2297
2298
2299
2300
2301
2302
2303
2304
2305
2306
2307
2308
2309
2310
2311
2312
2313
2314
2315
2316
2317
2318
2319
2320
2321
2322
2323
2324
2325
2326
2327
2328
2329
2330
2331
2332
2333
2334
2335
2336
2337
2338
2339
2340
2341
2342
2343
2344
2345
2346
2347
2348
2349
2350
2351
2352
2353
2354
2355
2356
2357
2358
2359
2360
2361
2362
2363
2364
2365
2366
2367
2368
2369
2370
2371
2372
2373
2374
2375
2376
2377
2378
2379
2380
2381
2382
2383
2384
2385
2386
2387
2388
2389
2390
2391
2392
2393
2394
2395
2396
2397
2398
2399
2400
2401
2402
2403
2404
2405
2406
2407
2408
2409
2410
2411
2412
2413
2414
2415
2416
2417
2418
2419
2420
2421
2422
2423
2424
2425
2426
2427
2428
2429
2430
2431
2432
2433
2434
2435
2436
2437
2438
2439
2440
2441
2442
2443
2444
2445
2446
2447
2448
2449
2450
2451
2452
2453
2454
2455
2456
2457
2458
2459
2460
2461
2462
2463
2464
2465
2466
2467
2468
2469
2470
2471
2472
2473
2474
2475
2476
2477
2478
2479
2480
2481
2482
2483
2484
2485
2486
2487
2488
2489
2490
2491
2492
2493
2494
2495
2496
2497
2498
2499
2500
2501
2502
2503
2504
2505
2506
2507
2508
2509
2510
2511
2512
2513
2514
2515
2516
2517
2518
2519
2520
2521
2522
2523
2524
2525
2526
2527
2528
2529
2530
2531
2532
2533
2534
2535
2536
2537
2538
2539
2540
2541
2542
2543
2544
2545
2546
2547
2548
2549
2550
2551
2552
2553
2554
2555
2556
2557
2558
2559
2560
2561
2562
2563
2564
2565
2566
2567
2568
2569
2570
2571
2572
2573
2574
2575
2576
2577
2578
2579
2580
2581
2582
2583
2584
2585
2586
2587
2588
2589
2590
2591
2592
2593
2594
2595
2596
2597
2598
2599
2600
2601
2602
2603
2604
2605
2606
2607
2608
2609
2610
2611
2612
2613
2614
2615
2616
2617
2618
2619
2620
2621
2622
2623
2624
2625
2626
2627
2628
2629
2630
2631
2632
2633
2634
2635
2636
2637
2638
2639
2640
2641
2642
2643
2644
2645
2646
2647
2648
2649
2650
2651
2652
2653
2654
2655
2656
2657
2658
2659
2660
2661
2662
2663
2664
2665
2666
2667
2668
2669
2670
2671
2672
2673
2674
2675
2676
2677
2678
2679
2680
2681
2682
2683
2684
2685
2686
2687
2688
2689
2690
2691
2692
2693
2694
2695
2696
2697
2698
2699
2700
2701
2702
2703
2704
2705
2706
2707
2708
2709
2710
2711
2712
2713
2714
2715
2716
2717
2718
2719
2720
2721
2722
2723
2724
2725
2726
2727
2728
2729
2730
2731
2732
2733
2734
2735
2736
2737
2738
2739
2740
2741
2742
2743
2744
2745
2746
2747
2748
2749
2750
2751
2752
2753
2754
2755
2756
2757
2758
2759
2760
2761
2762
2763
2764
2765
2766
2767
2768
2769
2770
2771
2772
2773
2774
2775
2776
2777
2778
2779
2780
2781
2782
2783
2784
2785
2786
2787
2788
2789
2790
2791
2792
2793
2794
2795
2796
2797
2798
2799
2800
2801
2802
2803
2804
2805
2806
2807
2808
2809
2810
2811
2812
2813
2814
2815
2816
2817
2818
2819
2820
2821
2822
2823
2824
2825
2826
2827
2828
2829
2830
2831
2832
2833
2834
2835
2836
2837
2838
2839
2840
2841
2842
2843
2844
2845
2846
2847
2848
2849
2850
2851
2852
2853
2854
2855
2856
2857
2858
2859
2860
2861
2862
2863
2864
2865
2866
2867
2868
2869
2870
2871
2872
2873
2874
2875
2876
2877
2878
2879
2880
2881
2882
2883
2884
2885
2886
2887
2888
2889
2890
2891
2892
2893
2894
2895
2896
2897
2898
2899
2900
2901
2902
2903
2904
2905
2906
2907
2908
2909
2910
2911
2912
2913
2914
2915
2916
2917
2918
2919
2920
2921
2922
2923
2924
2925
2926
2927
2928
2929
2930
2931
2932
2933
2934
2935
2936
2937
2938
2939
2940
2941
2942
2943
2944
2945
2946
2947
2948
2949
2950
2951
2952
2953
2954
2955
2956
2957
2958
2959
2960
2961
2962
2963
2964
2965
2966
2967
2968
2969
2970
2971
2972
2973
2974
2975
2976
2977
2978
2979
2980
2981
2982
2983
2984
2985
2986
2987
2988
2989
2990
2991
2992
2993
2994
2995
2996
2997
2998
2999
3000
3001
3002
3003
3004
3005
3006
3007
3008
3009
3010
3011
3012
3013
3014
3015
3016
3017
3018
3019
3020
3021
3022
3023
3024
3025
3026
3027
3028
3029
3030
3031
3032
3033
3034
3035
3036
3037
3038
3039
3040
3041
3042
3043
3044
3045
3046
3047
3048
3049
3050
3051
3052
3053
3054
3055
3056
3057
3058
3059
3060
3061
3062
3063
3064
3065
3066
3067
3068
3069
3070
3071
3072
3073
3074
3075
3076
3077
3078
3079
3080
3081
3082
3083
3084
3085
3086
3087
3088
3089
3090
3091
3092
3093
3094
3095
3096
3097
3098
3099
3100
3101
3102
3103
3104
3105
3106
3107
3108
3109
3110
3111
3112
3113
3114
3115
3116
3117
3118
3119
3120
3121
3122
3123
3124
3125
3126
3127
3128
3129
3130
3131
3132
3133
3134
3135
3136
3137
3138
3139
3140
3141
3142
3143
3144
3145
3146
3147
3148
3149
3150
3151
3152
3153
3154
3155
3156
3157
3158
3159
3160
3161
3162
3163
3164
3165
3166
3167
3168
3169
3170
3171
3172
3173
3174
3175
3176
3177
3178
3179
3180
3181
3182
3183
3184
3185
3186
3187
3188
3189
3190
3191
3192
3193
3194
3195
3196
3197
3198
3199
3200
3201
3202
3203
3204
3205
3206
3207
3208
3209
3210
3211
3212
3213
3214
3215
3216
3217
3218
3219
3220
3221
3222
3223
3224
3225
3226
3227
3228
3229
3230
3231
3232
3233
3234
3235
3236
3237
3238
3239
3240
3241
3242
3243
3244
3245
3246
3247
3248
3249
3250
3251
3252
3253
3254
3255
3256
3257
3258
3259
3260
3261
3262
3263
3264
3265
3266
3267
3268
3269
3270
3271
3272
3273
3274
3275
3276
3277
3278
3279
3280
3281
3282
3283
3284
3285
3286
3287
3288
3289
3290
3291
3292
3293
3294
3295
3296
3297
3298
3299
3300
3301
3302
3303
3304
3305
3306
3307
3308
3309
3310
3311
3312
3313
3314
3315
3316
3317
3318
3319
3320
3321
3322
3323
3324
3325
3326
3327
3328
3329
3330
3331
3332
3333
3334
3335
3336
3337
3338
3339
3340
3341
3342
3343
3344
3345
3346
3347
3348
3349
3350
3351
3352
3353
3354
3355
3356
3357
3358
3359
3360
3361
3362
3363
3364
3365
3366
3367
3368
3369
3370
3371
3372
3373
3374
3375
3376
3377
3378
3379
3380
3381
3382
3383
3384
3385
3386
3387
3388
3389
3390
3391
3392
3393
3394
3395
3396
3397
3398
3399
3400
3401
3402
3403
3404
3405
3406
3407
3408
3409
3410
3411
3412
3413
3414
3415
3416
3417
3418
3419
3420
3421
3422
3423
3424
3425
3426
3427
3428
3429
3430
3431
3432
3433
3434
3435
3436
3437
3438
3439
3440
3441
3442
3443
3444
3445
3446
3447
3448
3449
3450
3451
3452
3453
3454
3455
3456
3457
3458
3459
3460
3461
3462
3463
3464
3465
3466
3467
3468
3469
3470
3471
3472
3473
3474
3475
3476
3477
3478
3479
3480
3481
3482
3483
3484
3485
3486
3487
3488
3489
3490
3491
3492
3493
3494
3495
3496
3497
3498
3499
3500
3501
3502
3503
3504
3505
3506
3507
3508
3509
3510
3511
3512
3513
3514
3515
3516
3517
3518
3519
3520
3521
3522
3523
3524
3525
3526
3527
3528
3529
3530
3531
3532
3533
3534
3535
3536
3537
3538
3539
3540
3541
3542
3543
3544
3545
3546
3547
3548
3549
3550
3551
3552
3553
3554
3555
3556
3557
3558
3559
3560
3561
3562
3563
3564
3565
3566
3567
3568
3569
3570
3571
3572
3573
3574
3575
3576
3577
3578
3579
3580
3581
3582
3583
3584
3585
3586
3587
3588
3589
3590
3591
3592
3593
3594
3595
3596
3597
3598
3599
3600
3601
3602
3603
3604
3605
3606
3607
3608
3609
3610
3611
3612
3613
3614
3615
3616
3617
3618
3619
3620
3621
3622
3623
3624
3625
3626
3627
3628
3629
3630
3631
3632
3633
3634
3635
3636
3637
3638
3639
3640
3641
3642
3643
3644
3645
3646
3647
3648
3649
3650
3651
3652
3653
3654
3655
3656
3657
3658
3659
3660
3661
3662
3663
3664
3665
3666
3667
3668
3669
3670
3671
3672
3673
3674
3675
3676
3677
3678
3679
3680
3681
3682
3683
3684
3685
3686
3687
3688
3689
3690
3691
3692
3693
3694
3695
3696
3697
3698
3699
3700
3701
3702
3703
3704
3705
3706
3707
3708
3709
3710
3711
3712
3713
3714
3715
3716
3717
3718
3719
3720
3721
3722
3723
3724
3725
3726
3727
3728
3729
3730
3731
3732
3733
3734
3735
3736
3737
3738
3739
3740
3741
3742
3743
3744
3745
3746
3747
3748
3749
3750
3751
3752
3753
3754
3755
3756
3757
3758
3759
3760
3761
3762
3763
3764
3765
3766
3767
3768
3769
3770
3771
3772
3773
3774
3775
3776
3777
3778
3779
3780
3781
3782
3783
3784
3785
3786
3787
3788
3789
3790
3791
3792
3793
3794
3795
3796
3797
3798
3799
3800
3801
3802
3803
3804
3805
3806
3807
3808
3809
3810
3811
3812
3813
3814
3815
3816
3817
3818
3819
3820
3821
3822
3823
3824
3825
3826
3827
3828
3829
3830
3831
3832
3833
3834
3835
3836
3837
3838
3839
3840
3841
3842
3843
3844
3845
3846
3847
3848
3849
3850
3851
3852
3853
3854
3855
3856
3857
3858
3859
3860
3861
3862
3863
3864
3865
3866
3867
3868
3869
3870
3871
3872
3873
3874
3875
3876
3877
3878
3879
3880
3881
3882
3883
3884
3885
3886
3887
3888
3889
3890
3891
3892
3893
3894
3895
3896
3897
3898
3899
3900
3901
3902
3903
3904
3905
3906
3907
3908
3909
3910
3911
3912
3913
3914
3915
3916
3917
3918
3919
3920
3921
3922
3923
3924
3925
3926
3927
3928
3929
3930
3931
3932
3933
3934
3935
3936
3937
3938
3939
3940
3941
3942
3943
3944
3945
3946
3947
3948
3949
3950
3951
3952
3953
3954
3955
3956
3957
3958
3959
3960
3961
3962
3963
3964
3965
3966
3967
3968
3969
3970
3971
3972
3973
3974
3975
3976
3977
3978
3979
3980
3981
3982
3983
3984
3985
3986
3987
3988
3989
3990
3991
3992
3993
3994
3995
3996
3997
3998
3999
4000
4001
4002
4003
4004
4005
4006
4007
4008
4009
4010
4011
4012
4013
4014
4015
4016
4017
4018
4019
4020
4021
4022
4023
4024
4025
4026
4027
4028
4029
4030
4031
4032
4033
4034
4035
4036
4037
4038
4039
4040
4041
4042
4043
4044
4045
4046
4047
4048
4049
4050
4051
4052
4053
4054
4055
4056
4057
4058
4059
4060
4061
4062
4063
4064
4065
4066
4067
4068
4069
4070
4071
4072
4073
4074
4075
4076
4077
4078
4079
4080
4081
4082
4083
4084
4085
4086
4087
4088
4089
4090
4091
4092
4093
4094
4095
4096
4097
4098
4099
4100
4101
4102
4103
4104
4105
4106
4107
4108
4109
4110
4111
4112
4113
4114
4115
4116
4117
4118
4119
4120
4121
4122
4123
4124
4125
4126
4127
4128
4129
4130
4131
4132
4133
4134
4135
4136
4137
4138
4139
4140
4141
4142
4143
4144
4145
4146
4147
4148
4149
4150
4151
4152
4153
4154
4155
4156
4157
4158
4159
4160
4161
4162
4163
4164
4165
4166
4167
4168
4169
4170
4171
4172
4173
4174
4175
4176
4177
4178
4179
4180
4181
4182
4183
4184
4185
4186
4187
4188
4189
4190
4191
4192
4193
4194
4195
4196
4197
4198
4199
4200
4201
4202
4203
4204
4205
4206
4207
4208
4209
4210
4211
4212
4213
4214
4215
4216
4217
4218
4219
4220
4221
4222
4223
4224
4225
4226
4227
4228
4229
4230
4231
4232
4233
4234
4235
4236
4237
4238
4239
4240
4241
4242
4243
4244
4245
4246
4247
4248
4249
4250
4251
4252
4253
4254
4255
4256
4257
4258
4259
4260
4261
4262
4263
4264
4265
4266
4267
4268
4269
4270
4271
4272
4273
4274
4275
4276
4277
4278
4279
4280
4281
4282
4283
4284
4285
4286
4287
4288
4289
4290
4291
4292
4293
4294
4295
4296
4297
4298
4299
4300
4301
4302
4303
4304
4305
4306
4307
4308
4309
4310
4311
4312
4313
4314
4315
4316
4317
4318
4319
4320
4321
4322
4323
4324
4325
4326
4327
4328
4329
4330
4331
4332
4333
4334
4335
4336
4337
4338
4339
4340
4341
4342
4343
4344
4345
4346
4347
4348
4349
4350
4351
4352
4353
4354
4355
4356
4357
4358
4359
4360
4361
4362
4363
4364
4365
4366
4367
4368
4369
4370
4371
4372
4373
4374
4375
4376
4377
4378
4379
4380
4381
4382
4383
4384
4385
4386
4387
4388
4389
4390
4391
4392
4393
4394
4395
4396
4397
4398
4399
4400
4401
4402
4403
4404
4405
4406
4407
4408
4409
4410
4411
4412
4413
4414
4415
4416
4417
4418
4419
4420
4421
4422
4423
4424
4425
4426
4427
4428
4429
4430
4431
4432
4433
4434
4435
4436
4437
4438
4439
4440
4441
4442
4443
4444
4445
4446
4447
4448
4449
4450
4451
4452
4453
4454
4455
4456
4457
4458
4459
4460
4461
4462
4463
4464
4465
4466
4467
4468
4469
4470
4471
4472
4473
4474
4475
4476
4477
4478
4479
4480
4481
4482
4483
4484
4485
4486
4487
4488
4489
4490
4491
4492
4493
4494
4495
4496
4497
4498
4499
4500
4501
4502
4503
4504
4505
4506
4507
4508
4509
4510
4511
4512
4513
4514
4515
4516
4517
4518
4519
4520
4521
4522
4523
4524
4525
4526
4527
4528
4529
4530
4531
4532
4533
4534
4535
4536
4537
4538
4539
4540
4541
4542
4543
4544
4545
4546
4547
4548
4549
4550
4551
4552
4553
4554
4555
4556
4557
4558
4559
4560
4561
4562
4563
4564
4565
4566
4567
4568
4569
4570
4571
4572
4573
4574
4575
4576
4577
4578
4579
4580
4581
4582
4583
4584
4585
4586
4587
4588
4589
4590
4591
4592
4593
4594
4595
4596
4597
4598
4599
4600
4601
4602
4603
4604
4605
4606
4607
4608
4609
4610
4611
4612
4613
4614
4615
4616
4617
4618
4619
4620
4621
4622
4623
4624
4625
4626
4627
4628
4629
4630
4631
4632
4633
4634
4635
4636
4637
4638
4639
4640
4641
4642
4643
4644
4645
4646
4647
4648
4649
4650
4651
4652
4653
4654
4655
4656
4657
4658
4659
4660
4661
4662
4663
4664
4665
4666
4667
4668
4669
4670
4671
4672
4673
4674
4675
4676
4677
4678
4679
4680
4681
4682
4683
4684
4685
4686
4687
4688
4689
4690
4691
4692
4693
4694
4695
4696
4697
4698
4699
4700
4701
4702
4703
4704
4705
4706
4707
4708
4709
4710
4711
4712
4713
4714
4715
4716
4717
4718
4719
4720
4721
4722
4723
4724
4725
4726
4727
4728
4729
4730
4731
4732
4733
4734
4735
4736
4737
4738
4739
4740
4741
4742
4743
4744
4745
4746
4747
4748
4749
4750
4751
4752
4753
4754
4755
4756
4757
4758
4759
4760
4761
4762
4763
4764
4765
4766
4767
4768
4769
4770
4771
4772
4773
4774
4775
4776
4777
4778
4779
4780
4781
4782
4783
4784
4785
4786
4787
4788
4789
4790
4791
4792
4793
4794
4795
4796
4797
4798
4799
4800
4801
4802
4803
4804
4805
4806
4807
4808
4809
4810
4811
4812
4813
4814
4815
4816
4817
4818
4819
4820
4821
4822
4823
4824
4825
4826
4827
4828
4829
4830
4831
4832
4833
4834
4835
4836
4837
4838
4839
4840
4841
4842
4843
4844
4845
4846
4847
4848
4849
4850
4851
4852
4853
4854
4855
4856
4857
4858
4859
4860
4861
4862
4863
4864
4865
4866
4867
4868
4869
4870
4871
4872
4873
4874
4875
4876
4877
4878
4879
4880
4881
4882
4883
4884
4885
4886
4887
4888
4889
4890
4891
4892
4893
4894
4895
4896
4897
4898
4899
4900
4901
4902
4903
4904
4905
4906
4907
4908
4909
4910
4911
4912
4913
4914
4915
4916
4917
4918
4919
4920
4921
4922
4923
4924
4925
4926
4927
4928
4929
4930
4931
4932
4933
4934
4935
4936
4937
4938
4939
4940
4941
4942
4943
4944
4945
4946
4947
4948
4949
4950
4951
4952
4953
4954
4955
4956
4957
4958
4959
4960
4961
4962
4963
4964
4965
4966
4967
4968
4969
4970
4971
4972
4973
4974
4975
4976
4977
4978
4979
4980
4981
4982
4983
4984
4985
4986
4987
4988
4989
4990
4991
4992
4993
4994
4995
4996
4997
4998
4999
5000
5001
5002
5003
5004
5005
5006
5007
5008
5009
5010
5011
5012
5013
5014
5015
5016
5017
5018
5019
5020
5021
5022
5023
5024
5025
5026
5027
5028
5029
5030
5031
5032
5033
5034
5035
5036
5037
5038
5039
5040
5041
5042
5043
5044
5045
5046
5047
5048
5049
5050
5051
5052
5053
5054
5055
5056
5057
5058
5059
5060
5061
5062
5063
5064
5065
5066
5067
5068
5069
5070
5071
5072
5073
5074
5075
5076
5077
5078
5079
5080
5081
5082
5083
5084
5085
5086
5087
5088
5089
5090
5091
5092
5093
5094
5095
5096
5097
5098
5099
5100
5101
5102
5103
5104
5105
5106
5107
5108
5109
5110
5111
5112
5113
5114
5115
5116
5117
5118
5119
5120
5121
5122
5123
5124
5125
5126
5127
5128
5129
5130
5131
5132
5133
5134
5135
5136
5137
5138
5139
5140
5141
5142
5143
5144
5145
5146
5147
5148
5149
5150
5151
5152
5153
5154
5155
5156
5157
5158
5159
5160
5161
5162
5163
5164
5165
5166
5167
5168
5169
5170
5171
5172
5173
5174
5175
5176
5177
5178
5179
5180
5181
5182
5183
5184
5185
5186
5187
5188
5189
5190
5191
5192
5193
5194
5195
5196
5197
5198
5199
5200
5201
5202
5203
5204
5205
5206
5207
5208
5209
5210
5211
5212
5213
5214
5215
5216
5217
5218
5219
5220
5221
5222
5223
5224
5225
5226
5227
5228
5229
5230
5231
5232
5233
5234
5235
5236
5237
5238
5239
5240
5241
5242
5243
5244
5245
5246
5247
5248
5249
5250
5251
5252
5253
5254
5255
5256
5257
5258
5259
5260
5261
5262
5263
5264
5265
5266
5267
5268
5269
5270
5271
5272
5273
5274
5275
5276
5277
5278
5279
5280
5281
5282
5283
5284
5285
5286
5287
5288
5289
5290
5291
5292
5293
5294
5295
5296
5297
5298
5299
5300
5301
5302
5303
5304
5305
5306
5307
5308
5309
5310
5311
5312
5313
5314
5315
5316
5317
5318
5319
5320
5321
5322
5323
5324
5325
5326
5327
5328
5329
5330
5331
5332
5333
5334
5335
5336
5337
5338
5339
5340
5341
5342
5343
5344
5345
5346
5347
5348
5349
5350
5351
5352
5353
5354
5355
5356
5357
5358
5359
5360
5361
5362
5363
5364
5365
5366
5367
5368
5369
5370
5371
5372
5373
5374
5375
5376
5377
5378
5379
5380
5381
5382
5383
5384
5385
5386
5387
5388
5389
5390
5391
5392
5393
5394
5395
5396
5397
5398
5399
5400
5401
5402
5403
5404
5405
5406
5407
5408
5409
5410
5411
5412
5413
5414
5415
5416
5417
5418
5419
5420
5421
5422
5423
5424
5425
5426
5427
5428
5429
5430
5431
5432
5433
5434
5435
5436
5437
5438
5439
5440
5441
5442
5443
5444
5445
5446
5447
5448
5449
5450
5451
5452
5453
5454
5455
5456
5457
5458
5459
5460
5461
5462
5463
5464
5465
5466
5467
5468
5469
5470
5471
5472
5473
5474
5475
5476
5477
5478
5479
5480
5481
5482
5483
5484
5485
5486
5487
5488
5489
5490
5491
5492
5493
5494
5495
5496
5497
5498
5499
5500
5501
5502
5503
5504
5505
5506
5507
5508
5509
5510
5511
5512
5513
5514
5515
5516
5517
5518
5519
5520
5521
5522
5523
5524
5525
5526
5527
5528
5529
5530
5531
5532
5533
5534
5535
5536
5537
5538
5539
5540
5541
5542
5543
5544
5545
5546
5547
5548
5549
5550
5551
5552
5553
5554
5555
5556
5557
5558
5559
5560
5561
5562
5563
5564
5565
5566
5567
5568
5569
5570
5571
5572
5573
5574
5575
5576
5577
5578
5579
5580
5581
5582
5583
5584
5585
5586
5587
5588
5589
5590
5591
5592
5593
5594
5595
5596
5597
5598
5599
5600
5601
5602
5603
5604
5605
5606
5607
5608
5609
5610
5611
5612
5613
5614
5615
5616
5617
5618
5619
5620
5621
5622
5623
5624
5625
5626
5627
5628
5629
5630
5631
5632
5633
5634
5635
5636
5637
5638
5639
5640
5641
5642
5643
5644
5645
5646
5647
5648
5649
5650
5651
5652
5653
5654
5655
5656
5657
5658
5659
5660
5661
5662
5663
5664
5665
5666
5667
5668
5669
5670
5671
5672
5673
5674
5675
5676
5677
5678
5679
5680
5681
5682
5683
5684
5685
5686
5687
5688
5689
5690
5691
5692
5693
5694
5695
5696
5697
5698
5699
5700
5701
5702
5703
5704
5705
5706
5707
5708
5709
5710
5711
5712
5713
5714
5715
5716
5717
5718
5719
5720
5721
5722
5723
5724
5725
5726
5727
5728
5729
5730
5731
5732
5733
5734
5735
5736
5737
5738
5739
5740
5741
5742
5743
5744
5745
5746
5747
5748
5749
5750
5751
5752
5753
5754
5755
5756
5757
5758
5759
5760
5761
5762
5763
5764
5765
5766
5767
5768
5769
5770
5771
5772
5773
5774
5775
5776
5777
5778
5779
5780
5781
5782
5783
5784
5785
5786
5787
5788
5789
5790
5791
5792
5793
5794
5795
5796
5797
5798
5799
5800
5801
5802
5803
5804
5805
5806
5807
5808
5809
5810
5811
5812
5813
5814
5815
5816
5817
5818
5819
5820
5821
5822
5823
5824
5825
5826
5827
5828
5829
5830
5831
5832
5833
5834
5835
5836
5837
5838
5839
5840
5841
5842
5843
5844
5845
5846
5847
5848
5849
5850
5851
5852
5853
5854
5855
5856
5857
5858
5859
5860
5861
5862
5863
5864
5865
5866
5867
5868
5869
5870
5871
5872
5873
5874
5875
5876
5877
5878
5879
5880
5881
5882
5883
5884
5885
5886
5887
5888
5889
5890
5891
5892
5893
5894
5895
5896
5897
5898
5899
5900
5901
5902
5903
5904
5905
5906
5907
5908
5909
5910
5911
5912
5913
5914
5915
5916
5917
5918
5919
5920
5921
5922
5923
5924
5925
5926
5927
5928
5929
5930
5931
5932
5933
5934
5935
5936
5937
5938
5939
5940
5941
5942
5943
5944
5945
5946
5947
5948
5949
5950
5951
5952
5953
5954
5955
5956
5957
5958
5959
5960
5961
5962
5963
5964
5965
5966
5967
5968
5969
5970
5971
5972
5973
5974
5975
5976
5977
5978
5979
5980
5981
5982
5983
5984
5985
5986
5987
5988
5989
5990
5991
5992
5993
5994
5995
5996
5997
5998
5999
6000
6001
6002
6003
6004
6005
6006
6007
6008
6009
6010
6011
6012
6013
6014
6015
6016
6017
6018
6019
6020
6021
6022
6023
6024
6025
6026
6027
6028
6029
6030
6031
6032
6033
6034
6035
6036
6037
6038
6039
6040
6041
6042
6043
6044
6045
6046
6047
6048
6049
6050
6051
6052
6053
6054
6055
6056
6057
6058
6059
6060
6061
6062
6063
6064
6065
6066
6067
6068
6069
6070
6071
6072
6073
6074
6075
6076
6077
6078
6079
6080
6081
6082
6083
6084
6085
6086
6087
6088
6089
6090
6091
6092
6093
6094
6095
6096
6097
6098
6099
6100
6101
6102
6103
6104
6105
6106
6107
6108
6109
6110
6111
6112
6113
6114
6115
6116
6117
6118
6119
6120
6121
6122
6123
6124
6125
6126
6127
6128
6129
6130
6131
6132
6133
6134
6135
6136
6137
6138
6139
6140
6141
6142
6143
6144
6145
6146
6147
6148
6149
6150
6151
6152
6153
6154
6155
6156
6157
6158
6159
6160
6161
6162
6163
6164
6165
6166
6167
6168
6169
6170
6171
6172
6173
6174
6175
6176

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

482
492





DETAIL "A"


SS-18 - 1793 L.F. TYPE "C" FENCE

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
313-LA	SEE SHEET #10				
318-LA	YOUNGSTOWN HOSP. ASSOC	MISC. BLD'GS.	HOSPITAL BLD'GS.		158,970
319-LA	THE RENNER CO.	BREWERY BUILDINGS			0.754Ac
321-LA	PHILLIP GREIN	2 ST. BR.	18x18 FR.	12x62 C.B.	9,140
322-LA	JOHN BOGGANS, ET AL	1 ST. FR. 2 FR. ABANDONED		SHED	18,780
323-LA	EUGENE & ESTHER RUSNAK	2 ST. FR. 3 ST. BR.	20x18 20x30 18x18	STUCCO FR. BR.	2,600
326-LA	SEE SHEET #12				
320A-LA	ANNA M. PATTERSON	2-ST. FR.	29x16 FR.		4,500

NOTE: DEED INFORMATION MISSING ON PARCELS MARKED WITH ASTERISKS.

NOTE: SEE SHEET FOR INVENTORY.

NOTE:
THE HORIZONTAL CLEARANCE FROM LIMITED ACCESS LINE TO THE OUTSIDE FACE OF THE DRIVEN PILE IS CALCULATED AT A DISTANCE OF 24.50 FEET BELOW GROUND ELEVATION.



DETAIL "B" ~ DELETED
(No Scale)

WORK AGREEMENT		
PARCEL Nº	NAME	DESCRIPTION
323-WA	EUGENE & ESTHER RUSNAK	REMOVE FD'N.
321-WA	PHILLIP GREIN	REMOVE FD'N.
318-WA	YOUNGSTOWN HOSP. ASSOC.	FILL BASEMENT
319-WA	THE RENNER CO.	REMOVE FD'N.
313-WA	SEE SHEET #15	REMOVE SILO'S

Rev. Nº 8, Deleted 319-Aerial, Revised L.A. Line and Area Pcl. 319-LA Per Warranty Deed Vol 1017 Pg 657 & Case Nº 168065 12/16/63


REVISIONS				REVISIONS			DATE COMP.
REV Nº	NATURE	DATE	MADE BY	REV. NO.	NATURE OF REVISION	DATE	MADE BY
#3	ADDED SEWER EASEM'T Pcl 3195	4-10-61	T.J.	#1	ADDED BRIDGE	2-30-59	J.E.P.
#4	ADDED DETAIL "A" Pcl 319 S	4-18-61	T.J.		REVISED PIKE ST.	1-20-60	
#5	ADDED PARCEL 319 AERIAL	11-6-61	T.J.		REVISED ℄ LINE PARCEL 319-LA	1-20-60	
	REVISE AREA OF TAKING PARCEL 319-LA	11-6-61	T.J.	#2	ADDED R - ADDED TOPO	3-29-60	J.D.P.
#6	REVISED PARCEL 319 AERIAL & REVISED AREA OF TAKING, PARCEL 319 LA & 319 AERIAL	12-11-61			Pcl. 320-A-LA ADDED AREA	7-6-60	S.S.
#7	ADDED BUILDING & CROSS HATCHED	4-5-62			Pcl 318-LA Revised Area & Added Tails	10-18-60	S.S.

I-680

R/W SHEET NO. 17 OF 29

FED. RD.	STATE	PROJECT	
2	OHIO	MAH.-18-17.20	

483
492



SEE DETAIL SHEET No 16 FOR PARCEL 356-LA

WORK AGREEMENT		
PARCEL	NAME	DESCRIPTION
326-WA	RIDGE MEDICAL BLD'G. CO.	REVISE DRIVEWAY
333-WA	JOHN DORLOSAN MARY DORLOSAN	FILL BASEMENT
332-WA	MYRTLE I. MILLER VIRGINIA VIETS CRAMER DOROTHY VIETS GLINES	FILL BASEMENT
342-WA	ELIZABETH HILLOSKY, SR..	FILL BASEMENT
342-A-WA	FLORENCE L. EVANS	FILL BASEMENT
352-WA	LEROY E. BILLIG	FILL BASEMENT
352-A-WA		FILL BASEMENT
350-WA	RALPH A. KELLY ISABELLA M. KELLY	REMOVE FD'N.
353-WA	MORTON, RAYMOND D. & BERNARD WHITE	REMOVE FD'N.
340-WA	HAROLD P. SMITH EMILY E. SMITH	FILL BASEMENT

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
326-LA	RIDGE MEDICAL BLD'G. CO.	1 ST. BR.			42,609
327-LA	ELIZABETH GEORGE	2 ST. FR.	24×20 FR.		8,956
328-LA	LUCY S. MIKITA	2 ST. FR.	36×18 FR.		6,350
329-LA	LESLIE H. SABO ELIZABETH M. SABO	2 ST. FR.			3,409
329-A-LA	M. VERA HERSCHEL	2 ST. FR.	12×16 FR.	10×16 SHED	
330-LA	ANTHONY P. JULIUS	2 ST. FR.			6,250
331-LA	JOSEPH SARISKY	2 ST. FR.			5,686
332-LA	MYRTLE I. MILLER VIRGINIA VIETS CRAMER DOROTHY VIETS GLINES	2 ST. FR.	12×18 FR.	5×14 SHED	6,600
333-A-LA	JOHN DORLOSAN MARY DORLOSAN	2 ST. FR.	12×18 FR.	5×14 SHED	1,250
333-B-LA	GEARLD CARROLL & ALICE CARROLL	2 ST. FR.		8×8 SHED	
334-LA	TUFIC SAADI	1½ ST. FR.	26×16 FR.	22×16 SHED	7,500
335-LA	LALE GRAHOVAC	2 ST. FR.	20×18 FR.		7,500
336-LA	JOSEPH THURIK MARY THURIK	2 ST. FR.			7,500
337-LA	THE INCORPORATED TRUSTEES OF THE GOSPEL WORKER SOC.	2-1 ST. FR.			7,500
338-LA	MILDRED McDONALD	2 ST. FR.	24×20 FR.	10×16 SHED	7,000
339-LA	RALPH A. KELLY ISABELLA M. KELLY	2 ST. FR.	24×18 2 ST. FR.	16×16 SHED	7,344 *
340-LA	CHARLOTTA PISLAK	2 ST. FR.	26×18 2 ST. FR.		5,436
341-LA	JOHN W. TOMALKA, SR. MARY HAZEL TOMALKA	2 ST. FR.			2,875
342-LA	ELIZABETH HILLOSKY, SR.	2 ST. FR.	19×20 FR.		2,225
342-A-LA	FLORENCE L. EVANS	2 ST. FR.	14×18 FR.		1,575

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
344-LA	FRANK JAMES COLLA	2 ST. FR.			3,724
344-A	THE GREEK COMM. AGIOI IOANNIS ORTHODOX CHURCH		39/56		336
345-LA	MARY DEVAN	2 ST. FR.			5,366
346-LA	CLARA ANDERSON	2 ST. FR.	20×20 FR.		7,335
347-LA	FRANK JAMES COLLA	2 ST. FR.			3525
348-LA	JOHN PAUL	3-2 ST. FR.			3,150
350-LA	JOHN BUDAKER ANN BUDAKER	2-2 ST. FR.	12×20 FR.		4,100
352-LA	LEROY E. BILLIG	2 ST. FR.	28×20 20×16		1,025
353-LA	MORTON, RAYMOND D. & BERNARD WHITE	14×12 OFFICE			5,000
352-A-LA	MARY J. COMINOS	2 ST FR			320
356-LA	THE GENERAL ELECTRIC CO.				41,612
358-LA	THE ROAD OF REMEMBRANCE POST #472 AM. LEGION, DEPT. OF OHIO	2 ST. FR.	24×46 FR.		10,750
359-LA	JAMES E. & WENDELL H. BENNETT, IDA JOSEPHINE DATSON	2 ST. FR.			7,325
360-LA	HAROLD P. SMITH EMILY E. SMITH	4 ST. FR.			3,950

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
359-A-LA	JAMES E. & WENDELL H. BENNETT IDA JOSEPHINE DAWSON				1050
344-D-LA	FRANK JAMES COLLA				315
361C LA	NORTHERN INVESTMENT COMPANY				SEE R/W SHEET 19
356-A-LA	THE GENERAL ELECTRIC CO.				SEE R/W SHEET 18
356-T5	" " " "				4,960
348-A	THE CITY OF YOUNGSTOWN (FORMERLY JOHN PAUL)				450
350-A	THE CITY OF YOUNGSTOWN (FORMERLY JOHN BUDAKER)				744

REVISIONS		DATE	COMP. BY
REV. NO.	NATURE OF REVISION		
#3	DELETED 322WA, ADDED 342-A-WA		
	& 360-WA, ADDED R, REVISED R/W		
	FENCE	3-29-60	J.D.P.
#4	Parcels 344B-LA, 359-LA Revised	4-12-60	T.A.B.
#5	Parcel 339-LA Revised	4-18-60	T.A.B.
#6	ADDED PCLS. 348A & 350-A & SHOWED FEDERAL PARTICIPATION PER GUZIAK 6-3-68	6-3-68	J.R.B.

NOTE: DEED INFORMATION MISSING ON PARCELS MARKED WITH ASTERISKS.

REVISIONS		DATE	COMP. BY
REV. NO.	NATURE OF REVISION		
#1	ADDED RETAINING WALLS	12-30-59	J.E.P.
	REVISED ¼ AT PARCEL 326 LA	1-20-60	
	ADDED SEWER & PARCELS 355-A-LA & 341 LA.		
	REVISED 356-LA, 358-LA & 360-LA		
	DELETED 361-LA, ADDED W/AS.		
#2	ADDED 346A LA, 347ALA, REV. 352ALA		

Deleted Pcl. 347ALA, Combined with 347LA. 3-4-65
Revised Pcl. 344 A to include the area upon which the proposed sidewalk was constructed 11-19-62 @
ADDED PCL. 356-T5, DELETED 356-WA 2-22-60 S.S.
Parcel 344-A Revised 6-30-60 S.S.
Parcel 339-LA Revised 6-27-60 S.S.

RECEIVED NOV 23 1962 STATE HIGHWAY DEPT. DIV. NO. 1

FED. RD.	STATE	PROJECT	
2	OHIO		


484/492

MAH-18-17.20

PARCEL 356 LA

GENERAL ELECTRIC CO.

SCALE: 1" = 30'



	STATION	GROUND ELEV.	TOP ELEV.
BEGIN RETAINING WALL	11+77.85	935.66	958.72
	12+40	941.28	963.5
	13+00	942.84	963.5
	14+03.87	945.54	960.61
	14+47	946.68	959.11
	15+13	948.40	956.87
END RETAINING WALL	15+81	950.27	954.58

REVISED AREA OF TAKING

356 LA	37,500 SQ.FT.
356-A-LA	4,112 " "
356-TS	4,960 " "

ADDED PCL-356-TS 1-21-61

Rts. 356-LA & 356-A-LA Revised 7-6-60

I-680

R/W SHEET NO. 19 OF 20

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

485
492

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
356-A-LA	THE GENERAL ELECTRIC CO.				SEE R/W SHEET 18
361-C-LA	NORTHERN INVESTMENT COMPANY				125
362-LA	TINCO DE CARPENTIER	2 ST. BR. JOINING	APTS WITH GARAGES	(AD-	31,857
363-LA	RALPH E. GOFF AGNES E. GOFF	1 ST. C.B.			9,750
364-LA	JOHN COMEK MARY COMEK	2 ST. FR.			4,430
365-LA	SARAH KLATMAN HANNAH KLATMAN	2 ST. FR.			2,275
366-LA	FAY KIRKORSKY	2 ST. FR.	20×20 FR.		4,748
367-LA	IDEALIA HOWELL EUALEE HOWELL	2 ST. FR.	18×15 FR.	5×18 SHED	5,080
368-LA	JAMES DAVIS EULA MAE DAVIS	2 ST. FR.	12×18 FR.		5,420
369-LA	CARRIE E. WATSON	2 ST. FR.	18×16 FR.		5,840
370-LA	THE ECONOMY ELECTRIC CO.	3-2 ST. BR. 1 ST. TILE, 1 ST. BR.			3,094
371-LA	DOROTHY MOHN	2 ST. FR.			6,200
372-LA	DEMETRIOS G. MAVRIKIS	2 ST. FR.		5×8 SHED	5,053
373-LA	SOPHIA MARGOLIS	2 ST. FR.			6,507
374-LA	EDWARD PARKMAN MYRTLE L. PARKMAN	2 ST. FR.			5,871
375-LA	JOHN SPANOS ALEXANDRA SPANOS	2 ST. FR.	12×20 FR.	10×12 FR.	5,731
376-LA	MARY H. MENEGAY CLARA L. PAAR	2 ST. FR.	12×16 FR.		6,000
377-LA	NICHOLAS GLAROS NIKI GLAROS	2 ST. FR.	20×18 FR.		6,780
378-LA	JOHN SERINO & MARY MARZULLO	2 ST. FR.	20×16 FR.		5,467
379-LA	ROSE KNABEL	2 ST. FR.			2,650
380-LA	MARY DEVAN	2 ST. FR.	28×16 FR.		8,180
381-LA	HENRY B. GESSAMAN VIRGINIA GESSAMAN	2 ST. FR.	14×18 FR.		3,518
382-LA	NORQUIST LAND CO.				3,468
383-LA	JOHN J. VERNELLO EDNA M. VERNELLO	2 ST. FR.			3,350
383-B-LA	MARY C. CARTWRIGHT MARGARET CONROY	2 ST. FR.	13×21 C.B.		3,252
384-LA	WILMA V. GING	5-2 ST. FR.	10×16 FR.		6,090
387-LA	THE BOARD OF EDUCATION OF YOUNGSTOWN CITY SCHOOL DIST.	BRICK SCHOOL BLDG.			26,418

55-18 2438 L.F. TYPE "C" FENCE

BEGIN SHEET STA. 1030+00

END SHEET STA. 802+00

MARKET STREET

HAYES AVE

FULTON STREET

MARL Z STREET

PROJECT END MAH-18-17.80

PROJECT BEGIN MAH-7-14.20

THIS RIGHT-OF-WAY ACQUIRED UNDER PROJECT MAH-7-14.80

TEMPORARY CONSTRUCTION LIMITS

RAMP "N"

PARKING AREA

Temporary Easement Line

SEE R/W SHEET 18

NOTE: DEED INFORMATION MISSING ON PARCELS MARKED WITH ASTERISKS.

TEMPORARY EASEMENTS AREAS
370-T 5213 Sq Ft.
372-T 616 Sq Ft.

WORK AGREEMENT

PARCEL No.	NAME	DESCRIPTION
433-A-WA	RUTH. B. ROBINS	REMOVE FDT'N.
433-WA	WILLIE JAMES TALLEY	FILL BASEMENT
432-WA	JEAN WEISER ANDREW ROSENFELD	FILL BASEMENT
431-WA	ARNALD & CATHERINE HOWELL	FILL BASEMENT
430-WA	JOHN McCARTY SCHWARTZ	FILL BASEMENT
429-WA	GRANT BARNETT JOSEPHINE BARNETT	FILL BASEMENT
406-B-WA		FILL BASEMENT
378-WA	JOHN SERINO & MARY MARZULLO	FILL BASEMENT
379-WA	ROSE KNOBEL	FILL BASEMENT
362-WA	TINCO DE CARPENTIER	FILL BASEMENT
370-WA	THE ECONOMY ELECTRIC CO.	REMOVE FDT'N. & GRADE AREA
384-WA	WILMA V. GING	FILL BASEMENT

REVISIONS		DATE COMP.	
REV. NO	NATURE OF REVISION	DATE	MADE BY
8	REVISED AREA OF TAKING, FENCE CONSTRUCTION LIMITS & L/A LINE	9/18/61	T.J.
	PARCELS 373-LA, 374-LA, 375-LA, 380-LA 381-LA, 382-LA, 383-LA, 383-B-LA, 384-LA		
9	Added Parcels 370-T, 372-T & Areas	1-11-62	GF

REVISIONS		DATE COMP.	
NO.	NATURE OF REVISION	DATE	MADE BY
#1	ADDED PARCEL 393-A-LA (LAND CONTRACT SALE)	9-17-59	
#2	REVISED PARCELS 390-A-LA, 391-A-LA	11-27-59	
#3	REVISED PARCEL 363-LA	12-11-59	
#4	ADDED RETAINING WALL	12-30-59	J.E.P.
#5	REV. 372-LA, 373-LA, 374-LA, 375-LA, 376-LA, 380-LA		
	381-LA, 382-LA, 383-LA, 383-B-LA, 384-LA, 387-LA		
	ADDED WORK AGREEMENTS		
	PCL. 372-LA, 373-LA, ADDED WORK		
#6	ADDED 384-WA - INCLUDED GRADING		
	UNDER 370-WA - ADDED R.	3-30-60	J.D.P.
#7	ADDED PARCEL 393-A-LA	12-15-60	R.H.

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
390-LA	FREDRIKA I. BOGGS MINTER B. BOGGS	2 ST. FR.	12×18 FR.		3,750
* 390-A-LA	JAMES WALSH JR.				
391-LA	ROSE EVELYN STRAWDERMAN	2 ST. FR.			2,000
* 391-A-LA	MILTON KIBBLE MARY LOU KIBBLE				
392-LA	GIUSEPPE CHIRCHIGLIA ROSE CHIRCHIGLIA	2 ST. FR.			2,000
393-LA	FAY KIRKORSKY	2 ST. FR.			1,875
394-LA	MATTIE B. TERRELL	2 ST. FR.			3,750
395-LA	EVA WILLIAMS ROBERT WILLIAMS	2 ST. FR.	12×16 TILE		3,750
397-LA	CHESTER V. LONG MARGARET F. LONG	3 ST. FR. APT.			3,875
406-LA	CLOYDE JAMES FRY ROBERTA MARIAN FRY	2 ST. FR.	9×20 18×24		4,800
* 406-A-LA		2-2 ST. FR.	6-4×20		
* 406-B-LA		2 ST. FR.			

PARCEL NO.	NAME	BUILDINGS HOUSES	GARAGE	OTHER	AREA OF TAKING
407-LA	LOUIS HARRINGTON JULIA HARRINGTON	3-2 ST. FR.			10,593
425-LA	SOPHIE COHEN	3 ST. BR. 2 ST. BR.	6-0×16 FR.		10,923
426-LA	GEORGE BRADLEY FRANCES JUNE BRADLEY	2 ST. FR.			5,958
427-LA	HELEN BUGNO	2 ST. FR.			4,377
428-LA	EDWARD WILLIAMS J. B. WILLIAMS	1 ST. FR.			2,160
429-LA	GRANT BARNETT JOSEPHINE BARNETT	1 ST. FR.			1,485
430-LA	JOHN McCARTY SCHWARTZ	2 ST. FR.			592
431-LA	ARNOLD & CATHERINE HOWELL	2 ST. FR.			543
432-LA	JEAN WEISER ANDREW ROSENFELD				464
433-LA	WILLIE JAMES TALLEY	2 ST. FR.			342
433-A-LA	RUTH B. ROBINS	2 ST. BR. WAREHOUSE			3,231
393-A-LA	F. KIRKORSKY & C. & E. BENTLEY	2 ST. FR.			1,875

FED. RD	STATE	PROJECT	
2	OHIO	MAH-18-17.20	


486
492

LAKE ERIE & EASTERN RAILROAD RIGHT-OF-WAY PLAT

SCALE: 1" = 50'

PARCEL	OWNER	ACRES
313-LA	L. E. & E. R.R.	0.25
313-A-LA	L. E. & E. R.R.	0.33
313-A	L. E. & E. R.R.	0.93

313-WA	L. E. & E. R.R.	REMOVAL OF CONCRETE SILO



BEGIN DESCRIPTION PARCEL 313-LA
271.17' FROM R.R. STA. 264+63.56
@ AN ANGLE OF 102° 02'
(RAILROAD INFORMATION)
69.97' LEFT OF EXP'WY
STA. 1006+01.95 (ON A RADIAL LINE)

CURVE DATA - PROPOSED PIKE ST. RELOCATION

CURVE Nº 1	CURVE Nº 2	CURVE Nº 3
Δ: 28°	Δ: 8° 02' 44"	Δ: 11° 20' 50"
R: 200'	R: 1432.39'	R: 1056.88'
Dc: 28° 38' 52"	Dc: 4°	Dc: 5° 25' 16"
T: 49.87'	T: 100.73'	T: 105'
Lc: 97.74'	Lc: 201.14'	Lc: 209.31'

CURVE DATA FOR ARC IN LA LINE
Δ: 8° 02' 44"
R: 1415.89'
Dc: 4° 02' 47"
T: 99.57'
Lc: 198.82'

NOTE:
—℄— EXISTING R.R. PROPERTY LINE
—LA— LIMIT OF TAKING FOR EXP'WY
—RW— LIMIT OF TAKING FOR PIKE ST. RELOC.

I-680 R/W SHEET 21 of 26

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

487
492

BALTIMORE & OHIO RAILROAD RIGHT-OF-WAY PLAT

SCALE: 1"=100'


NOTE:
BEARINGS APPEARING IN BOXED PORTION ARE RELATED TO THE BALTIMORE & OHIO RAILROAD. ALL REMAINING BEARINGS ARE RELATED TO THE YOUNGSTOWN-TOWN EXPRESSWAY, S.R. 18.

EXISTING R.R. PROPERTY LINE
LIMIT OF TAKING FOR EXP'WY

PARCEL	OWNER	ACRES
146-A-LA	BALTIMORE & OHIO R.R.	0.11
164-LA	BALTIMORE & OHIO R.R.	2.60

EASEMENT		
144-S	BALTIMORE & OHIO R.R.	0.06


PARCEL	OWNER	ACRES
C-146-B	BALTIMORE & OHIO R.R.	0.07
C-146-C	BALTIMORE & OHIO R.R.	0.10




Revised 7/11/60 R.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

488
492



RIGHT-OF-WAY OAKWOOD AVENUE					
PARCEL Nº	LOT Nº	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
C-1WA	18181	MARGARET C. BOWREY		YES		HEDGE
C-2WA	18182	ELIZ. LESKO ZAVACAN		YES	YES	CONC. STEPS
C-3WA	18183	JOHN & WASYLYNA IWANIUK		YES	YES	WALL
C-4WA	18184	THEO. & NANCY HASSAY		YES	YES	CONC. STEPS
C-5WA	18185	KOLAR & KURTA		YES	YES	CONC. STEPS
C-6WA	18186	GUSSIE L. HEYMAN		YES	YES	
C-7WA	18187	CHARLES & FLO L. PALISEN		YES	YES	



RIGHT-OF-WAY SILLIMAN STREET					
PARCEL Nº	LOT Nº	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
C-9WA	6788	CHAS. & JUSTINE SEREDNESKY		YES	YES	
C-10WA	15349	MARY KNAPIK		YES	YES	
C-11WA	15350	JOHN & SOPHIE TOPORCER		YES	YES	
C-12WA	15351	JOHN LEJBA		YES	YES	
C-13WA	15352	ALEX & ADA HODORY		YES		
C-14WA	15353	MARY & JOHN SKLEPKO		YES	YES	
C-15WA	15354	PAUL & MARY KISSEL		YES	YES	
C-16WA	6789	MARY PODRAEZKY		YES	YES	
C-17WA	6790	JOHN & HELEN NESTERUK		YES	YES	
C-18WA	6791	PAUL & JULIA ANTEL		YES	YES	
C-19WA	11781	CHARLES F. SEMPLE		YES		
C-B	6784	CHARLES SR & CHRISTINA SEREDNESKY				

REVISIONS			DATE COMP.
REV. NO.	NATURE OF REVISION	DATE	MADE BY
# 1	DELETED PARCELS C-1A, C-2A, C-3A C-4A, C-5A, C-6A, C-7A	3-30-60	J.D.P.
# 2	REVISED R/W LINE ON OAKWOOD	4-4-60	J.D.P.


-LEGEND-
EXISTING R/W ———————
PROPOSED R/W ———————
SLOPE EASEMENT & WORK AGREEMENT LIMITS — — — —

SILLIMAN STREET

R/W OAKWOOD AVE. & SILLIMAN ST.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH.-18-17.20	

483
492



RIGHT-OF-WAY MARSHALL STREET

PARCEL No.	LOT No.	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK SLOPE	AGREEMENT DRIVEWAY	OTHER	
C-20A	9487	THE ISALY DAIRY CO.	34.4 SQ. FT.	YES	YES		
C-20WA		" " " "		YES			

REVISIONS


REV. NO.	NATURE OF REVISION	DATE	DATE COMP. MADE BY
#1	DELETED PARCEL C-21-WA		


-LEGEND-
EXISTING R/W
PROPOSED R/W
SLOPE EASEMENT & WORK AGREEMENT LIMITS

R/W MARSHALL ST.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

490
492





RIGHT-OF-WAY EDWARDS STREET

PARCEL Nº	LOT Nº	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
C-49A	3171	FLORENCE MACE	300 SQ. FT.			
C-50A	3172	MILITARY ORDER OF COOTIE, PUP TENT #5	150 SQ. FT.			
C-51A	3173	GEORGE A. GREIN	300 SQ. FT.			
C-52A	2653	ISALY DAIRY CO.	64 SQ. FT.			
C-53A	3407	ISALY DAIRY CO.	146 SQ. FT.			
C-54A	9508	BENJAMIN F. LEWIS	180 SQ. FT.			
C-55A	5721	RALPH M. McCRACKEN	150 SQ. FT.			
C-55WA	5721	" " "		YES		
C-56A	5722	LEONA LOUISE CALER	204 SQ. FT.			
C-56WA	5722	" " "		YES	YES	
C-57A	OL 379	CALVIN & MARTHA WESTON	164 SQ. FT.			
C-57WA	OL 379	" " "		YES	YES	
C-58A	30332	NAPOLEAN & DOROTHY BURT	200 SQ. FT.			
C-50BA	3172	FRANK P. SANDERS	110 SQ. FT.			
C-52BA	2653	MOFFET L.T. & B	70 SQ. FT.			
C-53BA	3407	DOLLAR SAVINGS & TRUST CO.	20 SQ. FT.			
C-54CA	9508	RALPH M. McCRACKEN	70 SQ. FT.			
C-56BA	5722	" " "	8 SQ. FT.			
C-57BA	OL 379	D.H. LEVY & S. DUNGER	164 SQ. FT.			
C57B-WA	OL 379	" " " "		YES	YES	
C56B-WA	5722	RALPH M. McCRACKEN		YES		

-LEGEND-
EXISTING R/W ————————
PROPOSED R/W ————————
SLOPE EASEMENT & WORK AGREEMENT LIMITS — — — — —

RIGHT-OF-WAY SALT SPRINGS ROAD

PARCEL Nº	LOT Nº	NAME	AREA OF TAKING HIGHWAY EASEMENT


REVISIONS


REV. NO.	NATURE OF REVISION	DATE	MADE BY	DATE COMP.
# 1	DELETED - C-55-A, C-53-B-WA, C-53-WA 221-A, C-54-BA	3-31-60	J.D.P.	

R/W EDWARDS ST.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	

491
492





℄ CURVE DATA

Δ = 21°40'12"
R = 261.24'
T = 50.00'
L℄ = 98.80'

-LEGEND-

EXISTING R/W ————————
PROPOSED R/W ————————
SLOPE EASEMENT & WORK AGREEMENT LIMITS — — — — —

RIGHT-OF-WAY HIGH STREET


PARCEL NO	LOT NO	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	WORK AGREEMENT DRIVEWAY	WORK AGREEMENT OTHER
C-22WA	3921	T. SAADI			YES	
C-23WA	3920	T. SAADI			YES	
C-24A	2363	EXIE SCRUGGS	500 SQ. FT.			
C-25A	2357	EMMA JANE MCCORKLE	500 SQ. FT.			
C-26WA	2327	CLIFTON DOUGLAS-LUCY ANN PARKER			YES	
C-27WA	2326	RUBY B. CHEIRS			YES	
C-28WA	1929	HATTIE BRADLEY			YES	
C-29A	2355	J.B. & H. COLLIER	250 SQ. FT.			
C-30A	2356	LAWRENCE & BEATRICE SMITH	250 SQ. FT.			
C-31A	876	TOFFIC SAADI	415 SQ. FT.			
C-33A	5662	WALTER & WILLO LEE FLIPPING	143 SQ. FT.			
C-33WA	5662	" " " "		YES		RETAIN. WALL
C-34A	5663	IDA BELLE PEARSON	188 SQ. FT.			
C-34WA	5663	" " "		YES	YES	
C-35A	5664	MARY CANNELL	200 SQ. FT.			
C-35WA	5664	" "		YES		CONC. STEPS
C-36A	5724	ANNA CENTRIC	300 SQ. FT.			
C-37A	5725	ALVIN & JOSEPHINE CLARK	300 SQ. FT.			
C-38A	55074	ANDERSON & OLA MAE JOHNSON	415 SQ. FT.			
C-39A	55077	MATTIE HART	57 SQ. FT.			
C-39WA	55077	" "		YES		
C-40A	848	CLARA WASHINGTON	437 SQ. FT.			
C-40WA	848	" "		YES		
C-41A	5650	UNION NATIONAL BANK TRUST	256 SQ. FT.			
C-42WA	1578	DOZIER RENAH-JAMES JACKSON		YES		
C-43WA	5668	EMIL E. RESTLE		YES		
C-44A	57454	LINDSAY CARRIE	71 SQ. FT.			
C-44WA	57454	" "		YES	YES	
C-45WA	57455	" " "		YES		
C-35B	5665		200 SQ. FT.			


REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
# 1	REVISED AREA OF TAKING PC'LS. C-24-A C-25-A, C-34-A, C-41-A, C-44-A		

R/W HIGH ST.

FED. RD.	STATE	PROJECT	
2	OHIO	MAH-18-17.20	


492/492





RIGHT OF WAY WOODLAND AVE. WEST

BUILDINGS	PARCEL NO.	LOT NO.	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
	C-46A	2316	NATIONAL CITY BANK OF CLEVE., TR.	1370 SQ. FT.			
	C-46WA	2316	" " " " "		YES	YES	WALL
	C-47A	2000	FIRESTONE TIRE & RUBBER, AKRON, OHIO	450 SQ. FT.			
	348A	2308	JOHN PAUL	450 SQ. FT.			
	348WA	2308	" "		YES	YES	
PORCH	350A	2300	JOHN & ANN BUDAKER	744 SQ. FT.			
	350-WA	2305	"			YES	
	C-47WA	2000	FIRESTONE TIRE & RUBBER, AKRON, OHIO		YES		



RIGHT OF WAY WOODLAND AVE. EAST

PARCEL NO.	LOT NO.	NAME	AREA OF TAKING HIGHWAY EASEMENT	WORK AGREEMENT SLOPE	DRIVEWAY	OTHER
C-60A	3371	THEO. R. CLAPP	372 SQ. FT.			
C-60WA	3371	" " "		YES		
C-61A	10101	FRED SHUTRUMP	268 SQ. FT.			
C-61WA	10101	" "		YES		
C-62A	1692	BEATRICE B. LOPEZ	630 SQ. FT.			
C-62WA	1692	" " "		YES		
C-63A	1691	NATHAM DARSKY	662 SQ. FT.			GARAGE
C-63WA	1691	" "		YES		
C-64A	1690	FRED WALLACE HUGHES	662 SQ. FT.			
C-64WA	1690	" " "		YES		
C-65A	1689	GEORGE & K. KONIESCKY	662 SQ. FT.			
C-65WA	1689	" " " "		YES	YES	

REVISIONS		DATE COMP.	
REV. NO.	NATURE OF REVISION	DATE	MADE BY
# 1	ADDED 350-WA; ADDED W/A FOR DRIVES FOR C-348-WA, C-65-WA. DELETED C-66-A	3-31-60	J.D.P.

-LEGEND-
EXISTING R/W ———
PROPOSED R/W ———
SLOPE EASEMENT & WORK AGREEMENT LIMITS — — — —

R/W WOODLAND AVE. WEST & EAST

TE-54-A
200-8-57

LEGEND FOR PROJECT-AVERAGE RESULTS OF TESTS- 111 SAMPLES TESTED

DESCRIPTION	H. R. B. CLASS	OHIO CLASS	% AGG.	% C. SAND	% F. SAND	% SILT	% CLAY	LIQUID LIMIT	PLASTICITY INDEX	WATER CONTENT	SAMPLES TESTED
Gravel or stone fragments	A-1-a (0)	A-1-a	68	13	10	6	3	NP	NP	13	30
Gravel or stone fragments with sand	A-1-b (0)	A-1-b	48	18	17	11	6	NP	NP	13	54
Fine sand	A-3 (0)	A-3	4	16	70	8	2	NP	NP	26	1
Coarse and fine sand	----	A-3a	11	22	49	13	5	NP	NP	16	24
Gravel or stone fragments with sand and silt	A-2-4 (0)	A-2-4	42	13	18	17	10	22	4	14	44
Gravel or stone fragments with sand, silt, and clay	A-2-6 (0)	A-2-6	54	15	10	11	10	29	13	15	8
Sandy silt	A-4 (4)	A-4a	19	8	20	34	19	23	5	15	155
Silt	A-4 (8)	A-4b	3	2	7	63	25	15	4	23	54
Elastic silt and clay with organic material	A-5 (9)	A-5	0	2	13	59	26	47	10	38	1
Silt and clay	A-6 (8)	A-6a	14	4	10	36	36	30	12	19	31
Silty clay	A-6 (10)	A-6b	6	3	9	42	40	35	16	22	5
Elastic clay	A-7-5 (17)	A-7-5	0	2	3	17	78	61	23	25	1
Clay	A-7-6 (11)	A-7-6	8	1	2	35	54	43	17	25	8
Slag or Cinders - fill material				CLASSIFIED BY VISUAL INSPECTION							1
Random fill (Glass, Bricks, Slag, Cinders & Ashes)				CLASSIFIED BY VISUAL INSPECTION							20
Sandstone				CLASSIFIED BY VISUAL INSPECTION							
Shale				CLASSIFIED BY VISUAL INSPECTION							4

Auger boring-plan view.

Drive sample-core boring-plan view.

Auger boring plotted to vertical scale only.

Water content nearly equal to or greater than liquid limit.

Number of blows for "Standard Penetration" test.
X=number of blows for the first 6 inches.
Y=number of blows for the second 6 inches.

NOTE: Figures beside borings indicate water content in percent as %

Sod and/or Topsoil=X'=Approximate depth.

Berm material

W——Free water

Small vertical figures beside borings indicate loss on ignition in percent, as 15 %

Moisture Density Samples
Lab. Nos. So.
11243 - 11244 incl.

Samples Tested
Lab. Nos. So.
11183- 11248 incl | 11581- 11594 incl.
11646- 11648 incl | 11694- 11785 incl.
12146- 12164 incl | 12219- 12241 incl.
12284- 12302 incl | 12419- 12422 incl.
12609- 12644 incl, 1 | 13172- 13180 incl.
14478- 14527 incl, 3 | 15133- 15740 incl.
16191- 16201 incl, 3 | 16354- 16377 incl.
16386- 16429 incl | 19466- 19480 incl.
19566- 19599 incl, 1 | 20097- 20103 incl.
[illegible] 20251 incl.
14478 - [illegible] 1.
[illegible] - [illegible] 1.
[illegible] - [illegible] 1.
[illegible] - [illegible] incl.
[illegible] - [illegible] 1.


MICROFILMED
SEP 19 1985

SOIL PROFILE
MAHONING COUNTY
MAH-18- 17.20
STATE HIGHWAY TESTING AND RESEARCH LABORATORY
O. S. U. CAMPUS, COLUMBUS, OHIO

I / 19

NOTE: INFORMATION SHOWN BY THIS SUBGRADE PROFILE WAS OBTAINED SOLELY FOR USE IN ESTABLISHING DESIGN CONTROLS FOR THE PROJECT; THE STATE OF OHIO DOES NOT GUARANTEE THE ACCURACY OF THIS DATA AND IT IS NOT TO BE CONSTRUED AS A PART OF THE PLANS GOVERNING CONSTRUCTION OF THE PROJECT.

I-1108 (1) old
FED. NO. I-680-9(1)222



LOCATION MAP

Recon- P.A.H.- Jan. 6, 1959
Core- W.A.M., K.D.E., W.L.T.- February 25, 1959
Auger- D.J.H., C.A.S., A.R.S., M.H.- February 26, March 2, April 1, May 12, 13, 1959
Drafting- J.H.W. June 15, 1959

REVISION

Drilling- W.L.T., H.E.H.- 4/22/59 to 5/13/59
Drafting- M.H.- 9/11/59

INDEX

ITEM	DRAWING SHEET NUMBER
LEGEND	1
SUMMARY OF SOIL TEST DATA	2-N
SUPPLEMENTARY SOIL TEST DATA	4A
PLAN VIEW	
Sta. 914+00 to 946+00	5
Sta. 946+00 to 978+00	6
Sta. 978+00 to 1010+00	7
Sta. 1010+00 to 1037+00, 804+79 to 800+00	111
Ramp A	5
Ramp B	5
Ramp C	5-A?
Ramp D	5-A?
Ramp E	7
Ramp F	9
Ramp G	9
Ramp H	9
Ramp J	9
Ramp K	9
Ramp L	9
Ramp M	9
Ramp N	9
Relocated Sullivan St.	9
Test Borings Road Sewer Line	9
Central Parking Lot	9
LOGS OF BORINGS	
Test Borings Road Sewer Line	9
Test Borings Parking Lot	9

ITEM	DRAWING SHEET NUMBER
PROFILE	
Sta. 914+00 to 946+00	6
Sta. 946+00 to 978+00	8
Sta. 978+00 to 1010+00	10
Sta. 1010+00 to 1037+00, 804+79 to 800+00	12
Ramp A	13
Ramp B	14
Ramp C	15
Ramp D	16
Ramp E	17
Ramp F	17
Ramp G	17
Ramp H	17
Ramp J	18
Ramp K	18
Ramp L	19
Ramp M	19
Ramp N	19
Relocated Sullivan St.	19
CROSS SECTIONS	
Sta. [illegible]	10
Sta. 100+00	10
Sta. 101+00	11
Sta. [illegible]	12
Sta. 102+00	12
Sta. [illegible]	12
Sta. [illegible] Ramp K	15
Sta. [illegible] Ramp D	15

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

STATE HIGHWAY TESTING AND RESEARCH LABORATORY
O. S. U. CAMPUS, COLUMBUS, OHIO

2/19

SUMMARY OF SOIL TEST DATA

NOTE:: NP shown in Liquid Limit and Plasticity Index columns indicates that the material is non-plastic.
*Denotes sample taken at or near grade.

STATION & OFFSET		DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS.
918+20	CL	0.3-16.0	Random Fill							37	Visual
		10.0-13.0	13	7	19	39	22	24	8	18	A-4a
		13.0-16.0	48	7	17	21	7	NP	NP	11	A-2-4
919+00	CL	20.0-25.0	11	9	22	44	14	NP	NP	15	A-4a
920+75	CL	0.4-2.0	4	3	9	40	44	36	16	27	A-6b
		2.0-8.0	16	7	25	33	19	20	6	16	A-4a
		8.0-13.0	17	9	19	40	15	20	6	13	A-4a
		13.0-21.0	8	8	21	45	18	19	4	14	A-4a*
		21.0-26.0	7	6	19	42	16	NP	NP	14	A-4a
922+10	120'Lt	0.3-4.0	15	8	16	35	26	24	9	13	A-4a
		4.0-10.0	19	7	13	46	15	19	2	12	A-4a
		10.0-20.0	11	7	31	41	10	NP	NP	11	A-4a*
924+00	CL	0.3-3.0	4	5	11	37	43	34	6	24	A-4a
		3.0-8.0	15	7	18	37	23	25	11	14	A-6a
		8.0-13.0	17	9	27	34	13	NP	NP	12	A-4a
		13.0-17.0	8	5	22	51	14	NP	NP	14	A-4b
927+00	15'Lt	0.3-5.0	7	6	17	44	26	26	11	26	A-6a
		5.0-11.0	17	10	20	38	15	22	7	16	A-4a
		11.0-22.0	8	7	26	39	20	20	4	13	A-4a*
930+40	15'Lt	0.4-6.0	6	8	15	43	28	28	12	15	A-6a
		6.0-10.0	Random Fill							15	Visual
		10.0-16.0	12	6	16	37	29	27	9	18	A-4a
		16.0-25.0	37	12	16	21	14	22	6	19	A-2-4*
		25.0-30.0	38	22	19	15	6	NP	NP	11	A-1-b
933+60	CL	0.4-8.0	13	10	22	31	24	24	7	13	A-4a
		8.0-13.0	21	13	19	34	13	NP	NP	14	A-4a
		13.0-14.0	14	8	10	45	23	20	4	12	A-4a
		14.0-22.0	9	8	24	40	19	NP	NP	13	A-4a*
		22.0-27.0	58	8	10	16	8	22	5	12	A-1-b
		27.0-30.0	3	32	42	14	9	NP	NP	5	A-3a
936+00	CL	12.0-14.0	10	7	16	39	28	24	8	11	A-4a
		20.0-30.0	13	8	20	42	17	19	1	13	A-4a*
938+00	CL	0.3-6.0	7	11	18	40	24	24	7	12	A-4a
		6.0-13.0	14	6	14	38	28	28	8	14	A-4a
		13.0-19.0	9	7	14	42	28	27	10	14	A-4a*
		19.0-22.0	17	8	16	37	22	22	7	12	A-4a
		22.0-25.0	12	7	14	39	28	23	6	14	A-4a*
941+00	CL	11.0-17.0	2	11	61	20	6	NP	NP	13	A-3a
		17.0-20.0	0	1	15	75	9	NP	NP	25	A-4b
944+75	CL	0.3-2.0	30	18	23	15	14	20	3	14	A-2-4
		2.0-8.0	40	13	24	16	7	NP	NP	17	A-1-b
		8.0-9.0	8	10	31	36	15	25	5	29	A-4a
		9.0-13.0	44	13	21	13	9	NP	NP	20	A-1-b
		13.0-17.0	13	14	53	14	6	NP	NP	23	A-3a
		17.0-25.0	39	25	26	7	3	NP	NP	13	A-1-b
947+20	15'Rt	0.4-6.0	15	9	16	36	24	27	10	13	A-4a
		6.0-9.0	5	4	14	61	16	NP	NP	16	A-4b
		9.0-25.0	30	17	20	25	8	NP	NP	11	A-2-4
951+00	90'Rt	0.0-6.0	10	8	18	38	26	26	8	18	A-4a
954+00	CL	0.5-8.0	31	10	19	28	12	22	3	17	A-4a
		8.0-20.0	70	20	4	6	0	NP	NP	6	A-1-a
957+25	15'Lt	0.3-5.0	41	28	17	7	7	NP	NP	10	A-1-b
		5.0-15.0	57	30	9	2	2	NP	NP	5	A-1-a
959+50	CL	0.4-5.0	0	0	1	74	25	29	2	26	A-4b
		7.0-8.0	12	2	5	51	30	27	9	21	A-4b
		8.0-25.0	38	34	18	7	3	NP	NP	6	A-1-b*
961+80	CL	6.0-20.0	48	3	16	20	13	23	7	8	A-2-4*
		20.0-25.0	25	4	5	36	30	37	14	14	A-6a

STATION & OFFSET		DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS.
964+00	15'Rt	6.0-10.0	65	14	10	7	4	23	7	16	A-2-4
		10.0-12.0	40	10	12	20	18	26	6	17	A-4a
		12.0-13.0	42	3	5	34	16	29	11	12	A-6a
965+45	CL	0.4-5.0	27	12	22	29	10	NP	NP	15	A-4a
		5.0-8.0	27	11	24	24	14	NP	NP	15	A-4a
		8.0-10.0	0	2	13	59	26	47	10	38	A-5*
		10.0-16.0	0	0	22	54	24	NP	NP	25	A-4b
		16.0-17.0	35	10	10	21	24	31	12	17	A-6a
968+70	100'Lt	0.3-5.0	18	7	21	37	17	25	3	13	A 4a
		5.0-10.0	17	2	6	33	42	44	17	13	A-7-6
969+60	125'Rt	0.3-6.0	63	9	11	11	6	25	5	13	A-1-b
971+00	CL	0.4-3.0	17	9	21	33	20	24	6	16	A-4a
		3.0-9.0	53	19	14	9	5	NP	NP	12	A-1-a
		9.0-13.0	76	8	7	6	3	NP	NP	8	A-1-a
974+00	50'Rt	2.0-4.0	16	28	38	12	6	NP	NP	12	A-3a
		13.0-23.0	56	23	6	9	6	31	14	17	A-2-6
		23.0-30.0	16	8	19	31	26	29	9	19	A-4a
975+00	25'Lt	0.5-1.0	47	12	11	17	13	29	5	18	A-2-4
		1.0-2.5	4	1	1	62	32	29	1	6	A-4b
		2.5-12.0	0	0	0	66	34	30	8	25	A-4b*
		12.0-14.0	11	6	30	28	25	24	8	19	A-4a*
		14.0-17.0	6	1	3	24	66	43	16	23	A-7-6
		17.0-19.0	0	1	10	40	49	30	11	20	A-6a
976+00	10'Rt	0.4-5.0	73	3	3	11	10	35	16	13	A-2-6*
		5.0-10.0	6	1	1	53	39	34	9	26	A-4b
979+85	20'Rt	3.0-7.0	17	8	14	37	24	29	9	18	A-4a
983+50	CL	0.4-5.0	3	2	6	49	40	36	11	29	A-6a
		5.0-9.0	9	1	3	51	36	42	19	26	A-7-6
		9.0-17.0	55	19	9	11	6	28	11	16	A-6a
		17.0-20.0	12	10	64	13	1	NP	NP	9	A-3a
		20.0-30.0	58	25	4	11	2	NP	NP	11	A-1-a
987+20	CL	0.6-5.0	21	11	13	36	19	21	7	17	A-4a
		5.0-12.0	27	11	22	27	13	20	6	17	A-4a
		12.0-17.0	22	10	27	25	16	NP	NP	16	A-4a
		17.0-20.0	47	9	19	19	6	NP	NP	14	A-1-a
		20.0-24.0	33	11	20	27	9	NP	NP	13	A-4a
989+05	CL	0.6-3.0	37	10	11	25	15	23	6	15	A-4a*
		3.0-7.0	0	1	1	61	37	28	8	26	A-4b
		7.0-10.0	0	1	0	43	56	26	11	26	A-6a
		10.0-15.0	49	20	20	6	5	NP	NP	6	A-1-b
992+50	CL	0.4-3.0	35	36	19	8	2	NP	NP	11	A-1-b
		3.0-4.0	60	8	10	15	7	NP	NP	16	A-1-b
995+20	CL	0.6-5.0	28	10	28	23	11	NP	NP	13	A-2-4
		5.0-12.0	14	7	18	40	21	22	6	19	A-4a
		12.0-14.0	48	10	16	14	12	20	7	19	A-2-4
		14.0-23.0	8	6	18	60	8	NP	NP	25	A-4b
996+15	CL	0.5-3.0	30	10	23	21	16	20	3	14	A-4a
		3.0-7.5	0	1	8	50	40	33	15	21	A-6a
		7.5-11.0	40	13	21	16	10	19	4	9	A-2-4
		11.0-17.0	58	24	6	7	5	27	10	13	A-2-4
		17.0-20.0	38	38	18	5	1	NP	NP	8	A-1-b
997+50	24'Rt	0.6-5.0	33	9	23	22	13	20	6	15	A-2-4
		5.0-7.0	69	7	9	9	6	21	8	12	A-2-4
1001+00	20'Rt	0.4-7.0	10	19	18	33	20	23	8	22	A-4a
		7.0-9.0	65	10	9	9	7	25	10	9	A-2-4
1005+45	45'Lt	0.6-7.0	15	8	22	35	20	22	7	18	A-4a
		7.0-12.0	0	0	9	62	29	25	9	27	A-4b
		12.0-18.0	30	24	32	7	7	NP	NP	16	A-1-b
		18.0-30.0	45	14	20	13	8	19	4	18	A-1-b

STATION & OFFSET		DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS.
1009+55	72'Rt	0.4-2.0	Random Fill							13	Visual
		2.0-7.5	49	14	20	13	4	NP	NP	10	A-1-b
1010+50	15'Rt	0.4-6.0	48	6	14	21	11	25	8	15	A-2-4
		6.0-11.0	Random Fill							14	Visual
		11.0-15.0	Random Fill							18	Visual
		15.0-20.0	74	8	9	6	3	NP	NP	8	A-1-a
		20.0-25.0	34	38	20	8	0	NP	NP	16	A-1-b
		25.0-30.0	67	20	8	4	1	NP	NP	10	A-1-a
1011+00	CL	0.4-13.0	Random Fill							15	Visual
1012+50	90'Rt	0.0-3.0	Random Fill							26	Visual
		3.0-13.0	Random Fill							18	Visual
		13.0-21.0	Random Fill							5	Visual
Moisture Density		0.0-13.0	Random Fill							17	Visual
1013+00	135'Lt	0.6-7.0	54	13	16	10	7	NP	NP	16	A-1-b
		7.0-12.0	48	18	18	10	6	NP	NP	16	A-1-b
		12.0-25.0	50	20	17	7	6	NP	NP	12	A-1-a
1016+50	40'Rt	0.4-10.0	Slag							4	Visual
1017+00	80'Lt	0.0-4.0	60	26	9	5	0	NP	NP	6	A-1-a
		4.0-10.0	38	17	13	16	16	28	11	16	A-2-6
		10.0-13.0	13	23	53	9	2	NP	NP	23	A-3a
		13.0-17.0	4	6	37	37	16	NP	NP	16	A-4a
		17.0-18.0	10	14	38	26	12	18	3	12	A-4a
1019+00	CL	0.4-4.0	0	0	2	36	62	43	14	28	A-7-6
		4.0-6.0	0	1	2	40	57	41	12	22	A-7-6
		6.0-18.0	0	1	1	51	47	28	6	22	A-4b
1020+40	55'Lt	0.4-3.0	37	9	22	20	12	19	6	17	A-2-4
		3.0-6.0	23	10	35	22	10	NP	NP	15	A-2-4
		6.0-10.0	46	13	19	12	10	21	5	15	A-1-b
		10.0-15.0	9	19	37	26	9	NP	NP	21	A-3a
		15.0-18.0	17	10	23	26	14	NP	NP	14	A-4a
		18.0-21.0	10	10	65	10	5	NP	NP	20	A-3a
		21.0-27.0	39	18	34	8	1	NP	NP	16	A-1-b
		27.0-31.0	33	6	20	29	12	17	5	12	A-4a
1020+40	CL	0.4-7.0	Random Fill							18	Visual
		7.0-13.0	19	10	25	33	13	18	1	14	A-4a
		13.0-18.0	4	8	45	33	10	NP	NP	18	A-4a*
		18.0-22.0	7	2	14	38	39	24	11	18	A-6a*
		22.0-24.0	75	2	10	12	1	NP	NP	15	A-1-a
		24.0-27.0	8	5	9	31	47	32	15	20	A-6a
		27.0-30.0	25	13	16	20	26	27	13	17	A-6a
		30.0-32.0	6	3	12	31	48	30	11	20	A-6a
1020+40	58'Rt	0.4-2.0	Random Fill							14	Visual
		2.0-7.0	13	13	39	25	10	NP	NP	13	A-3a
		7.0-14.0	77	5	11	4	3	NP	NP	9	A-1-a
		14.0-17.0	11	35	42	9	3	NP	NP	16	A-3a
		17.0-21.0	4	16	70	8	22	NP	NP	26	A-3
		21.0-23.0	2	4	23	33	38	23	11	24	A-6a
1023+25	CL	0.6-9.0	16	9	18	30	27	27	9	16	A-4a
		9.0-12.0	14	8	33	27	18	21	3	19	A-4a
		13.0-17.0	35	24	17	16	8	21	4	9	A-1-b
		17.0-24.0	44	29	11	9	7	28	11	14	A-2-6
		24.0-32.0	9	41	37	6	7	NP	NP	21	A-3a*
		32.0-38.0	55	15	21	7	2	NP	NP	15	A-1-a
1026+55	10'Lt	0.6-9.0	27	5	21	31	16	19	4	15	A-4a
		9.0-15.0	45	8	11	23	13	24	7	14	A-4a
		15.0-21.0	72	10	8	4	6	23	6	11	A-1-a*
1027+10	20'Rt	0.6-8.0	10	6	22	38	24	27	10	24	A-4a
		8.0-14.0	14	9	23	35	19	21	5	13	A-4a
		14.0-19.0	38	9	23	19	11	NP	NP	13	A-2-4*
		19.0-28.0	20	4	3	50	23	23	4	19	A-4b*
		28.0-32.0	0	1	2	56	47	27	8	18	A-4b

STATION & OFFSET		DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS.
1030+87	CL	0.6-4.0	6	7	28	34	25	23	7	14	A-4a
		4.0-12.0	19	7	26	30	18	21	2	10	A-4a
		12.0-20.0	55	4	15	17	9	19	6	7	A-4a
		20.0-23.0	24	8	26	26	16	NP	NP	13	A-4a
		23.0-27.0	0	0	2	41	57	33	13	25	A-6a
		27.0-32.0	0	0	1	50	49	30	7	23	A-4b
		32.0-34.0	83	2	5	6	4	NP	NP	18	A-1-a
1034+60	CL	0.6-7.0	18	9	23	33	17	23	10	11	A-4a
		7.0-11.0	27	7	22	26	18	22	6	9	A-4a
		11.0-16.0	18	8	25	32	17	18	4	8	A-4a
		16.0-25.0	14	1	2	50	33	28	10	9	A-4b
		25.0-26.0	Gray Shale							7	Visual
1036+30	CL	0.5-8.0	33	7	20	29	11	21	4	14	A-4a
		8.0-11.0	13	8	26	34	19	21	6	8	A-4a
		11.0-19.0	16	10	24	31	19	18	4	8	A-4a
		19.0-23.0	15	2	4	48	31	27	11	7	A-6a
		23.0-25.0	Gray Shale							5	Visual

RAMP A

0+30	12'Lt	0.3-4.0	9	8	21	44	18	22	6	19	A-4a*
		4.0-10.0	20	7	19	39	15	NP	NP	11	A-4a
4+00	35'Rt	0.4-4.0	42	10	17	19	12	29	14	21	A-2-6*
		4.0-7.0	16	9	20	40	15	21	7	13	A-4a*
		7.0-14.0	35	9	17	27	12	22	8	9	A-4a
8+00	10'Rt	0.3-4.0	18	10	16	37	19	29	8	25	A-4a
		17.0-23.0	0	7	17	69	5	NP	NP	24	A-4b
		23.0-25.0	12	8	18	46	16	19	2	15	A-4a

RAMP B (West Exit)

13+60	118'Rt	2.0-17.0	Random Fill							20	Visual
Moisture Density		2.0-17.0	Random Fill							14	Visual
14+00	50'Rt	0.5-5.0	11	4	11	38	36	29	15	18	A-6a
		5.0-12.0	11	9	23	40	17	NP	NP	14	A-4a
17+80	BL	0.4-3.0	23	9	19	26	23	31	14	18	A-6a*
		3.0-8.0	19	8	18	34	21	24	7	13	A-4a*

RAMP B (North Exit)

12+00	BL	0.5-1.0	Dark Gray, Slag, Cinders, and Soil							34	Visual
		1.0-5.0	15	6	13	40	26	27	7	22	A-4a
		5.0-13.0	28	9	18	28	17	21	6	13	A-4a
		13.0-23.0	31	19	18	20	12	20	5	11	A-2-4*
15+80	25'Lt	0.3-3.0	12	5	12	41	30	31	13	17	A-6a*
		3.0-10.0	17	7	15	40	21	23	7	14	A-4a

RAMP C

0+30	25'Lt	0.0-4.0	0	1	3	48	48	47	22	28	A-7-6
		4.0-10.0	42	4	10	24	20	29	11	16	A-6a
9+00	BL	0.4-6.0	15	7	19	42	17	26	5	16	A-4a*
10+80	25'Lt	0.4-5.0	28	18	28	16	10	NP	NP	26	A-2-4
		5.0-10.0	0	24	64	12	9	NP	NP	25	A-3a
		10.0-12.0	44	15	18	16	7	NP	NP	10	A-1-b
		12.0-25.0	73	13	7	4	3	NP	NP	11	A-1-a

RAMP D

9+00	15'Lt	0.4-4.0	34	17	19	21	9	20	2	11	A-2-4
		4.0-10.0	41	16	19	14	10	NP	NP	13	A-1-b
		10.0-25.0	42	27	14	10	7	22	7	14	A-2-4

Continued on next sheet

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

STATE HIGHWAY TESTING AND RESEARCH LABORATORY
O. S. U. CAMPUS, COLUMBUS, OHIO

3
19

SUMMARY OF SOIL TEST DATA (Continued)

NOTE: NP shown in Liquid Limit and Plasticity Index columns indicates that the material is non-plastic
*Denotes sample taken at or near grade

STATION & OFFSET		DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS.
					RAMP D (Continued)						
18+00	BL	6.0-13.0	18	10	13	41	18	27	6	26	A-4a
		13.0-15.0	0	1	20	55	24	NP	NP	33	A-4b
		15.0-18.0	0	1	17	66	16	NP	NP	29	A-4b
		18.0-24.0	1	2	28	56	13	NP	NP	26	A-4b
20+40	25'Lt	7.0-12.0	57	6	12	22	3	NP	NP	30	A-1-b
		12.0-13.0	10	4	9	51	26	35	3	41	A-4b
		13.0-17.0	1	1	8	70	20	30	7	23	A-4b
		17.0-23.0	0	0	18	60	22	NP	NP	26	A-4b
					RAMP F						
0+50	BL	1.0-7.0	21	9	14	39	17	26	5	15	A-4a*
		7.0-9.0	27	19	28	19	7	NP	NP	13	A-2-4
3+00	BL	0.4-3.0	28	11	17	30	14	26	3	17	A-4a
		3.0-8.0	7	4	34	44	11	NP	NP	17	A-4a
		8.0-13.0	69	17	4	7	3	27	2	18	A-1-a*
		13.0-14.0	29	8	14	29	20	21	7	18	A-4a*
		14.0-21.0	1	0	1	82	16	NP	NP	24	A-4b*
		21.0-25.0	0	0	0	77	23	NP	NP	22	A-4b
					RAMP F						
5+10	15'Lt.	0.6-7.0	33	8	19	24	16	26	5	20	A-4a
		7.0-9.0	55	6	11	16	12	27	12	20	A-2-6
		9.0-16.0	0	2	10	50	38	30	9	23	A-4b
		16.0-23.0	0	1	3	36	60	32	14	24	A-6a
8+10	BL	0.6-4.0	16	7	17	42	18	27	8	16	A-4a
		4.0-8.0	60	18	9	7	6	26	7	11	A-2-4*
		8.0-20.0	54	19	15	8	4	NP	NP	8	A-1-b
11+00	BL	0.4-2.0	Random Fill							41	Visual*
		2.0-10.0	40	18	13	18	11	NP	NP	16	A-2-4
		10.0-13.0	19	16	20	29	16	NP	NP	16	A-4a
		13.0-15.0	10	10	13	48	19	29	2	21	A-4a
					RAMP G						
0+00	BL	0.4-5.0	0	1	2	53	44	33	7	27	A-4b*
		5.0-10.0	0	4	68	21	7	NP	NP	16	A-3a
		10.0-13.0	45	4	26	15	10	NP	NP	12	A-2-4
1+00	BL	0.4-4.0	50	13	8	15	14	31	9	13	A-2-4
		4.0-6.5	11	3	17	42	27	25	6	22	A-4a
1+00	25'Rt	0.4-3.0	16	3	36	33	12	NP	NP	17	A-4a
		3.0-6.3	20	4	26	28	22	22	8	15	A-4a
2+50	30'Lt	0.4-6.0	61	14	12	7	6	NP	NP	12	A-1-a
		6.0-15.0	48	25	7	13	7	21	7	12	A-2-4
					RAMP H						
4+75	10'Rt	0.4-4.0	59	17	11	8	5	NP	NP	14	A-1-a
		4.0-12.0	8	9	711	8	4	NP	NP	7	A-3a
		12.0-17.0	27	31	39	6	7	NP	NP	23	A-3a*
		17.0-19.0	18	9	14	33	26	28	8	19	A-4a
		19.0-20.5	21	18	26	20	15	22	7	19	A-2-4
9+40	40'Rt	0.6-4.0	9	5	17	50	19	NP	NP	20	A-4b
		4.0-7.0	57	14	12	11	6	25	5	13	A-1-b
		7.0-13.0	68	4	10	11	7	22	3	12	A-1-b
		13.0-15.0	60	6	13	12	9	18	2	9	A-1-b
11+25	105'Rt	0.5-3.0	0	2	10	48	40	33	15	21	A-6a
		3.0-8.0	56	15	10	11	8	30	12	12	A-2-6
		8.0-14.5	32	9	16	28	15	25	5	16	A-4a
		14.5-22.0	42	13	15	17	13	26	10	9	A-2-4
		22.0-30.0	40	25	15	12	8	20	3	13	A-1-b

STATION & OFFSET		DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS
					RAMP J						
11+00	BL	0.6-4.0	57	18	9	10	6	22	6	9	A-1-b
		4.0-9.0	0	2	8	43	47	35	16	23	A-6b
		9.0-15.0	64	18	6	5	7	24	8	15	A-2-4
15+00	45'Rt	0.6-4.0	36	10	8	28	18	24	7	17	A-4a
		4.0-9.0	0	2	8	63	27	27	10	21	A-4b
		9.0-15.0	67	19	6	3	5	26	15	11	A-2-6
					RAMP K						
15+40	25'Lt	0.4-4.0	9	3	13	44	33	26	3	21	A-4a
		4.0-11.0	8	2	8	50	32	34	18	23	A-6b
		11.0-15.0	68	5	11	10	6	23	6	25	A-1-b
					RAMP L						
0+00	20'Rt	0.4-4.0	12	10	20	36	22	23	4	12	A-4a*
		4.0-9.0	35	9	18	25	13	22	6	7	A-4a
		9.0-15.0	9	7	16	42	26	22	7	14	A-4a
4+00	BL	0.4-4.0	7	6	16	43	28	29	8	20	A-4a
		4.0-8.0	42	5	14	24	15	25	7	17	A-4a
		8.0-12.0	12	9	48	23	8	NP	NP	16	A-3a*
		12.0-23.0	47	21	19	8	5	NP	NP	10	A-1-b*
					RAMP M						
9+00	BL	0.4-17.0	19	6	14	34	27	29	8	23	A-4a
		17.0-25.0	9	5	12	53	21	19	3	21	A-4b
		25.0-30.0	51	9	15	16	9	NP	NP	16	A-1-b*
		30.0-32.0	0	2	3	17	78	61	23	25	A-7-5
11+65	BL	0.4-6.0	21	5	17	43	23	26	9	19	A-4a
		6.0-13.0	8	6	25	37	24	24	9	14	A-4a
		13.0-25.0	15	8	25	34	18	19	5	11	A-4a
		25.0-30.0	29	10	22	24	15	18	4	9	A-4a*
16+25	BL	0.4-10.0	10	7	29	29	25	22	4	20	A-4a*
		10.0-13.0	16	8	28	30	18	22	8	13	A-4a*
		13.0-15.0	19	6	23	30	22	21	5	12	A-4a
		15.0-19.0	9	8	14	34	35	24	7	18	A-4a
		19.0-24.0	0	0	0	64	36	NP	NP	21	A-4b
		24.0-31.0	9	2	5	45	39	32	16	18	A-6b
					RAMP N						
0+30	50'Lt	0.6-3.0	9	10	24	38	19	20	5	20	A-4a
		3.0-10.0	29	7	38	15	11	NP	NP	16	A-2-4
		10.0-15.0	23	8	30	26	13	20	6	14	A-4a
4+00	20'Lt	0.6-8.0	11	6	14	40	29	27	9	18	A-4a
		8.0-11.0	17	20	20	28	15	20	4	15	A-4a
		11.0-14.0	19	11	19	31	20	20	2	15	A-4a
					SILLIMAN ST. RELOCATED						
9+90	25'Lt	7.0-10.0	23	7	21	31	18	22	5	14	A-4a
10+35	CL	3.0-7.0	10	6	13	34	37	31	16	20	A-6b
		7.0-10.0	11	10	20	28	21	NP	NP	16	A-4a
13+00	CL	6.0-10.0	17	8	17	40	18	24	4	15	A-4a
		10.0-15.0	23	10	21	36	10	NP	NP	15	A-4a
15+50	CL	0.5-4.0	24	9	19	36	12	NP	NP	16	A-4a*
					RELOCATED WATER AND SEWER LINES						
943+60	575'Lt	6.0-17.0	0	0	0	26	74	43	19	24	A-7-6
		17.0-25.0	47	33	7	7	6	NP	NP	10	A-1-b

STATION & OFFSET		DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS.
					RELOCATED WATER AND SEWER LINES (Continued)						
945+05	355'Lt	3.0-5.0	14	11	32	28	15	NP	NP	26	A-4a
		5.0-10.0	73	8	11	5	3	NP	NP	19	A-1-a
		10.0-20.0	56	15	21	6	2	NP	NP	18	A-1-a
947+10	205'Lt	0.4-5.0	24	15	28	20	13	NP	NP	12	A-2-4
949+85	110'Lt	0.4-7.0	3	34	49	11	3	NP	NP	15	A-3a
		7.0-13.0	29	37	21	6	7	NP	NP	20	A-1-b
		13.0-20.0	63	17	12	4	4	NP	NP	16	A-1-a
					MAH-7-14.80						
801+45	45'Rt	0.4-5.0	14	7	18	38	23	23	4	13	A-4a
		5.0-11.0	15	7	24	35	19	19	3	7	A-4a
		11.0-18.0	55	4	3	16	22	34	15	7	A-6a*
		18.0-19.5	Gray Shale							4	Visual
					SALT SPRINGS ROAD						
951+00	120'Lt	3.0-10.0	25	12	20	29	14	NP	NP	26	A-4a
		10.0-18.0	0	1	19	58	22	NP	NP	21	A-4b
		18.0-21.0	0	1	23	61	15	NP	NP	25	A-4b
		21.0-25.0	15	2	14	50	19	NP	NP	20	A-4b
		25.0-30.0	46	16	15	15	8	NP	NP	15	A-1-b
951+00	170'Lt	0.4-2.0	19	34	36	8	3	NP	NP	25	A-1-b
		2.0-10.0	46	18	15	13	8	NP	NP	18	A-1-b
		10.0-20.0	14	10	19	39	18	NP	NP	35	A-4a
		20.0-22.0	33	12	14	24	17	NP	NP	18	A-4a
		22.0-30.0	38	29	33	-10-	NP	NP		15	A-1-b
953+00	135'Lt	0.5-15.5	32	16	14	22	16	25	4	25	A-4a
		15.5-18.0	18	10	18	33	21	23	4	17	A-4a
		18.0-20.0	0	2	20	50	28	26	4	32	A-4b
		20.0-24.0	29	14	14	29	14	20	3	23	A-4a
		24.0-30.0	29	12	17	28	14	NP	NP	21	A-4a
954+90	120'Lt	1.0-6.0	27	24	24	15	10	NP	NP	14	A-1-b
		6.0-12.0	26	11	19	29	15	22	7	14	A-4a
		12.0-16.0	12	12	38	27	11	NP	NP	21	A-4a
		16.0-19.0	67	15	9	6	3	NP	NP	14	A-1-a
		19.0-30.0	54	24	15	-7-		NP	NP	13	A-1-a
					HOSPTIAL PARKING LOT						
1013+95	165'Rt	1.5-9.0	26	14	19	26	15	17	NP	11	A-4a
		9.0-14.0	42	11	15	18	14	NP	NP	15	A-2-4
		14.0-25.0	19	12	18	31	20	NP	NP	17	A-4a
		25.0-30.0	11	11	17	36	25	20	4	20	A-4a
1014+00	95'Rt	1.5-9.5	38	19	18	14	11	NP	NP	13	A-1-b
		9.5-17.0	20	9	47	15	9	NP	NP	9	A-3a
1014+95	102'Rt	1.0-7.0	24	14	17	26	19	NP	NP	12	A-4a
		7.0-14.0	20	6	14	43	17	NP	NP	20	A-4a
		14.0-20.0	6	2	8	53	31	NP	NP	21	A-4b
		20.0-22.5	21	12	22	29	16	NP	NP	19	A-4a
		22.5-27.5	39	19	30	8	4	NP	NP	9	A-1-b
1015+00	141'Rt	1.0-9.5	43	32	11	8	6	NP	NP	10	A-1-b
		9.5-20.0	39	12	23	17	9	NP	NP	15	A-2-4
1018+00	135'Rt	0.6-7.0	47	8	11	21	13	21	4	10	A-2-4
		7.0-16.0	20	11	22	29	18	NP	NP	14	A-4a
		16.0-18.0	24	24	24	17	11	NP	NP	14	A-2-4
		21.0-27.0	19	10	58	-13-		NP	NP	7	A-3a

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

STATE HIGHWAY TESTING AND RESEARCH LABORATORY
O. S. U. CAMPUS, COLUMBUS, OHIO

4 / 19

DRIVE SAMPLE SOIL TEST DATA

NOTE: NP shown in Liquid Limit and Plasticity Index columns indicates that the material is non plastic
*Denotes sample taken at or near grade

STATION & OFFSET	DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS.
929+73 58'Lt	5.0-6.0	5	2	9	54	30	21	4	23	A-4b
	10.0-11.0	10	6	13	53	18	NP	NP	24	A-4b
	15.0-16.0	45	16	10	23	6	NP	NP	11	A 2-4 *
	25.0-26.0	47	14	22	14	3	NP	NP	11	A-1-b *
	30.0-31.0	14	11	22	41	12	NP	NP	20	A-4a
	35.0-36.0	42	21	16	12	9	NP	NP	12	A-1-b
	40.0-41.0	49	15	15	18	3	NP	NP	11	A-1-b
	45.0-46.0	73	10	6	9	2	NP	NP	12	A-1-a
	50.0-51.0	66	9	9	4	12	NP	NP	11	A-1-b
	55.0-56.0	68	10	8	11	3	NP	NP	8	A-1-a
936+99 95'Lt	5.0-6.0	16	7	17	35	25	32	18	15	A-6b
	10.0-11.0	12	6	13	45	24	25	3	14	A-4a
	15.0-16.0	34	7	16	31	12	NP	NP	17	A-4a
	20.0-21.0	20	8	19	38	15	NP	NP	11	A-4a
	25.0-26.0	16	8	21	40	15	NP	NP	11	A-4a
	30.0-31.0	9	6	19	53	13	NP	NP	10	A-4b *
	35.0-36.0	17	11	23	37	12	NP	NP	11	A-4a
	40.0-40.6	20	11	19	36	14	NP	NP	13	A-4a
	45.0-45.6	70	11	14	5	0	NP	NP	17	A-1-a
	50.0-50.6	42	22	25	9	2	NP	NP	12	A-1-b
959+42 CL	5.0-6.0	31	9	14	32	14	NP	NP	18	A-4a
	10.0-11.0	33	25	27	13	2	NP	NP	12	A-1-b
	15.0-16.0	14	9	63	12	2	NP	NP	23	A-3a *
	20.0-21.0	24	42	20	13	1	NP	NP	15	A-1-b
	25.0-26.0	26	17	43	12	2	NP	NP	18	A-3a
	30.0-31.0	27	34	28	9	2	NP	NP	16	A-1-b
	35.0-36.0	59	14	16	9	2	NP	NP	10	A-1-a
	40.0-41.0	67	15	8	10	0	NP	NP	14	A-1-a
	45.0-46.0	0	52	31	17	0	NP	NP	28	A-3a
	51.0-52.0	56	19	10	12	3	NP	NP	9	A-1-a
968+80 CL	5.0-6.0	54	8	9	18	11	24	E	13	A-2-4
	10.0-11.0	30	4	17	31	18	23	8	15	A-4a
	15.0-16.0	Dark Gray Carbonaceous Shale							10	Visual
969+41 CL	5.0-6.0	38	6	16	20	20	25	7	20	A-4a
	10.0-11.0	7	9	16	49	19	NP	NP	11	A-4a
971+00 CL	15.0-16.0	60	5	19	16	0	NP	NP	14	A-1-b
	20.0-21.0	18	7	21	32	22	17	2	8	A-4a
	25.0-26.0	17	8	21	40	14	17	4	10	A-4a
1006+07 43'Lt	10.0-11.0	80	7	4	8	1	NP	NP	18	A-1-a
	15.0-16.0	56	14	10	14	6	NP	NP	10	A-1-b
	24.0-25.0	10	62	27	17	2	NP	NP	17	A-3a
	30.0-31.0	15	41	30	11	3	NP	NP	19	A-3a
	35.0-36.0	48	33	5	10	1	NP	NP	17	A-1-b
	40.0-41.0	67	24	16	3	10	NP	NP	18	A-1-a
	46.0-46.1	33	10	10	35	12	-	10	13	A-4a
1006+55 46'Rt	5.0-6.0	0	4	16	56	24	25	7	21	A-4b
	10.0-11.0	56	13	13	10	8	26	7	14	A-2-4
	15.0-16.0	83	5	5	6	1	NP	NP	16	A-1-a
	25.0-26.0	42	23	21	13	1	NP	NP	14	A-1-b
	30.0-30.4	48	19	13	17	3	NP	NP	12	A-1-b
1009+90 105'Rt	10.0-11.0	Random Fill							9	Visual *
	20.0-21.0	58	18	14	9	1	NP	NP	11	A-1-a
	30.0-31.0	46	41	8	5	0	NP	NP	17	A-1-b
1011+52 10'Rt	10.0-11.0	42	8	15	21	14	23	4	20	A-2-4
	15.0-16.0	51	8	18	17	6	NP	NP	16	A-1-b
	20.0-21.0	52	10	16	16	6	NP	NP	14	A-1-b
	25.0-26.0	19	35	35	10	1	NP	NP	16	A-3a

STATION & OFFSET	DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS.
1012+50 80'Rt	10.0-11.0	Random Fill							18	Visual
	30.0-31.0	Random Fill							24	Visual *
	40.0-41.0	Random Fill							17	Visual
	45.0-46.0	33	5	2	22	38	43	19	35	A-7-6
	50.0-51.0	38	1	3	21	37	32	11	34	A-6a
	55.0-56.0	0	1	1	40	58	37	14	36	A-6a
	60.0-61.0	3	24	44	16	13	NP	NP	19	A-3a
1013+90 65' Rt	10.0-11.0	Random Fill							11	Visual
	20.0-21.0	28	12	14	28	18	29	2	22	A-4a
	30.0-31.0	42	19	24	3	12	NP	NP	21	A-1-b *
	40.0-41.0	35	5	13	33	14	NP	NP	13	A-4a
	45.0-46.0	13	0	1	56	30	24	5	25	A-4b
	50.0-51.0	0	0	0	61	39	29	5	23	A-4b
	55.0-56.0	29	15	45	7	4	NP	NP	15	A-3a
1016+20 47'Rt	10.0-11.0	0	3	14	66	17	NP	NP	36	A-4b
	15.0-16.0	46	8	17	23	6	NP	NP	25	A-2-4
	20.0-21.0	21	4	11	32	32	29	11	15	A-6a
	25.0-26.0	11	1	3	57	28	26	6	19	A-4b
	30.0-31.0	0	0	1	66	33	25	6	21	A-4b *
	35.0-36.0	48	6	7	29	10	NP	NP	22	A-4a
	40.0-41.0	38	4	7	36	15	NP	NP	18	A-4a
	45.0-46.0	0	1	4	73	22	NP	NP	16	A-4b
	50.0-51.0	0	1	1	56	42	37	12	21	A-6a
1016+51 CL	10.0-11.0	73	8	12	4	3	NP	NP	12	A-1-a
	15.0-16.0	0	1	2	72	25	NP	NP	18	A-4b
	20.0-21.0	0	0	7	71	22	20	1	17	A-4b
	25.0-26.0	0	0	5	65	30	24	8	18	A-4b
	30.0-31.0	0	0	0	71	29	27	5	26	A-4b
	35.0-36.0	15	37	31	15	2	NP	NP	17	A-3a
1021+49 80'Rt	5.0-6.0	54	10	14	13	9	23	8	13	A-2-4
	10.0-11.0	80	5	9	4	2	NP	NP	14	A-1-a
	15.0-16.0	68	20	8	4	0	NP	NP	21	A-1-a
	20.0-21.0	6	31	51	10	2	NP	NP	21	A-3a
	25.0-26.0	15	23	54	7	1	NP	NP	14	A-3 *
	30.0-31.0	35	19	37	7	2	NP	NP	22	A-1-b
	40.0-41.0	22	23	46	8	1	NP	NP	18	A-3
1024+40 83'Rt	5.0-6.0	15	12	25	32	16	24	10	15	A-4a
	10.0-11.0	11	3	17	59	10	NP	NP	23	A-4b
	15.0-16.0	0	2	4	59	35	31	10	19	A-4b
	20.0-21.0	6	4	7	50	33	24	5	15	A-4b
	25.0-25.8	35	10	18	23	14	18	1	14	A-4a
	30.0-30.1	10	15	24	47	4	NP	NP	20	A-4a *
	35.0-36.0	0	1	3	46	50	29	11	20	A-6a
	40.0-41.0	0	1	5	50	44	25	6	27	A-4b
	45.0-45.1	0	0	14	77	9	NP	NP	24	A-4b
	50.0-51.0	0	4	43	36	17	NP	NP	11	A-4a
	55.0-56.0	0	0	2	62	36	25	7	19	A-4b
	60.0-61.0	0	1	1	30	68	42	17	20	A-7-6
1032+52 60'Lt	5.0-6.0	3	6	22	34	35	40	13	22	A-6a
	10.0-11.0	20	7	26	35	12	23	4	14	A-4a
	15.0-16.0	Brown Sandstone Fragments							10	Visual
	20.0-21.0	33	4	11	32	20	NP	NP	16	A-4a
	25.0-26.0	0	0	0	54	46	33	10	20	A-4b
	30.0-31.0	0	0	0	36	64	41	16	23	A-7-6 *
	35.0-36.0	0	0	0	42	58	40	11	25	A-6a
	40.0-41.0	0	0	0	35	65	48	22	30	A-7-6
	45.0-45.5	28	3	11	41	17	NP	NP	13	A-4a

STATION & OFFSET	DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS.
1034+00 15'Rt	5.0-6.0	34	7	13	24	22	25	13	18	A-6a
	10.0-11.0	34	19	21	16	10	NP	NP	13	A-2-4
	15.0-16.0	18	9	23	30	20	NP	NP	17	A-4a
	20.0-21.0	29	18	27	12	14	NP	NP	14	A-2-4
	25.0-26.0	93	1	4	0	2	NP	NP	12	A-1-a
RAMP A										
13+22 10'Rt	5.0-6.0	21	6	14	33	26	20	9	16	A-4a
	10.0-11.0	44	8	6	22	25	27	11	26	A-6a
	15.0-16.0	37	9	18	28	8	16	5	14	A-4a
	20.0-21.0	23	24	33	18	2	NP	NP	16	A-3a *
	25.0-26.0	41	15	11	27	6	NP	NP	12	A-2-4 *
	30.0-31.0	59	9	9	16	7	20	5	12	A-1-b
	35.0-36.0	60	9	7	20	4	NP	NP	12	A-1-b
	40.0-41.0	6	24	46	19	5	NP	NP	16	A-3a
	45.0-46.0	16	49	26	8	1	NP	NP	22	A-3a
	50.0-51.0	67	7	10	12	4	NP	NP	9	A-1-b
	55.0-56.0	37	24	17	19	3	NP	NP	12	A-1-b
RAMP C										
15+00 75'Lt	5.0-6.0	10	6	14	40	30	28	8	14	A-4a
	10.0-11.0	12	9	16	41	22	21	6	14	A-4a
	15.0-16.0	0	0	2	61	37	26	7	21	A-4b
	20.0-21.0	17	6	12	39	26	22	5	12	A-4a
	25.0-26.0	16	11	21	38	14	20	4	12	A-4a
	30.0-31.0	43	23	16	15	3	NP	NP	12	A-1-b
	40.0-41.0	83	9	3	4	1	NP	NP	14	A-1-a *
	45.0-45.9	39	17	18	24	2	NP	NP	13	A-2-4 *
	50.0-51.0	36	31	12	16	5	NP	NP	11	A-1-b
RAMP E										
6+00 70'Rt	5.0-6.0	18	6	17	35	24	25	4	14	A-4a
	10.0-11.0	27	7	12	37	17	23	5	15	A-4a
	15.0-16.0	64	12	11	11	2	NP	NP	16	A-1-a
	20.0-21.0	74	11	12	3	0	NP	NP	18	A-1-a
	25.0-26.0	21	8	18	32	21	26	7	17	A-4a
	30.0-31.0	0	1	0	87	12	NP	NP	27	A-4b
	35.0-36.0	0	1	0	83	16	NP	NP	30	A-4b
	40.0-41.0	0	0	0	83	17	NP	NP	25	A-4b *
	45.0-46.0	0	0	0	78	22	26	4	20	A-4b
	50.0-51.0	35	17	34	10	4	NP	NP	18	A-1-b
	55.0-56.0	17	15	56	11	5	NP	NP	14	A-3a
RAMP H										
7+60 25'Rt	5.0-6.0	63	16	8	12	1	NP	NP	10	A-1-a
	10.0-11.0	62	8	11	12	7	NP	NP	15	A-1-b
	16.0-17.0	80	7	6	6	1	NP	NP	17	A-1-a
	20.0-21.0	15	8	17	46	14	NP	NP	12	A-4a *
	25.0-26.0	0	0	1	48	51	35	11	16	A-6a *
	30.0-31.0	0	1	0	83	16	NP	NP	21	A-4b
	40.0-41.0	14	3	4	57	22	NP	NP	24	A-4b

TE-54.B
900-5-59

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

OHIO STATE HIGHWAY
TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS, OHIO

4A
19

REVISION SEPT. 11, 1959

DRIVE SAMPLE SOIL TEST DATA

NOTE: NP shown in Liquid Limit and Plasticity Index columns indicate that the material is non-plastic.

STATION & OFFSET	DEPTH FROM-TO	% AGG.	% C.S.	% F.S.	% SILT	% CLAY	L.L.	P.I.	% W.C.	SHTL CLASS
952+00 205'Lt	0.0-1.0	0	1	23	57	19	37	2	56	A-4b
	5.0-6.0	0	1	7	60	32	61	26	113	A-7-5
	10.0-10.6	75	7	11	-7-		NP	NP	18	A-1-a
	15.0-16.0	77	14	6	-3-		NP	NP	11	A-1-a
	20.0-20.6	38	13	25	16	8	NP	NP	13	A-1-b
	25.0-25.6	69	12	11	-8-		NP	NP	3	A-1-a
1009+90 70'Rt	5.0-6.0	43	7	12	23	15	25	5	18	A-4a
	10.0-11.0	30	12	17	25	16	28	10	15	A-4a
	15.0-16.0	62	16	13	-9-		NP	NP	13	A-1-a
	20.0-21.0	69	13	12	-6-		NP	NP	13	A-1-a
	25.0-26.0	36	31	24	-15-		NP	NP	15	A-1-b
	30.0-31.0	36	35	19	-10-		NP	NP	11	A-1-b
	35.0-36.0	47	16	30	-7-		NP	NP	10	A-1-b
1010+00 160'Rt	5.0-6.0	76	19	4	-1-		NP	NP	21	A-1-a
	10.0-11.0	35	28	26	-11-		NP	NP	14	A-1-b
	15.0-16.0	14	16	60	-10-		NP	NP	19	A-3
	20.0-21.0	44	29	18	-9-		NP	NP	10	A-1-b
	25.0-25.8	71	15	8	-6-		NP	NP	13	A-1-a
	30.0-31.0	68	17	10	-5-		NP	NP	13	A-1-a
	35.0-36.0	62	13	14	-11-		NP	NP	8	A-1-a
	40.0-41.0	54	17	12	9	8	NP	NP	10	A-1-b
1010+50 80'Rt	5.0-6.0	42	13	10	22	13	NP	NP	20	A-2-4
	10.0-11.0	Fill Material							21	Visual
	20.0-21.0	Fill Material							-	Visual
	25.0-26.0	Fill Material							16	Visual
	30.0-31.0	30	20	37	6	7	NP	NP	27	A-1-b
	35.0-36.0	55	11	25	-9-		NP	NP	18	A-1-b
	40.0-41.0	70	12	12	-6-		NP	NP	8	A-1-a
	45.0-46.0	55	23	10	-12-		NP	NP	6	A-1-a
1010+50 157'Rt	5.0-6.0	55	23	6	-16-		NP	NP	23	A-1-b
	10.0-11.0	71	13	8	-8-		NP	NP	14	A-1-a
	15.0-16.0	25	2	3	37	33	28	11	17	A-6a
	20.0-21.0	60	15	13	7	5	NP	NP	15	A-1-a
	25.0-26.0	42	19	32	-7-		NP	NP	13	A-1-b
	30.0-31.0	54	22	14	-10-		NP	NP	10	A-1-a
	35.0-36.0	52	22	11	-15-		NP	NP	9	A-1-a
	40.0-41.0	67	10	11	10	2	NP	NP	11	A-1-a
1012+00 60'Rt	5.0-6.0	72	22	4	-2-		NP	NP	5	A-1-a
	10.0-11.0	84	12	3	-1-		NP	NP	7	A-1-a
	15.0-16.0	Fill material							6	Visual
	20.0-21.0	50	15	15	12	18	NP	NP	11	A-1-b
	25.0-26.0	36	13	14	25	12	NP	NP	17	A-4a
	30.0-31.0	0	1	4	57	38	NP	NP	23	A-4b
	35.0-36.0	23	23	47	-7-		NP	NP	16	A-3
	40.0-41.0	63	18	8	-11-		NP	NP	9	A-1-a
	45.0-46.0	61	17	11	-11-		NP	NP	9	A-1-a
1012+17 125'Rt	5.0-6.0	64	8	12	6	10	NP	NP	12	A-1-b
	10.0-11.0	44	8	13	21	14	28	6	24	A-2-4
	15.0-16.0	63	5	5	15	12	31	10	25	A-2-4
	20.0-21.0	28	6	30	27	9	NP	NP	15	A-4a
	25.0-26.0	51	8	16	15	10	NP	NP	25	A-1-b
	30.0-31.0	Random Fill							27	Visual
	35.0-36.0	0	2	4	52	42	39	10	26	A-4b
	40.0-41.0	0	0	1	52	46	34	10	23	A-4b
	45.0-46.0	0	0	2	56	42	27	6	31	A-4b
	50.0-51.0	0	1	2	47	50	32	13	22	A-6a
1012+50 78'Lt	5.0-6.0	70	11	6	-4-		NP	NP	20	A-1-a
	10.0-11.0	73	11	12	-4-		NP	NP	13	A-1-a
	15.0-16.0	23	28	41	-8-		NP	NP	17	A-1-b
	20.0-21.0	28	31	19	4	8	NP	NP	14	A-1-b
	25.0-26.0	35	21	36	-8-		NP	NP	17	A-1-b
	30.0-31.0	47	8	17	20	8	NP	NP	20	A-2-4
	35.0-36.0	71	10	10	3	6	NP	NP	12	A-1-a
	40.0-41.0	62	18	13	-7-		NP	NP	14	A-1-a
1012+65 135'Rt	5.0-6.0	20	13	22	28	17	NP	NP	14	A-4a
	10.0-11.0	73	14	9	-4-		NP	NP	17	A-1-a
	15.0-16.0	Fill Material								Visual
	20.0-21.0	Random Fill							13	Visual
	25.0-26.0	23	6	26	32	13	NP	NP	18	A-4a
	30.0-31.0	0	0	1	80	19	NP	NP	22	A-4b
	35.0-36.0	0	1	0	37	62	39	14	24	A-6a
	40.0-41.0	49	14	23	2	12	NP	NP	13	A-1-b
	45.0-46.0	13	1	10	58	18	NP	NP	9	A-4b
1016+20 125'Rt	5.0-6.0	52	29	14	-5-		NP	NP	25	A-1-a
	10.0-11.0	15	31	44	-10-		NP	NP	10	A-3a
	15.0-16.0	43	16	31	-10-		NP	NP	12	A-1-b
	20.0-21.0	16	12	16	28	28	16	5	12	A-4a
	25.0-26.0	12	7	23	34	24	26	7	11	A-4a
1018+00 40'Lt	5.0-6.0	55	6	10	16	13	25	9	14	A-2-4
	10.0-11.0	0	1	0	65	34	NP	NP	33	A-4b
	15.0-16.0	38	26	21	8	7	NP	NP	16	A-1-b
	20.0-21.0	49	22	20	-9-		NP	NP	11	A-1-b
	25.0-26.0	53	28	13	-6-		NP	NP	12	A-1-a
	30.0-31.0	80	12	5	-3-		NP	NP	16	A-1-a
	35.0-36.0	62	16	9	10	3	NP	NP	9	A-1-a
1018+04 53'Rt	5.0-6.0	80	6	7	-7-		NP	NP	15	A-1-a
	10.0-11.0	57	10	8	9	16	26	5	15	A-1-b
	15.0-16.0	71	5	4	6	14	31	18	20	A-2-5
	20.0-21.0	0	1	22	60	17	NP	NP	27	A-4b
	25.0-26.0	5	2	50	34	9	NP	NP	21	A-4a
	30.0-31.0	0	0	28	62	10	NP	NP	29	A-4b
	35.0-36.0	0	1	45	46	8	NP	NP	22	A-4a
	40.0-41.0	8	1	4	45	42	28	11	24	A-6a
	45.0-46.0	8	1	3	43	45	28	11	19	A-6a
	50.0-51.0	4	5	6	44	41	33	11	21	A-6a

1E-54-B
600-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20
STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

5/19

Richland Ave.
Salt Springs Rd.
B&O R.R.
Bridge St.
℄ Ramp "D"
Junk Yard
Manhole
Relocated water line
Relocated sewer line
For logs of Auger borings on Sewer and Water lines see sheet 8
Wellington Ave.
Steel St.
Oneta St.
Lakeview Ave.
℄ - North Exit Ramp "B"
For profile of Ramp "B" North Exit see sheet 14
For profile of Relocated Sillimon St. see sheet 19.
Approx. limits of fill area
℄ - Relocated Sillimon St.
℄ West Exit Ramp "B" For profile of Ramp "B" West Exit see sheet 14
Connecticut Ave.
Maryland Ave.
Approx. limits of fill area
℄ - Ramp "B"
℄ - Proposed S.R. 18
For profile of Ramp "A" see sheet 13
Surface Dump
℄ - Ramp "A"
Sillimon St.
Oakwood Ave.
Evanston Ave.
Portland Ave.
Third
Second
Weeds and Brush
Weeds and Brush
℄ - Ramp "C"
For profile of Ramp "C" see sheet 15

TE-54-B
600-1-58

SOIL PROFILE

MAHONING COUNTY
MAH-18-17.20

6
19

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

980 970 960 950 940 930 920 910 900 890 880 870 860 850 840 830 820

914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946

℄ TS. =0.3 — Random Fill — Refusal (Boulders)
℄ TS. =0.4' — 37, 18, 11 — 15
℄ Sod & TS. =0.4 — 27, 16, 13, 14, 14
120' Lt. Sod & TS. =0.6' — 13, 12, 11
℄ Sod & TS. =0.3' — 24, 14, 12, 14 — Refusal (Boulders)
15' Lt. Sod & TS. =0.3' — 26, 16, 13 — Refusal
Ramp "B" West Exit
Drive Sample Boring 58' Lt. TS. =0.4' — 15 Soil Fill, 15 Random Fill, 18, 19, 11
15' Lt. — 23, 24, 8/17, 14/24, 11, 16/26, 20, 8/32, 12, 12/30, 11, 8/36, 12, 8/17, 11, 21/65, 8
Ramp "A"
℄ TS. =0.4' — 13, 14, 12, 13, 2, 5
℄ TS. =0.4' — 9/25, 15, 15/25, 14, 11/28, 17, 11, 13, 16/45, 10, 24/80, 11, 13, 50/5", 17, 50/5", 10, 50/4", 12
Drive Sample Boring 95' Lt. — 9/25, 15, 15/25, 14, 11/28, 17, 11, 13, 16/45, 10, 24/80, 11, 13, 50/5", 17, 50/5", 10, 50/4", 12
℄ TS. =0.3' — 12, 14, 14, 12, 14 — Refusol
℄ TS. =0.4' — 13, 25
℄ TS. =0.3' — 14, 17, 29, 20, 23, 13 — Hole caved at 4.0'

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

7
19

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

REVISION-SEPT. 11, 1959

Mahoning Ave. S.R. 18

Marshall St.

Rockview

Orange Ave.

Glenwood Ave.

High St.

Mill Creek Park

Mill Creek

Dam

Trees

Trees

Trees and Brush

Trees and Brush

Weeds and Brush

Weeds and Brush

Weeds and Brush

Junk Yard

Junk Yard

Junk Yard

Manhole

Relocated water line

Relocated sewer line

Salt Springs Rd.

For logs of Auger borings at Salt Springs Road see Sheet 8

Mahoning River

B.&O. R.R.

Pyles Rd.

S.R. 18

Mahoning Ave.

McKinley

Ramp "D"

Ramp "C"

Ramp "E"

Proposed S.R. 18

For profile of Ramp "D" see sheet 16

For profile of Ramp "C" see sheet 15

For profile of Ramp "E" see sheet 17

For profile of Ramp "G" see sheet 17

For Cross Section of Sta. 15+00 at Ramp "C" see sheet 15

For Cross Section of Sta. 2+50 at Ramp "D" see sheet 16

946

950

955

960

965

970

975

978

TE-54-9
600-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20


8/19

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO


REVISION-SEPT. 11, 1959

Logs of Offset Borings

For plan view see sheets 5 and 7



Auger borings for relocation of sewer and water lines



Logs of Offset Borings

For plan view see sheet 7
Auger borings at Salt Springs Road

TE-54-B
300-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

9/19

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

REVISION-SEPT. 11, 1959

Mahoning Ave. S.R. 18
Edwards St.
Marshall St.
℄ - Ramp "J"
990 ℄ - Proposed S.R. 18
978
985
995
1000
1005
1010
℄ - Ramp "F" For profile of Ramp "F" see sheet 17
For profile of Ramp "H" see sheet 17
℄ - Ramp "H"
For profile of Ramp "J" see sheet 18
West Ave.
Plum St.
City View
Smith
Hilker St.
Walter St.
Orange Ave.
Burns
Hall
Wallace
High St.
School St.
For Cross Section of Sta. 1006+07 see sheet 10
Cemetery
Coal Yard
Pike St.
Oak Hill Ave.
Dump
For Cross Section of Sta. 1009+90 see sheet 10

MICROFILMED
SEP 29 1959


TE-54-B
6OD-1-58


SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20


10
19

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

REVISION-SEPT.11,1959







TE-54-B
600-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

11/19

REVISION-SEPT. 11, 1959

Coal Yard
Pike St.
Dump
1010
15
14
13
12
11
10
9
8
7
6
5
4
3
2
1
0
1015
1020
For profile of Ramp "L" see sheet 18.
For logs of Auger borings of Proposed Parking Lot see sheet 12
For cross sections of Sta's 1010+50, 1012+50, 1013+90, 1016+20, and 1020+40 see sheet 12
Dump
℄ - Ramp "L"
Market St.
U.S.R. 62
S.R. 7
Woodland Ave. S.R. 90-164
Kyle
Marlin St.
800
804
1037
Sta Equation
Mah-18-17.20
Sta 804+00.75 Back =
Sta 804+79.04 Ahead
Mah-7-14.80
1035
Erie St.
Fulton St.
℄ - Ramp "N"
℄ - Proposed S.R. 18
Hayes Ave.
1030
℄ - Ramp "M"
For profile of Ramp "N" see sheet 19
For profile of Ramp "M" see sheet 19
1025
℄ - Ramp "K"
For profile of Ramp "K" see sheet 18
Williams
Ridge Ave.
Oak Hill Ave.
Woodland Ave.
Alley
Lakewood
Hughes
Hughes
Falls Ave.
Henry St.

MICROFILMED
SEP 19

TE-54-B
600-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20
STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

12/19

REVISION - SEPT. 11, 1959

Log of ℄ Boring
Sta. 1011+00
Sod = 0.3
Random Fill
Hole caved at 7.0

CROSS SECTION STA. 1020+40
Sod & TS=0.4'
Ground line
Random Fill
Proposed grade
Refusal
Hole caved at 17.0

CROSS SECTION STA. 1010+50
Drive Sample Boring
Approx Ground Line
Soil Fill
Random Fill
TS=0.4'
15 Soil Fill
Random Fill
* = 3" penetration

Moisture Density Sample
Sta. 1012+50 - 90' Rt.
0.0 - 13.0'
Max. Dry. Wt. 112.0 lbs./cu. ft.
Optimum Moisture 15.8 %

(Sta. 1012+17) Drive Sample Boring 125' Rt.
(Sta. 1012+65) Drive Sample Boring 135' Rt.
Drive Sample Boring 90' Rt.
Drive Sample Boring 65' Rt.
Random Fill
Soil Fill
Hole caved at 16.0'

Drive Sample Boring 47' Rt.
40' Rt. TS=0.4'
Drive Sample Boring 53' Rt.
Random Fill
Slag Fill
Hole caved at 5.0'
60' Lt.
Refusal
40' Lt.
Drive Sample Boring

Drive Sample Boring 83' Rt.
Drive Sample Boring 80' Rt.
Sod & TS=0.6'
Random Fill
Refusal
Ramp "K"
Ramp "M"
Ramp "N"
* 8.0" Penetration
** 8.0" Penetration

10' Lt
Sod & TS=0.6'
20' Rt
Slag=0.6'
Refusal (Boulders)

Drive Sample-Core Boring 60' Lt
Drive Sample-Core Boring 15' Rt
Sod & TS=0.6'
Sandstone block
Refusal
Ramp "N"
Gray clayey silt with sandstone boulders and some small gravel.
Top of Rock
Shale, gray, siliceous, micaceous, with thin interlayed argillaceous shale seams, somewhat calcareous, generally firm. Core loss 16%
Sandstone, gray, fine-grained, micaceous, firm, with clay seams. Core loss 13%
Shale, gray, siliceous, generally soft, badly broken with thick clay seams, and scattered sandstone stringers (up to 0.4' thick) Core loss 60%

℄ Sod & TS=0.5'
Sta. 1037+00.75 Back = Mah-18-17.20
Sta. 804+79.04 Ahead Mah-7-14.80
45' Rt.
Sod & TS=0.4'
Refusal

Logs of Offset Borings
For plan view see sheet 11
Auger borings at Hospital Parking Lot
15' Rt. TS=0.4'
135' Lt. TS=0.6'
165' Rt.
95' Rt.
105' Rt.
14' Rt.
135' Rt. TS=0.6'
Soil Fill
Random Fill
Hole caved at 27.0

Drive Sample Boring
Ground line
Proposed grade
CROSS SECTION STA. 1013+90
Penetration

CROSS SECTION STA. 1018+80
Drive Sample Boring
Sta. 1018+01) Lt.
Random Fill
Hole caved at 7.0
Soil Fill
Ground line
Proposed grade
(Sta. 1018+01) Drive Sample Boring
Penetration
Penetration

Sta. 1012+17 Drive Sample Boring
Sta. 1012+65 Drive Sample Boring
Random Fill

(Sta. 1018+04) Drive Sample Boring
Soil Fill
CROSS SECTION STA. 1018+00
Drive Sample Boring
Soil Fill
Proposed grade
3.0" Penetration
5.0" Penetration

(Sta. 1018+50) Drive Sample Boring
Random Fill
Slag Fill
Hole caved at 5.0'
Ground line
(Sta. 1018+39) Drive Sample Boring
Proposed grade
Slag Fill
Soil Fill


Drive Sample Boring
Soil Fill
* = 4.5" penetration

TE 54-B
800-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

13/19

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO



TE-54-B
600-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

14/19

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

Ramp "B" and Ramp "B"-West Exit

Ramp "B" West Exit

Ramp "B"-North Exit

(Sta.933+60-Ø)
45' Lt.
TS=0.4

(Sta.930+40-151 Lt.)
30' Lt.
TS=0.4

(Sta.929+73-58' Lt.)
Drive Sample Bor. 12 Rk

(Sta.927+00-151 Lt.)
43' Lt.
TS=0.3

(Sta.922+10-120' Lt.)
(Sta.12+00-Ø - Ramp "B" North Exit)
32' Lt.
Sod & TS=0.6
28' Rt.
TS=0.8

50' Rt.
TS=0.5
Sod & TS=0.4

18' Rt.
Sod & TS=0.4

8
Sod & TS=0.4

Soil Fill

Random Fill

Slag and Cinder

Refusal (Boulders)

Hole caved at 10.0'

Moisture Density Sample
Sta.13+60-18' Rt.
2.0-17.0'
Max. Dry Wt. 109.6 lbs./cu.ft.
Optimum Moisture 16.9%

(Sta.13+60-18' Rt.-
Ramp B West Exist)
55' Lt.
Sod & TS=0.4


25' Lt.
Sod & TS=0.3


8
TS=0.5


TE-54-B
60R-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20
STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO


15/19

















Ramp "C"

930
920
910
900
890
880
870
860
850
840
830

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26


TE-54-B
600-1-58


SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

16
19

REVISION-SEPT. 11, 1959








TE-54-B
600-1-58


SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20
STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

SHEET 19









TE-54-B
600-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20

18
19

STATE HIGHWAY TESTING LABORATORY
O. S. U. CAMPUS, COLUMBUS 10, OHIO

REVISION-SEPT. 11, 1959

Ramp "L"

Ramp "K"

Ramp "J"

TE 54-B
650-1-58

SOIL PROFILE
MAHONING COUNTY
MAH-18-17.20
STATE HIGHWAY TESTING LABORATORY
S. CAMPUS, COLUMBUS 10, OHIO

19/19

REVISION - SEPT. 11, 1959

Relocated Sillingan Street

Ramp "N"

Ramp "M"

(Sta. 0+30 - 25' Lt. Ramp "C")
10' Rt.
Sod & TS=0.4'
Random Fill
25' Lt.
Sod & TS=0.4'
Random Fill
Rock Layer at 17.0'
Random Fill
Cinder 1.0'
B
TS=0.5'
B
TS=0.5'
Sod & TS=0.4'
Random Fill

(Sta. 1023+25-℄)
35' Lt.
Sod & TS=0.6'

(Sta. 1026+53-10' Lt.)
35' Lt.
Sod & TS=0.6'
Refusal (Boulders)

(Sta. 1030+87-℄)
43' Lt.
Sod & TS=0.6'

(Sta. 1032+52 - 60' Lt.)
Core Sample
10' Rt.

(Sta. 1034+60-℄)
80' Rt.
Sod & TS=0.6'
Refusal

25' Lt.
Sod & TS=0.4'
Refusal

50' Lt.
Slag & Ashes=0.6'

Top of Rock

For description of Core Boring see sheet 12

* 30" Penetration
** 5.0" Penetration

B
Sod & TS=0.4'

(Sta. 1030+87-℄)
75' Lt.
Sod & TS=0.6'

(Sta. 1041+40 - 25' Lt. Ramp "K")
51' Rt.
Sod & TS=0.4'

(Sta. 1027+10 - 20 Rt.)
261' Lt.
Slag=.05'

B
Sod & TS=0.4'

		Date
Drawn by		
Checked by		
Recom. checked by		
Reviewed by		

Recommended		
Approved		
Approved		

Recommended		
Approved		
Approved		

REVISION

FINAL

PRELIMINARY