

J:\ODOT\102738.MED-3-12.00\Design\Roadway\Sheet\102738.GG00.dgn Sheet 10/9/2019 11:48:54 AM davi d-m

SHEET NUM.										PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
3	10	18	32	53	OFFICE CALCS.	01/S/2/BR	EXT	TOTAL								
<b>ROADWAY</b>																
LS						LS	201	11000	LUMP						CLEARING AND GRUBBING	3
		22				22	202	23000	22	SY					PAVEMENT REMOVED	
						180	202	23500	180	SY					WEARING COURSE REMOVED	
						180	202	23900	180	SY					CONCRETE BASE REMOVED	
	600					600	202	30000	600	SF					WALK REMOVED	
	172		288			460	202	35100	460	FT					PIPE REMOVED, 24" AND UNDER	
	3					3	202	58100	3	EACH					CATCH BASIN REMOVED	
	80					80	202	75000	80	FT					FENCE REMOVED	
				4		4	202	75610	4	EACH					VALVE BOX REMOVED	
						122	203	10000	122	CY					EXCAVATION	
						24	203	20000	24	CY					EMBANKMENT	
				22		246	268	10000	268	SY					SUBGRADE COMPACTION	
1						1	204	45000	1	HOUR					PROOF ROLLING	
	40					40	607	98000	40	FT					FENCE, MISC.:WOOD FENCE	3
	750					750	608	12000	750	SF					5" CONCRETE WALK	
				2		2	623	38500	2	EACH					MONUMENT ASSEMBLY	
						1	SPECIAL	69050100	1	EACH					MAILBOX SUPPORT SYSTEM, SINGLE	4
<b>EROSTON CONTROL</b>																
	2					2	659	00100	2	EACH					SOIL ANALYSIS TEST	
	50					50	659	00300	50	CY					TOPSOIL	
	448					448	659	00500	448	SY					SEEDING AND MULCHING, CLASS 1	
	22					22	659	14000	22	SY					REPAIR SEEDING AND MULCHING	
	22					22	659	15000	22	SY					INTER-SEEDING	
	0.06					0.06	659	20000	0.06	TON					COMMERCIAL FERTILIZER	
	0.09					0.09	659	31000	0.09	ACRE					LIME	
	2					2	659	35000	2	MGAL					WATER	
						16,327	16,327	832	30000	16,327	EACH				EROSION CONTROL	
<b>DRAINAGE</b>																
	16					16	611	02000	16	FT					8" CONDUIT, TYPE C	
	4					4	611	06100	4	FT					15" CONDUIT, TYPE C	
	41					41	611	07400	41	FT					18" CONDUIT, TYPE B	
	14					14	611	07600	14	FT					18" CONDUIT, TYPE C	
	125					125	611	10600	125	FT					24" CONDUIT, TYPE C	
	1					1	611	98470	1	EACH					CATCH BASIN, NO. 2-2B	
	2					2	611	98510	2	EACH					CATCH BASIN, NO. 2-3	
	2					2	611	99574	2	EACH					MANHOLE, NO. 3	
LS						LS	611	97300	LS						CONDUIT, MISC.: SUPPORT OF SANITARY SEWER	3
<b>PAVEMENT</b>																
						219	219	254	01000	219	SY				PAVEMENT PLANING, ASPHALT CONCRETE, 1 1/2" AVG.	
						50	50	301	46000	50	CY				ASPHALT CONCRETE BASE, PG64-22	
						39	39	304	20000	39	CY				AGGREGATE BASE	
						47	47	407	10000	47	GAL				TACK COAT	
						28	28	441	50000	28	CY				ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
				22		22	452	10010	22	SY					6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC1	

CALCULATED DAM CHECKED DPF  
**GENERAL SUMMARY**  
**MED - SR 3 - 12.00**  
 8  
 57