SHEET NUMBER								PARTICIPATION						ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
6	7	8	28	29	31	32	33	01/STR/PV	02/S<2/PV	03/NHS/PV	04/STR/BR	05/NHS/BR							
																		TRAFFIC SIGNALS	
				26				10		16				632	26501	26	EACH	DETECTOR LOOP, AS PER PLAN	29
																		MAINTENANCE OF TRAFFIC	
160										40	120			614	11110	160	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
	LUMP	LUMP								LUMP		LUMP		614	12420	LS		DETOUR SIGNING	
83								52	17	14				614	12460	83	EACH	WORK ZONE MARKING SIGN	
25								15	3	7				614	13000	25	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
					47						47			614	13202	47	EACH	BARRIER REFLECTOR, TYPE A2	
					12						12			614	13302	12	EACH	BARRIER REFLECTOR, TYPE B2	
60										30		30		614	18401	60	DAY	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6
			4.66							4.66				614	20550	4.66	MILE	WORK ZONE LANE LINE, CLASS III, 642 PAINT	
			28.66					22.24	2.78	3.64				614	21550	28.66	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
			3716					216		3500				614	23680	3716	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 642 PAINT	
			730					312	48	370				614	26610	730	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
					0.57						0.57			614	21200	0.57	MILE	WORK ZONE CENTER LINE, CLASS I, 740.06, TYPE I	
					0.92						0.92			614	22200	0.92	MILE	WORK ZONE EDGE LINE, CLASS I, 740.06, TYPE I	
					86						86			614	26400	86	FT	WORK ZONE STOP LINE, CLASS I, 740.06, TYPE I	
																		STRUCTURE UNDER 20 FOOT SPAN (WAY-94-1674)	
						62.5					62.5			517	73008	62.5	FT	RAILING (THRIE BEAM RAIL), MISC.:BRIDGE RAILING	35
																		STRUCTURE UNDER 20 FOOT SPAN (WAY-94-1830)	
						36					36			202	98100	36	EACH	REMOVAL MISC.:EXISTING PILE ENCASEMENT	34
						80					80			202	98200	80	FT	REMOVAL MISC.:JOINT SEALER	34
						LUMP					LUMP			503	11100	LS		COFFERDAMS AND EXCAVATION BRACING	
						4367					4367			509	10000	4367	LB	EPOXY COATED REINFORCING STEEL	
						21					21			511	43211	21	CY	CLASS QC1 CONCRETE, PIER, AS PER PLAN	34
						713					713			512	10300	713	SY	SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN	
						80					80			516	31000	80	FT	JOINT SEALER	
						11					11			SPECIAL	51910000	11	SY	PATCHING CONCRETE BRIDGE DECK OVERLAY WITH MICRO- SILICA MODIFIED CONCRETE	35
																		STRUCTURE UNDER 20 FOOT SPAN (WAY-94-1900)	
						3					3			202	32000	3	FT	CURB REMOVED	
						83					83			202	98200	83	FT	REMOVAL MISC.:JOINT SEALER	34
						229					229			512	10100	229	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
						166					166			516	31000	166	FT	JOINT SEALER	
						11					11			SPECIAL	51910000	11	SY	PATCHING CONCRETE BRIDGE DECK OVERLAY WITH MICRO- SILICA MODIFIED CONCRETE	35
																		STRUCTURE UNDER 20 FOOT SPAN (WAY-585-1512)	
							70				70			512	10100	70	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
							452				452			512	10300	452	SY	SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN	
							87.5				87.5			517	76300	87.5	FT	RAILING, MISC.:DEEP BEAM RAILING PANELS	35
							6				6			SPECIAL	51910000	6	SY	PATCHING CONCRETE BRIDGE DECK OVERLAY WITH MICRO- SILICA MODIFIED CONCRETE	35
																		STRUCTURE UNDER 20 FOOT SPAN (WAY-585-1649)	
							4					4		202	11300	4	CY	PORTIONS OF STRUCTURE REMOVED	34
							1					1		511	45511	1	CY	CLASS QC1 CONCRETE, ABUTMENT, AS PER PLAN	34
							3					3		511	53012	3	CY	CLASS QC2 CONCRETE, MISC.:	34
							3					3		512	33300	3	SY	TYPE A WATERPROOFING	
							55					55		516	31000	55	FT	JOINT SEALER	
							55					55		846	00100	55	FT	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	
							33					33		856	10000	33	CY	BRIDGE DECK WATERPROOFING ASPHALT CONCRETE	
																		STRUCTURE UNDER 20 FOOT SPAN (WAY-585-1851)	
							20					20		601	26000	20	CY	DUMPED ROCK FILL, TYPE B	
							1					1		613	41200	1	CY	LOW STRENGTH MORTAR BACKFILL	
																		INCIDENTALS	
														614	11000	LS		MAINTAINING TRAFFIC	
														619	16010	6	MNTH	FIELD OFFICE, TYPE B	
														623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
														624	10000	LS		MOBILIZATION	

CALCULATED MKP
CHECKED KRB

GENERAL SUMMARY

WAY-94-14.16
MED-94-0.00
WAY-585-(11.96)(14.78)

DESIGN FILE:i:\projects\86728\roadway\sheets\86728GG001.dgn
MODELNAME: Design
DATE:4/1/2015
WORKSTATION:salay