

LOCATION MAP

LATITUDE: N 41° 57′ 2″ LONGITUDE: W 81° 44′ 24″

SCALE IN MILES

0 1 2 3 4

N

PORTION TO BE IMPROVED
INTERSTATE & DIVIDED HIGHWAY
UNDIVIDED STATE & FEDERAL ROUTES
OTHER ROADS

DESIGN EXCEPTIONS:

NONE

STATE OF OHIO
DEPARTMENT OF TRANSPORTATION

WAY-94-14.16
MED-94-0.00
WAY-585-(11.96)(14.78)

VILLAGE OF DOYLESTOWN
VILLAGE OF MARSHALLVILLE
BAUGHMAN TOWNSHIP
CHIPPEWA TOWNSHIP
MILTON TOWNSHIP
WADSWORTH TOWNSHIP
MEDINA COUNTY
WAYNE COUNTY

INDEX OF SHEETS:

TITLE SHEET	1	DETECTOR LOOP GENERAL NOTES	29
STRAIGHT LINE DIAGRAM	2	LOOP DETECTOR DETAILS	30,30A,30B,30C
DESIGN DESIGNATION	2	MAINTENANCE OF TRAFFIC SUB-SUMMARY	31
GENERAL NOTES	3-5	STRUCTURE SUMMARY	32-33
MAINTENANCE OF TRAFFIC NOTES	6	STRUCTURE GENERAL NOTES	34-35
MAINTENANCE OF TRAFFIC NOTES & DETOUR MAP	7-8	STRUCTURE INFORMATION	36
MAILBOX FACILITIES	9	STRUCTURE WAY-94-1674	37
GENERAL SUMMARY	10-11	STRUCTURE WAY-94-1830	38-41
PAVEMENT AND SHOULDER DATA	12	STRUCTURE WAY-94-1900	42-43
TYPICAL SECTIONS	13-14	STRUCTURE WAY-585-1512	44-47
GUARDRAIL GENERAL NOTES	15	STRUCTURE WAY-585-1649	48-49
ROADWAY SUB-SUMMARY	16	STRUCTURE WAY-585-1851	50
GUARDRAIL DETAILS	17-25	RUMBLE STRIPES	51
CURB RAMP DETAILS	26-27	GUARDRAIL PLAN INSERT SHEETS	52-59
PAVEMENT MARKINGS/RPM SUB-SUMMARY	28		

PROJECT DESCRIPTION

THIS PROJECT WILL INCLUDE RESURFACING WITH ASPHALT CONCRETE, PAVEMENT REPAIRS, MINOR GUARDRAIL WORK, STRUCTURE MAINTENANCE, AND PAVEMENT MARKINGS.

EARTH DISTURBED AREAS

EARTH DISTURBED AREA: N/A ACRES (MAINTENANCE PROJECT)

ESTIMATED CONTRACTOR EARTH DISTURBED AREA: N/A ACRES (MAINTENANCE PROJECT)

NOTICE OF INTENT EARTH DISTURBED AREA: N/A ACRES (MAINTENANCE PROJECT)

2013 SPECIFICATIONS

THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING CHANGES AND SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PROPOSAL SHALL GOVERN THIS IMPROVEMENT.

I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF DETOURS WILL BE PROVIDED AS INDICATED ON SHEETS 7-8.

APPROVED Alan C. Brown
DATE 12-1-14 DISTRICT DEPUTY DIRECTOR

APPROVED Jerry Wray
DATE 12-2-14 DIRECTOR, DEPARTMENT OF TRANSPORTATION

ENGINEER'S SEAL:

STATE OF OHIO
KARLA R. BOHMER
E-76834
REGISTERED PROFESSIONAL ENGINEER

SIGNED: Karla R. Bohmer
DATE: 11/28/14

STANDARD CONSTRUCTION DRAWINGS

BP-3.1	7/18/14	MT-95.30	7/18/14	TC-41.20	10/18/13		
BP-4.1	7/19/13	MT-95.50	7/19/13	TC-42.20	10/18/13		
BP-7.1	7/18/14	MT-96.11	7/18/14	TC-52.10	10/18/13		
		MT-96.20	7/19/13	TC-52.20	7/18/14		
DM-4.3	7/19/13	MT-96.26	7/19/13	TC-61.30	7/18/14		
DM-4.4	7/20/12	MT-97.10	7/18/14	TC-65.10	1/17/14		
		MT-97.12	7/18/14	TC-65.11	7/18/14		
		MT-99.20	7/19/13	TC-71.10	1/17/14		
RM-1.1	7/18/14	MT-101.60	7/19/13	TC-82.10	10/18/13		
		MT-101.90	7/18/14				
		MT-105.10	7/19/13				
DBR-2-73	7/19/02						

SUPPLEMENTAL SPECIFICATIONS

800	1/21/15
821	4/20/12
832	1/17/14
846	4/18/14
856	4/18/14

SPECIAL PROVISIONS

UNDERGROUND UTILITIES
CONTACT BOTH SERVICES
CALL TWO WORKING DAYS
BEFORE YOU DIG
CALL
1-800-362-2764
(TOLL FREE)
OHIO UTILITIES PROTECTION SERVICE
NON-MEMBERS
MUST BE CALLED DIRECTLY
OIL & GAS PRODUCERS PROTECTIVE SERVICE CALL: 1-800-925-0988

PLANS PREPARED BY:

ODOT DISTRICT THREE PLANNING & ENGINEERING DEPT.

FEDERAL PROJECT NO. E090924

PID NO. 86728

CONSTRUCTION PROJECT NO.

RAILROAD INVOLVEMENT
CSX RAILROAD

WAY-94-14.16
MED-94-0.00
WAY-585-(11.96)(14.78)

DESIGN FILE: I:\projects\86728\roadway\sheets\86728GT001.dgn MODELNAME: Design
WORKSTATION: ksaloy DATE: 11/28/2014