CITY OF WADSWORTH
SINCE 1814
ENGINEERING

Utility Note—MED-57-1.48, PID 107578

Tuesday, September 21, 2021

STATUS OF REQUIRED UTILITY RELOCATIONS

There are utilities within the construction limits of the project. The status of the utility arrangements for the completion of the work prior to or in coordination with the physical construction is shown on the Utility Note below:

Bidders are advised that the following utility facilities may or may not be cleared from the construction area at the time of award of the contract. These utility facilities shall remain in place or be relocated within the limits of the project as set out below.

All station locations listed below are approximate unless otherwise stated.

City of Wadsworth – 69 kV Transmission Conductors, 12,470 Volt Distribution Conductor

The City of Wadsworth has overhead electric facilities located along the length of the construction project on Seville Road on both sides of the road. Underground electric facilities are located as shown on the plans.

City of Wadsworth Electric contact is Chad Looper at 330-335-2826.

Any power poles that need to be held during construction will be coordinated with the City of Wadsworth Electric Department.

Necessary relocations will be completed by 3/1/2022.

The following facilities will be modified or relocated:

Station	Offset	Location	Description
14+84	23	LT	Existing pole to remain.
15+31	29	RT	Existing pole to remain.
16+07	23	LT	Existing pole to remain.
17+00	28	RT	Existing pole to remain; guys and anchors on north side of the pole to be removed.
17+23	24	LT	Existing pole to remain; new guys to be placed 15' to the north and 25' to the east.
17+98	45	RT	Existing pole to remain.
18+05	50	LT	Existing pole to remain.
18+40	24	LT	Existing pole and underground conduits to be removed.
18+44	80	LT	Existing pole to remain.
18+85	61	RT	Existing pole to remain.

20+80	51	LT	Existing pole to remain.
20+80	65	RT	Existing pole to remain.
22+90	28	LT	Existing pole to remain.
22+98	38	RT	Existing pole to remain.
24+39	32	RT	Existing pole and 3phase service to remain.
25+40	50	LT	Existing pole to remain.
25+55	30	LT	Existing pole to remain.
25+80	23	LT	Existing pole to remain.

Frontier –Aerial Telephone Cable

Frontier maintains the following poles within the project limits. There are no anticipated conflicts.

Station	Offset	Location	Description
18+81	48	RT	Existing pole to remain.
20+76	54	RT	Existing pole to remain.
22+34	42	RT	Existing pole to remain.
24+10	24	RT	Existing pole to remain.

Frontier contact is Randy Howard at 330-722-9586.

Charter – Aerial Cable TV Lines

Spectrum maintains lines along the south side of Seville Road within the project limits, but there are no anticipated conflicts.

Charter contact is Christine Lienhardt at 330-633-9203.

Dominion East Gas of Ohio –Gas Mains

The Company has facilities within the project limits as shown on the plans. The Company will be relocating their facilities for the project as follows:

Station	Offset	Location	Description
18+25	42	LT	Connect new 6' MD plastic to existing line
18+25	46	LT	New 6" main
18+50	47	LT	New 6" main
19+00	49	LT	New 6" main
19+50	50	LT	New 6" main
20+00	52	LT	New 6" main

20+50	53	LT	New 6" main
20+75	55	LT	New 6" main
21+00	53	LT	New 6" main
21+50	50	LT	New 6" main
21+89	47	LT	New 6" main
22+00	47	LT	New 6" main
22+50	47	LT	New 6" main
23+00	47	LT	New 6" main
23+50	47	LT	New 6" main
24+00	47	LT	New 6" main
24+50	47	LT	New 6" main
24+56	47	LT	New 6" main
24+56	38	LT	Connect new 6' MD plastic to existing line

- The portion of existing gas line to be relocated runs from Sta. ~18+25 to Sta. ~24+60 at an offset of approximately 47' LT.
- The proposed relocation on the east leg of the intersection will be approximately 2' parallel from the existing R/W until the line reaches the existing SR 57 LA R/W. The gas line will be bored across the SR 57 LA R/W to the west leg of the intersection. The proposed relocation on the west leg will be approximately 3' parallel from the existing R/W to the next boring pit location at Sta. ~24+56. The relocated line is proposed at a typical 8' cover below existing grade.

New gas main will be installed at a minimum of 8' below existing grade. The old gas main will be abandoned in place.

A new service will be placed at 22+35 to serve the parcel to the north and another new service will be placed at 23+80 to serve the parcel to the south.

Relocation work will be complete by 3/1/2022.

Dominion East Gas of Ohio contact is Cheryl Golden 330-664-2493.

City of Wadsworth –Water Mains and Sanitary Sewers

The city owns and maintains all the water mains and sanitary sewers through the project limits. The highway contractor will perform water and sanitary work on the city's facilities as shown in the highway plans. All other water mains and sanitary lines will remain in place and active during construction. The highway contractor will need to use extreme caution while working around any active water and sanitary lines including laterals.

City of Wadsworth contact for water and sanitary sewers is Bob Leach: 330-335-2830.

CITY OF WADSWORTH
SINCE 1814
ENGINEERING

General Comments

The Contractor shall use extreme caution when working in proximity to any existing or relocated utilities. Bidders are advised that the utility relocation plans are on file and may be reviewed at the City of Wadsworth.

Sections 105.07 and 107.16 of the Department of Transportation Construction and Material Specifications Manual require, among other things, that the contractor cooperate with all utilities located within the construction limits of this project, and take responsibility for the protection of the utility property and services.