

ESTIMATED QUANTITIES					CALC.	DATE	CHK'D	DATE
ITEM	ITEM EXT.	UNIT	DESCRIPTION	ABUTMENTS	MLF	6/9/2025	MT	6/10/2025
					SUPER	GENERAL	TOTAL	SHT. REF.
202	11002	LS	STRUCTURE REMOVED, OVER 20 FOOT SPAN				LS	
503	11100	LS	COFFERDAMS AND EXCAVATION BRACING				LS	
503	21100	CY	UNCLASSIFIED EXCAVATION				70	
509	10000	LB	EPOXY COATED STEEL REINFORCEMENT	7,143	13,844		20,987	
511	34444	CY	CLASS QC2 CONCRETE, BRIDGE DECK				62	
511	33500	EACH	SEMI-INTEGRAL DIAPHRAGM GUIDE				4	
511	43512	CY	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING				75	
512	10100	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	62	198		250	
513	10201	LB	STRUCTURAL STEEL MEMBERS, LEVEL UF, AS PER PLAN				4,817	11/14
515	15020	EACH	DRAPED STRAND PRESTRESSED CONCRETE BRIDGE I-BEAM MEMBERS, LEVEL 3, TYPE 4 (100 FT)				3	
515	20000	EACH	INTERMEDIATE DIAPHRAGMS				6	
516	13900	SF	2" PREFORMED EXPANSION JOINT FILLER				121	
516	14020	FT	SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL				68	
516	44300	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE) (1'-0" x 1'-6" x 2.586" BEARING PAD & 1'-1" x 1'-7" x 1 1/2" LOAD PLATE)				6	
517	70000	FT	RAILING (TWIN STEEL TUBE)				210	
518	21200	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC				50	
518	40000	FT	6" PERFORATED CORRUGATED PLASTIC PIPE				78	
518	40012	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE				98	
524	94604	FT	DRILLED SHAFTS, 30" DIAMETER, INTO BEDROCK				56	
524	94702	FT	DRILLED SHAFTS, 36" DIAMETER, ABOVE BEDROCK				60	
601	21050	SY	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT				8	
601	32001	CY	ROCK CHANNEL PROTECTION, TYPE A WITH FILTER, AS PER PLAN				126	2/14
611	99710	EACH	PRECAST REINFORCED CONCRETE OUTLET				4	

ESTIMATED QUANTITIES
BRIDGE NO. MOE-T2214-00.414
TR2214 OVER SUNFISH CREEK

SFN
5631115

DESIGN AGENCY
fishbeck

DESIGNER
MT

CHECKER
MLF

REVIEWER
JBD 09/30/25

PROJECT ID
119037

SUBSET
3

TOTAL
14

SHEET
P.17

TOTAL
32