SHEET NUM. 3	4	5	7	9	PART. 01/NHS/PV	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
										ROADWAY	
1					1	623	39500	1	EACH	MONUMENT BOX ADJUSTED TO GRADE	
631					631	SPECIAL	69012150	631	GAL	ASPHALT REJUVENATING AGENT	3
LS					LS	SPECIAL	69012160	LS		TESTING	3
										DRAINAGE	
15					15	611	99654	15	EACH	MANHOLE ADJUSTED TO GRADE	
										PAVEMENT	
500					500	253	01001	500	SY	PAVEMENT REPAIR, AS PER PLAN	3
			14,556		14,556	254	01000	14,556	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1 3/4" DEPTH	
50					50	254	01601	50	SY	PATCHING PLANED SURFACE, AS PER PLAN	3
			1,240		1,240	407	20000	1,240	GAL	NON-TRACKING TACK COAT	
			709		709	442	00100	709	CY	ANTI-SEGREGATION EQUIPMENT	
			709		709	442	20001	709	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (448), AS PER PLAN, PG76-22M	3
										WATER WORK	
13					13	638	10800	13	EACH	VALVE BOX ADJUSTED TO GRADE	
										TRAFFIC CONTROL	
				104	104	621	00100	104	EACH	RPM	
	11				11	621	00101	11	EACH	RPM, AS PER PLAN	4
				165	165	621	54000	165	EACH	RAISED PAVEMENT MARKER REMOVED	
				0.89	0.89	644	00200	0.89	MILE	LANE LINE, 4"	
				0.49	0.49	644	00300	0.49	MILE	CENTER LINE	
				311	311	644	00400	311	FT	CHANNELIZING LINE, 8"	
				96	96	644	00500	96	FT	STOP LINE	
				1,130	1,130	644	00600	1,130	FT	CROSSWALK LINE	
				90	90	644	00700	90	FT	TRANSVERSE/DIAGONAL LINE	
				4	4	644	01100	4	EACH	SCHOOL SYMBOL MARKING, 72"	
				5	5	644	01300	5	EACH	LANE ARROW	
										TRAFFIC SIGNALS	
	1				1	632	26501	1	EACH	DETECTOR LOOP, AS PER PLAN	4
	1				1	632	27201	1	EACH	LOOP DETECTOR TIE IN, AS PER PLAN	4
										MAINTENANCE OF TRAFFIC	
		80			80	614	11110	80	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
				1.78	1.78	614	20550	1.78	MILE	WORK ZONE LANE LINE, CLASS III, 4", 642 PAINT	
				0.98	0.98	614	21550	0.98	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
				622	622	614	23680	622	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT	
				192	192	614	26610	192	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
				8	8	614	31740	8	EACH	WORK ZONE SCHOOL SYMBOL MARKING, 72", CLASS III, 642 PAINT	
					LS	614	11000	LS		MAINTAINING TRAFFIC	
					LS	624	10000	LS		MOBILIZATION	

CALCULATED TMK
CHECKED CWW

GENERAL SUMMARY

MOT-725-18.18

I:\ProjectData\MOT\102710_SR725-I815\Design\Roadway\Sheets\102710_GG001.dgn Sheet 10/7/2020 10:30:56 AM cweiss