

SHEET NUM.											PART.			ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
3	5	6	12	13	14	15					01/S>2	02/NFA			EXT	TOTAL			
											LS			201	11000	LS		ROADWAY	
																		CLEARING AND GRUBBING	
			301								170	131		202	23000	301	SY	PAVEMENT REMOVED	
			947								925	22		202	30000	947	SF	WALK REMOVED	
			123								95	28		202	32000	123	FT	CURB REMOVED	
			86								58	28		202	32500	86	FT	CURB AND GUTTER REMOVED	
			170								140	30		204	10000	170	SY	SUBGRADE COMPACTION	
				92	52						96	48		608	10000	144	SF	4" CONCRETE WALK	3
			2,213								1,267	946		608	52001	2,213	SF	CURB RAMP, AS PER PLAN	
																		EROSION CONTROL	
33											20	13		659	00300	33	CY	TOPSOIL	
300											181	119		659	00500	300	SY	SEEDING AND MULCHING, CLASS 1	
15											9	6		659	14000	15	SY	REPAIR SEEDING AND MULCHING	
15											9	6		659	15000	15	SY	INTER-SEEDING	
0.04											0.02	0.02		659	20000	0.04	TON	COMMERCIAL FERTILIZER	
0.06											0.04	0.02		659	31000	0.06	ACRE	LIME	
1.66											0.98	0.68		659	35000	1.66	MGAL	WATER	
											1,500	1,500		832	30000	3,000	EACH	EROSION CONTROL	
																		PAVEMENT	
			9								8	1		301	56000	9	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
			29								23	6		304	20000	29	CY	AGGREGATE BASE	
			12								10	2		407	20000	12	GAL	NON-TRACKING TACK COAT	
			41	1	1						25	18		411	10000	43	CY	STABILIZED CRUSHED AGGREGATE	
			6								5	1		441	70000	6	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
			6								5	1		441	70300	6	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)	
			86								58	28		609	12000	86	FT	COMBINATION CURB AND GUTTER, TYPE 2	
			147								147			609	26000	147	FT	CURB, TYPE 6	
			9								9			613	41200	9	CY	LOW STRENGTH MORTAR BACKFILL	
			1								1			638	10800	1	EACH	VALVE BOX ADJUSTED TO GRADE	
																		TRAFFIC CONTROL	
				203	231						216	218		630	03100	434	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
				5	5						6	4		630	08600	10	EACH	SIGN POST REFLECTOR	
				4							4			630	79500	4	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	
				88	125						99	114		630	80100	213	SF	SIGN, FLAT SHEET	
				1							1			630	80510	1	EACH	SIGN, STREET NAME	
				2							2			630	85100	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
				25	12						24	13		630	85200	37	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DELIVERY	
				11	7						11	7		630	86002	18	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
					2						2			630	97700	2	EACH	SIGNING, MISC.:REMOVAL AND REINSTALLATION OF BIKEWAY GUIDE SIGN AND POST, AS PER PLAN	4
				3							3			630	97700	3	EACH	SIGNING, MISC.:SOLAR-POWERED BORDER-ENHANCED LED SIGN ASSEMBLY, AS PER PLAN	3
				6	2						6	2		630	97700	8	EACH	SIGNING, MISC.:SOLAR-POWERED RECTANGULAR RAPID FLASHING BEACON SIGN ASSEMBLY, AS PER PLAN	3
						0.01					0.01			642	00104	0.01	MILE	EDGE LINE, 6", TYPE 1	
						51					27	24		642	00500	51	FT	STOP LINE, TYPE 1	
						383					270	113		642	00630	383	FT	CROSSWALK LINE, 24", TYPE 1	
						23					23			642	00700	23	FT	TRANSVERSE/DIAGONAL LINE, TYPE 1	
						365					204	161		642	30000	365	FT	REMOVAL OF PAVEMENT MARKING	
																		MAINTENANCE OF TRAFFIC	
			LS								LS			614	12421	LS		DETOUR SIGNING, AS PER PLAN	6
		LS									LS			614	11000	LS		INCIDENTALS	
											LS			623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS			624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY



CHOICE ONE ENGINEERING

DESIGNER

IJW

REVIEWER

NNS 7-18-2025

PROJECT ID

119384

SHEET

P.11

TOTAL

24