

P:\89130\Design\Roadway\Sheets\89130\_G0001.dgn Sheet 5/20/2020 3:36:59 PM mlr/tes

SHEET NUM.										PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	
OFFICE		9	20	21		66		68	70	01/NHS/OT	02/NHS/OT							
			LS								LS	201	11001	LS		ROADWAY	20	
						4					4	202	20010	4	EACH	HEADWALL REMOVED		
994											994	202	23000	994	SY	PAVEMENT REMOVED		
15,532											15,532	202	23010	15,532	SY	PAVEMENT REMOVED, ASPHALT		
						646					646	202	30700	646	FT	CONCRETE BARRIER REMOVED		
						321					321	202	32000	321	FT	CURB REMOVED		
						2					2	202	32501	2	FT	CURB AND GUTTER REMOVED, AS PER PLAN	82	
						1,233					1,233	202	35100	1,233	FT	PIPE REMOVED, 24" AND UNDER		
						9,916				6,891	3,025	202	38000	9,916	FT	GUARDRAIL REMOVED		
						9,437					9,437	202	38300	9,437	FT	GUARDRAIL REMOVED, BARRIER DESIGN		
						7				6	1	202	42001	7	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A, AS PER PLAN	20	
						4				3	1	202	42010	4	EACH	ANCHOR ASSEMBLY REMOVED, TYPE E		
						17				12	5	202	42040	17	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T		
						3				1	2	202	42050	3	EACH	ANCHOR ASSEMBLY REMOVED, TYPE B		
						17				9	8	202	47000	17	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED		
						6					6	202	47800	6	EACH	IMPACT ATTENUATOR REMOVED		
						2					2	202	58000	2	EACH	MANHOLE REMOVED		
						1					1	202	58001	1	EACH	MANHOLE REMOVED, AS PER PLAN	21	
						11					11	202	58100	11	EACH	CATCH BASIN REMOVED		
						1					1	202	58500	1	EACH	CATCH BASIN ABANDONED		
			6								6	202	67000	6	EACH	REGULATED UNDERGROUND STORAGE TANK REMOVED		
						80					80	202	75000	80	FT	FENCE REMOVED		
			LS								LS	202	98000	LS		REMOVAL MISC.: TRAFFIC MONITORING EQUIPMENT	21	
									14,065		14,065	203	10000	14,065	CY	EXCAVATION		
									518		518	203	20800	518	CY	EMBANKMENT		
											18	204	45000	18	HOUR	PROOF ROLLING		
											1,637	206	10500	1,637	TON	CEMENT		
											54,229	206	11000	54,229	SY	CURING COAT		
											54,229	206	15020	54,229	SY	CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP		
											LS	206	30000	LS		MIXTURE DESIGN FOR CHEMICALLY STABILIZED SOILS		
								7,187.5			6,075	1,112.5	606	15050	7,187.5	FT	GUARDRAIL, TYPE MGS	
								1,112.5			1,112.5		606	15100	1,112.5	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
								175			175	606	15550	175	FT	GUARDRAIL, BARRIER DESIGN, TYPE MGS		
								16			13	3	606	26150	16	EACH	ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016	
								17			15	2	606	26550	17	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
								3				3	606	35002	3	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	
								4		1	3	606	35102	4	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 2		
								3				3	606	60028	3	EACH	IMPACT ATTENUATOR, TYPE 2 (BIDIRECTIONAL), 60 MPH, 24" WIDE	
								80				80	607	23000	80	FT	FENCE, TYPE CLT	
								9,275			9,275	622	10140	9,275	FT	CONCRETE BARRIER, SINGLE SLOPE, TYPE C1		
								712			712	622	10160	712	FT	CONCRETE BARRIER, SINGLE SLOPE, TYPE D		
								1			1	622	10200	1	EACH	BARRIER TRANSITION		
								1			1	622	24850	1	EACH	CONCRETE BARRIER END SECTION, TYPE B1		
								1			1	622	24860	1	EACH	CONCRETE BARRIER END SECTION, TYPE C1		
								6			6	622	25000	6	EACH	CONCRETE BARRIER END SECTION, TYPE D		
								52			52	622	25014	52	EACH	CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE C1		
											7	623	38500	7	EACH	MONUMENT ASSEMBLY		

GENERAL SUMMARY

MOT-35-18.57  
GRE-35-0.00

P:\89130\Design\Roadway\Sheets\89130\_CS004.dgn Sheet 5/20/2020 3:37:08 PM milutes

SHEET NO.	REFERENCE NO.	STATION		SIDE	203		659	601		670								
		FROM	TO		EXCAVATION CY	EMBANKMENT CY	SEEDING AND MULCHING SY	TIED CONCRETE BLOCK MAT, TYPE 2 SY	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER CY	DITCH EROSION PROTECTION SY								
USR 35 - EARTHWORK & EROSION CONTROL																		
90-226		556+40.00	4+26.67	RT/LT	16510	518	2496											
82		601+41.00	604+35.50	LT				27										
80	EC-1	584+00.00		RT				1.33										
82	EC-2	599+50.00		RT				1.11										
83	EC-3	616+00.00		LT				1.33										
85	EC-4	643+85.00		LT				1.33										
87	EC-5	667+70.00		LT				1.33										
89	EC-6	684+24.25		RT				1.33										
89	EC-7	686+26.00	687+76.00	RT/LT						125								
90-110		DEDUCT PAVEMENT REMOVED, ASPHALT STA. 556+40.00 TO STA. 575+00.00 (EB INSIDE SHOULDER)		RT	-303													
110-226		DEDUCT PAVEMENT REMOVED, ASPHALT STA. 575+00.00 TO STA. 689+00.00 (EB & WB INSIDE / OUTSIDE SHOULDER)		RT/LT	-1906													
163-167		DEDUCT PAVEMENT REMOVED STA. 629+70.00 TO STA. 634+90.00 (FULL DEPTH)		RT	-236													
<b>TOTALS CARRIED TO SHEET 21</b>							2496											
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>					14065	518		27	7.76		125							

**EARTHWORK & EROSION CONTROL SUBSUMMARY**

**MOT -35 -18.57  
GRE -35 -0.00**

CALCULATED  
KRM  
CHECKED  
MLL

70  
310