

SHEET NUM.										PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	CALCULATED JDW	CHECKED ARM
3	5	7	20						01/STR/OT										
ROADWAY																			
										LUMP	201	11000	LS		CLEARING AND GRUBBING	3			
		6,462								6,462	203	10000	6,462	CY	EXCAVATION				
										LUMP	208	10000	LS		PRE-BLAST CONDITION SURVEY				
										LUMP	208	12000	LS		BLASTING CONSULTANT				
										LUMP	208	13000	LS		AIR BLAST AND NOISE CONTROL				
										LUMP	208	14000	LS		VIBRATION CONTROL AND MONITORING				
										LUMP	208	16000	LS		HYDROLOGIST				
EROSION CONTROL																			
		100								100	601	39501	100	FT	PAVED GUTTER, TYPE 5, AS PER PLAN	3			
		2,621								2,621	659	10000	2,621	SY	SEEDING AND MULCHING				
0.4										0.4	659	20000	0.4	TON	COMMERCIAL FERTILIZER				
0.6										0.6	659	31000	0.6	ACRE	LIME				
14.2										14.2	659	35000	14.2	MGAL	WATER				
										10,000	832	30000	10,000	EACH	EROSION CONTROL				
PAVEMENT																			
		831								831	254	01000	831	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"				
		67								67	407	20000	67	GAL	NON-TRACKING TACK COAT				
		35								35	441	50000	35	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22				
TRAFFIC CONTROL																			
		0.11								0.11	642	00104	0.11	MILE	EDGE LINE, 6", TYPE 1				
		0.11								0.11	642	00204	0.11	MILE	LANE LINE, 6", TYPE 1				
MAINTENANCE OF TRAFFIC																			
		2								2	614	12338	2	EACH	WORK ZONE IMPACT ATTENUATOR (BIDIRECTIONAL)				
		10								10	614	13310	10	EACH	BARRIER REFLECTOR, TYPE 1(BIDIRECTIONAL)				
		10								10	614	13360	10	EACH	OBJECT MARKER, TWO WAY				
		480								480	614	18600	480	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN				
										480	622	41000	480	FT	PORTABLE BARRIER, 32"				
INCIDENTALS																			
										LUMP	614	11000	LS		MAINTAINING TRAFFIC				
										LUMP	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING				
										LUMP	624	10000	LS		MOBILIZATION				
										LUMP	103	05000	LS		PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYMENT BOND				

GENERAL SUMMARY

I:\ProjectData\MRG\05021_MRG-60-10.44\Design\Roadway\Sheets\05021_GG001.dgn Sheet 3/18/2020 10:30:16 AM jwiseman