SHEET NUM. 3	5	7	20								PART.	01/STR/OT		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																		ROADWAY	
												LUMP		201	11000	LS		CLEARING AND GRUBBING	3
		6,462										6,462		203	10000	6,462	CY	EXCAVATION	
												LUMP		208	10000	LS		PRE-BLAST CONDITION SURVEY	
												LUMP		208	12000	LS		BLASTING CONSULTANT	
												LUMP		208	13000	LS		AIR BLAST AND NOISE CONTROL	
												LUMP		208	14000	LS		VIBRATION CONTROL AND MONITORING	
												LUMP		208	16000	LS		HYDROLOGIST	
																		EROSION CONTROL	
		100										100		601	39501	100	FT	PAVED GUTTER, TYPE 5, AS PER PLAN	3
		2,621										2,621		659	10000	2,621	SY	SEEDING AND MULCHING	
0.4												0.4		659	20000	0.4	TON	COMMERCIAL FERTILIZER	
0.6												0.6		659	31000	0.6	ACRE	LIME	
14.2												14.2		659	35000	14.2	MGAL	WATER	
												10,000		832	30000	10,000	EACH	EROSION CONTROL	
																		PAVEMENT	
		831										831		254	01000	831	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	
		67										67		407	20000	67	GAL	NON-TRACKING TACK COAT	
		35										35		441	50000	35	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
																		TRAFFIC CONTROL	
		0.11										0.11		642	00104	0.11	MILE	EDGE LINE, 6", TYPE 1	
		0.11										0.11		642	00204	0.11	MILE	LANE LINE, 6", TYPE 1	
																		MAINTENANCE OF TRAFFIC	
	2											2		614	12338	2	EACH	WORK ZONE IMPACT ATTENUATOR (BIDIRECTIONAL)	
	10											10		614	13310	10	EACH	BARRIER REFLECTOR, TYPE 1(BIDIRECTIONAL)	
	10											10		614	13360	10	EACH	OBJECT MARKER, TWO WAY	
												2		614	18600	2	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN	
	480											480		622	41000	480	FT	PORTABLE BARRIER, 32"	
																		INCIDENTALS	
												LUMP		614	11000	LS		MAINTAINING TRAFFIC	
												LUMP		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
												LUMP		624	10000	LS		MOBILIZATION	
												LUMP		103	05000	LS		PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYMENT BOND	

CALCULATED JDW
CHECKED ARM

GENERAL SUMMARY

MRG-60-10.44

I:\ProjectData\MRG\10502L_MRG-60-10.44\Design\Roadway\Sheets\10502L_GG001.dgn Sheet 3/18/2020 10:35:14 AM jwiseman