SHEET NUM. 4	5	8	9	12	13	14	15	16	17	PART. 01/S<2/PV	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
															ROADWAY	
							321			321	202	30000	321	SF	WALK REMOVED	
							36			36	202	32000	36	FT	CURB REMOVED	
20							24			44	202	32500	44	FT	CURB AND GUTTER REMOVED	
							11			11	203	10000	11	CY	EXCAVATION	
				7						7	209	60500	7	MILE	LINEAR GRADING	
6.44										6.44	209	72050	6.44	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING	
							450			450	608	10000	450	SF	4" CONCRETE WALK	
							378			378	608	52000	378	SF	CURB RAMP	
							91			91	608	52001	91	SF	CURB RAMP, AS PER PLAN	15
															EROSION CONTROL	
							53			53	660	30000	53	SY	SODDING UNSTAKED	
										10,000	832	30000	10,000	EACH	EROSION CONTROL	
															DRAINAGE	
2										2	611	99151	2	EACH	INLET ADJUSTED TO GRADE, AS PER PLAN	4
						9				9	611	99654	9	EACH	MANHOLE ADJUSTED TO GRADE	
															PAVEMENT	
2,171										2,171	253	02000	2,171	CY	PAVEMENT REPAIR	
				65,117	1,603					66,720	254	01001	66,720	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, 2 1/2"	4
				9,116	224					9,340	407	20000	9,340	GAL	NON-TRACKING TACK COAT	
16				1,809	45					1,870	424	12001	1,870	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B, AS PER PLAN	4
50										50	441	50000	50	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
39				2,714	67					2,820	442	20100	2,820	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 9.5 MM, TYPE A (448)	
20							8			28	609	12000	28	FT	COMBINATION CURB AND GUTTER, TYPE 2	
							11			11	609	26000	11	FT	CURB, TYPE 6	
				495						495	617	10100	495	CY	COMPACTED AGGREGATE	
				4,412						4,412	875	10000	4,412	LB	LONGITUDINAL JOINT ADHESIVE	
						10				10	638	10800	10	EACH	WATER WORK VALVE BOX ADJUSTED TO GRADE	
						1				1	638	10801	1	EACH	VALVE BOX ADJUSTED TO GRADE, AS PER PLAN	4
								327		327	621	00100	327	EACH	TRAFFIC CONTROL RPM	
								70		70	621	54000	70	EACH	RAISED PAVEMENT MARKER REMOVED	
								6.6		6.6	642	00104	6.6	MILE	EDGE LINE, 6", TYPE 1	
								3.85		3.85	642	00300	3.85	MILE	CENTER LINE, TYPE 1	
								2,275		2,275	644	00400	2,275	FT	CHANNELIZING LINE, 8"	
								206		206	644	00500	206	FT	STOP LINE	
								468		468	644	00601	468	FT	CROSSWALK LINE, AS PER PLAN	5
									606	606	644	00700	606	FT	TRANSVERSE/DIAGONAL LINE	
									34	34	644	01300	34	EACH	LANE ARROW	
									967	967	644	01500	967	FT	DOTTED LINE, 4"	
	7									7	625	31510	7	EACH	TRAFFIC SIGNALS PULL BOX REMOVED	
	2									2	632	90020	2	EACH	REMOVAL OF MISCELLANEOUS TRAFFIC SIGNAL ITEM:LOOP LEAD-IN CABLE	
	105									105	632	90500	105	FT	SIGNALIZATION, MISC.:UNLASH AND RELASH MESSENGER WIRE	5
	4									4	809	69000	4	EACH	ADVANCE RADAR DETECTION	
	7									7	809	69100	7	EACH	STOP LINE RADAR DETECTION	

CALCULATED TLM
CHECKED JMF

GENERAL SUMMARY

OTT-163-27.00

I:\ProjectData\OTT\10799_OTT_163_27.00\Design\Roadway\Sheets\10799_GG001.dgn Sheet 8/17/2020 8:18:34 AM tmaas