


| SHEET NUM. | | | | | | | | | | PART. | ITEM | ITEM | GRAND | UNIT | DESCRIPTION | SEE SHEET NO. |
|------------|----|---|---|---|----|----|----|----|--|-----------|------|-------|--------|------|--|--------------------------|
| 6 | 6A | 7 | 8 | 9 | 12 | 13 | 14 | 15 | | 01/NHS/PV | EXT | TOTAL | | | | |
| | | | | | | | | | | | | | | | (TRAFFIC CONTROL CONT.) | |
| | | | | | | | | | | 9,321 | 642 | 00404 | 9,321 | FT | CHANNELIZING LINE, 12", TYPE 1 | |
| | | | | | | | | | | 4,332 | 642 | 01510 | 4,332 | FT | DOTTED LINE, 6", TYPE 1 | |
| 20 | | | | | | | | | | 20 | 642 | 40000 | 20 | EACH | SPEED MEASUREMENT MARKING | |
| | | | | | | | | | | 484 | 644 | 00700 | 484 | FT | TRANSVERSE/DIAGONAL LINE | |
| | | | | | | | | | | 462 | 644 | 00720 | 462 | FT | CHEVRON MARKING | |
| | | | | | | | | | | 294 | 644 | 00900 | 294 | SF | ISLAND MARKING | |
| | | | | | | | | | | 17 | 644 | 01300 | 17 | EACH | LANE ARROW | |
| | | | | | | | | | | 3 | 644 | 01360 | 3 | EACH | WRONG WAY ARROW | |
| | | | | | | | | | | | | | | | STRUCTURE OVER 20 FOOT SPAN (OTT-2-1770) | |
| | | | | | | | | | | | | | | | SEE SHEET NO. 39 FOR QUANTITIES. | |
| | | | | | | | | | | | | | | | STRUCTURE OVER 20 FOOT SPAN (OTT-2-2306 L & R) | |
| | | | | | | | | | | | | | | | SEE SHEET NO. 40 FOR QUANTITIES. | |
| | | | | | | | | | | | | | | | MAINTENANCE OF TRAFFIC | |
| | | | | | | | | | | 120 | 614 | 11110 | 120 | SNMT | LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE | |
| | | | | | | | | | | 5 | 614 | 12384 | 5 | EACH | WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (BIDIRECTIONAL) | TOTAL QUANTITY REVISED |
| | | | | | | | | | | 22 | 614 | 12460 | 22 | EACH | WORK ZONE MARKING SIGN | |
| | | | | | | | | | | 20 | 614 | 12484 | 20 | EACH | WORK ZONE INCREASED PENALTIES SIGN | |
| | | | | | | | | | | 5 | 614 | 12500 | 5 | EACH | REPLACEMENT SIGN | |
| | | | | | | | | | | 15 | 614 | 12600 | 15 | EACH | REPLACEMENT DRUM | |
| | | | | | | | | | | 111 | 614 | 13310 | 111 | EACH | BARRIER REFLECTOR, TYPE 1, UNIDIRECTIONAL | TOTAL QUANTITIES REVISED |
| | | | | | | | | | | 111 | 614 | 13350 | 111 | EACH | OBJECT MARKER, ONE WAY | |
| | | | | | | | | | | 8 | 614 | 18600 | 8 | SNMT | PORTABLE CHANGEABLE MESSAGE SIGN | |
| | | | | | | | | | | 14 | 614 | 20056 | 14 | MILE | WORK ZONE LANE LINE, CLASS I, 6", 807 PAINT | |
| | | | | | | | | | | 28 | 614 | 20110 | 28 | MILE | WORK ZONE LANE LINE, CLASS I, 6", 642 PAINT | |
| | | | | | | | | | | 29 | 614 | 22056 | 29 | MILE | WORK ZONE EDGE LINE, CLASS I, 6", 807 PAINT | |
| | | | | | | | | | | 58 | 614 | 22110 | 58 | MILE | WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT | |
| | | | | | | | | | | 16,342 | 614 | 23210 | 16,342 | FT | WORK ZONE CHANNELIZING LINE, CLASS I, 12", 642 PAINT | |
| | | | | | | | | | | 8,464 | 614 | 24202 | 8,464 | FT | WORK ZONE DOTTED LINE, CLASS I, 6", 642 PAINT | |
| | | | | | | | | | | 14 | 614 | 30650 | 14 | EACH | WORK ZONE ARROW, CLASS III, 642 PAINT | |
| | | | | | | | | | | 5,537 | 622 | 41100 | 5,537 | FT | PORTABLE BARRIER, UNANCHORED | TOTAL QUANTITY REVISED |
| | | | | | | | | | | 51 | 808 | 18700 | 51 | SNMT | DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY | |
| | | | | | | | | | | | | | | | INCIDENTALS | |
| | | | | | | | | | | LUMP | 108 | 30000 | LS | | CPM PROGRESS SCHEDULE SHORT DURATION PROJECTS | |
| | | | | | | | | | | LUMP | 614 | 11000 | LS | | MAINTAINING TRAFFIC | |
| | | | | | | | | | | LUMP | 623 | 10001 | LS | | CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN | 6 |
| | | | | | | | | | | LUMP | 624 | 10000 | LS | | MOBILIZATION | |

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER
ALF

REVIEWER
JMF

PROJECT ID
107959

SHEET TOTAL
11 40