

I:\Project\data\05580\Design\Roadway\Sheets\05580_GG002.dgn Sheet 11/30/2020 9:33:51 AM ikohli

SHEET NUM.													PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION		
4	5	10	11	34	37	41	45	47	51	54	55	56	01/STR/CV	EXT	TOTAL					
																				TRAFFIC CONTROL
									117				117	630	03100	117	FT	GROUND MOUNTED SUPPORT, NO. 3 POST		
									34				34	630	08520	34	FT	STREET NAME SIGN SUPPORT, NO. 3 POST		
									6				6	630	08600	6	EACH	SIGN POST REFLECTOR		
									57.7				57.7	630	80100	57.7	SF	SIGN, FLAT SHEET		
									10				10	630	84900	10	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL		
									2				2	630	85000	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE		
									6				6	630	85100	6	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION		
									22				22	630	86002	22	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL		
									2				2	630	86006	2	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND STORAGE		
									0.18				0.18	642	00104	0.18	MILE	EDGE LINE, 6", TYPE 1		
									0.11				0.11	642	00300	0.11	MILE	CENTER LINE, TYPE 1		
																				MAINTENANCE OF TRAFFIC
	40												40	253	02000	40	CY	PAVEMENT REPAIR, MOT		
	40												40	304	20000	40	CY	AGGREGATE BASE, MOT		
	60												60	407	10000	60	GAL	TACK COAT, MOT		
	20												20	441	10000	20	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), PG64-22, MOT		
													LS	614	12420	LS		DETOUR SIGNING		
									0.11				0.11	614	21000	0.11	MILE	WORK ZONE CENTER LINE, CLASS I		
	80												80	617	10100	80	CY	COMPACTED AGGREGATE, MOT		
																				INCIDENTALS
													LS	614	11000	LS		MAINTAINING TRAFFIC		
													4	619	16010	4	MNTH	FIELD OFFICE, TYPE B		
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING		
													LS	624	10000	LS		MOBILIZATION		

CALCULATED
RDM
CHECKED
IMK

GENERAL SUMMARY (2 OF 2)

PAU-114-1.50
3.00 / 5.01 / 9.02

9
63

I:\Project\data\05580\Design\Roadway\Sheets\05580_TS001.dgn Sheet 11/30/2020 9:32:42 AM ikohli

SIGN QUANTITIES															
REF NO.	ROUTE	STATION	SIDE	CODE	SIZE (INCHES)	630	630	630	630		630	630	630	630	
						GROUND MOUNTED SUPPORT, NO. 3 POST	STREET NAME SIGN SUPPORT, NO. 3 POST	SIGN POST REFLECTOR	SIGN, FLAT SHEET	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	REMOVAL OF GROUND MOUNTED SIGN AND REECTION	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	REMOVAL OF GROUND MOUNTED POST SUPPORT AND STORAGE	
						FT	FT	EACH	SF		EACH	EACH	EACH	EACH	
S11	SR 114	79+19	LT	R1-1	30"x30"	12		1	6.25		1			2	
S12	SR 114	79+48	RT	R1-1	30"x30"	12		1	6.25		1			2	
S13	SR 114	79+52	RT				11					2		1	
S21	SR 114	157+55	RT	I-H2d	48"x24"	24			8.00		1			2	
S22	SR 114	158+31	LT	R1-1	30"x30"	12		1	6.25		1			2	
S23	SR 114	158+61	RT	R1-1	30"x30"	12		1	6.25		1			2	
S24	SR 114	158+71	RT				12					2		1	
				D10-H8	12"x12"				1.00						
				D10-H8	12"x12"				1.00						
S31	SR 114	474+67	LT	M1-5-3 M3-4	30"x24" 30"x15"	12			5.00 3.12		1			2	
S32	SR 114	475+08	RT	D10-H8 D10-H8	12"x12" 12"x12"	9			1.00 1.00		1			1	
S33	SR 114	476+15	LT	R1-1	30"x30"	12		1	6.25		1			2	
S34	SR 114	476+54	LT									2		2	
S35	SR 114	476+60	LT				11					2		1	
S36	SR 114	476+49	RT	R1-1	30"x30"	12		1	6.25		1			2	
S37	CR 87	25+83	LT								1			2	
TOTALS CARRIED TO GENERAL SUMMARY						117	34	6	57.7		10	6	2	22	2

PAVEMENT MARKING QUANTITIES							
REF NO.	ROUTE	STATION		614	642	642	642
				WORK ZONE CENTER LINE, CLASS 1	EDGE LINE, 6", TYPE 1 (WHITE)	CENTER LINE, TYPE 1 (DASHED)	CENTER LINE, TYPE 1 (SOLID / DASHED)
		FROM	TO	MILE	MILE	MILE	MILE
P11	SR 114	78+50	79+07	0.011	0.022	0.011	
P12	SR 114	79+55	80+00	0.009	0.018	0.009	
P21	SR 114	157+25	158+23	0.019	0.038	0.019	
P22	SR 114	158+74	159+00	0.005	0.010	0.005	
P31	SR 114	474+25	476+08	0.035	0.070	0.035	
P32	SR 114	476+60	477+25	0.012	0.024	0.012	
P33	CR 87	26+92	27+75	0.016			0.016
TOTALS TO GENERAL SUMMARY				0.11	0.18	0.09	0.02

CROSS REFERENCES	
SHEET NO.	DESCRIPTION
52	SIGN AND PAVEMENT MARKING PLAN

TRAFFIC CONTROL SUBSUMMARY

PAU-114-1.50
3.00 / 5.01 / 9.02