SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	9	10	17	29								01/BRF/BR /ROSE						
																		ROADWAY	
													LS	201	11000	LS		CLEARING AND GRUBBING	
			230										230	202	23010	230	SY	PAVEMENT REMOVED, ASPHALT	
			37										37	202	98300	37	SY	REMOVAL MISC.: DRIVEWAY REMOVED	4
				32									32	203	10000	32	CY	EXCAVATION	
				15									15	203	20000	15	CY	EMBANKMENT	
		454											454	204	10000	454	SY	SUBGRADE COMPACTION	
			206										206	254	01000	206	SY	PAVEMENT PLANING, ASPHALT CONCRETE (T = 1.25")	
		37.5											37.5	606	15100	37.5	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
		2											2	606	26150	2	EACH	ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016	4
		1											1	606	26550	1	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
		4											4	606	35002	4	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE I	
1													1	SPECIAL	69098000	1	EACH	ADJUST CLEANOUT TO GRADE	4
																		EROSION CONTROL	
													122	601	32200	122	CY	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
656													656	659	10000	656	SY	SEEDING AND MULCHING	
0.1													0.1	659	20000	0.1	TON	COMMERCIAL FERTILIZER	
0.14													0.14	659	31000	0.14	ACRE	LIME	
4													4	659	35000	4	MGAL	WATER	
																		ENVIRONMENTAL / REMEDIATION	
													LS	SPECIAL	69098400	LS		MISC.: WORK INVOLVING ASBESTOS CONTAINING MATERIALS	4
																		PAVEMENT	
			40										40	301	46000	40	CY	ASPHALT CONCRETE BASE, PG64-22	
			47										47	304	20000	47	CY	AGGREGATE BASE	
			50										50	407	10000	50	GAL	TACK COAT (0.06 GAL./SQ. YD.)	
			15										15	441	50000	15	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22 (T=1.25")	
			10										10	441	50300	10	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448) (T=1.75")	
			17										17	441	50300	17	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448) (T=VARIABLE)	
			13										13	411	10000	13	CY	STABILIZED CRUSHED AGGREGATE	
																		WATER WORK	
		5											5	638	07800	5	EACH	6" GATE VALVE AND VALVE BOX	
		425											425	638	98600	425	FT	WATER WORK, MISC.: 6" WATERLINE	
		1											1	638	10200	1	EACH	6" FIRE HYDRANT	
																		TRAFFIC CONTROL	
		11											11	626	00110	11	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL	
		1											1	630	85100	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
		2											2	630	84900	2	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
		4											4	630	86002	4	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
		12											12	630	01100	12	FT	GROUND MOUNTED SUPPORT, NO. 1 POST	
		0.05											0.05	642	00300	0.05	MILE	CENTER LINE, TYPE 1	

CALCULATED KAF
CHECKED JAH

GENERAL SUMMARY (1 OF 2)

PER-CR3-3.37

F:\Clients\Active\VRV\VRV002\106429_PER-CR3-3.37\Design\Roadway\Sheets\106429_GG001.dgn Sheet 3/11/2020 10:08:23 AM brussell