SHEET NUMBER												PARTICIPATION			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SHEET NO.
P.8	P.10-P.12	P.16	P.17	P.18	P.19	P.31	P.32					01/S<2/05/COC	02/STR/44	03/S5K/04						
																			ROADWAY	
					288								288		202	23000	288	SY	PAVEMENT REMOVED	
					12								12		203	10000	12	CY	EXCAVATION	
					266								266		204	13000	266	CY	EXCAVATION OF SUBGRADE	
					206								206		204	30020	206	CY	GRANULAR MATERIAL, TYPE C	
					320								320		204	50000	320	SY	GEOTEXTILE FABRIC	
													LS		878	25000	LS		INSPECTION AND COMPACTION TESTING OF UNBOUND MATERIALS	
																			EROSION CONTROL	
													1000		832	30000	1000	EACH	EROSION CONTROL	
																			DRAINAGE	
					60								60		605	31100	60	FT	AGGREGATE DRAINS	
4												4			611	98630	4	EACH	CATCH BASIN ADJUSTED TO GRADE	
4												4			611	99654	4	EACH	MANHOLE ADJUSTED TO GRADE	
																			PAVEMENT	
8		7												15	251	01041	15	SY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE), AS PER PLAN, 3.00"	P.8
123		1677												1800	251	01041	1800	SY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE), AS PER PLAN, 6.00"	P.8
42		438												480	253	02001	480	CY	PAVEMENT REPAIR, AS PER PLAN, 12.00"	P.8
			27555	653								28208			254	01000	28208	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.50"	
					88								88		301	56000	88	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
					52								52		304	20000	52	CY	AGGREGATE BASE	
			1505	38	48							1543	48		407	20000	1591	GAL	NON-TRACKING TACK COAT	
			845	21								866			407	20001	866	GAL	NON-TRACKING TACK COAT, AS PER PLAN	P.8
					24								24		441	70000	24	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
			1157									1157			442	10000	1157	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	
				30								30			442	22100	30	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (449)	
					1								1		617	10100	1	CY	COMPACTED AGGREGATE	
			53									53			617	10101	53	CY	COMPACTED AGGREGATE, AS PER PLAN	P.8
																			WATER WORK	
4												4			638	10800	4	EACH	VALVE BOX ADJUSTED TO GRADE	
																			TRAFFIC CONTROL	
						2							2		621	00100	2	EACH	RPM	
						2							2		621	54000	2	EACH	RAISED PAVEMENT MARKER REMOVED	
						1.93						1.93			644	00100	1.93	MILE	EDGE LINE, 4"	
						0.04							0.04		644	00104	0.04	MILE	EDGE LINE, 6"	
						1.82						1.80	0.02		644	00300	1.82	MILE	CENTER LINE	
						955						955			644	00400	955	FT	CHANNELIZING LINE, 8"	
						110						110			644	00500	110	FT	STOP LINE	
						210						210			644	00630	210	FT	CROSSWALK LINE, 24"	
						368						368			644	00700	368	FT	TRANSVERSE/DIAGONAL LINE	
						17						17			644	01300	17	EACH	LANE ARROW	
						2						2			644	01410	2	EACH	WORD ON PAVEMENT, 96"	
						135						135			644	01500	135	FT	DOTTED LINE, 4"	
						0.03						0.03			646	10200	0.03	MILE	CENTER LINE	
						105						105			646	10300	105	FT	CHANNELIZING LINE, 8"	
						24						24			646	10400	24	FT	STOP LINE	
						1						1			646	20300	1	EACH	LANE ARROW	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER
AMH

REVIEWER
DR 10/11/23

PROJECT ID
106262

SHEET P.14 TOTAL P.42

PIC-56-(15.48) (19.61), PIC-22-18.28

MODEL: 106262_GG001 PAPERSIZE: 34x22 (in.) DATE: 2/14/2024 TIME: 12:52:19 PM USER: ahollow1
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 06\Pickaway\106262\400-Engineering\Roadway\Sheets\106262_GG001.dgn