SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
							4	5	6	9	14	22							
																		ROADWAY	
										397				202	38000	397	FT	GUARDRAIL REMOVED	
										2				202	42000	2	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A	
										4				202	47000	4	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
											35			203	20000	35	CY	EMBANKMENT	
										275				606	15050	275	FT	GUARDRAIL, TYPE MGS	
										2				606	26150	2	EACH	ANCHOR ASSEMBLY, MGS TYPE E (NCHRP 350 OR MASH 2016)	
										4				606	35141	4	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4, AS PER PLAN	15
																		EROSION CONTROL	
							44							659	00300	44	CY	TOPSOIL	
							399							659	00500	399	SY	SEEDING AND MULCHING, CLASS 1	
							20							659	14000	20	SY	REPAIR SEEDING AND MULCHING	
							20							659	15000	20	SY	INTER-SEEDING	
							0.05							659	20000	0.05	TON	COMMERCIAL FERTILIZER	
							0.08							659	31000	0.08	ACRE	LIME	
							2							659	35000	2	MGAL	WATER	
							3,000							832	30000	3,000	EACH	EROSION CONTROL	
																		TRAFFIC CONTROL	
										20				621	00100	20	EACH	RPM	
										26				621	54000	26	EACH	RAISED PAVEMENT MARKER REMOVED	
										18				626	00110	18	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL	
										0.16				646	10010	0.16	MILE	EDGE LINE, 6"	
										0.08				646	10200	0.08	MILE	CENTER LINE	
																		STRUCTURE OVER 20 FOOT SPAN (SFN 6503764)	
												LS		202	11203	LS		PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	20
												74		516	10011	74	FT	ARMORLESS PREFORMED JOINT SEAL, AS PER PLAN	21
												750		517	75600	750	FT	DEEP BEAM BRIDGE RETROFIT RAILING	
												909		SPECIAL	51822300	909	FT	STEEL DRIP STRIP	22
												33		519	11101	33	SF	PATCHING CONCRETE STRUCTURE, AS PER PLAN	20
												LS		SPECIAL	53000200	LS		STRUCTURES CLEAN BRIDGE ABUTMENT SEATS	20
												1,551		848	10200	1,551	SY	SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION 1.75"	
												1,551		848	20001	1,551	SY	SURFACE PREPARATION USING HYDRODEMOLITION, AS PER PLAN	20
												28		848	30200	28	CY	SUPERPLASTICIZED DENSE CONCRETE OVERLAY (VARIABLE THICKNESS), MATERIAL ONLY	
												51		848	50000	51	SY	HAND CHIPPING	
												LS		848	50100	LS		TEST SLAB	
												2		848	50201	2	CY	FULL DEPTH REPAIR, AS PER PLAN	20
																		MAINTENANCE OF TRAFFIC	
									50					254	01000	50	SY	PAVEMENT PLANING, ASPHALT CONCRETE (1 ½" DEPTH)	
									25					301	46000	25	CY	ASPHALT CONCRETE BASE, PG64-22	
									50					407	10000	50	GAL	TACK COAT	
									100					441	50000	100	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
								16						614	11110	16	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE DURING CONSTRUCTION	5
																		OPERATIONS	
									LS					614	12420	LS		DETOUR SIGNING	6
									25					614	13000	25	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
									100					617	10100	100	CY	COMPACTED AGGREGATE	
									5					617	25000	5	MGAL	WATER	
									0.25					642	00300	0.25	MILE	CENTER LINE, TYPE 1	
																		INCIDENTALS	
														614	11000	LS		MAINTAINING TRAFFIC	5
														624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

PIC-316/762-4.31/0.33 (PIC-762-0.33)

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 3/28/2022 TIME: 12:40:31 PM USER: cbloor
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 06\Pickaway\111166\999-Scratch\112711_GG101.dgn

DESIGN AGENCY
KORDA

KORDA / NEMETH ENGINEERING, INC
1650 Watermark Drive, Suite 200, Columbus, OH 43215

DESIGNER
EAT

REVIEWER
BMV 11/08/21

PROJECT ID
112711

SHEET 8 TOTAL 23