

SHEET NUMBER							PART		ITEM	ITEM EXT	TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.06 - P.07	P.08 - P.10	P.13	P.35	P.43	P.44	01/NHS/PV								
				861			861	621	00100	861	EACH	TRAFFIC CONTROL		
				861			861	621	54000	861	EACH	RPM		
				246	20		266	644	00500	266	FT	RAISED PAVEMENT MARKER REMOVED		
				142	175		175	644	00701	175	FT	STOP LINE		
				142			142	644	00720	142	FT	TRANSVERSE/DIAGONAL LINE, AS PER PLAN	44	
					1,590		1590	644	01200	1590	FT	CHEVRON MARKING		
				16	2		18	644	01300	18	EACH	PARKING LOT STALL MARKING		
					2		2	644	01600	2	EACH	LANE ARROW		
				23.02			23.02	807	14010	23.02	MILE	HANDICAP SYMBOL MARKING		
				11.56			11.56	807	14110	11.56	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6"		
												WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"		
				2132			2132	807	14310	2132	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12"		
				34.58			34.58	850	10010	34.58	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)		
				2132			2132	850	10130	2132	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)		
												<b>MAINTENANCE OF TRAFFIC</b>		
	400						400	614	11110	400	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE		
	10						10	614	12460	10	EACH	WORK ZONE MARKING SIGN		
	4						4	614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	9	
	11.56						11.56	614	20560	11.56	MILE	WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT		
	23.02						23.02	614	22360	23.02	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT		
	2132						2132	614	23690	2132	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 12", 642 PAINT		
	246						246	614	26610	246	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT		
	16						16	614	30650	16	EACH	WORK ZONE ARROW, CLASS III, 642 PAINT		
												<b>INCIDENTALS</b>		
							LS	614	11000	LS		MAINTAINING TRAFFIC		
							LS	623	10001	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	7	
							LS	624	10000	LS		MOBILIZATION		

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER  
MAK  
REVIEWER  
DKR  
PROJECT ID  
112877  
SHEET TOTAL  
P.12 44

LOCATION						644 - THERMOPLASTIC			807 - WET REFLECTIVE			850 - GROOVING		621 - RPM										
SHEET NUMBER	ROUTE	BEGIN STATION	END STATION	SIDE	LENGTH		STOP LINE	LANE ARROW	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE 6"		WET REFLECTIVE PAVEMENT MARKING, LANE LINE, 6"	WET REFLECTIVE PAVEMENT MARKING, CHANNELIZING LINE, 12"	GROOVING FOR 6" RECESSED PAVEMENT MARKING (ASPHALT)	GROOVING FOR 12" RECESSED PAVEMENT MARKING (ASPHALT)	TWO WAY						RAISED PAVEMENT MARKER REMOVED	RPM		
					FT	MI			FT	FT					FT	WHITE RED		YELLOW RED		YELLOW YELLOW				
																RIGHT EDGE LINE	CHANN-ELIZING LINE	LANE LINE	CHANN-ELIZING LINE	RAMP EDGE LINE			CENTER LINE	
40'	80'	40'	80'	40'	80'	80'	EACH	EACH																
P.17	PIC 23	917+92.16	931+00.00	SB	1,308	0.25	34			0.25	0.24	0.25	139	0.74	139			5	18				23	23
	PIC 23	917+92.16	931+00.00	NB	1,308	0.25	24			0.25	0.24	0.25		0.74					18				18	18
P.18	PIC 23	931+00.00	951+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	931+00.00	951+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.19	PIC 23	951+00.00	971+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	951+00.00	971+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.20	PIC 23	971+00.00	991+00.00	SB	2,000	0.38				0.38	0.37	0.38		1.13					26				26	26
	PIC 23	971+00.00	991+00.00	NB	2,000	0.38		2		0.38	0.37	0.38	95	1.13	95			4	26				30	30
P.21	PIC 23	991+00.00	1011+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	991+00.00	1011+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.22	PIC 23	1011+00.00	1031+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	1011+00.00	1031+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.23	PIC 23	1031+00.00	1051+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	1031+00.00	1051+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.24	PIC 23	1051+00.00	1071+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	1051+00.00	1071+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.25	PIC 23	1071+00.00	1091+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	1071+00.00	1091+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.26	PIC 23	1091+00.00	1111+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	1091+00.00	1111+00.00	NB	2,000	0.38		2		0.38	0.38	0.38	463	1.14	463			13	26				39	39
P.27	PIC 23	1111+00.00	1131+00.00	SB	2,000	0.38	51			0.37	0.37	0.37	637	1.11	637			17	26				43	43
	PIC 23	1111+00.00	1131+00.00	NB	2,000	0.38	53			0.37	0.37	0.37	175	1.11	175			6	26				32	32
P.28	PIC 23	1131+00.00	1151+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	1131+00.00	1151+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.29	PIC 23	1151+00.00	1171+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	1151+00.00	1171+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.30	PIC 23	1171+00.00	1191+00.00	SB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
	PIC 23	1171+00.00	1191+00.00	NB	2,000	0.38				0.38	0.38	0.38		1.14					26				26	26
P.31	PIC 23	1191+00.00	1211+00.00	SB	2,000	0.38				0.38	0.37	0.38	177	1.13	177			6	26				32	32
	PIC 23	1191+00.00	1211+00.00	NB	2,000	0.38	40			0.38	0.37	0.38	275	1.13	275			8	26				34	34
P.32	PIC 23	1211+00.00	1222+85.32	SB	1,185	0.22	44			0.21	0.21	0.22	171	0.64	171			6	16				22	22
	PIC 23	1211+00.00	1222+85.32	NB	1,185	0.22				0.20	0.22	0.22		0.64					16				16	16
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>							246	142	16	23.02	11.56	2,132	34.58	2,132	<b>TOTALS CARRIED TO GENERAL SUMMARY</b>							861	861	

TRAFFIC CONTROL QUANTITIES (US-23)

DESIGN AGENCY  
  
 DESIGNER  
**MAK**  
 REVIEWER  
 DAC  
 PROJECT ID  
 112877  
 SHEET TOTAL  
 P.43 44

LOCATION		644					DESCRIPTION						
SHEET NUMBER	ROUTE	STOP LINE	TRANSVERSE/DIAGONAL LINE, AS PER PLAN	PARKING LOT STALL MARKING	HANDICAP SYMBOL MARKING	LANE ARROW							
		FT				FT	FT	EACH	LT	LT THRU	THRU	RT THRU	RT
									EACH	EACH	EACH	EACH	EACH
P.34	U. S. 23	20	175	1,590	2			2			REST AREA		
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>		20	175	1,590	2			2					

**ITEM 644 TRANSVERSE/DIAGONAL LINE, AS PER PLAN:**  
 THIS ITEM SHALL BE PLACED AS A 4" LINE INSTEAD OF THE CMS REQUIRED 24" LINE. ALL OTHER PORTIONS OF THE 644 SPECIFICATION SHALL APPLY.

TRAFFIC CONTROL QUANTITIES (REST AREA)

DESIGN AGENCY



DESIGNER  
**MAK**

REVIEWER  
**DAC**

PROJECT ID  
**112877**

SHEET TOTAL  
**P.44 | 44**