LOCATION	STATION FROM	STATION TO	LENGTH FT	WIDTH (AVG.) FT	AREA SF	CADD GENERATED AREA SF	202 PAVEMENT REMOVED SY	301 4" ASPHALT CONCRETE BASE, (449) CY	304 6" AGGREGATE BASE CY	407 TACK COAT (0.055 GAL./S.Y.) GAL	411 8" STABILIZED CRUSHED AGGREGATE CY	441 1.25" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22 CY	441 1.75" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449) CY
PLEASANT HILL RD													
	329+75.00	330+30.00	55.00	21.08	1159.40		132.51			14.17		4.47	6.26
	329+75.00	330+30.00	55.00	21.42	1178.10			14.54					
	329+75.00	330+30.00	55.00	22.75	1251.25				23.17				
	329+75.00	330+30.00	55.00	24.08	1324.40								
	329+75.00	330+30.00	55.00			44.40					1.10		
	330+30.00	334+30.82	400.82	22.00	8818.04		873.42			107.78		34.02	47.63
	330+30.00	334+30.82	400.82	22.67	9085.25			112.16					
	330+30.00	334+30.82	400.82	23.67	9486.07				175.67				
	330+30.00	334+30.82	400.82	25.00	10020.50								
	330+30.00	334+30.82	400.82			2139.30					52.82		
	334+30.82	335+31.92	101.10	24.23	2449.65		240.79			29.94		9.45	13.23
	334+30.82	335+31.92	101.10	24.89	2516.38			31.07					
	334+30.82	335+31.92	101.10	25.89	2617.48				48.47				
	334+30.82	335+31.92	101.10	27.23	2752.95								
	334+30.82	335+31.92	101.10	8.00	808.80						19.97		
	335+31.92	337+39.81	207.89	27.50	5716.97		349.68			69.87		22.06	30.88
	335+31.92	337+39.81	207.89	28.17	5855.57			72.29					
	335+31.92	337+39.81	207.89	29.17	6063.46				112.29				
	335+31.92	337+39.81	207.89	30.50	6340.64								
	335+31.92	337+39.81	207.89	8.00	1663.12						41.06		
	337+39.81	337+84.26	44.45	42.89	1906.46		264.81			23.30		7.36	10.30
	337+39.81	337+84.26	44.45	43.89	1950.91			24.09					
	337+39.81	337+84.26	44.45	45.38	2017.14				37.35				
	337+39.81	337+84.26	44.45	47.35	2104.71								
	337+39.81	337+84.26	44.45			748.60					18.48		
		SUBTOTAL											
TOTALS CARRIED TO GENERAL SUMMARY							1861	368	397	245	133	77	108

CALCULATED MGM
CHECKED TWG

PAVEMENT QUANTITIES

PIK-C.R.36-4.35

0
0

P:\PIK\TR\0031_PIK-CR36_SR220\00001_PIK-PLEASANTHIL\Design\Roadway\Sheets\Pavement Calculations.dgn Sheet 3/1/2023 5:38:24 AM cmt008