

MODEL: Sheet PAPER: 34x22 (in.) DATE: 6/2/2026 TIME: 1:35:02 PM PLTDRY: OHDOT\_PDF\_Plotter USER: Jessica.Grubb@dmn.com WORKSPACE: OHDOTCEv02 WORKSET: 112177 PRODUCT: OpenRoadsDesigner 24.00.00.205  
 p:\ohdot-pw-bentley.com\ohdot-pw-02\Documents\01 Active Projects\District 04\Porlage\112177\401-Engineering\_2\LMN\Roadway\Sheets\112177\_G002.dgn

**POR/SUM-CULVERTS-FY2026**

SHEET NUMBER											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.03-P.04	P.06	P.07	P.08	P.09	P.10	P.13-P.13A	P.14	P.15	P.16	P.17	01/NHS	02/S>2	03/STR						
DRAINAGE CONTINUED																			
30											10		20	611	04400	30	FT	12" CONDUIT, TYPE B	
10												10		611	04400	10	FT	12" CONDUIT, TYPE B (SUM-303-3.216)	
30											10		20	611	04600	30	FT	12" CONDUIT, TYPE C	
10												10		611	04600	10	FT	12" CONDUIT, TYPE C (SUM-303-3.216)	
30											10		20	611	05100	30	FT	12" CONDUIT, TYPE E	
10												10		611	05100	10	FT	12" CONDUIT, TYPE E (SUM-303-3.216)	
30											10		20	611	05200	30	FT	12" CONDUIT, TYPE F	
10												10		611	05200	10	FT	12" CONDUIT, TYPE F (SUM-303-3.216)	
						84					8			611	06100	8	FT	15" CONDUIT, TYPE C, 706.02	
												84		611	07600	84	FT	18" CONDUIT, TYPE C (SUM-303-3.216)	
												39		611	07600	39	FT	18" CONDUIT, TYPE C, 706.02	
												140		611	19200	140	FT	42" CONDUIT, TYPE A, 706.02, 707.33 OR 707.01 (0.064) ALUMINIZED	
													71	611	22200	71	FT	54" CONDUIT, TYPE A, 706.02, 707.33 OR 707.01 (0.079) ALUMINIZED	
												90		611	29001	90	FT	90" CONDUIT, TYPE A, AS PER PLAN, 707.02 (0.138) WITH FIELD PAVING OF PIPE (SUM-303-3.216)	
													60	611	53000	60	FT	38" X 60" CONDUIT, TYPE A, 706.04	
											2			611	99574	2	EACH	MANHOLE, NO. 3	
PAVEMENT																			
							47	18	13		47		31	301	56000	78	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
										40		40		301	56000	40	CY	ASPHALT CONCRETE BASE, PG64-22, (449) (SUM-303-3.216)	
							22	13	15		22		28	304	20000	50	CY	AGGREGATE BASE	
										40		40		304	20000	40	CY	AGGREGATE BASE (SUM-303-3.216)	
							33	11	9		33		20	407	20000	53	GAL	NON-TRACKING TACK COAT	
										30		30		407	20000	30	GAL	NON-TRACKING TACK COAT (SUM-303-3.216)	
								5	4				9	408	10001	9	GAL	PRIME COAT, AS PER PLAN	
										12		12		408	10001	12	GAL	PRIME COAT, AS PER PLAN (SUM-303-3.216)	
							17	6	7		17		13	441	70000	30	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	
										15		15		441	70000	15	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22 (SUM-303-3.216)	
							15				15			441	70801	15	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (449), (UNDER GUARDRAIL), AS PER PLAN	
								1	1				2	617	10101	2	CY	COMPACTED AGGREGATE, AS PER PLAN	
										1		1		617	10101	1	CY	COMPACTED AGGREGATE, AS PER PLAN (SUM-303-3.216)	
TRAFFIC CONTROL																			
2													2	621	54000	2	EACH	RAISED PAVEMENT MARKER REMOVED	
9												9		621	54000	9	EACH	RAISED PAVEMENT MARKER REMOVED (SUM-303-3.216)	
						24					9		15	626	00110	24	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL	
						11						11		626	00110	11	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL (SUM-303-3.216)	
45											15		30	630	02100	45	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
15												15		630	02100	15	FT	GROUND MOUNTED SUPPORT, NO. 2 POST (SUM-303-3.216)	
						24						24		630	03100	24	FT	GROUND MOUNTED SUPPORT, NO. 3 POST (SUM-303-3.216)	
						1						1		630	08600	1	EACH	SIGN POST REFLECTOR (SUM-303-3.216)	
						16.3						16.3		630	80100	16.3	SF	SIGN, FLAT SHEET (SUM-303-3.216)	
6											2		4	630	80100	6	SF	SIGN, FLAT SHEET, 730.20	
2												2		630	80100	2	SF	SIGN, FLAT SHEET, 730.20 (SUM-303-3.216)	
3						3					2		4	630	84900	6	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
5												5		630	84900	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL (SUM-303-3.216)	
4						2					2		4	630	86002	6	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
4												4		630	86002	4	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL (SUM-303-3.216)	
0.08											0.05		0.03	642	00104	0.08	MILE	EDGE LINE, 6", TYPE 1	
0.03												0.03		642	00104	0.03	MILE	EDGE LINE, 6", TYPE 1 (SUM-303-3.216)	
0.05											0.03		0.02	642	00300	0.05	MILE	CENTER LINE, TYPE 1	
0.02												0.02		642	00300	0.02	MILE	CENTER LINE, TYPE 1 (SUM-303-3.216)	
MAINTENANCE OF TRAFFIC																			
	30										10		20	614	11110	30	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
	10										LS			614	11110	10	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE (SUM-303-3.216)	
		LS	LS	LS							LS			614	12420	LS		DETOUR SIGNING	
					LS						LS			614	12420	LS		DETOUR SIGNING (SUM-303-3.216)	
	10										4		6	614	18601	10	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	
	2											2		614	18601	2	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN (SUM-303-3.216)	
INCIDENTALS																			
											LS			614	11000	LS		MAINTAINING TRAFFIC	
											12			619	16010	12	MNTH	FIELD OFFICE, TYPE B	
											LS			623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS			624	10000	LS		MOBILIZATION	

**GENERAL SUMMARY**

DESIGN AGENCY	
DESIGNER	<b>2LMN</b>
REVIEWER	MAK
PROJECT ID	JAB 01/14/26
SHEET TOTAL	112177 / 59