SHEET NUM. 3	4	6	7	8								PART. 01/STR/PV	02/SK2/PV	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																		ROADWAY	
				1,063								1,063		202	38000	1,063	FT	GUARDRAIL REMOVED	
				10								10		202	42001	10	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A, AS PER PLAN	3
				825								825		606	15100	825	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
				10								10		606	26150	10	EACH	ANCHOR ASSEMBLY, MGS TYPE E, (NCHRP 350 OR MASH 2016)	
																		PAVEMENT	
300												200	100	253	02000	300	CY	PAVEMENT REPAIR	
		88,692										72,318	16,374	254	01000	88,692	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	
		888										724	164	254	01600	888	SY	PATCHING PLANED SURFACE	
		7,983										6,509	1,474	407	20000	7,983	GAL	NON-TRACKING TACK COAT	
		2,973										2,431	542	441	00100	2,973	CY	ANTI-SEGREGATION EQUIPMENT	
		3,696										3,014	682	441	50000	3,696	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
		295										244	51	617	10100	295	CY	COMPACTED AGGREGATE, TYPE A, 1.5"	
		7,075										5,843	1,232	617	20000	7,075	SY	SHOULDER PREPARATION	
		6										5	1	617	25000	6	MGAL	WATER	
																		TRAFFIC CONTROL	
633												542	91	621	00100	633	EACH	RPM	
633												542	91	621	54000	633	EACH	RAISED PAVEMENT MARKER REMOVED	
				14								14		626	00110	14	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL	
			11.82									9.75	2.07	644	00104	11.82	MILE	EDGE LINE, 6"	
			6.03									4.92	1.11	644	00300	6.03	MILE	CENTER LINE	
			209										209	644	00404	209	FT	CHANNELIZING LINE, 12"	
			10										10	644	00500	10	FT	STOP LINE	
			171										171	644	00700	171	FT	TRANSVERSE/DIAGONAL LINE	
			3										3	644	01300	3	EACH	LANE ARROW	
																		MAINTENANCE OF TRAFFIC	
	6.03											4.92	1.11	614	21550	6.03	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
	11.82											9.75	2.07	614	22360	11.82	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
	209												209	614	23690	209	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 12", 642 PAINT	
	171												171	614	25620	171	FT	WORK ZONE TRANSVERSE/DIAGONAL LINE, CLASS III, 642 PAINT	
	10												10	614	26610	10	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
	3												3	614	30650	3	EACH	WORK ZONE ARROW, CLASS III, 642 PAINT	
																		INCIDENTALS	
												LS	LS	614	11000	LS		MAINTAINING TRAFFIC	
												LS	LS	623	10001	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	3
												LS	LS	624	10000	LS		MOBILIZATION	

CALCULATED SEC
CHECKED WWH

GENERAL SUMMARY

PRE-SR 732-9.46

I:\ProjectData\PRE\100622_PRE-732_726-9.46_2.90\Design\Roadway\Sheets\100622GG001.dgn Sheet 10/26/2020 9:32:51 AM whenson