

I:\ProjectData\PRE\100622_PRE-732_726-9.46_2.90\Design\Roadway\Sheets\100622GG00.dgn Sheet 10/26/2020 9:32:51 AM whenson

SHEET NUM.										PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
3	4	6	7	8						01/STR/PV	02/SC2/PV						
ROADWAY																	
				1,063						1,063		202	38000	1,063	FT	GUARDRAIL REMOVED	
				10						10		202	42001	10	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A, AS PER PLAN	3
				825						825		606	15100	825	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
				10						10		606	26150	10	EACH	ANCHOR ASSEMBLY, MGS TYPE E, (NCHRP 350 OR MASH 2016)	
PAVEMENT																	
300												200	100	253	CY	PAVEMENT REPAIR	
		88,692										72,318	16,374	254	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	
		888										724	164	254	SY	PATCHING PLANED SURFACE	
		7,983										6,509	1,474	407	GAL	NON-TRACKING TACK COAT	
		2,973										2,431	542	441	CY	ANTI-SEGREGATION EQUIPMENT	
												3,014	682	441	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
												244	51	617	CY	COMPACTED AGGREGATE, TYPE A, 1.5"	
												5,843	1,232	617	SY	SHOULDER PREPARATION	
												5	1	617	MGAL	WATER	
TRAFFIC CONTROL																	
633												542	91	621	EACH	RPM	
633												542	91	621	EACH	RAISED PAVEMENT MARKER REMOVED	
				14								14		626	EACH	BARRIER REFLECTOR, TYPE 2, BIDIRECTIONAL	
				11.82								9.75	2.07	644	MILE	EDGE LINE, 6"	
				6.03								4.92	1.11	644	MILE	CENTER LINE	
													209	644	FT	CHANNELIZING LINE, 12"	
													10	644	FT	STOP LINE	
													171	644	FT	TRANSVERSE/DIAGONAL LINE	
													3	644	EACH	LANE ARROW	
MAINTENANCE OF TRAFFIC																	
	6.03											4.92	1.11	614	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
	11.82											9.75	2.07	614	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
	209												209	614	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 12", 642 PAINT	
	171												171	614	FT	WORK ZONE TRANSVERSE/DIAGONAL LINE, CLASS III, 642 PAINT	
	10												10	614	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
													3	614	EACH	WORK ZONE ARROW, CLASS III, 642 PAINT	
INCIDENTALS																	
												LS	LS	614	LS	MAINTAINING TRAFFIC	
												LS	LS	623	LS	CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	3
												LS	LS	624	LS	MOBILIZATION	

GENERAL SUMMARY

PRE - SR 732-9.46