

H:\2016\160801\02 - Eaton SRTS\0909\Design\Roadway\Sheets\0909\GG001.dgn Sheet 12/1/2020 3:10:33 PM Kcollins

SHEET NUM.													PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
5	6	7	9	16	22							01/SAF/OT	EXT	TOTAL					
													LS	201	11000	LS		<b>ROADWAY</b>	
													57	202	23000	110	SY	CLEARING AND GRUBBING	
			110															PAVEMENT REMOVED	
			1,039										1,039	202	30000	1,039	SF	WALK REMOVED	
			205										205	202	32000	205	FT	CURB REMOVED	
				2									2	203	10000	2	CY	EXCAVATION	
				73									73	203	20000	73	CY	EMBANKMENT	
				50									50	204	10000	50	SY	SUBGRADE COMPACTION	
													1,912	608	10000	1,912	SF	4" CONCRETE WALK	
													239	608	13020	239	SF	7" CONCRETE WALK	
													756	608	52000	756	SF	CURB RAMP	
																		<b>EROSION CONTROL</b>	
2													2	659	00100	2	EACH	SOIL ANALYSIS TEST	
45													45	659	00300	45	CY	TOPSOIL	
410													410	659	00500	410	SY	SEEDING AND MULCHING, CLASS 1	
21													21	659	14000	21	SY	REPAIR SEEDING AND MULCHING	
0.06													0.06	659	20000	0.06	TON	COMMERCIAL FERTILIZER	
													0.09	659	31000	0.09	ACRE	LIME	
													2	659	35000	2	MGAL	WATER	
													3,000	832	30000	3,000	EACH	EROSION CONTROL	
																		<b>PAVEMENT</b>	
			15										15	253	02001	15	CY	PAVEMENT REPAIR, AS PER PLAN	4
			260										260	254	01000	260	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 3"	
			32										32	407	20000	32	GAL	NON-TRACKING TACK COAT	
			22										22	441	50000	22	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
			50										50	452	10010	50	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
			148										148	609	12000	148	FT	COMBINATION CURB AND GUTTER, TYPE 2	
																		<b>WATER WORK</b>	
			3										3	638	10800	3	EACH	VALVE BOX ADJUSTED TO GRADE	
																		<b>TRAFFIC CONTROL</b>	
		2											2	625	32000	2	EACH	GROUND ROD	
					42								42	630	03100	42	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
					33								33	630	80100	33	SF	SIGN, FLAT SHEET	
					1								1	630	85100	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
					1								1	630	86002	1	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
					2								2	630	97700	2	EACH	SIGNING, MISC.:SOLAR POWERED RETANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY	7
		2											2	632	64020	2	EACH	PEDESTAL FOUNDATION	
					0.05								0.05	644	00100	0.05	MILE	EDGE LINE, 4"	
					0.01								0.01	644	00300	0.01	MILE	CENTER LINE	
					82								82	644	00500	82	FT	STOP LINE	
					1,090								1,090	644	00600	1,090	FT	CROSSWALK LINE, 12"	
					720								720	644	00601	720	FT	CROSSWALK LINE, AS PER PLAN, 24"	4
					192								192	642	00800	192	FT	CURB MARKING, TYPE 1	
					960								960	644	30000	960	FT	REMOVAL OF PAVEMENT MARKING	
																		<b>MAINTENANCE OF TRAFFIC</b>	
	0.01												0.01	614	21100	0.01	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
																		<b>INCIDENTALS</b>	
													LS	614	11000	LS		MAINTAINING TRAFFIC	
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	624	10000	LS		MOBILIZATION	

**GENERAL SUMMARY**

**PRE-EATON-SRTS**

H:\2016\160801\02 - Eaton SRTS\0909\Design\Roadway\Sheets\0909\T500\dgn Sheet 3/8/2021 2:49:01 PM kcollins

REF NO.	SHEET NO.	STATION TO STATION				630	630	630	630		644	101	642	644	644	644	644	644	630									
						REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	GROUND MOUNTED SUPPORT, NO. 3 POST	SIGN, FLAT SHEET		REMOVAL OF PAVEMENT MARKING		CURB MARKING, TYPE 1	STOP LINE	CROSSWALK LINE, 12"	CROSSWALK LINE, AS PER PLAN, 24"	EDGE LINE, 4"	CENTER LINE		SIGNING, MISC.: SOLAR POWERED RETANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY								
				TO		EACH	EACH	FT	SF		FT	FT	FT	FT	FT	MILE	MILE	EACH										
SN1	23	9+57	L		9+56	1	1	14																				
SN2	24	21+56	R															1										
SN3	24	21+68	L															1										
SN4	25							14	16.5																			
SN5	25							14	16.5																			
SL1	23	9+58	L		9+78					20			20															
SL2	24									21			21															
SL3	25									20			20															
SL4	25									21			21															
CW1	23	9+58	C		9+99					82			82	56														
CW2	23	14+17	R		14+28					82			82	56														
CW3	23	14+29	R		14+66					70			70	48														
CW4	24	21+04	L		21+50					85			81	48														
CW5	24	21+55	C		21+65								56	40														
CW6	24									122			122	80														
CW7	24									77			77	48														
CW8	25									121			121	80														
CW9	25												80	56														
CW10	25									104			104	64														
CW11	25												80	56														
CW12	25									135			135	88														
EL1	24	20+38	R		21+55												0.023											
EL2	24	21+73	L		22+91												0.023											
CM1	24	21+36	R		22+26							91																
CM2	24	21+47	L		22+26							101																
CI1	24	21+69	C		22+26																			0.011				
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>						1	1	42	33		960		192	82	1090	720.00	1	0.01	2									

TRAFFIC SUB - SUMMARY

CALCULATED  
KJC  
CHECKED  
SAM

PRE-EATON - SRTS